

RESOLUTION NO. 5180-14

RESOLUTION APPROVING WITH CONDITIONS THE ARCHITECTURAL REVIEW APPLICATION FOR THE NYBERG RIVERS SHOPPING CENTER LOCATED AT 7455-7925 SW NYBERG STREET (TAX MAP 2S1 24 A, TAX LOTS 1601, 1602, 1900, 2502, 2506, 2507, 2508, AND 2700; TAX MAP 2S1 24B, TAX LOTS 2000, 2001, AND 2100 (AR-13-07)

WHEREAS, Center Cal Properties LLC submitted an Architectural Review application for the Nyberg Rivers Shopping Center; and

WHEREAS, the application was considered by the Architectural Review Board and a decision issued; and

WHEREAS, a request for review of the Architectural Review Board decision was filed; and

WHEREAS, a public hearing was held before the City Council of the City of Tualatin on January 27, 2014, to consider the request for review; and

WHEREAS, notice of public hearing was given as required by Tualatin Development Code 1.031; and

WHEREAS, the City Council heard and considered the testimony and information presented by the City staff, the applicant, the appellant, and those appearing at the public hearing; and

WHEREAS, the City Council finds that with the conditions imposed, the applicant has provided sufficient evidence to demonstrate that all of the architectural review features requirements of the Tualatin Development Code relative to the decision have been satisfied; and

WHEREAS, after the conclusion of the public hearing, the Council voted unanimously to approve the application with conditions.

NOW THEREFORE, BE IT RESOLVED BY THE CITY COUNCIL OF THE CITY OF TUALATIN, OREGON, that:

Section 1. The application for Architectural Review for the Nyberg Rivers Shopping Center, which is attached as "Exhibit 1" and incorporated by reference, is approved with the following conditions:

AR-1 Prior to issuance of any grading permits or other on-site work on the entirety of the subject site per CWS, TVF&R and ODOT:

- A. CWS: Submit to the City of Tualatin Planning Division a copy of the Clean Water Services Site Development Permit to show compliance with the following:

A Clean Water Services (the District) Storm Water Connection Permit Authorization must be obtained. Application for the District's Permit Authorization must be in accordance with the requirements of the Design and Construction Standards, Resolution and Order No. 07-20, (or current R&O in effect at time of Engineering plan submittal), and is to include:

1. Detailed plans prepared in accordance with Chapter 2, Section 2.04.2.b-l.
2. Detailed grading and erosion control plan. An Erosion Control Permit will be required.
3. Area of Disturbance must be clearly identified on submitted construction plans. If site area and any offsite improvements required for this development exceed one-acre of disturbance, project will require a 1200-CN Erosion Control Permit. If site area and any offsite improvements required for this development exceed five-acres of disturbance, project will require a 1200-C Erosion Control Permit.
4. Detailed plans showing the development having direct access by gravity to public storm and sanitary sewer.
5. Provisions for water quality in accordance with the requirements of the above named design standards. Water Quality is required for all new development and redevelopment areas per R&O 07-20, Section 4.05.5, Table 4-1. Access shall be provided for maintenance of facility per R&O 07-20, Section 4.02.4.
6. If use of an existing offsite or regional Water Quality Facility is proposed, it must be clearly identified on plans, showing its location, condition, capacity to treat this site and, any additional improvements and/or upgrades that may be needed to utilize that facility.
7. If private lot LIDA systems proposed, must comply with the current CWS Design and Construction Standards. A private maintenance agreement, for the proposed private lot LIDA systems, needs to be provided to the City for review and acceptance.
8. Show all existing and proposed easements on plans. Any required storm sewer, sanitary sewer, and water quality related easements

must be granted to the City.

9. *Application may require additional permitting and plan review from the District's Source Control Program. For any questions or additional information, please contact Source Control at (503) 681-5175.*
10. *Site contains a "Sensitive Area." Applicant shall comply with the conditions as set forth in the Service Provider Letter No. 13-000801, dated April 4, 2013.*
11. *Clean Water Services shall require an easement over the Vegetated Corridor conveying storm and surface water management to Clean Water Services that would prevent the owner of the Vegetated Corridor from activities and uses inconsistent with the purpose of the corridor and any easements therein.*
12. *Detailed plans showing the sensitive area and corridor delineated, along with restoration and enhancement of the corridor.*
13. *Provide DSL and Corps of Engineers permits for any work in the wetlands or creek prior to any on site work, including grading and erosion control. Include permit number on cover sheet of plans or provide concurrence with the delineation.*
14. *Any proposed offsite construction activities will require an update or amendment to the current Service Provider Letter for this project.*

This Land Use Review does not constitute the District's approval of storm or sanitary sewer compliance to the NPDES permit held by the District. The District, prior to issuance of any connection permits, must approve final construction plans and drainage calculations.

- B. Fire: Provide the City of Tualatin Planning Division evidence/documentation that the following has been reviewed and approved. Submit plans to TVF&R for review and approval showing the following.
 1. Parking lots and drive aisles able to sustain 60,000 pounds GVW and 12,500 pounds point load.
 2. Please provide a full size scaled drawing at a scale of 1" = 40' or 1" = 50' for verification of turning radius.
- C. ODOT: The applicant shall obtain an ODOT Permit for construction of the bike lane, right turn lane, planter strip, sidewalk, landscape buffer, retaining wall and drainage within the state highway right of way. Tree placement and design shall be consistent with the ODOT Highway Design Manual or a design exception shall be obtained. The types of

trees to be approved by ODOT. Applicant shall enter into a Cooperative Improvement Agreement with ODOT to address ODOT permit requirements, providing graffiti removal and maintenance of the retaining wall including and the transfer of ownership of the improvement to ODOT. The agreement shall address the work standards that must be followed, maintenance responsibilities, and compliance with ORS 276.071, which includes State of Oregon prevailing wage requirements.

To facilitate the closure of SW 75th Ave (private), the applicant shall:

1. *Ensure that a permanent access easement is recorded to provide access to a public roadway (Nyberg Rd) for tax lots 2508, 2502, 2506, 2100, 2507, and 2700.*
2. *Record a 15ft maintenance easement adjacent to the retaining wall and a maintenance vehicle access easement through the development with ODOT.*

Illumination within the ODOT right of way must be in accordance with AASHTO illumination standards and the ODOT Lighting Policy and Guidelines, January 2003, which states that local jurisdictions must enter into an intergovernmental agreement (IGA) with ODOT wherein the local jurisdiction is responsible for installation, maintenance, operation, and energy costs.

Noise Advisory:

The applicant is advised that outdoor activity areas on the proposed site may be exposed to traffic noise levels that exceed federal noise guidelines. Builders should take appropriate measures to mitigate this impact. It is generally not the State's responsibility to provide mitigation for receptors that are built after the noise source is in place.

- AR-2 No building permit shall be issued by the Building Official for the City of Tualatin for the erection, construction, conversion or alteration of any building or structure or use of land unless the Community Development Director or designee has first determined that such land use, building or structure, as proposed, would comply with the Tualatin Community Plan and Development Code (TDC 31.114).
- AR-3 Prior to Issuance of the Building Permit for construction of any of the buildings on the entirety of the subject site, the applicant shall submit a revised plan set inclusive of the following for review and approval. Provide evidence or documentation to the City of Tualatin Planning Division that all items have been completed prior to Planning signing off on any building construction permit:

A. Architecture

1. All roof top equipment on all buildings shall be entirely screened from view from all sides and from all public sidewalk vantage points 6-feet above grade (TDC 73.150 (18)).
2. On the west side of Cabela's, the entirety of the load dock screen wall as shown on plan sheet A3.10a shall be at least 15-feet high and opaque to fully screen a semi-trailer truck (TDC 73.390(3)).
3. On the north side of Michael's (building D-110) install a 15-foot high wall to screen, a semi-trail truck parked at the loading dock to meet Condition N of Resolution 5163-13.
4. Add manufactured stone veneer columns and the trellis architectural features to the west side of Cabela's to match the north and east elevations to meet Condition M of Resolution 5163-13.
5. The applicant shall construct the west elevation (along the pedestrian walkway) of Cabela's including the stone veneer and wood screen wall with the architecture proposed on page 5.3 and 5.4 of the December 9th submittal booklet. The applicant shall also add the architectural features shown in the picture below to all sides and all corners of the building as proposed during the master plan. The applicant shall also add all architectural features shown on page 30 of the December 3rd presentation to the Architectural Review Board. In addition the Cabela's building shall also add the trellises shown on the north side of Cabela's on page A3.10a of the complete plan set intake stamped date November 12, 2013 to the south side of the building. These trellises shall be 62-feet wide, 18-feet in height, and have three stone veneer columns exactly like the trellises shown on the north side of the building. The applicant shall also screen the trash compacter with the exact same treatment as the proposed Cabela's loading dock screen wall shown on page 5.3 and 5.4 of the December 9th submittal booklet.



6. The northwest and northeast elevation of building N-100 shall be upgraded with architectural features that match the quantity and quality of the features shown on the southwest and southeast elevation of the building to meet Condition L of Resolution 5163-13.

7. Elevations and building permit application shall be revised to show building N-100 (LA Fitness) to have a 45-foot building height inclusive of any architectural features (TDC 53.090).
8. The north side of New Seasons, Michaels, and Home Goods shall be upgraded with the same quantity and quality of architecture shown in the front of the buildings. This includes showing more reliefs, more changes in color, and more material changes and other elements to break up large massing to improve pedestrian scale over what was proposed with the December 9th submittal packet.
9. The entirety of the east side of Restaurant 1030 shall be upgraded to have the same quality and quantity of architectural features as shown on the front façade. This includes showing reliefs, changes in color, and material changes. The upgrade shall also show the windows and awnings proposed with the December 9th submittal.
10. The south side of the Home Goods architecture shall be enhanced to provide a change in roof line, more changes in color, more reliefs, and more material changes. The south elevation of Home Goods shall be further explored, developed, enhanced to create a stronger focal point and entry for the site.
11. The applicant shall install the lighting fixtures along the entirety of the plaza area shown on page 5.4 of the December 9th submittal booklet.
12. Any retaining walls shall be decorative like the right image on sheet 9.0 of the December 9th submittal booklet. Plain retaining walls as shown on the left image on sheet 9.0 are not acceptable, and shall be upgraded with a stone veneer. The architectural treatment on the retaining wall for the Nyberg Street right turn lane shall be approved by ODOT in coordination with the City of Tualatin.

B. Civil:

1. On the revised grading plan show all preserved trees protected with sturdy fencing (chain link fence) during the construction process.
2. A note shall be placed on the grading plans that states, "No grading activities will allow preserved tree roots to remain exposed per TDC 73.250(2)(f)."
3. Provide for required vanpool and carpool spaces on the striping and signage plan.
4. All site plan amendments shall reflect required revised and approved planning site plan.

C. Landscaping and Irrigation

1. Fill in the street tree gaps along all public and public-like streets to match the City standard of 30-feet on center (TDC 74.765 and Map 74-1) (landscape plan sheet L1.0-L1.2)
2. Choose from the City's street tree list for SW Nyberg Street frontage and the main entrance frontage (TDC 74.765 and Map 74-1). Unapproved trees such as Beach Plum, Quaking Aspen, and Serviceberry are shown (landscape plan sheet L1.0-L1.2). Street Tree List: <http://www.tualatinoregon.gov/developmentcode/tdc-chapter-74-public-improvement-requirements#74.765>
3. Replace all "Central Oregon" species with either "Coast Range" or "Tualatin River" species (landscape plan sheets L1.0-L1.9) to meet Condition T of Resolution 5163-13.
4. An irrigation system is required pursuant to TDC 73.280. Supply an irrigation plan. The future irrigation plan shall relocate all City irrigation lines and install a water meter with doublecheck to assure continued service (TDC 73.280). The irrigation plan shall also supply lines to the ODOT frontage. The irrigation plan shall be approved by ODOT for the ODOT frontage. A permit from ODOT shall be obtained for installation of the irrigation system.
5. On the south side of the trail between the west end of building D-130 and the east end of building 1010, plant 2 canopy trees and 4 understory trees per 100 lineal feet. No Central Oregon plant species allowed per 73.020.
6. Add six more Vine Maples to the northwest side of LA Fitness (building N-100) or other similar tall growing shrub or small tree in the planter strip to break up the massing of the building per 73.020.
7. Add two more Vine Maples to the northeast side of LA Fitness (building N-100) or other similar tall growing shrub or small tree in the planter strip to break up the massing of the building per 73.020.
8. Move trees and shrubs to appropriate locations from the edge of the shared pathway shy area so routine pruning to prevent branches/plants from encroaching over shy or path when full grown is not required. This does not include tree that can have branches pruned to maintain an eight to ten foot clearance above shared paths (73.160(3)(e) and 73.260(5)).
9. Provide a note on the revised landscaping plans that shrubs in all parking areas will be maintained to not exceed 30-inches in height and that all trees will be maintained to not extend below 8-feet measured from grade pursuant to TDC 73.160(3)(e).
10. Show all trees preserved in the C2 series of preliminary plans protected with chain link fence or other sturdy fencing through the duration of the construction process per 73.250(2)(6).

11. The applicant shall plant all coniferous to at least 8-feet in height as proposed.
12. The applicant shall plant deciduous trees to at least 2-inches in caliper at breast height as proposed.
13. Pursuant to TDC 73.290(1) the revised site and grading plans shall include a specification for replanting areas where existing vegetation or landscaping has been removed or damaged through grading and construction activities.
14. Add or demarcate where 15 additional Douglas Fir, Western Red Cedar, or other tall-maturing conifer trees were placed on tax lot 2502 pursuant to Condition T of Resolution 5163-13. Add an additional landscaping sheet in the revised landscaping plans that show specific compliance with Condition T of Resolution 5163-13.
15. Add or demarcate where the replacement trees pursuant to Condition S of Resolution 5163-13 are shown. Deciduous replacement trees shall be at least 3-inches in caliper at breast height and coniferous trees shall be at least 10 feet in height at time of planting. Add an additional landscaping sheet that shows specific compliance with Condition S of Resolution 5163-13.
16. Add the bike parking plans to the site and landscaping plans. Show revised landscaping based on placement of bike racks and covered bike storage. Show a 5-foot clear concrete or asphalt walkway around all bike parking per 73.370(1)(p).
17. Show that planting around trash enclosure walls will be evergreen exclusive of the bike rack pursuant to TDC 73.227(6)(b)(iii).
18. Show how the proposed ground cover will fully cover the ground in 3 years pursuant to TDC 73.240(11).
19. Provide evidence and/or documentation that the trees proposed for the diamond planters will meet Condition P of Resolution 5163-13.
20. Landscaping abutting I-5 shall be consistent with the ODOT approved list.

D. Lighting

1. Provide elevations and/or spec sheets of all proposed lighting to determine if cut-offs meet TDC 73.160(3)(c) and 73.380(6).
2. Provide a lighting plan that shows all light measurements down to .1 foot candles as it passes over the property line per 73.380 (6).
3. Light poles shall be LED with pedestrian scale lighting at the entries to the subject site as proposed.
4. Show how lights without full cut-off will not cause light pollution.

E. Fire (See TVF&R full comment letter for explanation).

1. New buildings shall have full NFPA 13 fire sprinklers.
2. Identify aerial apparatus access lanes on each building in excess of 30 feet in height.
3. A parking restriction sign plan (OFC D103.6).
4. A fire lane curb marking plan (OFC 503.3).
5. Any proposed gates with approved Fire District lock mechanisms.
6. A current fire flow test of the nearest fire hydrant demonstrating available flow at 20 psi residual pressure as well as fire flow calculation worksheets. Please forward copies to both TVF&R as well as local building department. Fire flow calculation worksheets as well as instructions are available at www.tvfr.com. Please provide fire flow calculation worksheets for each new building on the campus.
7. A fire hydrant distribution plan based on fire flow calculations.
8. Bollards at each new fire hydrant and fire department connection.
9. Fire sprinkler Fire Department connections shall be plumbed to the fire sprinkler riser downstream of all control valves.
10. Each new building is to be afforded with a Knox box.
11. Pursuant to TDC 73.160(3)(d), provide an identification system which clearly locates buildings and their entries emergency services.

F. Planning

1. All crosswalks shown to be striped on sheet C1.0 of the plan set shall be made of different raised material such as solid colored thermal plastic. Crosswalks made with paint only are not allowed per 73.160(1)(a)(iii).
2. All crosswalks shown to be a brick or paver pattern shall be created of raised brick or pavers of a significantly different color than the underlying asphalt or cement per 73.160(1)(a)(iii). Raised and scored colored concrete is acceptable.
3. The accessway proposed on plan set sheet C1.3 from northeast side of building 1040 to the edge of the sensitive area containing the Tualatin River Greenway shall be at least 8-foot wide and constructed of Portland Concrete Cement pursuant to TDC 73.160(1)(d).
4. The 14-foot wide accessway from the rear of building 1010 on tax lot 1601 to the Tualatin River Greenway shall be constructed of Portland Concrete Cement pursuant to TDC 73.160(1)(d).

5. Show all mechanical and electrical equipment on site. Show that all electrical and mechanical equipment will be fully screen with landscaping, fencing, or a wall pursuant to TDC 73.160(4)(a).
6. Refine the site plan to show refuse and recycling storage areas for building A, B, C, E-100, D-130, D-125, D-120, and D-110 that meet Section 73.227. These include the existing recycling and refuse storage areas that exist and are not shown on the site plan. In addition building 1005 shows a trash compactor and bicycle parking in the same area. This conflict shall be rectified through a revised site and refuse plan.
7. Place a note on the grading, landscaping, and tree preservation plan that neither top soil storage nor construction material storage shall be located within the drip line of trees designated to be preserved pursuant to TDC 73.250(2)(d).
8. Pursuant to 73.370(1)(a), show designated carpool and vanpool spaces on the revised site plan.
9. Pursuant to 73.370(1)(u) a bike parking signage plans shall be submitted in the revised plan set and through the sign plan package for site signage. Bike parking directional signage shall be placed at the main pedestrian entrance for each building if bike parking is not within 50-feet and viewable from the pedestrian main entrance.
10. 53 carpool or vanpool spaces shall be indicated in a revised site plan and signed or otherwise designated in the parking lot per 73.370(1)(x).
11. All internal walk ways, access ways, crosswalks, and sidewalks shall be at least 6-feet in width pursuant to TDC 73.160(1)(a)(ii). A reduction may be requested if existing sidewalk.
12. Show where recycling will be located on a revised trash enclosure and site plan to meet TDC 73.226(5).
13. Show that trash enclosure doors can open wider than a 90-degree angle, that there will be no center pole between the trash enclosure doors, and that the doors can be lockable in this open position as requested by the trash hauler.
14. Show how trash and site plan meet TDC 73.227.
15. Provide for required vanpool and carpool spaces on the striping and signage plan.
16. The elevation for building J-100 (BJ's restaurant), do not match the footprint of the site plan, please revise.
17. Revise the west side of the main entrance to be a City standard 5-foot tree well and 9-foot wide pathway.
18. All dog kennels shall be fully screened with the same material used to build Cabela's, (no chain link fencing with slats).

19. All dumpsters and trash cans on the north side of Building A shall be fully screened in an enclosure that matches the building materials of Building A.

G. Parks

1. An additional crosswalk from east of Street A sidewalk to building D-130.
2. Access path to Tualatin River Greenway at Building 1040 needs to be the same width as the main path, 16-feet: a 12-foot path with a 2-foot shy, with a 2-foot shy on either side through the sensitive area.
3. Affirm that access path to Tualatin River Greenway from building N-100 has been eliminated (it is shown on Exhibit M).
4. The connection to the west along the Tualatin River shall be shown within the outer 40-feet from top of bank at the northwest corner of N-100.

H. Artwalk Signage

1. Create a sign plan that shows route to art and location of wayfinding and all other Artwalk signs.

AR-4 The following shall be performed for Washington County prior to the issuance of any City of Tualatin building permit for any and all buildings on the entirety of the subject site. Provide evidence/documentation to the City of Tualatin Planning Division that all items have been completed prior to Planning signing off on any building permit for building construction:

NOTE: Any work within County-maintained right-of-way requires a permit from the Washington County Operations Division (503.846.7623). No private infrastructure can be located within the right-of-way.

- A. The following shall be recorded (contact appropriate jurisdiction for recordation of prepared documents):
 1. All public improvements identified in Washington County's Traffic Staff report dated May 21, 2013 shall be located within public right-of-way and/or easements.
- B. Submit to Washington County Public Assurance Staff, 503-846-3843:
 1. Completed "Design Option" form (a form that states who will be building the improvements and submitting to the Washington County Road Standards).

2. **\$15,000.00** Administration Deposit.

NOTE: *The Administration Deposit is a cost-recovery account used to pay for County services provided to the developer, including plan review and approval, field inspections, as-built approval, and project administration. The Administration Deposit amount noted above is an estimate of what it will cost to provide these services. If, during the course of the project, the Administration Deposit account is running low, additional funds will be requested to cover the estimated time left on the project (at then-current rates per the adopted Washington County Fee Schedule). If there are any unspent funds at project close out, they will be refunded to the applicant. PLEASE NOTE: Any point of contact with County staff can be a chargeable cost. If project plans are not complete or do not comply with County standards and codes, costs will be higher. There is a charge to cover the cost of every field inspection. Costs for enforcement actions will also be charged to the applicant.*

3. A copy of the City's Land Use Approval with Conditions, signed and dated.
 4. Three (3) sets of complete engineering plans for construction of the following public improvements (refer to attached Traffic Staff Report dated May 21, 2013):
 - a. A westbound right-turn lane on SW Nyberg Road.
 - b. Two (2) southbound left-turn lanes and a shared through/right-turn lane from the site's access on SW Nyberg Road and two (2) inbound receiving lanes.
 - c. Modify the traffic signal to accommodate the widening of the driveway and the westbound right turn movement.
- C. Obtain a Washington County Facility Permit upon completion of the following:
1. Obtain Engineering Division approval and provide a financial assurance for the construction of the public improvements listed in condition **AR-3.B.4.**

NOTE: The Washington County Public Assurance staff (503-846-3843) will send the required forms to the applicant's representative **after** submittal and approval of items listed under **AR-3.B.4.**

***The Facility Permit** allows construction work within County rights-of-way and permits site access only after the developer first submits plans and obtains Washington County Engineering approval, obtains*

required grading and erosion control permits, and satisfies various other requirements of Washington County's Assurances Section including but not limited to execution of financial and contractual agreements. This process ensures that the developer accepts responsibility for construction of public improvements, and that improvements are closely monitored, inspected, and built to standard in a timely manner. Access will only be permitted under the required Washington County Facility Permit, and only following submittal and County acceptance of all materials required under the facility permit process.

- D. Pay a lump sum of \$10,000 to the County for field visit and retiming of the existing corridor signal system with the recommended traffic signal phasing change at main entrance intersection into the subject site.

AR-5 Prior to Occupancy of any building on the entirety of the subject site:

- A. Obtain a finalized Washington County Facility Permit, contingent upon the following:
 - 1. The road improvements required in condition **AR-3.B.4** above shall be completed and accepted by Washington County.
- B. The applicant shall show evidence to City of Tualatin staff that the diamond planter trees were installed consistent with the approved AR planting specifications.
- C. Provide a copy of the subject site's landscape and maintenance manual as required by Condition R of Resolution 5163-13.
- D. Survey and stake area of easements in areas not to be constructed at this time. The City shall approve the location of the easement prior to its acceptance per 74.310(1). (Please see Public Facilities Report for more information)
- E. Submit a tree maintenance plan as required by Condition R of Resolution 5163-13.
- F. Provide an arborist's report that the trees in the diamond planters have been planted properly and according to Condition Q of Resolution 5163-13.

AR-6 All conditions of approval, except where otherwise stated, shall be subject to field inspection prior to Certificate of Occupancy.

AR-7 No trees shall be removed associated with Seneca Street until the Seneca extension is approved.

- AR-8 Trees along the shared pathways will be maintained to have an 8-foot vertical clearance per TMC 74.725(2).
- AR-9 To meet the requirement of 73.100(2), all building exterior improvements approved through the Architectural Review Process shall be continually maintained including necessary painting and repair so as to remain substantially similar to original approval through the Architectural Review Process, unless subsequently altered with Community Development Director approval, as a condition of approval.
- AR-10 To meet the requirement of 73.100(1), all landscaping approved through architectural review (AR) shall be continually maintained, including necessary watering, weeding, pruning and replacement, in a manner substantially similar to that originally approved by the AR decision, unless subsequently altered through AR.
- AR-11 The applicant shall separately from this AR submit sign permit applications for any proposed signage. Pursuant to TDC 73.160(3)(d), provide an identification system which clearly locates buildings and their entries for patrons and emergency services.
- AR -12 Encroachment upon any identified preserved trees must occur under the direction of a qualified arborist to assure the health needs of trees within the preserved area per TDC 73.250(2)(e).
- AR-13 Except as allowed by Subsection (2), all landscaping and exterior improvements required as part of the Community Development Director's, Architectural Review Board's or City Council's approval shall be completed in addition to Fire and Life Safety, and Engineering/Building Department requirements prior to the issuance of any certificate of occupancy (TDC 73.095).
- AR-14 The subject site shall comply with all ADA standards.

Section 2. The City Council adopts as its Findings and Analysis the findings set forth in "Exhibit 2," which is attached and incorporated by reference.

Section 3. This Resolution is effective upon adoption.

Adopted by the City Council this 10 Day of February, 2014.

CITY OF TUALATIN, OREGON

BY [Signature]
Mayor

APPROVED AS TO FORM
BY [Signature]
City Attorney

ATTEST:
BY [Signature]
City Recorder

Exhibits to Resolution No. 5180-14 are available upon request in the Administration Department.

18861 SW Martinazzi Ave, Suite 200

Tualatin, OR 97062

503.691.3011

MEMORANDUM



To: Clare Fuchs, AICP
From: Michael Cerbone, AICP
Project Manager

Date: October 23, 2013

Project: Nyberg Rivers
Cardno#: 21198310

Re: Completeness Responses for Case File AR-13-07 Nyberg Rivers ARB

5415 SW Westgate Drive
Suite 100
Portland, Oregon 97221
USA

Phone (503) 419-2500
Fax (503) 419-2600

www.cardno.com

This memo will serve as a response to the Notice of Incomplete Application issued by the City of Tualatin on October 16, 2013. The project team has reviewed the incompleteness and preliminary review items and drafted responses and plan updates to reflect changes as requested by the City. The following items and responses are provided to address specific elements of both the plan set, the project narrative and the *Exhibit A—Report on Compliance with Master Plan Conditions of Approval*. Please find included within this submittal a revised plan set, an updated Compliance Report as well as excerpts from the narrative that were revised per the comments received. Please do not hesitate to contact me if there are any questions, comments or concerns.

ITEMS IDENTIFIED AS “INCOMPLETE”

1. *Civil Sheets—from Engineering*

- a. *Consistently show all public lines and easements on all plan sheets. Staff is unable to determine all concerns because public lines and easements are not shown on all sheets (PWCC 202.2.00). (All sheets)*

Response: All Civil and Landscaping Sheets have been updated to show all public lines and easements through the site. A full-size plan set has been submitted with this memo with those updates.

- b. *Utilities, trash enclosure, and buildings on adjacent City-owned property are missing on the plans. Staff needs these items shown to determine the feasibility with the proposal. Please show adjacent properties. Please identify slope easements and construction needed to support the Street A construction (PWCC 203.2.02). (ex: C1.1)*

Response: The plans have been updated to show utilities, trash enclosures and buildings on adjacent City-owned property. Also, slope easements and construction needed to support the Street “A” construction is shown on sheet C1.1.

- c. *Show abutting properties to determine how trail connections and future auto connections at Heron’s Landing will work with the proposal. (PWCC 203 and TDC 75.120(8)(b)). (ex: C1.1)*



Response: Abutting properties to the north and west are shown on the plans. Trail and future auto connections are shown on the plans, with particular focus on the Heron's Landing residential complex.

d. *Show how all parking areas will be drained. (ex: C4.0)*

Response: Drainage through all parking areas is reflected in the Grading and Utility Plans included with this updated submittal. Specifically, the storm drainage basins and lines show how the parking areas will be drained.

2. *Civil Sheets—from Planning*

a. *The greenway does not connect in three places to the Heron's Landing Apartments as conditioned in Resolution 5163-13. The connection points will need to be provided as public access easements (ex: sheet C1.0)*

Response: The Civil and Landscape Plan Sheets have been updated to reflect greenway connections in three places to the Heron's Landing Apartments. These connection points will be provided as public access easements.

3. *Architectural Sheets—from Planning*

a. *The loading dock doors are difficult to decipher, especially for New Seasons and the Home Goods stores. Staff was unable to count and measure them to see if they meet TDC. (sheets A2.10 #3, A2.11 #3, and A2.12 #2).*

Response: Additional elevations have been provided to detail the loading areas for Home Goods and New Seasons.

b. *On elevation #4, staff was unable to determine what the 10-foot high structure is on the left side of the elevation. Please identify. It appears to be a trash compactor. If so, it needs to be screened (sheet A2.10)*

Response: Additional elevations have been provided which show screening for this area.

c. *Staff is unsure what the three roof top shapes are. Please identify either what architectural features these are or what roof equipment is being proposed. All roof top equipment must be screened from view (TDC 73.150(18)). (sheet A2.13 #2)*

Response: Elevation #4 has been detailed and labeled to provide information about the rooftop equipment and screen.

d. *The architectural features proposed at the July 23, 2013 City Council Hearing are missing. (sheet A2.11, A2.12, A2.13, A3.10)*

Response: The applicant has reviewed the elevations with City staff and has provided updated elevations that provide green screens flanking the Home Goods



store. The Master Plan depicted an element above the existing Barbara Johnson store. The Barbara Johnson store will remain until their lease expires, at which time the elevation and interior space will be revised consistent with the Master Plan. The applicant has included a perspective with enhanced landscaping that shows the corner. The proposed improvements along with the building articulation provide for visual interest at the corner that is distinct.

- e. *The applicant has separately proposed a parapet to screen the roof top equipment during this architectural review. Please show proposed roof top equipment on these elevations along with proposed screening. (sheet A3.10)*

Response: The applicant has revised the elevations to depict rooftop equipment.

- f. *The plans are not to scale. Consequently, staff cannot determine if the elevations meet code or conditions of approval without a scale. Please include a scale on sheets A3.10, A4.10, A5.10, and A6.10.*

Response: The applicant has provided scales on the elevations.

- g. *The plans show 147 overall bike parking spaces and 74 covered spaces. Please show your bike parking calculation on the plans or in the narrative. In staff's initial calculation 255 overall bike parking spaces and 139 covered bike parking spaces are required (TDC 73.360(2)(a)). (sheet A7.10)*

Response: The applicant has addressed this comment below under 5a.

- h. *Add the architectural items in Condition L of Resolution 5163-13. (all A sheets)*

Response: The applicant has provided elevations within the submittal. The applicant understands the Architectural Review process may result in additional conditions being placed on the development.

NARRATIVE PACKAGE and EXHIBITS

4. Narrative—from Engineering

- a. **The top of page 14 indicates proposed connections from the shared pathway easement to Heron's Landing Apartments. These are not indicated clearly on the plans. Please revise the plan accordingly and show access as a public access easement (ex: p. 14)**

Response: The Civil Sheets have been updated to reflect greenway connections in three places to the Heron's Landing Apartments. These connection points will be provided as public access easements. Page 14 within the project narrative has been updated to reflect the addition of the greenway connections.



b. State the three southbound lanes are either 11 or 12-feet. Plan sheet C1.1 indicates 12-foot wide lanes which matches requirements, but conflicts with this statement (Resolution 5163-13). (p. 20, #7)

Response: Page 20, #7 within the project narrative has been updated to state that all three southbound lanes are each 12-feet wide.

5. Narrative and Exhibit A—from Planning

a. Please show bike parking compliance calculation. Staff calculates a significantly higher required covered and overall bike parking than shown. Please refer to Incomplete Item #1g. (p. 51 and Exhibit A)

Response: Please find City calculations as well as the applicant's calculations below. The applicant is proposing to use the "shopping center" requirement. This is appropriate as the site is being developed as a shopping center and patrons are expected to visit one or more businesses when they visit the site.

| BUILDING | SF | USE | BICYCLE PARKING RATIO | MINIMUM BICYCLE PARKING | COVERED BIKE PARKING |
|----------|----------------|------------------------|--|-------------------------|----------------------|
| 1005 | 33,562 | Retail Shop | 0.5/1,000 SF | 17 | 8.39 |
| 1010 | 21,750 | Retail Shop | 0.5/1,000 SF | 11 | 5.44 |
| 1030 | 2,900 | Restaurant | 2/1,000 SF | 6 | 1.45 |
| 1040 | 110,093 | Shopping Center | 0.5/1,000 SF Gross Floor Area | 55 | 27.52 |
| A | 12,500 | Retail Shop | 0.5/1,000 SF | 6 | 3.13 |
| B | 5,850 | Retail Shop | 0.5/1,000 SF | 3 | 1.46 |
| C | 3,950 | Bank | 2 or 0.33/1,000 SF Whichever is greater | 2 | 0.20 |
| D | 32,459 | Retail Shop | 0.5/1,000 SF | 16 | 8.11 |
| E | 3,172 | Bank Drive Up | 2 or 0.33/1,000 SF Whichever is greater | 2 | 0.20 |
| F | 5,500 | Restaurant | 2/1,000 SF | 11 | 2.75 |
| G-100 | 6,500 | Restaurant Drive Up | 2/1,000 SF | 13 | 3.25 |
| H-100 | 4,526 | Restaurant | 2/1,000 SF | 9 | 2.26 |
| J-100 | 5,797 | Restaurant | 2/1,000 SF | 12 | 2.90 |
| N-100 | 45,000 | Health Club | 2/1,000 SF Exercise Area | 90 | 45.00 |
| | 293,559 | | | 253 | 112 |



| | | | | | |
|------------|---------|-----------------|-------------|-----|----|
| Total Area | 293,559 | Shopping Center | .5/1,000 SF | 147 | 74 |
|------------|---------|-----------------|-------------|-----|----|

- b. Narrative and plans do not discuss the conditions to be added to Street A as stated they were discussed in the Compliance Report. (p. 92 and Exhibit A)

Response: The applicant has revised page 21 to provide additional detail concerning Street A. The applicant has also revised the attached plan set to include a cross section for Street A as well as a slope easement.

6. Exhibit A and Conditions of Approval Compliance Report—from Planning
a. Conditions M and O relating to Cabela's architectural features and oversize vehicle parking are missing from the Compliance Report responses.

Response: The applicant understands the conditions and has provided elevations for the proposed Cabela's within the attached plan set. The applicant is not proposing to construct oversized vehicle parking.

7. Exhibit A – Bicycle and Pedestrian Plan—from Engineering
a. Pedestrian and Bicycle Plan shows shared pathway easement connection to Heron's Landing on the east side, unlike the plans (C1.0). Plans do not show crosswalk at Boones Ferry Road crossing Street A.

Response: Sheet C1.0 and the rest of the attached plan set have been revised to show the pedestrian and bicycle connections referenced above.

8. Exhibit A – Cross-Section A-A—from Engineering
a. The tree well width shown on the shared path is 2-foot wide, not the City standard 5' x 5' (Resolution 5163-13 and PWCC Drawing #514). Please revise.

Response: The applicant is proposing an alternative standard which is detailed within the attached landscape plans. The 2' x 2' grate is provided and there is a 5' x 5' planting area provided.

9. Exhibit A – Cross-Section C-C—from Engineering
a. Show tree wells on the east side of the public-like street, but the plans (L1.2) do not.

Response: Cross Section C-C has been revised to accurately reflect the landscape plan. Please see the revised cross section attached.



10. Exhibit A – Bicycle and Pedestrian Plan—from Engineering

- a. Pedestrian and Bicycle Plan shows shared pathway easement connection to Heron's Landing on the east side, unlike the plans (C1.0). Plans do not show crosswalk at Boones Ferry Road crossing Street A.

Response: The easements to Heron's Landing on have been provided within the revised plan set.

Nyberg Rivers

Tualatin, Oregon

An Application For:
Architectural Review Board

September 13, 2013

Completeness Responses October 23~~18~~, 2013

Formatted: Font: Italic

Formatted: Font: Italic

Applicant:
Centercal Properties, LLC
7455 SW Bridgeport Road, Suite 205
Tigard, OR 97224
Phone: (503) 968-8940
Contact: Michael Kirk

Prepared by:
Cardno
5415 SW Westgate Drive, Suite 100
Portland, Oregon 97221
Phone: 503-419-2500
Fax: 503-419-2600

21198310

PAGE INTENTIONALLY LEFT BLANK

TABLE OF CONTENTS

TABLE OF CONTENTS..... 3

I. INTRODUCTION..... 7

GENERAL INFORMATION 7

SUMMARY OF PROPOSAL..... 8

 Background 8

SURROUNDING USES 9

II. TUALATIN DEVELOPMENT CODE (TDC)..... 10

TDC 73: COMMUNITY DESIGN STANDARDS 13

 Section 73.150 Objectives 13

 Section 73.160 Standards..... 27

 Section 73.200 Structure Design - Commercial, Industrial, Public and Semi-Public Uses. 33

 Section 73.210 Objectives 34

 Section 73.220 Standards..... 37

 Section 73.226 Objectives 38

LANDSCAPING 39

 Section 73.240 Landscaping General Provisions. 39

 Section 73.250 Tree Preservation..... 42

 Section 73.310 Landscape Standards - Commercial, Industrial, Public and Semi-Public Uses. 43

OFF-STREET PARKING LOT LANDSCAPING 44

 Section 73.320 Off-Street Parking Lot Landscaping Standards..... 44

 Section 73.340 Off-Street Parking Lot and Loading Area Landscaping - Commercial, Industrial, Public and Semi-Public Uses, and Residential and Mixed Use Residential Uses within the Central Design District..... 44

 Section 73.360 Off-Street Parking Lot Landscape Islands - Commercial, Industrial, Public, and Semi-Public Uses. 45

 Section 73.370 Off-Street Parking and Loading..... 48

 Section 73.380 Off-Street Parking Lots..... 57

 Section 73.390 Off-Street Loading Facilities. ~~606059~~

 Section 73.400 Access..... ~~616160~~

TDC 74: PUBLIC IMPROVEMENT REQUIREMENTS ~~676766~~

IMPROVEMENTS ~~676766~~

 Section 74.110 Phasing of Improvements. ~~676766~~

 Section 74.120 Public Improvements..... 67

 Section 74.130 Private Improvements. ~~686867~~

 Section 74.140 Construction Timing..... ~~686867~~

RIGHT-OF-WAY ~~696968~~

 Section 74.210 Minimum Street Right-of-Way Widths..... ~~696968~~

EASEMENTS AND TRACTS ~~707069~~

 Section 74.310 Greenway, Natural Area, Bike, and Pedestrian Path Dedications and Easements. ~~707069~~

 Section 74.320 Slope Easements. ~~707069~~

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

| | |
|---|-------------------------|
| Section 74.330 Utility Easements..... | <u>717470</u> |
| Section 74.340 Watercourse Easements..... | <u>717470</u> |
| Section 74.350 Tracts..... | <u>727274</u> |
| TRANSPORTATION..... | <u>727274</u> |
| Section 74.410 Future Street Extensions..... | <u>727274</u> |
| Section 74.420 Street Improvements..... | <u>767676</u> |
| Section 74.440 Streets, Traffic Study Required..... | <u>828284</u> |
| Section 74.450 Bikeways and Pedestrian Paths..... | <u>848483</u> |
| Section 74.470 Street Lights..... | <u>848483</u> |
| UTILITIES..... | <u>858584</u> |
| Section 74.610 Water Service..... | <u>858584</u> |
| Section 74.620 Sanitary Sewer Service..... | <u>868686</u> |
| Section 74.630 Storm Drainage System..... | <u>868686</u> |
| Section 74.640 Grading..... | <u>878786</u> |
| Section 74.650 Water Quality, Storm Water Detention and Erosion Control..... | <u>878786</u> |
| Section 74.660 Underground..... | <u>898988</u> |
| Section 74.670 Existing Structures..... | <u>898988</u> |
| Section 74.705 Street Tree Removal Permit..... | <u>898988</u> |
| Section 74.720 Protection of Trees During Construction..... | <u>919190</u> |
| Section 74.765 Street Tree Species and Planting Locations..... | <u>919190</u> |
| TDC 75: ACCESS MANAGEMENT ON ARTERIAL STREETS..... | <u>929294</u> |
| Section 75.050 Approval Process For Access Onto Arterials, and Appeal Provisions..... | <u>929294</u> |
| Section 75.060 Existing Driveways and Street Intersections..... | <u>939392</u> |
| Section 75.070 New Intersections..... | <u>939392</u> |
| Section 75.080 Alternate Access..... | <u>949493</u> |
| Section 75.090 Interim Access..... | <u>959594</u> |
| Section 75.100 Exceptions..... | <u>959594</u> |
| Section 75.110 New Streets..... | <u>959594</u> |
| Section 75.120 Existing Streets..... | <u>969696</u> |
| TDC 50: OFFICE COMMERCIAL PLANNING DISTRICT (CO)..... | <u>989897</u> |
| Section 50.020 Permitted Uses..... | <u>989897</u> |
| CURD Block 1 Uses..... | <u>989897</u> |
| Section 50.050 Lot Size..... | <u>999998</u> |
| Section 50.060 Setback Requirements..... | <u>999998</u> |
| Section 50.065 Central Urban Renewal Area--Lot Sizes..... | <u>10040099</u> |
| Section 50.070 Structure Height..... | <u>101401400</u> |
| Section 50.080 Access..... | <u>101401400</u> |
| TDC 53: CENTRAL COMMERCIAL PLANNING DISTRICT (CC)..... | <u>102402404</u> |
| Section 53.020 Permitted Uses..... | <u>102402404</u> |
| Section 53.060 Lot Sizes..... | <u>102402404</u> |
| Section 53.070 Central Urban Renewal Area - Lot Sizes..... | <u>102402404</u> |
| Section 53.080 Setback Requirements..... | <u>103403402</u> |
| Section 53.090 Structure Height..... | <u>105405404</u> |
| Section 53.100 Access..... | <u>106406405</u> |

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

TDC 70: FLOOD PLAIN DISTRICT 107107106
Section 70.010 Purpose..... 107107106
Section 70.020 Methods of Reducing Flood Losses..... 108108107
Section 70.040 Lands to Which This Chapter Applies..... 108108107
III. CONCLUSION 109109108

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

EXHIBITS

- Exhibit A Master Plan and Conditional Use Findings
Master Plan Cross-Sections
- Exhibit B ARB Application
- Exhibit C Affidavit of Posting
- Exhibit D Natural Resource Assessment
- Exhibit E CWS Service Provider Letter
- Exhibit F Neighborhood Developer Meeting Materials
- Exhibit G Legal Description of the Property
- Exhibit H Vicinity Map
- Exhibit I Mixed Solid Waste Plan
- Exhibit J Washington County Assessor's Maps
- Exhibit K Mailing Labels
- Exhibit L Traffic Impact Analysis
- Exhibit M Arborist Report
- Exhibit N Stormwater Report
- Exhibit O Plan Set
Existing Conditions Plan
Site Plan
Grading Plan
Tree Preservation Plan
Public Facilities Plan
Photometric Plan
Landscape Plan
Building Elevations
Bicycle Parking & Trash Enclosures

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

I. INTRODUCTION

GENERAL INFORMATION

Applicant: Centercal Properties, LLC
7455 SW Bridgeport Road, Suite 205
Tigard, Oregon 97224
Phone: (503) 968-8940
Contact: Michael Kirk
mkirk@centercal.com

Applicant's Representative Cardno
5415 SW Westgate Drive; Suite 100
Portland, Oregon 97221
(503) 419-2500 phone
(503) 419-2600 fax
Contact: Michael Cerbone, AICP
michael.cerbone@cardno.com

| | | |
|-----------------------------|-----------------|--|
| Tax Lot Information: | Map | Tax Lots |
| | 2S124A & 2S124B | 1601, 1602, 2000, 2001, 2100, 2502, 2506, 2507, 2508, 2700 |

Location: City of Tualatin, Oregon
Generally bounded by SW Nyberg Rd to the south,
Martinazzi Ave to the west, Interstate 5 to the east,
and the Tualatin River to the north.

Current Zoning Districts: Office Commercial (CO)
Central Commercial (CC)
High Density Residential (RH)

Project Site Area: +/- 31.91 acres

SUMMARY OF PROPOSAL

The applicant is requesting Architectural Review approval for the all of the site improvements detailed within the plan set attached as Exhibit O. Existing buildings are proposed to be improved as detailed within the Architectural Elevations provided within Exhibit O. New buildings are proposed to be constructed consistent with the approved Nyberg Rivers Master Plan. Building pads G-100 and H-100 are proposed to be constructed as pads, with site improvements including landscaping and parking fields. The applicant understands that subsequent development of these pads (G-100 and H-100) will be subject to Architectural Review at a later date.

BACKGROUND

On August 26, 2013, the City Council voted unanimously to approve the Nyberg Rivers Master Plan and the associated Conditional Use Permit. The adopted findings for the unanimous master plan and conditional use approvals are attached as Exhibit A and incorporated herein by reference.

The Master Plan evaluated the proposed development under the Central Urban Renewal Plan Goals and Objectives including building location and size, transportation systems, pedestrian and bike networks, site plan improvements and the like. The Master Plan decision contains many conditions of approval, compliance with which is illustrated here in this ARB submittal. The Master Plan decision specifically notes those specific areas where the Master Plan did not provide a review or related conditions of approval. Those areas are found on page 3 of the Master Plan decision and are repeated here for ease of reference:


- Approve and permit retail uses within the Office Commercial (CO) designated portions of the property.
- Approve and permit outdoor sales within the Central Commercial designated portion of the property.
- Approve right-of-way vacation of the Oregon Department of Transportation property along Nyberg Road.
- Approval of any modification of land uses.
- Acceptance by the City of any easements or other land transactions for pedestrian or transportation facilities.
- A decision on whether to adopt a separate review procedure for the Master Plan
- Approve the Nyberg Rivers alternate sign program.

All of these elements were not approved by the Master Plan but were instead left for either the Conditional Use Permit or this ARB. The first two items have since been approved by the City Council in its final decision on the Conditional Use Permit attached as Exhibit A. The balance of these elements are addressed here in the ARB.

Because this site is located in an area of the City that requires Master Plan approval before ARB approval, many of the issues that would normally first arise in the ARB have already been addressed and decided by the City Council in the master plan proceeding. Thus, where these decisions have already been made and conditions of approval imposed, this application specifically lists those conditions and how the ARB proposal complies with those conditions.

The approval criteria for this ARB are listed under TDC Chapter 73, Community Design Standards. This application addresses each of those applicable criteria, as well as the development standards in each base zone, and demonstrates that the proposal meets those criteria and complies with all of the conditions of approval imposed by the City in the final Master Plan and Conditional Use permit decisions.

Lastly, a Neighborhood Meeting was held August 8, 2013 at the Sylvan Learning Center located at 7809 SW Nyberg Street in Tualatin. Attendees were presented with general information about the redevelopment project including construction timelines and procedures. A copy of the noticing and meeting materials is included with this narrative under Exhibit F.



SURROUNDING USES

Table A: SURROUNDING LAND USE

| <i>Location</i> | <i>Zoning Designation</i> | <i>Land Use</i> |
|-----------------|--|--|
| North | High Density Residential (RH) General Commercial (CG) | Tualatin River & Heron's Landing Apartments |
| South | Central Commercial (CC) | SW Nyberg Street/ Fred Meyer |
| East | General Commercial (CG) | Interstate 5 |
| West | General Commercial (CG) | SW Martinazzi Avenue/ Tualatin Central Downtown |

Formatted: Font: 9.5 pt
Formatted: Font: 9.5 pt

II. TUALATIN DEVELOPMENT CODE (TDC)

TDC 73.050 ARCHITECTURAL REVIEW

(1) In exercising or performing his or her powers, duties, or functions, the Community Development Director shall determine whether there is compliance with the following:

(a) The proposed site development, including the site plan, architecture, landscaping, parking and graphic design, is in conformance with the standards of this and other applicable City ordinances insofar as the location, height, and appearance of the proposed development are involved;

Response: The findings set forth below demonstrate that the proposal is in conformance with the approved Master Plan, as well as the standards of the TDC referenced above. The following sections demonstrate compliance with the Community Design Standards of this chapter, as well as the underlying standards of each of the applicable base zones.

(b) The proposed design of the development is compatible with the design of other developments in the general vicinity; and

Response: The approved Master Plan adopted the following findings regarding the proposed development, at page 4: "The site is located directly adjacent Interstate 5 to the east and just north of Nyberg Street, a regional roadway that provides a access to Tualatin as well as the City of Sherwood and the Highway 99w corridor. Nyberg Rivers is surrounded by a mix of compatible uses both to the west and south. To the south, the existing Fred Meyer's anchor and surrounding retail uses provide a variety of retail tenants to attract both local and regional shoppers, with more of a focus on vehicular access and vehicular trips. To the west, the Downtown Tualatin area is more focused on pedestrian scale commercial, office, and civic uses. Nyberg Rivers is situated as a regional shopping opportunity to promote both vehicle and pedestrian access into the site. The Nyberg Rivers center will serve to extend the existing downtown to the east through the network of pedestrian paths and landscape amenities that will tie into the surrounding urban fabric to create a complementary and compatible development. The vehicle access into the site will allow for safe and efficient circulation that is compatible with the Fred Meyer's development to the south.

"The Master Plan proposes to redevelop an underutilized shopping center with new construction and new tenants in an effort to enhance and reinvigorate this commercial area. The proposal features a strong commercial component including a new mix of upgraded tenants, a large retailer and an assortment of small and medium sized retail and restaurant uses. The now vacant K-Mart and the existing Jiggles restaurant are proposed to be demolished. In addition to the commercial aspect of the project, the Applicant is proposing an outdoor plaza space and amenities, pedestrian and bicycle paths, and new private roadway connections that resemble public streets with sidewalks or multiuse paths, planters and curbs. The demolition of the dated, empty buildings and

construction of new, integrated buildings eliminates blight and prevents future blight. The construction of new buildings and the development of a new and revitalized shopping center will increase the overall property value of the site. The shopping center and outdoor areas, which are in close proximity to City offices and the Public Library, will encourage public and private land uses that are anticipated to result in activity throughout business hours and into the evening."

"The site serves as a gateway to the City and eastern extension of downtown. A redeveloped center will contribute to the social and economic development of central Tualatin by improving property values. By including a range of retail, restaurant, and other uses, the proposed Master Plan includes aspects that will encourage activity during business hours, evenings, nights and weekends. Plaza spaces and outdoor seating areas will encourage outdoor activity.

The proposed development within the Master Plan area presents an opportunity to redevelop the eastern extension of downtown in a way that meets the Plan goals. The City Council concluded that certain conditions of approval are required in order for the Master Plan to be consistent with the Plan Goals and Objectives. The City Council finds that the Master Plan proposal with the conditions imposed meets the Plan Goals and Objectives."

In adopting these findings the City Council concluded that the project would meet the primary goal of the Central Urban Renewal District Plan to "encourage and facilitate commercial development in the Urban Renewal Area with an emphasis on establishing a visible and viable central business district that encourages community and business activity on weekdays, evenings and weekends".

In this same manner, the development and its design is compatible with the surrounding development as further discussed below.

(c) The location, design, size, color and materials of the exterior of all structures are compatible with the proposed development and appropriate to the design character of other developments in the vicinity.

Response: The design elevations are included in Exhibit O. These elevations demonstrate that the designs of the structures within the development have been tastefully integrated with the new development in the same center as well as surrounding properties.

The property is bordered on the north and east with vegetated corridors either along I-5 or the Tualatin River. To the south is Nyberg Street and the Fred Meyer center and to the immediate west is City Hall and Martinazzi. The design environment for this proposal is largely created by the development itself. Because there are existing buildings to be retained on the site, the architecture of the new buildings is designed to create a coherent design environment. The palette of materials contain quality elements such as natural tone elements like a mohave blend (darker tan) brick veneer, an earth-finish stone veneer, and a Dakota Land (tan) plaster body finish. . The color palette is designed to soften

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

and brighten the center against its natural backdrop and to work in tandem with the proposed mix of materials that includes wood, brick stone. Together with the trees to be preserved including the greenway corridor, the landscape plan brings the natural landscape through and around the site in a natural Oregon theme. The color palate and building materials are complemented by the proposed landscaping detailed within Exhibit O that includes a variety of Oregon native tree and shrub species. Trees species selected include Oregon White Oak, Douglas fir, Western Red Cedar, Vine Maple as well as Western Dogwood. Understory shrubs and ground cover include Oregon Grape, Nootka Rose, Snowberry, Bearberry, Mahonia and Juniper.

The master plan finding adopted by the City Council also found, as stated above and incorporated herein by reference, that the demolition of the dated, empty buildings and construction of new, integrated buildings eliminates blight and prevents future blight. "The construction of new buildings and the development of a new and revitalized shopping center will increase the overall property value of the site. The shopping center and outdoor areas, which are in close proximity to City offices and the Public Library, will encourage public and private land uses that are anticipated to result in activity throughout business hours and into the evening."

"The site serves as a gateway to the City and eastern extension of downtown. A redeveloped center will contribute to the social and economic development of central Tualatin by improving property values. By including a range of retail, restaurant, and other uses, the proposed Master Plan includes aspects that will encourage activity during business hours, evenings, nights and weekends. Plaza spaces and outdoor seating areas will encourage outdoor activity."

The design properly integrates the site with its surrounding uses through form and function in compliance with this criterion.

(2) In making his or her determination of compliance with the above requirements, the Community Development Director shall be guided by the objectives and standards set forth in this chapter. If the architectural review plan includes utility facilities or public utility facilities, then the City Engineer shall determine whether those aspects of the proposed plan comply with applicable standards.

Response: Again, the sections below demonstrate compliance with the Community Design Standards of this chapter, as well as address the public and private utility aspects of the project.

(3) In determining compliance with the requirements set forth, the Community Development Director shall consider the effect of his or her action on the availability and cost of needed housing. The Community Development Director shall not use the requirements of this section to exclude needed housing types. However, consideration of these factors shall not prevent the Community Development Director from imposing conditions of approval necessary to meet the requirements of this section. The costs of such conditions shall not unduly increase the cost of housing beyond the minimum necessary to achieve the purposes of this Code. As part of the Architectural Review

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

process, the Community Development Director has no authority to reduce dwelling unit densities.

Response: The development is largely limited to CC and CO zoned lands which does not require residential development. Thus redevelopment of the center does not affect the availability or cost of needed housing.

(4) As part of Architectural Review, the property owner may apply for approval to remove trees, in addition to those exemptions allowed in TDC 34.200(3), by submitting information concerning proposed tree removal, pursuant to TDC 34.210(1). The granting or denial of a tree removal permit shall be based on the criteria in TDC 34.230.

Response: The applicant has submitted a tree removal plan with this application, attached as Exhibit O and detailed within the Arborist Report included as Exhibit M. Trees within the public utility corridor will be removed under the public utility permit prior to ARB. All other trees proposed for removal will either be removed prior to ARB under the tree removal plan based on the tree location within an approved building footprint under the master plan or will not be removed until the AR is in process or complete.

TDC 73: COMMUNITY DESIGN STANDARDS

SECTION 73.150 OBJECTIVES.

All commercial, industrial, public and semi-public projects should strive to meet the following objectives to the maximum extent practicable. Architects and developers should consider these elements in designing new projects. In the Central Design District, the Design Guidelines of TDC 73.610 shall be considered. In the case of conflicts between objectives, the proposal shall provide a desirable balance between the objectives. Site elements shall be placed and designed, to the maximum extent practicable, to:

- (1) Provide convenient walkways and crosswalks which separate pedestrians from vehicles and link primary building entries to parking areas, other on-site buildings and the public right-of-way.

Response: Pedestrian access was one of the primary focuses of the master plan proceeding and review. To that end the master plan contains the following findings:

Excerpt from Master Plan findings page 6.

"The City Council finds that a well-designed commercial development that provides connections to and from nearby multi-family property meets the purposes of Goal 2. The Applicant designed the site to prove an attractive façade that faces the residential property to the north, with landscaping and screening envisioned that will provide a critical step in ensuring the resulting design will meet the City's pedestrian and design requirements.

The relationship of the Master Plan site design, building design, and pedestrian connectivity to residential uses in the downtown is discussed further in Central

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

Urban Renewal District Goals 4, 5, 6 and 11. The Applicant has proposed connections from the Shared Pathway Easement to Heron's Landing Apartments to the north. These connections provide access to the proposed development including pedestrian and bicycle paths that connect to the City Hall and Library Campus. Additionally, the proposed "Street A" will provide connections from the residential development to the western portion of downtown via a 12-foot multi-use path that leads to Boones Ferry Road. These pedestrian and bicycle paths provide connectivity to existing and future residential development in the downtown area such as in the Tualatin Commons.

The City Council finds it necessary to condition the Master Plan to ensure adequate pedestrian connectivity to existing and future housing and comply with Goal 2.

The Master Plan area and Nyberg Rivers site shall provide attractive and pedestrian-oriented features including accessways and pathways that will connect to existing and future residential development in the downtown area and specifically to the adjoining Heron's Landing Apartments property.

The Master Plan with the condition that oriented features including accessways and pathways will connect to existing and future residential development in the downtown area such as in the Tualatin Commons and the adjoining Heron's Landing Apartments property supports the neighboring housing. Walking to the Master Plan area to shop for groceries and other items supports multi-family housing and the Plan's Goal 2. With the imposition of the condition of approval, the Master Plan meets Goal 2."

Excerpt from Master Plan findings pages 8-9.

Connections between Private and Civic Facilities. The Central Urban Renewal District Plan identifies the Nyberg Rivers site as part of the Tualatin Downtown and it is adjacent to the Tualatin Library and City Hall campus along Martinazzi Avenue. The Master Plan contains pedestrian and bicycle circulation that connects the Nyberg Rivers site to the City Hall campus and the western portion of downtown Tualatin. A shared pathway is shown on the west side of "Street A" continuing south and terminating at a pedestrian route just to the east City property. Two pedestrian routes are shown, one on the north side and one on the south side, of the continuation of Seneca Street. Bike lanes proposed by the developer are also show on the north and south sides of a future Seneca Street. These circulation routes demonstrate a connection between the proposed development and civic facilities

The Applicant originally proposed loading and services facilities on the north side of Buildings D1, D2, 1005, 1010, 1030 and 1040. The proposed loading and service truck route ("Primary Truck Circulation") showed trucks accessing SW Martinazzi and SW Boones Ferry Road through the Library/City Hall Campus. Trucks using these routes are a significant conflict for the Library and City Hall functions, public plazas and the public that use them. The Council finds it necessary to remove these routes as truck routes on the Master Plan.

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

The Master Plan shows a plaza between Building 1030 and the west corner of Building 1040. This is the intersection of the north-south bicycle and pedestrian aisle/accessway that passes between the buildings and the east-west walkway that extends across the south-facing elevations (facing the parking lot/SW Nyberg Street) of the main building storefronts. The plaza contains seating, canopies, awnings, landscape planters, water, a mastodon statue, and statuary features. The width of the open portions of the plaza range from approximately 20 ft. to 30 ft. with 10 ft. to 12 ft. wide aisles within the plaza. The area of the plaza is approximately 6,400 sq. ft., including the outdoor dining area associated with Building 1030 (food & beverage), raised planters and sculpture/feature pads.

The Master Plan also includes the east-west building front walkway that extends across the building storefronts from Building D1/D2 on the west (Michaels store) to the east corner of Building 1040 as a plaza. The walkway area in front of Buildings 1030, 1010, 1005, D2 and D1 includes raised planters, seating, sculpture features, canopies and outdoor dining/outdoor sales areas associated with the grocer and retailer storefronts. The width of the east west walkway/plaza surface is approximately 12-16 ft. while the passage way for pedestrians ranges from 8 ft. to 16 ft. taking into account raised planters, trees, and space devoted to dining/ retail activities. The Master Plan provides and promotes civic facilities such as community gathering spaces and pedestrian amenities.

The dimensions and features of the plaza create potential conflicts with bicycles and pedestrians passing through the narrow sections of the proposed plaza and the walkway plaza. Adequately sized passages between objects and structures located in the plaza are necessary to allow circulation of bicycle and pedestrian users that are traveling through the plaza area between the stores or on the bicycle and pedestrian paths that connect to public areas and ways such as the Tualatin River Greenway, Civic Center and south of SW Nyberg Street.

The conditions of approval imposed reduce conflicts and expand public spaces. The Master Plan's public gathering places and pedestrian and bicycle connections to the nearby civic facilities will provide a public benefit consistent with Goal 4.

Council finds conditions of approval are needed to satisfy Goal 4. The conditions of approval are:

- Recreational equipment, apparel and sports outfitting sales are prohibited in areas identified as public gathering, multi-function open plaza and plaza seating with fire pit as identified in the Building Frontage landscape plan.
- A minimum of 12 feet of clear, unobstructed width for walkways or accessways through a plaza or along the building frontage between Building D1 and northeast corner of the public gathering, multi-function plaza seating with fire pit as identified in the Building Frontage landscape plan.
- The Truck Route designations from "Street A" and Seneca Street are removed.
- The Master Plan with the conditions of approval satisfies Goal 4."

- The applicant has proposed a pedestrian network that complies with these findings and conditions of approval.

All buildings within the Nyberg Rivers project are served by sidewalks at their entrances. All new buildings provide pedestrian sidewalks and designated routes across driveways to other new buildings within the development. Specifically, there is a continuous sidewalk in front of new buildings D-110, D-120, D-125, D-130, 1005, 1010, 1030 and 1040. There is a continuous sidewalk and crosswalk network that links new buildings E-100, F-100, G-100, H-100, J-100 and N-100 that provides a protected pedestrian route. See Sheets L 1.7-A, 1.7-B, 1.8-A and L1.8-B to show the central plaza elements and pedestrian treatments along the central plaza. Specific pedestrian circulation patterns are illustrated on Exhibit O and in cross sections A-A through G-G approved in the Master Plan and incorporated here as sheets within Exhibit M. The site plan approved as a part of the Master Plan and submitted to the ARB includes an extensive pedestrian system that both links the buildings to parking and off-site areas and provides a convenient and safe on-site pedestrian system that provides separation from the public right-of-way.

(2) Avoid barriers to disabled individuals.

Response: The Site Plan included with this application shows ADA compliant parking stalls located in the central parking area nearest the primary entrances to the buildings. These stalls are adjacent to pedestrian crossing areas that provide safe access to the buildings consistent with the ADA requirements. As shown on the Site Plan (Sheets C1.0-1.2, Exhibit O) provided with this application and summarized in the Project Summary notes on the Site Plan, the ADA stalls are all 9-feet wide by 19-feet deep, with an associated off-loading area for van accessible spaces that is 8-feet wide. As shown on the Grading Plans (Sheets 3.0-3.2, Exhibit O), the general grades through the ADA areas vary from 2.1 to 2.8% resulting in a site and overall design that is easily navigated. The site grades coupled with the numerous pathways and sidewalks provide the opportunity for access from and to all areas proposed for development within the master plan area consistent with the intent of this criterion.

(3) Locate and design drive-through facilities in a manner which does not conflict with pedestrian routes or other vehicular circulation and minimizes adverse impacts on adjacent properties.

Response: The Master Plan originally showed a new building H-100 identified as a drive-thru restaurant, this building pad is no longer shown as a drive-thru. The Master Plan area currently has three drive-thru banks and one drive-thru restaurant (Wendy's). The Applicant submitted a supplemental site plan for the August 7, 2013 master plan hearing eliminating one of the drive-thru restaurants (H-100). The City found that eliminating an additional drive-thru restaurant was conducive to pedestrian friendly developments, reducing pedestrian crossing conflicts and would not discourage people from walking between buildings and connecting to public walkways. (Master Plan findings at page 5).

Thus the City appropriately conditioned the Master Plan on the following:

- The City Council finds it necessary to condition the Master Plan to limit the number of drive-thru facilities in the Master Plan to no more than four and designing any new or re-located drive-thru facilities so the service windows and service aisles are screened from public streets.

The City further found that by limiting the total number of drive-thru facilities to four and screening service windows and aisles from public streets the Goal 1 objective is satisfied.

As shown on the Site Plan sheets L1.2 and 1.3 included with this ARB under Exhibit O, all relocated drive-thru facilities are sited to negate any conflict with pedestrian routes or vehicular circulation accessways. The drive-through facilities are located between the building and the property line or right-of-way, away from the central parking area and pedestrian access paths. In compliance with the Master Plan condition of approval, the relocated drive through service window and service aisle at Building F-100 are screened from SW Nyberg Road with a combination of trees and shrubs. According to the planting plan and planting legend and notes on Sheet L1.0 within Exhibit M, the trees along SW Nyberg Road include Serviceberries, River Birch, Western Juniper, Red Pine, and Thornless Honeylocust within the landscape strip right-of-way. Shrubs and accents include Snowberry, Wood's Rose, Coralberry, and Fountain Grass.

- (4) **Break up parking areas with landscaping (trees, shrubs and walkways) and buildings to lessen the overall impact of large paved areas.**

Response: As shown on Sheets L1.2 through L1.6 under Exhibit O, all proposed and existing parking lots within the site are broken up with landscaping that includes trees, shrubs, groundcovers and walkways. The main entryway is lined with street trees and includes a landscaped median to welcome customers and soften the edges of the driveway. All landscaping elements were approved under the Master Plan process.

- (5) **Utilize landscaping in parking areas to direct and control vehicular movement patterns, screen headlights from adjacent properties and streets, and lessen the visual dominance of pavement coverage.**

Response: This objective was specifically addressed in the Master Plan findings at pages 23-24. There the findings state:

"The Master Plan proposes 6 ft. x 6 ft. (measured to outside of curb) "Parking Diamonds" as a form of required parking area interior landscaping as an alternative to planters that extend between rows of parking and separate groups of parking stalls. The Community Design Standards of the Tualatin Development Code (TDC 73.310, 73.320, 73.360) requires parking lot landscaping to provide shade within the parking lot for users and with required trees and other planted vegetation in parking lot planters to both physically and visually break up the extensive paved surfaces and the parked vehicles in the parking area.

Community Design standards require 25 sq. ft. of parking area landscaping (both interior and perimeter to the parking area), a minimum of 1 deciduous shade tree per 4 parking stalls within a 5 foot wide (inside of curb) planter island. The proposed "diamonds" have limited surface area as a planter within a paved parking area. With limited planter area in the diamonds, there is more paved surface area in a parking lot and less landscaping to break up the scale of the pavement and the parked vehicles. This has an impact for people who using the parking lot and visually for the public from adjacent streets and public ways. Staff was concerned that the proposed "diamonds" do not serve the purposes of landscaped islands and do not provide adequate soil volume for the long term growth of the required shade trees."

The City was concerned about the adequacy of the 6 ft. x 6 ft. "diamond" planters and found:

"The Applicant submitted plans for the diamond planters that indicates that the proposed Nyberg Rivers "diamond planters" will be constructed differently and in a manner that will support adequate deciduous tree growth and be able to meet the standard of achieving a minimum 30 ft. mature height and a sufficient canopy required in TDC 73.360 Parking Lot Landscaping."

To ensure the success of the Applicant's proposed planters, the City imposed a condition of approval.

To ensure adequate tree growth and shade, Council finds the following conditions of approval necessary to meet Goal 11:

- Trees planted in "diamond planters" shall achieve a growth that is a minimum of 66 % (2/3) of the 30 ft. mature tree height standard in TDC 73.360(7)(a-e) within 5 years of planting.
- Trees planted in the "diamond planters" shall be monitored annually. The applicant, its successors or assigns, shall submit a report from a certified arborist that documents tree height, health of canopy, and size of trunk by November 1 of each year after planting.
- If the trees do not meet the performance requirement, then Applicant, its successors and assigns, must remedy the failure. Such remedy shall be up to and including rebuilding and expanding the planting area.

The proposed landscape planting plans included as Exhibit O – L1.2 through L1.6 shows how landscape islands, diamond and corridors direct and control vehicular movement patterns, screen headlights and soften the pavement coverage and will meet the master plan condition of approval. The mix of landscape islands interspersed with landscape diamonds uniformly throughout the parking field provides a variety of parking lot landscape treatments to achieve the intent of the code. Shade via a mix of native tree species is provided throughout the parking lot to reduce the heat island effect that can result from parking lots. A mix of evergreen and deciduous trees provides for a variety tree

forms, leaf types and color that adds visual interest and complements the existing natural areas adjacent the site. Likewise the mix of shrubs and ground covers work together to provide for visual interest and assist with breaking up the parking fields within the site. Parking lot islands and landscape strips are provided along the central driveway and at the end of parking aisles to control vehicular movement patterns and screen headlights. The landscape diamonds will soften the pavement coverage by providing a tree canopy to reduce the "heat-island effect" within Nyberg Rivers.

(6) Provide vehicular connections to adjoining sites.

Response: The City Council comprehensively reviewed the transportation system and the vehicle connections to adjoining sites in the Master Plan findings. There the City found that the proposed connections provide both adequate transportation facilities and connections to adjoining sites. To ensure these connections, the City imposed the following conditions of approval.

City Council finds the following transportation improvements are needed for the Master Plan to comply with Goal 5, and therefore imposes them as conditions of approval:

- The Seneca Street extension to the Nyberg Rivers site with a signal at SW Martinazzi Avenue constructed to the standards of a Minor Collector Street. The time of construction will be determined through the public facilities decision process and is not anticipated or required to occur prior to removal of the Council Chambers building.
- A westbound right turn lane on SW Nyberg Road.
- Two southbound left turn lanes and a shared through/right turn lane from the site's access onto SW Nyberg Road.
- Two inbound receiving lanes; and
- The associated signal improvements at the main entrance.

In addition, City Council finds the street cross-sections need to be modified to satisfy Goal 5 and are needed to serve the Master Plan area. The City Council approves the Master Plan cross sections with the following modifications:"

The City Council then listed several modifications to the cross sections at pages 14-16 of the Master Plan findings.

Exhibit M – Sheet C1.0 and the modified cross sections in compliance with the conditions are attached here within Exhibit A. The Exhibits show the vehicular connections through the site, with connections to adjoining sites and streets that support the local and regional traffic circulation pattern. Upon review of these same connections in the recent and unanimous approval by the City of the master plan, the City found that these connections with the modified cross sections provide vehicular connections to adjoining sites. Those same findings can be made here as the applicant has complied with the conditions of approval

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

imposed by the City to ensure that these cross sections provide adequate access in compliance with this criterion.

- (7) **Emphasize entry drives into commercial complexes and industrial park developments with special design features, such as landscaped medians, water features and sculptures.**

Response: The proposed design complies with this criterion. The Applicant has provided a main entry drive to the commercial center from Nyberg Street. Several exhibits demonstrate the entry character of this main entry: Cross section A-A: Nyberg Main Entry, the Nyberg Rivers Entry Landscaping exhibit and the Enlargement 'A' Plan View and Section were all submitted as a part of the Master Plan approval package. The Landscape Planting Plan submitted with this ARB package on Sheet L1.2, Exhibit O, does show the proposed trees, shrubs and groundcover proposed along the main entry aisle. The east side of the entry will reflect Coast Range plantings with Beach Plum, Cascara, Red Sunset Maples, and Urbanite Ash, while the west side will transition to Central Oregon plantings to include Quaking Aspen and Serviceberry. Sheet L1.7-B, shown on Sheet L1.7, does show the central entry as it transitions to the front of the central plaza, with enhanced concrete pavers at the pedestrian crossings, plaza amenities to include benches, entry icon elements, seating and patios, and columnar deciduous trees to buffer from the adjacent traffic.

Elements shown on the Landscape Planting Plan includes (2) 12-foot northbound travel or entry lanes; (3) southbound or egress lanes also at ~~either 11 or 12~~-feet; a 1.5 foot median between the travel lanes; a varying 4 to 7-foot planter strip to the east; a 14-foot shared path with tree wells; and a 4-foot planter strip to the west side of the entry.

- (8) **Locate, within parking lots, pedestrian amenities and/or landscaping in areas which are not used for vehicle maneuvering and parking.**

Response: As shown on the Landscape Planting Plan, Exhibit M – L1.0 through L1.6, all areas within the parking lot not used for parking stalls or drive isles are designated as landscape areas or walkways. Several pedestrian plazas are also incorporated into the site design and provide areas for patrons to rest and socialize. These areas enhance the aesthetics and pedestrian experience of the Nyberg Rivers redevelopment. The cross sections attached as Exhibit O show the width and character of the pedestrian amenities providing well landscaped and well lighted access throughout the site including within and around the parking areas in compliance with this objective.

- (9) **Encourage outdoor seating areas which provide shade during summer and sun during winter, trash receptacles and other features for pedestrian use. Plantings with a variety of textures and color are encouraged.**

Response: Three primary outdoor seating areas have been incorporated into the design. A central pedestrian plaza is shown between Buildings 1010 and 1040 that will provide outdoor seating areas. Two additional pedestrian plazas and seating areas have been incorporated in the site design; one in the southwest corner of the site and one in between proposed buildings H-100 and J-100. As shown on

the elevations submitted as Exhibit O – C1.0, plantings and pedestrian amenities will be featured along the building frontages to create a sense of place and scale suitable to a pedestrian environment. These amenities include dining patios, cove seating, bench seating, a pedestrian promenade, outdoor art, a water feature, a fire pit and enhanced paving at the central pedestrian plaza. Trees, shrubs, ground cover and raised planting areas are provided in and around the pedestrian areas to provide shade and a variety of plant forms and colors.

The location and design elements of each of these plazas was articulated as well in the City's final decision on the Master Plan. At pages 8-9, the Master Plan decision states:

The Master Plan shows a plaza between Building 1030 and the west corner of Building 1040. This is the intersection of the north-south bicycle and pedestrian aisle/accessway that passes between the buildings and the east-west walkway that extends across the south-facing elevations (facing the parking lot/SW Nyberg Street) of the main building storefronts. The plaza contains seating, canopies, awnings, landscape planters, water, a mastodon statue, and statuary features. The width of the open portions of the plaza range from approximately 20 ft. to 30 ft. with 10 ft. to 12 ft. wide aisles within the plaza. The area of the plaza is approximately 6,400 sq. ft., including the outdoor dining area associated with Building 1030 (food & beverage), raised planters and sculpture/feature pads.

The Master Plan also includes the east-west building front walkway that extends across the building storefronts from Building D1/D2 on the west (Michaels store) to the east corner of Building 1040 as a plaza. The walkway area in front of Buildings 1030, 1010, 1005, D2 and D1 includes raised planters, seating, sculpture features, canopies and outdoor dining/outdoor sales areas associated with the grocer and retailer storefronts. The width of the east west walkway/plaza surface is approximately 12-16 ft. while the passage way for pedestrians ranges from 8 ft. to 16 ft. taking into account raised planters, trees, and space devoted to dining/ retail activities. The Master Plan provides and promotes civic facilities such as community gathering spaces and pedestrian amenities.

The Master Plan conditions of approval require:

- Recreational equipment, apparel and sports outfitting sales are prohibited in areas identified as public gathering, multi-function open plaza and plaza seating with fire pit as identified in the Building Frontage landscape plan.
- A minimum of 12 feet of clear, unobstructed width for walkways or accessways through a plaza or along the building frontage between Building D1 and northeast corner of the public gathering, multi-function plaza seating with fire pit as identified in the Building Frontage landscape plan.
- The Truck Route designations from "Street A" and Seneca Street are removed.

Exhibit O, Sheets L1.7 and 1.8 demonstrate that each of these conditions of approval have been satisfied. No outdoor sales area is designated within the plaza, a minimum of 12 foot clear is provided for an unobstructed walkway and the truck route designations have been removed from Street A

(10) Create opportunities for, or areas of, visual and aesthetic interest for occupants and visitors to the site.

Response: The approved Nyberg Rivers Master Plan document shows examples of landscaping and building elements and articulation that will create areas of visual and aesthetic interest for visitors to the site. The perspective plans included with the approved Master Plan portray a retail center with ample landscaping, pedestrian pathways, and visual amenities to draw the user interest into the site and central plaza area. The perspective plan is acted out in the Master Plan approved Landscape Plant Material Schedule and Building Frontage Landscape Plan, as well as the Pedestrian and Bicycle Plan. In particular, the on-site pedestrian system shown on the Master Plan Pedestrian and Bicycle Plan included within Exhibit A creates walking and biking opportunities throughout the site. The pedestrian system is complimented by an extensive landscaping plan. The Master Plan findings at pages 7-9 discuss the pedestrian system and how it and the overall design of the project provide areas of visual and aesthetic interest to occupants and visitors:

“The Master Plan contains pedestrian and bicycle circulation that connects the Nyberg Rivers site to the City Hall campus and the western portion of downtown Tualatin. A shared pathway is shown on the west side of “Street A” continuing south and terminating at a pedestrian route just to the east City property. Two pedestrian routes are shown, one on the north side and one on the south side, of the continuation of Seneca Street. Bike lanes proposed by the developer are also show on the north and south sides of a future Seneca Street. These circulation routes demonstrate a connection between the proposed development and civic facilities.”

“The Master Plan shows a plaza between Building 1030 and the west corner of Building 1040. This is the intersection of the north-south bicycle and pedestrian aisle/accessway that passes between the buildings and the east-west walkway that extends across the south-facing elevations (facing the parking lot/SW Nyberg Street) of the main building storefronts. The plaza contains seating, canopies, awnings, landscape planters, water, a mastodon statue, and statuary features. The width of the open portions of the plaza range from approximately 20 ft. to 30 ft. with 10 ft. to 12 ft. wide aisles within the plaza. The area of the plaza is approximately 6,400 sq. ft., including the outdoor dining area associated with Building 1030 (food & beverage), raised planters and sculpture/feature pads.

The Master Plan also includes the east-west building front walkway that extends across the building storefronts from Building D1/D2 on the west (Michaels store) to the east corner of Building 1040 as a plaza. The walkway area in front of Buildings 1030, 1010, 1005, D2 and D1 includes raised planters, seating, sculpture features, canopies and outdoor dining/outdoor sales areas associated with the grocer and retailer storefronts. The width of the east west walkway/plaza surface is approximately 12-16 ft. while the passage way for pedestrians ranges

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

from 8 ft. to 16 ft. taking into account raised planters, trees, and space devoted to dining/ retail activities. The Master Plan provides and promotes civic facilities such as community gathering spaces and pedestrian amenities." In addition, at page17 of the Master Plan findings, the City Council found that the Art Walk and Ice Age Discovery Trail would add important visual elements to the project:

"Connections are shown and/or described that would bring the ArtWalk - A Self-Guided Tour of Tualatin's Art, Cultural and Natural History, and the Ice Age Discovery Trail into the site. When combined with the proposed Mastodon sculpture, the ArtWalk and Ice Age Discovery Trail would bring a sense of place, local history, and interpretive opportunities to the development."

The approved Master Plan also includes a shared pathway easement through the natural area adjacent to the Tualatin River. The pathway is shown on Site Plan Sheet C1.2 under Exhibit O. The Applicant will provide an easement to the City for this pathway, but the Applicant does not propose to construct the pathway as a part of this application. Ultimately, the pathway will provide opportunities to retail customers and the public to view the Tualatin River and provides an excellent aesthetic element of the project.

(11) Conserve, protect and restore fish and wildlife habitat areas, and maintain or create visual and physical corridors to adjacent fish and wildlife habitat areas.

Response: Although there are no specifically identified fish or wildlife habitat areas on the project site itself, the Master Plan includes a large natural area adjacent to the Tualatin River Greenway. A shared pathway easement will go through the natural area and provide a link to the Tualatin River Greenway. To the extent that the natural area is considered a habitat area, by maintaining the area as a natural area, the project conserves and protects this habitat area. Additionally, both the natural area and the future pathway will provide visual and a physical corridor to the Tualatin River and the greenway. The City Council's Master Plan findings at pages 16 to 17 further described the natural area and pathway:

"The Tualatin River Greenway will provide connectivity and links with residential and commercial areas in east Tualatin when the trail crosses under I-5 and joins the existing segment of the Tualatin River Greenway Trail that runs through Brown's Ferry Park to Tualatin's eastern boundary. This Shared Pathway is especially important because it will serve as an alternative route that would be safer than using the Nyberg Street bridge over I-5 (at exit 289) where bicyclists and pedestrians are required to cross several freeway on-and-off ramps with high traffic volumes. The Nyberg Street bridge over I-5 (at exit 289) was identified as a high accident location in the recently adopted Transportation System Plan.

A future connection to the west along the Tualatin River that is located within the outer 40' from the top of bank is needed and so it will fit within the boundaries as defined for the Tualatin River Greenway."

- (12) Provide safe pathways for pedestrians to move from parking areas to building entrances.

Response: As demonstrated in the Master Plan and Site Plan (Exhibit O – C1.0 to 1.2) and the Landscape Planting Plan (Exhibit O – Sheets L1.2 through L1.6), separate pedestrian walkways and crosswalks are provided along the primary building entrances from the parking areas, between buildings, and to the adjacent public right-of-ways. Landscape islands and plantings along the walkways help distinguish the pedestrian circulation routes from the vehicular circulation routes. Every parking area is connected to an on-site pathway that connects the parking area to public streets and to building entrances. Pathways extend north and south, as well as east and west throughout the site and connect to adjacent properties or streets on all sides of the site.

- (13) Design the location of buildings and the orientation of building entrances for commercial, public and semi-public uses such as churches, schools and hospitals to provide adequate pedestrian circulation between buildings and to provide preferential access for pedestrians to existing or planned transit stops and transit stations.

Response: As demonstrated in the Site Plan (Exhibit O – C1.0 to 1.2) and the Landscape Planting Plan (Exhibit O – Sheets L1.2 through L1.6), separate pedestrian walkways and crosswalks are provided along the primary building entrances from the parking areas, between buildings, and to the adjacent public right-of-ways. There is an existing bus transit stop located along SW Martinazzi Avenue, directly west of the site. Pedestrian and bicycle connectivity is provided to the bus stop. Goal 6 of the Central Urban Renewal Plan specifically addresses transit. The Council's findings regarding transit are set forth on page 19 of the findings:

"TriMet service is located nearby on SW Martinazzi (a stop at the City Library) and on SW Boones Ferry Road extending from the WES Commuter Rail station further west to the Tualatin Park & Ride located at I-5 Exit 290 to the north. The proposed "Street A" extension from the Nyberg Rivers site to SW Boones Ferry Road will be near an existing TriMet bus stop on SW Boones Ferry Road near the Tualatin River Bridge. In addition, this development is within the boundaries of the Southwest Corridor Plan which identifies the need for improved transit service. Current options being evaluated by the region show high capacity transit service potentially traveling along Boones Ferry Road, with a terminus at the WES station. The Master Plan, as currently proposed, would provide sufficient connections to the existing and proposed transit improvements near the site on Boones Ferry Road and Martinazzi Avenue.

The Master Plan supports the metropolitan transportation system and its goals to provide alternate modes of transportation for the residential and employment population of the Urban Renewal Area. The Master Plan complies with Goal 7."

As recognized by the City Council, the on-site pedestrian circulation plan provides a robust pedestrian circulation plan that provides direct access to existing and planned transit stops and stations.

- (14) Provide accessways between commercial, public and semi-public development and publicly-owned land intended for general public use; arterial and collector streets where a transit stop and/or a bike lane is provided or designated; and abutting residential, commercial and semi-public property.

Response: As demonstrated on the Site Plan (Exhibit O – C1.0 to 1.2) and the Landscape Planting Plan (Exhibit O – Sheets L1.2 through L1.6), separate pedestrian walkways and crosswalks are provided along the primary building entrances from the parking areas, between buildings, and to the adjacent public right-of-ways. There is an existing bus transit stop located along SW Martinazzi Avenue, directly west of the site. Pedestrian and bicycle connectivity is provided to the bus stop. The City Council's findings at page 19 demonstrate that the project provides more than adequate connections between the commercial elements of the project and the public and semi-public uses on adjacent and nearby property:

"The City Council finds that the purpose of Goal 6 is met with the Master Plan's pedestrian/bicycle system as well as the conditions of approval. The bicycle and pedestrian facilities serve the purposes outlined in the Transportation System Plan. The bicycle and pedestrian facilities provide on-and-off street connectivity in all directions to residential, commercial, and industrial areas with public parks, the library, and schools. The system of pedestrian and bicycle facilities contributes to and promotes linkage between the downtown project site and Community Park. In particular, the bicycle and pedestrian system provides a link between the Urban Renewal Area and residential area, parks, natural areas, as well as links to the business areas north and south of SW Boones Ferry Road. Pedestrian and bikeways allow a direct connection through the site and in all directions. Pedestrian and bikeways will be lighted in accordance with City standards, and the buildings will incorporate awnings and other shade and rain protection forms. The overall site will include attractive pedestrian streetscapes. The City Council concludes the Master Plan with the conditions of approval complies with Goal 6."

- (15) Not applicable

- (16) Accessways should be designed and located in a manner which does not restrict or inhibit opportunities for developers of adjacent properties to connect with an accessway, and provide continuity from property to property for pedestrians and bicyclists to use the accessway.

Response: As demonstrated in the Site Plan (Exhibit O – C1.0 to 1.2) and the Landscape Planting Plan (Exhibit O – Sheets L1.2 through L1.6), separate pedestrian walkways and crosswalks are provided along the primary building entrances from the parking areas, between buildings, and to the adjacent public right-of-ways. These accessways and their locations do not restrict or inhibit opportunities for developers of adjacent properties to connect with an accessway. As discussed above, the City Council found the following with respect to connectivity to adjacent properties:

"The City Council finds that the purpose of Goal 6 is met with the Master Plan's pedestrian/bicycle system as well as the conditions of approval. The bicycle and pedestrian facilities serve the purposes outlined in the Transportation System

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

Plan. The bicycle and pedestrian facilities provide on-and-off street connectivity in all directions to residential, commercial, and industrial areas with public parks, the library, and schools. The system of pedestrian and bicycle facilities contributes to and promotes linkage between the downtown project site and Community Park. In particular, the bicycle and pedestrian system provides a link between the Urban Renewal Area and residential area, parks, natural areas, as well as links to the business areas north and south of SW Boones Ferry Road. Pedestrian and bikeways allow a direct connection through the site and in all directions. Pedestrian and bikeways will be lighted in accordance with City standards, and the buildings will incorporate awnings and other shade and rain protection forms. The overall site will include attractive pedestrian streetscapes. The City Council concludes the Master Plan with the conditions of approval complies with Goal 6."

- (17) **Provide preferential parking for carpool and vanpools to encourage employees to participate in carpools and vanpools.**

Response: Carpool or vanpool designated spots have not been demarcated at this time. However, the applicant will work with the City to address carpool and vanpool parking if needed.

- (18) **Screen elements such as mechanical and electrical equipment, above ground sewer or water pump stations, pressure reading stations and water reservoirs from view.**

Response: The buildings have been designed to screen mechanical and electrical equipment from view. There are no proposed above ground sewer or water pump stations within the project. Mechanical equipment has been located on top of the proposed buildings and is screened from view utilizing walls. The attached elevations included as part of Exhibit O provide more detail.

- (19) **Not applicable**

- (20) **When a fish and wildlife habitat area abuts or is on the subject property the applicant and decision authority for a development application should consider locating buildings farther away from the fish and wildlife habitat area. [Ord. 635-84, § 36, 6/11/84; Ord. 649-84, §7, 11/26/84; Ord. 661-85, §10, 3/25/85; Ord. 827-91, §6 and 7, 3/25/91; Ord. 849-91, §38 and 39, 11/25/91; Ord. 862-92, §51, 3/23/92; Ord. 895-93, §8, 5/24/93; Ord. 904-93, §47, 9/13/93; Ord. 920-94, §17, 4/11/94; Ord. 965-96, §82, 12/9/96; Ord. 979-97, §52, 7/14/97; Ord. 1097-02, 2/11/02; Ord. 1224-06 §22, 11/13/06]**

Response: While no specific fish and wildlife habitat area has been identified on the property, the applicant has elected to preserve a large natural area adjacent to the Tualatin River. This area will ultimately include a shared pathway easement and two overlook areas. The proposed alignment of the trail easement and overlooks was arrived at after close coordination with Clean Water Services and City staff. The proposed setbacks are further away from the Tualatin River and the Tualatin River Greenway than required by the TDC in order to preserve the natural area and views of the Tualatin River.

SECTION 73.160 STANDARDS.

The following standards are minimum requirements for commercial, industrial, public and semi-public development, and it is expected that development proposals shall meet or exceed these minimum requirements.

(1) Pedestrian and Bicycle Circulation.

(a) For commercial, public and semi-public uses:

- (i) a walkway shall be provided between the main entrance to the building and any abutting public right-of-way of an arterial or collector street where a transit stop is designated or provided. The walkway shall be a minimum of 6 feet wide and shall be constructed of concrete, asphalt, or a pervious surface such as pavers or grasscrete, but not gravel or woody material, and be ADA compliant, if applicable;**

Response: As shown on the Site Plan (Exhibit O– Sheets C1.0-1.2), direct pedestrian connections are present from each building to every other building on the site, forming complete pedestrian connections throughout the site and to adjacent property. The pedestrian walkways also connect directly to public rights of way, adjacent property and the natural area adjacent to the Tualatin River. All walkways exceed 6 feet, are constructed of concrete or pavers and are ADA compliant.

- (ii) walkways shall be provided between the main building entrances and other on-site buildings and accessways. The walkways shall be a minimum of 6 feet wide and shall be constructed of concrete, asphalt, or a pervious surface such as pavers or grasscrete, but not gravel or woody material, and be ADA compliant, if applicable;**

Response: As shown on the Site Plan (Exhibit O– Sheets C1.0-1.2), direct pedestrian connections are present from each building to every other building on the site, forming complete pedestrian connections throughout the site and to adjacent property. The pedestrian walkways also connect directly to public rights of way, adjacent property and the natural area adjacent to the Tualatin River. All walkways exceed 6 feet, are constructed of concrete or pavers and are ADA compliant.

- (iii) walkways through parking areas, drive aisles, and loading areas shall be visibly raised and of a different appearance than the adjacent paved vehicular areas;**

Response: As shown on the Site Plan (Exhibit O– Sheets C1.0-1.2), all pedestrian walkways are raised above parking and loading areas, bordered by landscaping where possible and are significantly different in appearance from adjacent vehicular areas. Contrasting materials serve to set the walkway apart from the vehicle areas, where these connections cross vehicle areas, pavers and/or crosswalk striping is utilized to denote the presence of pedestrians.

- (iv) **accessways shall be provided as a connection from the development's internal bikeways and walkways to all of the following locations that apply: abutting arterial or collector streets upon which transit stops or bike lanes are provided or designated; abutting undeveloped residential or commercial areas; adjacent undeveloped sites where an agreement to provide an accessway connection exists; and to abutting publicly-owned land intended for general public use, including schools;**

Response: As shown on the Site Plan (Exhibit O – Sheets C1.0-1.2), there are direct pedestrian connections to public rights of way abutting the site. All walkways exceed 6 feet, are constructed of concrete and are ADA compliant. As the City Council's findings for the Master Plan provide, at page 19:

"The City Council finds that the purpose of Goal 6 is met with the Master Plan's pedestrian/bicycle system as well as the conditions of approval. The bicycle and pedestrian facilities serve the purposes outlined in the Transportation System Plan. The bicycle and pedestrian facilities provide on-and-off street connectivity in all directions to residential, commercial, and industrial areas with public parks, the library, and schools. The system of pedestrian and bicycle facilities contributes to and promotes linkage between the downtown project site and Community Park. In particular, the bicycle and pedestrian system provides a link between the Urban Renewal Area and residential area, parks, natural areas, as well as links to the business areas north and south of SW Boones Ferry Road. Pedestrian and bikeways allow a direct connection through the site and in all directions. Pedestrian and bikeways will be lighted in accordance with City standards, and the buildings will incorporate awnings and other shade and rain protection forms. The overall site will include attractive pedestrian streetscapes. The City Council concludes the Master Plan with the conditions of approval complies with Goal 6."

The AR proposal continues to comply with this finding in compliance with this criterion.

- (v) **fences or gates which prevent pedestrian and bike access shall not be allowed at the entrance to or exit from any accessway.**

Response: As shown on the Site Plan (Exhibit O – Sheets C1.0-1.2), no fences or gates which prevent pedestrian and bike access are proposed.

- (vi) **bikeways shall be provided which link building entrances and bike facilities on the site with the adjoining public right-of-way and accessways.**

Response: As shown on the Site Plan (Exhibit O – Sheets C1.0-1.2), all bikeways linking the on-site buildings are directly connected to adjoining rights of way and accessways. The City Council's findings for the Master Plan provide, at page 19:

"The City Council finds that the purpose of Goal 6 is met with the Master Plan's pedestrian/bicycle system as well as the conditions of approval. The bicycle and pedestrian facilities serve the purposes outlined in the Transportation System

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

Plan. The bicycle and pedestrian facilities provide on-and-off street connectivity in all directions to residential, commercial, and industrial areas with public parks, the library, and schools. The system of pedestrian and bicycle facilities contributes to and promotes linkage between the downtown project site and Community Park. In particular, the bicycle and pedestrian system provides a link between the Urban Renewal Area and residential area, parks, natural areas, as well as links to the business areas north and south of SW Boones Ferry Road. Pedestrian and bikeways allow a direct connection through the site and in all directions. Pedestrian and bikeways will be lighted in accordance with City standards, and the buildings will incorporate awnings and other shade and rain protection forms. The overall site will include attractive pedestrian streetscapes. The City Council concludes the Master Plan with the conditions of approval complies with Goal 6."

- (vii) **Outdoor Recreation Access Routes shall be provided between the development's walkway and bikeway circulation system and parks, bikeways and greenways where a bike or pedestrian path is designated.**

Response: As shown on the Site Plan (Exhibit O – Sheets C1.0-1.2), there is a direct connection between the commercial component of the project and the natural area adjacent to the Tualatin River. The shared pathway system on the site provides an east-west connection, as well as a direct connection to the south. As shown on Site Plan C1.0, the shared pathway from SW Nyberg Road will provide north-south access into the site from Nyberg Road and the Fred Meyer commercial complex to the south. The path extends along the central entry across a pedestrian crossing into the central pedestrian plaza. A shared pathway is also denoted along Street 'A' on the south/west side of the street. This pathway extends into the site before meeting up with the proposed Seneca Street sidewalk which then ties into the east-west pedestrian path along both the south side of the east-west drive aisle and the north side (the central plaza). Designated bicycle lanes are located along Nyberg Road and the Seneca Street extension.

- (c) **Curb ramps shall be provided wherever a walkway or accessway crosses a curb.**

Response: Exhibit O demonstrates that curb ramps will be provided on-site wherever a walkway or accessway crosses a curb.

- (d) **Accessways shall be a minimum of 8 feet wide and constructed in accordance with the Public Works Construction Code if they are public accessways, and if they are private accessways they shall be constructed of asphalt, concrete or a pervious surface such as pervious asphalt or concrete, pavers or grasscrete, but not gravel or woody material, and be ADA compliant, if applicable.**

Response: Exhibit O, Sheets L1.7 and 1.8 __ demonstrate that all proposed accessways along the building frontages will be meet or exceed the minimum 8-foot standard. Where the accessways are public, they will be constructed to public works

standards. Where private, they will be constructed of concrete or asphalt and, where applicable, be ADA compliant.

- (e) **Accessways to undeveloped parcels or undeveloped transit facilities need not be constructed at the time the subject property is developed. In such cases the applicant for development of a parcel adjacent to an undeveloped parcel shall enter into a written agreement with the City guaranteeing future performance by the applicant and any successors in interest of the property being developed to construct an accessway when the adjacent undeveloped parcel is developed. The agreement shall be subject to the City's re-view and approval.**

Response: The Nyberg Rivers redevelopment project will be developed in whole, with no proposed undeveloped parcels. Therefore, this criterion does not apply. Pad G-100 and H-100 will be developed at a later date, however the applicant is proposing to construct the pedestrian connections at this time consistent with the intent of this requirement.

- (g) **Accessways shall be constructed, owned and maintained by the property owner.**

Response: All accessways will be constructed, owned and maintained by the property owner with two clarifications. The construction of Street A requires the dedication of additional ROW by the City prior to construction. In addition, in compliance with the master plan conditions of approval, Seneca Street will not be constructed until such time as the City decides to relocate Council Chambers and make available sufficient right of way for the construction. The City Council specifically found that the Seneca Street extension was not required until such time as these conditions were satisfied.

(2) **Drive-up Uses.**

- (a) **Drive-up uses shall provide a minimum stacking area clear of the public right-of-way and parking lot aisles from the window serving the vehicles as follows:**

- (i) **Banks--each lane shall provide a minimum capacity for five automobiles.**
- (ii) **Restaurants--each lane shall provide a minimum capacity for eight automobiles.**
- (iii) **Other Drive-Up Uses--each lane shall provide a minimum capacity for two to eight automobiles, as determined through the architectural review process.**
- (iv) **For purposes of this Section, an automobile shall be considered no less than twenty feet in length. The width and turning radius of drive-up aisles shall be approved through the architectural review process.**

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

- (b) Parking maneuvers shall not occur in the stacking area. The stacking area shall not interfere with safe and efficient access to other parking areas on the property.
- (c) Locate drive-up aisles and windows a minimum of 50 feet from residential planning districts to avoid adverse impacts. A wall or other visual or acoustic may be required through the architectural review process.

Response: The Nyberg Rivers redevelopment project proposes one relocated drive-up restaurant in addition to the three existing bank drive-ups on site. The relocated drive-up restaurant will be housed in building F-100. The vehicle queuing lanes for building F-100 are shown on the Site Plan (Exhibit O – C1.1). The queuing length for building F-100 allows for 11 cars in the queue, well above the 8 automobile minimum. In approving the Master Plan, the City Council found that a total number of four drive-thru buildings would be permitted and imposed the following condition of approval:

"The City Council finds it necessary to condition the Master Plan to limit the number of drive-thru facilities in the Master Plan to no more than four and designing any new or re-located drive-thru facilities so the service windows and service aisles are screened from public streets.

The relocated drive-thru facility service windows are screened from public streets through a mix of landscape trees and shrubs. Therefore, the Applicant has addressed this standard and also met the requirements of the Master Plan. No drive-thru facilities are proposed within 50 feet of residential planning districts.

(3) Safety and Security.

- (a) Locate windows and provide lighting in a manner which enables tenants, employees and police to watch over pedestrian, parking and loading areas.
- (b) In commercial, public and semi-public development and where possible in industrial development, locate windows and provide lighting in a manner which enables surveillance of interior activity from the public right-of-way.
- (c) Locate, orient and select on-site lighting to facilitate surveillance of on-site activities from the public right-of-way without shining into public rights-of-way or fish and wildlife habitat areas.
- (d) Provide an identification system which clearly locates buildings and their entries for patrons and emergency services.
- (e) Shrubs in parking areas must not exceed 30 inches in height. Tree canopies must not extend below 8 feet measured from grade.
- (f) Above ground sewer or water pumping stations, pressure reading stations, water reservoirs, electrical substations, and above ground natural gas pumping stations shall provide a minimum 6' tall security fence or wall.

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

Response: As shown on the building elevations submitted as part of Exhibit O, each of the buildings feature a large percentage of glazing along the building exterior, primarily along the front building façade, creating eyes to the public places. Also, lighting will be provided throughout the site, both in the internal parking area, as well as the pedestrian accessways and plazas throughout the site. Light locations and cover are provided as Exhibit L – E-1 through E-6. The Site Plan included with this application demonstrates safe and efficient access into and through the site, both for pedestrian and vehicle access. The central entry located at Nyberg Street provides a focal entry point to the major tenant spaces, with signage to direct visitors through the site. As shown on the Landscape Planting Plan (Exhibit O – Sheets L1.2 through L1.6), parking lot landscaping will not exceed 30 inches in shrub height and tree canopies will not extend below 8 feet measured from grade. Landscaping and pathways will also assist with directing pedestrians and provide safe visibility corridors throughout the site. The Landscape Planting Plan and the landscape elements outlined in the elevation exhibits (Exhibit O) display the landscape elements and amenities to be provided throughout the site. These elements will combine to provide a safe and secure site.

(4) Service, Delivery and Screening.

- (a) On and above grade electrical and mechanical equipment such as transformers, heat pumps and air conditioners shall be screened with sight obscuring fences, walls or landscaping.**
- (b) Outdoor storage, excluding mixed solid waste and source separated recyclables storage areas listed under TDC 73.227, shall be screened with a sight obscuring fence, wall, berm or dense evergreen landscaping.**
- (c) Above ground pumping stations, pressure reading stations, water reservoirs; electrical substations, and above ground natural gas pumping stations shall be screened with sight-obscuring fences or walls and landscaping.**

Response: Specific locations for mechanical equipment have not been determined at this time, however, consistent with this requirement, all above grade electrical and mechanical equipment will be screened with site-obscuring fences, walls and/or landscaping, fully consistent with other enclosures and storage areas. Any site obscuring landscaping will be consistent with the landscaping throughout the project site. Outdoor storage areas are shown on the attached Site Plan between buildings F-100 and G-100, buildings G-100 and H-100, and on the north side of J-100. Those areas will be screened with a site obscuring wall. There are no above-ground pumping stations or water reservoirs proposed on-site. The bicycle parking and trash enclosure exhibit included with the building elevations shows the combination trash enclosure and bike rack. This structure effectively screens the trash enclosure through a sight obscuring wood wall.

- (5) The Federal Americans with Disabilities Act (ADA) applies to development in the City of Tualatin. Although TDC, Chapter 73 does not include the Oregon Structural Specialty Code's (OSSC) accessibility standards as requirements to be reviewed during the Architectural Review process, compliance with the OSSC is a**

requirement at the Building Permit step. It is strongly recommended all materials submitted for Architectural Review show compliance with the OSSC.

Response: All development on the project site is designed to meet the applicable standards of the ADA. While specific building standards will be addressed at the building permit stage, the site plan demonstrates that the number and location of parking stalls meets ADA requirements, that all pedestrian walkways and building frontages meet ADA standards. Those ADA stalls are marked on the Site Plan (Exhibit O – Sheets C1.0 - 1.2).

- (6) (a) All industrial, institutional, retail and office development on a transit street designated in TDC Chapter 11 (Figure 11-6) shall provide either a transit stop pad on-site, or an on-site or public sidewalk connection to a transit stop along the subject property's frontage on the transit street.
- (b) In addition to (a) above, new retail, office and institutional uses abutting major transit stops as designated in TDC Chapter 11 (Figure 11-6) shall:
- (i) locate any portion of a building within 20 feet of the major transit stop or provide a pedestrian plaza at the transit stop;
 - (ii) provide a reasonably direct pedestrian connection between the major transit stop and a building entrance on the site;
 - (iii) provide a transit passenger landing pad accessible to disabled persons;
 - (iv) provide an easement or dedication for a passenger shelter as determined by the City; and
 - (v) provide lighting at the major transit stop. [Ord. 862-92, §51, 3/23/92; Ord. 895-93, §9, 5/24/93; Ord. 898-93, §5, 6/14/93; Ord. 904-93, §48, 49 and 50, 9/13/93; Ord. 947-95, §8, 9, 10 and 11, 7/24/95; Ord. 965-96, §83 and 84, 12/9/96; Ord. 1008-98, §6, 7/13/98; Ord. 1046-00 §35, 2/14/00; Ord. 1103-02, , 3/25/02; Ord. 1224-06 §23, 11/13/06]

Response: Martinazzi Avenue is classified as a transit street, with a bus line and bus stop located near the City Library, just west of Nyberg Rivers. Pedestrian and bicycle accessways are provided from the site to the transit stop. The transit stop provides a covered bench and waiting area, trash receptacle and bicycle rack, which constitutes as pedestrian plaza. The connection to the transit stop is via a direct accessway to the larger project site, and is lighted in accordance with City standards.

SECTION 73.200 STRUCTURE DESIGN - COMMERCIAL, INDUSTRIAL, PUBLIC AND SEMI-PUBLIC USES.

Purpose.

The purpose of commercial, industrial, public and semi-public building design objectives and standards is to implement the purpose and objectives of TDC 73.020(2) and are intended to promote functional, safe, innovative and attractive buildings which are

compatible with the surrounding environment. This concerns the building form including the articulation of walls and roof design, materials, colors, placement of elements such as windows, doors, mechanical equipment and identification features. [Ord. 705-86, §6, 9/8/86]

Response: This narrative, the attached Site Plan, and the building elevations and view perspectives provided with this submittal package and the approved Master Plan, demonstrate that the design and layout of the site and the buildings promote functional, safe, innovative and attractive buildings which are compatible with the surrounding environment. This is primarily achieved through building siting, articulation, materials, colors, and the placement of glazing, doors, and other identification features. Site design elements combine with the structure design to create a safe, innovative, and attractive redevelopment project that ties into the existing infrastructure and provides a transition to both the downtown area to the west and the natural area along the Tualatin River to the north of the site.

SECTION 73.210 OBJECTIVES.

All commercial, industrial, public and semi-public projects should strive to meet the following objectives to the maximum extent practicable. Architects and developers should consider these elements in designing new projects. In the Central Design District, the Design Guidelines of TDC 73.610 shall be considered. In case of conflicts between objectives, the proposal shall provide a desirable balance between the objectives. Buildings shall be designed, to the maximum extent practicable, to:

- (1) Minimize disruption of natural site features such as topography, trees and water features.

Response: As the majority of the Nyberg Rivers site features existing development, there will be minimal disruption of the natural site features. Site topography will remain relatively unchanged, larger tree stands located to the east and north in the site will remain, and there is no proposed structural development within the conservation area or the Tualatin River riparian area. The only trees that will be removed from the site will be those necessary to facilitate construction of the approved Master Plan structures, uses, parking and utilities. The site plan does propose a walkway with outlook points providing pedestrian and bicycle circulation within the conservation area, however, it would be constructed at a later date, as only the easement is proposed as a part of this application.

- (2) Provide a composition of building elements which is cohesive and responds to use needs, site context, land form, a sense of place and identity, safety, accessibility and climatic factors. Utilize functional building elements such as arcades, awnings, entries, windows, doors, lighting, reveals, accent features and roof forms, whenever possible, to accomplish these objectives.

Response: The composition of building elements is best displayed in the collection of elevations attached in Exhibit O, which shows a retail center with a sense of place, created through a mix of building articulation and roof forms, columns and glazing, and landscaping within the plaza. Patios, cove seating, awnings, entries, windows and lighting all work to create a cohesive development, while avoiding unnecessary uniformity that welcomes users into the site. New construction will include significant glazing, articulated facades, varied roof lines and other distinguishing features.

The design proposed is consistent with the City's decision and direction in the master plan as shown in the following excerpt:

"The Master Plan includes design concepts for each elevation of the proposed buildings which demonstrate the high quality of the intended finishes as well as the architectural massing and articulation of each façade. Cross-sections demonstrate the attractive and functional streetscape and walkway lighting. Together with the integrated landscape plan evokes a sense of place. Each of the design elements enhance the overall appearance of the site, as well as public safety and convenient within the Urban Renewal Area. The Master Plan with the conditions imposed will result in an aesthetically pleasing development which will tend to promote the desirability of investment and occupancy of the Master Plan area.

The City did have some concerns about the design of certain buildings on the site as shown in this additional excerpt:

"To be consistent with Goal 11, the Nyberg Rivers Master Plan should incorporate more windows and architectural features on each of the four sides of Buildings 1040, G-100, H-100, J-100 and N-100. These include additional building articulation and variation in height, incorporate more windows on Building 1040 and other Buildings to provide a visual connection between the store interior and the exterior including walkways and parking areas, and to add distinguishing building design features and materials to achieve a stronger design relationship to Tualatin's downtown architectural style."

The City Council then imposed the following condition: There shall be additional windows and architectural features on each of the four sides of Buildings 1040, G-100, H-100, J-100 and N-100.

The applicant has revised the elevations for buildings 1040, G-100, J-100 and N-100 as provided within Exhibit O. Where feasible the applicant has provided additional windows, architectural features have been added to elevations to provide for visual interest and break up walls consistent with the intent of this condition.

- (3) **Where possible, locate loading and service areas so that impacts upon surrounding areas are minimized. In industrial development loading docks should be oriented inward to face other buildings or other loading docks. In commercial areas loading docks should face outward towards the public right-of-way or perimeter of the site or both.**

Response: Loading and service areas for the central retail center of the site will all be located on the back side of the building, along the northern edge of the property and will face the perimeter of the site, consistent with this requirement. This portion of the site is configured to handle larger truck circulation and loading docks, while limiting conflict with shoppers and pedestrians accessing the shared

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

pathway through the natural area. Loading for the individual tenant buildings will be conducted during non-business hours to minimize conflict with pedestrian and vehicle traffic and, to the extent practicable, have been located to minimize the impacts on surrounding areas.

- (4) **Enhance energy efficiency in commercial and industrial development through the use of landscape and architectural elements such as arcades, sunscreens, lattice, trellises, roof overhangs and window orientation.**

Response: The Landscape Planting Plan submitted as Exhibit O – Sheets L1.2 through L1.6 features trees, shrubs, and groundcover that create natural canopies throughout the site to limit the heat-island effect. Proposed glazing along the building frontages will provide natural lighting into the tenant spaces, reducing the need for internal building lighting. Also, as the central retail center and plaza is south facing, solar exposure will be maximized. Many of the buildings include awnings, overhangs and other features that both enhance energy efficiency and provide protection from the elements.

- (5) **Locate and design entries and loading/service areas in consideration of climatic conditions such as prevailing winds, sun and driving rains.**

Response: The primary entrances to the central retail buildings are oriented to the south, which will provide natural solar exposure. The loading areas are located to the back portion of the building to the north. The loading facilities are angled to “tuck” into the buildings, providing some level of screening and protection from the elements.

- (6) **Give consideration to organization, design and placement of windows as viewed on each elevation having windows. Surveillance over parking areas from the inside, as well as visual surveillance from the outside in, should be considered in window placement.**

Response: Glazing on the buildings is located in the central portion of many buildings, providing visual corridors both into the tenant spaces and out to the surrounding pedestrian and parking areas. Where windows are not present on a particular elevation, the reason for such omission is due to the internal features and activities of the building at issue. For example, it is impractical to include windows on an elevation where the interior of the building contains storage or other features which are incompatible with windows.

- (7) **Select building materials which contribute to the project’s identity, form and function, as well as to the surrounding environment.**

Response: The building elements and materials selected for Nyberg Rivers provides a palette of colors, materials, and design elements that create a sense of place and identity for the site. The existing buildings (buildings A, B and C) have facades using stone facing around entrances and pillars and a beige/brown color palette with red accenting on the signage. The Applicant is proposing to continue this color palette and stone detailing throughout the entire site with slight variations in architectural form and accenting color to distinguish each building and tenant. For example, New Seasons would have lime green accent walls flanked by dark

brown walls and a slanted roof line above the main entrance. Specific materials and architectural styles are presented in Exhibit O.

- (8) **Select colors in consideration of lighting conditions and the context under which the structure is viewed, the ability of the material to absorb, reflect or transmit light and the color's functional role (e.g., to identify and attract business, aesthetic reasons, image-building).**

Response: The palette of colors maintains a lighter, softer color palette with brighter colors used as accents and highlights. While the background palate provides a cohesive and lighter design theme, the accents allow special identify for individual users. As an example, the existing buildings (buildings A, B and C) have facades using stone facing around entrances and pillars and a beige/brown color palette with red accenting on the signage. The Applicant is proposing to continue this color palette and stone detailing throughout the entire site with slight variations in architectural form and accenting color to distinguish each building and tenant. For example, New Seasons would have lime green accent walls flanked by dark brown walls and a slanted roof line above the main entrance. Specific materials and architectural styles are presented in Exhibit O.

- (9) **Where possible, locate windows and provide lighting in a manner which enables tenants, employees and police to watch over pedestrian, parking and loading areas.**

Response: Glazing on the buildings is located in the central portion of many buildings, providing visual corridors both into the tenant spaces and out to the surrounding pedestrian and parking areas. As discussed above, where windows are not present on a particular elevation, the reason for such omission is due to the internal activities and uses of the building.

- (10) **Where practicable locate windows and provide lighting in a manner which enables surveillance of interior activity from the public right-of-way or other public areas. [Ord. 904-93, §51, 9/13/93; Ord. 1097-02, 2/11/02]**

Response: Glazing on the buildings is located in the central portion of many buildings, providing visual corridors both into the tenant spaces and out to the surrounding pedestrian and parking areas, which enables surveillance of interior activity from the central plaza and parking areas.

SECTION 73.220 STANDARDS.

The following standards are minimum requirements for commercial, industrial, public and semi-public development and it is expected that development proposals shall meet or exceed these minimum requirements.

- (1) **Safety and Security.**

- (a) Locate, orient and select on-site lighting to facilitate surveillance of on-site activities from the public right-of-way or other public areas without shining into public rights-of-way or fish and wildlife habitat areas.
- (b) Provide an identification system which clearly identifies and locates buildings and their entries.
- (c) Shrubs in parking areas shall not exceed 30 inches in height, and tree canopies must not extend below 8 feet measured from grade, except for parking structures and underground parking where this provision shall not apply. [Ord. 904-93, §52, 9/13/93; Ord. 20-94, §18, 4/11/94; Ord. 1224-06 §24, 11/13/06]

Response: Adequate lighting will be provided on-site, as is demonstrated in the site photometric plan provided with this application within Exhibit O. Adequate signage will be provided to guide users into the site, as well as directing them to the specific tenant areas within the different buildings. All parking lot landscaping will conform to the requirements listed above in order to ensure clear vision corridors. As shown on the site photometric plan, lighting will be consistent with City standards, will not shine into public rights-of-way and will not be directed to the natural area on the north edge of the site. All entries will be clearly identifiable through signage, windows and doors. Landscaping materials selected are consistent with the standards set forth above and will be maintained to meet these standards.

SECTION 73.226 OBJECTIVES.

All new or expanded multi-family, including townhouses, commercial, industrial, public and semi-public projects should strive to meet the following objectives to the maximum extent practicable. Architects and developers should consider these elements in designing new projects. In the Central Design District, the Design Guidelines of TDC 73.610 shall be considered. In the case of conflicts between objectives, the proposal shall provide a desirable balance between the objectives. Townhouses may necessitate a different balancing than multi-family developments such as apartments. Mixed solid waste and source separated recyclable storage areas shall be designed to the maximum extent practicable, to:

- (1) Screen elements such as garbage and recycling containers from view.
- (2) Ensure storage areas are centrally located and easy to use.
- (3) Meet dimensional and access requirements for haulers.
- (4) Designed to mitigate the visual impacts of storage areas.
- (5) Provide adequate storage for mixed solid waste and source separated recyclables.
- (6) Improve the efficiency of collection of mixed solid waste and source separated recyclables. [Ord. 898-93, §7, 6/14/93. Ord. 1025-99, §40, 7/26/99; Ord. 1097-02, 2/11/02]

Response: As described above, for the central buildings, mixed solid waste and source separated recyclables will be located within the buildings, while storage areas are

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

shown between buildings F-100 and G-100, G-100 and H-100, and north of J-100. All garbage and recycling storage bins will be contained within enclosed structures. These structures will be approximately 18' L x 24' W. Proposed locations and structure details are provided as Exhibit O. The storage areas meet the dimensional and access requirements for haulers, while providing easy access for the tenant spaces. Landscaping will be provided to soften the edges of the structures and provide some additional screening. The location and design of the solid waste areas was coordinated with the local garbage hauler, Exhibit I includes a Mixed Solid Waste Plan and correspondence from the hauler that the location and design are acceptable.

LANDSCAPING

SECTION 73.240 LANDSCAPING GENERAL PROVISIONS.

- (1) The following standards are minimum requirements.
- (3) The minimum area requirement for landscaping for uses in CO, CR, CC, CG, ML and MG Planning Districts shall be fifteen (15) percent of the total land area to be developed, except within the Core Area Parking District, where the minimum area requirement for landscaping shall be 10 percent. When a dedication is granted in accordance with the planning district provisions on the subject property for a fish and wildlife habitat area, the minimum area requirement for landscaping may be reduced by 2.5 percent from the minimum area requirement as determined through the AR process.

Response: Nyberg Rivers is located within the CC, CO, and RH Districts. Therefore, the minimum landscape percentage is 15%. As shown on the Site Plan provided with this narrative, there are 5.6 acres or 21% of the net land area (not including the natural area) designated as landscape area. This also accounts for the central plaza and hardscape elements located throughout the site. The Applicant's landscaping plan exceeds the minimum requirement by 6 percent.

- (9) Yards adjacent to public streets, except as described in the Hedges Creek Wetlands Mitigation Agreement, TDC 73.240(7), shall be planted to lawn or live groundcover and trees and shrubs and be perpetually maintained in a manner providing a park-like character to the property as approved through the Architectural Review process.

Response: The landscape setback along Nyberg Street could qualify as a yard adjacent to a public street. The setback area is shown on Exhibit O, Sheet C1.1 and is planted with deciduous trees and lawn and live groundcover that will be maintained in a manner providing a park-like character to the Nyberg Rivers property. The landscape area adjacent to Nyberg Street has an average width of 10 feet as proposed and approved in the master plan.

- (10) Yards not adjacent to public streets or Low Density Residential (RL) or Manufacturing Park (MP) Planning Districts shall be planted with trees, shrubs, grass or other live groundcover, and maintained consistent with a landscape plan indicating areas of future expansion, as approved through the Architectural Review process.

Response: The only qualifying area that may be considered as a yard not adjacent to a public street or RL or MP Planning District would be the area along the natural area. This portion of the site located to the north of the proposed commercial center is proposed to be planted with trees, shrubs and grass to be maintained in a park-like setting. No future expansion is proposed through this area. While not likely relevant to this approval criterion, this landscaped area is shown on Exhibit O, Sheets L 1.5 and 1.6 and is not modified from the plan submitted and approved is part of the master plan.

(11) Any required landscaped area shall be designed, constructed, installed, and maintained so that within three years the ground shall be covered by living grass or other plant materials. (The foliage crown of trees shall not be used to meet this requirement.) A maximum of 10% of the landscaped area may be covered with un-vegetated areas of bark chips, rock or stone. Disturbed soils are encouraged to be amended to an original or higher level of porosity to regain infiltration and stormwater storage capacity.

Response: The proposed landscape plan attached as Exhibit O, Sheets L 1.0 through L 1.10, demonstrates compliance with this standard. The proposed landscape materials have been selected, and will be planted and maintained, to achieve the coverage within 3 years. In addition, in adopting the Master Plan, the City Council imposed several conditions of approval relative to the parking lot diamond planters:

- Trees planted in "diamond planters" shall achieve a growth that is a minimum of 66 % (2/3) of the 30 ft. mature tree height standard in TDC 73.360(7)(a-e) within 5 years of planting.
- Trees planted in the "diamond planters" shall be monitored annually. The applicant, its successors or assigns, shall submit a report from a certified arborist that documents tree height, health of canopy, and size of trunk by November 1 of each year after planting.
- If the trees do not meet the performance requirement, then Applicant, its successors and assigns, must remedy the failure. Such remedy shall be up to and including rebuilding and expanding the planting area.

The proposed landscape diamond planters have been submitted and approved as a part of the Master Plan approval. In order to assure that the tree diamond landscape areas do achieve a viable size and performance level, the applicant is committing to the following measures:

- Prior to planting, all trees procured for the project will receive a rigorous and thorough review by the Landscape Architect prior to planting. This includes a coordinated selection process with regional nurseries as well as tree inspection after delivery and prior to installation.
- All tree planting topsoil will be imported and amended per topsoil analysis provided by a qualified soils lab. The applicant's landscape architect will review the subgrade preparation and, as shown on the Enlargement C exhibit submitted with the Master Plan, include an

Cardno

Submitted September 13, 2013

Completeness Responses October 23, 2013

added layer of drain rock and perforated pipe. Once installed, the applicant's landscape architect will perform a review of the topsoil placement to ensure that the soil is compacted properly. An additional review will be done after trees are installed to ensure that the root balls are not damaged during handling and to confirm that the burlap and wire baskets are removed to the greatest extent possible.

- The applicant's landscape architect will perform a punch list walkthrough with the Landscape Contractor at the completion of planting operations to ensure that all trees are appropriately installed, staked, and irrigated.
- Within the first year from the date of substantial completion, the Landscape Contractor will be responsible for maintaining all new plantings. This will include but is not limited to--- selective pruning for shape, fertilization and ample seasonal irrigation. A maintenance agreement will also be contracted between the Owner and Landscape Contractor. At the completion of the one-year maintenance and warranty period, Cardno will perform a warranty walkthrough with the Landscape Contractor to ensure all trees are established. Trees that require special attention or replacement will be identified at that time and replacement trees will be installed by the Landscape Contractor and provided with a new one-year warranty from the date of replanting.
- After the first year, the applicant's qualified landscape architect shall complete the following quarterly site observations:
 - A visual inspection of the irrigation system for problems and to identify any required repairs.
 - Take soil samples and send to a testing lab. Soil will be tested in at least three (3) landscape diamonds across the site in the spring of each year.
 - Selective pruning of dead limbs or crossed branches.
 - Trees will be inspected for indications of pests or disease. If discovered, the appropriate herbicide or pesticide will be applied per the manufacturer's recommendations, in accordance with state and local codes.

(13) Landscape plans for required landscaped areas that include fences should carefully integrate any fencing into the plan to guide wild animals toward animal crossings under, over, or around transportation corridors. [Ord. 882-92 §15, 12/14/92; Ord. 890-93 §9, 4/12/93; Ord. 904-93 §53 and 54, 9/13/93; Ord. 993-94 §48, 11/28/94; Ord. 1025-99 §41, 7/26/99; Ord. 1035-99 §16, 11/8/99; Ord. 1070-01 §11, 4/9/01; Ord. 1070-01, 4/9/01; Ord. 1216-06, 7/24/06; Ord. 1224-06 §25, 11/13/06; Ord. 1321-11 §49, 4/25/11]

Response: No fences are proposed with this application.

SECTION 73.250 TREE PRESERVATION.

- (1) **Trees and other plant materials to be retained shall be identified on the landscape plan and grading plan.**

Response: Trees to be retained on-site are identified on Tree Preservation Site Plan submitted as Exhibit O – C 2.0 through C 2.2. The City has approved the removal of trees within the public utility corridor prior to this AR. Trees near and within the building footprints in the northeast corner of the site will be reviewed for removal under the Arborist Report submitted here as Exhibit M. The remaining trees while already reviewed for removal under the approved master plan will not be removed until this AR is complete.

- (2) **During the construction process:**

- (a) **The owner or the owner's agents shall provide above and below ground protection for existing trees and plant materials identified to remain.**
- (b) **Trees and plant materials identified for preservation shall be protected by chain link or other sturdy fencing placed around the tree at the drip line.**
- (c) **If it is necessary to fence within the drip line, such fencing shall be specified by a qualified arborist as defined in TDC 31.060.**
- (d) **Neither top soil storage nor construction material storage shall be located within the drip line of trees designated to be preserved.**
- (e) **Where site conditions make necessary a grading, building, paving, trenching, boring, digging, or other similar encroachment upon a preserved tree's drip-line area, such grading, paving, trenching, boring, digging, or similar encroachment shall only be permitted under the direction of a qualified arborist. Such direction must assure that the health needs of trees within the preserved area can be met.**
- (f) **Tree root ends shall not remain exposed.**

Response: The applicant's representative will provide above and below ground protection for existing trees identified to remain. These trees will feature visible protection to avoid any impact from construction-related activities. If there is proposed work within a preserved tree's drip-line area, the work will be conducted under the direction of a qualified arborist and tree root ends will not be exposed in compliance with this criterion..

- (2) **Landscaping under preserved trees shall be compatible with the retention and health of said tree.**

Response: All landscaping shown on the Landscape Plan will be installed in a manner that preserves and protects any preserved tree in compliance with this criterion.

- (4) When it is necessary for a preserved tree to be removed in accordance with TDC 34.210 the landscaped area surrounding the tree or trees shall be maintained and replanted with trees that relate to the present landscape plan, or if there is no landscape plan, then trees that are complementary with existing, nearby landscape materials. Native trees are encouraged
- (5) Pruning for retained deciduous shade trees shall be in accordance with National Arborist Association "Pruning Standards For Shade Trees," revised 1979.
- (6) Except for impervious surface areas, one hundred percent (100%) of the area preserved under any tree or group of trees retained in the landscape plan (as approved through the Architectural Review process) shall apply directly to the percentage of landscaping required for a development. [Ord. 904-93, §55, 9/13/93; Ord. 1224-06, §26, 11/13/06]

Response: The Landscape Plan and Tree Removal Plan show the trees to be retained and the trees to be removed. Where trees are removed, the area not approved for development is to be replanted in conformance with the Landscape Plan. During the construction process any trees identified for preservation will be protected with adequate fencing and root protection to ensure tree and root health.

SECTION 73.310 LANDSCAPE STANDARDS - COMMERCIAL, INDUSTRIAL, PUBLIC AND SEMI-PUBLIC USES.

- (1) A minimum 5-foot-wide landscaped area must be located along all building perimeters which are viewable by the general public from parking lots or the public right-of-way, excluding loading areas, bicycle parking areas and pedestrian egress/ingress locations. Pedestrian amenities such as landscaped plazas and arcades may be substituted for this requirement. This requirement shall not apply where the distance along a wall between two vehicle or pedestrian access openings (such as entry doors, garage doors, carports and pedestrian corridors) is less than 8 feet.
- (2) Areas exclusively for pedestrian use that are developed with pavers, bricks, etc., and contain pedestrian amenities, such as benches, tables with umbrellas, children's play areas, shade trees, canopies, etc., may be included as part of the site landscape area requirement.
- (3) All areas not occupied by buildings, parking spaces, driveways, drive aisles, pedestrian areas or undisturbed natural areas shall be landscaped. [Ord. 882-92, §16, 12/14/92; Ord. 904-93, §58, 9/13/93]

Response: As noted in the Landscape Planting Plan (Exhibit O – Sheets L1.0 through L1.10), foundation and building landscaping will be installed with landscape qualifying material to complement the architectural style and soften building appearance within the overall Site Plan. A minimum of 5-foot wide landscaped area is located along the building perimeters that are viewable by the general public from the right of way or parking areas. In large part, this standard is satisfied through the pedestrian amenities such as landscaped plazas and arcades along the northern building frontages that qualify as landscape elements

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

to meet the standard. Aside from loading areas and building entrances, 5-foot wide landscape areas are provided along all building sides. All landscaping meets or exceeds the numerical standards set forth above. Areas with predominate storefronts, multiple entryways, covered arcades, and/or outdoor seating areas provide landscaping between the drive aisle and pedestrian pathways to achieve a well vegetated urban environment.

OFF-STREET PARKING LOT LANDSCAPING

SECTION 73.320 OFF-STREET PARKING LOT LANDSCAPING STANDARDS.

SECTION 73.340 OFF-STREET PARKING LOT AND LOADING AREA LANDSCAPING - COMMERCIAL, INDUSTRIAL, PUBLIC AND SEMI-PUBLIC USES, AND RESIDENTIAL AND MIXED USE RESIDENTIAL USES WITHIN THE CENTRAL DESIGN DISTRICT.

- (1) A clear zone shall be provided for the driver at ends of on-site drive aisles and at driveway entrances, vertically between a maximum of 30 inches and a minimum of 8 feet as measured from the ground level, except for parking structures and underground parking where this provision shall not apply.
- (2) Perimeter site landscaping of at least 5 feet in width shall be provided in all off-street parking and vehicular circulation areas (including loading areas). For conditional uses in multifamily residential planning districts the landscape width shall be at least 10 feet except for uses allowed by TDC 40.030(3), 40.030(5)(j), 40.030(5)(m), 40.030(5)(n) and 41.030(2).
 - (a) The landscape area shall contain:
 - (i) Deciduous trees an average of not more than 30 feet on center. The trees shall meet the requirements of TDC 73.360(7).
 - (ii) Plantings which reach a mature height of 30 inches in three years which provide screening of vehicular headlights year round.
 - (iii) Shrubs or ground cover, planted so as to achieve 90 percent coverage within three years.
 - (iv) Native trees and shrubs are encouraged.
 - (b) Where off-street parking areas on separate lots are adjacent to one another and are connected by vehicular access, the landscaped strips required in subsection (2) of this section are not required. [Ord. 882-92, §18, 12/14/92; Ord. 904-93, § 61, 9/13/93; Ord. 920-94, §19, 4/11/94; Ord. 1224-06 §30, 11/13/06]

Response: A 5-foot wide landscape area is provided along the perimeter of all off-street parking and vehicular circulation areas. All landscape areas do contain deciduous trees at a spacing no more than 30-feet on center, with ground plantings that reach a mature height of 30-inches in three years. Shrubs or groundcover will achieve 90 percent coverage within three years. A landscape

planting plan under Exhibit O, Sheets L 1.0 through L1.10 is included with this application demonstrating compliance with this criteria.

SECTION 73.360 OFF-STREET PARKING LOT LANDSCAPE ISLANDS - COMMERCIAL, INDUSTRIAL, PUBLIC, AND SEMI-PUBLIC USES.

- (1) A minimum of 25 square feet per parking stall shall be improved with landscape island areas. They may be lower than the surrounding parking surface to allow them to receive stormwater run-off and function as water quality facilities as well as parking lot landscaping. They shall be protected from vehicles by curbs, but the curbs may have spaces to allow drainage into the islands. They shall be dispersed throughout the parking area [see TDC 73.380(3)]. They shall be planted with groundcover or shrubs that will completely cover the island area within 3 years. They shall be planted with deciduous shade trees when needed to meet the parking lot shade tree requirements. Native plant materials are encouraged. Landscape square footage requirements shall not apply to parking structures and underground parking.

Response: With 1,316 parking spaces located throughout Nyberg Rivers, a minimum of 32,900 SF of landscaping is required within landscape islands areas. The total amount of planted area landscaping provided within landscape islands is 53,404 SF, which is well above the 25 SF per stall requirement. As included with the Master plan, and as detailed above and incorporated herein by reference, several parking landscape islands have been approved as landscape diamonds, shown under [Exhibit O, included in this application.. The Landscape Planting Plan (Exhibit O – L1.0 through L1.10) shows a variety of deciduous shade trees located within those landscape islands. Sheet L1.0 outlines the Planting Legend and Notes, with specific reference to tree protection and tree planting installation requirements.

- (2) Landscaped island areas with deciduous parking lot shade trees shall be a minimum of 5 feet in width (from inside of curb to curb).

Response: As shown in Exhibit O to this application, 6-foot landscape diamonds with drain rock and perforated pipe are proposed throughout the central vehicle landscape island areas. Traditional landscape islands are also scattered throughout the site, with a width of a minimum of five feet, measured from inside of curb to curb. Under the master plan conditions of approval, and as detailed above these islands will be constructed and maintained in a manner that ensures the targeted growth and canopy.

- (3) A minimum of one deciduous shade tree shall be provided for every four (4) parking spaces to lessen the adverse impacts of glare, reduce heat from paved surfaces, and to emphasize circulation patterns. Required shade trees shall be uniformly distributed throughout the parking lot (see TDC 73.380(3)), except that within the Central Design District landscape islands and shade trees may be placed to frame views of the Tualatin Commons water feature or identified architectural focal elements. The trees shall meet the requirements of TDC 73.360(7). Parking lot shade tree requirements shall not apply to parking structures and underground parking.

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

Response: With 1,316 parking spaces, there are a total of 329 deciduous trees required within the parking lot landscape islands. There are a total of 547 deciduous trees provided throughout the parking lot area. As shown on the Landscape Planting Plan, the parking lot trees are all deciduous trees and are uniformly distributed throughout the parking areas..

- (4) Landscape islands shall be utilized at aisle ends to protect parked vehicles from moving vehicles and emphasize vehicular circulation patterns. Landscape island location requirements shall not apply to parking structures and under-ground parking.

Response: As shown on the Site Plan and Landscape Planting Plan, landscape islands are provided at parking area aisle ends. The minimum dimension of these islands is five feet, as dimensioned on the Site Plan.

- (5) Required plant material in landscape islands shall achieve 90 percent coverage within three years. Native shrubs and trees are encouraged.

Response: The applicant is aware of this provision and will note on the Landscape Planting Plan the requirement to achieve 90 percent coverage within three years. The plants will be installed in a manner that facilitates reaching 90% coverage in 3 years,

(6)

- (a) Except as in (b) below, site access from the public street shall be defined with a landscape area not less than 5 feet in width on each side and extend 25 feet back from the property line for commercial, public, and semi-public development with 12 or more parking spaces and extend 30 feet back from the property line for industrial development, except for parking structures and under-ground parking which shall be determined through the Architectural Review process.

- (b) In the Central Design District where driveway access is on local streets, not collectors or arterials, and the building(s) on the property is(are) less than 5,000 square feet in gross floor area, or parking is the only use on the property, site access from the public street shall be defined with a landscape area not less than 5 feet in width on each side and extend 5 feet back from the property line, except for parking structures and underground parking which shall be determined through the Architectural Review process.

Response: As shown on the Site Plan attached as Exhibit O, Sheets C1.0 through C1.2 and the Cross Section A-A attached as Exhibit A for the site entry at Nyberg Street, the central entry includes tree lined planters on both sides of the travel lanes and a landscaped median. The west side of the street features a 14-foot shared path with tree wells and a 4-foot planter. The east side of the street features a planter that ranges from 4-feet to 7-feet. These landscape areas continue into the site before terminating in front of the central pedestrian plaza.

Cross-Section D-D, included under Exhibit A with this application, shows the general configuration for Street 'A', which includes 4-foot landscape planters on both the east and west sides of the street, with a 12-foot multi-use path on the west side and a 5-foot sidewalk on the east side of the property. A 2-foot minimum landscape planter is located back of the pathways to provide additional buffering for pedestrians.

Based on the street configuration shown for SW Seneca Street on the Site Plan included under Exhibit O and Sheet C1.0, a 5 to 6-foot landscape planter is provided between the sidewalk and traffic and bicycle lanes.

(7) **Deciduous shade trees shall meet the following criteria:**

- (a) **Reach a mature height of 30 feet or more;**
- (b) **Cast moderate to dense shade in summer;**
- (c) **Long lived, i.e., over 60 years;**
- (d) **Do well in an urban environment:**
 - (i) **Pollution tolerant.**
 - (ii) **Tolerant of direct and reflected heat.**
- (e) **Require little maintenance:**
 - (i) **Mechanically strong.**
 - (ii) **Insect- and disease-resistant.**
 - (iii) **Require little pruning.**
- (f) **Be resistant to drought conditions;**
- (g) **Be barren of fruit production. [Ord. 882-92, §20, 12/14/92; Ord. 904-93, §64, 9/13/93; Ord. 920-94, §20, 4/11/94; Ord. 945-95, §1, 5/8/95; Ord. 1224-06 §32, 11/13/06]**

Response: The proposed deciduous shade trees shown on the Landscape Planting Plan have been selected to achieve the minimum criteria outlined above. The deciduous trees include: oaks, maples, honey locust and ash, which have been selected due to their ability to cast a moderate to dense shade in the summer, live over 60 years, do well in an urban setting, require little maintenance, be resistant to drought conditions, and yield no fruit.

SECTION 73.370 OFF-STREET PARKING AND LOADING.

(1) General Provisions.

- (a) At the time of establishment of a new structure or use, or change in use, or change in use of an existing structure, within any planning district of the City, off-street parking spaces, off-street vanpool and carpool parking spaces for commercial, institutional and industrial uses, off-street bicycle parking, and off-street loading berths shall be as provided in this and following sections, unless greater requirements are otherwise established by the conditional use permit or the Architectural Review process, based upon clear findings that a greater number of spaces are necessary at that location for protection of public health, safety and welfare or that a lesser number of vehicle parking spaces will be sufficient to carry out the objectives of this section. In the Central Design District, the Design Guidelines of TDC 73.610 shall be considered. In case of conflicts between guidelines or objectives in TDC Chapter 73, the proposal shall provide a balance.

Response: As this project represents both a change in use and the establishment of new structures, the general provisions outlined in this section do apply.

- (b) At the time of enlargement of an existing multi-family residential, commercial, institutional or industrial structure or use, TDC 73.370 shall apply to the existing and enlarged structure or use.

Response: As this project represents both a change in use and the establishment of new structures, the general provisions outlined in this section do apply.

- (c) Except where otherwise specified, the floor area measured shall be the gross floor area of the building primary to the function of the particular use of the property other than space devoted to off-street parking or loading.

Response: All floor area measurements do use the gross floor area of the building, which is used to determine parking requirements by use, as well as transportation trip generation rates.

- (d) Where employees are specified, the term shall apply to all persons, including proprietors, working on the premises during the peak shift.

Response: Specific employees by tenant are not identified with this ARB application.

- (e) Calculations to determine the number of required parking spaces and loading berths shall be rounded to the nearest whole number.

Response: All calculations are rounded to the nearest whole number.

- (f) If the use of a property changes, thereby increasing off-street parking or loading requirements, the increased parking/loading area shall be provided prior to commencement of the new use.

Response: The applicant is aware of this provision. All parking/loading area requirements are calculated based on the proposed new uses.

- (g) Parking and loading requirements for structures not specifically listed herein shall be determined by the Community Development Director, based upon requirements of comparable uses listed.

Response: All proposed structures generally fall within a defined land use designation category as defined by the Tualatin Development Code.

- (h) When several uses occupy a single structure, the total requirements for off-street parking may be the sum of the requirements of the several uses computed separately or be computed in accordance with TDC 73.370(1)(m), Joint Use Parking.

Response: The total requirements for off-street parking do include the sum of all uses within Nyberg Rivers. These uses were calculated both on a separate and combined shopping center use designation. Off-street parking spaces provided exceed both the individual uses and combined shopping center parking requirements.

- (i) Off-street parking spaces for dwellings shall be located on the same lot with the dwelling. Other required parking spaces may be located on a separate parcel, provided the parcel is not greater than five hundred (500) feet from the entrance to the building to be served, measured along the shortest pedestrian route to the building. The applicant must prove that the parking located on another parcel is functionally located and that there is safe vehicular and pedestrian access to and from the site. The parcel upon which parking facilities are located shall be in the same ownership as the structure.

Response: All off-street parking spaces are located on-site, within the Nyberg Rivers complex.

- (j) Required parking spaces shall be available for the parking of operable passenger automobiles of residents, customers, patrons and employees and shall not be used for storage of vehicles or materials or for the parking of trucks used in conducting the business.

Response: The applicant is aware of this provision. All parking spaces proposed on-site will be available for the customers, patrons, and employees at Nyberg Rivers.

- (k) Institution of on-street parking, where none is previously provided, shall not be done solely for the purpose of relieving crowded parking lots in commercial or industrial planning districts.

Response: There is no on-street parking proposed with this project.

- (l) Parking facilities may be shared by users on adjacent parcels if the following standards are met:
 - (i) One of the parcels has excess parking spaces, considering the present use of the property; the other parcel lacks sufficient area for required parking spaces.
 - (ii) The total number of parking spaces meets the standards for the sum of the number of spaces which would be separately required for each use.
 - (iii) Legal documentation, to the satisfaction of the City Attorney, shall be submitted verifying permanent use of the excess parking area on one lot by patrons of the uses deficient in required parking area.
 - (iv) Physical access between adjoining lots shall be such that functional and reasonable access is actually provided to uses on the parcel deficient in parking spaces.
 - (v) Adequate directional signs shall be installed specifying the joint parking arrangement.
 - (vi) Areas in the Natural Resource Protection Overlay District, Other Natural Areas identified in Figure 3-4 of the Parks and Recreation Master Plan, or a Clean Water Services Vegetated Corridor would be better protected.

Response: All parcels associated with Nyberg Rivers within the proposed development area will allow for general off-street parking for customers, patrons, and employees to the site.

- (m) **Joint Use Parking.** Joint use of parking spaces may occur where two or more separate developments or multiple uses in a development are able to jointly use some or all of the same required parking spaces because their parking demands occur at different times. Joint use of parking spaces may be allowed if the following standards are met:
 - (i) There shall be no substantial conflict in the principal operating hours of the buildings or uses for which the joint use parking is proposed. Future change of use, such as expansion of a building or establishment of hours of operation which conflict with or affect a joint use parking agreement are prohibited, unless approval is obtained through the Architectural Review process;

- (ii) The joint use parking spaces shall be located no more than 500 feet from a building or use to be served by the joint use parking;
- (iii) The number and location of parking spaces, hours of use and changes in operating hours of uses subject to joint use shall be approved through the Architectural Review process;
- (iv) Legal documentation, to the satisfaction of the City Attorney, shall be submitted verifying the joint use parking between the separate developments. Joint use parking agreements may include provisions covering maintenance, liability, hours of use and cross easements; and
- (v) The City Attorney approved legal documentation shall be recorded by the applicant at the Washington or Clackamas County Recorder's Office and a copy of the recorded document submitted to the Planning Department prior to issuance of a building permit.
- (vi) Areas in the Natural Resource Protection Overlay District, Other Natural Areas identified in Figure 3-4 of the Parks and Recreation Master Plan, or a Clean Water Services Vegetated Corridor would be better protected.

Response: All parcels associated with Nyberg Rivers within the proposed development area will allow for general off-street parking for customers, patrons, and employees to the site.

- (n) Bicycle parking facilities shall either be lockable enclosures in which the bicycle is stored, or secure stationary racks which accommodate a bicyclist's lock securing the frame and both wheels.

Response: As shown on the Bicycle Parking and Trash Enclosure Plan included under Exhibit O, the proposed bicycle parking options will include a ground mounted bike rack (Type A), a trash enclosure with hanging bicycle racks (Type B), and a standalone bike enclosure (Type C). There are a total of (91) Type A, (36) Type B and (24) Type C bicycle parking options for a total of 151 bicycle parking spaces. Each of these options will allow for bicycle storage that will accommodate a bicyclist's lock.

- (o) Each bicycle parking space shall be at least 6 feet long and 2 feet wide, and overhead clearance in covered areas shall be at least 7 feet, unless a lower height is approved through the Architectural Review process.

Response: An elevation of the Type A, B and C bicycle parking options are shown on the Bicycle Parking and Trash Enclosure Plan within Exhibit O. The Type B design features a 10-foot overhead clearance, with vertical spacing at least 2-feet wide. The Type C enclosure allows for 8-feet of overhead clearance, with 14-foot spacing to accommodate 8 bikes.

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

- (p) A 5-foot-wide bicycle maneuvering area shall be provided beside or between each row of bicycle parking. It shall be constructed of concrete, asphalt or a pervious surface such as pavers or grasscrete, but not gravel or woody material, and be maintained.

Response: All proposed bicycle parking areas will provide a 5-foot wide bicycle maneuvering area between each row of bicycle parking. This area will be constructed of concrete or concrete pavers.

- (q) Access to bicycle parking shall be provided by an area at least 3 feet in width. It shall be constructed of concrete, asphalt or a pervious surface such as pavers or grasscrete, but not gravel or woody material, and be maintained.

Response: Access to the bicycle parking areas will be provided by an area at least 3-feet in width, constructed of concrete or concrete pavers.

- (r) Required bicycle parking shall be located in convenient, secure, and well-lighted locations approved through the Architectural Review process. Lighting, which may be provided, shall be deflected to not shine or create glare into street rights-of-way or fish and wildlife habitat areas.

Response: The proposed bicycle parking locations are shown on the Bicycle Parking and Trash Enclosure Plan included under Exhibit O in this application. These areas are spaced across the site to allow for ample bicycle parking options for the multiple tenant spaces, with both covered and uncovered options. These areas will be well lit, with minimal candling onto adjacent properties.

- (s) Bicycle parking facilities may be provided inside a building in suitable secure and accessible locations.

Response: All proposed bicycle parking is located outside any building. Specific tenants may desire to locate bicycle parking inside their space, although no interior parking is proposed at this time.

(t)

- (u) Bicycle parking areas and facilities shall be identified with appropriate signing as specified in the Manual on Uniform Traffic Control Devices (MUTCD) (latest edition). At a minimum, bicycle parking signs shall be

located at the main entrance and at the location of the bicycle parking facilities.

Response: Bicycle parking areas and facilities will be identified with the appropriate signing as specified by the above-noted manual. Bicycle parking signs will be located at the main entrance and at the specific location of the bike parking facilities.

- (v) Required bicycle parking spaces shall be provided at no cost to the bicyclist, or with only a nominal charge for key deposits, etc. This shall not preclude the operation of private for-profit bicycle parking businesses.

Response: There will be no charge for required bicycle parking spaces.

- (w) Parking on existing residential, commercial and industrial development may be redeveloped as a transit facility as a way to encourage the development of transit supportive facilities such as bus stops and pullouts, bus shelters and park and ride stations. Parking spaces converted to such uses in conjunction with the transit agency and approved through the Architectural Review process will not be required to be replaced.




Response: There are no transit facilities proposed with this redevelopment project. There is an existing Tri-Met bus stop located along Martinazzi Boulevard, just west of the site. Access to the bus stop is provided via the Seneca Street extension or Street 'A'.

- (x) Required vanpool and carpool parking shall meet the 9-foot parking stall standards in Figure 73-1 and be identified with appropriate signage.

Response: There is no proposed vanpool or carpool parking.

Bicycle Parking Diagram



| LEGEND | TYPE OF BIKE RACK |
|---|--|
|  | BIKE RACK A - FITS 7 BIKES PER MODULE |
|  | TRASH ENCLOSURE B WITH HANGING BIKES - FITS 12 BIKES |
|  | BIKE ENCLOSURE C - FITS 24 BIKES |

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

| | REQUIRED | PROVIDED | RACK TYPE/DTY |
|---------------------------|----------------------------|------------|---------------------------------------|
| OVERALL BICYCLE PARKING | 147 SPACES | 151 SPACES | (84) TYPE A, (36) TYPE B, (24) TYPE C |
| COVERED BICYCLE PARKING | 74 SPACES (50% OF OVERALL) | 74 SPACES | (44) TYPE A, (36) TYPE B, (24) TYPE C |
| UNCOVERED BICYCLE PARKING | NO SPECIFIC REQUIREMENTS | 77 SPACES | (77) TYPE A |

BIKE PARKING REQUIRED : 0.50 space per 1000 sq. ft. of gross floor area 50 % COVERED

293,919 SF / 1000 * 0.50 = 146.95 OR 147 REQ'D (147 * 0.5 = 74 REQ'D COVERED)

(2) Off-Street Parking Provisions.

- (a) The following are the minimum and maximum requirements for off-street motor vehicle parking in the City, except for minimum parking requirements for the uses in TDC 73.370(2)(a) (Residential Uses: iii, iv, v, vi, vii; Places of Public Assembly: I, ii, iv; Commercial Amusements: I, ii; and Commercial: I, ii, xi, xii, xiv) within the Core Area Parking District (CAPD). Minimum standards for off-street motor vehicle parking for the uses in 73.370(2) (a) Residential Uses: iii, iv, v, vi, vii; Places of Public Assembly: I, ii, iv; Commercial Amusements: I, ii; and Commercial: I, ii, xi, xii, xiv in the CAPD are in TDC 73.370(2)(b). The maximum requirements are divided into Zone A and Zone B, as shown on the Tualatin Parking Zone Map, Figure 73-3. The following are exempt from calculation of maximum parking requirements: parking structures; fleet parking; parking for vehicles for sale, lease or rent; car/vanpool parking; dedicated valet parking; and user-paid parking.

| USE | MINIMUM MOTOR VEHICLE PARKING REQUIREMENT | MAXIMUM MOTOR VEHICLE PARKING REQUIREMENT | BICYCLE PARKING REQUIREMENT | PERCENTAGE OF BICYCLE PARKING TO BE COVERED |
|--|--|--|--|---|
| (iii) Shopping center (over 100,000 sq. ft. of gross floor area) | 4.1 spaces per 1,000 sq. ft. of gross floor area | Zone A: 5.1 spaces per 1,000 sq. ft. gross floor area Zone B: 6.2 spaces per 1,000 sq. ft. gross floor area | 0.50 space per 1,000 sq. ft. of gross floor area | 50 |

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

Response: The Nyberg Rivers commercial area is classified as a shopping center with greater than 100,000 SF of gross floor area. Therefore, the parking requirement of 4.1 spaces per 1,000 SF of gross floor area is applied. With a maximum permissible building area of 307,000 SF, the minimum number of spaces required is 1,259, while the total parking stalls provided is 1,316 stalls. The City has also asked that we assess each tenant space based on the specific use for each space. Using this calculation as shown in the table below, there is 1 less stall required versus the general shopping center use designation. Therefore, the minimum parking stall requirement is met.

As shown in the second table provided below, For 147 bicycle parking 147 spaces are required on-site based on the overall shopping center designation. A breakout of specific uses would require a total of 253 parking spaces, with 112 of those stalls requiring a cover. The location of the bicycle parking stalls is shown on the Bicycle Parking Diagram above, as well as the Bicycle Parking and Trash Enclosure Plan included under Exhibit O.

Formatted: Indent: First line: 0"

VEHICLE PARKING REQUIREMENTS

Formatted: Font: 11 pt, Font color: Text 1

Formatted: Caption, Centered, Keep with next

| BUILDING | SF | USE | MINIMUM PARKING RATIO | MINIMUM PARKING | MAXIMUM PARKING RATIO | MAXIMUM PARKING |
|----------|---------|------------------------|-----------------------|-----------------|-----------------------|-----------------|
| 1005 | 33,562 | Retail Shop | 4/1000 | 134 | 5.1/1000 | 171 |
| 1010 | 21,750 | Retail Shop | 4/1000 | 87 | 5.1/1000 | 111 |
| 1030 | 2,900 | Restaurant | 10/1000 | 29 | 19.1/1000 | 55 |
| 1040 | 110,093 | Shopping Center | 4.1/1000 | 451 | 5.1/1000 | 561 |
| A | 12,500 | Retail Shop | 4/1000 | 50 | 5.1/1000 | 64 |
| B | 5,850 | Retail Shop | 4/1000 | 23 | 5.1/1000 | 30 |
| C | 3,950 | Bank | 4.3/1000 | 17 | 5.4/1000 | 21 |
| D | 32,459 | Retail Shop | 4/1000 | 130 | 5.1/1000 | 166 |
| E | 3,172 | Bank Drive Up | 4.3/1000 | 14 | 5.4/1000 | 17 |
| F | 5,500 | Restaurant | 9.9/1000 | 54 | 12.4/1000 | 68 |
| G-100 | 6,500 | Restaurant Drive Up | 10/1000 | 65 | 19.1/1000 | 124 |
| H-100 | 4,526 | Restaurant | 9.9/1000 | 45 | 12.4/1000 | 56 |
| J-100 | 5,797 | Restaurant | 10/1000 | 58 | 19.1/1000 | 111 |
| N-100 | 45,000 | Health Club | 1/1000 | 45 | 1.3/1000 | 59 |
| | 293,559 | | TOTAL | 1,203 | | 1,614 |

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

Total
 Area 293,559 Shopping Center 4.1/1000 1,204 5.1/1000 1,497
 As Shopping Center

BICYCLE PARKING REQUIREMENTS

| <u>BUILDING</u> | <u>SF</u> | <u>USE</u> | <u>BICYCLE PARKING RATIO</u> | <u>MINIMUM BICYCLE PARKING</u> | <u>COVERED BIKE PARKING</u> |
|-------------------|----------------|------------------------|--------------------------------------|--------------------------------|-----------------------------|
| <u>1005</u> | <u>33,562</u> | <u>Retail Shop</u> | <u>0.5/1,000 SF</u> | <u>17</u> | <u>8.39</u> |
| <u>1010</u> | <u>21,750</u> | <u>Retail Shop</u> | <u>0.5/1,000 SF</u> | <u>11</u> | <u>5.44</u> |
| <u>1030</u> | <u>2,900</u> | <u>Restaurant</u> | <u>2/1,000 SF</u> | <u>6</u> | <u>1.45</u> |
| | | | <u>0.5/1,000 SF Gross Floor Area</u> | | |
| <u>1040</u> | <u>110,093</u> | <u>Shopping Center</u> | | <u>55</u> | <u>27.52</u> |
| <u>A</u> | <u>12,500</u> | <u>Retail Shop</u> | <u>0.5/1,000 SF</u> | <u>6</u> | <u>3.13</u> |
| <u>B</u> | <u>5,850</u> | <u>Retail Shop</u> | <u>0.5/1,000 SF</u> | <u>3</u> | <u>1.46</u> |
| | | | <u>2 or 0.33/1,000 SF</u> | | |
| <u>C</u> | <u>3,950</u> | <u>Bank</u> | <u>Whichever is greater</u> | <u>2</u> | <u>0.20</u> |
| <u>D</u> | <u>32,459</u> | <u>Retail Shop</u> | <u>0.5/1,000 SF</u> | <u>16</u> | <u>8.11</u> |
| | | | <u>2 or 0.33/1,000 SF</u> | | |
| <u>E</u> | <u>3,172</u> | <u>Bank</u> | <u>Whichever is greater</u> | <u>2</u> | <u>0.20</u> |
| | | <u>Drive Up</u> | | | |
| <u>F</u> | <u>5,500</u> | <u>Restaurant</u> | <u>2/1,000 SF</u> | <u>11</u> | <u>2.75</u> |
| <u>G-100</u> | <u>6,500</u> | <u>Restaurant</u> | <u>2/1,000 SF</u> | <u>13</u> | <u>3.25</u> |
| | | <u>Drive Up</u> | | | |
| <u>H-100</u> | <u>4,526</u> | <u>Restaurant</u> | <u>2/1,000 SF</u> | <u>9</u> | <u>2.26</u> |
| <u>J-100</u> | <u>5,797</u> | <u>Restaurant</u> | <u>2/1,000 SF</u> | <u>12</u> | <u>2.90</u> |
| <u>N-100</u> | <u>45,000</u> | <u>Health Club</u> | <u>2/1,000 SF Exercise Area</u> | <u>90</u> | <u>45.00</u> |
| | <u>293,559</u> | | | <u>253</u> | <u>112</u> |
| <u>Total Area</u> | <u>293,559</u> | <u>Shopping Center</u> | | <u>147</u> | <u>73.39</u> |

Formatted Table

SECTION 73.380 OFF-STREET PARKING LOTS.

A parking lot, whether an accessory or principal use, intended for the parking of automobiles or trucks, shall comply with the following:

- (1) Off-street parking lot design shall comply with the dimensional standards set forth in Figure 73-1 of this section, except for parking structures and underground parking where stall length and width requirements for a standard size stall shall

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

be reduced by .5 feet and vehicular access at the entrance if gated shall be a minimum of 18 feet in width.

Response: Figure 73-1 requires standard 90-degree parking stall dimensions of 9-feet wide by 18.5-feet deep, with a 24-foot aisle width between stall lines. Subcompact parking requires a stall width of 7.7-feet, stall depth of 15-feet, with a 20-foot aisle width. As shown on the Site Plan, Sheets C1.0 through C1.2, the proposed standard parking stall dimensions are 9-feet by 19-feet, with compact stalls measuring 7.7-feet by 16-feet. All drive aisles widths on-site are 24-feet or greater. These dimensions exceed the standard parking requirements.

- (2) **Parking stalls for sub-compact vehicles shall not exceed 35 percent of the total parking stalls required by TDC 73.370(2). Stalls in excess of the number required by TDC 73.370(2) can be sub-compact stalls.**

Response: There are 1,316 total parking stalls located within the Nyberg Rivers site. 228, or approximately 17%, of those stalls are sub-compact parking stalls as shown on the attached Site Plan (Exhibit O – Sheets C1.0 through C1.2). Of these 22 of the total stalls are Handicap Accessible. The applicant provides sub-compact spaces throughout the site, but well below the 35-percent threshold

- (3) **Off-street parking stalls shall not exceed eight continuous spaces in a row without a landscape separation, except for parking structures and underground parking. For parking lots within the Central Design District that are designed to frame views of the central water feature or identified architectural focal elements as provided in TDC 73.350(3), this requirement shall not apply and the location of parking lot landscape islands shall be determined through the Architectural Review process.**

Response: The Site Plans and Landscape Planting Plans included under Exhibit O demonstrate that off-street parking stalls do not exceed eight continuous spaces without a landscape island or diamond separation.

- (4) **Parking lot drive aisles shall be constructed of asphalt or concrete, including pervious concrete. Parking stalls shall be constructed of asphalt or concrete, or a pervious surface such as pavers or grasscrete, but not gravel or woody material. Drive aisles and parking stalls shall be maintained adequately for all-weather use and drained to avoid water flow across sidewalks. Pervious surfaces such as pervious concrete, pavers and grasscrete, but not gravel or woody material, are encouraged for parking stalls in or abutting the Natural Resource Protection Overlay District, Other Natural Areas identified in Figure 3-4 of the Parks and Recreation Master Plan, or in a Clean Water Services Vegetated Corridor.**

Response: Parking lot drive aisles will be constructed of asphalt, while parking stalls will also be constructed of asphalt. The maintenance of these areas will be conducted by the Nyberg Rivers maintenance staff.

- (5) **Artificial lighting, which may be provided, shall be deflected to not shine or create glare in a residential planning district, an adjacent dwelling, street right-of-way in such a manner as to impair the use of such way or a Natural Resource Protection**

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

Overlay District, Other Natural Areas identified in Figure 3-4 of the Parks and Recreation Master Plan, or a Clean Water Services Vegetated Corridor.

Response: Artificial lighting will be deflected to avoid shining or creating glare into any residential planning district, street right-of-way or adjacent dwelling. A site Photometric Plan is provided with this ARB submittal package to address these requirements is included within Exhibit O. The lighting is deflected to reduce light trespass at the property lines. The northwest corner of the site that is adjacent to existing residential development does not exceed .1 foot candles at the property line.

- (8) **Service drives to off-street parking areas shall be designed and constructed to facilitate the flow of traffic, provide maximum safety of traffic access and egress, and maximum safety of pedestrians and vehicular traffic on the site.**

Response: As noted above and shown on the Site Plans, Sheets C1.0 through C1.2, all drive aisles are 24-feet or greater. These drive aisles provide both north-south and east-west circulation that connects with the central vehicle entry off Nyberg Street, with secondary access from Street 'A' and Seneca Street. Service drive aisles will be designed and constructed to facilitate the flow of traffic, provide maximum safety of traffic access and egress, while promoting the maximum safety of pedestrians and vehicular traffic on the site.

- (9) **Parking bumpers or wheel stops or curbing shall be provided to prevent cars from encroaching on the street right-of-way, adjacent landscaped areas, or adjacent pedestrian walkways.**

Response: Curbing will be provided to prevent cars from encroaching on to the street right-of-way, adjacent landscaped areas and adjacent pedestrian walkways. [All proposed curbing is shown on the Site Plans under Exhibit O, Sheet C1.0 through 1.2, with a specific "Proposed Curb Line" line type shown in the Site Plan legend.

- (10) **Disability parking spaces and accessibility shall be provided in accordance with applicable federal and state requirements.**

Response: As shown on the Site Plans, Exhibit O—Sheets C1.0 through C1.2, a total of 22 ADA compliant parking spaces are provided nearest the building entrances in those parking areas closest to the primary entrances of the tenant spaces. These stalls are provided in accordance with federal and state requirements.

- (11) **On-site drive aisles without parking spaces, which provide access to parking areas with regular spaces or with a mix of regular and sub-compact spaces, shall have a minimum width of 22 feet for two-way traffic and 12 feet for one-way traffic. On-site drive aisles without parking spaces, which provide access to parking areas with only sub-compact spaces, shall have a minimum width of 20 feet for two-way traffic and 12 feet for one-way traffic. [Ord. 882-92, §22, 12/14/92; Ord. 904-93, §68, 69 and 70, 9/13/93; Ord. 920-94, §22, 4/11/94; Ord. 956-96, §38, 1/8/96; Ord. 1224-06 §34, 11/13/06]**

Response: As shown on the Site Plans, Exhibit O—Sheets C1.0 through C1.2, all proposed on-site drive aisles are dimensioned to be 24-feet or greater, surpassing the minimum width requirement of 22-feet.

SECTION 73.390 OFF-STREET LOADING FACILITIES.

- (1) The minimum number of off-street loading berths for commercial, industrial, public and semi-public uses is as follows:

| Square Feet of Floor Area | Number of Berths |
|---------------------------|------------------|
| Less than 5,000 | 0 |
| 5,000 - 25,000 | 1 |
| 25,000 - 60,000 | 2 |
| 60,000 and over | 3 |

- (2) Loading berths shall conform to the following minimum size specifications.
- (a) Commercial, public and semi-public uses of 5,000 to 25,000 square feet shall be 12' x 25' and uses greater than 25,000 shall be 12' x 35'
 - (b) Industrial uses - 12' x 60'
 - (c) Berths shall have an unobstructed height of 14'
 - (d) Loading berths shall not use the public right-of-way as part of the required off-street loading area.
- (3) Required loading areas shall be screened from public view from public streets and adjacent properties by means of sight-obscuring landscaping, walls or other means, as approved through the Architectural Review process.
- (4) Required loading facilities shall be installed prior to final building inspection and shall be permanently maintained as a condition of use.
- (6) The off-street loading facilities shall in all cases be on the same lot or parcel as the structure they are intended to serve. In no case shall the required off-street loading spaces be part of the area used to satisfy the off-street parking requirements.
- (7) Subject to Architectural Review approval, the Community Development Director may allow the standards in this Section to be relaxed within the Central Design District, where a dense mix of uses is desirable in close proximity, pedestrian circulation is strongly emphasized, and the orientation of structures around a central water feature virtually eliminates the possibility of reserving any side of a

building solely for truck access. Adjustments may include, but are not limited to, reduction in the number of loading berths required, adjustment of loading berth size specifications and right-of-way restrictions, shared loading berths and maneuvering areas for use by more than one building, alteration or elimination of screening requirements, and requirements for maintenance of berths in a clean and visually appealing condition. [Ord. 882-92, §23, 12/14/92; Ord. 956-96, §39, 1/8/96]

Response: As shown on the Site Plans, Exhibit O—Sheets C1.0 through C1.2, off-street loading facilities are located behind the central buildings, thereby screening these areas from public view. These on-site loading areas provide semi-truck access into and through the site, with truck turning radii to allow semi-trucks up to 62-feet in length. There are more than three (3) loading areas shown on the Site Plan surpassing the 3 space minimum required by code. All berths meet the 14-foot height requirement and are 68 feet long by 17.5 feet wide. Buildings 1005, 1030 and 1040 each have one loading space provided that is detailed on the attached site plan included as part of Exhibit O.

SECTION 73.400 ACCESS.

- (1) The provision and maintenance of vehicular and pedestrian ingress and egress from private property to the public streets as stipulated in this Code are continuing requirements for the use of any structure or parcel of real property in the City of Tualatin. No building or other permit shall be issued until scale plans are presented that show how the ingress and egress requirement is to be fulfilled. If the owner or occupant of a lot or building changes the use to which the lot or building is put, thereby increasing ingress and egress requirements, it shall be unlawful and a violation of this code to begin or maintain such altered use until the required increase in ingress and egress is provided.

Response: As part of the Master Plan approval, the City Council approved the location of all access points to the project. As shown on the Site Plans (Exhibit O, Sheets C1.0 through C1.2), the access points proposed as part of this application conform to the approved Master Plan. Ingress and egress are provided at Nyberg Street, Street 'A' and Seneca Street. Scaled dimensions of these accessways are provided on the Site Plan included with this ARB package, with the Master Plan approved cross-sections included under Exhibit A for supporting evidence.

- (2) Owners of two or more uses, structures, or parcels of land may agree to utilize jointly the same ingress and egress when the combined ingress and egress of both uses, structures, or parcels of land satisfies their combined requirements as designated in this code; provided that satisfactory legal evidence is presented to the City Attorney in the form of deeds, easements, leases or contracts to establish joint use. Copies of said deeds, easements, leases or contracts shall be placed on permanent file with the City Recorder.

Response: An access easement will be established to allow for joint ingress and egress to serve both the properties owned by the Nyberg family, as well as the MacBale properties. A 15-foot access easement is shown from the main entrance off Nyberg Street to connect to the ODOT maintenance easement and the (6) tax

lots that currently use the existing access road. The 15-foot access easement will be located within the proposed 62.50' access easement at the primary entry before tying into the 30-foot ODOT access easement along the east-west drive aisle just north of Building E. This 30-foot easement continues to the east before heading in a northeasterly direction. At this point the proposed 15-foot access easement swings southeast to connect to the 10-foot maintenance easement. See Sheets C1.0 and C1.1 under Exhibit O for reference.

(3) Joint and Cross Access.

- (a) Adjacent commercial uses may be required to provide cross access drive and pedestrian access to allow circulation between sites.**
- (b) A system of joint use driveways and cross access easements may be required and may incorporate the following:**
 - (i) a continuous service drive or cross access corridor extending the entire length of each block served to provide for driveway separation consistent with the access management classification system and standards.**
 - (ii) a design speed of 10 mph and a maximum width of 24 feet to accommodate two-way travel aisles designated to accommodate automobiles, service vehicles, and loading vehicles;**
 - (iii) stub-outs and other design features to make it visually obvious that the abutting properties may be tied in to provide cross access via a service drive;**
 - (iv) a unified access and circulation system plan for coordinated or shared parking areas.**
- (c) Pursuant to this section, property owners may be required to:**
 - (i) Record an easement with the deed allowing cross access to and from other properties served by the joint use driveways and cross access or service drive;**
 - (ii) Record an agreement with the deed that remaining access rights along the roadway will be dedicated to the city and pre-existing driveways will be closed and eliminated after construction of the joint-use driveway;**
 - (iii) Record a joint maintenance agreement with the deed defining maintenance responsibilities of property owners;**
 - (iv) If (i-iii) above involve access to the state highway system or county road system, ODOT or the county shall be contacted and shall approve changes to (i-iii) above prior to any changes.**

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

Response: All commercial uses and properties on-site will be utilizing the network of drive aisles, accessways, and driveways into and through the site. The entire site will operate as a single shopping center, with each tenant having the right to utilize the entire shopping center, all drives, aisles, parking and accessways. Per coordination with ODOT, a 10-foot wide maintenance access easement along the new Nyberg Street right-of-way is shown on the Site Plan, Sheet C1.1 under Exhibit O. Also, a 15-foot access easement is shown from the main entrance off Nyberg Street to connect to the ODOT maintenance easement and the (6) tax lots that currently use the existing access road.

(4) Requirements for Development on Less than the Entire Site.

- (a) To promote unified access and circulation systems, lots and parcels under the same ownership or consolidated for the purposes of development and comprised of more than one building site shall be reviewed as one unit in relation to the access standards. The number of access points permitted shall be the minimum number necessary to provide reasonable access to these properties, not the maximum available for that frontage. All necessary easements, agreements, and stipulations shall be met. This shall also apply to phased development plans. The owner and all lessees within the affected area shall comply with the access requirements.
- (b) All access must be internalized using the shared circulation system of the principal commercial development or retail center. Driveways should be designed to avoid queuing across surrounding parking and driving aisles.

Response: The entire site is being developed as a cohesive shopping center, and no property is being omitted from the development. Pursuant to the master plan approval, the City Council approved all access points for the property. Those access points are shown on the Site Plan Sheets C1.0 through C1.2 under Exhibit O and are consistent with the approved Master Plan. There are five proposed access points into the site, with the primary access via Nyberg Street and secondary access points from Boones Ferry Road via Street 'A' and SW Seneca Street. Existing access points west of the primary entrance along Nyberg Street and just north on Martinazzi Avenue will be maintained with this redevelopment.

(5) Lots that front on more than one street may be required to locate motor vehicle accesses on the street with the lower functional classification as determined by the City Engineer.

Response: The City Council comprehensively reviewed the site access for the redeveloped project under the master plan proceedings. The Site Plan, attached as Exhibit O, Sheets C1.0- C1.2, is in compliance with the access plan approved by the City Council in the master plan decision. Specifically, the City adopted the location and design of the Loop Road as shown on the Site Plan. The master plan findings relative to the Loop Road are excerpted here and incorporated by reference:

"The City Council finds that the applicant is providing a Loop Road in the location permitted by the TSP and has designed that road consistent with the terms of the Urban Renewal Plan. The City's TSP shows a "future minor collector" on the project site. The future minor collector is shown as a dashed green line that connects Boones Ferry with Seneca Street and SW Nyberg Street. No specific alignment is proposed in the TSP. Rather, Figure 1 expressly states: "Future roadway alignments are approximate and subject to additional engineering and design." The TSP further provides that the function of this minor collector is to "connect two major arterials, SW Boones Ferry Road and SW Nyberg Street." The TSP shows the additional task of connecting Seneca Street to Boones Ferry and SW Nyberg through the site. This location is in the same conceptual location shown in the 2013 TSP. ...The Loop Road is not in the parking lot drive aisles. Instead the Loop Road commences at Boones Ferry Road continues through the site connecting with the improved Seneca Street and continues with a through connection to SW Nyberg Street. This location is consistent with the TSP and fully meets the desired objective of the Loop Road which is to connect Seneca Street, Boones Ferry and SW Nyberg Street.

The Urban Renewal Plan also specifically addresses the design of the Loop Road under the section entitled, Public Improvements at page 19. There the Plan defines the Loop Road as a minor collector. It then states: "This entire street will be a special section, but will generally follow Street Section Cb and be modified as specific areas warrant."

Street cross-section Cb has been amended with the updated TSP and is now listed as a "Minor Collector" in TDC Chapter 74 Figures 74-2A through 74-2G which provides two travel lanes, bike lanes, a plant strip and a sidewalk. The standard is not prescriptive and like the Urban Renewal Plan can be a special section that is modified as specific areas warrant. Accordingly, not only is the Loop Road specifically called out as a special section in the Urban Renewal Plan with anticipated modifications to the minor collector standards, the standard referenced also provides a recommendation that can be modified by the City Engineer or, in the case of a master plan, by the City Council.

The Loop Road cross sections are consistent with the description of the Loop Road in the Urban Renewal Plan. The cross sections provide sidewalks and/or shared paths, bike facilities, at least 2 travel lanes, and landscaped planter areas. In some cases, these cross sections provide even greater ultimate width than is shown in Minor Collector."

The Loop Road cross sections are attached as Exhibit A.

- (6) Except as provided in TDC 53.100, all ingress and egress shall connect directly with public streets. [Ord. 882-92, § 24,12/14/92]

Response: As shown on the Site Plan, Exhibit O, Sheets C1.0 through C1.2, all ingress and egress points connect directly with Nyberg Street, Boones Ferry Road and/or Martinazzi Avenue, all defined as public streets. The site is also served by a new minor collector, the Loop Road described above, in compliance with this criterion.

- (7) Vehicular access for residential uses shall be brought to within 50 feet of the ground floor entrances or the ground floor landing of a stairway, ramp or elevator leading to dwelling units.

Response: No residential uses are proposed within Nyberg Rivers. This provision does not apply.

- (8) To afford safe pedestrian access and egress for properties within the City, a sidewalk shall be constructed along all street frontage, prior to use or occupancy of the building or structure proposed for said property. The sidewalks required by this section shall be constructed to City standards, except in the case of streets with inadequate right-of-way width or where the final street design and grade have not been established, in which case the sidewalks shall be constructed to a design and in a manner approved by the City Engineer. Sidewalks approved by the City Engineer may include temporary sidewalks and sidewalks constructed on private property; provided, however, that such sidewalks shall provide continuity with sidewalks of adjoining commercial developments existing or proposed. When a sidewalk is to adjoin a future street improvement, the sidewalk construction shall include construction of the curb and gutter section to grades and alignment established by the City Engineer.

Response: Sidewalks, pedestrian plazas, and general pedestrian access into and through the site were all approved in the master plan and are incorporated here as shown on the Site Plan under Exhibit O, Sheets C1.0 through C1.2. The Pedestrian and Bicycle Plan included with the Master Plan and incorporated here in Exhibit A includes the locations of all proposed sidewalks and pathways, while specific design elements are shown on the cross-sections provided with the approved Master Plan and attached here as Exhibit A. Each of these paths provides safe pedestrian access and egress along all street and building frontages and are proposed to City standards.

(14) **Maximum Driveway Widths and Other Requirements.**

- (a) Unless otherwise provided in this chapter, maximum driveway widths shall not exceed 40 feet.
- (b) Except for townhouse lots, no driveways shall be constructed within 5 feet of an adjacent property line, except when two adjacent property owners elect to provide joint access to their respective properties, as provided by Subsection (2).
- (c) There shall be a minimum distance of 40 feet between any two adjacent driveways on a single property unless a lesser distance is approved by the City Engineer.

Response: Although the existing entrance provided between Buildings A and B from Nyberg Street and the alley entrance behind Building A may be defined as a driveway, none of the proposed access points qualify as a driveway. The proposed central

entry from Nyberg Street, as well as the secondary accesses from Seneca and Street 'A', is defined as a street with required easement dedication. Therefore, the minimum distance spacing requirements do not apply.

(15) Distance between Driveways and Intersections.

Except for single-family dwellings, the minimum distance between driveways and intersections shall be as provided below. Distances listed shall be measured from the stop bar at the intersection.

- (a) At the intersection of collector or arterial streets, driveways shall be located a minimum of 150 feet from the intersection.
- (b) At the intersection of two local streets, driveways shall be located a minimum of 30 feet from the intersection.
- (c) If the subject property is not of sufficient width to allow for the separation between driveway and intersection as provided, the driveway shall be constructed as far from the intersection as possible, while still maintaining the 5-foot setback between the driveway and property line as required by TDC 73.400(14)(b).
- (d) When considering a public facilities plan that has been submitted as part of an Architectural Review plan in accordance with TDC 31.071(6), the City Engineer may approve the location of a driveway closer than 150 feet from the intersection of collector or arterial streets, based on written findings of fact in support of the decision. The written approval shall be incorporated into the decision of the City Engineer for the utility facilities portion of the Architectural Review plan under the process set forth in TDC 31.071 through 31.077.

Response: The applicant is not proposing to construct any new driveway approaches. One driveway is proposed to remain southeast of Building A which is located over 200 feet from the intersection of Martinazzi and Nyberg. Although the existing entrance provided between Buildings A and B from Nyberg Street and the alley entrance behind Building A may be defined as a driveway, none of the proposed access points qualify as a driveway. The proposed central entry from Nyberg Street, as well as the secondary accesses from Seneca and Street 'A', are defined as a street with required easement dedication. Therefore, the minimum distance spacing requirements do not apply.

(16) Vision Clearance Area.

- (a) **Local Streets - A vision clearance area for all local street intersections, local street and driveway intersections, and local street or driveway and railroad intersections shall be that triangular area formed by the right-of-way lines along such lots and a straight line joining the right-of-way lines at**

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

points which are 10 feet from the intersection point of the right-of-way lines, as measured along such lines (see Figure 73-2 for illustration).

- (b) **Collector Streets** - A vision clearance area for all collector/arterial street intersections, collector/arterial street and local street intersections, and collector/arterial street and railroad intersections shall be that triangular area formed by the right-of-way lines along such lots and a straight line joining the right-of-way lines at points which are 25 feet from the intersection point of the right-of-way lines, as measured along such lines. Where a driveway intersects with a collector/arterial street, the distance measured along the driveway line for the triangular area shall be 10 feet (see Figure 73-2 for illustration).
- (c) **Vertical Height Restriction** - Except for items associated with utilities or publicly owned structures such as poles and signs and existing street trees, no vehicular parking, hedge, planting, fence, wall structure, or temporary or permanent physical obstruction shall be permitted between 30 inches and 8 feet above the established height of the curb in the clear vision area (see Figure 73-2 for illustration). [Ord. 895-93 §3, 5/24/93; Ord. 945-95, 5/8/95; Ord. 1025-99, §7, 7/26/99; Ord. 1026-99 §97, 8/9/99; Ord. 1103-02, 3/25/02; Ord. 1096-02, 1/28/02]

Response: Exhibit O, Sheets L1.2 and L1.4 show the vision clearance areas for local and collector streets, and demonstrate that the standards above are met or exceeded.

**TDC 74: PUBLIC IMPROVEMENT REQUIREMENTS
IMPROVEMENTS**

SECTION 74.110 PHASING OF IMPROVEMENTS.

The applicant may build the development in phases. If the development is to be phased the applicant shall submit a phasing plan to the City Engineer for approval with the development application. The timing and extent or scope of public improvements and the conditions of development shall be determined by the City Council on subdivision applications and by the City Engineer on other development applications.

Response: There is no proposed phasing planned for the Nyberg Rivers redevelopment project. However, within the conservation area in the northwest corner of the site, the Applicant proposes a "Shared Pathway Easement" that will allow for future development and the extension of the Tualatin River Trail at a later date. The pathway will be provided as an easement to the City, but construction of the pathway is not proposed as a part of this application.

SECTION 74.120 PUBLIC IMPROVEMENTS.

- (1) Except as specially provided, all public improvements shall be installed at the expense of the applicant. All public improvements installed by the applicant shall be constructed and guaranteed as to workmanship and material as required by the Public Works Construction Code prior to acceptance by the City. No work

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

shall be undertaken on any public improvement until after the construction plans have been approved by the City Engineer and a Public Works Permit issued and the required fees paid.

Response: The Applicant is aware that all public improvements shall be installed at the expense of the Applicant. And those public improvements will be constructed and guaranteed as to workmanship and material as required by the Public Works Construction Code prior to acceptance by the City. As stated above, Street A requires additional City owned property to commence construction and Seneca Street will be constructed at such time as the City decides to relocate Council Chambers and make sufficient right of way available for that use.

SECTION 74.130 PRIVATE IMPROVEMENTS.

All private improvements shall be in-stalled at the expense of the applicant. The property owner shall retain maintenance responsibilities over all private improvements.

Response: The Applicant is aware that all private improvements shall be installed at the expense of the Applicant and maintenance of those improvements will be under the responsibility of the Applicant.

SECTION 74.140 CONSTRUCTION TIMING.

- (1) All the public improvements required under this chapter shall be completed and accepted by the City prior to the issuance of a Certificate of Occupancy; or, for subdivision and partition applications, in accordance with the requirements of the Subdivision regulations.
- (2) All private improvements required under this chapter shall be approved by the City prior to the issuance of a Certificate of Occupancy; or for subdivision and partition applications, in accordance with the requirements of the Subdivision regulations.

Response: The Applicant is aware that the public and private improvements must be completed and accepted prior to the issuance of a Certificate of Occupancy. However, as articulated in the master plan, the Seneca Street extension will not be constructed until such time as the City determines it is necessary or desired to move City facilities to accommodate the extension. In particular, the master plan final decision concluded "the time of construction will be determined through the public facilities decision process and is not anticipated or required to occur prior to removal of the Council Chambers building." (Resolution 5163-13 at page 11). Thus, it is not likely nor required that Seneca Street is constructed prior to a Certificate of Occupancy as contemplated in the master plan approval.

RIGHT-OF-WAY

SECTION 74.210 MINIMUM STREET RIGHT-OF-WAY WIDTHS.

The width of streets in feet shall not be less than the width required to accommodate a street improvement needed to mitigate the impact of a proposed development. In cases where a street is required to be improved according to the standards of the TDC, the width of the right-of-way shall not be less than the minimums indicated in TDC Chapter 11, Transportation Plan.

- (2) For development applications other than subdivisions and partitions, wherever existing or future streets adjacent to property proposed for development are of inadequate right-of-way width, the additional right-of-way necessary to comply with the Transportation Element of the Tualatin Community Plan shall be dedicated to the City for use by the public prior to issuance of any building permit for the proposed development. This right-of-way dedication shall be for the full width of the property abutting the roadway and, if required by the City Engineer, additional dedications shall be provided for slope and utility easements if deemed necessary.
- (4) If the City Engineer deems that it is impractical to acquire the additional right-of-way as required in subsections (1)-(3) of this section from both sides of the center-line in equal amounts, the City Engineer may require that the right-of-way be dedicated in a manner that would result in unequal dedication from each side of the road. This requirement will also apply to slope and utility easements as discussed in TDC 74.320 and 74.330. The City Engineer's recommendation shall be presented to the City Council in the preliminary plat approval for subdivisions and partitions, and in the recommended decision on all other development applications, prior to finalization of the right-of-way dedication requirements.
- (5) Whenever a proposed development is bisected by an existing or future road or street that is of inadequate right-of-way width according to TDC Chapter 11, Transportation Plan, additional right-of-way shall be dedicated from both sides or from one side only as determined by the City Engineer to bring the road right-of-way in compliance with this section.
- (6) When a proposed development is adjacent to or bisected by a street proposed in TDC Chapter 11, Transportation Plan and no street right-of-way exists at the time the development is proposed, the entire right-of-way as shown in TDC Chapter 11 shall be dedicated by the applicant. The dedication of right-of-way required in this subsection shall be along the route of the road as determined by the City.

Response: The Applicant is aware that additional right-of-way may need to be dedicated in order to facilitate street improvements along adjacent roadways that serve the Nyberg Rivers site. Based on discussion with City Transportation Engineers and coordination with ODOT, the Nyberg Street ROW is owned by ODOT and therefore no additional ROW dedication for improvements is needed. The Loop Road will also be a public road consistent with the terms of the final master plan decision. The cross sections for each road and the associated right of way widths are shown in Exhibit O. These cross sections and widths were specifically reviewed and approved under the master plan. Proposed improvements provide

Cardno

Submitted September 13, 2013

Completeness Responses October 23, 2013

for all modes of travel consistent with the City's design standards located within the transportation system plan. All streets proposed for development have adequate right of way width or will maintain that width through a dedicated easement conveyance.

EASEMENTS AND TRACTS

SECTION 74.310 GREENWAY, NATURAL AREA, BIKE, AND PEDESTRIAN PATH DEDICATIONS AND EASEMENTS.

- (1) Areas dedicated to the City for Greenway or Natural Area purposes or easements or dedications for bike and pedestrian facilities during the development application process shall be surveyed, staked and marked with a City approved boundary marker prior to acceptance by the City.
- (2) For subdivision and partition applications, the Greenway, Natural Area, bike, and pedestrian path dedication and easement areas shall be shown to be dedicated to the City on the final subdivision or partition plat prior to approval of the plat by the City; or
- (3) For all other development applications, Greenway, Natural Area, bike, and pedestrian path dedications and easements shall be submitted to the City Engineer; building permits shall not be issued for the development prior to acceptance of the dedication or easement by the City. [Ord. 933-94 §50, 11/28/94; Ord. 979-97 §52, 7/14/97; Ord. 1026-99 §98, 8/9/99].

Response: As shown on the attached Site Plan, Exhibit O, Sheets C1.0 through C1.2, the Applicant proposes a "Shared Pathway Easement" that will allow for future development and the extension of the Tualatin River Trail at a later date. This easement will be accepted by the City prior to issuance of building permits, but construction of the pathway is not proposed as a part of this review. The applicant is not proposing a land division at this time. The applicant will prepare easements and dedications for the City engineers review consistent with the requirements stated above.

SECTION 74.320 SLOPE EASEMENTS.

- (1) The applicant shall obtain and convey to the City any slope easements determined by the City Engineer to be necessary adjacent to the proposed development site to support the street improvements in the public right-of-way or accessway or utility improvements required to be constructed by the applicant.
- (2) For subdivision and partition applications, the slope easement dedication area shall be shown to be dedicated to the City on the final subdivision or partition plat prior to approval of the plat by the City; or
- (3) For all other development applications, a slope easement dedication shall be submitted to the City Engineer; building permits shall not be issued for the development prior to acceptance of the easement by the City. [Ord. 933-94, § 51, 11/28/94]

Response: The Applicant is aware that slope easements determined by the City Engineer may be necessary to support the street improvements in the public ROW. If the City Engineer so decides, slope easements will be provided by the applicant during the final engineering design and permitting process.

SECTION 74.330 UTILITY EASEMENTS.

- (1) Utility easements for water, sanitary sewer and storm drainage facilities, telephone, television cable, gas, electric lines and other public utilities shall be granted to the City.
- (4) For development applications other than subdivisions and partitions, and for both on-site and off-site easement areas, a utility easement shall be granted to the City; building permits shall not be issued for the development prior to acceptance of the easement by the City. The City may elect to exercise eminent domain and condemn necessary off-site public utility easements at the applicant's request and expense. The City Council shall determine when condemnation proceedings are to be used.
- (5) The width of the public utility easement shall meet the requirements of the Public Works Construction Code. All subdivisions and partitions shall have a 6-foot public utility easement adjacent to the street and a 5-foot public utility easement adjacent to all side and rear lot lines. [Ord. 933-94, § 52, 11/28/94]

Response: The Applicant is aware that utility easements will be required for water, sanitary sewer and storm draining facilities. Existing easements are shown on the Existing Conditions Sheets C0.1 through C0.3 under Exhibit O, while proposed and existing easements are shown on the Site Plans, Sheets C1.0 through C1.2.

SECTION 74.340 WATERCOURSE EASEMENTS.

- (1) Where a proposed development site is traversed by or adjacent to a watercourse, drainage way, channel or stream, the applicant shall provide a storm water easement, drainage right-of-way, or other means of preservation approved by the City Engineer, conforming substantially with the lines of the watercourse. The City Engineer shall determine the width of the easement, or other means of preservation, required to accommodate all the requirements of the Surface Water Management Ordinance, existing and future storm drainage needs and access for operation and maintenance.
- (2) For subdivision and partition applications, any watercourse easement dedication area shall be shown to be dedicated to the City on the final subdivision or partition plat prior to approval of the plat by the City; or
- (3) For all other development applications, any watercourse easement shall be executed on a dedication form submitted to the City Engineer; building permits shall not be issued for the development prior to acceptance of the easement by the City.

- (4) The storm water easement shall be sized to accommodate the existing water course and all future improvements in the drainage basin. There may be additional requirements as set forth in TDC Chapter 72, Greenway and Riverbank Protection District, and the Surface Water Management Ordinance. Water quality facilities may require additional easements as described in the Surface Water Management Ordinance. [Ord. 933-94, § 53, 11/28/94]

Response: The Applicant is not proposing a subdivision, nor is there any known watercourse or drainage way that is located on the property that would necessitate an easement per the standards set forth above.

SECTION 74.350 TRACTS.

A dedicated tract or easement will be required when access to public improvements for operation and maintenance is required, as determined by the City Engineer. Access for maintenance vehicles shall be constructed of an all-weather driving surface capable of carrying a 50,000-pound vehicle. The width of the tract or easement shall be 15-feet in order to accommodate City maintenance vehicles. In subdivisions and partitions, the tract shall be dedicated to the City on the final plat. In any other development, an access easement shall be granted to the City and recorded prior to issuance of a building permit. [Ord. 933-94, § 54, 11/28/94]

Response: The applicant will be dedicating proper easements with the Nyberg Rivers redevelopment project. These easements will include dedications for utilities and shared pathways as shown on the site plan included within Exhibit O. Based on input received from ODOT, a 10-foot wide maintenance access easement along the new Nyberg Street right-of-way is required and shown on the Site Plan, Sheet C1.1 under Exhibit O. Also, a 15-foot access easement is shown from the main entrance off Nyberg Street to connect to the ODOT maintenance easement and the (6) tax lots that currently use the existing access road. The 15-foot access easement will be located within the proposed 62.50' access easement at the primary entry before tying into the 30-foot ODOT access easement along the east-west drive aisle just north of Building E. This 30-foot easement continues to the east before heading in a northeasterly direction. At this point the proposed 15-foot access easement swings southeast to connect to the 10-foot maintenance easement. See Sheets C1.0 and C1.1 for reference. Access for maintenance vehicles shall be constructed of an all-weather driving surface capable of carrying a 50,000-pound vehicle consistent with city requirements.

TRANSPORTATION

SECTION 74.410 FUTURE STREET EXTENSIONS.

- (1) Streets shall be extended to the proposed development site boundary where necessary to:
- (a) give access to, or permit future development of adjoining land;
 - (b) provide additional access for emergency vehicles;

- (c) provide for additional direct and convenient pedestrian, bicycle and vehicle circulation;
- (d) eliminate the use of cul-de-sacs except where topography, barriers such as railroads or freeways, existing development, or environmental constraints such as major streams and rivers prevent street extension.
- (e) eliminate circuitous routes. The resulting dead end streets may be approved without a turnaround. A reserve strip may be required to preserve the objectives of future street extensions.

Response: Future street extensions proposed for the Nyberg Rivers redevelopment include the Street 'A' extension off Boones Ferry Road, the loop road system, as well as the SW Seneca Street extension across City-owned property. The applicant has provided a comprehensive Traffic Impact Analysis for the site that demonstrates that the site provides the necessary street extensions to provide access to the site. The TIA is attached as Exhibit L. The City found in its master plan decision that the streets proposed provide access to the commercial development, improve existing functions of transportation facilities in the area and provide direct and convenient pedestrian, vehicle and bicycle access in compliance with this criterion. This access plan is illustrated on Exhibit O and defined in the cross sections also attached under Exhibit A.

(2) Proposed streets shall comply with the general location, orientation and spacing identified in the Local Streets Plan, TDC 11.630, Figure 11-1 and Figure 11-3.

- (b) Streets proposed as part of new industrial or commercial development shall comply with TDC 11.630(2) and Figure 11-1.

Response: The proposed streets do comply with the general location, orientation and spacing identified in Figure 11-1. Specifically, Figure 11-1 identifies the Loop Road extension that is achieved through the Street 'A', SW Seneca Street and main entry extensions.

The City Council comprehensively reviewed the site access for the redeveloped project under the master plan proceedings. The Site Plan, attached as Exhibit O, Sheets C1.0- C1.2. is in compliance with the access plan approved by the City Council in the master plan decision. Specifically, the City adopted the location and design of the Loop Road as shown on the Site Plan. The master plan findings relative to the Loop Road are excerpted here and incorporated by reference:

"The City Council finds that the applicant is providing a Loop Road in the location permitted by the TSP and has designed that road consistent with the terms of the Urban Renewal Plan. The City's TSP shows a "future minor collector" on the project site. The future minor collector is shown as a dashed green line that connects Boones Ferry with Seneca Street and SW Nyberg Street. No specific alignment is proposed in the TSP. Rather, Figure 1 expressly states: "Future roadway alignments are approximate and subject to additional engineering and

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

design." The TSP further provides that the function of this minor collector is to "connect two major arterials, SW Boones Ferry Road and SW Nyberg Street." The TSP shows the additional task of connecting Seneca Street to Boones Ferry and SW Nyberg through the site. This location is in the same conceptual location shown in the 2013 TSP. The Loop Road is not in the parking lot drive aisles. Instead the Loop Road commences at Boones Ferry Road continues through the site connecting with the improved Seneca Street and continues with a through connection to SW Nyberg Street. This location is consistent with the TSP and fully meets the desired objective of the Loop Road which is to connect Seneca Street, Boones Ferry and SW Nyberg Street.

The Urban Renewal Plan also specifically addresses the design of the Loop Road under the section entitled, Public Improvements at page 19. There the Plan defines the Loop Road as a minor collector. It then states: "This *entire street will be a special section*, but will *generally* follow Street Section Cb and be modified as specific areas warrant."

Street cross-section Cb has been amended with the updated TSP and is now listed as a "Minor Collector" in TDC Chapter 74 Figures 74-2A through 74-2G which provides two travel lanes, bike lanes, a plant strip and a sidewalk. The standard is not prescriptive and like the Urban Renewal Plan can be a special section that is modified as specific areas warrant. Accordingly, not only is the Loop Road specifically called out as a special section in the Urban Renewal Plan with anticipated modifications to the minor collector standards, the standard referenced also provides a recommendation that can be modified by the City Engineer or, in the case of a master plan, by the City Council.

The Loop Road cross sections are consistent with the description of the Loop Road in the Urban Renewal Plan. The cross sections provide sidewalks and/or shared paths, bike facilities, at least 2 travel lanes, and landscaped planter areas. In some cases, these cross sections provide even greater ultimate width than is shown in Minor Collector."

The Loop Road cross sections are attached within Exhibit A.

- (3) During the development application process, the location, width, and grade of streets shall be considered in relation to existing and planned streets, to topographical conditions, to public convenience and safety, and to the proposed use of the land to be served by the streets. The arrangement of streets in a subdivision shall either:
- (a) provide for the continuation or appropriate projection of existing streets into surrounding areas; or
 - (b) conform to a street plan approved or adopted by the City to meet a particular situation where topographical or other conditions make continuance of or conformance to existing streets impractical.

Response: The location, width, and grade of streets were reviewed and determined during the approved Master Plan process. The Master Plan included cross-sections showing the widths and back of curb pedestrian and landscaping elements for the proposed streets and driveways. The master plan findings on the street plan are incorporated herein by reference as well as the findings of the TIA attached as Exhibit L. The cross sections attached as Exhibit A show that the streets proposed meet the grade of existing streets protecting the public safety and convenience. The streets conform to the TSP in design and location and provide for continuation of streets through the project site in compliance with this criterion.

- (4) **The City Engineer may require the applicant to submit a street plan showing all existing, proposed, and future streets in the area of the proposed development.**

Response: A plan of the street networks is shown within Exhibit O and conforms to the street plan and cross-sections approved by the City Council in the master plan proceedings. The street plan shows all proposed, existing and future (Seneca extension) streets in the area of the proposed development in compliance with this criterion.

- (5) **The City Engineer may require the applicant to participate in the funding of future off-site street extensions when the traffic impacts of the applicant's development warrant such a condition. [Ord. 933-94 §55, 11/28/94; Ord. 1026-99 §99, 8/9/99; Ord. 1103-02, 3/25/02]**

Response: The traffic impacts of this development were exhaustively reviewed in the master plan proceedings. The transportation findings from the final master plan decision are incorporated herein by reference. The TIA demonstrates that all study intersections will continue to operate at acceptable levels of service and some intersections will improve over existing conditions. The applicant agreed in the master plan proceedings to fund a number of street improvements including: a signalized intersection at the SW Martinazzi Avenue and SW Seneca Street intersection; Street "A" on the Site Plan will be dedicated and extended from Boones Ferry Road into the site, connecting to Seneca and Nyberg Streets; Nyberg Street will be expanded with additional right turn lane; An access easement will be dedicated with the Street "A" extension in order to provide future access to the Future Development Area 4. As shown on the Site Plan and in the findings above, the Site Plan provides direct and convenient pedestrian, bicycle and vehicle access through the site. New sidewalks and streets are planned through the site, connecting with the surrounding vehicle, pedestrian and bicycle network. These proposed streets and drive aisles meet the design standards identified by TDC 11.630, Figure 11-1 and Figure 11-3 and consider the context of existing, adjacent streets.

The Site Plan is sensitively designed to facilitate development of adjoining properties through the location of uses and street extensions.

The findings provided earlier in this narrative addressing the street, pedestrian and bike improvements are incorporated herein by reference.

SECTION 74.420 STREET IMPROVEMENTS.

When an applicant proposes to develop land adjacent to an existing or proposed street, including land which has been excluded under TDC 74.220, the applicant should be responsible for the improvements to the adjacent existing or proposed street that will bring the improvement of the street into conformance with the Transportation Plan, and the City's Public Works Construction Code, subject to the following provisions:

- (1) For any development proposed within the City, roadway facilities within the right-of-way described in TDC 74.210 shall be improved to standards as set out in the Public Works Construction Code.

Response: Other than the future Seneca Street extension, the only proposed work within the existing ROW will occur on the north side of Nyberg Street, within the ODOT ROW. As ODOT already owns the ROW, for the proposed improvements along Nyberg, no additional dedication is needed. As mentioned above in detail, a new Loop Road will be constructed through the site to the design parameters of a minor collector as approved in the master plan. The Loop Road will be a public road throughout the site.

- (2) The required improvements may include the rebuilding or the reconstruction of any existing facilities located within the right-of-way adjacent to the proposed development to bring the facilities into compliance with the Public Works Construction Code.

Response: The only proposed work within the existing ROW will occur on the north side of Nyberg Street, within the ODOT ROW. As ODOT already owns the ROW for the proposed improvements, no additional dedication is needed. Improvements will also occur at Street A and Lower Boones Ferry, at Martinazzi and Seneca (subject to ROW provided by the City) as well as the main entrance and Nyberg. These improvements will be in compliance with the Public Works Construction Code which will be assured during the permitting and construction process.

- (3) The required improvements may include the construction or rebuilding of off-site improvements which are identified to mitigate the impact of the development.

Response: The applicant will construct all of the off-site improvements identified in the master plan:

- *The Seneca Street extension to the Nyberg Rivers site with a signal at SW Martinazzi Avenue constructed to the standards of a Minor Collector Street. The time of construction will be determined through the public facilities decision process and is not anticipated or required to occur prior to removal of the Council Chambers building.*
- *A westbound right turn lane on SW Nyberg Road.*
- *Two southbound left turn lanes and a shared through/right turn lane from the site's access onto SW Nyberg Road.*
- *Two inbound receiving lanes; and*
- *The associated signal improvements at the main entrance.*

In addition, City Council finds the street cross-sections need to be modified to satisfy Goal 5 and are needed to serve the Master Plan area. The City Council approves the Master Plan cross sections with the following modifications:"

The applicant revised the cross sections to meet these modification requests and the findings and this record demonstrate that the applicable jurisdictions reviewed the proposal and found, with the conditions of approval, that the proposal met each of their standards.

- (4) Where development abuts an existing street, the improvement required shall apply only to that portion of the street right-of-way located between the property line of the parcel proposed for development and the centerline of the right-of-way, plus any additional pavement beyond the centerline deemed necessary by the City Engineer to ensure a smooth transition between a new improvement and the existing roadway (half-street improvement). Additional right-of-way and street improvements and off-site right-of-way and street improvements may be required by the City to mitigate the impact of the development. The new pavement shall connect to the existing pavement at the ends of the section being improved by tapering in accordance with the Public Works Construction Code.

Response: The only proposed work within the existing ROW will occur on the north side of Nyberg Street, within the ODOT ROW. The improvement applies only to that portion of the street right-of-way located between the property line of the parcel proposed for development and the centerline of the right-of-way, plus any additional pavement beyond the centerline deemed necessary by the City Engineer to ensure a smooth transition between a new improvement and the existing roadway (half-street improvement).

- (5) If additional improvements are required as part of the Access Management Plan of the City, TDC Chapter 75, the improvements shall be required in the same manner as the half-street improvement requirements.

Response: The Applicant is aware of this provision, although no additional improvements are foreseen within the proposed scope of work along Nyberg Street.

- (6) All required street improvements shall include curbs, sidewalks with appropriate buffering, storm drainage, street lights, street signs, street trees, and, where designated, bikeways and transit facilities.

Response: The proposed half-street improvements along the north side of Nyberg Street includes a 15-foot right-hand turn lane, a 4-foot planter and a combined 12-foot shared pathway to accommodate both bicycle and pedestrian access. A cross-section of these improvements was summarized under cross-section G-G, submitted under the approved Master Plan and attached here under Exhibit A.

The master plan decision at pages 14 through 16 adopted these cross sections as modified.

- (7) For subdivision and partition applications, the street improvements required by TDC Chapter 74 shall be completed and accepted by the City prior to signing the final subdivision or partition plat, or prior to releasing the security provided by the applicant to assure completion of such improvements or as otherwise specified in the development application approval.

Response: No subdivision or partition applications have been submitted as part of the Nyberg Rivers redevelopment project.

- (8) For development applications other than subdivisions and partitions, all street improvements required by this section shall be completed and accepted by the City prior to the issuance of a Certificate of Occupancy.

Response: The applicant is aware of this provision and will complete the street improvements prior to issuance of a Certificate of Occupancy. The only exception to this criterion is the Seneca Street extension. That extension is not required as part of this development application but instead will occur if and when the City decides to relocate Council Chambers.

- (10) Streets within, or partially within, a proposed development site shall be graded for the entire right-of-way width and constructed and surfaced in accordance with the Public Works Construction Code.

Response: All internal driveways and accessways within the proposed development will be graded, constructed, and surfaced for the entire portion of the site. The public streets dedicated with this project are the Street 'A' extension, the Loop Road and the expansion of Nyberg Street.

- (11) Existing streets which abut the proposed development site shall be graded, constructed, reconstructed, surfaced or repaired as necessary in accordance with the Public Works Construction Code and TDC Chapter 11, Transportation Plan.

Response: Existing streets which abut Nyberg Rivers will be graded, constructed, reconstructed, surfaced, or repaired as necessary. The only proposed work within the existing public ROW is along the north side of Nyberg Street.

- (12) Sidewalks with appropriate buffering shall be constructed along both sides of each internal street and at a minimum along the development side of each external street in accordance with the Public Works Construction Code.

Response: As shown on the Landscaping Planting Plan, Exhibit O – Sheets L1.0 through L1.10, sidewalks have been located to provide connectivity into and through the site along both north-south and east-west corridors. Landscape buffering or landscape islands are provided along all sidewalks.

- (13) The applicant shall comply with the requirements of the Oregon Department of Transportation (ODOT), Tri-Met, Washington County and Clackamas County when

Nyberg Rivers
Architectural Review

78

Cardno
Submitted September 13, 2013

Completeness Responses October 23, 2013

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

a proposed development site is adjacent to a roadway under any of their jurisdictions, in addition to the requirements of this chapter.

Response: All applicable jurisdictions provided comments on this development as part of the master plan review. Each found that the development complied with their requirements subject to conditions of approval. Those conditions of approval were incorporated into the master plan and are incorporated herein by reference from pages 9-16 of the master plan final decision:

"ODOT reviewed the submitted information for their facilities (I-5 and Nyberg Street). Based on the analysis performed by ODOT, the Applicant's proposed improvements mitigate the impact of the development on ODOT facilities. Per coordination with ODOT, a 10-foot wide maintenance access easement along the new Nyberg Street right-of-way is shown on the Site Plan, Sheet C1.1 under Exhibit O. Also, a 15-foot access easement is shown from the main entrance off Nyberg Street to connect to the ODOT maintenance easement and the (6) tax lots that currently use the existing access road. Sufficient right-of-way exists; however, final design may indicate the need for refinements and adjustments to the site plan to accommodate public improvements. The ODOT required mitigation is a condition of approval.

Washington County also reviewed the information and they have provided a list of conditions and measures to mitigate impacts on Nyberg Street and Tualatin-Sherwood Road. Final design may indicate the need for additional right-of-way. The Washington County required mitigation is a condition of approval."

"The Tualatin Transportation System Plan and Tualatin Development Code chapters 11, 74, and 75 includes future Minor Collector streets within the project area including a Loop Road; a western extension of SW Seneca Street that would connect to a new street between the main site entrance as well as SW Boones Ferry Road plus SW Nyberg Road from the Kmart/Fred Meyer intersection to SW Martinazzi. SW Boones Ferry Road and SW Nyberg Road from I-5 to the Kmart/Fred Meyer intersection are classified as Major Arterials.

Private streets with public access over the locations of the Loop Road instead of public streets are supported by:

- The submitted traffic study shows public access will function adequately.
- The cross-sections for the locations of the public access have "street-like" qualities.
- Future arrangements for maintenance will assure the continued functionality of the public access to public standards.

The Loop Road collector is intended to provide public vehicular and pedestrian access through Urban Renewal Blocks 2 and 5 and the eastern portion of the City's downtown core. The cross-sections include characteristics of Minor Collectors like sidewalks and bike-lanes or multi use paths, planter strips or tree wells, streetlights, and through travel lanes. Parking is either available adjacent

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

to planters and sidewalks within the cross-section or within adjacent parking lots."

"The City Council concludes that the Master Plan, with the proposed conditions, complies with Goal 5. Adequate transportation facilities providing connections and improvements consistent with the transportation system meets Goal 5.

City Council finds the following transportation improvements are needed for the Master Plan to comply with Goal 5, and therefore imposes them as conditions of approval:

- *The Seneca Street extension to the Nyberg Rivers site with a signal at SW Martinazzi Avenue constructed to the standards of a Minor Collector Street. The time of construction will be determined through the public facilities decision process and is not anticipated or required to occur prior to removal of the Council Chambers building.*
- *A westbound right turn lane on SW Nyberg Road.*
- *Two southbound left turn lanes and a shared through/right turn lane from the site's access onto SW Nyberg Road.*
- *Two inbound receiving lanes; and*
- *The associated signal improvements at the main entrance.*

In addition, City Council finds the street cross-sections need to be modified to satisfy Goal 5 and are needed to serve the Master Plan area. The City Council approves the Master Plan cross sections with the following modifications:"

The applicant revised the cross sections to meet these modification requests and the findings and this record demonstrate that the applicable jurisdictions reviewed the proposal and found, with the conditions of approval, that the proposal met each of their standards.

- (14) **The applicant shall construct any required street improvements adjacent to parcels excluded from development, as set forth in TDC 74.220 of this chapter.**

Response: The Applicant is aware of the street improvements adjacent to parcels excluded from development provision. Both the Street 'A' and SW Seneca Street extension are considered street improvements adjacent to parcels excluded from development. As noted above the construction of Seneca is subject to the City providing right-of-way and is not needed to be constructed prior to occupancy.

- (15) **Except as provided in TDC 74.430, whenever an applicant proposes to develop land with frontage on certain arterial streets and, due to the access management provisions of TDC Chapter 75, is not allowed direct access onto the arterial, but instead must take access from another existing or future public street thereby providing an alternate to direct arterial access, the applicant shall be required to construct and place at a minimum street signage, a sidewalk, street trees and street lights along that portion of the arterial street adjacent to the applicant's**

property. The three certain arterial streets are S.W. Tualatin-Sherwood Road, S.W. Pacific Highway (99W) and S.W. 124th Avenue. In addition, the applicant may be required to construct and place on the arterial at the intersection of the arterial and an existing or future public non-arterial street warranted traffic control devices (in accordance with the Manual on Uniform Traffic Control Devices, latest edition), pavement markings, street tapers and turning lanes, in accordance with the Public Works Construction Code.

Response: The development has access to a new minor collector, the internal Loop Road. The Loop Road is the primary access for the entire site. The Loop Road connects at an intersection with Nyberg Street and Boones Ferry Road. Because the Loop Road will be a public minor collector road, this standard does not apply. The applicant is aware of the access management provisions of TDC Chapter 75, but based on conversation and input from the City, the proposed access points will not negatively impact or create access management issues within the region. This is supporting by the findings outlined in the TIA included under Exhibit L.

- (16) The City Engineer may determine that, although concurrent construction and placement of the improvements in (14) and (15) of this section, either individually or collectively, are impractical at the time of development, the improvements will be necessary at some future date. In such a case, the applicant shall sign a written agreement guaranteeing future performance by the applicant and any successors in interest of the property being developed. The agreement shall be subject to the City's approval.

Response: The applicant is aware of this provision, but does not foresee that construction and street improvements will occur separately, with the exception of Seneca Street..

- (17) Intersections should be improved to operate at a level of service of at least D and E for signalized and unsignalized intersections, respectively. [Ord. 933-94 §56, 11/28/94; Ord. 1026-99 §100, 8/9/99; Ord.1103-02, 3/25/02; Ord. 1224-06 §36, 11/13/06]

Response: The scope of the traffic report and required level of service analysis and street standards applicable in the TIA were reviewed and approved by all of the relevant jurisdictions prior to commencing the TIA analysis. The analysis demonstrates that all signalized and unsignalized intersections that are impacted at more than a de minimis level will continue to operate at LOS D or E, respectively consistent with this criterion.

The TIA Conclusions and Recommendations section found within the TIA on pages 53 to 56, demonstrate that all intersections will continue to operate at acceptable levels of service D and E and some intersections will experience improved service. The master plan final decision shares this conclusion with enumerated conditions of approval, as described above.

SECTION 74.440 STREETS, TRAFFIC STUDY REQUIRED.

- (1) The City Engineer may require a traffic study to be provided by the applicant and furnished to the City as part of the development approval process as provided by this Code, when the City Engineer determines that such a study is necessary in connection with a proposed development project in order to:
- (a) Assure that the existing or proposed transportation facilities in the vicinity of the proposed development are capable of accommodating the amount of traffic that is expected to be generated by the proposed development, and/or
 - (b) Assure that the internal traffic circulation of the proposed development will not result in conflicts between on-site parking movements and/or on-site loading movements and/or on-site traffic movements, or impact traffic on the adjacent streets.

Response: A traffic study prepared by Kittelson and Associates, Inc. was drafted and included as a part of the Master Plan application. The TIA is attached here as Exhibit L and includes the original traffic study and all of the supplemental memorandum and analysis developed during the master plan proceedings. The traffic study demonstrates, and the master plan final decision concludes, that all study intersections will continue to operate at acceptable levels of service with the conditions of approval and all internal traffic circulation will not result in conflicts between on-site movements.

- (2) The required traffic study shall be completed prior to the approval of the development application.

Response: The traffic study completed by Kittelson and Associates, Inc. is complete and attached as Exhibit L.

- (3) The traffic study shall include, at a minimum:
- (a) an analysis of the existing situation, including the level of service on adjacent and impacted facilities.
 - (b) an analysis of any existing safety deficiencies.
 - (c) proposed trip generation and distribution for the proposed development.
 - (d) projected levels of service on adjacent and impacted facilities.
 - (e) recommendation of necessary improvements to ensure an acceptable level of service for roadways and a level of service of at least D and E for signalized and unsignalized intersections respectively, after the future traffic impacts are considered.

- (f) The City Engineer will determine which facilities are impacted and need to be included in the study.
 - (g) The study shall be conducted by a registered engineer.
- (4) The applicant shall implement all or a portion of the improvements called for in the traffic study as determined by the City Engineer. [Ord. 1103-02, 3/25/02]

Response: The required TIA was scoped with the City and County and was completed by Kittelson and Associates. That TIA is included as Exhibit L and addresses all of the above requirements while demonstrating that the proposed development will have no impact or will improve the existing transportation infrastructure. The mitigation to improve traffic efficiency is also noted in the TIA. Those improvements include:

- A new roadway connection to SW Boones Ferry Road (shown as "Street A" in Figure 2 of the TIA) that includes sidewalks.
- An enhanced site-access through development of the Loop Road that will better accommodate vehicular queuing and demand.
- A potential future (assuming the City desires to move forward) new site-access connection to SW Martinazzi Avenue that aligns across from SW Seneca Street. This connection would be the Seneca Street extension envisioned in the Town Center Plan. Prior to the City making a decision on any new SW Street Seneca alignment, the redevelopment site plan preserves this connection opportunity in the present or future.
- The preservation of east-west and north-south travel ways that will provide vehicular and pedestrian access between Street A, the Seneca Street alignment/extension, and enhanced access to SW Nyberg Street.
- New sidewalks along the enhanced site-access driveway to SW Nyberg Street that provide pedestrian connections to the integrated site circulation network.
- New bikeway connections along the perimeter of the site.
- Closure of the existing SW 75th Avenue site-access driveway to SW Nyberg Street to minimize turning movement conflicts, allow for construction of a westbound right-turn lane at SW Nyberg Street/signalized site driveway, and to improve the interchange access spacing conditions along SW Nyberg Street.
- A new 350-foot westbound right-turn lane constructed on SW Nyberg Street
- The site design also facilitates connections to surrounding properties and does not preclude the development of other transportation facilities consistent with the TSP. These commitments by the applicant will work to create a more

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

efficient and coordinated transportation system within Nyberg Rivers and the City Center.

The transportation conditions of approval imposed by the master plan final decision are detailed above and not repeated here but incorporated by reference.

The TIA also contains all of the required components required above on page 56 within the TIA.

SECTION 74.450 BIKEWAYS AND PEDESTRIAN PATHS.

- (1) Where proposed development abuts or contains an existing or proposed bikeway or pedestrian path, as set forth in TDC Chapter 11, Transportation Plan, the City may require that a bikeway or pedestrian path be constructed, and an easement or dedication provided to the City.
- (2) Where required, bikeways and pedestrian paths shall be provided as follows:
 - (a) Bike and pedestrian paths shall be constructed and surfaced in accordance with the Public Works Construction Code.
 - (b) The applicant shall install the striping and signing of the bike lanes and shared roadway facilities, where designated. [Ord. 933-94, § 57, 11/28/94]

Response: As approved with the Master Plan, the Applicant is proposing to dedicate a shared pathway easement for the future build out of a pedestrian and bicycle path along the Tualatin River Trail network. That shared pathway easement is located at the northern end of Nyberg Rivers, within the conservation area along the south side of the Tualatin River. The Applicant is also proposing to construct two north-south connections through the site as detailed within the site plan included within Exhibit O; the first bisects the site running north from the main entrance off of Nyberg Street through the site, between proposed buildings 1030 and 1040 connecting in with the planned Tualatin River Trail. The second north-south connection is located within the western portions of the site and connects Seneca Street to proposed Street "A" and the planned Tualatin River Trail. All pathways will be constructed in accordance with the Public Works Construction Code. These pathways are shown within the Site Plan include within Exhibit O.

SECTION 74.470 STREET LIGHTS.

- (1) Street light poles and luminaries shall be installed in accordance with the Public Works Construction Code.
- (2) The applicant shall submit a street lighting plan for all interior and exterior streets on the proposed development site prior to issuance of a Public Works Permit.

Response: The Applicant is aware of the street lighting provision. Street lighting and a Photometric Plan is included with this ARB application as Exhibit O – E-1 through E-6.

UTILITIES

SECTION 74.610 WATER SERVICE.

- (1) Water lines shall be installed to serve each property in accordance with the Public Works Construction Code. Water line construction plans shall be submitted to the City Engineer for review and approval prior to construction.
- (2) If there are undeveloped properties adjacent to the subject site, public water lines shall be extended by the applicant to the common boundary line of these properties. The lines shall be sized to provide service to future development, in accordance with the City's Water System Master Plan, TDC Chapter 12.
- (3) As set forth is TDC Chapter 12, Water Service, the City has three water service levels. All development applicants shall be required to connect the proposed development site to the service level in which the development site is located. If the development site is located on a boundary line between two service levels the applicant shall be required to connect to the service level with the higher reservoir elevation. The applicant may also be required to install or provide pressure reducing valves to supply appropriate water pressure to the properties in the proposed development site. [Ord. 933-94, § 59, 11/28/94]

Response: The subject property is bounded by I-5 to the east, the Tualatin River to the north, Nyberg Street to the south and City owned property that fronts Martinazzi Avenue to the west. There are currently water lines in Martinazzi Avenue providing service to the adjacent City owned properties. Likewise the existing apartment development located north is connected to the water system in Boones Ferry Road. The Applicant has included a proposed water system plan, Exhibit O – Sheets C6.0-6.2, that provides access to water for domestic as well as fire protection for the site. All proposed and existing buildings will be served by the proposed water system. The proposed water system onsite will extend a portion of the public water line with a 15 foot easement to serve the proposed buildings F-100. At the property line the public water line will change to a private water line (proposed double check valve assembly to differentiate the private and public). This private portion of the water line will consist of private fire system loop extend around the site to provide service to proposed buildings G-100, H-100, J-100, N-100, 1040, 1010, and 1005. The public loop will have double check detector assemblies located at both looped connections to the public system. Fire hydrants and FDC's have been placed around the proposed buildings for fire protection. All new buildings have been proposed as with fire sprinkler systems.

The domestic water for F-100 and G-100 will be served from new public meters. The remainder to the proposed building will be served from the proposed public meter located north of the existing Michael's and a 4" domestic line extended through the site.

SECTION 74.620 SANITARY SEWER SERVICE.

- (1) Sanitary sewer lines shall be installed to serve each property in accordance with the Public Works Construction Code. Sanitary sewer construction plans and calculations shall be submitted to the City Engineer for review and approval prior to construction.
- (2) If there are undeveloped properties adjacent to the proposed development site which can be served by the gravity sewer system on the proposed development site, the applicant shall extend public sanitary sewer lines to the common boundary line with these properties. The lines shall be sized to convey flows to include all future development from all up stream areas that can be expected to drain through the lines on the site, in accordance with the City's Sanitary Sewer System Master Plan, TDC Chapter 13. [Ord. 933-94, § 60, 11/28/94]

Response: All sanitary water will be conveyed through an on-site sanitary sewer system as shown in Exhibit O – Sheets C5.0 - 5.2. The proposed sanitary sewer system will reroute a portion of the public sewer line with a 15 foot easement to ensure sanitary service to the property in the southeast corner of the site and the acquired ODOT land (Proposed Building F-100, G-100, and H-100). A proposed main private sanitary line will serve proposed buildings J-100, N-100, 1005, 1010 and 1040 will run north of the proposed buildings and connect into the existing public sanitary sewer line. Grease interceptors will be located prior to the public sanitary sewer line connection for any proposed restaurant or building tenant requiring grease interceptors.

SECTION 74.630 STORM DRAINAGE SYSTEM.

- (1) Storm drainage lines shall be installed to serve each property in accordance with City standards. Storm drainage construction plans and calculations shall be submitted to the City Engineer for review and approval prior to construction.
- (2) The storm drainage calculations shall confirm that adequate capacity exists to serve the site. The discharge from the development shall be analyzed in accordance with the City's Storm and Surface Water Regulations.
- (3) If there are undeveloped properties adjacent to the proposed development site which can be served by the storm drainage system on the proposed development site, the applicant shall extend storm drainage lines to the common boundary line with these properties. The lines shall be sized to convey expected flows to include all future development from all up stream areas that will drain through the lines on the site, in accordance with the Tualatin Drainage Plan in TDC Chapter 14. [Ord. 933-94, § 61, 11/28/94; Ord. 952-95, § 2, 10/23/95]

Response: The existing stormwater system onsite is comprised of a public storm sewer mainline and multiple private collection laterals feeding into that public line. The public line is encompassed within a 15 foot public easement running just north of the existing retail buildings and then heading south to serve the property in the southeast corner. Treatment for the site provided by several Contech stormfilter catch basins and vaults structures sized per CWS standards prior to discharging

into the public lines. Additionally, Low Impact Development features have been added prior to the filter vaults for added pretreatment. Whereas these features are not required prior to stormfilter cartage treatment and will not be designed to the LIDA handbook standard, they will provide benefit by providing additional water quality and flow reduction.

The public line outfalls into the Tualatin River just north of the site. A Storm Layout is provided as Exhibit O – Sheets C4.0-4.2. The Applicant has also included a Stormwater Drainage Memo under Exhibit N that provides drainage calculations for water quality consistent with this requirement. As previously stated, the site is surrounded by public facilities, natural features or property already committed to development.

Low Impact Development (LID) stormwater facilities have been located throughout the site where feasible as detailed within sheets C4.0 through 4.2 of Exhibit O. Specifically these facilities have been located east and south of Building 1040. Site grading precludes the use of LID's within other landscape areas of the site. The proposed stormwater system is consistent with the Master Plan approval and conditions contained within.

SECTION 74.640 GRADING.

- (1) **Development sites shall be graded to minimize the impact of storm water runoff onto adjacent properties and to allow adjacent properties to drain as they did before the new development.**
- (2) **A development applicant shall submit a grading plan showing that all lots in all portions of the development will be served by gravity drainage from the building crawl spaces; and that this development will not affect the drainage on adjacent properties. The City Engineer may require the applicant to remove all excess material from the development site.**

Response: The Applicant has included a grading plan as part of this submittal (Exhibit O – C3.0- 3.2). The Applicant is proposing to re-grade the vast majority of the site in order to direct stormwater into appropriate basins for subsequent treatment. Proposed new grades on the site range from a low point of approximately 124 msl near the northwest corner of the site to a high point of approximately 137 msl near the eastern boundary of the site.

SECTION 74.650 WATER QUALITY, STORM WATER DETENTION AND EROSION CONTROL.

The applicant shall comply with the water quality, storm water detention and erosion control requirements in the Surface Water Management Ordinance. If required:

- (1) **On subdivision and partition development applications, prior to approval of the final plat, the applicant shall arrange to construct a permanent on-site water quality facility and storm water detention facility and submit a design and**

calculations indicating that the requirements of the Surface Water Management Ordinance will be satisfied and obtain a Stormwater Connection Permit from Clean Water Services; or

- (2) On all other development applications, prior to issuance of any building permit, the applicant shall arrange to construct a permanent on-site water quality facility and storm water detention facility and submit a design and calculations indicating that the requirements of the Surface Water Management Ordinance will be met and obtain a Stormwater Connection Permit from Clean Water Services.
- (3) For on-site private and regional non-residential public facilities, the applicant shall submit a stormwater facility agreement, which will include an operation and maintenance plan provided by the City, for the water quality facility for the City's review and approval. The applicant shall submit an erosion control plan prior to issuance of a Public Works Permit. No construction or disturbing of the site shall occur until the erosion control plan is approved by the City and the required measures are in place and approved by the City. [Ord. 952-95, § 3, 10/23/95; Ord. 1070-01, 4/9/01; Ord. 1327-11 §1; 6/27/11]

Response: The proposed project includes the construction of public and private storm sewer lines as shown in Exhibit O – Sheet C6.0. All on-site surface water will be captured, conveyed and treated through an on-site stormwater system before discharging into the public system. Public storm lines have been designed for the Street "A" and SW Seneca Street extension with treatment from Contech stormfilter structures. Additionally, a public storm line with a 15-foot easement has been proposed behind the proposed retail buildings (1005, 1010, and 1040). The public line then runs south to serve the property in the southeast corner of the site and the acquired ODOT land (Proposed building F-100). A private storm line will be extended to the north for connections to proposed buildings G-100, H-100, J-100 and N-100. The storm service for existing buildings "A", "B", and "C" will remain in place, but will be retrofit with Contech stormfilter structures to treat the existing impervious area.

The remainder of the site will be captured in sumped catch basins and conveyed to Contech stormfilter structures. Sumped catch basins and Contech stormfilter structures are an approved pretreatment and treatment device per the City of Tualatin and Clean Water Services. A Storm Drainage Plan and Drainage Report included as Exhibit N was submitted as a part of the approved Master Plan. Operation and maintenance of the storm drainage areas will be the responsibility of Nyberg Rivers property management. The City found in the master plan decision that the Master Plan area shall use vegetative treatment of stormwater where feasible.

Low Impact Development (LID) stormwater facilities have been located throughout the site where feasible as detailed within sheets C4.0 through 4.2 of Exhibit O. Specifically these facilities have been located east and south of Building 1040. Site grading precludes the use of LID's within other landscape areas of the site. The proposed stormwater system is consistent with the Master Plan approval and conditions contained within.

SECTION 74.660 UNDERGROUND.

- (1) All utility lines including, but not limited to, those required for gas, electric, communication, lighting and cable television services and related facilities shall be placed underground. Surface-mounted transformers, surface-mounted connection boxes and meter cabinets may be placed above ground. Temporary utility service facilities, high capacity electric and communication feeder lines, and utility transmission lines operating at 50,000 volts or above may be placed above ground. The applicant shall make all necessary arrangements with all utility companies to provide the underground services. The City reserves the right to approve the location of all surface-mounted transformers.
- (2) Any existing overhead utilities may not be upgraded to serve any proposed development. If existing overhead utilities are not adequate to serve the proposed development, the applicant shall, at their own expense, provide an underground system. The applicant shall be responsible for obtaining any off-site deeds and/or easements necessary to provide utility service to this site; the deeds and/or easements shall be submitted to the City Engineer for acceptance by the City prior to issuance of the Public Works Permit.

Response: The Applicant is aware of this provision and will underground all utilities as required. Any surface mounted transformers or connection boxes will feature landscape or structural screening to limit visual impacts.

SECTION 74.670 EXISTING STRUCTURES.

- (1) Any existing structures requested to be retained by the applicant on a proposed development site shall be connected to all available City utilities at the expense of the applicant.
- (2) The applicant shall convert any existing overhead utilities serving existing structures to underground utilities, at the expense of the applicant.
- (3) The applicant shall be responsible for continuing all required street improvements adjacent to the existing structure, within the boundaries of the proposed development site.

Response: Several existing structures are proposed to be retained as a part of the Nyberg Rivers redevelopment. The Applicant will ensure that those structures are connected to all City utilities and that those utilities are placed underground. Proposed structures to be retained include Buildings A through D.

SECTION 74.705 STREET TREE REMOVAL PERMIT.

- (1) A person who desires to remove or destroy a tree, as defined in TDC 31.060, in or upon public right-of-way shall make application to the Operations Director on City forms.
- (2) The applicant must provide:

- (a) the applicant's name and contact information and if applicable that of the applicant's contractor;
 - (b) the number and species of all street trees the applicant desires to remove;
 - (c) a clear description of the street trees' the applicant desires to remove;
 - (d) the date of removal;
 - (e) the reason(s) for removal; and
 - (f) other information as the Operations Director deems necessary.
- (3) Upon the Operations Director approving the removal of a street tree, the applicant or designated contractor shall replace each removed tree on a one-for-one basis by fulfilling the following requirements:
- (a) Remove both the tree and stump prior to planting a replacement tree, or request the City to remove the tree and stump and pay the applicable fee(s) established in TDC 74.706; and
 - (b) Replace the removed tree by planting a species of street tree permitted by Schedule A of the TDC Chapter 74 within the time period specified in writing by the Operations Director; or, the applicant may request within sixty (60) days of the permit approval date that the City replace the street tree and pay the applicable fee(s) established in TDC 74.706. If an applicant opts for the City to plant the replacement tree, the Operations Department may plant the tree on its usual tree-planting schedule. Planting done by the applicant or designated contractor shall comply with all applicable TDC sections and any additional requirements imposed by the Operations Director.
 - (c) The applicant shall comply with all applicable TDC sections and additional requirements imposed by the Operations Director. The Operations Director may:
 - (d) waive the one-for-one replacement requirement if he or she determines that the replacement would:
 - (i) conflict with public improvements or utility facilities, including but not limited to fire hydrants, water meters and pipes, lighting fixtures, traffic control signs; private improvements or utility facilities – including but not limited to driveways and power, gas, telephone, cable television lines; or, minimum vision clearance;
 - (ii) interfere with the existing canopy of adjacent trees, the maturation of the crown of the proposed replacement tree, or both;

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

- (A) cause a conflict by planting trees too close to each other, hurting their health;
- (iii) limit the selection of species from Schedule A: and;
- (iv) direct how to plant replacement tree(s).
- (e) a person who fails to comply with TDC 74.705 shall pay an enforcement fee and a restoration fee to the City of Tualatin, as set forth in TDC 34.220(3), in addition to civil penalties in TDC 31.111. [Ord. 963-96, § 9, 6/24/96. Ord. 1079-01, § 2, 7/23/01; Ord. 1279-09 §3, 3/23/09]

Response: The Applicant has submitted Tree Removal Permit applications as necessary for the Nyberg Rivers redevelopment. Exhibit M and Exhibit O, Sheets – C2.0 through C2.5 identify all trees to remain and to be removed with the associated reason for removal if any additional street trees need to be removed in the future, the Applicant will comply with these standards. Proposed new street trees are included in the Landscape Planting Plan included with this application under Exhibit O – L1.0 through L1.10. Street trees are being removed to facilitate the extension of Street A to Lower Boones Ferry, the relocation of Seneca as well as the new right-turn lane that is proposed on Nyberg Street. A street tree at the corner of Martinazzi and Nyberg is proposed for removal as it interferes with the clear vision area.

SECTION 74.720 PROTECTION OF TREES DURING CONSTRUCTION.

- (1) During the erection, repair, alteration or removal of a building or structure, it is unlawful for the person in charge of such erection, repair, alteration or removal to leave a tree in or upon a public right-of-way in the vicinity of the building or structure without a good and sufficient guard or protectors to prevent injury to the tree arising out of or by reason of such erection, repair, alteration or removal.
- (2) Excavations and driveways shall not be placed within six feet of a tree in or upon a public right-of-way without written permission from the City Engineer. During excavation or construction, the person shall guard the tree within six feet and all building material or other debris shall be kept at least four feet from any tree. [Ord. 963-96, § 9, 6/24/96]

Response: The Applicant is aware of the requirements for tree protection during construction. Proper protection is shown on the Grading Plan submitted as Exhibit O – C3.0 through C3.2 with this ARB application.

SECTION 74.765 STREET TREE SPECIES AND PLANTING LOCATIONS.

All trees, plants or shrubs planted in the right-of-way of the City shall conform in species and location and in accordance with the street tree plan in Schedule A. If the Operations Director determines that none of the species in Schedule A is appropriate or finds appropriate a species not listed, the Director may substitute an unlisted species. [Ord. 963-96, § 9, 6/24/96; Ord. 1279-09 §7, 3/23/09]

Formatted: Font: 9.5 pt
Formatted: Font: 9.5 pt

Response: The Applicant has presented a landscape plan that includes approved trees from the Schedule A: Street Tree Species list. As included under Exhibit O – Sheets L1.0 through L1.10, the proposed Landscape Planting Plan includes a wide variety of approved trees including Oak, Hawthorne, Cedar, and Ash throughout the street frontage and interior landscape areas.

TDC 75: ACCESS MANAGEMENT ON ARTERIAL STREETS

SECTION 75.050 APPROVAL PROCESS FOR ACCESS ONTO ARTERIALS, AND APPEAL PROVISIONS.

- (1) All requests for access onto arterials shall be reviewed by the City Engineer and follow the process described in TDC 31.074 through TDC 31.078 unless it is processed in conjunction with an application requiring a public hearing by the City Council. Based on provisions of this chapter and of the procedure described in TDC 31.074 through TDC 31.078, the City Engineer shall approve, approve with conditions, or reject the request for access in writing, stating the reasons for his or her decision.
- (2) Notice of the City Engineer's decision shall be distributed in accordance with TDC 31.074. The applicant shall be responsible for preparing the list of property owners within the notification area in the manner provided by TDC 31.071. The City Engineer's decision shall be final 14 calendar days after the date the notice of the decision is distributed unless within the 14 calendar the City Engineer receives a request for review of the decision. Requests for review shall be submitted in accordance with TDC 31.076 and a hearing conducted in accordance with TDC 31.077. [§75.05(3) Re-pealed by Ord. 743-88, §29 & 34, 3/28/88; Ord. 982-97, §6, 8/4/97; Ord. 96-07, 5/12/97; Ord. 1096-02 §38, 1/28/02]

Response: Although this section sets out only an approval process and not a criterion, the proposed Nyberg Rivers Site Plan utilizes an existing access point onto SW Nyberg Street. Based on input received from ODOT, a 10-foot wide maintenance access easement along the new Nyberg Street right-of-way is required and shown on the Site Plan, Sheet C1.1 under Exhibit O. Also, a 15-foot access easement is shown from the main entrance off Nyberg Street to connect to the ODOT maintenance easement and the (6) tax lots that currently use the existing access road. The Applicant is also proposing to remove an existing access point on Nyberg Street (75th Street) as well as two driveways that are located along Martinazzi. The Applicant is providing an easement for future connection to Street "A" to allow for future access management along Boones Ferry Road. The Applicant is also proposing that the connection from Street "A" to Boones Ferry Road be constructed as a right-in/right-out improvement consistent with these requirements. It should be noted that no curb extensions are proposed for Street "A", as no on-street parking is allowed along Street "A". As noted in the TIA provided as Exhibit L, several transportation improvements are proposed that will work to enhance access management and vehicle circulation and efficiency. Those findings are again incorporated herein by reference. Most notably, the primary access for the site is from a new minor collector, Loop Road that will serve all uses within the shopping center.

SECTION 75.060 EXISTING DRIVEWAYS AND STREET INTERSECTIONS.

- (1) Existing driveways with access onto arterials on the date this chapter was originally adopted shall be allowed to remain. If additional development occurs on properties with existing driveways with access onto arterials then this chapter applies and the entire site shall be made to conform with the requirements of this chapter.
- (2) The City Engineer may restrict existing driveways and street intersections to right-in and right-out by construction of raised median barriers or other means. [Ord. 635-84, §48, 6/11/84; Ord. 982-97, §7, 8/4/97]

Response: The master plan comprehensively reviewed the driveway access points to the site. There the City found: At the intersection of collector or arterial streets, driveways needs to be located a minimum of 150 feet from the intersection. Several accesses are within 150 feet from either SW Boones Ferry Road or SW Nyberg Road, both Major Arterials. Access to the City staff parking lot and the access easement to Heron's Landing Apartments are approximately 140 feet and 110-feet away from SW Boones Ferry Road, respectively. Locating the City staff parking lot access farther south would require relocation of the cement block trash enclosure, therefore the location is acceptable. The Heron's Landing Apartments access is too close to SW Boones Ferry Road; therefore, it will need to be located farther south to match the location of the City staff access. The Applicant will need to locate the Heron's Landing Apartment access opposite the City staff parking lot access. Along the Nyberg Main Entry access to the east and west parking lots are approximately 120 feet from SW Nyberg Road; however left turns are restricted by a median, therefore the location is acceptable.

The City further decided that the best operational environment would be preserved by closure of the driveways south of City Hall and south of the Council Building. The attached Site Plan, Exhibit O, Sheets C1.0 through C1.2, demonstrates compliance with all of these requirements.

SECTION 75.070 NEW INTERSECTIONS.

Except as shown in TDC Chapter 11, Transportation, (Figures 11-1 and 11-3), all new intersections with arterials shall have a minimum spacing of ½ mile between intersections. [Ord. 635-84, §49, 6/11/84]

Response: The Applicant is proposing to provide a new extension, Street "A" and the Loop Road that will connect with Boones Ferry Road in the north and Nyberg Street in the south as depicted within the City's TSP. The proposed location of the connection was arrived at based on site distance, topography and the conceptual alignment depicted in the City's TSP. The master plan adopted this Loop Road alignment and intersection location with Boones Ferry at pages 11-30 of the master plan decision incorporated herein by reference.

SECTION 75.080 ALTERNATE ACCESS.

Except as provided in TDC 75.090 all properties which abut an arterial and another road or street shall not have access on the arterial. [Ord. 635-84, §50, 6/11/84]

Response: "Access Management Policy 2: Where a property abuts an arterial and another roadway, the access for the property shall be located on the other roadway, not the arterial."

This management policy is similar in wording to 75.080. The City found that the development as proposed satisfies this criteria. The master plan found the following:

First, the Loop Road is a required component of the Central Urban Renewal Master Plan, with its location within the site subject to modification. Section 75.120, which "describes in detail the freeways and arterials . . . with respect to access" clarifies that the existing intersection on Nyberg is intended to serve Urban Renewal Area Block 2 to the north of Nyberg and the Fred Meyer property to the south of Nyberg. 75.120(5). That section provides "On the south side between Fred Meyer and I-5 any development shall be served by the Fred Meyer driveway Tax Lot 2S1 24CA 200 or Urban Renewal Area Block 6) aligned with the Urban Renewal Area Block 2 driveway on the north side and shall not be granted any access to Nyberg Street. No additional driveways will be allowed." Further, as detailed in these findings and incorporated herein by reference, the Loop Road is a designated minor collector and is designed under this proposal to the minor collector standards as contemplated by the Urban Renewal Plan. The minor collector runs through the site and connects to the arterials that surround the site. Each of the properties within the site will have access to the minor collector and from the minor collector to the surrounding arterials. Intersections between arterials and collectors are not only encouraged by the code they are a necessary component of the street system. The Loop Road as a minor collector is a public road that with public access. Thus, the development takes access off of the minor collector.

The master plan area is also comprised of several separate lots. The City Council concluded that the reference to "Property" in TDC 11.630(5)(a)(ii) refers to each of the underlying lots within the Master Plan area. Several of the individual lots have frontage solely on SW Nyberg Street or have no street frontage whatsoever. For example, Tax Lot 2100, which comprises the K-Mart store and which will include the Loop Road has frontage solely along an arterial, SW Nyberg Street. Because Tax Lot 2100 abuts an arterial but does not abut another roadway, TDC 11.630(5)(a)(ii) does not apply and does not require access to Tax Lot 2100 be taken from the non-arterial.

Accordingly, because the Loop Road is a public minor collector and each of the properties within the project have access onto the minor collector, the proposal satisfies TDC 11.630(5)(a)(ii) and 75.080. Even if the Loop Road were a private road, the proposal still satisfies this criterion because each property within the site is evaluated individually under this section.

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

SECTION 75.090 INTERIM ACCESS.

When a property abuts a freeway, expressway or arterial and a future street shown on Map 75-1, or abuts or bisects the property, the City Engineer may approve an interim access on the arterial subject to the following conditions:

Response: The Applicant is not seeking interim or temporary access onto any arterial roads. Thus this criterion does not apply.

SECTION 75.100 EXCEPTIONS.

If the City Engineer finds that it is physically impossible for a property to receive access from any other street or road than an arterial as defined in TDC 75.030 and that the property cannot physically be served by any new street as shown on Map 75-1 or any logical extension of or addition thereto, the City Engineer may grant a permanent access directly to an arterial. In doing so the City Engineer may impose conditions on the construction of said access including, but not limited to:

- (1) Dedication of additional right-of-way on the arterial.
- (2) Creation of a joint access.
- (3) Construction of left turn lanes.
- (4) Construction of right turn lanes.
- (5) Installation of traffic signals.
- (6) Limitation of access to right turn in, right turn out by construction of raised median barriers or other means. [Ord. 635-84, §52, 6/11/84]

Response: The Applicant is not currently seeking an arterial access exception.

SECTION 75.110 NEW STREETS.

- (1) New streets designed to serve as alternatives to direct, parcel by parcel, access onto arterials are shown on Map 75-1. These streets are shown as corridors with the exact location determined through the partition, subdivision, public works permit or Architectural Review process. Unless modified by the City Council by the procedure set out below, these streets will be the only new intersections with arterials in the City. See map for changes
- (2) Specific alignment of a new street may be altered by the City Engineer upon finding that the street, in the proposed alignment, will carry out the objectives of this chapter to the same, or a greater degree as the described alignment, that access to adjacent and nearby properties is as adequately maintained and that the revised alignment will result in a segment of the Tualatin road system which is reasonable and logical.
- (3) The City Council may include additional streets on Map 75-1 through the plan amendment procedure. In addition to other required findings, the City Council must find that the addition is necessary to implement the objectives of this chapter. [Ord. 635-84, §53, 6/11/84; Ord. 743-88, §31, 3/28/88; Ord. 975-97, §3, 5/12/97; Ord. 1023-99, §11, 6/28/99]

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

Response: The Applicant is proposing to provide a new extension, the Loop Road connecting Street "A", Boones Ferry Road and Nyberg Street as depicted within the City's TSP. The proposed location of the connection was arrived at based on site distance, topography and the conceptual alignment depicted in the City's TSP. Consistent with these criteria, the streets on the TSP are shown as corridors only with the exact location determined through public works or architectural review process. The applicant incorporates by reference the findings above in this narrative addressing the location, design and function of Street A and incorporating the master plan findings on the same.

SECTION 75.120 EXISTING STREETS.

The following list describes in detail the freeways, expressways and arterials as defined in TDC 75.030 with respect to access. Recommendations are made for future changes in accesses and location of future accesses. These recommendations are examples of possible solutions and shall not be construed as limiting the City's authority to change or impose different conditions if additional studies result in different recommendations from those listed below.

S.W. NYBERG STREET

Tualatin-Sherwood Road to 65th Avenue:

On the south side between Fred Meyer and I-5 Freeway any development shall be served by the Fred Meyer driveway aligned with the K-Mart driveway on the north side and shall not be granted any access to Nyberg Street.

Response: The proposed redevelopment at Nyberg Rivers will utilize the existing Fred Meyer/K-Mart intersection to provide primary access into the Nyberg Rivers redevelopment site in compliance with this criterion. The Loop Road will be improved to a minor collector pursuant to its design and designation as a public minor collector. Particular engineering work was performed to ensure that the minor collector was aligned with the driveway entrance to Fred Meyer. This alignment and the design of the minor collector are illustrated in Exhibit A under cross-section A-A.

BOONES FERRY ROAD

North City Limits to Tualatin River:

All existing driveways will remain. No new driveways will be permitted.

Tualatin River to Tualatin Road:

Between the River and Martinazzi Avenue on the south side, the access for the apartments (2S1 24B/1500) will be closed and converted over to the Loop Road. The Loop Road may have a right-in, right-out connection to Boones Ferry Road between the river and Martinazzi Avenue. On the south side of Boones Ferry Road between Martinazzi Avenue and the driveway for the White Lot (old Lot C), any development or redevelopment shall take access over the White Lot or from Martinazzi Avenue. Between the White lot and 84th Avenue, all properties shall have combined accesses resulting in only one access on Boones Ferry Road. Between 84th Avenue and Tualatin Road on the south side, any redevelopment shall result in no driveways onto Boones Ferry Road and access shall be taken from 84th Avenue or Seneca Street.

Response: The cross section under Exhibit A and Site Plan (Exhibit O- Sheets C1.0 through C1.2), show compliance with this standard. The Loop Road connects with Boones Ferry and provides future access to the apartments. An access easement from Street "A" is proposed to serve the high-density residential apartments located in the northwest portion of Nyberg Rivers. This access easement will provide access onto the future Loop Road, which will provide right-in, right-out access onto Boones Ferry Road. These connections, design and function were also approved as part of the master plan and are in compliance with the conditions or approval established at pages 14-16 of the master plan decision, incorporated herein by Exhibit A containing the City approved cross sections of Street A, City Parking Lot, and Heron's Landing.

MARTINAZZI AVENUE

Boones Ferry Road to Seneca Street:

On the west side, any redevelopment on the Doyle (old Silvey) property (2S1 24BC/1500, 1503) or the Halstin (old post office property) (2S1 24BC/1502) shall result in combining these two driveways into one driveway on Martinazzi Avenue, or the Halstin property shall take access from the White public parking lot (old Lot C) to Boones Ferry Road. On the east side the existing driveway shall be removed and access shall be taken off of the Loop Road.

Seneca Street to Nyberg Street:

No driveways shall be permitted. The raised center median prohibiting left turns in this area shall remain until driveways are removed. On the west side the Wells Fargo driveway shall be removed and access taken from Seneca Street or Nyberg Street. On the east side the driveway for 2S114B/2000 shall be removed and access taken from the Loop Road or Nyberg Street.

Nyberg Street to Tualatin-Sherwood Road:

There shall be no access to Martinazzi Avenue.

Response: There are two existing driveways on Seneca Street. The driveway access to Council Chambers will be preserved only until such time as the Seneca Street extension is constructed. At that time the driveway will be removed under this criterion. The other existing driveway located south of Seneca and between Seneca and Nyberg will be closed with this application in conformance with this requirement. No new driveways are proposed along any of the targeted frontages.

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

TDC 50: OFFICE COMMERCIAL PLANNING DISTRICT (CO)

SECTION 50.020 PERMITTED USES.

No building, structure or land shall be used in this district except for the following uses when conducted wholly within a completely enclosed building, except for utility facilities and wireless communication facilities, and provided retail uses on land designated Employment Area, Corridor or Industrial Area on Map 9-4 shall not be greater than 60,000 square feet of gross floor area per building or business:

- (1) Offices, studios or clinics of accountants, architects, artists, attorneys, authors, dentists, designers, investment counselors, landscape architects, management consultants, and physicians or other practitioners of the healing arts.
- (2) Offices of administrative, editorial, educational, financial, governmental, insurance, real estate, religious, research, scientific or statistical organizations.
- (3) Health or fitness facility as defined in TDC 31.060, with indoor operation only.
- (4) Greenways, including but not limited to bike and pedestrian paths and interpretive stations.
- (6) Parking lot, parking structure or underground parking.
- (11) Other uses of similar character, found by the Planning Director to meet the purpose of this district, as provided by TDC 31.070.
- (12) Transportation facilities and improvements. [Ord. 635-84 §16, 6/11/84; Ord. 668-85 §2, 6/10/85; Ord. 771-89 §2, 4/10/89; Ord. 824-91 §6, 2/11/91; Ord. 849-91 §16, 11/25/91; Ord. 920-94 §13, 4/11/94; Ord. 965-96 §38, 12/9/96; Ord. 991-98 §1, 2/23/98; Ord. 992-98 §1, 2/23/98; Ord. 1006-98 §1;7/13/98; Ord. 1026-99 §42, 8/9/99; Ord. 1103-02, 03/25/02]

Response: The buildings within the CO District contain uses that are permitted in the CO District. Proposed uses for these buildings include office or health/fitness facility use and a portion of a sporting goods store. The health and fitness and office uses are expressly permitted outright as listed above. The retail use within the CO portion of the Cabela's is a conditional use. That use has been approved by the City in the final decision Resolution No. 5164-13 CU 13-04, attached here as Exhibit A

CURD BLOCK 1 USES

Uses permitted in the Central Commercial Planning District are permitted as conditional uses.

Response: Within the CC district sporting goods stores are permitted uses. Consequently, on CURD Block 1, sporting goods stores are permitted as conditional uses. Pursuant to CUP 13-04, the City Council approved a sporting goods store as a conditional use on CURD Block 1. As a result, the proposed uses within the CO portion of the property are either outright permitted uses, or have previously been approved as conditional uses by the City Council.

SECTION 50.050 LOT SIZE.

Except for lots for public utility facilities, natural gas pumping stations and a wireless communication facility which shall be established through the Subdivision, Partition or Lot Line Adjustment process, the following requirements shall apply:

- (1) The minimum lot size shall be 10,000 square feet.
- (2) The minimum average lot width shall be 80 feet.
- (3) The minimum lot width at the street shall be 40 feet.
- (4) For flag lots, the minimum lot width at the street shall be sufficient to comply with at least the minimum access requirements contained in TDC 73.400(8) to (12).
- (5) The minimum lot width at the street shall be 40 feet on a cul-de-sac street. [Ord. 866-92, §13, 4/27/92; Ord. 965-96, §40, 12/9/96.; §50.055 Repealed by Ord. 862-92, §17, 3/23/92]

Response: The portion of the Nyberg Rivers site located in the CO District is located within a split-zoned lot approved by Property Line Adjustment PLA 13-03. PLA 13-03 consolidated three (3) lots into one (1) approximately 22.6 acres lot. This consolidated lot meets the minimum lot size and has an average lot width greater than 80 feet and a minimum lot width greater than 40 feet.

SECTION 50.060 SETBACK REQUIREMENTS.

- (1) **Front yard.** Except for townhouses whose set backs shall conform to the setback standards in the RH District, the minimum front yard setback shall be 20 feet, except where a fish and wildlife habitat area on the subject property is placed in a Tract and dedicated to the City at the City's option, dedicated in a manner approved by the City to a nonprofit conservation organization or is retained in private ownership by the developer, the decision authority may allow a reduction of up to 35% of the required front yard setback, as determined in the Architectural Review process, if as a result the buildings are farther away from fish and wildlife habitat areas.
- (2) **Side yard.** Except for townhouses whose setbacks and separation between buildings shall conform to the setback and separation standards in the RH District, and except for structures greater than 35 feet in height which shall have a setback of 30 feet when the subject side yard abuts a lot in the RL District and a setback of 20 to 30 feet as determined through the Architectural Review process when the subject side yard abuts a lot in a multifamily district, the side yard setback shall be zero to 15 feet, as determined through the Architectural Review process.
- (3) **Rear yard.** Except for townhouses whose setbacks and separation between buildings shall conform to the setback and separation standards in the RH District, and except for structures greater than 35 feet in height which shall have a setback of 30 feet when the subject rear yard abuts a lot in the RL District and a

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

setback of 20 to 30 feet as determined through the Architectural Review process when the subject side yard abuts a lot in a multifamily district, the rear yard setback shall be zero to 15 feet, as determined through the Architectural Review process.

- (4) Corner lot yards. Except for town-houses whose setbacks shall conform to the setback standards in the RH District, zero to 20 feet along each street frontage for a sufficient distance to provide adequate sight distance for vehicular and pedestrian traffic at an intersection, as determined through the Architectural Review process.
- (5) Except for townhouses whose set-backs shall conform to the setback standards in the RH District, off-street parking and vehicular circulation areas shall be set back a minimum of 5 feet from any public right-of-way or property line, except as approved through the Architectural Review process.
- (6) Except for townhouses which may construct a fence on the property line, no fence shall be constructed within 5 feet of a public right-of-way.

Response: There are two buildings in the CO District: building N-100 and a portion of building 1040. Both buildings are oriented towards the interior of the site facing the central parking area. Therefore, the area between the building and the central drive aisles and parking stalls would be considered the front yard setback. The locations of the buildings, as well as the setbacks, were approved as part of the Master Plan approval. Each of the approved setbacks conforms to the above standards as follows: As shown on Exhibit O, the front yard setback for both structures is well over 100 feet, and therefore meets the 20-foot minimum setback. As shown on Exhibit O, the side yard setback is well over 50 feet, which meets the minimum 20 to 30 foot setback. The rear yard setback is well over 60 feet, as shown on Exhibit O, which exceeds the 20 to 30-foot requirement of the zone. No buildings are proposed in the CO zone on corner lots, therefore, the corner lot setback does not apply. All parking and circulation areas are setback at least 5 feet from public right of ways within the CO zone. No fences are proposed within 5 feet of any public right of way.

SECTION 50.065 CENTRAL URBAN RENEWAL AREA--LOT SIZES.

Except for townhouses whose lot sizes shall conform to the lot size standards in the RH District, the minimum lot sizes in the Central Urban Renewal District are as described on Map 9-3. [Ord. 694-86 §8, 5/27/86; Ord. 1025-99 §29, 7/26/99; Ord. 1026-99 §45, 8/9/99; Ord. 1046-00 §6, 2/14/00]

Response: The entire Nyberg Rivers site is located within the Urban Renewal Area. According to Map 9-3 in the Central Urban Renewal Report, Urban Renewal Area Blocks 1, 2, 3 and a portion of 4 are located within the Nyberg Rivers site. Based on Map 9-3, the minimum lot size for Blocks 1, 2, 3 and 5 is 25,000 SF. There are five (5) existing lots within the Nyberg Rivers site. Two (2) are a result of PLA 13-03 and PLA 13-04. The smallest lot contains approximately 30,492 SF, well above the minimum lot requirement. A portion of the SW Nyberg Street right-of-way is also proposed as being part of the Nyberg Rivers development. If approved as a lot, it would contain approximately 30,000 SF.

SECTION 50.070 STRUCTURE HEIGHT.

- (1) Except for flagpoles displaying the flag of the United States of America, either alone or with the State of Oregon flag which shall not exceed 100 feet in height above grade, and except as provided by subsection (2) of this section, the maximum height of any structure in this district is 45 feet.
- (2) Maximum structure height for a wireless communication support structure and antennas located within 300 feet of the centerline of I-5 is 120 feet. [Ord. 792-90, §1, 1/8/90; Ord. 965-96, S§42, 12/9/96; Ord 974-97, §2, 5/12/97; Ord. 978-97, §1, 6/23/97; Ord. 1116-02, 08/26/2002]

Response: The Applicant is aware of the maximum structure heights within the CO District. Proposed building N-100 would have a maximum height of 38 feet. The portion of proposed building 1040 located in the CO District would have a maximum height of 28 feet. The proposed buildings would meet the district height requirements. For building elevations refer to Exhibit L.

SECTION 50.080 ACCESS.

All lots created after September 1, 1979, shall abut a public street, except secondary condominium lots, which shall conform to the access provisions in TDC 73.400 and TDC Chapter 75. Lots and tracts created to preserve wetlands, greenways, Natural Areas and Stormwater Quality Control Facilities identified by TDC Chapters 71, 72, Figure 3-4 of the Parks and Recreation Master Plan and the Surface Water Management Ordinance, TMC Chapter 3-5, as amended, respectively, or for the purpose of preserving park lands in accordance with the Parks and Recreation Master Plan, may not be required to abut a public street. [Ord. 872-92 §8, 6/29/92; Ord. 1025-99 §30, 7/26/99; Ord. 1026-99 §46, 8/9/99]

Response: No new lots are proposed as a part of this application; consequently, this standard does not apply in the context of Architectural Review. The lot resulting from the approval of PLA 13-03 abuts SW Nyberg Street, a public street. The proposed conservation area located at the northwestern corner of Nyberg Rivers, adjacent to the Tualatin River and including the shared pathway easement, may be established as a lot or tract to preserve the natural area.

TDC 53: CENTRAL COMMERCIAL PLANNING DISTRICT (CC)

SECTION 53.020 PERMITTED USES.

No building, structure or land shall be used except for the following uses when conducted wholly within a completely enclosed building, except for utility facilities and wireless communication facilities, and provided retail uses on land designated Employment Area, Corridor or Industrial Area on Map 9-4 shall not be greater than 60,000 square feet of gross floor area per building or business.

Response: All proposed uses in the CC District qualify as permitted uses in the CC District, excepting only outdoor storage and sales associated with the sporting goods store which constitutes a conditional use, subject to the standards of Chapter 32. The outdoor storage and sales component was approved by the City Council under CUP 13-04. Consequently, all uses proposed are either permitted outright in the CC zone or have previously been approved by the City Council. CUP 13-04 is attached as Exhibit A.

SECTION 53.060 LOT SIZES.

Except for lots for public utility facilities, natural gas pumping stations and wireless communication facilities which shall be established through the Subdivision, Partition or Lot Line Adjustment process, the following requirements shall apply:

- (1) The minimum lot area shall be 10,000 square feet.
- (2) The minimum average lot width shall be 75 feet.
- (3) The minimum lot width at the street shall be 40 feet.
- (4) For flag lots, the minimum lot width at the street shall be sufficient to comply with at least the minimum access requirements contained in TDC 73.400(8) to (12).
- (5) The minimum lot width at the street shall be 40 feet on a cul-de-sac street. [Ord. 866-92, §15, 4/27/92; Ord. 965-96, §48, 12/9/96]

Response: No new lots are proposed as a part of this application. There are four (4) lots located within the CC District on the site. Two (2) lots are existing and two (2) were approved recently (PLA 13-03 and PLA 13-04). The smallest lot contains approximately 52,272 SF. All lots exceed the minimum area, have an average lot width greater than 80 feet and a minimum lot width greater than 40 feet.

SECTION 53.070 CENTRAL URBAN RENEWAL AREA - LOT SIZES.

Except for lots for public utility facilities, natural gas pumping stations and wireless communication facilities which shall be established through the Subdivision, Partition or Lot Line Adjustment process, and excepting any lot in the Core Area Parking District where TDC 53.070(1)-(5) apply, the minimum lot size in the Central Urban Renewal District shall conform to the lot sizes described on Map 9-3:

- (1) Except for mixed use developments, and common-wall dwellings on separate lots:
 - (a) The minimum lot area shall be 5,000 square feet.

- (b) The minimum average lot width shall be 40 feet.
 - (c) The minimum lot width at the street shall be 40 feet.
 - (d) For flag lots, the minimum lot width at the street shall be sufficient to comply with at least the minimum access requirements in TDC 73.400(8) - (12).
 - (e) The minimum lot width at the street shall be 35 feet on a cul-de-sac street.
- (2) For mixed use developments, and common-wall dwellings on separate lots:
 - (a) Lot areas, widths and frontages shall be determined through the Architectural Review Process.
 - (b) Frontage on a public street shall not be required when access via easements is provided in accordance with TDC 73.400.
 - (3) The minimum lot width at the street shall be 40 feet.
 - (4) For flag lots, the minimum lot width at the street shall be sufficient to comply with at least the minimum access requirements in TDC 73.400(8) - (12).
 - (5) The minimum lot width at the street shall be 40 feet on a cul-de-sac street. [Ord. 635-84 §24, 6/11/84; Ord. 694-86 §6, 5/27/86; Ord. 872-92 §11, 6/29/92; Ord. 882-92 §7, 12/14/92; Ord. 965-96 §49, 12/9/96; Ord. 1026-99 §58, 8/9/99]

Response: Again, no new lots are proposed as part of the present Architectural Review application. The entire Nyberg Rivers site is located within the Urban Renewal Area. According to Map 9-3 in the Central Urban Renewal Report, Urban Renewal Area Blocks 1, 2, 3 and a portion of 4 are located within the Nyberg Rivers site. Based on Map 9-3, the minimum lot size for Blocks 1, 2, 3 and 5 is 5,000 SF. There are five (5) existing lots within the Nyberg Rivers site. Two (2) are a result of PLA 13-03 and PLA 13-04. The smallest lot contains approximately 30,492 SF, well above the minimum lot requirement. A portion of the SW Nyberg Street right-of-way is also proposed as being part of the Nyberg Rivers development, if approved as a lot, it would contain approximately 30,000 SF. All lots have an average lot width greater than 40 feet and a minimum lot width greater than 40 feet. To the extent that the minimum lot size standard applies to Architectural Review, the minimum lot standards have been met.

SECTION 53.080 SETBACK REQUIREMENTS.

- (1) Front yard. Except as provided by TDC 53.090(2)(a), zero to 20 feet, as determined through the Architectural Review process.
- (2) Side yard. Except as provided by TDC 53.090(2)(a), zero to 20 feet, as determined through the Architectural Review process.
- (3) Rear yard. Zero to 15 feet, as determined through the Architectural Review process.

Formatted: Font: 9.5 pt
Formatted: Font: 9.5 pt

- (4) Corner lot yards. Zero to 20 feet for a sufficient distance to provide adequate sight distance for vehicular and pedestrian traffic at an intersection, as determined through the Architectural Review process.
- (5) Off-street parking and vehicular circulation areas shall be set back a minimum of 5 feet from any public right-of-way or property line, except as approved through the Architectural Review process.
- (6) No fence shall be constructed within 5 feet of a public right-of-way, except that in residential and mixed use residential developments within the Central Design District the minimum fence setback shall be determined through Architectural Review, with no minimum requirement.
- (7) For residential garage doors facing a public street, the minimum setback shall be 20' from the right-of-way.
- (8) Setbacks for a wireless communication facility shall be established through the Architectural Review process, shall consider TDC 73.510, shall be a minimum of 5 feet, and shall be set back from an RL District, or an RML District with an approved small lot subdivision, no less than 175 feet for a monopole that is no more than 35 feet in height and the setback shall increase five feet for each one foot increase in height up to 80 feet in height, and the setback shall increase 10 feet for each one foot increase in height above 80 feet. [Ord. 643-84, §2, 9/10/84; Ord. 862-92, §27, 3/23/92; Ord. 882-92, §8, 12/14/92; Ord. 904-93, §24, 9/13/93; Ord. 965-96, §50, 12/9/96; Ord. 1098-02, 2/11/02]

Response: There are no previously approved Architectural Reviews for the Nyberg Rivers site that provide specific setback distances. The Master Plan approved a specific layout of all proposed buildings, with specifically identified setbacks. The current proposal is consistent with the approved Master Plan. Existing buildings located within lots that have remained unchanged during this application process are Building A, Building B, and Building C as shown on Exhibit L – C1.0. Because these buildings are existing, the setback standards do not apply. Existing building E-100 is located on the consolidated lot approved through PLA 13-03, which maintained or increased the existing setbacks. Buildings D-110, D-120, D-125, D-130, 1005, 1010 and 1030 share walls and effectively create one structure (see Exhibit L – C1.0). This structure is bisected by a property line running north-south along the wall shared by buildings 1005 and D-110. Buildings 1005 and D-110 are existing and are the only buildings located on the site with a zero-foot setback. Of the proposed buildings, the shortest setbacks are the rear setbacks for buildings G-100, H-100 and J-100 with 9 feet, 7 feet and 9 feet respectively. All remaining setbacks for new buildings would exceed the 20 foot maximum setback, however the specific location of building footprints was approved as part of the Master Plan process, detailed findings are included as Exhibit A. All buildings are oriented towards the interior of the site facing the central parking area. Therefore, the area between the building and the central drive aisles and parking stalls would be considered the front yard setback. All buildings feature a pedestrian accessway along the building frontage of at least 8-foot wide. And all off-street parking and vehicle circulation areas are set back at least 5-feet from any public right-of-way or property line.

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

SECTION 53.090 STRUCTURE HEIGHT.

- (1) Except for flagpoles displaying the flag of the United States of America, either alone or with the State of Oregon flag which shall not exceed 100 feet in height above grade, and except as provided in TDC 53.090(2), (3) and (4), the maximum height for a structure is 45 feet.
- (2) In the CC Planning District north of SW Boones Ferry Road and south of the Tualatin River, the maximum height for a structure is 125 feet, when approved by Conditional Use Permit pursuant to TDC Chapter 32 and subject to the following setback requirements:
 - (a) Front yard. Any structure south of Hedges Creek shall comply with the CC District setbacks and any structure north of Hedges Creek shall comply with the TDC Chapter 72 setbacks for Hedges Creek.
 - (b) Side yard. The minimum side yard setback shall be:
 - (i) For structures 45 feet or less in height, zero to 15 feet as determined through the Architectural Review process.
 - (ii) For structures greater than 45 feet, but less than 84 feet, the side yard setback shall be 30 feet for that portion of the structure greater than 45 feet and less than 84 feet in height.
 - (iii) For structures greater than 84 feet but less than or equal to 125 feet in height, the side yard setback shall be 45 feet for that portion of the building greater than 84 feet in height.
- (3) Maximum structure height for specified portions of the Central Urban Renewal Plan area is:
 - (a) 35 feet between the Tualatin Commons central water feature and the primary pedestrian corridor around the central water feature, except for architectural focal elements.
 - (b) Except as provided in TDC 53.090(3)(a), 75 feet in Block 13.
 - (c) Except as provided in TDC 53.090(3)(a), 60 feet in Blocks 1, 2, 3, 5, 14, 15, 16, 17, 18, 19, 20 and 22.
 - (d) 75 feet for architectural focal elements in Blocks 14, 17, 18 and 20.
- (4) Maximum structure height for a wireless communication support structure and antennas located within 300 feet of the centerline of I-5 is 120 feet. [Ord. 792-90 §2, 1/8/90; Ord. 882-92 §9, 12/14/92; Ord. 965-96 §51, 12/9/96; Ord. 1026-99 §59, 8/9/99; Ord. 1116-02, 8/26/02; Ord. 1109-02, 4/22/02]

Response:

Proposed Height

Maximum Height

Nyberg Rivers
Architectural Review

105

Cardno
Submitted September 13, 2013
Completeness Responses October 23, 2013

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

| | |
|---------------------------------------|-----|
| Building A – Existing | N/A |
| Building B – Existing | N/A |
| Building C – Existing | N/A |
| D-110 – 34 feet | |
| D-120 – 30 feet | |
| D-125 – 26 feet | |
| D-130 – 26 feet | |
| E-100 – Existing | |
| F-100 – 28 feet | |
| G-100 – Not a part of the application | |
| H-100 – Not a part of the application | |
| J-100 – 30 feet | |
| 1005 – 34 feet | |
| 1010 – 34 feet | |
| 1030 – 34 feet | |
| 1040 – 38 feet | |
| N-100 – 50.5 feet | |

SECTION 53.100 ACCESS.

Except as provided below, no lot shall be created without provision for access to the public right-of-way in accordance with TDC 73.400 and TDC Chapter 75. Such access may be provided by lot frontage on a public street, or via permanent access easement over one or more adjoining properties, creating uninterrupted vehicle and pedestrian access between the subject lot and the public right-of-way. Lots and tracts created to preserve wetlands, greenways, Natural Areas and Stormwater Quality Control Facilities identified by TDC Chapters 71, 72, Figure 3-4 of the Parks and Recreation Master Plan and the Surface Water Management Ordinance, TMC Chapter 3-5, as amended, respectively, or for the purpose of preserving park lands in accordance with the Parks and Recreation Master Plan, may not be required to abut a public street. [Ord. 872-92 §12, 6/29/92; Ord. 882-92 §10, 12/14/92; Ord. 979-97 §21, 7/14/97; Ord. 1026-99 §60, 8/9/99]

Response: No new lots are proposed in conjunction with Architectural Review. Several lots were recently consolidated pursuant to PLA 13-03 and PLA 13-04, resulting in

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

the consolidation of five (5) lots into two (2) lots. The consolidated lot approved by PLA 13-03 has frontage along SW Nyberg Street and Interstate 5. The consolidated lot approved by PLA 13-04 has frontage along Interstate 5 and access to SW Nyberg Street through the parking lot of the consolidated lot approved by PLA 13-03. SW Nyberg Street is a public street. Both consolidated lots take primary access from that public street in compliance with this criterion. The new Loop Road is also a public road and minor collector. The proposed natural area located at the northern end of Nyberg Rivers, adjacent to the Tualatin River and including the shared pathway easement will be established as a lot or tract to preserve the natural area.

TDC 70: FLOOD PLAIN DISTRICT

SECTION 70.010 PURPOSE.

It is the purpose of this chapter to promote the public health, safety, and general welfare, and to minimize public and private losses due to flood conditions in specific areas by provisions designed:

- (1) To protect human life and health;
- (2) To minimize expenditure of public money and costly flood control projects;
- (3) To minimize the need for rescue and relief efforts associated with flooding and generally undertaken at the expense of the general public;
- (4) To minimize prolonged business interruptions;
- (5) To minimize damage to public facilities and utilities such as water and gas mains; electric, telephone and sewer lines; streets; and bridges located in areas of special flood hazard;
- (6) To help to maintain a stable tax base by providing for the sound use and development of areas of special flood hazard so as to minimize future flood blight areas;
- (7) To ensure that potential buyers are notified that property is in an area of special flood hazard; and
- (8) To ensure that those who occupy the areas of special flood hazard assume responsibility for their actions.
- (9) Comply with Metro's Urban Growth Management Functional Plan, Title 3. [Ord. 1070-01 §9, 4/9/01; Ord. 1070-01, 04/09/01]

Response: No structural development is proposed within the 100-year floodplain along Tualatin River. The proposed shared pathway easement within the natural area, portions of the vehicle circulation area in the northwest corner of the site, portions of Street A and portions of the Seneca relocation will be within the floodplain. All cuts and fills within these areas have been designed to balance onsite so that there is no net increase in the amount of fill located within the floodplain. The proposed improvements will be designed consistent with these requirements.

The final engineering permitting process will assure that cuts and fills are balanced.

SECTION 70.020 METHODS OF REDUCING FLOOD LOSSES.

In order to accomplish its purposes, this chapter includes methods and provisions for:

- (1) Restricting or prohibiting uses that are dangerous to health, safety, and property due to water or erosion hazards, or that result in damaging increases in erosion or in flood heights or velocities;
- (2) Requiring that uses vulnerable to floods, including facilities that serve such uses, be protected against flood damage at the time of initial construction;
- (3) Controlling the alteration of natural flood plains, stream channels, and natural protective barriers, which help accommodate or channel flood waters;
- (4) Controlling filling, grading, dredging, and other development that may increase flood damage; and
- (5) Preventing or regulating the construction of flood barriers that will unnaturally divert flood waters or that may increase flood hazards in other areas.

Response: No structural development is proposed within the 100-year floodplain along Tualatin River. The proposed shared pathway easement within the natural area, portions of the vehicle circulation area in the northwest corner of the site, portions of Street A and portions of the Seneca relocation will be within the floodplain. All cuts and fills within these areas have been designed to balance onsite so that there is no net increase in the amount of fill located within the floodplain. The proposed improvements will be designed consistent with these requirements. The final engineering permitting process will assure that cuts and fills are balanced.

SECTION 70.040 LANDS TO WHICH THIS CHAPTER APPLIES.

This chapter shall apply to all areas of special flood hazards within the jurisdiction of the City of Tualatin.

Response: No structural development is proposed within the 100-year floodplain along Tualatin River. The proposed shared pathway easement within the natural area, portions of the vehicle circulation area in the northwest corner of the site, portions of Street A and portions of the Seneca relocation will be within the floodplain. All cuts and fills within these areas have been designed to balance onsite so that there is no net increase in the amount of fill located within the floodplain. The proposed improvements will be designed consistent with these requirements. The final engineering permitting process will assure that cuts and fills are balanced. (5) Review of Building Permits. Where elevation data is not available either through the Flood Insurance Study or from another authoritative source (TDC 70.140(2)), applications for buildings permits shall be reviewed to assure that proposed construction will be reasonably safe from flooding. The test of reasonableness is a local judgment and includes use of historical data, high water marks, photographs of past flooding, etc., where

available. Failure to elevate at least two feet above grade in these zones may result in higher insurance rates. [Ord. 717-87, §14, 4/27/87; Ord. 988-97, §10, 12/8/97; Ord. 1265-08 §4, 7/28/08.

Response: The applicant is aware of the provision, but no structural development is proposed within the 100-year floodplain along the Tualatin River. The proposed shared pathway easement within the natural area will be within the floodplain, but no structures are proposed.

III. CONCLUSION

The Nyberg Rivers ARB package represents a comprehensive and collaborative effort to create a vibrant center that provides a seamless extension of the Tualatin City Center. The primary commercial tenants will work to attract regional visitors to the City core in an effort to create a more vibrant and active City Center. The mix of uses will create a sense of place, with vibrancy present during all hours and days of the week. In addition, this project will provide pedestrian and bicycle amenities and linkages to the regional framework to encourage a more active and healthy option for visitors to the site. The proposed public improvements, when combined with the on-site pedestrian and landscape amenities, provide a safe and efficient network for multi-modal access to and through the site. As evidenced throughout this project narrative, Nyberg Rivers does meet or exceed any applicable development regulation and objective of the Tualatin Development Code as it relates to the Architectural Review process. The design elevations show a high quality material and color palette that links the existing buildings with the new buildings to create a cohesive and attractive design. Based on this evidence provided, the applicant requests Architectural Board Review and approval to proceed to building and site development.

Formatted: Font: 9.5 pt

Formatted: Font: 9.5 pt

Conditions of Approval Compliance Report

MP 13-01

Resolution No. 5163-13

Each condition of approval from the master plan MP 13-01 is listed below with a reference to how this Architectural Review narrative satisfies each of the conditions of approval. The condition of approval from MP 13-01 is listed in italics in order of its imposition under Resolution No. 5163-13 with a response in bold font.

A. The City Council finds it necessary to condition the Master Plan to limit the number of drive-thru facilities in the Master Plan to no more than four and designing any new or re-located drive-thru facilities so the service windows and service aisles are screened from public streets.

The AR site plan shows only four drive-thru facilities in compliance with this condition. See the Site Plan enclosed under Exhibit O, Sheets C1.0 through C1.2. The AR narrative at pages 16 and 17 demonstrate that the service windows and service aisles on the singular relocated drive-through are screened from public streets.

B. The Master Plan area and Nyberg Rivers site shall provide attractive and pedestrian-oriented features including accessways and pathways that will connect to existing and future residential development in the downtown area and specifically to the adjoining Heron's Landing Apartments property.

The AR site plan shows multiple pathways that connect to the adjoining Heron's Landing Apartments and the Tualatin downtown area. See the Site Plan enclosed under Exhibit O, Sheets C1.0 through C1.2. Sheet C1.0 shows both the shared pathway easement to the north of the property that provides pedestrian access to the natural area, the remainder of the Nyberg Rivers commercial center, as well as connectivity to Street 'A' and an additional shared pathway to connect to SW Seneca Street. Street 'A' connects to SW Boones Ferry Road, which then provides pedestrian connectivity to the downtown area. The proposed sidewalks on both side of SW Seneca Street will provide pedestrian access into the downtown area. The AR narrative at pages 13 through 16 demonstrate that the accessways and pathways will connect to Heron's Landing and the downtown area to the west.

C. Recreational equipment, apparel and sports outfitting sales are prohibited in areas identified as public gathering, multi-function open plaza and plaza seating with fire pit as identified in the Building Frontage landscape plan.

The conditional use exhibit included under Exhibit A with the ARB package, and originally submitted as a part of the Master Plan approval, showed potential outdoor sales areas along the Cabela's frontage. As shown on the AR Landscape Planting Plan

included under Exhibit O, Sheets L1.8A and L1.8B depict the proposed plaza along the Cabela's building frontage. The plaza seating and landscape amenities do not begin until the Cabela's (Building 1040) frontage recesses at the southwest corner of the building. Thus, the broom finished concrete areas shown on the landscape sheets are free and clear to serve the proposed outdoor sales use. The landscaping at the building façade on the eastern portion of the Cabela's frontage is also outside the proposed outdoor sales area. The AR narrative at pages 21 and 22 demonstrate that the outdoor sales areas do not conflict with the pedestrian plazas with enhanced landscape amenities.

D. A minimum of 12 feet of clear, unobstructed width for walkways or accessways through a plaza or along the building frontage between Building D1 and northeast corner of the public gathering, multi-function plaza seating with fire pit as identified in the Building Frontage landscape plan.

The AR landscape planting plan Sheets L1.7 and L1.8 display the walkway dimensions through the central plaza, with specific attention paid to access through the enhanced pedestrian plaza areas. A minimum of 12-foot clear, unobstructed width is shown throughout the plaza. site plan shows only four drive-thru facilities in compliance with this condition. See the Site Plan enclosed under Exhibit O, Sheets C1.0 through C1.2. The AR narrative at pages 15-16 and 21-22 provide responses pertaining to the 12-foot free and clear access through the central plaza.

E. The Truck Route designations from "Street A" and Seneca Street are removed.

Any reference to Street 'A' or Seneca Street as a designated truck route is removed from the ARB application package. The Transportation Plan submitted under this Exhibit A and referenced as Exhibit M has been updated to remove any reference to Street 'A' or Seneca Street as a designated truck route.

F. City Council finds the following transportation improvements are needed for the Master Plan to comply with Goal 5, and therefore imposes them as conditions of approval:

a. The Seneca Street extension to the Nyberg Rivers site with a signal at SW Martinazzi Avenue constructed to the standards of a Minor Collector Street. The time of construction will be determined through the public facilities decision process and is not anticipated or required to occur prior to removal of the Council Chambers building.

The AR site plan does show the proposed SW Seneca Street extension along with the proposed bicycle path, landscape strip, and detached sidewalk. See the Site Plan enclosed under Exhibit O, Sheets C1.0 through C1.2. However, as noted above, the "time of construction will be determined through the public facilities decision process". The AR narrative at page 68 notes this condition and the proposed timing for the SW Seneca Street extension.

b. A westbound right turn lane on SW Nyberg Road.

The AR site plan shows the proposed westbound right turn lane and the dedicated right-of-way needed for the additional turn lane. See the Site Plan enclosed under Exhibit O, Sheets C1.0 through C1.2, as well as Cross-Section G-G provided under Exhibit A. The AR narrative at page 69 discusses the proposed improvement to be provided by the applicant.

c. Two southbound left turn lanes and a shared through/right turn lane from the site's access onto SW Nyberg Road.

The AR site plan shows the two proposed southbound left turn lanes with a shared through/right turn lane for the central entry into the site via SW Nyberg Road. See the Site Plan enclosed under Exhibit O, Sheets C1.0 through C1.2, as well as Cross-Section A-A provided under Exhibit A. The AR narrative at page 20 discusses the proposed improvement to be provided by the applicant.

d. Two inbound receiving lanes; and

The AR site plan shows the two proposed inbound receiving lanes from SW Nyberg Road. See the Site Plan enclosed under Exhibit O, Sheets C1.0 through C1.2, as well as Cross-Section A-A provided under Exhibit A. The AR narrative at page 20 discusses the proposed improvement to be provided by the applicant.

e. The associated signal improvements at the main entrance.

The AR narrative at pages 19 and 79 discusses the proposed improvement to be provided by the applicant.

G. In addition, City Council finds the street cross-sections need to be modified to satisfy Goal 5 and are needed to serve the Master Plan area. The City Council approves the Master Plan cross sections with the following modifications:

a. Cross-section A-A:

A 4 to 7-foot planter strip on the east side with curb, streetlights, and trees

A 4-foot planter on the west side with curb, streetlights adjacent to the travel lanes, and groundcover and shrubs with a 14-foot shared path with tree wells

Three 12-foot southbound travel

lane Two northbound 12-foot travel

lanes

A center median consisting of an 18-inch concrete median, with striping on both sides for a total of 2.5-feet

The road shall be a public road.

The AR submittal package includes updated cross-sections under Exhibit A. Cross-section A-A has been updated to reflect the City Council request. These design details are also reflected on the Site Plan, Sheet C1.0 included as Exhibit O and an updated detail sheet xx to depict the proposed tree well design for the tree wells located within the 14-foot shared path. The AR narrative

at page 20 discusses the proposed improvements to the main entry to be provided by the applicant.

b. Cross-section B-B:

A 12-foot pedestrian walkway on the north side with tree wells

Two 13-foot travel lanes. 12 foot travel lanes are acceptable.

A 6-foot planter on the south side

A 5-foot sidewalk on the south side

The road shall be a public road.

The AR submittal package includes updated cross-sections under Exhibit A. Cross-section B-B has been updated to reflect the City Council request. These design details are also reflected on the Site Plan, Sheet C1.0 and the Landscape Planting Plan, Sheet 1.7, both included as Exhibit O. The AR narrative at pages 13-16 discusses the proposed improvement to be provided by the applicant.

c. Cross-section C-C:

A 10-foot wide pedestrian walkway on the east side with tree wells

17.5-foot angled parking on both sides

Two 14-foot travel lanes

A 4-foot sloped landscape area on the west side

A 12-foot multi-use path on the west side

The road shall be a public road.

The AR submittal package includes updated cross-sections under Exhibit A. Cross-section C-C has been updated to reflect the City Council request. These design details are also reflected on the Site Plan, Sheet C1.0 included as Exhibit O.

d. "Street A": Cross section D-D:

A 12-foot multi-use path on the west side

A 4-foot planter strip with curb, streetlights, and trees

Two 12-foot travel lanes

A 6-foot bike lane on the east side

A 5-foot sidewalk on the east side

The pork chop at the intersection of Boones Ferry Road will be mountable for emergency vehicles

The road shall be a public road.

The AR submittal package includes updated cross-sections under Exhibit A. Cross-section D-D has been updated to reflect the City Council request. It should also be noted that the Street "A" improvements do not include curb extensions, as no on-street parking is proposed along Street "A". The AR narrative at page 92 has been updated to reflect this clarification. These design details are also reflected on the Site Plan, Sheet C1.0 included as Exhibit O. The AR narrative at page 63 discusses the proposed improvement to be provided by the applicant.

e. *City Parking Lot/Heron's Landing/Access to "Street A" and intersection with the greenway:*

The accessway shown is 40-feet wide

The multiuse path crossing is located south of the

accessway The crossing will include striping and bump-outs

The Heron's Landing Apartment access easement opposite the City staff parking lot access.

A crosswalk on "Street A" adjacent to SW Boones Ferry Road

The road shall be a public road.

The AR submittal package includes a Site Plan, Sheet C1.0 included as Exhibit O, that reflects the requested updates to the City Parking Lot/Heron's Landing/Street 'A' area. The AR narrative at page 92 discusses the proposed improvement to be provided by the applicant.

f. *Nyberg Street between the entrance of the site and Martinazzi Avenue: Cross section F-F:*

A 4-6 foot planter strip with trees. This planter does not include curbs and streetlights, which are placed on the curb-tight sidewalk.

A 5-6-foot curb-tight sidewalk on the north side of Nyberg Road

A 6-foot bike lane

Two 11-foot westbound travel lanes

The north-south crosswalk across Nyberg Street will have a dedicated pedestrian/bicyclist-activated sequence

The road shall be a public road.

The AR submittal package includes updated cross-sections under Exhibit A. Cross-section F-F has been updated to reflect the City Council request. These design details are also reflected on the Site Plan, Sheet C1.0 included as Exhibit O. The AR narrative at page 77 discusses the proposed improvement to Nyberg Street to be provided by the applicant.

g. *Nyberg Street between the entrance of the site and I-5: Cross section G-G:*

A 5-foot wide bike lane between the westbound right-turn lane and the central travel lanes

A 7-foot wide sidewalk for pedestrian use on the north side of Nyberg Road

A 4-foot planter strip with curb, streetlights, and trees

A 15-foot westbound right-turn lane

No proposed changes to the existing west and east-bound turn lanes

The road shall be a public road.

A two foot landscape strip prior to a hand rail on top of a retaining wall, then a water quality pond

The AR submittal package includes updated cross-sections under Exhibit A. Cross-section G-G has been updated to reflect the City Council request. These design details are also reflected on the Site Plan, Sheet C1.1 included as Exhibit O. The AR narrative at page 77 discusses the proposed improvement along Nyberg Street to be provided by the applicant.

h. *Seneca Street and the signal at SW Martinazzi*

Avenue Two 12-foot travel lanes

One 14-foot center turn lane

Two 6-foot bike lanes

Two 8-foot parking strips

Two 6-foot planter strips with curbs, streetlights, and street

trees Two 6-foot sidewalks

The road shall be a public road.

These proposed design details for SW Seneca Street is shown on the Site Plan, Sheet C1.0 included as Exhibit O. The AR narrative at page 58 discusses the proposed design and improvements to Seneca Street to be provided by the applicant.

H. All shared pathways shall be open to the public.

All proposed shared pathways throughout the Nyberg Rivers commercial center will be open to the public.

I. New or relocated buildings on the Nyberg Rivers site shall have bicycle parking facilities.

Based on the shopping center land use designation, bicycle parking is required at a ratio of 0.50 spaces per 1,000 SF of gross floor area. The proposed building square footage for all buildings on-site is 293,559 SF, requiring 147 bicycle parking stalls. At least half of those stalls are required to be covered. The AR submittal package includes a Bicycle Parking Plan included with the Site Plan set under Exhibit O. As shown on the plan, bicycle parking areas are proposed along the building frontages for Buildings B, C, D, E and F and between Buildings K-100, J- 100, H-100 and G-100. Those spaces between buildings provide bicycle parking in close proximity to the buildings. The AR narrative at pages 52-55 discusses bicycle parking to be provided by the applicant.

J. The Master Plan area shall use vegetative treatment of stormwater where feasible.

Low Impact Development (LID) stormwater facilities have been located throughout the site where feasible, as detailed within sheets C4.0 through 4.2 of Exhibit O. Specifically these facilities have been located east and south of Building 1040. The AR narrative at page 86 discusses LID stormwater treatment to be provided by the applicant.

K. No increase in the 100-Year Floodplain associated with improvements to public "Street A" and SW Seneca Street.

No structural development is proposed within the 100-year floodplain along Tualatin River. While portions of Street A and the Seneca Street extension will be within the floodplain, all cuts and fills within these areas have been designed to balance onsite so that there is no net increase in the amount of fill located within the floodplain. The proposed improvements will be designed consistent with these requirements. The final engineering permitting process will assure that cuts and

fills are balanced. The AR narrative at pages 107-108 discusses floodplain management as proposed by the applicant.

L. There shall be additional windows and architectural features on each of the four sides of Buildings 1040, G-100, H-100, J-100 and N-100.

The AR submittal package includes updated building elevations under Exhibit O. The elevations for Buildings 1040, G-100, H-100, J-100 and N-100 do provide additional windows and architectural features on each of the four sides of the building. The AR narrative at page 32 discusses building elevation treatment to be provided by the applicant.

M. Building 1040 shall have variations in building height, a additional gabled roof feature, canopy feature, entry feature, dimensional wall feature such as columns or pilasters and projected entries, show larger window and entry areas and show diversity in the exterior wall design and amterial on all four sides of the buildings.

The AR submittal package includes updated building elevations, including revised elevations and perspectives for propsoed building 1040. The AR narrative at page 32 discusses building elevations treatment to be provided by the applicant.

N. The loading and service facilities for the existing Michaels (Building D2) and new Buildings 1005, 1010 and 1040 shall provide adequate visual and noise buffering for the benefit of nearby public areas and residential areas.

The AR submittal package displays loading and service facilities included with the Site Plan, Sheets C1.0 through C1.2 under Exhibit O. As shown on the plan, loading and service facilities are proposed at the back portion of the buildings. Landscape planting plan Sheets L1.4 and L1.5 show Red Sunset Maples and Armstrong Maples as trees to buffer the loading facilities from the neighboring residential zone and those pedestrians using the shared pathway through the natural area. The AR narrative at pages 35-36 discusses bicycle parking to be provided by the applicant.

O. If oversized vehicle parking stalls are occupy or replace standard parking stalls proposed in the Master Plan, the total number of parking stalls and the dimensions shall be sadjusted accordingly to reflect the revision.

The AR submittal package does not include a proposal for oversized vehicle parking. No adjsments have been made, this condition is not applicable to this review.

P. Trees planted in "diamond planters" shall achieve a growth that is a minimum of 66 % (2/3) of the 30 ft. mature tree height standard in TDC 73.360(7)(a-e) within 5 years of planting.

As noted on the Landscape Planting Legends and Notes, Sheet L1.0 under Exhibit O, a Tree Maturity note states that, "trees delivered to the site will range from 10 to 20-

feet at the time of installation, depending on species. Trees will vary in growth rate and form during the establishment period and should take approximately 10-15 years for all parking lot species to reach the required minimum height of 30-feet.”

Therefore, trees planted in the diamond planters shall achieve a growth that is a minimum of 20-feet within 5 years of planting. The applicant will work with the landscape contractor to select more mature trees for placement within the landscape diamonds to ensure that the trees achieve the required height within the 5 year window. A discussion of the tree planting methodology is summarized on pages 40-42 of the AR narrative.

Q. Trees planted in the “diamond planters” shall be monitored annually. The applicant, its successors or assigns, shall submit a report from a certified arborist that documents tree height, health of canopy, and size of trunk by November 1 of each year after planting.

As noted on the Landscape Planting Legends and Notes, Sheet L1.0 under Exhibit O, the *General Notes: Landscape Planting Plan* includes note “13.) Installation contractor shall maintain trees, shrubs, lawns and other plants for a period of one year (365 days) unless otherwise directed by the owner.” This note will be updated to include an annual monitoring requirement for the diamond planters. A discussion of the tree planting methodology is summarized on pages 40-42 of the AR narrative.

If the trees do not meet the performance requirement, then Applicant, its successors and assigns, must remedy the failure. Such remedy shall be up to and including rebuilding and expanding the planting area.

A note has been added to the General Notes located on the Landscape Planting Legends and Notes, Sheet L1.0 under Exhibit O. The note shall read, “If the trees do not meet the performance requirement, then Applicant, its successors and assigns, must remedy the failure. Such remedy shall be up to and including rebuilding and expanding the planting area.” A discussion of the tree planting methodology is summarized on pages 40-42 of the AR narrative.

R. Prior to development, a tree maintenance plan shall be established for all trees in Master Plan area where development occurs.

As noted on the Landscape Planting Legends and Notes, Sheet L1.0 under Exhibit O, the *General Notes: Landscape Planting Plan* includes note “13.) Installation contractor shall maintain trees, shrubs, lawns and other plants for a period of one year (365 days) unless otherwise directed by the owner.” This note will be updated to include an annual monitoring requirement for the diamond planters. Additionally,


a Landscape and Maintenance (L & M) Manual will be provided to the owner outlining the maintenance requirements for plantings on site. A copy of the manual will be provided to the City at the time of final approval. A discussion of the tree planting methodology is summarized on pages 40-42 of the AR narrative.

S. All trees on the former Nyberg House site (tax lot 2502), adjacent to Building C (Tax Lot 1602) and in the vicinity of the proposed Building N-100 shall be preserved and retained as reasonably feasible. Where tree preservation is not reasonably feasible, 3" caliper or 10-12 foot replacement tree plantings of a similar character shall be planted in the vicinity of where trees were removed on Tax Lot 2502.

The AR submittal package includes a Tree Preservation Site Plan. Sheet C2.2 under Exhibit O does include the proposed tree preservation and tree removal elements in the vicinity of the proposed Building N-100. All proposed trees within the proposed parking area and building location will be removed, while a note is included stating, "Tree anticipated to be removed, effort to be taken during construction to preserve trees." There are approximately 10 trees "clouded" on Sheet C2.2 that the applicant will attempt to preserve. The AR narrative at page 42 discusses tree preservation elements to be provided by the applicant. The applicant has included an exhibit entitled *Tree Mitigation* attached to this document that details the trees proposed for removal on near building C, N-100 and G-100. The applicant is mitigating those trees that are not located within a building footprint or within the associated parking field depicted within the master plan. These trees cannot be retained do to the need to grade the subject property for building N-100 and G-100 and have therefore been mitigated as detailed within the planting plan included within the plan set. The trees proposed for removal on Building C will be impacted when the existing curb is removed and replaced and will be mitigated.

T. Plant 15 additional Douglas Fir, Western Red Cedar, or other tall-maturing conifer tree plantings in the landscape plan for location on the site's eastern frontage along I-5.

The AR submittal package includes a Landscape Planting Plan under Exhibit O, Sheet L1.3 that addresses landscape treatment for the eastern portion of the site along I-5. Sheet L1.3 and the Tree Preservation Site Plan C2.1 show (7) existing Western Red Cedars and (1) Lodgepole Pine that will remain, primarily along the back of Building G-100. Proposed plantings include a dense mix of Ponderosa Pine, Western Juniper, Thornless Honeylocust, Toba Hawthorn and River Birch. The retention of the existing trees and the dense mix of proposed trees will achieve the intent of the City Council request. The AR narrative at page 42 discusses tree preservation elements to be provided by the applicant.



Nyberg Rivers

A-A- Nyberg Main Entry

DATE: 09-11-2013


TUALATIN, OREGON



0 10' 20'

SCALE IN FEET

**Exhibit 1
Attachment A-4**



Nyberg Rivers

B-B - Michaels Frontage

DATE: 09-11-2013


TUALATIN, OREGON



0 10' 20'

SCALE IN FEET

**Exhibit 1
Attachment A-4**



Nyberg Rivers

C-C - Retail Shop Frontage

DATE: 10-18-2013


TUALATIN, OREGON



0 10' 20'

SCALE IN FEET

**Exhibit 1
Attachment A-4**



Nyberg Rivers

D-D - Street "A"

DATE: 09-11-2013


TUALATIN, OREGON



0 10' 20'

SCALE IN FEET

Exhibit 1
Attachment A-4



Nyberg Rivers

E-E - Boones Ferry Road

DATE: 9-11-2013


TUALATIN, OREGON



0 10' 20'

SCALE IN FEET

**Exhibit 1
Attachment A-4**



Nyberg Rivers

F-F - Nyberg Road - Entrance to Martinazzi

DATE: 9-11-2013
TUALATIN, OREGON





Exhibit 1
Attachment A-4



Nyberg Rivers

G-G - Nyberg Road - I-5 to Eastern Entrance

DATE: 10-02-2013

TUALATIN, OREGON



0 10' 20'

SCALE IN FEET

EXHIBIT 1-7
Attachment A-4






Exhibit 4




Nyberg Rivers

Future Minor Collector "Loop Road"

As shown on the approved City of Tualatin TSP, February 2013

Tualatin, Oregon
 Exhibit 1
 Attachment A-6

SECTION 'A'



ENLARGEMENT 'A'





Exhibit K


Nyberg Rivers Enlargement 'A' Plan View and Section

LEGEND

- Primary Pedestrian Circulation Routes
- Shared Pathway Easement
- Future Bicycle Lanes (City)
- Future Bicycle Lanes (Developer)
- Existing Bicycle Lanes
- Art Walk (Existing)
- Master Plan Boundary
- Primary Development Area



PEDESTRIAN & BICYCLE PLAN




Nyberg Rivers

Entry Landscaping

CENTERCAL PROPERTIES, LLC
 TUALATIN, OREGON

Cardno
 SCALE 0 10 20 40
 DATE: June 24, 2013
 2119310



LEGEND

-  Outdoor Sales Area
-  Building Area within CO District



PORTLAND
 5415 SW WESTGATE DR, STE 100, PORTLAND, OR 97221
 TEL: (503) 419-2500 FAX: (503) 419-2600
 www.cardno.com

**Nyberg Rivers
 Conditional Use Exhibit**




CenterCal
 Tualatin, Oregon

PROJECT NO. 21198310
 DATE: 06/13/2013
 BY: RG
 SCALE: 1" = 80'
 SHEET NO. —


TREE MITIGATION EXHIBIT - TAX LOT 2700
 NYBERG RIVERS
 CENTRAL PROPERTIES
 TUALATIN, OREGON

PROJECT NO. 21198310
 DATE: 10/23/2013
 PEG
 BY: L-EX-01
 SHEET NO.



Attachment A-7
 Exhibit 1





6 EVERGREEN TREES AND 1 DECIDUOUS TREE ARE TO BE REMOVED AND MITIGATED FOR ON TAX LOT 1502. PLEASE REFERENCE A.R.B. PLAN SET SHEET L1.3 FOR MITIGATION TREE TYPE AND LOCATION.



Attachment A-7
Exhibit 1






7 DECIDUOUS TREES ARE TO BE REMOVED AND MITIGATED FOR ON TAX LOT 1502. PLEASE REFERENCE A.B. PLAN SET SHEET L1.3 FOR MITIGATION TREE TYPE AND LOCATION.




TREE MITIGATION EXHIBIT - NYBERG HOUSE
 NYBERG RIVERS
 CENTRAL PROPERTIES
 TUALATIN, OREGON

PROJECT NO. 21198310
 DATE: 10/23/2013
 PEG
 L-EX-03
 BY:
 SHEET NO.

Attachment A-7
 Exhibit 1



2 EVERGREEN TREES ARE TO BE REMOVED AND
 MITIGATED FOR ON TAX LOT 1602. PLEASE
 REFERENCE A.B. PLAN SET SHEET L1.3 FOR
 MITIGATION TREE TYPE AND LOCATION.




APPLICATION FOR ARCHITECTURAL REVIEW

| | |
|---|---|
| Direct Communication to | |
| Name: <u>Michael Cerbone - Cardno</u> | Title: <u>Planning Manager</u> |
| Address: <u>5415 SW Westgate Dr, Suite 100 Portland, OR 97221</u> | E-mail address: <u>michael.cerbone@cardno.com</u> |
| Phone Number: <u>(503) 419-2500</u> | Fax Number: |
| Applicant's Name: <u>CenterCal Properties, LLC</u> | E-mail address: <u>mkirk@centercal.com</u> |
| Address: <u>7455 SW Bridgeport Rd, Suite 205 Tigard, OR 97224</u> | |
| Phone Number: <u>(503) 968-8940</u> | Fax Number: |
| Applicant's Signature: <u><i>Michael Cerbone</i></u> | Date: <u>9/13/13</u> |
| Property Owner's Name: <u>Dean Macbale</u> | Phone Number: |
| Address: <u>10860 Beaverton-Hillsdale Hwy Beaverton, OR 97005</u> | |
| Property Owner's Signature: <u><i>Dean Macbale</i></u> | Date: <u>9-10-13</u> |
| (NOTE: Letter of authorization is required if not signed by owner.) | |
| Architect: <u>Tom Ventura - Mulvanny G2 Architecture</u> | E-mail address: <u>tom.ventura@mulvannyg2.com</u> |
| Address: <u>601 SW Second Ave, Suite 1200 Portland, OR 97204</u> | |
| Phone Number: <u>(503) 223-8030</u> | Fax Number: |
| Landscape Architect: <u>Pat Gaynor - Cardno</u> | E-mail address: <u>pat.gaynor@cardno.com</u> |
| Address: <u>5415 SW Westgate Dr, Suite 100 Portland, OR 97221</u> | |
| Phone Number: <u>(503) 419-2500</u> | Fax Number: |
| Engineer: <u>Jeff Shoemaker - Cardno</u> | E-mail address: <u>jeff.shoemaker@cardno.com</u> |
| Address: <u>5415 SW Westgate Dr, Suite 100 Portland, OR 97221</u> | |
| Phone Number: <u>(503) 419-2500</u> | Fax Number: |
| Project Title: <u>Nyberg Rivers</u> | |
| Project Address: <u>7500 SW Nyberg St</u> | |
| Brief Project Description: <u>ARB for 307,000 SF commercial center</u> | |
| Proposed Use: <u>Shopping center</u> | |
| VALUE OF IMPROVEMENTS: \$ | |
| AS THE PERSON RESPONSIBLE FOR THIS APPLICATION, I HEREBY ACKNOWLEDGE THAT I HAVE READ THIS APPLICATION AND STATE THAT THE INFORMATION ABOVE, ON THE FACT SHEET AND THE SURROUNDING PROPERTY OWNER MAILING LIST IS CORRECT. I AGREE TO COMPLY WITH ALL APPLICABLE CITY AND COUNTY ORDINANCES AND STATE LAWS REGULATING BUILDING CONSTRUCTION AND LAND USE. | |
| APPLICANT'S SIGNATURE <u><i>Michael Cerbone</i></u> | DATE <u>9/13/13</u> |

| | | |
|---|---|--|
| Case No. _____ | Date Received _____ | Application Complete as of _____ |
| Received by _____ | Receipt No. _____ | ARB hearing date (if applicable) _____ |
| Fee: complete review (\$111- \$4829) _____ | | Posting verification _____ |
| 9 copies of drawings (folded) _____ | 1 reproducible 8½ x 11" site, grading, LS, Public Facilities plan _____ | |
| 1 reproducible 8½" X 11" vicinity map _____ | Neighborhood / Developer meeting materials _____ | |

APPLICATION FOR ARCHITECTURAL REVIEW

| | |
|--|---|
| Direct Communication to | |
| Name: Michael Cerbone-- Cardno | Title: Planning Manager |
| Address: 5415 SW Westgate Dr, Suite 100 Portland, OR 97221 | E-mail address: michael.cerbone@cardno.com |
| Phone Number: (503) 419-2500 | Fax Number: |
| Applicant's Name: CenterCal Properties, LLC | E-mail address: mkirk@centercal.com |
| Address: 7455 SW Bridgeport Rd, Suite 205 Tigard, OR 97224 | |
| Phone Number: (503) 968-8940 | Fax Number: |
| Applicant's Signature: | Date: |
| Property Owner's Name: TUALA Northwest, LLC | Phone Number: (503) 799-8324 |
| Address: 5638 Dogwood Drive Lake Oswego, OR 97035 | |
| Property Owner's Signature: | Date: |
| (NOTE: Letter of authorization is required if not signed by owner.) | |
| Architect Tom Ventura - Mulvanny G2 Architecture | E-mail address: tom.ventura@mulvannyg2.com |
| Address: 601 SW Second Ave, Suite 1200 Portland, OR 97204 | |
| Phone Number: (503) 223-8030 | Fax Number: |
| Landscape Architect: Pat Gaynor - Cardno | E-mail address: pat.gaynor@cardno.com |
| Address: 5415 SW Westgate Dr, Suite 100 Portland, OR 97221 | |
| Phone Number: (503) 419-2500 | Fax Number: |
| Engineer: Jeff Shoemaker - Cardno | E-mail address: jeff.shoemaker@cardno.com |
| Address: 5415 SW Westgate Dr, Suite 100 Portland, OR 97221 | |
| Phone Number: (503) 419-2500 | Fax Number: |
| Project Title: Nyberg Rivers | |
| Project Address: 7500 SW Nyberg St | |
| Brief Project Description: ARB for 307,000 SF commercial center | |
| Proposed Use: Shopping center | |
| VALUE OF IMPROVEMENTS: \$ | |
| <p>AS THE PERSON RESPONSIBLE FOR THIS APPLICATION, I HEREBY ACKNOWLEDGE THAT I HAVE READ THIS APPLICATION AND STATE THAT THE INFORMATION ABOVE, ON THE FACT SHEET AND THE SURROUNDING PROPERTY OWNER MAILING LIST IS CORRECT. I AGREE TO COMPLY WITH ALL APPLICABLE CITY AND COUNTY ORDINANCES AND STATE LAWS REGULATING BUILDING CONSTRUCTION AND LAND USE.</p> | |
| APPLICANT'S SIGNATURE  | DATE 9/11/13 |

| | | |
|---|--|--|
| Case No. _____ | Date Received _____ | Application Complete as of _____ |
| Received by _____ | Receipt No. _____ | ARB hearing date (if applicable) _____ |
| Fee: complete review (\$111-\$4829) _____ | | Posting verification _____ |
| 9 copies of drawings (folded) _____ | 1 reproducible 8 1/2 x 11" site, grading, LS, Public Facilities plan _____ | |
| 1 reproducible 8 1/2 X 11" vicinity map _____ | Neighborhood / Developer meeting materials _____ | |



Oregon

John A. Kitzhaber, M.D., Governor

Department of Transportation

Right of Way Section

4040 Fairview Industrial Dr. SE MS-2

Salem, OR 97302-1142

Phone: (503) 986-3600

Fax: (503) 986-3625

Web : www.oregon.gov/odot/hwy/row

October 8, 2013

File: 17888

Clare L. Fuchs, Senior Planner
Planning - Community Development
City of Tualatin
18880 SW Martinazzi Ave.
Tualatin, OR 97062

Dear Ms. Fuchs:

As you requested, I am sending you the original of ODOT's letter of authorization for the Nyberg Rivers architectural review. Please let me know if you need anything further. You may contact me via e-mail at tamara.s.patrick@odot.state.or.us or by phone at (503) 731-8444.

Sincerely,

Tamara Patrick
Senior Property Agent

Enc.

c: Jean Paul Wardy, jwardy@centercal.com



Oregon

John A. Kitzhaber, M.D., Governor

Department of Transportation

Right of Way Section

4040 Fairview Industrial Dr. SE MS-2

Salem, OR 97302-1142

Phone: (503) 986-3600

Fax: (503) 986-3625

Web : www.oregon.gov/odot/hwy/row

September 10, 2013

Alice Cannon Rouyer
Assistant City Manager
18880 SW Martinazzi Ave.
Tualatin, Oregon 97062-7092

File: 17888

Dear Ms. Rouyer:

ODOT owns certain property along Nyberg Road in the northwest quadrant of the I-5 – Nyberg Road Interchange. Such property is currently used as an access road for adjacent property. CenterCal Properties, LLC (“Applicant”) desires to purchase a portion of this property and include it in the Nyberg Rivers redevelopment project. Applicant has included the ODOT property in its Application for Architectural Review. As a result, ODOT, as the current property owner, is required to consent to the filing of the application. This letter will serve as ODOT’s consent for Applicant to include ODOT’s property in such application, subject to the limitations discussed below.

This letter is merely consent for Applicant to include ODOT’s property in its Application for Architectural Review. It is not an approval of the application or any of the information contained therein. ODOT is not a co-applicant and shall not be deemed to be an applicant. This letter shall not in any way limit ODOT’s ability to make comment on or object to the contents of the application; and ODOT specifically reserves the right to do so. This letter is not a commitment by ODOT to sell any of its property.

Although ODOT is working to sell some of its property, there are many prerequisites to sale which may or may not be met. Thus, it is possible that a sale may not take place. ODOT is signing this letter as an accommodation to the Applicant. This letter shall not be interpreted as an approval of the proposed property boundary, an agreement to sell any property, nor a guaranty that any property will be available for sale to Applicant.

If you have any questions regarding this letter, please feel free to contact Tamara Patrick at 503-731-8444.

Sincerely,

Rick Crager
State Right of Way Manager

TP

PUBLIC NOTICE POSTING

As the applicant for the NYBERG RIVERS ARB
project, I hereby certify that on this day, September 16, 2013, four (4)
signs were posted on the subject property in accordance with the requirements
of the Tualatin Development Code and the Community Development Department -
Planning Division.

Applicant's Name: THATCH MOYLE
(PLEASE PRINT)

Applicant's Signature: 

Date: 9/17/2013

**Natural Resource Assessment
for the Nyberg Rivers
Commercial and Retail Development
in Tualatin, Oregon**

(Township 2 South, Range 1 West, Section 24A & 24B)


Prepared for

CenterCal Properties, LLC
7455 SW Bridgeport Road, Suite 205
Tigard, Oregon 97224

Prepared by

Pacific Habitat Services, Inc.
Wilsonville, Oregon 97070
(503) 570-0800
(503) 570-0855 FAX

March 14, 2013



**Natural Resource Assessment
for the Nyberg Rivers
Commercial and Retail Development
in Tualatin, Oregon**

(Township 2 South, Range 1 West, Section 24A & 24B)

Prepared for

Hank Murphy
CenterCal Properties, LLC
7455 SW Bridgeport Road, Suite 205
Tigard, Oregon 97224

Prepared by

Shawn Eisner
Pacific Habitat Services, Inc.
9450 SW Commerce Circle, Suite 180
Wilsonville, Oregon 97070
(503) 570-0800
(503) 570-0855 FAX
PHS Project Number: 5141

March 14, 2013

TABLE OF CONTENTS

| | <u>Page</u> |
|---|-------------|
| 1.0 INTRODUCTION..... | 1 |
| 2.0 EXISTING CONDITIONS | 1 |
| 3.0 DISCUSSION OF WATER QUALITY SENSITIVE AREAS..... | 1 |
| 4.0 VEGETATED CORRIDOR ASSESSMENT | 2 |
| 4.1 Vegetated Corridor Width Determination | 2 |
| 4.2 Vegetated Corridor Plant Communities | 2 |
| 4.3 Vegetated Corridor Plant Community Condition..... | 3 |
| 5.0 PROPOSED PROJECT | 3 |
| 5.1 Project Overview | 3 |
| 5.2 Vegetated Corridor Enhancements | 4 |
| 5.3 Vegetated Corridor Encroachments..... | 5 |
| 5.4 Proposed Vegetated Corridor Mitigation | 5 |
| 5.5 Alternative Analysis | 6 |
| APPENDIX A: Figures | |
| APPENDIX B: Nyberg II Wetland Determination Memo | |
| APPENDIX C: Vegetated Corridor Sample Points Table & Photodocumentation | |
| APPENDIX D: NRA Definitions and Methodology and References | |

1.0 INTRODUCTION

Pacific Habitat Services, Inc. (PHS) conducted a natural resource assessment for Nyberg Rivers, a proposed retail and commercial development project in Tualatin, Oregon. The project is located north of Nyberg Road, just west of I-5 in the 7400 to 7900 blocks of SW Nyberg Road in Tualatin, Oregon (Township 2 South, Range 1 West, Section 24A tax lots 2502, 2506, 2507, 2508 & 2700 and Section 24B tax lots 1601, 1602, 1900, 2000, 2001 & 2100). Figure 1 shows the approximate location of the nearly 29-acre site; all figures are in Appendix A. This report presents the definitions and the methodology used to assess the natural resources on the site, as well as proposed vegetated corridor encroachments, as required by CWS.

2.0 EXISTING CONDITIONS

The project site is bounded generally by the Tualatin River to the north; SW Martinazzi Avenue and adjoining development to the west; SW Nyberg Road to the south; and Interstate 5 to the east. It includes a mix of existing commercial and retail spaces; previously developed but currently unoccupied properties; as well as undeveloped grass and forest land. The undeveloped areas include three general categories of vegetative cover; forested areas west of I-5 and along the south bank of the Tualatin River; a swath of native vegetation enhancements approximately 125 feet wide that begin south of the Tualatin River; and fallow grassland, which lies between existing development and the forested and enhanced areas to the north and east. The forested and enhancement areas are overwhelmingly dominated by upland plant species, though tree and shrub species that prefer moist conditions, such as Oregon ash and western red cedar, are present within the riparian areas along the river.

South of the undeveloped grasslands the site is nearly fully paved. It includes numerous existing businesses, vacant buildings, a former building pad, and many acres of parking lot.

3.0 DISCUSSION OF WATER QUALITY SENSITIVE AREAS

The Natural Resource Assessment field work and data collection are a compilation of work completed in two phases. Initially, a wetland determination was completed on November 15, 2011. PHS returned to the site on March 5, 2013, to confirm the prior assessment and to collect data associated with existing vegetated corridors. These site visits have confirmed that the Tualatin River is the only sensitive area on or immediately adjoining the site. Appendix B includes a determination letter and data points from the November 2011 assessment that confirm this assessment.

The current work did not include confirming the edge of the Tualatin River. Its location was determined in 2005 when this site was utilized as an offsite mitigation area for Nyberg Woods, a commercial/retail development located east of I-5, just downstream from this site (see existing CWS file number 05-004283). It is presumed that the prior work that defined the edge of the river utilized the location of the 2 year surface water elevation, which has been calculated by Pacific Water Resources, for Watershed Management at Clean Water Services. The 2 year surface water elevation, as calculated by the model, is located just below 112 feet near the west end of the site and decreases slightly, to 111.4 at the I-5 Tualatin River Bridge at the east end of the site. The northern boundary of the vegetated corridor as shown on Figure 2 follows the 112 contour line.

4.0 VEGETATED CORRIDOR ASSESSMENT

4.1 Vegetated Corridor Width Determination

The location and widths of vegetated corridors on the site are shown on Figure 2. While slopes immediately along the Tualatin River exceed 25%, slopes a distance of 50 to 75 feet from the river are much flatter. As a result of slopes less than 25% within 50 feet, the standard corridor width of 125 feet for the Tualatin River will apply. This original width determination was made as part of another development project which utilized a portion of the vegetated corridor on this site as mitigation for offsite vegetated corridor encroachment. The vegetated corridor as shown on Figure 2 exceeds the 125 foot minimum for much of its length. This is the result of corridor expansion related to the previously mentioned offsite project.

4.2 Vegetated Corridor Plant Communities

The vegetated corridor south of the Tualatin River is comprised of three plant communities (Figure 2). A discussion of each community is included below. Vegetative sample sites were chosen at representative locations throughout the project area. A single table in Appendix C includes all vegetation data points, organized by community. Appendix C also includes photographs of each community.

Community A (102,624 square feet) includes that portion of the vegetated corridor that has seen previous enhancement. Enhancement in this area was tied to development on another property. The initial enhancement occurred in 2007. Prior to enhancement this area was a grass or grain field. Community A is dominated by native tree and shrub plantings at densities very near CWS current standards. The herbaceous layer lacks native vegetation and due to the fact that the tree saplings range in height from about 5 to 15 feet there is no tree canopy within the community. In general there are few invasive species, though Himalayan blackberry, Scotch broom, and thistles are all present.

Community B (14,677 square feet) includes the southern limits of the forested riparian area along the Tualatin River. Across the western portion of the site this community is generally 10 to 25 feet wide. Though the actual riparian area is about 40 feet wide, only the southern extent is located beyond the 2-year storm elevation and therefore outside of the defined sensitive area. Despite the narrow width of the riparian area, the tree canopy is quite dense, ranging from 85 to 100 percent and is composed almost entirely of native trees. The shrub layer is variable; open in some areas and more dense in others. The denser areas tend to be dominated by invasive species, such as Himalayan blackberry and Scotch broom. Where more open, snowberry, trailing blackberry, and tall Oregon grape are more common. Like the mid-story, ground cover is variable. In large areas English ivy dominates the understory and there are, as a result, only a few sword fern or grasses that rise above the ivy. Where ivy is lacking, and the area is not overrun with blackberries, there is a more diverse mix of grasses and forbs, though natives are not common. The transition from forested conditions in Community B to the assemblage of enhancement plantings and grasses in Community A is quite abrupt, the apparent result of vegetation management in the enhancement area.

Community C (90,220 square feet) encompasses that portion of the vegetated corridor east of Communities A and B. This area includes a mature stand of Douglas fir, with additional common species including big leaf maple and western red cedar. Other native and non-native trees, such as Oregon white oak, sweet cherry, and English hawthorn are present but represent a very small percentage of the overall community. Unlike Community A, which has moderate to dense shrub layer, this forested area is quite open. Shrubs are not common, and where present, are generally represented by small thickets or individual shrubs of Himalayan blackberry. Snowberry is present, as are tall Oregon grape and Indian plum but they are scattered or found in small groupings. Groundcover is a patchwork mosaic of English ivy, mixed non-native grasses, geranium species, and bare ground. Documented invasive species include Himalayan blackberry, English ivy, and a small area of reed canarygrass.

4.3 Vegetated Corridor Plant Community Condition

Table 1 shows the percent composition of native versus non- native species, and tree canopy cover in accordance with Clean Water Services’ standards. Appendix C includes a table of all species documented at each sample point. The table is followed by photodocumentation of each community.

Table 1. Summary of Plant Communities

| Corridor Condition | | Plant Communities | | |
|--------------------|--|--------------------------|-------------|-------------|
| | | A | B | C |
| Good | >80% cover of native plants, and >50% tree canopy | | 93% canopy | 88% canopy |
| Marginal | 50% - 80% cover of native plants, and 26-50% tree canopy | | | |
| Degraded | <50% cover of native plants, and ≤ 25% tree canopy | 38% natives 0% canopy | 48% natives | 48% natives |

The condition of the vegetated corridor is defined by the percentages of native species and canopy cover. As the enhancement area (Plant Community A) has not yet matured, the predominance of native vegetation is not enough to offset the predominance of non-native herbaceous species. As a result, this community remains in degraded condition, though based upon the presumption of continued plant survival is ‘on trajectory for good condition’. Communities B and C maintain good tree canopies, but there are few natives in the mid and ground story. This is due primarily to the high percentage of cover by non-native grasses and forbs, English ivy and/or Himalayan blackberry. As a result, each of these communities warrants an overall community condition of ‘marginal.’

5.0 PROPOSED PROJECT

5.1 Project Overview

The proposed project as shown on Figure 3 includes new construction as well as modifications to existing buildings and parking areas. The new development will also expand into currently undeveloped land behind (north of) the existing commercial area. Existing structures along

Nyberg Road and Martinazzi Avenue will remain, as well the Michael's craft store. The existing Kmart building will be removed to facilitate a new anchor store and expansion/modification of the existing parking areas. The development will also allow for additional building pads along the east and north east portions of the site. All of these elements are located south of the regulated vegetated corridor.

The applicant is proposing to provide an easement for the future construction of a pathway. A conceptual path alignment is shown on Figure 3, with anticipated encroachment totals shown on Figure 4. The final location of the path will be subject to review and approval by the City of Tualatin; the alignment as shown may need to be modified but is believed to be sufficient to determine project intent and to analyze and calculate vegetated corridor encroachments. Though the path will pass through previously enhanced as well as forested areas, it is the applicant's intent to allow for flexibility in the final alignment to avoid as much native vegetation in the previously enhanced area as possible. Within the forested area, the mature trees are quite far apart and it will be possible to avoid all but a few trees in the northeast corner, just west of an existing bridge. The applicant is proposing an easement to accommodate a future path through the vegetated corridor but wants it to have as little impact on existing vegetation as possible.

5.2 Vegetated Corridor Enhancements

Though the project includes future encroachment for an easement for a future pedestrian path system in the vegetated corridor, the path will largely be located in the central and outer portions of the vegetated corridor (see Section 5.0 below) and as a result, 67,133 square feet of corridor enhancement will occur per CWS standards. As the vegetated corridor is in excess of 50 feet wide, the 50 feet closest to the Tualatin River will be enhanced to meet good corridor condition (see Figure 4). This will include maintenance and limited plantings within the previously enhanced areas at the northern limits of Community A, as well as more significant efforts in Communities B and C along the Tualatin River. Though the timing of path construction in relation to the overall project is not known, vegetated corridor enhancement will occur concurrent with or immediately following development of the commercial and retail areas. Preceding the installation of plantings, all invasive species as identified by CWS will be removed. Species observed in one or more areas include Himalayan blackberry, English ivy, Scotch broom, reed canarygrass, as well as bull and Canada thistle.

Enhancement will be consistent with Clean Water Services' standards (refer to *Appendix A: Planting Requirements* of R&O 07-20). The overall goal will be to restore all plant communities to "good" condition, as required by Clean Water Services. Due to the overwhelmingly native tree canopy in Communities B and C, and the existing density of tree saplings in Community A, enhancement measures will focus on the establishment of a native shrub layer, with additional herbaceous plantings as well. A formal planting plan for on-site enhancements is not included with this report but will be provided for CWS review and approval concurrent with engineering review of the project.

5.3 Vegetated Corridor Encroachments

Though the vegetated corridor was utilized as mitigation of one form or another for a prior development, paths are being proposed across the site in order to line up with proposed paths east of the site, as well as to fulfill the City of Tualatin's strategy to develop a complete network of paths along the Tualatin River. The proposed path will be composed of concrete and will be 10 feet wide with one-foot shoulders on either side. The path will begin outside the vegetated corridor, near the west side of the site, and enter the corridor approximately 600 feet to the east. From its point of entry into the corridor, the path will approach the river at several locations but will remain at least 30 feet from the river. The path will also include sections that pass closer to the outer limits of the corridor where side paths will provide access to the main path. The western and central arterial paths will also be 10 feet wide with 1 foot shoulders, with the eastern path at 6 feet wide, including shoulders. North and east of the development the path will continue through the outer (southern) portion of the forested area, approaching the Tualatin River in the very northeast portion of the site where the path is proposed to pass beneath the existing I-5 Tualatin River Bridge and connect to additional offsite paths proposed in that area. In order to pass beneath the bridge, the path is required to approach the Tualatin River closer than is necessary for the remainder of the path. In this area it will be necessary for the path to be within 30 feet of the river. The combined area of all proposed path encroachments as described above is 18,832 square feet (0.43 acre). Mitigation for proposed encroachments is discussed in Section 5.4 below.

As all but the easternmost extent of the path is located beyond 30 feet from the Tualatin River, only that section near the river would not be considered an allowed use. This "non-allowed" section would therefore need to be examined and approved by CWS through a Tier 2 analysis. As the current path alignment is conceptual, the precise area of Tier 2 encroachment has not been identified, though it has been anticipated within this submittal (see Section 5.4 Alternatives Analysis).

5.4 Proposed Vegetated Corridor Mitigation

Much, if not all, of the existing vegetated corridor on the site has been utilized as mitigation for the previously mentioned project (CWS File Number 05-004283). As a result, the possibilities for onsite mitigation are diminished. Despite this limitation, the applicant is reviewing onsite mitigation options. The applicant also intends to work with the City of Tualatin to identify offsite mitigation opportunities. The applicant is looking to work with the City and CWS to identify mitigation options that best balance the needs of the project and allow for mitigation to occur in an area where the greatest water quality benefit can be found, whether the location be on- or off-site.

The location of the mitigation site in relation to the development site will be very important and if off-site mitigation is required, every attempt to provide mitigation within one-quarter mile of the development site will sought. If mitigation needs to occur at a greater distance, then mitigation will be provided at an increase ratio, as required by CWS regulations.

All mitigation will be consistent with Clean Water Services' standards (per Section 3.08 *Replacement Mitigation Standards*, and *Appendix A: Planting Requirements* of R&O 07-20). The overall goal will be to restore or create vegetated corridor to "good" condition.

5.4 Alternatives Analysis

As the entire vegetated corridor has already been utilized for vegetated corridor mitigation to one extent or another, avoiding existing corridor mitigation areas is not feasible. As the proposed path is required by the City of Tualatin, full avoidance of the vegetated corridor was not feasible. The applicant has sought to minimize encroachments of the path through its proposed placement. The only Tier 2 section of path is located in the northeast extent of the project area, where its proximity to the Tualatin River is necessary to pass beneath the existing bridge and access proposed paths to the east. As a result of this section of path, a Tier 2 Alternatives Analysis is required. The proposed project will meet all Tier 2 Alternative Analysis criteria; responses to the criteria are detailed below.

1. The proposed encroachment area is mitigated in accordance with Section 3.08.

Mitigation for 18,832 square feet (0.43 acre) of encroachment to the vegetated corridor for the easement for future path construction will be consistent with Clean Water Services' standards (per Section 3.08 *Replacement Mitigation Standards*, and *Appendix A: Planting Requirements* of R&O 07-20). The overall goal will be to restore or create vegetated corridor to "good" condition.

2. The replacement mitigation protects the functions and values of the Vegetated Corridor and Sensitive Area.

Mitigation for 18,832 square feet (0.43 acre) of encroachment to the vegetated corridor for path encroachments will be provided. Though a corridor mitigation plan has not been prepared, the applicant is committed to providing full mitigation for all encroachments at or above the standards required by CWS. Whether onsite or off, mitigation at the chosen site will focus on enhancement or restoration of conditions that protect adjoining sensitive areas and their regulated corridors.

3. Enhancement of the replacement area, if not already in Good Corridor Condition, and either the remaining Vegetated Corridor on the site or the first 50 feet of width closest to the resource, whichever is less, to a Good Corridor Condition.

The first 50 feet of vegetated corridor along the Tualatin River will be enhanced to good condition. This will include a portion of area that has seen prior enhancement, as well as riparian and upland forested areas. The total area of proposed enhancement will be 67,133 square feet (1.5 acres).

4. A District Stormwater Connection Permit is likely to be issued based on proposed plans.

The applicant reasonably expects to obtain a District Stormwater Connection Permit based on proposed plans for the project.

5. Location of development and site planning minimizes incursion into the Vegetated Corridor.

As the vegetated corridor on this site was determined as part of a prior development action, the current proposal places all new development, except for the pedestrian path, outside of the existing corridor. The path encroachments have been minimized to the extent practicable by keeping the path within allowed use areas of the corridor except where by necessity the path must approach the river to connect with proposed path sections east of the development site. The Tier 2 section of path is unavoidable, as the only other pedestrian option to areas east of I-5 is to route pedestrians south, back through the development, east over I-5 via Nyberg Road, and then north back through existing development and sensitive areas east of I-5; a distance of approximately three-quarters of a mile. As the path section east of I-5 has already been approved, the proposed route beneath the Tualatin River Bridge is the most straightforward connection to this section of path.

6. No practicable alternative to the location of the development exists that will not disturb the Sensitive Area or Vegetated Corridor.

As the intent of the path is to allow pedestrians an “off-street” alternative to access commercial and residential areas east of I-5, there are no development options that will not disturb the vegetated corridor.

As described above, the only alternative that avoids vegetated corridors is to require pedestrians to utilize existing and proposed sidewalks between the proposed development and existing development to the east. As the proposed project, as well as anticipated development east of I-5, will increase vehicular traffic in this area of Tualatin, a well-planned pedestrian alternative will encourage use of the path and perhaps an associated reduction in vehicular traffic.

7. The proposed encroachment provides public benefits.

The public benefit of vegetated corridor encroachment includes supporting City goals for increased pedestrian circulation via its ever growing network of paths along the Tualatin River. Increased pedestrian traffic should result in at least a localized reduction in vehicular traffic. It also increases the market for existing and future residential development east of I-5 because access to commercial and retail areas west of I-5 can be accessed without crossing vehicular traffic exiting and accessing I-5. Though a corridor mitigation plan has not been prepared, the applicant is committed to providing full mitigation for all encroachments at or above the standards required by CWS. In so doing, the mitigation area will be upholding CWS’ commitment to protecting water quality and the resources that depend upon clean water.

Appendix A

Figures





3/11/13

5141

FIGURE 1

Nyberg Rivers, a proposed commercial development west of I-5 in Tualatin, Oregon (Air photo base map provided by Cardno WRG, 2011).





FIGURE
2

Existing Conditions
Nyberg Rivers Commercial Retail Development- Tualatin, Oregon

Exhibit 1
Attachment D

Base map provided by CARDNO WRG.






Note:
Base Map provided by CARDNO WRG.

Proposed Development Plan
Nyberg Rivers Commercial Retail Development- Tualatin, Oregon

FIGURE
3

03-07-2013

Exhibit 1
Attachment D



Note:
Base map provided by CARDNO WRG.

Vegetated Corridor Encroachment and Necessary Enhancements
Nyberg Rivers Commercial Retail Development- Tualatin, Oregon

FIGURE
4

03-07-2013

Exhibit 1
Attachment D

Appendix B

Nyberg II Wetland Determination Memo





PACIFIC HABITAT SERVICES, INC

9450 SW Commerce Circle, Suite 180
Wilsonville, OR 97070

(800) 871-9333 • (503) 570-0800 • Fax (503) 570-0855

November 21, 2011

Kevin Russell
Cardno WRG
5415 SW Westgate Drive Suite 100
Portland, Oregon 97221

**Re: Nyberg II; Wetland Determination
PHS Project # 4921**

Kevin:

The properties within the project parcel were visited by biologists at Pacific Habitat Services, Inc. (PHS) on November 15, 2011. This memo and associated figure and data sheets are being provided as documentation of our work. Figure 1 includes the limits of the study area as well as the location of two data points that were collected to document typical conditions. Our work confirmed that the Tualatin River is the only sensitive areas (wetland or waterway) within the project parcel.

Existing Conditions

Pacific Habitat Services, Inc. (PHS) completed a wetland determination of the project parcel, which is bounded generally by the Tualatin River to the north, SW Martinazzi Ave and adjoining development to the west, SW Nyberg St to the south, and Interstate 5 to the east. The study area included both commercially developed properties, and undeveloped forest and grassland.

Though we did investigate existing vegetated areas immediately adjoining the project boundaries, as well as along parking lots and driveways, the focus of the determination was undeveloped areas in the northern portion of the study area. The undeveloped areas include three general categories of vegetative cover; forested areas west of I-5 and along the south bank of the Tualatin River; a swath of native vegetation enhancements approximately 125 feet wide that begin south of the Tualatin River; and fallow grassland, which lies between existing development and the forested and enhanced areas to the north.

The forested and enhancement areas were overwhelmingly dominated by upland plant species, though tree and shrub species that prefer moist conditions, such as Oregon ash and western red cedar, are present within the riparian areas along the river. Soils were well drained and there was no evidence of ponding or flooding. The only evidence of hydrology was near the northern tip of the study area, where the roadside ditch along I-5 enters a small PVC pipe at the base of the roadway embankment. It appears that the flow path to the pipe is constricted and periodic

stormwater discharge onto the site via overtopping of the shallow ditch may occur. Soils in this area suggested a history of disturbance.

The fallow grassland is dominated by two common turf grass species; tall fescue and creeping bentgrass. Though it is not uncommon to find each of these species in wetlands, they grow equally well in drier conditions. Though fallow, it appears that the grassland is regularly mowed. The soils throughout the grassland appear well drained and there was no evidence of ponding or seasonally saturated soil conditions.

Air Photos & Mapping


A review of available natural resources mapping, as well as recent aerial photographs of the site confirms the results of the site work. The grassland area and the enhanced areas to the north were farmed until 2005. In late 2006 or early 2007 the corridor south of the Tualatin River was established and planted, though the remaining areas have remained as grass.

Other than the Tualatin River the City of Tualatin Local Wetland Inventory map does not identify wetlands or other water features. Likewise, mapped soil units suggest upland conditions and do not include hydric (wetland) soils.

Conclusion

Our on-site and off-site work indicates that the Tualatin River is the only potentially jurisdictional water feature within the designated study area. Feel free to contact me if you have any questions regarding the results of this wetland determination.

Thank you,



Shawn Eisner
Wetland Scientist



11/17/11

4921

FIGURE 1

Nyberg II, a proposed commercial development west of I-5 in Tualatin, Oregon (Air photo base map provided by Cardno WRG, 2011).

WETLAND DETERMINATION DATA FORM - Western Mountains, Valleys, and Coast Region

Project/Site: Nyberg II City/County: Tualatin/Washington Sampling Date: 11/15/2011
 Applicant/Owner: Centercal State: OR Sampling Point: 1
 Investigator(s): S. Eisner / A. Hawkins Section, Township, Range: Section 24B, T 2 South, R 1 West
 Landform (hillslope, terrace, etc.): _____ Local relief (concave, convex, none): none Slope (%): _____
 Subregion (LRR): LRR A Lat: 45.3849 Long: -122.7552 Datum: _____
 Soil Map Unit Name: Chehalis silt loam NWI Classification: none
 Are climatic/hydrologic conditions on the site typical for this time of year? Yes X No _____ (if no, explain in Remarks)
 Are vegetation _____ Soil _____ or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? (Y/N) Y
 Are vegetation _____ Soil _____ or Hydrology _____ naturally problematic? If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

| | |
|---|---|
| Hydrophytic Vegetation Present? Yes <u>X</u> No _____ | Is Sampled Area within a Wetland? Yes _____ No <u>X</u> |
| Hydric Soil Present? Yes _____ No <u>X</u> | |
| Wetland Hydrology Present? Yes _____ No <u>X</u> | |
| Remarks: Pit typical of existing conditions at west end of undeveloped area. | |

VEGETATION - Use scientific names of plants.

| | absolute % cover | Dominant Species? | Indicator Status | |
|--|------------------|-------------------|------------------|---|
| Tree Stratum (plot size: _____) | | | | |
| 1 | _____ | _____ | _____ | Dominance Test worksheet: Number of Dominant Species That are OBL, FACW, or FAC: <u>1</u> (A) Total Number of Dominant Species Across All Strata: <u>1</u> (B) Percent of Dominant Species That are OBL, FACW, or FAC: <u>100%</u> (A/B) |
| 2 | _____ | _____ | _____ | |
| 3 | _____ | _____ | _____ | |
| 4 | _____ | _____ | _____ | |
| | <u>0</u> | = Total Cover | | |
| Sapling/Shrub Stratum (plot size: _____) | | | | |
| 1 | _____ | _____ | _____ | Prevalence Index Worksheet: Total % Cover of _____ Multiply by: OBL Species _____ x 1 = <u>0</u> FACW species _____ x 2 = <u>0</u> FAC Species _____ x 3 = <u>0</u> FACU Species _____ x 4 = <u>0</u> UPL Species _____ x 5 = <u>0</u> Column Totals <u>0</u> (A) <u>0</u> (B) Prevalence Index =B/A = <u>#DIV/0!</u> |
| 2 | _____ | _____ | _____ | |
| 3 | _____ | _____ | _____ | |
| 4 | _____ | _____ | _____ | |
| 5 | _____ | _____ | _____ | |
| | <u>0</u> | = Total Cover | | |
| Herb Stratum (plot size: <u>5</u>) | | | | |
| 1 | <u>90</u> | <u>X</u> | <u>FAC</u> | Hydrophytic Vegetation Indicators: _____ 1- Rapid Test for Hydrophytic Vegetation <u>X</u> 2- Dominance Test is >50% _____ 3-Prevalence Index is ≤ 3.0 ¹ _____ 4-Morphological Adaptations ¹ (provide supporting data in Remarks or on a separate sheet) _____ 5- Wetland Non-Vascular Plants ¹ _____ Problematic Hydrophytic Vegetation ¹ (Explain) ¹ Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic. Hydrophytic Vegetation Present? Yes <u>X</u> No _____ |
| 2 | <u>10</u> | _____ | <u>FACW</u> | |
| 3 | <u>1</u> | _____ | <u>(FAC)</u> | |
| 4 | _____ | _____ | _____ | |
| 5 | _____ | _____ | _____ | |
| 6 | _____ | _____ | _____ | |
| 7 | _____ | _____ | _____ | |
| 8 | _____ | _____ | _____ | |
| | <u>101</u> | = Total Cover | | |
| Woody Vine Stratum (plot size: _____) | | | | |
| 1 | _____ | _____ | _____ | |
| 2 | _____ | _____ | _____ | |
| | <u>0</u> | = Total Cover | | |
| % Bare Ground in Herb Stratum _____ | | | | |
| Remarks: This is a periodically mowed herbaceous area immediate south of presumed vegetative buffer enhancements south of the Tualatin River. | | | | |

SOIL

PHS # 4921

Sampling Point: 1

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

| Depth (Inches) | Matrix | | Redox Features | | | | Texture | Remarks |
|-------------------|---------------|----|----------------|---|-------------------|------------------|-----------|-------------------|
| | Color (moist) | % | Color (moist) | % | Type ¹ | Loc ² | | |
| 0-16 | 10YR 3/3 | 40 | | | | | Silt Loam | mixed matrix soil |
| 0-16 | 10YR 3/4 | 60 | | | | | Silt Loam | mixed matrix soil |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |

¹Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains.

²Location: PL=Pore Lining, M=Matrix.

Hydric Soil Indicators: (Applicable to all LRRs, unless otherwise noted.)

Indicators for Problematic Hydric Soils³:

| | | |
|--|---|---|
| <input type="checkbox"/> Histosol (A1) | <input type="checkbox"/> Sandy Redox (S5) | <input type="checkbox"/> 2 cm Muck (A10) |
| <input type="checkbox"/> Histic Epipedon (A2) | <input type="checkbox"/> Stripped Matrix (S6) | <input type="checkbox"/> Red Parent Material (TF2) |
| <input type="checkbox"/> Black Histic (A3) | <input type="checkbox"/> Loamy Mucky Mineral (F1) (except MLRA 1) | <input type="checkbox"/> Very Shallow Dark Surface (TF12) |
| <input type="checkbox"/> Hydrogen Sulfide (A4) | <input type="checkbox"/> Loamy Gleyed Matrix (F2) | <input type="checkbox"/> Other (explain in Remarks) |
| <input type="checkbox"/> Depleted Below Dark Surface (A11) | <input type="checkbox"/> Depleted Matrix (F3) | |
| <input type="checkbox"/> Thick Dark Surface (A12) | <input type="checkbox"/> Redox Dark Surface (F6) | |
| <input type="checkbox"/> Sandy Mucky Mineral (S1) | <input type="checkbox"/> Depleted Dark Surface (F7) | |
| <input type="checkbox"/> Sandy Gleyed Matrix (S4) | <input type="checkbox"/> Redox Depressions (F8) | |

³Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if present):

Type: None

Depth (inches):

Hydric Soil Present? Yes No

Remarks:

HYDROLOGY

Wetland Hydrology indicators:

Primary Indicators (minimum of one required; check all that apply)

Secondary Indicators (2 or more required)

| | | |
|--|---|--|
| <input type="checkbox"/> Surface Water (A1) | <input type="checkbox"/> Water stained Leaves (B9) (Except MLRA 1, 2, 4A, and 4B) | <input type="checkbox"/> Water stained Leaves (B9) (Except MLRA1, 2, 4A, and 4B) |
| <input type="checkbox"/> High Water Table (A2) | <input type="checkbox"/> Salt Crust (B11) | <input type="checkbox"/> Drainage Patterns (B10) |
| <input type="checkbox"/> Saturation (A3) | <input type="checkbox"/> Aquatic Invertebrates (B13) | <input type="checkbox"/> Dry-Season Water Table (C2) |
| <input type="checkbox"/> Water Marks (B1) | <input type="checkbox"/> Hydrogen Sulfide Odor (C1) | <input type="checkbox"/> Saturation Visible on Aerial Imagery (C9) |
| <input type="checkbox"/> Sediment Deposits (B2) | <input type="checkbox"/> Oxidized Rhizospheres along Living Roots (C3) | <input type="checkbox"/> Geomorphic Position (D2) |
| <input type="checkbox"/> Drift Deposits (B3) | <input type="checkbox"/> Presence of Reduced Iron (C4) | <input type="checkbox"/> Shallow Aquitard (D3) |
| <input type="checkbox"/> Algal Mat or Crust (B4) | <input type="checkbox"/> Recent Iron Reduction in Plowed Soils (C6) | <input type="checkbox"/> Fac-Neutral Test (D5) |
| <input type="checkbox"/> Iron Deposits (B5) | <input type="checkbox"/> Stunted or Stressed Plants (D1) (LRR A) | <input type="checkbox"/> Raised Ant Mounds (D6) (LRR A) |
| <input type="checkbox"/> Surface Soil Cracks (B6) | <input type="checkbox"/> Other (Explain in Remarks) | <input type="checkbox"/> Frost-Heave Hummocks (D7) |
| <input type="checkbox"/> Inundation Visible on Aerial Imagery (B7) | | |
| <input type="checkbox"/> Sparsely Vegetated Concave Surface (B8) | | |

Field Observations:

Surface Water Present? Yes No Depth (inches):

Water Table Present? Yes No Depth (inches):

Saturation Present? Yes No Depth (inches): (includes capillary fringe)

Wetland Hydrology Present? Yes No

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:

None

Remarks:

WETLAND DETERMINATION DATA FORM - Western Mountains, Valleys, and Coast Region

Project/Site: Nyberg II City/County: Tualatin/Washington Sampling Date: 11/15/2011
 Applicant/Owner: Centercal State: OR Sampling Point: 2
 Investigator(s): S. Eisner / A. Hawkins Section, Township, Range: Section 24B, T 2 South, R 1 West
 Landform (hillslope, terrace, etc.): _____ Local relief (concave, convex, none): none Slope (%): _____
 Subregion (LRR): LRR A Lat: 45.3868 Long: -122.752 Datum: _____
 Soil Map Unit Name: Chehalis silt loam NWI Classification: none
 Are climatic/hydrologic conditions on the site typical for this time of year? Yes X No _____ (if no, explain in Remarks)
 Are vegetation _____ Soil _____ or Hydrology _____ significantly disturbed? Are "Normal Circumstances" present? (Y/N) Y
 Are vegetation _____ Soil _____ or Hydrology _____ naturally problematic? If needed, explain any answers in Remarks.)

SUMMARY OF FINDINGS – Attach site map showing sampling point locations, transects, important features, etc.

| | |
|--|---|
| Hydrophytic Vegetation Present? Yes _____ No <u>X</u> | Is Sampled Area within a Wetland? Yes _____ No <u>X</u> |
| Hydric Soil Present? Yes _____ No <u>X</u> | |
| Wetland Hydrology Present? Yes _____ No <u>X</u> | |
| Remarks: Pit taken in localized depression. Pit taken to document the most likely location for wetland to have been present in the forested portion of the site. | |

VEGETATION - Use scientific names of plants.

| | absolute % cover | Dominant Species? | Indicator Status | |
|---|------------------|-------------------|------------------|---|
| Tree Stratum (plot size: <u>30</u>) | | | | Dominance Test worksheet: Number of Dominant Species That are OBL, FACW, or FAC: <u>1</u> (A) Total Number of Dominant Species Across All Strata: <u>4</u> (B) Percent of Dominant Species That are OBL, FACW, or FAC: <u>25%</u> (A/B) |
| 1 | <u>60</u> | <u>X</u> | <u>FACU</u> | |
| 2 | <u>10</u> | | <u>FAC</u> | |
| 3 | <u>5</u> | | <u>FACU</u> | |
| 4 | | | | |
| | <u>75</u> | = Total Cover | | |
| Sapling/Shrub Stratum (plot size: <u>5</u>) | | | | |
| 1 | <u>15</u> | <u>X</u> | <u>FACU</u> | |
| 2 | | | | |
| 3 | | | | |
| 4 | | | | |
| 5 | | | | |
| | <u>15</u> | = Total Cover | | |
| Herb Stratum (plot size: <u>5</u>) | | | | Prevalence Index Worksheet: Total % Cover of _____ Multiply by: OBL Species _____ x 1 = <u>0</u> FACW species _____ x 2 = <u>0</u> FAC Species _____ x 3 = <u>0</u> FACU Species _____ x 4 = <u>0</u> UPL Species _____ x 5 = <u>0</u> Column Totals <u>0</u> (A) <u>0</u> (B) Prevalence Index = B/A = <u>#DIV/0!</u> |
| 1 | <u>20</u> | | <u>UPL</u> | |
| 2 | <u>25</u> | <u>X</u> | <u>FAC</u> | |
| 3 | <u>10</u> | | <u>FACW</u> | |
| 4 | <u>50</u> | <u>X</u> | <u>UPL</u> | |
| 5 | <u>tr</u> | | <u>FAC</u> | |
| 6 | <u>3</u> | | <u>UPL</u> | |
| 7 | <u>tr</u> | | <u>FAC</u> | |
| 8 | | | | |
| | <u>108</u> | = Total Cover | | |
| Woody Vine Stratum (plot size: _____) | | | | |
| 1 | | | | |
| 2 | | | | |
| | <u>0</u> | = Total Cover | | |
| % Bare Ground in Herb Stratum <u>0</u> | | | | |

Hydrophytic Vegetation Indicators:

- 1- Rapid Test for Hydrophytic Vegetation
- 2- Dominance Test is >50%
- 3- Prevalence Index is ≤ 3.0¹
- 4- Morphological Adaptations¹ (provide supporting data in Remarks or on a separate sheet)
- 5- Wetland Non-Vascular Plants¹

Problematic Hydrophytic Vegetation¹ (Explain)

¹Indicators of hydric soil and wetland hydrology must be present, unless disturbed or problematic.

Hydrophytic Vegetation Present? Yes _____ No X

Remarks:

SOIL

PHS # 4921

Sampling Point: 2

Profile Description: (Describe to the depth needed to document the indicator or confirm the absence of indicators.)

| Depth (Inches) | Matrix | | Redox Features | | | | Texture | Remarks |
|-------------------|---------------|-----|----------------|---|-------------------|------------------|-----------|---------|
| | Color (moist) | % | Color (moist) | % | Type ¹ | Loc ² | | |
| 0-4 | 10YR 2/2 | 100 | | | | | Loam | |
| 4-17 | 10YR 3/3 | 100 | | | | | Silt Loam | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |
| | | | | | | | | |

¹Type: C=Concentration, D=Depletion, RM=Reduced Matrix, CS=Covered or Coated Sand Grains. ²Location: PL=Pore Lining, M=Matrix.

| Hydric Soil Indicators: (Applicable to all LRRs, unless otherwise noted.) | | Indicators for Problematic Hydric Soils ³ : | |
|---|---|---|--|
| <input type="checkbox"/> Histosol (A1) | <input type="checkbox"/> Sandy Redox (S6) | <input type="checkbox"/> 2 cm Muck (A10) | |
| <input type="checkbox"/> Histic Epipedon (A2) | <input type="checkbox"/> Stripped Matrix (S6) | <input type="checkbox"/> Red Parent Material (TF2) | |
| <input type="checkbox"/> Black Histic (A3) | <input type="checkbox"/> Loamy Mucky Mineral (F1) (except MLRA 1) | <input type="checkbox"/> Very Shallow Dark Surface (TF12) | |
| <input type="checkbox"/> Hydrogen Sulfide (A4) | <input type="checkbox"/> Loamy Gleyed Matrix (F2) | <input type="checkbox"/> Other (explain in Remarks) | |
| <input type="checkbox"/> Depleted Below Dark Surface (A11) | <input type="checkbox"/> Depleted Matrix (F3) | | |
| <input type="checkbox"/> Thick Dark Surface (A12) | <input type="checkbox"/> Redox Dark Surface (F6) | | |
| <input type="checkbox"/> Sandy Mucky Mineral (S1) | <input type="checkbox"/> Depleted Dark Surface (F7) | | |
| <input type="checkbox"/> Sandy Gleyed Matrix (S4) | <input type="checkbox"/> Redox Depressions (F8) | | |

³Indicators of hydrophytic vegetation and wetland hydrology must be present, unless disturbed or problematic.

Restrictive Layer (if present):

Type: None

Depth (inches): _____

Hydric Soil Present? Yes _____ No X

Remarks:

HYDROLOGY

| Wetland Hydrology Indicators: | | Secondary Indicators (2 or more required) | |
|--|---|--|--|
| Primary Indicators (minimum of one required; check all that apply) | | | |
| <input type="checkbox"/> Surface Water (A1) | <input type="checkbox"/> Water stained Leaves (B9) (Except MLRA 1, 2, 4A, and 4B) | <input type="checkbox"/> Water stained Leaves (B9) (Except MLRA1, 2, 4A, and 4B) | |
| <input type="checkbox"/> High Water Table (A2) | <input type="checkbox"/> Salt Crust (B11) | <input type="checkbox"/> Drainage Patterns (B10) | |
| <input type="checkbox"/> Saturation (A3) | <input type="checkbox"/> Aquatic Invertebrates (B13) | <input type="checkbox"/> Dry-Season Water Table (C2) | |
| <input type="checkbox"/> Water Marks (B1) | <input type="checkbox"/> Hydrogen Sulfide Odor (C1) | <input type="checkbox"/> Saturation Visible on Aerial Imagery (C9) | |
| <input type="checkbox"/> Sediment Deposits (B2) | <input type="checkbox"/> Oxidized Rhizospheres along Living Roots (C3) | <input type="checkbox"/> Geomorphic Position (D2) | |
| <input type="checkbox"/> Drift Deposits (B3) | <input type="checkbox"/> Presence of Reduced Iron (C4) | <input type="checkbox"/> Shallow Aquitard (D3) | |
| <input type="checkbox"/> Algal Mat or Crust (B4) | <input type="checkbox"/> Recent Iron Reduction in Plowed Soils (C6) | <input type="checkbox"/> Fac-Neutral Test (D5) | |
| <input type="checkbox"/> Iron Deposits (B5) | <input type="checkbox"/> Stunted or Stressed Plants (D1) (LRR A) | <input type="checkbox"/> Raised Ant Mounds (D6) (LRR A) | |
| <input type="checkbox"/> Surface Soil Cracks (B6) | <input type="checkbox"/> Other (Explain in Remarks) | <input type="checkbox"/> Frost-Heave Hummocks (D7) | |
| <input type="checkbox"/> Inundation Visible on Aerial Imagery (B7) | | | |
| <input type="checkbox"/> Sparsely Vegetated Concave Surface (B8) | | | |

Field Observations:

Surface Water Present? Yes _____ No X Depth (inches): _____

Water Table Present? Yes _____ No X Depth (inches): _____

Saturation Present? Yes _____ No X Depth (inches): _____
(includes capillary fringe)


Wetland Hydrology Present? Yes _____ No X

Describe Recorded Data (stream gauge, monitoring well, aerial photos, previous inspections), if available:
None

Remarks:

Appendix C

Vegetated Corridor Sample Points Table & Photodocumentation



Nyberg Rivers Development Vegetated Corridor Sample Sites

| Plant Community | A | | | B | | C | | | | |
|--------------------------------|---------|-----|-----|---------|-----|-----|---------|-----|-----|----|
| Sample Site | 1 | 3 | 7 | 2 | 4 | 5 | 6 | | | |
| TREES | | | | | | | | | | |
| <i>Acer macrophyllum</i> | | | | 20 | 10 | | 2 | | | |
| <i>Alnus rubra</i> | | | | 40 | | | | | | |
| <i>Crataegus monogyna</i> | | | | 15 | | | 2 | | | |
| <i>Pseudotsuga menziesii</i> | | | | 10 | 90 | 90 | 75 | | | |
| <i>Thuja plicata</i> | | | | | | | 30 | | | |
| SHRUBS & SAPLINGS | | | | | | | | | | |
| <i>Acer circinatum</i> | 2 | | | | | | | | | |
| <i>Acer macrophyllum</i> | 5 | 1 | 5 | | | | | | | |
| <i>Berberis aquifolium</i> | 1 | 5 | 5 | | 5 | 2 | 2 | | | |
| <i>Crataegus douglasii</i> | 10 | 10 | 10 | | | | | | | |
| <i>Crataegus monogyna</i> | 10 | | | 5 | | 3 | | | | |
| <i>Oemleria cerasiformis</i> | | | | | | 1 | | | | |
| <i>Pseudotsuga menziesii</i> | 20 | 20 | 20 | | | | | | | |
| <i>Quercus garryana</i> | 5 | 5 | 5 | | | | | | | |
| <i>Rosa nutkana</i> | 15 | 10 | 15 | | | | | | | |
| <i>Rubus armeniacus</i> | 1 | 1 | 5 | 25 | 1 | 10 | 25 | | | |
| <i>Rubus ursinus</i> | | | | 5 | | | 25 | | | |
| <i>Symphoricarpos albus</i> | 2 | 2 | 5 | 15 | 20 | | 5 | | | |
| HERBS/WOODY VINES | | | | | | | | | | |
| <i>Agrostis capillaris</i> | 40 | 80 | 20 | | 10 | | | | | |
| <i>Anthoxantum odoratum</i> | | | | | | | | | | |
| <i>Arrhenatherum elatius</i> | | | | | | | | | | |
| <i>Berberis nervosa</i> | 1 | | | | | | | | | |
| <i>Cirsium arvense/vulgare</i> | | | 5 | | | | | | | |
| <i>Dactylus glomerata</i> | 20 | 5 | 40 | | 60 | 45 | 50 | | | |
| <i>Daucus carota</i> | 10 | | | | | | | | | |
| <i>Festuca arundinacea</i> | 5 | | | | | | | | | |
| <i>Galium aparine</i> | | | | | 5 | | | | | |
| <i>Geranium lucidum</i> | | | | | 10 | 10 | 20 | | | |
| <i>Geranium molle</i> | | | | | 5 | | | | | |
| <i>Geranium robertianum</i> | | | | | 5 | | | | | |
| <i>Hedera helix</i> | | | | 100 | 2 | 20 | 10 | | | |
| <i>Holcus lanatus</i> | 5 | 10 | 30 | | | | | | | |
| <i>Lapsana communis</i> | | | | 5 | | 10 | 20 | | | |
| <i>Plantago lanceolata</i> | 2 | | | | | | | | | |
| <i>Polystichum munitum</i> | | | | 10 | 1 | 1 | 2 | | | |
| Unidentified grasses | | | | 5 | | 20 | | | | |
| <i>Vicia</i> sp. | | 5 | | | 3 | | | | | |
| | Average | | | Average | | | Average | | | |
| Canopy cover | 0 | 0 | 0 | 0 | 90 | 95 | 93 | 90 | 85 | 88 |
| % Native Species | 40 | 34 | 39 | 38 | 39 | 58 | 48 | 44 | 53 | 48 |
| % Invasive Species | 1 | 1 | 6 | 2 | 49 | 1 | 25 | 14 | 13 | 14 |
| Total cover | 154 | 154 | 165 | | 255 | 227 | | 212 | 268 | |



Photo A:

View to the north in the western portion of the corridor. Foreground is Community A. The larger deciduous trees are part of Community B. The fir trees in the background are located across the Tualatin River and are not on the site.

Photo B:

View to the northeast from the eastern portion of Community A. The larger trees in the background are in Community C.



5141
3/8/13



Pacific Habitat Services, Inc.
9450 SW Commerce Circle, Suite 180
Wilsonville, OR 97070

Photo documentation of existing plant communities north of Nyberg Rivers.
Both photos taken on March 5, 2013.



Photo C:

View to the northeast along the south bank of the Tualatin River. Left side of the photo is Community B; the right side is Community A; and the background includes Community C.

Photo D:

View to the northeast across the western extent of Community C.



5141
3/8/13



Pacific Habitat Services, Inc.
9450 SW Commerce Circle, Suite 180
Wilsonville, OR 97070

Photo documentation of existing plant communities north of Nyberg Rivers.
Both photos taken on March 5, 2013.



Photo E:

View to the southwest
across the north end of
Community C.

Photo F:

View to the southwest of the
small area of Community A
within Community C.



5141
3/8/13



Pacific Habitat Services, Inc.
9450 SW Commerce Circle, Suite 180
Wilsonville, OR 97070

Photo documentation of existing plant communities north of Nyberg Rivers.
Both photos taken on March 5, 2013.

Appendix D

NRA Definitions and Methodology and References



NATURAL RESOURCE ASSESSMENT (NRA)

Regulatory Jurisdiction

Clean Water Services, as part of their revised Design and Construction Standards, requires that natural resource assessments be conducted for Sensitive Natural Resource Areas within their jurisdiction. Sensitive Natural Resource Areas include intermittent and perennial creeks, wetlands, springs and seeps, and associated vegetated corridors. The intent of these requirements is to "...prevent or reduce adverse impacts to the drainage system and water resources of the Tualatin River Basin" (CWS 2007). CWS requires a wetland determination/delineation and vegetated corridor assessment on projects that contain or are within 200 feet of a Sensitive Area.

Natural Resource Assessment Methodology

The Natural Resource Assessment (NRA) contains two components: a delineation of the water quality sensitive areas and a vegetated corridor evaluation. A detailed discussion of the methodology is included in Chapter 3 of CWS's revised Design and Construction Standards (CWS, 2007). A brief description of each component is included below.

Delineation of water quality sensitive areas

A delineation of all on-site water quality sensitive areas (wetland, intermittent/perennial streams, springs, and natural lakes or ponds) must be conducted. For wetlands, the required criteria and suggested methodologies of the *Corps of Engineers Wetland Delineation Manual Technical Report Y-87-1*, (Environmental Laboratory, 1987) must be used to delineate the boundaries. This manual defines wetlands as requiring indicators of hydric soils, a dominance of hydrophytic vegetation, and wetland hydrology. A determination as to whether streams are intermittent or perennial must be made. The extent of all streams, springs, and natural lakes or ponds must also be determined.

When known sensitive areas exist on adjacent properties, an attempt must be made by the applicant to obtain access to delineate the limits of these off-site features, especially if vegetated corridors associated with an off-site sensitive area may extend onto a proposed development site.

Determine Vegetated Corridor Width and Condition

The width of the vegetated corridor must be determined at least every 100 feet along the boundary of the water quality sensitive area. The corridor width can range between 15 and 200 feet and is measured horizontally from the outer edge of the water quality sensitive area. The boundaries of the sensitive areas and their vegetated corridors must be staked, surveyed, and mapped within the property and within 200 feet of the property line on a base map. The vegetated corridor width is based on the type of water resource (wetland, lake, stream), the size and nature of the water resource (acreage and/or perennial/intermittent), the size of the watershed, and the adjacent slope.

Upon identification of the regulated vegetated corridor boundary, the existing condition of the vegetated corridor must also be determined. This is accomplished by 1) identifying the plant community types present in the vegetated corridor, 2) documenting representative sample points, 3) characterizing each plant community type, 4) determining the cover by native species, invasive species, and noxious plants, and 5) based on this information determining whether the existing vegetated corridor condition for each plant community is good, marginal, or degraded.

REFERENCES

Clean Water Services, 2007. *Design and Construction Standards (R&O 7-20)*.

US Geologic Survey, 1984. *7.5-minute topographic map, Beaverton, Oregon quadrangle*.

US Geologic Survey, 1984. *7.5-minute topographic map, Lake Oswego, Oregon quadrangle*.



CWS File Number 13-000801

Service Provider Letter

13-000801

This form and the attached conditions will serve as your Service Provider Letter in accordance with Clean Water Services Design and Construction Standards (R&O 07-20).

| | | | |
|---------------------------------|---|-----------------------------|-----------------------|
| Jurisdiction: | <u>City of Tualatin</u> | Review Type: | <u>No Impact</u> |
| Site Address / Location: | <u>7055 SW Nyberg ST</u> <u>Tualatin, OR 97062</u> | SPL Issue Date: | <u>April 04, 2013</u> |
| | | SPL Expiration Date: | <u>April 04, 2015</u> |

| | | | |
|-------------------------------|--|---------------------------|-----------------------------------|
| Applicant Information: | | Owner Information: | |
| Name | <u>MICHAEL CERBONE</u> | Name | <u>NYBERG LIMITED PARTNERSHIP</u> |
| Company | <u>CARDNO</u> | Company | <u>(MULTIPLE OWNERS)</u> |
| Address | <u>5415 SW WESTGATE DRIVE SUITE 100</u> <u>PORTLAND, OR 97221</u> | Address | <u></u> |
| Phone/Fax | <u>(503) 419-2500</u> | Phone/Fax | <u></u> |
| E-mail: | <u>Michael.cerbone@cardno.com</u> | E-mail: | <u></u> |

| Tax lot ID | Development Activity |
|---|-----------------------------|
| <u>2S124A002502, 002507,</u> <u>2S124A002700,</u> <u>2S124B002100,</u> <u>2S124A002506, 002508,</u> <u>2S124B001601, 001602,</u> <u>001900, 002000, 002001,</u> <u>2S124B001601</u> | <u>Multi Lot Commercial</u> |

| Pre-Development Site Conditions: | Post Development Site Conditions: |
|--|--|
| Sensitive Area Present: <input checked="" type="checkbox"/> On-Site <input checked="" type="checkbox"/> Off-Site Vegetated Corridor Width: <u>125</u> Vegetated Corridor Condition: <u>Good/Marginal</u> | Sensitive Area Present: <input checked="" type="checkbox"/> On-Site <input checked="" type="checkbox"/> Off-Site Vegetated Corridor Width: <u>125</u> |

| | |
|--|---|
| Enhancement of Remaining Vegetated Corridor Required: <input checked="" type="checkbox"/> | Square Footage to be enhanced: <u>67,133</u> |
|--|---|

| Encroachments into Pre-Development Vegetated Corridor: | |
|--|-----------------------------|
| Type and location of Encroachment: <u>No Encroachment Proposed; Future Development of the Trail</u> | Square Footage: <u>0</u> |
| <u></u> | <u></u> |
| <u></u> | <u></u> |

| Mitigation Requirements: | |
|--|--------------------------------|
| Type/Location <u>No Mitigation Required</u> | Sq. Ft./Ratio/Cost <u>0</u> |
| <u></u> | <u></u> |
| <u></u> | <u></u> |

Conditions Attached
 Development Figures Attached (3)
 Planting Plan Attached
 Geotech Report Required

This Service Provider Letter does NOT eliminate the need to evaluate and protect water quality sensitive areas if they are subsequently discovered on your property.

In order to comply with Clean Water Services water quality protection requirements the project must comply with the following conditions:

1. No structures, development, construction activities, gardens, lawns, application of chemicals, uncontained areas of hazardous materials as defined by Oregon Department of Environmental Quality, pet wastes, dumping of materials of any kind, or other activities shall be permitted within the sensitive area or Vegetated Corridor which may negatively impact water quality, except those allowed in R&O 07-20, Chapter 3.
2. Prior to any site clearing, grading or construction the Vegetated Corridor and water quality sensitive areas shall be surveyed, staked, and temporarily fenced per approved plan. During construction the Vegetated Corridor shall remain fenced and undisturbed except as allowed by R&O 07-20, Section 3.06.1 and per approved plans.
3. If there is any activity within the sensitive area, the applicant shall gain authorization for the project from the Oregon Department of State Lands (DSL) and US Army Corps of Engineers (USACE). The applicant shall provide Clean Water Services or its designee (appropriate city) with copies of all DSL and USACE project authorization permits.
4. An approved Oregon Department of Forestry Notification is required for one or more trees harvested for sale, trade, or barter, on any non-federal lands within the State of Oregon.
5. **Prior to ground disturbance, an Erosion Control Permit is required through the City. Appropriate Best Management Practices (BMP's) for Erosion Control, in accordance with Clean Water Services' Erosion Prevention and Sediment Control Planning and Design Manual, shall be used prior to, during, and following earth disturbing activities.**
6. Prior to construction, a Stormwater Connection Permit from Clean Water Services or its designee is required pursuant to Ordinance 27, Section 4.B.
7. Activities located within the 100-year floodplain shall comply with R&O 07-20, Section 5.10.
8. Removal of native, woody vegetation shall be limited to the greatest extent practicable.
9. The water quality facility shall be planted with Clean Water Services approved native species, and designed to blend into the natural surroundings.
10. **Should final development plans differ significantly from those submitted for review by Clean Water Services, the applicant shall provide updated drawings, and if necessary, obtain a revised Service Provider Letter.**

SPECIAL CONDITIONS

11. The Vegetated Corridor width for sensitive areas within the project site shall be a minimum of 125 feet wide, as measured horizontally from the delineated boundary of the sensitive area.
12. **For Vegetated Corridors greater than 50 feet in width, the applicant shall enhance the first 50 feet closest to the sensitive area to meet or exceed good corridor condition as defined in R&O 07-20, Section 3.14.2, Table 3-3.**
13. Prior to any site clearing, grading or construction, the applicant shall provide Clean Water Services or the City with a Vegetated Corridor enhancement/restoration plan. Enhancement/restoration of the Vegetated Corridor shall be provided in accordance with R&O 07-20, Appendix A, and shall include planting specifications for all Vegetated Corridor, including any cleared areas larger than 25 square feet in Vegetated Corridor rated ""good.""
14. **Prior to installation of plant materials, all invasive vegetation within the Vegetated Corridor shall be removed per methods described in Clean Water Services' Integrated Pest Management Guide, 2009. During removal of invasive vegetation care shall be taken to minimize impacts to existing native tree and shrub species.**
15. Clean Water Services or the City shall be notified 72 hours prior to the start and completion of enhancement/restoration activities. Enhancement/restoration activities shall comply with the guidelines provided in Landscape Requirements (R&O 07-20, Appendix A).

16. Maintenance and monitoring requirements shall comply with R&O 07-20, Section 2.11.2. If at any time during the warranty period the landscaping falls below the 80% survival level, the owner shall reinstall all deficient planting at the next appropriate planting opportunity and the two year maintenance period shall begin again from the date of replanting.
17. Performance assurances for the Vegetated Corridor shall comply with R&O 07-20, Section 2.06.2.
18. For any developments which create multiple parcels or lots intended for separate ownership, Clean Water Services may require that the sensitive area and Vegetated Corridor be contained in a separate tract and subject to a ""STORM SEWER, SURFACE WATER, DRAINAGE AND DETENTION EASEMENT OVER ITS ENTIRETY"" to be granted to the City or Clean Water Services.

FINAL PLANS

19. **Final construction plans shall include landscape plans.** In the details section of the plans, a description of the methods for removal and control of exotic species, location, distribution, condition and size of plantings, existing plants and trees to be preserved, and installation methods for plant materials is required. Plantings shall be tagged for dormant season identification and shall remain on plant material after planting for monitoring purposes.
20. **A Maintenance Plan** shall be included on final plans including methods, responsible party contact information, and dates (minimum two times per year, by June 1 and September 30).
21. **Final construction plans shall clearly depict the location and dimensions of the sensitive area and the Vegetated Corridor** (indicating good, marginal, or degraded condition). Sensitive area boundaries shall be marked in the field.
22. Protection of the Vegetated Corridors and associated sensitive areas shall be provided by the installation of signage between the development and the outer limits of the Vegetated Corridors. **Signage details to be included on final construction plans.**


This Service Provider Letter is not valid unless CWS-approved site plan is attached.

Please call (503) 681-3653 with any questions.



Amber Wierck
Environmental Plan Review

Attachments (3)




Base map provided by CARDNO WRG.

FIGURE 2

Existing Conditions

Nyberg Rivers Commercial Retail Development- Tualatin, Oregon

03-07-2013



Conceptual Path Alignment
 * FUTURE CONSTRUCTION OF THE PATH WILL REQUIRE AN ENVIRONMENTAL REVIEW AND SEPARATE SPL


LEGEND
 Existing Regulated Vegetated Corridor
 (207,521 sf / 4.8 ac)

Cover 2019
 CWS File No. 13-000801
 Approved
 Clean Water Services
 Environmental Review
 By: AN Date: 9/4/13
 SPL ATTACHMENT 2 of 3



Note:
 Base Map provided by CARDNO WRG.

Proposed Development Plan
 Nyberg Rivers Commercial Retail Development- Tualatin, Oregon
 FIGURE 3
 05-07-2013



Color copy
 CWS file no. 13-000801
 Approved
 Clean Water Services
 Environmental Review
 By AW Date 4/1/15
 SPL Attachment 3 of 3

LEGEND

- Existing Regulated Vegetated Corridor (207,521 sf / 4.8 ac)
- Vegetated Corridor Enhancement (67,133 sf / 1.5 ac)
- Vegetated Corridor Encroachment (18,832 sf / 0.43 ac)

POTENTIAL FUTURE

* APPROVAL OF THE ENCROACHMENT IS SUBJECT TO AN ENVIRONMENTAL REVIEW

NOTE:
 Mitigation For Proposed Trail Encroachments To Be Completed Offsite Per The Requirements of CWS R&O 07-20; Chapter 3 Appendix A
 * OFF-SITE MITIGATION MAY REQUIRE AN INCREASED RATIO BASED ON HOW FAR THE MITIGATION LOCATION IS FROM THE ENCROACHMENT SITE.

Note: Base map provided by CARDNO WRG.

PHS
 Pacific Habitat Services, Inc.
 4000 SW Commercial Street, Suite 100, Portland, Oregon 97204
 Phone: 503-253-8200 Fax: 503-253-8202

FIGURE 4
 Vegetated Corridor Encroachment and Necessary Enhancements
 Nyberg Rivers Commercial Retail Development- Tualatin, Oregon

03-07-2013

**NEIGHBORHOOD/DEVELOPER MEETING
AFFIDAVIT OF MAILING**

STATE OF OREGON)
) SS
COUNTY OF WASHINGTON)


I, Thatch Moyle, being first duly sworn, depose and say:


That on the 25 day of July, 2013, I served upon the persons shown on Exhibit "A," attached hereto and by this reference incorporated herein, a copy of the Notice of Neighborhood/Developer meeting marked Exhibit "B," attached hereto and by this reference incorporated herein, by mailing to them a true and correct copy of the original hereof. I further certify that the addresses shown on said Exhibit "A" are their regular addresses as determined from the books and records of the Washington County and/or Clackamas County Departments of Assessment and Taxation Tax Rolls, and that said envelopes were placed in the United States Mail with postage fully prepared thereon.



Signature

SUBSCRIBED AND SWORN to before me this 21st day of August, 2013.





Notary Public for Oregon
My commission expires: April 30, 2017

RE: _____



Nyberg Rivers

Tax Lots & 1,000 Foot Buffer Within City Limits

Tualatin, Oregon

NOTE: The difference in parcels reflects those parcels removed that are listed under a different Jurisdiction i.e. Lake Oswego, Tigard, Durham, Rivergrove



Exhibit A-7
Attachment F

EXHIBIT "B-1"



July 25, 2013

5415 SW Westgate Drive
Suite 100
Portland, Oregon 97221
USA

Re: Architectural Review & Tree Removal Permit for Nyberg Rivers redevelopment

Phone (503) 419-2500
Fax (503) 419-2600

Dear Property Owner/Neighborhood Representative:

www.cardno.com

You are cordially invited to attend a meeting on August 8, 2013 from 5:30 p.m. to 6:30 p.m. at the Sylvan Learning Center branch located at 7809 SW Nyberg Street in Tualatin. This meeting shall be held to discuss a proposed architectural review & tree removal permit application for the proposed Nyberg Rivers development located at 7655 Nyberg Street in Tualatin. These applications follow the Nyberg Rivers Master Plan already submitted and under review by the City.

The tree removal permit pertains to Tax Lots 2502, 2507, 2508 and 2700. Generally, trees are proposed to be removed within the proposed commercial center, with trees retained within the Tualatin River greenway area. The Architectural Review pertains to the new proposed buildings onsite as shown on the attached site plan.

Please note that this will be an informational meeting on preliminary plans with the developer and representatives only and is not intended to take the place of a public hearing before the Architectural Review Board. You will have an opportunity to present testimony to this body and City staff when each application is submitted to the City for review.

We look forward to meeting you at the August meeting and hearing your thoughts on the proposed project!

Sincerely,

A handwritten signature in blue ink that reads "Thatch Moyle".

Thatch Moyle, AICP
Senior Planner, Cardno WRG

Enclosure: Site Plan

EXHIBIT "B-2"




Exhibit 1
Attachment F

**NEIGHBORHOOD/DEVELOPER MEETING
PUBLIC NOTICE MAILING**

As the applicant for the NYBERG RIVERS ARB & TREE REMOVAL
project, I hereby certify that on July 25, 2013, notice of the Neighborhood /
Developer meeting was mailed in accordance with the requirements of the
Tualatin Development Code and the Community Development Department -
Planning Division.

Applicant's Name: THATCH MOYLE
(PLEASE PRINT)

Applicant's Signature: *Thatch Moyle*

Date: 8/31/2013

NEIGHBORHOOD/DEVELOPER MEETING
PUBLIC NOTICE POSTING

As the applicant for the NYBERG RIVERS ARB & TREE REMOVAL
project, I hereby certify that on July 25, 2013, Six (6) sign(s)
were posted on the subject property in accordance with the requirements of the
Tualatin Development Code and the Community Development Department -
Planning Division.

Applicant's Name: THATCH MOYLE
(PLEASE PRINT)

Applicant's Signature: 

Date: 8/21/2013



Nyberg Rivers

Public Noticing-- Sign Locations

Tualatin, Oregon



Shaping the Future

**Exhibit 1
Attachment F**

Neighborhood Meeting Sign Posting Locations July 25, 2013



Site #1



Site #2



Site #3



Site #4



Site #5



Site #6

Nyberg Rivers
ARB/Tree Removal
Neighborhood Meeting
SIGN IN SHEET
August 8, 2013

| Name | Address Street Zip | Phone Number | E-Mail Address |
|----------------|---|----------------|-------------------------|
| FORDSON WILDER | 19190 SW 90th AVE #4768 TUALATIN, OR. 97062-9997 | (503) 882-6011 | fordsonwilder@yahoo.com |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

NYBERG RIVERS NEIGHBORHOOD MEETING

MEETING MINUTES



5415 SW Westgate Drive
Suite 100
Portland, Oregon 97221
USA

Phone (503) 419-2500
Fax (503) 419-2600

August 8, 2013

www.cardno.com

Cardno hosted a neighborhood meeting for the Nyberg Rivers redevelopment Architectural Review and Tree Removal Permit submittal at the Sylvan Learning Center on August 8, 2013 from 5:30 pm to 6:30 pm. The Sylvan Learning Center is located at 7809 SW Nyberg Street in Tualatin. There were two attendees at the neighborhood meeting, including one City of Tualatin planner and one private citizen. Cardno presented general information on the redevelopment project and answered specific questions regarding construction timelines and procedures. No comments or concerns were submitted in writing by the attendees during the meeting.

Exhibit "A"

LEGAL DESCRIPTION
Nyberg II 21198310
Boundary Description
May 31, 2013
Page 1 OF 5

A TRACT OF LAND LOCATED IN THE NORTHEAST AND NORTHWEST QUARTER OF SECTION 24, TOWNSHIP 2 SOUTH, RANGE 1 WEST, WILLAMETTE MERIDIAN, CITY OF TUALATIN, WASHINGTON COUNTY, OREGON, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT THE MOST NORTHERLY CORNER OF PARCEL 1, PARTITION PLAT NO. 1993-123, WASHINGTON COUNTY SURVEY RECORDS, SAID POINT BEING 120.00 FEET WESTERLY OF THE CENTERLINE OF THE SOUTHBOUND LANE OF INTERSTATE HIGHWAY NO. 5, WHEN MEASURED PERPENDICULAR THERETO;

THENCE ALONG THE WESTERLY RIGHT OF WAY LINE OF INTERSTATE HIGHWAY NO. 5 (VARIABLE WIDTH) SOUTH 15°49'17" WEST, 169.04 FEET TO A POINT BEING 120.00 FEET WESTERLY OF THE CENTERLINE OF THE SOUTHBOUND LANE OF INTERSTATE HIGHWAY NO. 5, WHEN MEASURED PERPENDICULAR THERETO;

THENCE SOUTH 12°33'01" WEST, 350.57 FEET TO A POINT BEING 100.00 FEET WESTERLY OF THE CENTERLINE OF THE SOUTHBOUND LANE OF INTERSTATE HIGHWAY NO. 5, WHEN MEASURED PERPENDICULAR THERETO;

THENCE PARALLEL WITH SAID CENTERLINE SOUTH 15°49'17" WEST, 170.29 FEET TO A POINT BEING 100.00 FEET WESTERLY OF THE CENTERLINE OF THE SOUTHBOUND LANE OF INTERSTATE HIGHWAY NO. 5, WHEN MEASURED PERPENDICULAR THERETO;

THENCE SOUTH 21°33'44" WEST, 542.28 FEET TO A POINT BEING 154.33 FEET WESTERLY OF THE CENTERLINE OF THE SOUTHBOUND LANE OF INTERSTATE HIGHWAY NO. 5, WHEN MEASURED PERPENDICULAR THERETO, SAID POINT ALSO BEING THE NORTHEAST CORNER OF DEED DOCUMENT NO. 2004-135929, WASHINGTON COUNTY DEED RECORDS;

THENCE ALONG THE NORTHERLY LINE OF SAID DEED DOCUMENT NO. 2004-135929 SOUTH 89°46'15" WEST, 374.82 FEET TO THE NORTHWEST CORNER THEREOF;

THENCE ALONG THE WESTERLY LINE OF SAID DEED DOCUMENT NO. 2004-135929 SOUTH 00°13'45" EAST, 361.43 FEET TO THE NORTHERLY RIGHT OF WAY LINE OF SW NYBERG ROAD (COUNTY ROAD NO. 2545)(VARIABLE WIDTH);

THENCE ALONG SAID NORTHERLY RIGHT OF WAY LINE SOUTH 89°46'15" WEST, 203.68 FEET;

THENCE SOUTH 44°46'46" WEST, 110.68 FEET;

THENCE SOUTH 82°09'15" WEST, 343.77 FEET;

W:\21198310\Survey\Legal Descriptions\9831-SUR-LEGAL-OVERALL.doc

LEGAL DESCRIPTION
Nyberg II 21198310
Boundary Description
May 31, 2013
Page 2 OF 5

THENCE SOUTH 89°46'15" WEST, 497.24 FEET TO A POINT ON THE EASTERLY RIGHT OF WAY LINE OF SW MARTINAZZI AVENUE, 15.00 FEET FROM THE CENTERLINE THEREOF, WHEN MEASURED PERPENDICULAR THERETO;

THENCE ALONG SAID EASTERLY RIGHT OF WAY LINE NORTH 07°41'07" WEST, 183.49 FEET TO THE SOUTHWEST CORNER OF THAT TRACT OF LAND DESCRIBED IN BOOK 773, PAGE 872, WASHINGTON COUNTY DEED RECORDS , TO THE CITY OF TUALATIN (TUALATIN TRACT);

THENCE ALONG THE NORTHERLY LINE OF SAID TUALATIN TRACT NORTH 89°46'15" EAST, 206.44 FEET TO THE SOUTHEAST CORNER OF SAID TUALATIN TRACT;

THENCE ALONG THE EASTERLY LINE OF SAID TUALATIN TRACT NORTH 07°41'07" WEST, 206.02 FEET TO THE SOUTHEAST CORNER OF THAT TRACT OF LAND DESCRIBED AS PARCEL I, IN BOOK 709, PAGE 82, SAID COUNTY RECORDS;

THENCE ALONG THE EASTERLY LINE OF SAID PARCEL I, AND THE EASTERLY LINE OF THAT TRACT OF LAND DESCRIBED IN DEED TO TUALATIN FIRE PROTECTION DISTRICT IN BOOK 751, PAGE 314, SAID DEED RECORDS, AND A PORTION OF THE EASTERLY LINE OF THAT TRACT OF LAND DESCRIBED IN BOOK 714, PAGE 436, SAID DEED RECORDS, NORTH 04°17'34" EAST, 376.00 FEET TO THE SOUTHERLY LINE OF THAT TRACT OF LAND DESCRIBED IN DEED DOCUMENT NO. 2004-022480, SAID DEED RECORDS;

THENCE ALONG THE SOUTHERLY LINE OF SAID DEED DOCUMENT NO. 2004-022480, SOUTH 85°42'26" EAST, 578.02 FEET TO THE WESTERLY LINE OF SAID PARCEL I, PARTITION PLAT NO. 1993-123;

THENCE ALONG SAID WESTERLY LINE NORTH 05°34'18" EAST, 244.44 FEET TO THE NORTHERLY LINE OF SAID PARCEL I;

THENCE ALONG SAID NORTHERLY LINE SOUTH 83°06'05" EAST, 70.20 FEET;

THENCE SOUTH 89°16'30" EAST, 118.95 FEET;

THENCE NORTH 78°06'38" EAST, 47.99 FEET;

THENCE NORTH 63°03'09" EAST, 102.02 FEET;

THENCE NORTH 61°05'09" EAST, 113.50 FEET;


THENCE NORTH 43°58'54" EAST, 73.56 FEET;

LEGAL DESCRIPTION
Nyberg II 21198310
Boundary Description
May 31, 2013
Page 3 OF 5



THENCE NORTH 35°38'54" EAST, 211.29 FEET;
THENCE NORTH 37°11'23" EAST, 115.37 FEET;
THENCE NORTH 32°54'07" EAST, 136.68 FEET;
THENCE NORTH 47°49'30" EAST, 114.34 FEET;
THENCE NORTH 63°23'23" EAST, 123.30 FEET;
THENCE NORTH 70°19'41" EAST, 70.09 FEET;
THENCE 78°48'21" EAST, 74.52 FEET TO THE POINT OF BEGINNING.

CONTAINS 1,248,324 SQUARE FEET OR 28.658 ACRES, MORE OR LESS.

THE ATTACHED EXHIBIT "B" ENTITLED "BOUNDARY EXHIBIT" IS MADE A PART HEREOF.



SCALE: 1"=200'




PORTLAND
5415 SW WESTGATE DR, STE 100, PORTLAND, OR 97221
TEL: (503) 419-2500 FAX: (503) 419-2500
www.cardno.com


EXHIBIT "B" BOUNDARY EXHIBIT

S 24, T 2 S., R 1 W., WILLAMETTE MERIDIAN
WASHINGTON COUNTY, OREGON


PROJECT NO. 21198310
DATE: 5/29/2013
BY: EDL
SCALE: 1"=200'
PAGE **NO. 4** OF 5
Attachment G



SCALE: 1"=200'




TUALATIN RIVER



DOC. NO.
2004-022480

PARCEL 1
PARTITION PLAT
1993-123



Cardno
Shaping the Future
PORTLAND
5415 SW WESTGATE DR, STE 100, PORTLAND, OR 97221
TEL: (503)-419-2500 FAX: (503)-419-2600
www.cardno.com

EXHIBIT "B"
BOUNDARY EXHIBIT

S 24, T 2 S., R 1 W., WILLAMETTE MERIDIAN
WASHINGTON COUNTY, OREGON

PROJECT NO. 21198310
DATE: 5/29/2013
BY: EDL
SCALE: 1"=200'
PAGE NO. 5 OF 5

Exhibit 1
Attachment G

Exhibit "A"

LEGAL DESCRIPTION
Nyberg II 21198310
McBale Boundary Description
May 31, 2013
Page 1 OF 2

THAT TRACT OF LAND DESCRIBED IN DEED DOCUMENT NO. 2004-135929, WASHINGTON COUNTY DEED RECORDS, LOCATED IN THE NORTHEAST QUARTER OF SECTION 24, TOWNSHIP 2 SOUTH, RANGE 1 WEST, WILLAMETTE MERIDIAN, CITY OF TUALATIN, WASHINGTON COUNTY, OREGON, BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT THE SOUTHWEST CORNER OF SAID DEED DOCUMENT NO. 2004-135929, THENCE ALONG THE WESTERLY LINE OF SAID DEED DOCUMENT NORTH $00^{\circ}13'45''$ WEST, 361.43 FEET TO THE NORTHWEST CORNER THEREOF;

THENCE ALONG THE NORTHERLY LINE OF SAID DEED DOCUMENT NORTH $89^{\circ}46'15''$ EAST, 374.82 FEET TO A POINT ON THE WESTERLY RIGHT OF WAY LINE OF THE SOUTHBOUND LANE OF INTERSTATE HIGHWAY NO. 5, SAID POINT BEING 154.33 FEET WESTERLY OF THE CENTERLINE THEREOF, WHEN MEASURED PERPENDICULAR THERETO;


THENCE ALONG SAID WESTERLY RIGHT OF WAY LINE SOUTH $21^{\circ}33'44''$ WEST, 113.08 FEET;

THENCE SOUTH $31^{\circ}00'49''$ WEST, 299.93 FEET TO THE NORTHERLY RIGHT OF WAY LINE OF SW NYBERG ROAD (COUNTY ROAD NO. 2545)(VARIABLE WIDTH);

THENCE ALONG SAID NORTHERLY RIGHT OF WAY LINE SOUTH $89^{\circ}46'15''$ WEST, 177.28 FEET TO THE POINT OF BEGINNING.

CONTAINS 102,557 SQUARE FEET OR 2.354 ACRES, MORE OR LESS.

THE ATTACHED EXHIBIT "B" ENTITLED "BOUNDARY EXHIBIT" IS MADE A PART HEREOF.



SCALE: 1" = 100'






EXHIBIT "B"
BOUNDARY EXHIBIT

S 24, T 2 S., R 1 W., WILLAMETTE MERIDIAN
WASHINGTON COUNTY, OREGON



Nyberg Rivers

Aerial - Community Scale



Tualatin, Oregon

EXHIBIT
Attachment H



August 20, 2013

Korey Derrick
Project Designer
Cardno
5415 SW Westgate Drive
Suite 100
Portland, OR 97221

Re: Nyberg Rivers Mixed Solid Waste Plan

Dear Derrick;

Thank you, for sending us the site plans for this development located in Tualatin.

My Company: Republic Services of Clackamas & Washington Counties has the franchise agreement to service this area with the City of Tualatin. We will be able to continue to provide complete commercial waste removal services and recycling services as needed on a weekly basis for this location.

The plans for the enclosures look good and are accessible for my trucks too service. Please allow the gates to open over 90 degrees degrees, and be able to lock in an open position. No center pole in opening of enclosure. Thanks!

Sincerely,

Frank J. Lonergan
Operations Manager
Republic Services



10295 SW Ridder Road
Wilsonville, OR 97070
503-570-0626 • Fax 503-570-0523
republicservices.com

Exhibit 1
Attachment I

| | |
|--------------|----------|
| PROJECT NO.: | 21-10013 |
| DATE: | 02/20/23 |
| DESIGNED BY: | RDS |
| DRAWN BY: | KEO |
| CHECKED BY: | JBC |

**TRASH
 EXHIBIT**

EX-1
 Attachment 1




NW 1/4 SECTION 24 T2S RIW W.M.

WASHINGTON COUNTY OREGON

SCALE 1"=200'

2S | 24B

CANCELLED TAX LOTS
2003 004445.00, 1001.000
2003 004446.00, 1001.000
2003 004447.00, 1001.000
2003 004448.00, 1001.000
2003 004449.00, 1001.000
2003 004450.00, 1001.000



TUALATIN
2S | 24B

NE 1/4 SECTION 24 T2S R1W W.M.

WASHINGTON COUNTY OREGON

SCALE 1"=200'

2S 1 24A

CANCELLED TAX LOT NUMBERS
2400-2500, 2501-2600, 2601-2700, 2701-2800, 2801-2900, 2901-3000, 3001-3100, 3101-3200, 3201-3300, 3301-3400, 3401-3500, 3501-3600, 3601-3700, 3701-3800, 3801-3900, 3901-4000, 4001-4100, 4101-4200, 4201-4300, 4301-4400, 4401-4500, 4501-4600, 4601-4700, 4701-4800, 4801-4900, 4901-5000, 5001-5100, 5101-5200, 5201-5300, 5301-5400, 5401-5500, 5501-5600, 5601-5700, 5701-5800, 5801-5900, 5901-6000, 6001-6100, 6101-6200, 6201-6300, 6301-6400, 6401-6500, 6501-6600, 6601-6700, 6701-6800, 6801-6900, 6901-7000, 7001-7100, 7101-7200, 7201-7300, 7301-7400, 7401-7500, 7501-7600, 7601-7700, 7701-7800, 7801-7900, 7901-8000, 8001-8100, 8101-8200, 8201-8300, 8301-8400, 8401-8500, 8501-8600, 8601-8700, 8701-8800, 8801-8900, 8901-9000, 9001-9100, 9101-9200, 9201-9300, 9301-9400, 9401-9500, 9501-9600, 9601-9700, 9701-9800, 9801-9900, 9901-10000.

COUNTY

FOR ASSESSMENT PURPOSES ONLY
DO NOT RELY ON FOR ANY OTHER USE


SEE MAP
2S 1 24AA

SEE MAP
2S 1 24AB

SEE MAP
2S 1 24B

SEE MAP
2S 1 24A

SEE MAP
2S 1 24DB



2S124BC01701
AMCO TUALATIN LLC
BY WYSE INVESTMENT SERVICES CO
1501 SW TAYLOR ST STE 100
PORTLAND, OR

2S124BC06800
BELL ROBERT P & SUZANNE
22605 PINEHURST DR
SHERWOOD, OR

2S124BC02700
BLUMENKRON RACHEL & FRANK
BY STEPHENS & ASSOC
PO BOX 90427
PORTLAND, OR
2S124BC08000

BROSMAN WAYNE H & BRIDGITTE
18710 SW BOONES FERRY RD
TUALATIN, OR

2S124BC07900
CHALUPNY CAROLINE
18720 SW BOONES FERRY RD
TUALATIN, OR

2S124AB00800
CLUBSPORT OREGON LLC
18120 SW LOWER BOONES FY RD
TIGARD, OR

2S124CB00204
COPPER MOUNTAIN TRUST CORP
BY QUEST PROPERTY MGMT
1 SW COLUMBIA ST #435
PORTLAND, OR

2S124AA05400
CUSICK LARRY & JUDY A
7190 SW CHILDS RD
LAKE OSWEGO, OR

2S124BC01502
DIERINGER'S PROPERTIES INC
10505 SE 44TH AVE
MILWAUKIE, OR

2S124AA01601
ELLIS DAVID &
WARD CECILIA
6956 SW CHILDS RD
LAKE OSWEGO, OR

2S124AA02900
ANDUEZA ANA I
2231 NE HALSEY ST
PORTLAND, OR

2S124CB90000
BEN LAKE CONDOMINIUM
OWNERS OF UNITS

2S124AB01301
BOONES BUILDING LLC
7007 SW CARDINAL LN #185
PORTLAND, OR

2S124AB01500
CAILEY PROPERTIES LLC
PO BOX 4223
TUALATIN, OR

2S124AA03900
CHEN RENBO
16869 65TH AVE #360
LAKE OSWEGO, OR

2S124AA04800
COLUMBIA REAL ESTATE SERVICES LL
4214 SW 51ST PL
PORTLAND, OR

2S124AA86882
COURTIS MARY
6882 MONTAUK CIR
LAKE OSWEGO, OR

2S124AA02000
CUSICK LARRY G
7190 SW CHILDS RD
LAKE OSWEGO, OR

2S124AA66931
DUDA IRENE E
6931 MONTAUK CIR
LAKE OSWEGO, OR

2S124AB00500
ESG INVESTMENTS LLC
BY DEERING MGMT GROUP INC
4800 SW MACADAM AVE STE 120
PORTLAND, OR

2S124AB01600
AXIOM INDUSTRIES INC
P O BOX 1147
TUALATIN, OR

2S113DC02100
BLASER JOHN E & LORETTA
10555 SW LANCASTER RD
PORTLAND, OR

2S124BC07300
BRASHEAR GARY T
8175 SW SENECA ST
TUALATIN, OR

2S124CB00201
CENTURY HOTEL LLC
4601 NE 78TH ST STE 130
VANCOUVER, WA

2S124AA03500
CHILDS BARBARA C
PO BOX 90
OCEANSIDE, OR

2S124AA96928
CONNER GARY TIMOTHY
6928 SW MONTAUK CIR
LAKE OSWEGO, OR

2S124BC01301
CSB LLC
PO BOX 2708
ISSAQUAH, WA

2S124BC07000
DAVISON JAMES E
8145 SW SENECA #4
TUALATIN, OR

2S124AB01701
DURHAM CITY OF
17160 SW UPPER BOONES FY RD
PORTLAND, OR

2S124AA66929
FAHRENDORF JOSEPH B &
FAHRENDORF JANET M
1143 MANOR DR
SONOMA, CA

**Exhibit 1
Attachment K**

| | | |
|---|---|--|
| 2S124AA70000 FALCON RUN CONDO OWNERS OF ALL UNITS | 2S124A002800 FOREST RIM INVESTORS LP BY GERSON BAKAR & ASSOCIATES 201 FILBERT ST 7TH FL SAN FRANCISCO, CA 2S124CB90021 GIONET LEONARD A TRUST 1502 SW MONTGOMERY PORTLAND, OR | 2S124DB00100 G&S FAMILY LTD PARTNERSHIP THE 20752 SW 120TH AVE TUALATIN, OR |
| 2S124AA04500 GIBBS CATHLEEN & GIBBS JAMES 11621 SE 222ND AVE DAMASCUS, OR 2S124AA77200 GRIFFITHS ROBERT 19748 WILDWOOD DR WEST LINN, OR | 2S124AA02600 GUIDER ROBERT S TRUST BY GUIDER ROBERT S TR 17 LOCKE WAY SCOTTS VALLEY, CA 2S124AA05100 HARRIS DENISE BY ARTHUR WINN PROPERTY SERVICES 10121 SE SUNNYSIDE RD #300 CLACKAMAS, OR | 2S124AA04900 GRANT EUGENE L & JANET K 11311 SE CHARVIEW CT CLACKAMAS, OR |
| 2S124BC05900 HARDEN ROBERT C 8285 SW SENECA ST TUALATIN, OR | 2S124AA66927 HILLER PHILIP J & HILLER TRACEE R 16590 SW WOODCREST AVE TIGARD, OR 2S124AA50010 HOLLMAN PROPERTIES LLC 3161 SW RIVERFRONT TER WILSONVILLE, OR | 2S124BC01503 HABERMAN PROPERTIES LLC PO BOX 1562 BEAVERTON, OR |
| 2S124BC00800 HEDGES MEADOW LLC 22830 SW ENO PL TUALATIN, OR | 2S124AA03800 I & A CORP PO BOX 82002 PORTLAND, OR | 2S124AA01900 HARVEY ROBERT E REV LIV TRUST 10460 SW WINDWOOD WAY PORTLAND, OR |
| 2S124BC07200 HO SON & TRAN HA 19905 SW 58TH TER TUALATIN, OR 2S124AA02700 HUNTER NANCY H REV LIV TRUST 19 BLOCH TER LAKE OSWEGO, OR | 2S124AA00600 HILLSBORO MALL LLC BY ERIC LINDGREN PO BOX 1681 GIG HARBOR, WA 2S124AA04600 HUNT TROY E 8170 SW 87TH PORTLAND, OR | 2S113DC02200 INTERNATIONAL CHURCH OF THE FOUR SQUARE GOSPEL PO BOX 1027 TUALATIN, OR 2S124BC00901 JONATHAN & JOANNE CRANE LLC PO BOX 1935 TUALATIN, OR |
| 2S124AA04000 IRONSIDE METAL CORPORATION 3210 VETERAN AVE LOS ANGELES, CA | 2S124B001007 JEWELL ATTACHMENTS LLC ATTN: LUANNE PELTON 18135 SW BOONES FERRY RD PORTLAND, OR | 2S124BC01300 KAPLAN GORDON & KAPLAN FAMILY TRUST 1025 NW COUCH ST #611 PORTLAND, OR |
| 2S124BC05700 JONES KEITH N 8305 SW SENECA ST TUALATIN, OR | 2S124AA77206 JOREK KRISTEN 7206 SW MONTAUK CIR LAKE OSWEGO, OR | 2S124BC01802 KILHEFNER MARY JANE PO BOX 67049 PORTLAND, OR |
| 2S124AA03700 KENNEDY EILEEN 199 W STERLING POND THE WOODLANDS, TX | 2S124AA02100 KENNEDY KARA M 10127 SE CAMBRIDGE LN MILWAUKIE, OR | |

| | | |
|---|--|---|
| 2S124AA03000 KURZ FRANK J & MARY W 5450 SE 40TH AVE PORTLAND, OR | 2S124BC05800 LARSEN DINAH W TRUST PO BOX 623 TUALATIN, OR | 2S124BC07600 LECLAIRE MOLLIE J 18750 SW BOONES FERRY RD TUALATIN, OR |
| 2S124AB01700 LOGOS ASSOCIATES LTD PARTNERSHIP BY THOMSON REUTERS (PROPERTY TAX SE 2235 FARADAY AVE #0 CARLSBAD, CA 2S124CB02600 MARTINAZZI SQUARE LLC BY API/PICHON VIII LLC 112 THIRD ST LAKE OSWEGO, OR 2S124AA80000 MEADOWLARK RUN CONDO OWNERS OF ALL UNITS | 2S124AA04400 LU LAN 20801 NW ROCKSPRING LN BEAVERTON, OR 2S124AA86886 MCCAGHREN KARIN A 6886 SW MONTAUK CIR LAKE OSWEGO, OR 2S124AA96926 MERLO-FLORES VALERIA 6926 SW MONTAUK CIR LAKE OSWEGO, OR | 2S124AA86880 MANNING LINDA L 6880 SW MONTAUK CIR LAKE OSWEGO, OR 2S124BC06000 MEADE PAUL J 17667 SW 80TH PL PORTLAND, OR 2S124CA00200 METROPOLITAN LIFE INS CO BY FRED MEYER INC STORE #393 1014 VINE ST CINCINNATI, OH 2S124AA04100 MINOR MARYLUE & MINOR J WARDEN & ELIOT QUINN & 16890 SW CAMINO DR KING CITY, OR 2S124BC06700 MORLAN SUSAN E 6510 SE 32ND AVE PORTLAND, OR |
| 2S124BC07400 MEWS AT THE COMMONS HOMEOWNERS ASSOCIATION 4934 SE WOODSTOCK PORTLAND, OR 2S124AA01500 MOHR JOHN H & DEERING-MOHR LORI 6950 SW CHILDS RD LAKE OSWEGO, OR 2S124BC05600 MROCKIEWICZ JACQUELINE 8315 SW SENECA ST TUALATIN, OR | 2S124BC06200 MILTON NANCY E 8255 SW SENECA ST TUALATIN, OR 2S124AA03200 MONTAUK LLC BY FIFTH & C LLC 1795 PALISADES TERRACE DR LAKE OSWEGO, OR 2S124B001500 NELSON ROSCOE C JR 1 SW COLUMBIA #1620 PORTLAND, OR 2S124AA96930 NOUGUIER MARK A 6930 SW MONTAUK CIR LAKE OSWEGO, OR | 2S124BC05500 NOREEN LLC 2625 NW 205TH ST SHORELINE, WA 2S124CB00202 NW MOJO III LLC 12012 SE WILLOW OTTY RD HAPPEY VALLEY, OR |
| 2S113DD01000 NORTHWEST NATURAL GAS CO 220 NW SECOND AVE PORTLAND, OR | 2S124DB00400 NYBERG CREEK FOUNDATION LLC BY JOHN C NYBERG 21840 NE SUNNYCREST RD NEWBERG, OR 2S124CB90011 OREGON EVERGREEN & HOLLY LAND AND FARM 23544 SW GAGE RD WILSONVILLE, OR | 2S124BC06900 OLSON LARENE REVOCABLE TRUST BY OLSON LARENE TR 8135 SW SENECA ST TUALATIN, OR 2S124B001000 PACIFIC REALTY ASSOCIATES ATTN: N PIVEN 15350 SW SEQUOIA PKWY #300 PORTLAND, OR |

| | | |
|--|---|---|
| 2S124BC05400 PHILLIPS LEONARD JOHN PO BOX 4421 TUALATIN, OR | 2S124BC07800 PROUTY KATHRYN L 18730 SW BOONES FERRY RD TUALATIN, OR | 2S113DC01200 PROVIDENCE HEALTH SYSTEM-OREGON ATTN: REAL ESTATE & PROPERTY MANAGE 4400 NE HALSEY BLDG 1 #160 PORTLAND, OR 2S124AA86884 ROBERTS WAYNE V & SHERI REVOCABLE LIVING TRUST 3100 SW SCHAEFFER RD WEST LINN, OR 2S124AA01700 SANTORSOLA MICHAEL R & SANTORSOLA MICHAEL J 901 WHITEHAVEN TER GLENDALE, CA 2S124BC01708 SEE PROPERTIES 1100 SW 6TH AVE #1425 PORTLAND, OR |
| 2S124AA90000 QUAIL RUN CONDO OWNERS OF ALL UNITS | 2S124B001300 ROBB MARGUERITE A PO BOX 31 TUALATIN, OR | 2S124BC01500 SOFT TOUCH DENTISTRY PC BY DANNY SADAKAH 1301 NE BROADWAY PORTLAND, OR 2S124AB00700 SUMMIT PROPERTIES INC 5550 SW MACADAM BLVD #205 PORTLAND, OR |
| 2S124AA77204 ROBERTS WAYNE V & SHERL REV LIV c/o THORPE TOM & 7204 SW MONTAUK CIR LAKE OSWEGO, OR 2S124BC08200 SCHMAUDER JOHNNIE E & SCHMAUDER LATIESIA J 18690 SW BOONES FY RD TUALATIN, OR 2S124BC02701 SENECA PLAZA LLC 3380 BARRINGTON DR WEST LINN, OR | 2S124CB01700 S & T SPOSITO LIVING TRUST c/o BISACCIO GARY & PAULA 5283 SW 201ST AVE ALOHA, OR 2S124AA02400 SD @ PIPERS'S RUN LLC 3750 SAINT ANDREWS DR SANTA ROSA, CA | 2S124AA05300 TENNIS JON B & TERRI PO BOX 231 WEST LINN, OR |
| 2S124AA60000 SPARROW RUN CONDOMINIUM ASSN | 2S124BC07500 SMITH JAMES S 18760 SW BOONES FERRY RD TUALATIN, OR | 2S124AA05200 THOMAS THOMAS M 19000 NW EVERGREEN PKWY #265 HILLSBORO, OR |
| 2S124AA02500 SUSSMAN MARC REV LIV TRUST & JOHNSON JUDY REV LIV TRUST 5908 SW KNIGHTS BRIDGE DR PORTLAND, OR 2S124AA05200 THOMAS THOMAS M 19000 NW EVERGREEN PKWY #265 HILLSBORO, OR | 2S124AA04300 STECKLEY FAMILY TRUST THE BY LE NOI W STECKLEY TR 1560 NW 116TH AVE PORTLAND, OR 2S124BC05300 SZABO PAMELA H & FERNANDO A 8345 SW SENECA ST TUALATIN, OR | 2S124A002503 TUALA NORTHEAST LLC 5638 DOGWOOD DR LAKE OSWEGO, OR |
| 2S124CA00100 TUALATIN GARDENS PROPERTY LLC 5638 SW DOGWOOD LN LAKE OSWEGO, OR | 2S124CD01000 TUALATIN HOTEL PARTNERS LLC 5809 JEAN RD LAKE OSWEGO, OR | 2S124CB00100 TUALATIN DEVELOPMENT COMM URBAN RENEWAL AGENCY 18880 SW MARTINAZZI AVE TUALATIN, OR 2S124BC01801 TUALATIN OFFICE BUILDING 1 LLC PO BOX 2985 TUALATIN, OR |

2S124BC05001
TUALATIN TWIN CINEMA
3380 BARRINGTON DR
WEST LINN, OR

2S124BC06300
VILLAS ON THE LAKE
OWNERS OF LOTS 1-10

2S124AA77202
WARBERG JIM
PO BOX 2287
LAKE OSWEGO, OR

2S124AA01800
WHEELLOCK ZEBUNNISA M
7140 SW CHILDS RD
LAKE OSWEGO, OR

2S124BC04700
WINONA GRANGE 271
BY REO BACON SECRETARY
7735 SW NORSE HALL ROAD
TUALATIN, OR

Jan Giunta
17655 SW Shawnee Trail
Tualatin, OR

Doug Ulmer
7149 SW Sagert St., Unit 105
Tualatin, OR

Stefan Feuerherdt
9930 SW Killarney Ln
Tualatin, OR

Scott Alvey
20900 SW Teton Ave.
Tualatin, OR

Alan Campbell
8728 SW Palmico
Tualatin, OR

2S124AA03600
USHER BRENT D & WENDY E
814 SE LEXINGTON ST
PORTLAND, OR

2S124BC08300
VILLAS ON THE LAKE NO.2
HOMEOWNERS ASSOCIATION

2S124AB01300
WASHINGTON COUNTY
FACILITE MGMT
169 N FIRST AVE #42
HILLSBORO, OR
2S124BC06100
WHERITY KATHLEEN R
8265 SW SENECA ST
TUALATIN, OR

2S124AB01400
WOÉ PROPERTIES LTD PARTNERSHIP
PO BOX 2009
BELLEVUE, WA

Cindy Phillips
P.O. Box 2601
Tualatin, OR

Charlie Benson
5915 SW Sequoia Dr.
Tualatin, OR

Jim Muir
9850 SW Avery Street
Tualatin, OR

Deb Maryanov
8768 SW Iroquois Dr.
Tualatin, OR

Linda Loop
21090 SW 86th Ct.
Tualatin, OR

2S124AA03100
VERHEY CLIFFORD J &
VERHEY MARCIA K
PO BOX 721
LAKE OSWEGO, OR
2S124BC06400
VILLAS ON THE LAKE NO.I HOMEOWNE
VILLAS ON THE LAKE NO.II HOMEOWNERS

2S124BC02702
WELLS FARGO BANK NA
BY DELOITTE TAX LLP
PO BOX 2609
CARLSBAD, CA
2S124BC07700
WILLMAN BRIAN M
18740 SW BOONES FERRY RD
TUALATIN, OR

2S124BC08100
WOO WON HO
18700 SW BOONES FERRY RD
TUALATIN, OR

Toni Anderson
17790 Cheyenne Way
Tualatin, OR

Alex Simshaw
10198 SW Siletz Drive
Tualatin, OR

Tammy Palumbo
9510 SW Siuslaw Ln
Tualatin, OR

Kay Dix
8777 SW Parnlico Court
Tualatin, OR

Melinda Wittman
8794 SW Iroquois Dr
Tualatin, OR

Robert E. Kellogg
9412 SW Arikara Dr.
Tualatin, OR

Erik Johannes
11016 SW Oneida St.
Tualatin, OR

Nic Herriges
27420 SW Grahams Ferry Rd.
Tualatin, OR

Julie Makarowsky
10775 SW Willow St.
Tualatin, OR

Jonathan Crane
21890 SW 103rd Ct.
Tualatin, OR

Willie Fisher
22445 SW Chilkat Terrace
Tualatin, OR

Steve Caporale
21497 SW 92nd Court
Tualatin, OR

Chris Burchill
22435 SW Martinazzi
Tualatin, OR

Peggy Fisher
22445 SW Chilkat Terrace
Tualatin, OR

Jonathan Crane
PO Box 1935
Tualatin, OR

Ron Audette
7455 SW Bridgeport Rd., Ste 205
Tigard, OR

Cheryl Dorman
8805 SW Tualatin-Sherwood Rd.
Tualatin, OR

Cathy Holland
10740 SW Lucas Dr.
Tualatin, OR

Christine Tunstall
17400 SW Cheyenne Way
Tualatin, OR

Transportation Impact Analysis

Nyberg Rivers

Tualatin, Oregon

April 2013



KITTELSON & ASSOCIATES, INC.
TRANSPORTATION ENGINEERING/PLANNING

Transportation Impact Analysis

Nyberg Rivers TIA

Tualatin, Oregon

Prepared For:
CenterCal Properties
1600 E. Franklin Avenue
El Segundo, CA 90245

Prepared By:
Kittelsohn & Associates, Inc.
610 SW Alder, Suite 700
Portland, OR 97205
(503) 228-5230

Project No. 12116

April 2013



TABLE OF CONTENTS

| | |
|--------------------------------------|----|
| Executive Summary..... | 2 |
| Introduction | 7 |
| Existing Conditions..... | 12 |
| Transportation Impact Analysis | 24 |
| Conclusions and Recommendations..... | 53 |



LIST OF FIGURES

| | | |
|--------------|---|----|
| Figure 1: | Site Vicinity Map | 8 |
| Figure 2: | Redevelopment Site Plan | 9 |
| Figure 3a: | Existing Lane Configurations and Traffic Control Devices | 13 |
| Figure 3b: | Roadway Ownership Map..... | 14 |
| Figure 4a: | Year 2012 Existing Traffic Conditions, Weekday PM Peak Hour | 18 |
| Figure 4b: | Year 2012 Existing Traffic Conditions, Saturday Midday Peak Hour | 19 |
| Figure 5a: | Year 2014 Background Traffic Conditions, Weekday PM Peak Hours | 26 |
| Figure 5b: | Year 2014 Background Traffic Conditions, Weekday PM Peak Hours | 27 |
| Figure 6: | Assumed Site Access Configurations and Traffic Control Devices | 31 |
| Figure 7: | Estimated Trip Distribution Pattern..... | 34 |
| Figure 8aA: | Estimated Year 2014 Site-Generated (Added) Traffic Volumes, Weekday PM Peak Hour | 36 |
| Figure 8aPB: | Estimated Year 2014 Site-Generated (Pass-by) Traffic Volumes, Weekday PM Peak Hour | 37 |
| Figure 8bA: | Estimated Year 2014 Site-Generated (added) Traffic Volumes, Saturday Midday Peak Hour | 38 |
| Figure 8bPB: | Estimated Year 2014 Site-Generated (Pass-by) Traffic Volumes, Saturday Midday Peak Hour | 39 |
| Figure 9a: | Year 2014 Total Traffic Conditions, Weekday PM Peak Hour..... | 40 |
| Figure 9b: | Year 2014 Total Traffic Conditions, Saturday Midday Peak Hour..... | 41 |
| Figure 10: | Alternative Site Access Configuration and Traffic Control Devices | 46 |
| Figure 11a: | Year 2014 Total Traffic Conditions, Alternative Access Configuration, Weekday PM Peak Hour | 47 |
| Figure 11b: | Year 2014 Total Traffic Conditions, Alternative Access Configuration Saturday Midday Peak Hour | 48 |



LIST OF TABLES

| | | |
|-----------|--|----|
| Table 1: | Existing Transportation Facilities | 15 |
| Table 2: | 2012 Existing Conditions Operations Summary..... | 17 |
| Table 3: | Existing Daily Traffic Volumes on Select Roadway Segments..... | 20 |
| Table 4: | Intersection Crash History (January 1, 2009 through December 31, 2011) | 22 |
| Table 5: | Historical Traffic Counts | 24 |
| Table 6: | 2014 Background Traffic Conditions..... | 28 |
| Table 7: | 2014 Background Daily Traffic Profile..... | 29 |
| Table 8: | Estimated Nyberg Rivers Trip Generation | 33 |
| Table 9: | 2014 Total Traffic Operations | 42 |
| Table 10: | 2014 Total Daily Traffic Profile..... | 43 |
| Table 11: | Estimated 95 th Percentile Queuing Analysis | 44 |
| Table 12: | SW Martinazzi Avenue/SW Seneca Street Intersection Mitigation (2014 Total Traffic Conditions) | 49 |

Section 1
Executive Summary

EXECUTIVE SUMMARY

CenterCal Properties, LLC is proposing to redevelop a portion of an existing Tualatin retail center located in the northwest quadrant of the I-5/Nyberg Road interchange. The redevelopment, known as Nyberg Rivers, will consist of a reconfiguration of portions of the larger existing shopping center site. The redevelopment plan includes demolition of existing buildings, construction of new retail pads, and the relocation of some existing uses. In addition, several access changes will be made to the site to better accommodate the estimated traffic volumes being generated by the redevelopment. When complete, the proposed redeveloped plan will consist of a maximum total of 307,000 square feet of retail space.

The transportation analysis demonstrates that the proposed Nyberg Rivers redevelopment project can be constructed while maintaining acceptable traffic operations and safety at the study intersections within the immediate site vicinity, assuming provision of the recommended mitigation measures.

FINDINGS

Year 2012 Existing Conditions

- All of the study intersections currently operate acceptably during the weekday p.m. and Saturday midday peak hours with the exception of the SW Martinazzi Avenue/SW Sagert Street and SW 65th Avenue/SW Sagert Road intersections.
 - At both the SW Martinazzi Avenue/SW Sagert Street and SW 65th Avenue/SW Sagert Street intersections, the southbound approach during the weekday p.m. peak hour operates at LOS F.

Year 2014 Background Traffic Conditions

- All of the study intersections are forecast to operate acceptably during the weekday p.m. and Saturday midday peak hours with the exception of SW Martinazzi Avenue/SW Sagert Road and SW 65th Avenue/SW Sagert Road intersections.
 - At both the SW Martinazzi Avenue/SW Sagert Street and SW 65th Avenue/SW Sagert Street intersections, the southbound approach during the weekday p.m. peak hour is forecast to continue to operate at LOS F. These findings are consistent with analysis conducted as part of the recent Tualatin Transportation System Plan (TSP) Update and future improvements are identified within the TSP for both of these intersections.



Proposed Redevelopment Plan

- Under the redevelopment plan, the existing SW 75th Avenue connection to SW Nyberg Road will be closed to improve access management along SW Nyberg Road and to better accommodate the redevelopment proposal.
- The existing signalized access on SW Nyberg Road that currently serves the shopping center and the adjacent Fred Meyer site will remain. However, the following changes are proposed in order to better accommodate the proposed redevelopment, provide additional capacity for future growth in traffic, and improve safety relative to the existing condition:
 - A westbound right-turn lane will be developed on SW Nyberg Road to enhance access to the site and minimize vehicle queuing on SW Nyberg Road.
 - The existing site driveway is proposed to be widened as shown in the proposed site plan. This widening will include dual southbound left-turn lanes, a shared through/right-turn lane, and dual in-bound receiving lanes. A raised median will be constructed in the driveway throat to reduce turning conflicts on-site turning maneuvers and manage vehicle queues on the approach to the signal.
 - The north and south approach signal phasing is proposed to be modified from permissive left-turn phasing to split phasing.
- With the anticipated mix of new retail uses, the proposed redevelopment is estimated to generate 405 net new trips during the weekday p.m. peak hour and 725 net new trips during the Saturday midday peak hour.

Year 2014 Total Traffic Conditions

- All of the study intersections within the immediate site vicinity, including the site access points and internal site intersections, are forecast to operate acceptably during the weekday p.m. and Saturday midday peak hours.
- The SW Martinazzi Avenue/SW Sagert Road and SW 65th Avenue/SW Sagert Road intersections are forecast to continue to operate at LOS F.
 - The proposed development will have an insignificant impact at either intersection, resulting in an estimated 1.6% and 0.6% increase, respectively, during the weekday p.m. peak hour.
 - The Tualatin TSP has identified mitigations for these two intersections that, when implemented, will address the long-term operations.
 - The Washington County Transportation Development Tax (TDT) in part funds an improvement project on SW Sagert Street that will add capacity and reduce delay to both intersections.
- Beyond the site's frontage along SW Tualatin Sherwood Road and SW Martinazzi Avenue, where significant transportation improvements are proposed (including implementing the



intent of the City's Loop Road), the project will have an insignificant impact on the other study intersections (generally resulting in less than a two percent increase in traffic relative to 2014 background conditions).

- At all signalized intersections beyond the site frontage (with the exception of the I-5 interchange), the project will add on average one vehicle or less per signal cycle to any movement. This level of impact is less than significant by any traffic engineering standard and well below the level that would be perceived by motorists.
- Anticipated vehicle queues can be accommodated at the I-5 ramp terminals and the SW Nyberg Road/Signalized site driveway.
- The proposed Nyberg Rivers redevelopment project has proposed an on-site roadway network that will meet the intent of the loop road connection. The proposal includes the following:
 - A new roadway connection to SW Boones Ferry Road (shown as "Street A" in Figure 2) that includes sidewalks.
 - An enhanced site-access driveway to SW Nyberg Road that will better accommodate vehicular queuing and demand.
 - A potential future (assuming the City desires to move forward) new site-access connection to SW Martinazzi Avenue that aligns across from SW Seneca Street. This connection would be the Seneca Street extension envisioned in the Town Center Plan. Prior to the City making a decision on any new SW Street Seneca alignment, the redevelopment site plan preserves this connection opportunity in the present or future.
 - The preservation of east-west and north-south travel ways that will provide vehicular and pedestrian access between Street A, the Seneca Street alignment/extension, and enhanced access to SW Nyberg Road.
 - New sidewalks along the enhanced site-access driveway to SW Nyberg Road that provide pedestrian connections to the integrated site circulation network.
 - New bikeway connections along the perimeter of the site.

SW Martinazzi Avenue and SW Boones Ferry Road Site Access Alternatives

- An alternative site access scenario was evaluated that demonstrates the impact of potentially adding a fourth leg (in the form of a site-access driveway) to the existing SW Martinazzi Avenue/SW Seneca Street intersection and closing the existing SW Martinazzi Avenue site driveway adjacent to the library. This analysis produced the following results:
 - The east and west approaches to a modified SW Martinazzi Avenue/SW Seneca Street intersection would operate at Level of Service (LOS) F and over capacity during the



weekday p.m. peak hour with the addition of a fourth site-access leg. Signalizing the intersection would provide the following:

- Mitigation that results in LOS A or better (a significant improvement over existing conditions).
 - Additional excess intersection capacity beyond what is needed to serve the Nyberg Rivers project traffic.
 - Enhanced east-west pedestrian connectivity across SW Martinazzi Avenue.
 - A safety improvement relative to stop sign control.
- In addition to the modified SW Martinazzi Avenue/SW Seneca Street intersection, another site-access alternative was evaluated that demonstrates the impacts of adding a limited access site-driveway to SW Boones Ferry Road. The analysis shows that with a direct connection to SW Boones Ferry Road, there would be some shifting of site-generated traffic off of SW Martinazzi Avenue. This additional access would further improve connectivity, help implement the City's loop road concept, and provide additional capacity beyond what is needed to serve the Nyberg Rivers project.

RECOMMENDATIONS

- With the proposed Nyberg Rivers redevelopment:
- The existing SW 75th Avenue site-access driveway to SW Nyberg Road should be closed in order to minimize turning movement conflicts, allow for the construction of a westbound right-turn lane at the SW Nyberg Road/signalized site driveway, and improve the interchange access spacing conditions along SW Nyberg Road.
 - To better accommodate the anticipated site-generated traffic at the SW Nyberg Road/Signalized site driveway:
 - A new westbound right-turn lane should be constructed on SW Nyberg Road.
 - The site driveway should be modified to include dual southbound left-turn lanes, a shared through/right-turn lane, and two inbound receiving lanes.
 - The existing north/south traffic signal phasing should be modified from permissive phasing to split phasing. Right-turn overlap phasing should be provided for the westbound right-turn movement into the Nyberg Rivers site.
- If site access to SW Martinazzi Avenue is provided via a new fourth leg to the SW Martinazzi Avenue/SW Seneca Street intersection, the intersection should be signalized.
- If a new site access driveway is provided to SW Boones Ferry Road, the driveway should be limited to right-in/right-out only access.



Section 2
Introduction

INTRODUCTION

PROJECT DESCRIPTION



CenterCal Properties, LLC is proposing to redevelop a portion of the existing Tualatin shopping center located in the northwest quadrant of the I-5/Nyberg Road interchange. The existing shopping center has been anchored by K-Mart and includes an assortment of other supporting retail uses such as drive-thru banks, fast-food restaurants, and small to medium miscellaneous retailers. The Tualatin City Hall and Library is also located within the boundary of the shopping center site, but on its own legal lot of record and in separate ownership than the shopping center. Figure 1 illustrates the location of the site in relationship to the larger regional vicinity.

In an effort to enhance and reinvigorate the existing shopping center, CenterCal is proposing to redevelop the center as shown in Figure 2. Known as the Nyberg Rivers project, the full redevelopment vision will entail the following components:

- The existing 96,799 square foot former K-Mart building will be removed.
- The existing 3,500 square foot building currently occupied by a Wendy's will be relocated to a new pad within the shopping center site.
- All other existing buildings will remain and it has been assumed that the existing tenants will continue to operate as-is for the foreseeable future.
- While a specific tenant mix is still being developed by CenterCal, it is envisioned that the redevelopment will include a large retailer and an assortment of small and medium-sized retail/restaurant uses. For the purposes of this traffic study, it has been assumed that this mix of uses will total approximately 245,456 square feet of new leasable area bringing the total net leasable square footage for the entire shopping center to 307,000.
- The existing SW 75th Avenue access to SW Nyberg Road is proposed to be closed.
- The existing signalized access on SW Nyberg Road that currently serves the shopping center will remain and continue to serve as the main entrance.
- All other shopping center driveways located off of SW Nyberg Road and SW Martinazzi Avenue will remain.
- While not required under this proposal, in consultation and cooperation with the City of Tualatin, the existing SW Martinazzi Avenue driveway (adjacent to the library/city hall) could close and alternative access could be provided via a new driveway across from SW Seneca Street. This option would only be pursued if it was with the mutual agreement of the City and on a timeline acceptable to the City.

Redevelopment construction is expected to begin in 2013 and with completion and full occupancy anticipated in 2014.






LEGEND

● - STUDY INTERSECTIONS

SITE VICINITY MAP TUALATIN, OREGON

FIGURE 1

H:\profile\12116 - K-Mart Tualatin Redevelopment\dwg\figs\April2013\12116_Fig01.dwg Apr 15, 2013 - 4:07pm - minughart Layout Tab: Fig01



PROJECT SUMMARY

| | |
|-------------------|--------------|
| NET AREA | 271 ACRES |
| NET BUILDING AREA | 1,817,000 SF |
| NET PARKING AREA | 1,817,000 SF |
| NET TOTAL AREA | 4,534,000 SF |
| NET BUILDING AREA | 1,817,000 SF |
| NET PARKING AREA | 1,817,000 SF |
| NET TOTAL AREA | 4,534,000 SF |
| NET BUILDING AREA | 1,817,000 SF |
| NET PARKING AREA | 1,817,000 SF |
| NET TOTAL AREA | 4,534,000 SF |

BUILDING AREA:

| | |
|--------|-----------|
| BLDG A | 271 ACRES |
| BLDG B | 271 ACRES |
| BLDG C | 271 ACRES |
| BLDG D | 271 ACRES |
| BLDG E | 271 ACRES |
| BLDG F | 271 ACRES |
| BLDG G | 271 ACRES |
| BLDG H | 271 ACRES |
| BLDG I | 271 ACRES |
| BLDG J | 271 ACRES |
| BLDG K | 271 ACRES |
| BLDG L | 271 ACRES |
| BLDG M | 271 ACRES |
| BLDG N | 271 ACRES |
| BLDG O | 271 ACRES |
| BLDG P | 271 ACRES |
| BLDG Q | 271 ACRES |
| BLDG R | 271 ACRES |
| BLDG S | 271 ACRES |
| BLDG T | 271 ACRES |
| BLDG U | 271 ACRES |
| BLDG V | 271 ACRES |
| BLDG W | 271 ACRES |
| BLDG X | 271 ACRES |
| BLDG Y | 271 ACRES |
| BLDG Z | 271 ACRES |

TOTAL PROVIDED STALL: 1,200 VEH
PARKING IN USE: 2,000 VEH
CONNECT: 7,200 VEH

NOTES:
 1) This site plan includes only the main building structure and parking areas. It does not include site-specific details such as landscaping, site furniture, or other site-specific details.
 2) The site plan is based on the information provided by the client and is subject to change without notice.
 3) The site plan is for informational purposes only and does not constitute a contract.

Nyberg Rivers **DRAFT**

Concept Plan - 19Vic - Dual Entry Lanes



Tualatin, Oregon

FIGURE 2
PROPOSED SITE PLAN
TUALATIN, OREGON

SCOPE OF THE REPORT

This analysis determines the transportation-related impacts associated with the proposed Nyberg Rivers redevelopment and was prepared in accordance with the City of Tualatin, Washington County, and Oregon Department of Transportation (ODOT) requirements for traffic impact studies. The study intersections and scope of this project were selected in consultation with City, County, and ODOT staff. Appendix A contains a copy of the traffic impact study scoping letter and feedback received from the agency staff. Based on this correspondence, this study contains the following elements:

- Year 2012 existing land-use and transportation-system conditions within the site vicinity during the weekday p.m. and Saturday midday peak periods;
- Forecast year 2014 background traffic conditions during the weekday p.m. and Saturday midday peak periods;
- Trip generation and distribution estimates for the proposed Nyberg Rivers redevelopment;
- Forecast year 2014 total traffic conditions during the weekday p.m. and Saturday midday peak periods with build-out of the site;
- Vehicle queuing operations at the Nyberg Road site access driveway and the I-5 off-ramps;
- On-site traffic operations and circulation; and
- Recommendations



Section 3
Existing Conditions

EXISTING CONDITIONS

The existing conditions analysis identifies the site conditions and current operational and geometric characteristics of the roadways within the study area. These conditions will be compared with future conditions later in this report.

Kittelson & Associates, Inc. (KAI) staff visited and inventoried the proposed Nyberg Rivers redevelopment site and surrounding study area. At that time, KAI collected information regarding site conditions, adjacent land uses, existing traffic operations, and transportation facilities in the study area.



SITE CONDITIONS AND ADJACENT LAND USES

As shown in Figure 1, the existing shopping center is located in the northwest quadrant of the I-5/Nyberg Road interchange in Tualatin. The shopping center is bounded by Nyberg Road to the south, I-5 to the east, SW Martinazzi Avenue to the west, and Boones Ferry Road/Tualatin River to the north. The shopping center currently consists of an unoccupied former K-Mart, two drive-thru banks, a fast-food restaurant, and an assortment of retail uses. In addition, the Tualatin City Hall, city administrative offices, and public library are located in the northwest portion of the shopping center site on City-owned property and a separate legal lot of record.

TRANSPORTATION FACILITIES

Table 1 identifies the characteristics of key roadways located within the vicinity of the redevelopment site. Figure 3a identifies the existing lane configurations and traffic control devices at all of the study intersections while Figure 3b identifies the study area roadway ownership.





LEGEND

- STOP SIGN
- TRAFFIC SIGNAL

EXISTING LANE CONFIGURATIONS AND TRAFFIC CONTROL DEVICES
 TUALATIN, OREGON
 FIGURE 3A

KITTELSON & ASSOCIATES, INC.
 TRANSPORTATION ENGINEERING / PLANNING

H:\projects\12116 - K-Mat1 Tualatin Redevelopment\ngs\figs\fig20121116_Fig01.dwg Apr 15, 2013 - 4:03pm - rnh\at Layout Tab: fig03A



LEGEND

- ODOT
- Washington County
- City of Tualatin

KITTELSON & ASSOCIATES, INC.
 TRANSPORTATION ENGINEERING / PLANNING

ROADWAY OWNERSHIP MAP
 TUALATIN, OREGON

FIGURE
3B

H:\profile\12116 - K-Mart Tualatin Redevelopment\dwg\figs\April2013\12116_Fig01.dwg Apr 15, 2013 - 4:09pm - mhughart Layout Tab: Fig03B

Table 1: Existing Transportation Facilities

| Roadway | Functional Classification (By Jurisdiction) | Number of Lanes | Posted Speed (mph) | Sidewalks | Bicycle Lanes | On-Street Parking |
|----------------------------|--|-----------------|--------------------|-----------|------------------|-------------------|
| I-5 | Interstate Highway - (ODOT) | 7-8 lanes | 55 | No | No | No |
| SW Nyberg Road | Arterial (east of T-S Road) - (Washington County) ¹ | 6 lanes | 30 | Yes | Yes | No |
| | Minor Collector (west of T-S Road) -- (Tualatin) | 2 lanes | 30 | Yes | No | No |
| Tualatin-Sherwood Road | Arterial -- (Washington County) | 5 lanes | 35 | Yes | No | No |
| SW Martinazzi Avenue | Minor Arterial (north of T-S Road) -- (Tualatin) | 3 lanes | NP | Yes | No | No |
| | Major Arterial (south of T-S Road) -- (Tualatin) | 5 lanes | 35 | Yes | No | No |
| Boones Ferry Road | Major Arterial (east of Martinazzi) -- (Tualatin) | 3 lanes | 35 | Yes | Yes | No |
| | Minor Arterial (west of Martinazzi) -- (Tualatin) | 3 lanes | 30 | Yes | Yes | No |
| | Major Arterial (south of Tualatin Road) -- (Tualatin) | 2-4 lanes | 30-35 | Yes | Yes | No |
| Lower Boones Ferry Road | Minor Arterial -- (Tualatin) | 3 lanes | 35 | Yes | Yes | No |
| Upper Boones Ferry Road | District Highway -- (ODOT) | 3 lanes | 35 | Yes | Yes | No |
| SW Seneca Street | Local Commercial -- (Tualatin) | 2 lanes | NP | Yes | No | No |
| SW 65 th Avenue | Major Arterial -- (Tualatin) | 3 lanes | 35 | Yes | No | No |
| SW Sagert Street | Major Arterial -- (Tualatin) (east of SW Martinazzi Ave) | 2-3 lanes | 35 ² | Yes | Yes | No |
| | Major Collector -- (Tualatin) (west of SW Martinazzi Ave) | | | | | |
| | Minor Arterial -- (Tualatin) (west of SW Boones Ferry Rd) | | | | | |
| SW Borland Rd | Major Arterial -- (Tualatin) | 2-3 lanes | 35 | Yes | Yes ³ | No |
| | Minor Arterial (Clackamas County) | | | | | |

Notes:

¹ ODOT has jurisdictional control over SW Nyberg Road within the vicinity of the northbound and southbound I-5 ramp terminals² 30 mph west of SW Martinazzi Avenue³ There are no bicycle lanes within the vicinity of the SW 65th Avenue intersection

NP = Not Posted

T-S Road = Tualatin-Sherwood Road

TRAFFIC VOLUMES AND PEAK HOUR OPERATIONS

In late May 2012 (while local schools were still in session), manual turning-movement counts were obtained for the all the study intersections and site driveways located within the immediate vicinity of the shopping center. In addition, traffic count data collected as part of the on-going Tualatin Transportation System Plan Update were utilized for all of the other study intersections¹. Figures 4a and 4b provide a summary of the existing turning-movement counts, which are rounded to the nearest five vehicles per hour for the weekday p.m. and Saturday midday peak hours. *Appendix "B" contains the traffic count worksheets used in this study.*

¹ Saturday midday counts were only collected at the site-access driveways and adjacent study area intersections.

Operational Standards

Level of service (LOS) and volume-to-capacity (V/C) ratio are the two performance measures utilized by the affected review agencies for determining intersection operations. A description of each is outlined below.

Level of Service

All level-of-service analyses described in this report were performed in accordance with the procedures stated in the 2000 *Highway Capacity Manual*. A description of level of service and the criteria by which they are determined is presented in Appendix "C". Appendix "C" also indicates how level of service is measured and what is generally considered the acceptable range of level of service. The City of Tualatin has adopted level-of-service standards for signalized and unsignalized intersections. LOS "D" is considered acceptable at signalized intersections and LOS "E" is considered acceptable at an unsignalized intersections.

V/C Ratio

The V/C ratio is a measure of an intersection's theoretical capacity. As the V/C ratio approaches 1.0, vehicle congestion worsens and the intersection becomes less capable of accommodating the vehicular demand. For all of the Washington County study intersections, the maximum acceptable V/C ratio is 0.99 during the first hour and 0.90 during second hour. For the ODOT study intersections, the minimum acceptable V/C ratio is 0.99.

All intersection level-of-service evaluations used the peak 15-minute flow rate during the weekday p.m. and Saturday midday peak hours. Using the peak 15-minute flow rate ensures that this analysis is based on a reasonable worst-case scenario. For this reason, the analysis reflects conditions that are only likely to occur for 15 minutes out of each average peak hour. The transportation system will likely operate under conditions better than those described in this report during all other time periods.

Figures 4a, 4b, and Table 2 summarize the operational performance for the study intersections under the existing peak hour conditions. As shown, all of the study intersections currently operate at acceptable levels of service and V/C ratios during the peak hours with the exception of the SW Martinazzi Avenue/SW Sagert Road and SW 65th Avenue/SW Sagert Road intersections. Appendix "D" includes the operational worksheets under year 2012 existing traffic conditions.

Table 2: 2012 Existing Conditions Operations Summary


| Number | Intersection | Maximum Operating Standard | Weekday PM Peak Hour | | Saturday Midday Peak Hour | |
|---|--|----------------------------|----------------------|------|---------------------------|--------------|
| | | | LOS | V/C | LOS | V/C |
| Signalized Intersections | | | | | | |
| 1 | SW Upper Boones Ferry Road/ SW Lower Boones Ferry Road/ SW Boones Ferry Road | 0.99 | C | 0.74 | Not Analyzed | Not Analyzed |
| 2 | SW Boones Ferry Road/ SW Tualatin Road | 0.99 | B | 0.58 | Not Analyzed | Not Analyzed |
| 3 | SW Boones Ferry Road/ SW Martinazzi Avenue | 0.99 | C | 0.91 | B | 0.64 |
| 8 | SW Nyberg Road/ SW Martinazzi Avenue | 0.99 | B | 0.51 | B | 0.39 |
| 10 | SW Nyberg Road/ SW Tualatin-Sherwood Road/ Fred Meyer/Site Access | 0.99 | B | 0.80 | B | 0.66 |
| 12 | I-5 SB Ramp Terminal/ SW Nyberg Road | 0.85 | C | 0.80 | C | 0.77 |
| 13 | I-5 NB Ramp Terminal/ SW Nyberg Road | 0.85 | B | 0.60 | C | 0.55 |
| 14 | SW Nyberg Road/ Nyberg Woods Driveway | 0.99 | B | 0.70 | B | 0.64 |
| 15 | SW Nyberg Road/ SW 65 th Avenue | 0.99 | C | 0.75 | Not Analyzed | Not Analyzed |
| 16 | SW Tualatin-Sherwood Road/ SW Boones Ferry Road | 0.99 | D | 0.82 | Not Analyzed | Not Analyzed |
| 17 | SW Tualatin-Sherwood Road/ SW Martinazzi Avenue | 0.99 | D | 0.85 | C | 0.76 |
| 18 | SW 65 th Avenue/ SW Borland Road | 0.99 | D | 0.88 | Not Analyzed | Not Analyzed |
| 19 | SW Boones Ferry Road/ SW Sagert Street | 0.99 | C | 0.68 | Not Analyzed | Not Analyzed |
| Unsignalized Intersections¹ | | | | | | |
| 4 | SW Martinazzi Avenue/ North Site Driveway | E | C | 0.11 | B | 0.11 |
| 5 | SW Martinazzi Avenue/ SW Seneca Street | E | D | 0.50 | C | 0.22 |
| 6 | SW Martinazzi Avenue/ Site Driveway | E | C | 0.10 | B | 0.07 |
| 7 | SW Martinazzi Avenue/ Right-Out Only Site Driveway | E | B | 0.04 | B | 0.02 |
| 9 | SW Nyberg Road/ Site Driveway | E | B | 0.15 | B | 0.08 |
| 11 | SW Nyberg Road/ Right-in Right-Out Site Driveway | 0.99 | A | 0.01 | A | 0.02 |
| All-Way Stop controlled Intersections | | | | | | |
| 20 | SW Sagert Street/ SW Martinazzi Avenue | D | F | N/A | Not Analyzed | Not Analyzed |
| 21 | SW Sagert Street/ SW 65 th Avenue | D | F | N/A | Not Analyzed | Not Analyzed |

Notes:

¹ LOS and V/C reported for the highest delay or critical movement

For intersections #4, #5, #6, and #7, it is recognized that the operational results shown may differ slightly due to the presence of vehicle queuing along SW Martinazzi Avenue during peak time periods.







EXISTING TRAFFIC CONDITIONS, WEEKDAY PM PEAK HOUR TUALATIN, OREGON

Exhibit 1
Attachment L

LEGEND
 CM = CRITICAL MOVEMENT (TWSC)
 LOS = INTERSECTION LEVEL OF SERVICE (SIGNALIZED/AVSC)/CRITICAL MOVEMENT LEVEL OF SERVICE (TWSC)
 Del = INTERSECTION AVERAGE CONTROL DELAY (SIGNALIZED/AVSC) / CRITICAL MOVEMENT CONTROL DELAY (TWSC)
 V/C = CRITICAL VOLUME-TO-CAPACITY RATIO
 TWSC = TWO-WAY STOP CONTROL
 AVSC = ALL-WAY STOP CONTROL

KITTELSON & ASSOCIATES, INC.
 TRANSPORTATION ENGINEERING / PLANNING

14:00/14:11:10 - K:\141 Tualatin Rd\trnsprn\engr\figs\fig4a\1412116_Fig01.dwg Apr 16, 2013 - 2:37pm - mhughett Layout Tab: Fig04A



LEGEND
 CM = CRITICAL MOVEMENT (TWSC)
 LOS = INTERSECTION LEVEL OF SERVICE (SIGNALIZED/AVIS)/CRITICAL MOVEMENT LEVEL OF SERVICE (TWSC)
 Del = INTERSECTION AVERAGE CONTROL DELAY (SIGNALIZED/AVIS) / CRITICAL MOVEMENT CONTROL DELAY (TWSC)
 VIC = CRITICAL VOLUME-TO-CAPACITY RATIO
 TWSC = TWO-WAY STOP CONTROL
 AVISC = ALL-WAY STOP CONTROL

KITTELSON & ASSOCIATES, INC.
 TRANSPORTATION ENGINEERING / PLANNING

EXISTING SATURDAY MIDDAY PEAK TRAFFIC VOLUMES
 TUALATIN, OREGON
FIGURE 4B

Exhibit 1
Attachment L

H:\projects\12116 - K:\t\Tualatin\Federal\preliminary\figs\Fig01.dwg Apr 17, 2013 - 12:43pm - mhughart Layout Tab: Fig01b

SW 65th Avenue/SW Sagert Street

The SW 65th Avenue/SW Sagert Street intersection is an all-way stop-controlled intersection. Based on the existing traffic demand, the intersection currently operates at LOS F conditions during the weekday p.m. peak hour. These findings are consistent with the existing conditions analysis prepared as part of the recent update to the Tualatin Transportation System Plan (TSP).

SW Martinazzi Avenue/SW Sagert Road

The SW Martinazzi Avenue/SW Sagert Street intersection is an all-way stop-controlled intersection. Based on the existing traffic demand, the intersection currently operates at LOS F conditions during the weekday p.m. peak hour. These findings are consistent with existing conditions analysis prepared as part of the recent update to the Tualatin TSP.

Existing Daily Traffic Profile

A summation of daily traffic volumes was prepared at the request of the City of Tualatin. Using available daily traffic volume counts collected by Washington County and those daily counts collected as part of the on-going Tualatin Transportation System Plan Update, it was generally determined that the weekday p.m. peak hour traffic volumes are approximately 8% of the daily traffic profile. Applying this factor to the weekday p.m. peak hour turning movement volumes collected at the study area intersections, daily traffic volume estimates were derived and summarized in Table 3.

Table 3: Existing Daily Traffic Volumes on Select Roadway Segments

| Roadway | Segment | Estimated Daily Volume |
|----------------------------|---|------------------------|
| SW Lower Boones Ferry Road | East of SW Upper Boones Ferry Road | 13,200 |
| SW Boones Ferry Road | East of SW Martinazzi Avenue | 28,100 |
| SW Boones Ferry Road | West of SW Martinazzi Avenue | 24,400 |
| SW Martinazzi Avenue | South of SW Boones Ferry Road and north of SW Nyberg Road | 13,700 |
| SW Martinazzi Avenue | South of SW Tualatin-Sherwood Road | 17,100 |
| SW Boones Ferry Road | North of SW Tualatin-Sherwood Road | 14,000 |
| SW Boones Ferry Road | South of SW Tualatin-Sherwood Road | 15,200 |
| SW Tualatin-Sherwood Road | West of SW Boones Ferry Road | 30,800 |
| SW Tualatin-Sherwood Road | East of SW Boones Ferry Road and west of SW Martinazzi Avenue | 34,000 |
| SW Tualatin-Sherwood Road | East of SW Martinazzi Avenue and west of SW Nyberg Road | 44,600 |
| SW Nyberg Lane | West of SW Tualatin-Sherwood Road and east of SW Martinazzi Avenue | 9,000 |
| SW Nyberg Road | East of SW Tualatin-Sherwood Road and west of I-5 SB Ramp Terminal | 51,900 |
| SW Nyberg Road | West of I-5 SB Ramp Terminal and east of I-5 NB Ramp Terminal | 38,600 |
| SW Nyberg Road | East of I-5 NB Ramp Terminal and west of SW 65 th Avenue | 23,100 |
| SW 65 th Avenue | South of SW Nyberg Road | 17,500 |
| SW Borland Road | East of SW 65 th Avenue | 14,900 |
| SW 65 th Avenue | South of SW Sagert Street | 9,600 |
| SW Sagert Street | West of SW 65 th Avenue | 11,500 |
| SW Sagert Street | East of SW Martinazzi Avenue | 11,200 |

SAFETY ANALYSIS

This section provides analysis of roadway safety information within the site vicinity. Three sources of crash data were considered: the ODOT Safety Priority Index System, the Washington County Safety Priority Indexing System (SPIS), and review of crash data provided by ODOT. The ODOT crash data includes all reported crashes that occurred at the study intersections for the three-year period from January 1, 2009 to December 31, 2011 (matching the Tualatin TSP Update review period).

ODOT Statewide Priority Index System

The Statewide Priority Index System (ODOT SPIS) is a method developed by ODOT for identifying hazardous locations on state highways through consideration of crash frequency, crash rate, and crash severity. The ODOT SPIS designates a roadway segment as a SPIS site if a location experiences three or more crashes or one or more fatal crashes over a three-year period. Under this method, all state highways are analyzed in 0.10 mile segments to identify SPIS sites. Statewide, there are approximately 6,000 SPIS sites. SPIS sites are typically intersections, but can also be roadway segments.

Within the study area, none of the ODOT controlled intersections or roadway segments are included in ODOT's SPIS ranking program for 2009-2011.

Washington County Safety Priority Index System (SPIS)

Washington County ranks their high accident SPIS locations based on a formula that identifies potentially hazardous locations. The formula takes into consideration the frequency, rate, and severity of crashes.

Within the study area, there are two intersections that rank within the top 50 SPIS locations. These include SW Tualatin-Sherwood Road/SW Boones Ferry Road and SW Tualatin-Sherwood Road/SW Martinazzi Avenue.

Intersection Crash Data Analysis

The individual crash history of the study intersections was reviewed in an effort to identify potential intersection safety issues. The crash types and crash rates from the analysis are presented in Table 4. Typically, crash rates that meet or exceed 1.0 crashes per million entering vehicles are reviewed for additional geometric and operational investigation. As shown in the table, all of the reported intersections have crash rates less than 1.0. These findings are generally consistent with the crash assessment provided in the Tualatin TSP Update.

Table 4: Intersection Crash History (January 1, 2009 through December 31, 2011)

| Intersection | Collision Type | | | | | | Total Crashes | Estimated Annual Average Daily Traffic | Crash Rate (crashes per million entering vehicles) |
|--|----------------|---------|----------|--------------|------------|-------|---------------|--|--|
| | Angle | Turning | Rear End | Fixed Object | Ped / Bike | Other | | | |
| SW Upper Boones Ferry Road/ SW Lower Boones Ferry Road/ SW Boones Ferry Road | - | 1 | - | 1 | - | - | 2 | 22,300 | 0.08 |
| SW Boones Ferry Road/ SW Tualatin Road | - | - | 4 | - | 2 | - | 6 | 24,800 | 0.22 |
| SW Boones Ferry Road/ SW Martinazzi Avenue | - | - | 4 | - | - | - | 4 | 28,300 | 0.13 |
| SW Nyberg Road/ SW Martinazzi Avenue | - | 4 | 4 | - | - | - | 8 | 16,950 | 0.43 |
| SW Nyberg Road/ SW Tualatin-Sherwood Road | - | 8 | 7 | 1 | - | - | 16 | 44,650 | 0.33 |
| I-5 SB Ramp Terminal/ SW Nyberg Road | 1 | 20 | 24 | - | 2 | 1 | 48 | 50,900 | 0.86 |
| I-5 NB Ramp Terminal/ SW Nyberg Road | - | 6 | 9 | - | - | - | 15 | 40,500 | 0.34 |
| SW Nyberg Road/ SW 65 th Avenue | - | 1 | 2 | - | - | - | 3 | 21,300 | 0.13 |
| SW Tualatin-Sherwood Road/ SW Boones Ferry Road | 3 | 11 | 21 | - | - | 4 | 39 | 38,750 | 0.92 |
| SW Tualatin-Sherwood Road/ SW Martinazzi Avenue | 6 | 2 | 8 | 1 | - | - | 17 | 42,800 | 0.36 |
| SW 65 th Avenue/ SW Borland Road | - | 1 | 1 | - | - | - | 2 | 20,750 | 0.09 |
| SW Boones Ferry Road/ SW Sagert Street | - | 3 | 2 | - | - | - | 5 | 18,600 | 0.25 |
| SW Sagert Street/ SW Martinazzi Avenue | 4 | - | - | - | - | - | 4 | 17,500 | 0.21 |
| SW Sagert Street/ SW 65 th Avenue | - | - | - | - | - | - | 0 | 15,750 | 0.00 |

Section 4
Transportation Impact Analysis

TRANSPORTATION IMPACT ANALYSIS

The transportation impact analysis identifies how the study area's transportation system will operate in the year the proposed redevelopment is expected to be fully built and occupied (2014). The impact of traffic generated by the proposed Nyberg Rivers development during the typical weekday p.m. and Saturday midday peak hours was examined as follows:

- Background weekday p.m. and Saturday midday peak hour traffic conditions for the 2014 (build-out year of the Nyberg Rivers redevelopment) was analyzed at each of the study intersections.
- Background conditions were developed by applying a 1.5-percent annual growth rate to the existing traffic volumes to account for regional growth in the site vicinity between years 2012 and 2014.
- Site-generated trips were estimated for build-out of the site.
- Site trip-distribution patterns were derived from a review of existing traffic patterns and regional planning model outputs.
- Year 2014 (build-out year of the Nyberg Rivers redevelopment) total traffic conditions were analyzed at each of the study intersections and site-access points during the weekday p.m. and Saturday midday peak hours.
- On-site circulation issues and site-access alternatives were evaluated.

YEAR 2014 BACKGROUND TRAFFIC CONDITIONS

The year 2014 background traffic analysis identifies how the study area's transportation system will operate without the proposed Nyberg Rivers redevelopment. This analysis includes traffic attributed to general growth in the region, but does not include traffic from the proposed redevelopment.

Traffic Volumes

In order to develop a near-term traffic growth rate, the last five years of annual Washington County daily traffic counts were reviewed along SW Tualatin-Sherwood Road (just east of SW Boones Ferry Road) and SW Nyberg Road (west of SW 65th Avenue). A summary of these counts is provided in Table 5 below.

Table 5: Historical Traffic Counts

| Count Location | 2008 | 2009 | 2010 | 2011 | 2012 |
|--|--------|--------|--------|--------|--------|
| SW Nyberg Road (west of SW 65 th Avenue) | 21,837 | 20,764 | 21,733 | 21,506 | 21,351 |
| SW Tualatin-Sherwood Road (east of SW Boones Ferry Road) | 40,469 | 38,813 | 39,671 | 41,137 | 40,591 |



As shown in the table, traffic growth within the general site vicinity between 2008 and 2012 has been minimal to negative, in part reflecting the economic slowdown that occurred after 2008. City staff recommended a 1.5% annual growth rate be applied to reflect a reasonable, yet conservative approximation of traffic growth at each of the study intersections. This growth rate is consistent with other traffic studies that have been submitted in the past within the project vicinity. Figures 5a and 5b illustrate the resulting forecast year 2014 background traffic volumes during the weekday p.m. and Saturday midday peak hours.

2014 Background Operations Analysis



The weekday p.m. and Saturday midday peak-hour turning-movement volumes shown in Figure 5a and 5b were used to conduct an operational analysis at each study intersection to determine the year 2014 background traffic levels of service. As indicated by the respective figures and Table 6, the background traffic analysis determined that all of but two of the study intersections are forecast to operate at acceptable standards during both the weekday p.m. and Saturday midday peak hours. *Appendix "E" contains the year 2014 background traffic level-of-service worksheets.*

SW 65th Avenue/SW Sagert Street

Based on the estimated future traffic demand, the intersection is forecast to continue to operate at LOS F conditions during the weekday p.m. peak hour.

SW Martinazzi Avenue/SW Sagert Road


Based on the existing traffic demand, the intersection is forecast to continue to operate at LOS F conditions during the weekday p.m. peak hour.



LEGEND
 CM = CRITICAL MOVEMENT (TWSC)
 LOS = INTERSECTION LEVEL OF SERVICE (SIGNALIZED/ANSC)/CRITICAL MOVEMENT LEVEL OF SERVICE (TWSC)
 Del = INTERSECTION AVERAGE CONTROL DELAY (SIGNALIZED/ANSC) / CRITICAL MOVEMENT CONTROL DELAY (TWSC)
 V/C = CRITICAL VOLUME-TO-CAPACITY RATIO
 TWSC = TWO-WAY STOP CONTROL
 ANSC = ALL-WAY STOP CONTROL

2014 BACKGROUND TRAFFIC CONDITIONS, WEEKDAY PM PEAK HOUR TUALATIN, OREGON

H:\projects\12116 - K-M-R Tualatin Tualatin Redevelopment\Tualatin\figs\fig01.dwg Apr 16, 2013 - 2:36pm - mhughan Layout Tab: fig05a



2014 BACKGROUND TRAFFIC CONDITIONS, SATURDAY MIDDAY PEAK HOUR TUALATIN, OREGON

LEGEND
 CM = CRITICAL MOVEMENT (TWSC)
 LOS = INTERSECTION LEVEL OF SERVICE (SIGNALIZED/AVSC)/CRITICAL MOVEMENT LEVEL OF SERVICE (TWSC)
 Del = INTERSECTION AVERAGE CONTROL DELAY (SIGNALIZED/AVSC) / CRITICAL MOVEMENT CONTROL DELAY (TWSC)
 V/C = CRITICAL VOLUME-TO-CAPACITY RATIO
 TWSC = TWO-WAY STOP CONTROL
 AVSC = ALL-WAY STOP CONTROL

KITTELSON & ASSOCIATES, INC.
 TRANSPORTATION ENGINEERING / PLANNING

Table 6: 2014 Background Traffic Conditions

| Number | Intersection | Maximum Operating Standard | Weekday PM Peak Hour | | Saturday Midday Peak Hour | |
|---|--|----------------------------|----------------------|------|---------------------------|--------------|
| | | | LOS | V/C | LOS | V/C |
| Signalized Intersections | | | | | | |
| 1 | SW Upper Boones Ferry Road/ SW Lower Boones Ferry Road/ SW Boones Ferry Road | 0.99 | C | 0.76 | Not Analyzed | Not Analyzed |
| 2 | SW Boones Ferry Road/ SW Tualatin Road | 0.99 | B | 0.61 | Not Analyzed | Not Analyzed |
| 3 | SW Boones Ferry Road/ SW Martinazzi Avenue | 0.99 | D | 0.93 | B | 0.66 |
| 8 | SW Nyberg Road/ SW Martinazzi Avenue | 0.99 | B | 0.46 | B | 0.40 |
| 10 | SW Nyberg Road/ SW Tualatin-Sherwood Road/ Fred Meyer/Site Driveway | 0.99 | B | 0.81 | B | 0.67 |
| 12 | I-5 SB Ramp Terminal/ SW Nyberg Road | 0.85 | C | 0.81 | C | 0.81 |
| 13 | I-5 NB Ramp Terminal/ SW Nyberg Road | 0.85 | B | 0.62 | C | 0.56 |
| 14 | SW Nyberg Road/ Nyberg Woods Driveway | 0.99 | B | 0.70 | B | 0.65 |
| 15 | SW Nyberg Road/ SW 65 th Avenue | 0.99 | C | 0.81 | Not Analyzed | Not Analyzed |
| 16 | SW Tualatin-Sherwood Road/ SW Boones Ferry Road | 0.99 | D | 0.85 | Not Analyzed | Not Analyzed |
| 17 | SW Tualatin-Sherwood Road/ SW Martinazzi Avenue | 0.99 | D | 0.88 | C | 0.78 |
| 18 | SW 65 th Avenue/ SW Borland Road | 0.99 | E | 0.92 | Not Analyzed | Not Analyzed |
| 19 | SW Boones Ferry Road/ SW Sagert Street | 0.99 | C | 0.67 | Not Analyzed | Not Analyzed |
| Unsignalized Intersections¹ | | | | | | |
| 4 | SW Martinazzi Avenue/ North Site Driveway | E | C | 0.12 | B | 0.11 |
| 5 | SW Martinazzi Avenue/ SW Seneca Street | E | D | 0.51 | C | 0.23 |
| 6 | SW Martinazzi Avenue/ Site Driveway | E | C | 0.11 | B | 0.07 |
| 7 | SW Martinazzi Avenue/ Right-Out Only Site Driveway | E | C | 0.04 | B | 0.02 |
| 9 | SW Nyberg Road/ Site Driveway | E | B | 0.15 | B | 0.08 |
| 11 | SW Nyberg Road/ Right-in Right-Out Site Driveway | 0.99 | A | 0.01 | A | 0.02 |
| All-Way Stop-Controlled Intersections | | | | | | |
| 20 | SW Sagert Street/ SW Martinazzi Avenue | D | F | N/A | Not Analyzed | Not Analyzed |
| 21 | SW Sagert Street/ SW 65 th Avenue | D | F | N/A | Not Analyzed | Not Analyzed |

Notes:

¹ LOS and V/C reported for the highest delay or critical movement

For intersections #4, #5, #6, and #7, it is recognized that the operational results shown may differ slightly due to the presence of vehicle queuing along SW Martinazzi Avenue during peak time periods.

Background Daily Traffic Profile

A summation of the 2014 Background daily traffic volumes and their comparison to 2012 existing conditions is summarized in Table 7 below (the growth shown in Table 7 reflects the assumed 1.5% annual growth).

Table 7: 2014 Background Daily Traffic Profile

| Roadway | Segment | Estimated Daily Volume | |
|----------------------------|---|------------------------|-----------------|
| | | 2012 Existing | 2014 Background |
| SW Lower Boones Ferry Road | East of SW Upper Boones Ferry Road | 13,200 | 13,600 |
| SW Boones Ferry Road | East of SW Martinazzi Avenue | 28,100 | 28,800 |
| SW Boones Ferry Road | West of SW Martinazzi Avenue | 24,400 | 25,100 |
| SW Martinazzi Avenue | South of SW Boones Ferry Road and north of SW Nyberg Road | 13,700 | 14,100 |
| SW Martinazzi Avenue | South of SW Tualatin-Sherwood Road | 17,100 | 17,600 |
| SW Boones Ferry Road | North of SW Tualatin-Sherwood Road | 14,000 | 14,500 |
| SW Boones Ferry Road | South of SW Tualatin-Sherwood Road | 15,200 | 15,700 |
| SW Tualatin-Sherwood Road | West of SW Boones Ferry Road | 30,800 | 31,800 |
| SW Tualatin-Sherwood Road | East of SW Boones Ferry Road and west of SW Martinazzi Avenue | 34,000 | 34,900 |
| SW Tualatin-Sherwood Road | East of SW Martinazzi Avenue and west of SW Nyberg Road | 36,400 | 37,400 |
| SW Nyberg Lane | West of SW Tualatin-Sherwood Road and east of SW Martinazzi Avenue | 9,000 | 9,200 |
| SW Nyberg Road | East of SW Tualatin-Sherwood Road and west of I-5 SB Ramp Terminal | 51,900 | 52,900 |
| SW Nyberg Road | West of I-5 SB Ramp Terminal and east of I-5 NB Ramp Terminal | 38,600 | 39,600 |
| SW Nyberg Road | East of I-5 NB Ramp Terminal and west of SW 65 th Avenue | 23,100 | 23,800 |
| SW 65 th Avenue | South of SW Nyberg Road | 17,500 | 18,100 |
| SW Borland Road | East of SW 65 th Avenue | 14,900 | 15,400 |
| SW 65 th Avenue | South of SW Sagert Street | 9,600 | 9,900 |
| SW Sagert Street | West of SW 65 th Avenue | 11,500 | 11,900 |
| SW Sagert Street | East of SW Martinazzi Avenue | 11,200 | 11,600 |

PROPOSED REDEVELOPMENT PLAN

In an effort to enhance and reinvigorate the existing shopping center, CenterCal is proposing to redevelop a portion of the existing center. The redevelopment is envisioned to entail the following:

- The 96,799 square foot former K-Mart building will be removed.
- The existing 3,500 square foot building currently occupied by a Wendy's will be relocated to a new pad within the shopping center site.
- All other existing buildings (and associated access driveways) will remain as it has been assumed that the existing tenants will continue to operate as-is for the foreseeable future.
- While a specific tenant mix is still being developed by CenterCal, it is envisioned that the redeveloped portion of the center will include large and medium sized retailers and an assortment of smaller retail/restaurant uses. For the purposes of this traffic study, it has





been assumed that this mix of uses will total approximately 245,456 square feet of new leasable area bringing the total net leasable area for the entire shopping center to 307,000 square feet.

In order to enhance access to the redeveloped shopping center, several modifications to the existing shopping center driveways are proposed. These include the following:

- The existing SW 75th Avenue connection to SW Nyberg Road is proposed to be closed under the redevelopment plan. This closure will minimize turning movement conflicts along a busy segment of SW Nyberg Road and it will improve the interchange access spacing conditions within the I-5/Nyberg Interchange influence area.
- The existing signalized access on SW Nyberg Road that serves the shopping center and the adjacent Fred Meyer site will remain at its current location; however, the following changes are proposed to increase intersection capacity:
 - A westbound right-turn lane is proposed on SW Nyberg Street to enhance access to the site and minimize vehicle queuing on SW Nyberg Street.
 - The existing site driveway is proposed to be widened as shown in the site plan to accommodate increased site traffic. This widening will include dual southbound left-turn lanes, a shared through/right-turn lane, and dual in-bound receiving lanes (See the *"Impacts of the Nyberg Rivers Development on Identified Transportation Planning Projects"* section for further discussion on these improvements).
 - The north and south approach signal phasing is proposed to be modified from permissive left-turn phasing to split phasing. Westbound right-turn overlap phasing is proposed for the westbound right-turn lane into the Nyberg Rivers site.
 - No modifications are proposed to the existing Fred Meyer driveway at this intersection.

Figure 6 shows the proposed site-access configurations and traffic control devices that will be assumed as part of the total traffic analysis. Construction of this development is expected to begin in 2013 with the build-out projected to occur in year 2014.



LEGEND

- NEW TRAVEL LANE
- STOP SIGN
- TRAFFIC SIGNAL

ASSUMED SITE ACCESS CONFIGURATION AND TRAFFIC CONTROL DEVICES
 TUALATIN, OREGON

Redevelopment Plan Trip Generation

Given that the proposed project is only a partial redevelopment of the larger shopping center; a trip generation methodology was developed to reflect the characteristics of a unified and vibrant shopping center. The following outline describes the trip generation methodology that was used:

- Traffic counts were conducted at all of the site driveways to quantify the trip generation profile of the existing retail and civic uses currently operating on the site.
- Recognizing that the City offices/library are not retail uses and the layout of the site/parking fields prevents an accurate quantification of trips being generated by these uses, estimates were developed using the standard reference manual, *Trip Generation*, published by the Institute of Transportation Engineers (ITE). The Library and Single Tenant Office Building land uses were used in the estimate process. The resulting estimates were then subtracted from the existing site driveway counts to produce a trip profile estimate for the existing 158,343 square feet of retail building space at the site.
- A trip generation rate was calculated using the Shopping Center land use in ITE *Trip Generation* for the 245,456² square feet of new retail use plus the 61,544 square feet of remaining retail uses³.
- The existing site retail traffic estimate was then subtracted from the total shopping center and office trip generation estimate to arrive at a total trip estimate for the net increase in shopping center and office square footage. A pass-by rate reduction of 34%⁴ was assumed for the shopping center component to generate the net new trip estimate for the site. This pass-by estimate is consistent with ITE *Trip Generation* for similar shopping center uses. Furthermore, given the mix of existing uses (fast-food restaurants, drive-thru banks, and shopping center commercial uses) that will remain on the site and proposed mix of uses (large and medium sized general retailers and assortment of general retail/restaurant uses), this pass-by reduction rate is considered to be reasonable and conservatively appropriate.

² New Retail Uses = Total Proposed Area – Existing Uses that Remain = 307,000 sq. ft. – 61,544 sq. ft. = 245,456 sq. ft.

³ Remaining uses = Existing building area – Existing Kmart = 158,343 sq. ft. - 96,799 sq. ft. = 61,544 sq. ft.)

⁴ There are approximately 55,000-60,000 vehicles per day passing by the site frontage on SW Tualatin-Sherwood Road and SW Martinazzi Avenue. This volume is considered sufficient to justify the standard 34 percent pass-by assumption for the shopping center (the average 34 percent was obtained directly from the Institute of Transportation Engineers (ITE) *Trip Generation*, 9th Edition). It is also expected that some trips will re-route from I-5, which would be considered “diverted trips”. All trips coming from I-5 were considered “primary” trips in an effort to present a conservative and reasonable worst-case condition. ITE *Trip Generation* Shopping Center trip rates indicate that an average 26 percent of shopping center trips are diverted, in addition to the 34 percent pass-by. By not accounting for diverted trips, the current study is inherently conservative and likely overstates impacts between the main site driveway and the I-5 interchange ramps.



Table 8 below illustrates the trip generation calculation process (all trip ends shown in Table 8 have been rounded to the nearest five trips).

Table 8: Estimated Nyberg Rivers Trip Generation

| | ITE Code | Size (sq. ft.) | Weekday PM Peak Hour | | | Saturday Midday Peak Hour | | |
|--|----------|----------------------|----------------------|------------|------------|---------------------------|------------|------------|
| | | | Total | In | Out | Total | In | Out |
| Existing Site | | | | | | | | |
| Existing Site Driveways ¹ | - | - | 945 | 435 | 510 | 970 | 490 | 480 |
| <i>Less Existing Library²</i> | 590 | 22,123 | (160) | (75) | (85) | (150) | (80) | (70) |
| <i>Less Existing Civic Uses³</i> | 715 | ~10,000 | (50) | (10) | (40) | - | - | - |
| Total Existing Retail | | | 735 | 350 | 385 | 820 | 410 | 410 |
| Future Site | | | | | | | | |
| Shopping Center | 820 | 307,000 ⁴ | 1,350 | 660 | 690 | 1,775 | 925 | 850 |
| <i>Less Existing Retail Driveway Counts</i> | | | (735) | (350) | (385) | (820) | (410) | (410) |
| Sub Total | | | 615 | 310 | 305 | 955 | 515 | 440 |
| <i>Pass-by Trips (Weekday 34%, Saturday 26%)</i> | | | (210) | (105) | (105) | (230) | (115) | (115) |
| Net New Trips | | | 405 | 205 | 200 | 725 | 400 | 325 |

¹Represents the total site driveway counts during the weekday p.m. peak hour of 4:35-5:35 p.m. and Saturday midday peak hour of 12:10-1:10 p.m. This is the traffic volume being generated by the existing 158,343 square feet of shopping center currently residing on the site prior to Kmart's closure.

²The library traffic counts were estimated using the *Library* land use in ITE Trip Generation.

³The City Hall traffic counts were estimated using the *Single Tenant Office Building* land use in ITE Trip Generation. The existing City Hall square footage was estimated to be approximately 10,000 square feet in size.

⁴Includes the 158,343 square feet of existing shopping center (minus the 96,799 square foot former K-Mart) plus the 245,456 square feet of proposed shopping center uses.

As shown in Table 8, the proposed redevelopment project is anticipated to generate approximately 405 net new weekday p.m. peak hour trips and 725 net new Saturday midday peak hour trips.

Site Trip Distribution/Trip Assignment

The trip distribution pattern for the proposed redevelopment project was estimated based on a review of existing traffic patterns and a select zone assignment obtained from Washington County's travel demand model. A summary output sheet from the travel demand model and the distribution calculations derived from it is provided in the first part of Appendix F. The trip distribution pattern used in the analysis is shown in Figure 7.




FIGURE 7

ESTIMATED TRIP DISTRIBUTION PATTERN TUALATIN, OREGON

H:\profiles\12116 - K-Mart Tualatin Redevelopment\hws\figs\April2013\12116_Fig01.dwg Apr 15, 2013 - 4:10pm - mhughan Layout Tab: Fig07

The estimated site-generated trips were assigned to the network by distributing the trips shown in Table 8 according to the trip distribution pattern shown in Figure 7. Figures 8aA/8aPB and 8bA/8bBP illustrate the site-generated/pass-by trips that are expected to use the roadway system during the weekday p.m. and Saturday midday peak hours.

YEAR 2014 TOTAL TRAFFIC CONDITIONS

The total traffic conditions analysis forecasts how the study area's transportation system will operate with the traffic generated by the Nyberg Rivers redevelopment plan. The year 2014 background traffic volumes for the weekday p.m. and Saturday midday peak hours (shown in Figure 5a and 5b) were added to the site-generated traffic (shown in Figures 8aA/8aPB and 8bA/8bPB) to arrive at the total traffic volumes that are shown in Figures 9a and 9b.

2014 Total Traffic Operations

The weekday p.m. and Saturday midday peak hour turning-movement volumes shown in Figures 9a and 9b were used to conduct an operational analysis at each study intersection and site driveway to determine the year 2014 total traffic operations. The results of the total traffic analysis shown in Figures 9a, 9b, and Table 9 indicate that all of the study intersections and site access points, except for the SW 65th Avenue/SW Sager Road and SW Martinazzi Avenue/SW Sagert Road intersections, are forecast to operate at acceptable operations during the weekday p.m. and Saturday midday peak hours. *Appendix "F" contains the year 2014 total traffic level-of-service worksheets.*

The SW Martinazzi Avenue/SW Sagert Road and SW 65th Avenue/SW Sagert Road intersections are forecast to continue to operate at LOS F. The proposed development is estimated to contribute an additional 1.6% and 0.6%, respectively, during the weekday p.m. peak hour. Given this small increase, no development-driven traffic mitigation is recommended for the following reasons:

- The Tualatin TSP has identified mitigations for these two intersections that, when implemented, will address the long-term operations.
- The Washington County Transportation Development Tax (TDT) in part funds an improvement project on SW Sagert Street that will add capacity and reduce delay to both intersections.







FIGURE 8aA
 SITE-GENERATED TRIPS (ADDED TRIPS), WEEKDAY PM PEAK HOUR
 ASSUMED SITE ACCESS CONFIGURATION
 TUALATIN, OREGON



NOTE: NEGATIVE VOLUMES REPRESENT PASS-BY TRIPS

FIGURE 8aPB SITE-GENERATED TRIPS (PASS BY TRIPS), WEEKDAY PM PEAK HOUR, ASSUMED SITE ACCESS CONFIGURATION, TUALATIN, OREGON









FIGURE 8ba
 SITE-GENERATED TRIPS (ADDED TRIPS), SATURDAY MIDDAY PEAK HOUR
 ASSUMED SITE ACCESS CONFIGURATION
 TUALATIN, OREGON




NOTE: NEGATIVE VOLUMES REPRESENT PASS-BY TRIPS

FIGURE 1
SITE-GENERATED TRIPS (PASS BY TRIPS), SATURDAY MIDDAY PEAK HOUR
ASSUMED SITE ACCESS CONFIGURATION
TUALATIN, OREGON



LEGEND
 CM = CRITICAL MOVEMENT (TWSC)
 LOS = INTERSECTION LEVEL OF SERVICE (SIGNALIZED/AVSC)/CRITICAL MOVEMENT LEVEL OF SERVICE (TWSC)
 Dm = INTERSECTION AVERAGE CONTROL DELAY (SIGNALIZED/AVSC) / CRITICAL MOVEMENT CONTROL DELAY (TWSC)
 V/C = CRITICAL VOLUME-TO-CAPACITY RATIO
 TWSC = TWO-WAY STOP CONTROL
 AVSC = ALL-WAY STOP CONTROL

2014 TOTAL TRAFFIC CONDITIONS, WEEKDAY PM PEAK HOUR
 ASSUMED SITE ACCESS CONFIGURATION
 TUALATIN, OREGON



2014 TOTAL TRAFFIC CONDITIONS, SATURDAY MIDDAY PEAK HOUR
 ASSUMED SITE ACCESS CONFIGURATION
 TUALATIN, OREGON

Exhibit 1
 Attachment L

LEGEND
 CM = CRITICAL MOVEMENT (TWSC)
 LOS = INTERSECTION LEVEL OF SERVICE (SIGNALIZED/AVSC)/CRITICAL MOVEMENT LEVEL OF SERVICE (TWSC)
 DBI = INTERSECTION AVERAGE CONTROL DELAY (SIGNALIZED/AVSC) / CRITICAL MOVEMENT CONTROL DELAY (TWSC)
 V/C = CRITICAL VOLUME-TO-CAPACITY RATIO
 TWSC = TWO-WAY STOP CONTROL
 AVSC = ALL-WAY STOP CONTROL

KITTELSON & ASSOCIATES, INC.
 TRANSPORTATION ENGINEERING / PLANNING

H:\projects\1210 - K-That Tualatin Pedestrian\working\figs\fig1210_121116_fig01.dwg Apr 17, 2013 - 12:45pm - mngbhart Layout Tab: Figure_Synchr

Table 9: 2014 Total Traffic Operations

| Number | Intersection | Maximum Operating Standard | Weekday PM Peak Hour | | Saturday Midday Peak Hour | |
|---|--|----------------------------|----------------------|------|---------------------------|--------------|
| | | | LOS | V/C | LOS | V/C |
| Signalized Intersections | | | | | | |
| 1 | SW Upper Boones Ferry Road/ SW Lower Boones Ferry Road/ SW Boones Ferry Road | 0.99 | C | 0.77 | Not Analyzed | Not Analyzed |
| 2 | SW Boones Ferry Road/ SW Tualatin Road | 0.99 | B | 0.63 | Not Analyzed | Not Analyzed |
| 3 | SW Boones Ferry Road/ SW Martinazzi Avenue | 0.99 | D | 0.96 | B | 0.68 |
| 8 | SW Nyberg Road/ SW Martinazzi Avenue | 0.99 | B | 0.49 | B | 0.44 |
| 10 | SW Nyberg Road/ SW Tualatin-Sherwood Road/ Fred Meyer/Site Access | 0.99 | C | 0.83 | D | 0.71 |
| 12 | I-5 SB Ramp Terminal/ SW Nyberg Road | 0.85 | C | 0.82 | C | 0.89 |
| 13 | I-5 NB Ramp Terminal/ SW Nyberg Road | 0.85 | B | 0.64 | C | 0.60 |
| 14 | SW Nyberg Road/ Nyberg Woods Driveway | 0.99 | B | 0.71 | B | 0.66 |
| 15 | SW Nyberg Road/ SW 65 th Avenue | 0.99 | C | 0.83 | Not Analyzed | Not Analyzed |
| 16 | SW Tualatin-Sherwood Road/ SW Boones Ferry Road | 0.99 | D | 0.87 | Not Analyzed | Not Analyzed |
| 17 | SW Tualatin-Sherwood Road/ SW Martinazzi Avenue | 0.99 | D | 0.89 | C | 0.83 |
| 18 | SW 65 th Avenue/ SW Borland Road | 0.99 | E | 0.95 | Not Analyzed | Not Analyzed |
| 19 | SW Boones Ferry Road/ SW Sagert Street | 0.99 | C | 0.68 | Not Analyzed | Not Analyzed |
| Unsignalized Intersections¹ | | | | | | |
| 4 | SW Martinazzi Avenue/ North Site Driveway | E | C | 0.23 | C | 0.20 |
| 5 | SW Martinazzi Avenue/ SW Seneca Street | E | E | 0.54 | C | 0.23 |
| 7 | SW Martinazzi Avenue/ Right-Out Only Site Driveway | E | C | 0.04 | B | 0.02 |
| 9 | SW Nyberg Road/ Site Driveway | E | B | 0.19 | B | 0.11 |
| 22* | SW Boones Ferry Road/ Right-In/Right-Out Site Driveway | 0.99 | D | 0.23 | C | 0.16 |
| All-Way Stop-Controlled Intersections | | | | | | |
| 20 | SW Sagert Street/ SW Martinazzi Avenue | D | F | N/A | Not Analyzed | Not Analyzed |
| 21 | SW Sagert Street/ SW 65 th Avenue | D | F | N/A | Not Analyzed | Not Analyzed |

Notes:

¹ LOS and V/C reported for the highest delay or critical movement

* Results reported reflect SW Martinazzi Avenue and SW Boones Ferry Road Site Access Alternatives discussed beginning on page 45.

For intersections #4, #5, #6, and #7, it is recognized that the operational results shown may differ slightly due to the presence of vehicle queuing along SW Martinazzi Avenue during peak time periods.

Existing and background conditions along the Tualatin-Sherwood corridor between the I-5 ramp terminals and Boones Ferry Road reflect consistent timing parameters due to the limited change in traffic volumes. Under the total conditions, with the new site traffic, timing parameters have been optimized in a more focused effort to approximate the SCATS adaptive system's response to the new traffic. The difference in timing optimization levels contributes to the variation in performance between background and total conditions.



Total Daily Traffic Profile

A summation of the 2014 Total Traffic daily traffic volumes is summarized in Table 10 below.

Table 10: 2014 Total Daily Traffic Profile

| Roadway | Segment | Estimated Daily Volume | | |
|----------------------------|---|------------------------|-----------------|------------|
| | | 2012 Existing | 2014 Background | 2014 Total |
| SW Lower Boones Ferry Road | East of SW Upper Boones Ferry Road | 13,200 | 13,600 | 13,900 |
| SW Boones Ferry Road | East of SW Martinazzi Avenue | 28,100 | 28,800 | 29,600 |
| SW Boones Ferry Road | West of SW Martinazzi Avenue | 24,400 | 25,100 | 25,400 |
| SW Martinazzi Avenue | South of SW Boones Ferry Road and north of SW Nyberg Road | 13,700 | 14,100 | 14,400 |
| SW Martinazzi Avenue | South of SW Tualatin-Sherwood Road | 17,100 | 17,600 | 18,100 |
| SW Boones Ferry Road | North of SW Tualatin-Sherwood Road | 14,000 | 14,500 | 14,500 |
| SW Boones Ferry Road | South of SW Tualatin-Sherwood Road | 15,200 | 15,700 | 16,100 |
| SW Tualatin-Sherwood Road | West of SW Boones Ferry Road | 30,800 | 31,800 | 32,300 |
| SW Tualatin-Sherwood Road | East of SW Boones Ferry Road and west of SW Martinazzi Avenue | 34,000 | 34,900 | 35,900 |
| SW Tualatin-Sherwood Road | East of SW Martinazzi Avenue and west of SW Nyberg Road | 36,400 | 37,400 | 38,300 |
| SW Nyberg Lane | West of SW Tualatin-Sherwood Road and east of SW Martinazzi Ave | 9,000 | 9,200 | 9,500 |
| SW Nyberg Road | East of SW Tualatin-Sherwood Road and west of I-5 SB Ramp Terminal | 51,900 | 52,900 | 55,900 |
| SW Nyberg Road | West of I-5 SB Ramp Terminal and east of I-5 NB Ramp Terminal | 38,600 | 39,600 | 41,300 |
| SW Nyberg Road | East of I-5 NB Ramp Terminal and west of SW 65 th Avenue | 23,100 | 23,800 | 24,300 |
| SW 65 th Avenue | South of SW Nyberg Road | 17,500 | 18,100 | 18,400 |
| SW Borland Road | East of SW 65 th Avenue | 14,900 | 15,400 | 15,700 |
| SW 65 th Avenue | South of SW Sagert Street | 9,600 | 9,900 | 10,000 |
| SW Sagert Street | West of SW 65 th Avenue | 11,500 | 11,900 | 11,900 |
| SW Sagert Street | East of SW Martinazzi Avenue | 11,200 | 11,600 | 11,700 |

Queuing Analysis

A 95th percentile vehicle queuing analysis was performed at the I-5 off-ramps and the SW Nyberg Road/Signalized site driveway. Per ODOT requirements, the ramp terminal queuing was assessed using SimTraffic software⁵. The queuing analysis was completed in accordance with the assumptions stipulated in the ODOT *Analysis Procedures Manual (APM)*.

Each vehicle was assumed to occupy 25 feet. Table 11 summarizes the queuing analysis at the study intersections for the 2014 total traffic conditions (critical weekday p.m. peak hour). All queues reported

⁵ Tualatin-Sherwood Road between the I-5 ramp terminals and Teton Avenue currently operates with an adaptive signal system (TransCore SCATSTM), which adjusts cycle length, green splits and offsets to match capacity to traffic demands. This traffic analysis approximated the SCATS system using an upper-end cycle length based on the existing logs from the SCATS system, provided by Washington County. The Synchro/SimTraffic analysis is still a static representation of the adaptive system, thus better than reported results for delay and queue lengths are expected due to the adaptive system capabilities.

are rounded up to the nearest vehicle length. Appendix "F" contains the year 2014 total traffic queuing analysis worksheets.

Table 11: Estimated 95th Percentile Queuing Analysis

| Intersection | Movement | Estimated 95 th Percentile Queue (ft) | | | | Storage Length |
|---|----------|--|---------------|---------------------------|---------------|------------------|
| | | Weekday PM Peak Hour | | Saturday Midday Peak Hour | | |
| | | Background Traffic | Total Traffic | Background Traffic | Total Traffic | |
| I-5 SB Ramp Terminal/ SW Nyberg Road | SB LT/TH | 675 | 700 | 550 | 650 | 700 ¹ |
| | SB RT | 550 | 450 | 400 | 475 | 700 ¹ |
| I-5 NB Ramp Terminal/ SW Nyberg Road | NB TH/LT | 400 | 625 | 375 | 675 | 1,270 |
| | NB RT | 225 | 275 | 250 | 300 | 1,270 |
| SW Nyberg Road/ Signalized Site Driveway | WB LT | 150 | 150 | 150 | 150 | 225 |
| | SB LT | 225 | 200 | 100 | 200 | 250 |
| | EB LT | 75 | 150 | 100 | 225 | 225 |
| | NB RT | 250 | 275 | 250 | 250 | 275 |

NB = Northbound; SB = Southbound; EB = Eastbound; WB = Westbound

LT = Left-Turn; TH = Through; RT = Right-Turn

¹Storage length is framed by the portion of the freeway off-ramp needed to bring a vehicle to a full stop from the posted freeway speed (55 mph) at a deceleration rate of 6.5 feet/second². Ramp length is approximately 1,200 feet long with a deceleration distance of approximately 500 feet.

Table 11 shows that adequate storage exists for the forecast 95th percentile queues at the identified intersections and main sight-access driveway under total traffic conditions.

SW Martinazzi Avenue and SW Boones Ferry Road Site Access Alternatives

As part of this study, a separate site access alternative was evaluated that includes the following options:

- Adding a fourth leg (in the form of a site-access driveway) to the existing SW Martinazzi Avenue/SW Seneca Street intersection and closing the existing SW Martinazzi Avenue site driveway adjacent to the library⁶. For initial evaluation purposes, it was assumed that the modified intersection would be stop-controlled on the east-west Seneca Street approaches



⁶ It should be noted that this site-access is not required to mitigate for any impacts from the proposed development. Rather, it was evaluated in the event the City determined that it had a desire to reconfigure its property and therefore realign the access. Such realignment is not immediately required and can await the City's preferred timeline for redevelopment of its site. For the purposes of analyzing this scenario, it was assumed that the City buildings would be relocated somewhere within the existing shopping center site to ensure that this transportation impact analysis accounted for the trips associated with those uses.

and the new westbound approach would have a separate left- and shared through-right lane.

- Adding a new site driveway that would connect to SW Boones Ferry Road (identified as the Street "A" connection in Figure 2). Given the limited site frontage along SW Boones Ferry Road, the nearby SW Martinazzi Avenue/SW Boones Ferry Road intersection, and the nearby Tualatin River Bridge, it was assumed that this driveway connection would be limited to right-in/right-out access.

Figure 10 shows the assumed site-access configurations and traffic control devices associated with these site-access alternatives. Figures 11a and 11b summarize the resulting intersection operations for the weekday p.m. and Saturday midday peak hours.







LEGEND

- NEW TRAVEL LANE
- STOP SIGN
- TRAFFIC SIGNAL

KITTELSON & ASSOCIATES, INC.
TRANSPORTATION ENGINEERING / PLANNING



ALTERNATIVE SITE ACCESS CONFIGURATION AND TRAFFIC CONTROL DEVICES
TUALATIN, OREGON **FIGURE 10**

H:\proj\12118 - K-Mkt Trueth Trueth Fidenelopment\dings\15\12118\Fig10.dwg Apr 15, 2018 - 4:13pm - mhjgmt Layout Tab: Fig10



LEGEND
 CM = CRITICAL MOVEMENT (TWSC)
 LOS = INTERSECTION LEVEL OF SERVICE (SIGNALIZED/AVSC)/CRITICAL MOVEMENT LEVEL OF SERVICE (TWSC)
 Del = INTERSECTION AVERAGE CONTROL DELAY (SIGNALIZED/AVSC) / CRITICAL MOVEMENT CONTROL DELAY (TWSC)
 VIC = CRITICAL VOLUME-TO-CAPACITY RATIO
 TWSC = TWO-WAY STOP CONTROL
 AVSC = ALL-WAY STOP CONTROL

2014 TOTAL TRAFFIC CONDITIONS, WEEKDAY PM PEAK HOUR
 ALTERNATIVE SITE ACCESS CONFIGURATION
 TUALATIN, OREGON



LEGEND
 CM = CRITICAL MOVEMENT (TWSC)
 LOS = INTERSECTION LEVEL OF SERVICE (SIGNALIZED/AVSC)/CRITICAL MOVEMENT LEVEL OF SERVICE (TWSC)
 Del = INTERSECTION AVERAGE CONTROL DELAY (SIGNALIZED/AVSC)/CRITICAL MOVEMENT CONTROL DELAY (TWSC)
 V/C = CRITICAL VOLUME-TO-CAPACITY RATIO
 TWSC = TWO-WAY STOP CONTROL
 AVSC = ALL-WAY STOP CONTROL

KITTELSON & ASSOCIATES, INC.
 TRANSPORTATION ENGINEERING / PLANNING

2014 TOTAL TRAFFIC CONDITIONS, SATURDAY MIDDAY PEAK HOUR
 ALTERNATIVE SITE ACCESS CONFIGURATION
 TUALATIN, OREGON

H:\proj\12115 - K:\Alan Tualatin\redesign\trngs\fig11b\Fig11b.dwg Apr 17, 2013 - 12:47pm - mhghnt Layout Tab: Fig11b

As shown in the Figure 11a, both the eastbound and westbound left-turn volumes at the modified SW Martinazzi Avenue/SW Seneca Street intersection are forecast to operate at LOS F and over capacity during the weekday p.m. peak hour conditions under this alternative. Based on these conditions, a traffic signal with permissive left-turn phasing was evaluated as a potential mitigation measure. Table 12 summarizes the resulting operations for the weekday p.m. and Saturday midday peak hours.

Table 12: SW Martinazzi Avenue/SW Seneca Street Intersection Mitigation (2014 Total Traffic Conditions)

| Mitigation | Weekday PM Peak Hour | | | Saturday Midday Peak Hour | | |
|--|----------------------|-----|------|---------------------------|-----|------|
| | Delay | LOS | V/C | Delay | LOS | V/C |
| Traffic Signal ¹ | 10.6 | B | 0.68 | 5.5 | A | 0.37 |
| ¹ Permissive left-turn phasing was assumed on all approaches. | | | | | | |

Table 12 indicates that signalization of the intersection will mitigate the LOS F conditions under the previously assumed two-way stop-controlled approach on SW Seneca Street. *Appendix "G" contains the year 2014 total traffic operations worksheets for the alternative access scenario at SW Martinazzi Avenue/SW Seneca Street intersection.* As indicated in Table 12, a traffic signal at the SW Martinazzi Avenue/SW Seneca Street intersection provides a significant capacity and safety benefit. In particular, signalization would:

- Provide additional excess capacity compared to an unsignalized east-west stop-controlled intersection.
- Enhance east-west pedestrian movements by providing a signalized crossing where one does not exist today.

From a signal operations standpoint, progression along SW Martinazzi Avenue is constrained by the endpoints of SW Tualatin-Sherwood Road and SW Boones Ferry. Operational analysis indicates a new signal at Seneca and the existing signal at SW Martinazzi Avenue/SW Boones Ferry Road could operate well during the peak period as a fully actuated, uncoordinated signal. Queuing should be monitored, particularly for other time periods to determine if including one or both of these signals into the adaptive signal system would be advantageous. Note, the new signal at Seneca provides much needed queue management on SW Martinazzi (as seen in SimTraffic modeling) to facilitate traffic flows and represents a large improvement over the no-build conditions for the assumed 2014 traffic demand.

In addition to the modified SW Martinazzi Avenue/SW Seneca Street intersection, Figures 11a and 11b demonstrate the impacts of adding a limited access site-driveway to SW Boones Ferry Road (Street "A" connection). The analysis shows that the driveway would provide a direct connection to SW Boones Ferry Road, but that it would not provide an operational benefit to any other study intersection of site driveway beyond the base site layout analysis.

IMPACTS OF THE NYBERG RIVERS DEVELOPMENT ON IDENTIFIED TRANSPORTATION PLANNING PROJECTS

Figure 1 of the current Tualatin Transportation System Plan (TSP) has identified a future minor collector (Cb) roadway through the proposed Nyberg Rivers development area that would connect SW Nyberg Road to SW Boones Ferry Road. The TSP does not identify a specific alignment for this roadway. The *Tualatin Town Center Plan* subsequently identifies this connection as a "loop road" that would conceptually extend from SW Boones Ferry Road around the Kmart building and internally connect with a future Seneca Street extension from the west. The TSP and Town Center Plan do not specifically address how or where the loop road would make the final connection to SW Nyberg Road.

The Nyberg Rivers redevelopment project has proposed an on-site roadway network that will meet the intent of the loop road connection and completes the connection to SW Nyberg Road. While not meeting all the specific design requirements called for in the City's proposed collector roadway designation, offers the functionality and connectivity that would be provided by a fully developed collector street system. The proposal includes the following:

- A new roadway connection to SW Boones Ferry Road (shown as "Street A" in Figure 2) that includes sidewalks.
- An enhanced site-access driveway to SW Nyberg Road that will better accommodate vehicular queuing and demand.
- A potential future (assuming the City desires to move forward) new site-access connection to SW Martinazzi Avenue that aligns across from SW Seneca Street. This connection would be the Seneca Street extension envisioned in the Town Center Plan. Prior to the City making a decision on any new SW Street Seneca alignment, the redevelopment site plan preserves this connection opportunity in the present or future.
- The preservation of east-west and north-south travel ways that will provide vehicular and pedestrian access between Street A, the Seneca Street alignment/extension, and enhanced access to SW Nyberg Road.
- New sidewalks along the enhanced site-access driveway to SW Nyberg Road that provide pedestrian connections to the integrated site circulation network.
- New bikeway connections along the perimeter of the site.

While all of these elements contribute towards the desired connectivity identified in the Tualatin TSP, development to full city standards is difficult for the following reasons:

- The TSP and Town Center Plan do not specifically address how or where the loop road would connect to SW Nyberg Road, however the graphics suggest the connection would occur somewhere within the vicinity of the existing SW 75th Avenue connection to SW Nyberg Road. Based on current ODOT access management policies, it is recognized that ODOT would not allow such a connection to be made given that it would be within 200-300 feet of the I-5 Southbound ramp terminal. Instead, it has been assumed that the existing SW



Nyberg Road/signalized site driveway would represent the only access connection that ODOT would continue to support within the influence area of the interchange.

- The proposed Nyberg Rivers project is not a complete redevelopment of the existing shopping center site. A large number of existing uses (Michaels, US Bank, Banner Bank, Tualatin City Library and administrative offices, and other retail space) will remain on the site. As a result, much of the site layout (including buildings and parking areas) will remain substantially unchanged.
 - For example, the "loop road" concept in the Tualatin Town Center Plan suggested that the conceptual connection occur around and behind the existing Kmart building. As noted in the proposed development plan, this area of the site will be redeveloped with retail pads. A limited site configuration for the placement of new buildings and a need to maintain a sizable number of existing buildings/parking areas does not accommodate a "loop road" alignment.

Section 5
Conclusions and Recommendations

CONCLUSIONS AND RECOMMENDATIONS

The results of this study indicate that the proposed Nyberg Rivers redevelopment project can be constructed while maintaining acceptable traffic operations and safety at the study intersections, assuming provision of the recommended mitigation measures.

FINDINGS

Year 2012 Existing Conditions

- All of the study intersections currently operate acceptably during the weekday p.m. and Saturday midday peak hours with the exception of the SW Martinazzi Avenue/SW Sagert Street and SW 65th Avenue/SW Sagert Road intersections.
 - At both the SW Martinazzi Avenue/SW Sagert Street and SW 65th Avenue/SW Sagert Street intersections, the southbound approach during the weekday p.m. peak hour operates at LOS F.

Year 2014 Background Traffic Conditions

- All of the study intersections are forecast to operate acceptably during the weekday p.m. and Saturday midday peak hours with the exception of SW Martinazzi Avenue/SW Sagert Road and SW 65th Avenue/SW Sagert Road intersections.
 - At both the SW Martinazzi Avenue/SW Sagert Street and SW 65th Avenue/SW Sagert Street intersections, the southbound approach during the weekday p.m. peak hour is forecast to continue to operate at LOS F. These findings are consistent with analysis conducted as part of the recent Tualatin Transportation System Plan (TSP) Update and future improvements are identified within the TSP for both of these intersections.

Proposed Redevelopment Plan

- Under the redevelopment plan, the existing SW 75th Avenue connection to SW Nyberg Road will be closed to improve access management along SW Nyberg Road and to better accommodate the redevelopment proposal.
- The existing signalized access on SW Nyberg Road that currently serves the shopping center and the adjacent Fred Meyer site will remain. However, the following changes are proposed in order to better accommodate the proposed redevelopment, provide additional capacity for future growth in traffic, and improve safety relative to the existing condition:
 - A westbound right-turn lane will be developed on SW Nyberg Road to enhance access to the site and minimize vehicle queuing on SW Nyberg Road.

- The existing site driveway is proposed to be widened as shown in the proposed site plan. This widening will include dual southbound left-turn lanes, a shared through/right-turn lane, and dual in-bound receiving lanes. A raised median will be constructed in the driveway throat to reduce turning conflicts on-site turning maneuvers and manage vehicle queues on the approach to the signal.
- The north and south approach signal phasing is proposed to be modified from permissive left-turn phasing to split phasing.
- With the anticipated mix of new retail uses, the proposed redevelopment is estimated to generate 405 net new trips during the weekday p.m. peak hour and 725 net new trips during the Saturday midday peak hour.

Year 2014 Total Traffic Conditions

- All of the study intersections within the immediate site vicinity, including the site access points and internal site intersections, are forecast to operate acceptably during the weekday p.m. and Saturday midday peak hours.
- The SW Martinazzi Avenue/SW Sagert Road and SW 65th Avenue/SW Sagert Road intersections are forecast to continue to operate at LOS F.
 - The proposed development will have an insignificant impact at either intersection, resulting in an estimated 1.6% and 0.6% increase, respectively, during the weekday p.m. peak hour.
 - The Tualatin TSP has identified mitigations for these two intersections that, when implemented, will address the long-term operations.
 - The Washington County Transportation Development Tax (TDT) in part funds an improvement project on SW Sagert Street that will add capacity and reduce delay to both intersections.
- Beyond the site's frontage along SW Tualatin Sherwood Road and SW Martinazzi Avenue, where significant transportation improvements are proposed (including implementing the intent of the City's Loop Road), the project will have an insignificant impact on the other study intersections (generally resulting in less than a two percent increase in traffic relative to 2014 background conditions).
- At all signalized intersections beyond the site frontage (with the exception of the I-5 interchange), the project will add on average one vehicle or less per signal cycle to any movement. This level of impact is less than significant by any traffic engineering standard and well below the level that would be perceived by motorists.
- Anticipated vehicle queues can be accommodated at the I-5 ramp terminals and the SW Nyberg Road/Signalized site driveway.



- The proposed Nyberg Rivers redevelopment project has proposed an on-site roadway network that will meet the intent of the loop road connection. The proposal includes the following:
 - A new roadway connection to SW Boones Ferry Road (shown as "Street A" in Figure 2) that includes sidewalks.
 - An enhanced site-access driveway to SW Nyberg Road that will better accommodate vehicular queuing and demand.
 - A potential future (assuming the City desires to move forward) new site-access connection to SW Martinazzi Avenue that aligns across from SW Seneca Street. This connection would be the Seneca Street extension envisioned in the Town Center Plan. Prior to the City making a decision on any new SW Street Seneca alignment, the redevelopment site plan preserves this connection opportunity in the present or future.
 - The preservation of east-west and north-south travel ways that will provide vehicular and pedestrian access between Street A, the Seneca Street alignment/extension, and enhanced access to SW Nyberg Road.
 - New sidewalks along the enhanced site-access driveway to SW Nyberg Road that provide pedestrian connections to the integrated site circulation network.
 - New bikeway connections along the perimeter of the site.

SW Martinazzi Avenue and SW Boones Ferry Road Site Access Alternatives

- An alternative site access scenario was evaluated that demonstrates the impact of potentially adding a fourth leg (in the form of a site-access driveway) to the existing SW Martinazzi Avenue/SW Seneca Street intersection and closing the existing SW Martinazzi Avenue site driveway adjacent to the library. This analysis produced the following results:
 - The east and west approaches to a modified SW Martinazzi Avenue/SW Seneca Street intersection would operate at Level of Service (LOS) F and over capacity during the weekday p.m. peak hour with the addition of a fourth site-access leg. Signalizing the intersection would provide the following:
 - Mitigation that results in LOS A or better (a significant improvement over existing conditions).
 - Additional excess intersection capacity beyond what is needed to serve the Nyberg Rivers project traffic.
 - Enhanced east-west pedestrian connectivity across SW Martinazzi Avenue.
 - A safety improvement relative to stop sign control.

- In addition to the modified SW Martinazzi Avenue/SW Seneca Street intersection, another site-access alternative was evaluated that demonstrates the impacts of adding a limited access site-driveway to SW Boones Ferry Road. The analysis shows that with a direct connection to SW Boones Ferry Road, there would be some shifting of site-generated traffic off of SW Martinazzi Avenue. This additional access would further improve connectivity, help implement the City's loop road concept, and provide additional capacity beyond what is needed to serve the Nyberg Rivers project.

RECOMMENDATIONS

- With the proposed Nyberg Rivers redevelopment:
 - The existing SW 75th Avenue site-access driveway to SW Nyberg Road should be closed in order to minimize turning movement conflicts, allow for the construction of a westbound right-turn lane at the SW Nyberg Road/signalized site driveway, and improve the interchange access spacing conditions along SW Nyberg Road.
 - To better accommodate the anticipated site-generated traffic at the SW Nyberg Road/Signalized site driveway:
 - A new westbound right-turn lane should be constructed on SW Nyberg Road.
 - The site driveway should be modified to include dual southbound left-turn lanes, a shared through/right-turn lane, and two inbound receiving lanes.
 - The existing north/south traffic signal phasing should be modified from permissive phasing to split phasing. Right-turn overlap phasing should be provided for the westbound right-turn movement into the Nyberg Rivers site.
- If site access to SW Martinazzi Avenue is provided via a new fourth leg to the SW Martinazzi Avenue/SW Seneca Street intersection, the intersection should be signalized.
- If a new site access driveway is provided to SW Boones Ferry Road, the driveway should be limited to right-in/right-out only access.

Appendix A
Scoping Memorandum



KITTELSON & ASSOCIATES, INC.

TRANSPORTATION ENGINEERING / PLANNING

610 SW Alder Street, Suite 700, Portland, OR 97205 P 503.228.5230 F 503.273.8169

DRAFT SCOPING MEMORANDUM #1

Date: August 22, 2012 Project #: 12116

To: Kaaren Hofmann, P.E., Tony Doran, City of Tualatin
Jinde Zhu, P.E., Washington County
Avi Tayar, P.E., Doug Baumgartner, Marah Danielson, ODOT

From: Matt Hughart, AICP; Chris Brehmer, P.E.; Mark Vandehey, P.E.

Project: Nyberg Woods II – Tualatin, OR

Subject: Proposed Traffic Study Scope of Work

The purpose of this memorandum is to provide an opportunity for the City of Tualatin, Washington County, and ODOT staff to review and provide guidance on project assumptions associated with conducting a traffic study for a proposed partial redevelopment of the existing K-Mart shopping center in Tualatin, Oregon. Details of the proposed project assumptions are documented below.

Proposed Development Plan

The project entails a partial redevelopment of the existing shopping center currently anchored by a K-Mart and supported by a number of other retail uses. While a specific site plan and tenant mix is still being developed, the redevelopment will likely entail the following components:

- K-Mart will close and its existing 96,799 square foot building will be removed.
- The existing adult cabaret will close and its 4,800 square foot building will be removed.
- Approximately 208,180 square feet of new shopping center uses and 30,000 square feet of office space will be constructed on the site.
- The existing 3,500 square foot building currently occupied by a Wendy's will be relocated to a new pad within the shopping center site.
- All other existing buildings will remain and their uses will continue to operate as is.
- The existing 75th Avenue access to SW Nyberg Road is proposed to be closed.

- The existing signalized access on SW Nyberg Road that currently serves the site and the Fred Meyer site will remain. The traffic study will look at potential enhancements to this intersection to better accommodate site traffic and vehicle queuing.
- The traffic study will look at different access scenarios to SW Martinazzi Avenue and SW Boones Ferry Road. Specifically, the impacts/improvements necessary to realign the existing SW Martinazzi Avenue driveway (adjacent to the library/city hall) to access SW Martinazzi Avenue across from Seneca Street and a new site access driveway to SW Boones Ferry Road.

Proposed Study Intersections


A preliminary list of study intersections was identified based on the size of the anticipated development and its location. This list of intersections is identified below. Figures 1 and 2 illustrate their location and associated lane configurations/traffic control devices.

- SW Martinazzi Avenue/SW Boones Ferry Road (#3)
- SW Martinazzi Avenue/Existing Site Driveway (near City Hall) (#4)
- SW Martinazzi Avenue/SW Seneca Street (#5)
- SW Martinazzi Avenue/Existing Site Driveway (#6)
- SW Martinazzi Avenue/Existing Right-Out Only Driveway (#7)
- SW Tualatin-Sherwood Road/SW Martinazzi Avenue (#17)
- SW Nyberg Street/SW Martinazzi Avenue (#8)
- SW Nyberg Street/Unsignalized Site Driveway (#9)
- SW Nyberg Street/SW Tualatin-Sherwood Road/Fred Meyer/Site Driveway (#10)
- SW Nyberg Street/SW 75th Avenue (#11)
- SW Nyberg Street/I-5 SB Ramp Terminal (#12)
- SW Nyberg Street/I-5 NB Ramp Terminal (#13)
- SW Nyberg Street/Signalized entrance to Nyberg Woods (#14)

In anticipation of the need to study these intersections at a minimum, traffic counts were obtained in May 2012 (before the end of the spring school semester) during the analysis periods discussed in the following section.


LEGEND

CM = CRITICAL MOVEMENT (UN SIGNALIZED)
 LOS = INTERSECTION LEVEL OF SERVICE (SIGNALIZED)/CRITICAL MOVEMENT LEVEL OF SERVICE (UN SIGNALIZED)
 Del = INTERSECTION AVERAGE CONTROL DELAY (SIGNALIZED)/CRITICAL MOVEMENT CONTROL DELAY (UN SIGNALIZED)
 V/C = CRITICAL VOLUME-TO-CAPACITY RATIO



STUDY INTERSECTIONS AND TRIP DISTRIBUTION PATTERN TUALATIN, OREGON

FIGURE 1



KITTELSON & ASSOCIATES, INC.
TRANSPORTATION ENGINEERING / PLANNING

LANE CONFIGURATION AND TRAFFIC CONTROL DEVICES
TUALATIN, OREGON

Traffic Analysis Periods and Scenarios

In order to assess the impact of the proposed development, traffic conditions are proposed to be analyzed during the peak hour of the following time periods:

- Weekday evening roadway peak hour (3:00-6:00 p.m.)
- Saturday midday peak hour (11:00 a.m. - 2:00 p.m.)

The proposed redevelopment is anticipated to be completed by 2014. Intersections are proposed to be analyzed for the following three time periods:

- Existing (2012)
- Background (without shopping center redevelopment) (2014)
- Total Traffic (with shopping center redevelopment) (2014)

EXISTING CONDITIONS ANALYSIS

The existing operations will be assessed at the identified study intersections during the weekday evening and Saturday midday peak periods using the traffic data collected. Synchro 8 analysis software will be used in accordance with the methodology in the *2010 Highway Capacity Manual* and the *ODOT Analysis Procedures Manual* (where applicable). The most recent 5-year crash data at each study intersection will be obtained and reviewed.

BACKGROUND ANALYSIS

This analysis will assess traffic operations at the study intersections during the two study periods in the year 2014 without any improvements or changes to the roadway network. Traffic volumes for the year 2014 will be based on an assumed growth rate of 1.0% per year. This near-term growth rate was derived from a review of Washington County traffic counts on Tualatin-Sherwood Road and Nyberg Street. In-process development data will be obtained from the City of Tualatin and Washington County and included as part of year 2014 forecast traffic volumes.

TRIP GENERATION

Given that the proposed project is only a partial redevelopment of the larger shopping center, a trip generation methodology was developed that would more accurately reflect the characteristics of a unified and vibrant shopping center. This methodology is outlined in greater detail in Appendix A. The resulting trip estimate is summarized in Table 1 below.

Table 1 Trip Generation

| | ITE Code | Size (sq. ft.) | Weekday PM Peak Hour | | | Saturday Midday Peak Hour | | |
|--|----------|----------------------|----------------------|------------|------------|---------------------------|------------|------------|
| | | | Total | In | Out | Total | In | Out |
| Existing Site | | | | | | | | |
| Existing Site Driveways ¹ | - | - | 945 | 435 | 510 | 970 | 490 | 480 |
| <i>Less Existing Library²</i> | 590 | 22,123 | (160) | (75) | (85) | (150) | (80) | (70) |
| <i>Less Existing Civic Uses³</i> | 715 | ~10,000 | (50) | (10) | (40) | - | - | - |
| Total Existing Retail | | | 735 | 350 | 385 | 820 | 410 | 410 |
| Future Site | | | | | | | | |
| Shopping Center | 820 | 264,924 ⁴ | 1,225 | 600 | 625 | 1,615 | 840 | 775 |
| <i>Less Existing Retail Driveway Counts</i> | - | - | (735) | (350) | (385) | (820) | (410) | (410) |
| Sub Total | - | - | 490 | 250 | 240 | 795 | 430 | 365 |
| <i>Pass-by Trips (Weekday 34%, Sat. 26%)</i> | - | - | (160) | (80) | (80) | (190) | (95) | (95) |
| Office | 710 | 30,000 | 45 | 10 | 35 | 10 | 5 | 5 |
| Net New Trips | | | 375 | 180 | 195 | 615 | 340 | 275 |

¹Represents the total site driveway counts during the weekday p.m. peak hour of 4:35-5:35 p.m. and Saturday midday peak hour of 12:10-1:10 p.m. This is the traffic volume being generated by the existing 158,343 square feet of shopping center currently residing on the site.

²The library traffic counts were estimated using the *Library* land use in ITE Trip Generation.

³The City Hall traffic counts were estimated using the *Single Tenant Office Building* land use in ITE Trip Generation. The existing City Hall square footage was estimated to be approximately 10,000 square feet in size.

⁴Includes the 158,343 square feet of existing shopping center (minus the 96,799 square foot K-Mart and 4,800 square foot adult cabaret) plus the 208,180 square feet of proposed shopping center uses.


TRIP ASSIGNMENT

The trip distribution pattern for the proposed project was estimated based on a select zone assignment obtained from Washington County's travel demand model. The resulting trip distribution pattern is also shown in Figure 1.

PROPORTIONATE SHARE IMPACT

City staff requested a proportional impact analysis for the project based on the proposed trip generation and distribution for the site at the May 30, 2012 preliminary project meeting with the City of Tualatin. To complete this analysis, regionally significant traffic counts used in the on-going Tualatin Transportation System Plan Update were reused. The resulting proportional impact of the net new site-generate trips at each regionally significant intersection is illustrated in Figure 3. Based on these findings, we request that City, County, and ODOT staff review these impacts and confirm the need to study the remaining list of intersections not previously identified earlier in this memorandum.

NOTE: SEE FIGURE 1 FOR LEGEND



PROPORTIONAL SHARE IMPACT
SITE GENERATED TRIPS - WEEKDAY PM PEAK HOUR
TUALATIN, OREGON

We trust that this memorandum provide adequate documentation of the proposed development plan, study intersections, analysis scenarios, and estimated trip generation. We formally request that the City of Tualatin, Washington County, and ODOT provide written confirmation regarding the proposed methodology and project assumptions as soon as possible. If you have any questions, please give us a call at (503)228-5230.

Appendix A
Trip Generation
Methodology

PROPOSED TRIP GENERATION METHODOLOGY

The proposed project is only a partial redevelopment of the larger shopping center. In order to avoid overestimating the trip generation characteristics of the net new retail uses, the following trip generation methodology is proposed:

- Traffic counts were conducted at all of the site driveways to quantify the trip generation profile of the existing retail and civic uses currently operating on the site.
- Recognizing that the City offices/library are not retail uses and the layout of the site/parking fields prevents an accurate quantification of trips being generated by these uses, estimates were developed using the standard reference manual, *Trip Generation*. The Library and Single Tenant Office Building land uses were used in the estimate process. The resulting estimates were then subtracted from the existing site driveway counts to produce a trip profile estimate for the existing 158,343 square feet of retail building space at the site.
- A trip generation rate was calculated using the Shopping Center land use in *ITE Trip Generation* for the 208,180 square feet of new retail use plus the 56,744 square feet of remaining retail uses (158,343 square feet of existing retail minus 96,799 square foot K-Mart and 4,800 square foot adult cabaret). A separate estimate for the 30,000 square foot of office use was also prepared.
- The existing site retail traffic estimate was then subtracted from the total shopping center and office trip generation estimate to arrive at a total trip estimate for the net increase in shopping center and office square footage. A pass-by rate reduction of 34% was assumed for the shopping center component to generate the Net New Trip estimate for the site.

Table 2 below illustrates the trip generation calculation process.

Table 2 Trip Generation Estimate

| | ITE Code | Size (sq. ft.) | Weekday PM Peak Hour | | | Saturday Midday Peak Hour | | |
|--|----------|----------------------|----------------------|------------|------------|---------------------------|------------|------------|
| | | | Total | In | Out | Total | In | Out |
| Existing Site | | | | | | | | |
| Existing Site Driveways ¹ | - | - | 945 | 435 | 510 | 970 | 490 | 480 |
| <i>Less Existing Library²</i> | 590 | 22,123 | (160) | (75) | (85) | (150) | (80) | (70) |
| <i>Less Existing Civic Uses³</i> | 715 | ~10,000 | (50) | (10) | (40) | - | - | - |
| Total Existing Retail | | | 735 | 350 | 385 | 820 | 410 | 410 |
| Future Site | | | | | | | | |
| Shopping Center | 820 | 264,924 ⁴ | 1,225 | 600 | 625 | 1,615 | 840 | 775 |
| <i>Less Existing Retail Driveway Counts</i> | - | - | (735) | (350) | (385) | (820) | (410) | (410) |
| Sub Total | - | - | 490 | 250 | 240 | 795 | 430 | 365 |
| <i>Pass-by Trips (Weekday 34%, Sat. 26%)</i> | - | - | (160) | (80) | (80) | (190) | (95) | (95) |
| Office | 710 | 30,000 | 45 | 10 | 35 | 10 | 5 | 5 |
| Net New Trips | | | 375 | 180 | 195 | 615 | 340 | 275 |

¹Represents the total site driveway counts during the weekday p.m. peak hour of 4:35-5:35 p.m. and Saturday midday peak hour of 12:10-1:10 p.m. This is the traffic volume being generated by the existing 158,343 square feet of shopping center currently residing on the site.

²The library traffic counts were estimated using the *Library* land use in ITE Trip Generation.

³The City Hall traffic counts were estimated using the *Single Tenant Office Building* land use in ITE Trip Generation. The existing City Hall square footage was estimated to be approximately 10,000 square feet in size.

⁴Includes the 158,343 square feet of existing shopping center (minus the 96,799 square foot K-Mart and 4,800 square foot adult cabaret) plus the 208,180 square feet of proposed shopping center uses.

As shown in Table 2, the combined 264,180 square feet of shopping center use is estimated to generate 1,225 weekday p.m. peak hour trips and 1,615 Saturday midday peak hour trips, respectfully. To check the validity of this methodology, weekday p.m. and Saturday midday peak hour traffic counts were taken at the previously developed 215,000 square foot Nyberg Woods shopping center on the east side of I-5. Based on these counts, it was determined that this shopping center is generating approximately 3.76 trips/1,000 square feet during the weekday p.m. peak hour and 4.76 trips/1,000 square feet during the Saturday midday peak period. Applying these rates to proposed addition of 208,180 square feet of new retail space indicates that the proposed trip generation methodology is consistent with or more conservative than actual trip generation observations at similar retail centers.


Appendix B
Traffic Count Data

Type of peak hour being reported: User-Defined










Method for determining peak hour: Total Entering Volume

LOCATION: SW Martinazzi Ave -- SW Boones Ferry Rd
CITY/STATE: Tualatin, OR

QC JOB #: 10772125
DATE: Tue, Jun 05 2012



Peak-Hour: 4:35 PM -- 5:35 PM
Peak 15-Min: 5:00 PM -- 5:15 PM



| 5-Min Count Period Beginning At | SW Martinazzi Ave (Northbound) | | | | SW Martinazzi Ave (Southbound) | | | | SW Boones Ferry Rd (Eastbound) | | | | SW Boones Ferry Rd (Westbound) | | | | Total | Hourly Totals |
|------------------------------------|--------------------------------|------|-------|---|--------------------------------|------|-------|---|--------------------------------|------|-------|---|--------------------------------|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 4:00 PM | 27 | 0 | 11 | 0 | 0 | 0 | 0 | 0 | 0 | 57 | 12 | 0 | 25 | 70 | 0 | 0 | 202 | 2305 |
| 4:05 PM | 27 | 0 | 38 | 0 | 0 | 0 | 0 | 0 | 0 | 61 | 16 | 0 | 21 | 64 | 0 | 0 | 227 | 2346 |
| 4:10 PM | 32 | 0 | 29 | 0 | 0 | 0 | 0 | 0 | 1 | 48 | 15 | 0 | 26 | 70 | 0 | 0 | 221 | 2370 |
| 4:15 PM | 29 | 0 | 38 | 0 | 0 | 0 | 0 | 0 | 0 | 59 | 8 | 0 | 30 | 81 | 0 | 0 | 245 | 2431 |
| 4:20 PM | 27 | 0 | 28 | 0 | 0 | 0 | 0 | 0 | 0 | 53 | 12 | 0 | 24 | 67 | 0 | 0 | 211 | 2464 |
| 4:25 PM | 38 | 0 | 30 | 0 | 0 | 0 | 0 | 0 | 0 | 40 | 13 | 0 | 26 | 64 | 0 | 0 | 211 | 2509 |
| 4:30 PM | 17 | 0 | 16 | 0 | 0 | 0 | 0 | 0 | 0 | 49 | 12 | 0 | 32 | 76 | 0 | 0 | 202 | 2516 |
| 4:35 PM | 39 | 0 | 40 | 0 | 0 | 0 | 0 | 0 | 0 | 50 | 12 | 0 | 19 | 65 | 0 | 0 | 225 | 2545 |
| 4:40 PM | 22 | 0 | 27 | 0 | 0 | 1 | 0 | 0 | 0 | 47 | 15 | 0 | 35 | 90 | 0 | 0 | 237 | 2583 |
| 4:45 PM | 23 | 0 | 30 | 0 | 0 | 0 | 0 | 0 | 0 | 53 | 16 | 0 | 33 | 74 | 1 | 0 | 230 | 2599 |
| 4:50 PM | 20 | 0 | 19 | 0 | 0 | 0 | 0 | 0 | 1 | 64 | 14 | 0 | 30 | 81 | 0 | 0 | 229 | 2622 |
| 4:55 PM | 28 | 0 | 21 | 0 | 0 | 0 | 0 | 0 | 0 | 52 | 15 | 0 | 29 | 70 | 0 | 0 | 215 | 2655 |
| 5:00 PM | 26 | 0 | 41 | 0 | 0 | 0 | 0 | 0 | 0 | 54 | 12 | 0 | 36 | 75 | 0 | 0 | 244 | 2697 |
| 5:05 PM | 25 | 0 | 42 | 0 | 0 | 0 | 0 | 0 | 0 | 44 | 9 | 0 | 43 | 81 | 0 | 0 | 244 | 2714 |
| 5:10 PM | 29 | 0 | 30 | 0 | 0 | 0 | 0 | 0 | 0 | 56 | 15 | 0 | 41 | 79 | 0 | 0 | 250 | 2743 |
| 5:15 PM | 25 | 0 | 33 | 0 | 0 | 0 | 0 | 0 | 0 | 59 | 15 | 0 | 28 | 78 | 0 | 0 | 238 | 2736 |
| 5:20 PM | 23 | 0 | 33 | 0 | 0 | 0 | 0 | 0 | 0 | 51 | 10 | 0 | 42 | 78 | 0 | 0 | 237 | 2762 |
| 5:25 PM | 25 | 0 | 25 | 0 | 0 | 0 | 0 | 0 | 0 | 60 | 14 | 0 | 38 | 66 | 0 | 0 | 228 | 2779 |
| 5:30 PM | 29 | 0 | 25 | 0 | 0 | 0 | 0 | 0 | 0 | 55 | 12 | 0 | 30 | 66 | 0 | 0 | 217 | 2794 |
| 5:35 PM | 35 | 0 | 32 | 0 | 0 | 0 | 0 | 0 | 0 | 45 | 12 | 0 | 30 | 73 | 1 | 0 | 228 | 2797 |
| 5:40 PM | 28 | 0 | 26 | 0 | 0 | 0 | 0 | 0 | 0 | 42 | 12 | 0 | 31 | 76 | 0 | 0 | 215 | 2775 |
| 5:45 PM | 36 | 0 | 22 | 0 | 0 | 0 | 1 | 0 | 0 | 39 | 12 | 0 | 30 | 75 | 0 | 0 | 215 | 2760 |
| 5:50 PM | 26 | 0 | 23 | 0 | 0 | 0 | 0 | 0 | 0 | 42 | 5 | 0 | 31 | 81 | 0 | 0 | 208 | 2739 |
| 5:55 PM | 28 | 0 | 24 | 0 | 0 | 0 | 0 | 0 | 0 | 32 | 9 | 0 | 24 | 61 | 0 | 0 | 178 | 2702 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| All Vehicles | 320 | 0 | 452 | 0 | 0 | 0 | 0 | 0 | 0 | 616 | 144 | 0 | 480 | 940 | 0 | 0 | 2952 | |
| Heavy Trucks | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 8 | 0 | 0 | 8 | 8 | 0 | 0 | 28 | |
| Pedestrians | | 4 | | | | 12 | | | | 8 | | | | 12 | | | 36 | |
| Bicycles | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 2 | 0 | 0 | 4 | |
| Railroad | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined








Method for determining peak hour: Total Entering Volume

LOCATION: SW Martinazzi Ave -- Existing Site Dwy near City Hall
CITY/STATE: Tualatin, OR

QC JOB #: 10772123
DATE: Tue, Jun 05 2012



Peak-Hour: 4:35 PM -- 5:35 PM
Peak 15-Min: 5:00 PM -- 5:15 PM



| 5-Min Count Period | SW Martinazzi Ave (Northbound) | | | | SW Martinazzi Ave (Southbound) | | | | Existing Site Dwy near City Hall (Eastbound) | | | | Existing Site Dwy near City Hall (Westbound) | | | | Total | Hourly Totals |
|-----------------------|--------------------------------|------|-------|---|--------------------------------|------|-------|---|--|------|-------|---|--|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 4:00 PM | 0 | 39 | 8 | 0 | 14 | 30 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 8 | 0 | 102 | 1149 |
| 4:05 PM | 0 | 57 | 6 | 0 | 14 | 18 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 11 | 0 | 109 | 1166 |
| 4:10 PM | 0 | 54 | 5 | 0 | 8 | 30 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | 0 | 14 | 0 | 116 | 1192 |
| 4:15 PM | 0 | 50 | 3 | 0 | 13 | 34 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 9 | 0 | 110 | 1208 |
| 4:20 PM | 0 | 42 | 9 | 0 | 11 | 25 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 6 | 0 | 97 | 1210 |
| 4:25 PM | 0 | 48 | 7 | 0 | 11 | 26 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 14 | 0 | 108 | 1226 |
| 4:30 PM | 0 | 37 | 8 | 0 | 12 | 32 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 5 | 0 | 98 | 1228 |
| 4:35 PM | 0 | 58 | 3 | 0 | 13 | 27 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 18 | 0 | 122 | 1252 |
| 4:40 PM | 0 | 47 | 5 | 0 | 15 | 35 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 10 | 0 | 112 | 1275 |
| 4:45 PM | 0 | 37 | 5 | 0 | 12 | 40 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 8 | 0 | 102 | 1283 |
| 4:50 PM | 0 | 42 | 6 | 0 | 10 | 37 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 11 | 0 | 108 | 1276 |
| 4:55 PM | 0 | 50 | 3 | 0 | 14 | 27 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 9 | 0 | 105 | 1289 |
| 5:00 PM | 0 | 54 | 5 | 0 | 13 | 43 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 9 | 0 | 128 | 1315 |
| 5:05 PM | 0 | 47 | 7 | 0 | 7 | 40 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 14 | 0 | 118 | 1324 |
| 5:10 PM | 0 | 59 | 7 | 0 | 14 | 41 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 122 | 1330 |
| 5:15 PM | 0 | 49 | 10 | 0 | 14 | 30 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 8 | 0 | 114 | 1334 |
| 5:20 PM | 0 | 44 | 6 | 0 | 11 | 38 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 8 | 0 | 109 | 1346 |
| 5:25 PM | 0 | 52 | 4 | 0 | 10 | 40 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 3 | 0 | 113 | 1351 |
| 5:30 PM | 0 | 49 | 4 | 0 | 9 | 35 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | 0 | 5 | 0 | 107 | 1360 |
| 5:35 PM | 0 | 57 | 5 | 0 | 9 | 32 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 5 | 0 | 110 | 1348 |
| 5:40 PM | 0 | 46 | 6 | 0 | 9 | 35 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 10 | 0 | 110 | 1346 |
| 5:45 PM | 0 | 48 | 4 | 0 | 4 | 35 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | 0 | 7 | 0 | 103 | 1347 |
| 5:50 PM | 0 | 47 | 4 | 0 | 6 | 39 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 5 | 0 | 104 | 1343 |
| 5:55 PM | 0 | 44 | 3 | 0 | 9 | 20 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 7 | 0 | 83 | 1321 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| All Vehicles | 0 | 640 | 76 | 0 | 136 | 496 | 0 | 0 | 0 | 0 | 0 | 0 | 28 | 0 | 96 | 0 | 1472 | |
| Heavy Trucks | 0 | 4 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 8 | |
| Pedestrians | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 12 | 0 | 0 | 0 | 16 | |
| Bicycles | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | |
| Railroad | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Stopped Buses | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |


Comments: N

Type of peak hour being reported: User-Defined






Method for determining peak hour: Total Entering Volume

LOCATION: SW Martinazzi Ave -- SW Seneca St
CITY/STATE: Tualatin, OR

QC JOB #: 10772121
DATE: Tue, Jun 05 2012



Peak-Hour: 4:35 PM -- 5:35 PM
Peak 15-Min: 5:00 PM -- 5:15 PM



| 5-Min Count Period | SW Martinazzi Ave (Northbound) | | | | SW Martinazzi Ave (Southbound) | | | | SW Seneca St (Eastbound) | | | | SW Seneca St (Westbound) | | | | Total | Hourly Totals |
|-----------------------|--------------------------------|------|-------|---|--------------------------------|------|-------|---|--------------------------|------|-------|---|--------------------------|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 4:00 PM | 6 | 43 | 0 | 0 | 0 | 24 | 7 | 0 | 2 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 87 | 1076 |
| 4:05 PM | 6 | 66 | 0 | 0 | 0 | 25 | 2 | 0 | 3 | 0 | 9 | 0 | 0 | 0 | 0 | 0 | 111 | 1101 |
| 4:10 PM | 11 | 46 | 0 | 0 | 0 | 29 | 4 | 0 | 3 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 98 | 1109 |
| 4:15 PM | 7 | 57 | 0 | 0 | 0 | 32 | 1 | 0 | 2 | 0 | 6 | 0 | 0 | 0 | 0 | 0 | 105 | 1130 |
| 4:20 PM | 7 | 43 | 0 | 0 | 0 | 22 | 5 | 0 | 5 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 87 | 1128 |
| 4:25 PM | 10 | 56 | 0 | 0 | 0 | 31 | 1 | 0 | 3 | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 104 | 1140 |
| 4:30 PM | 9 | 36 | 0 | 0 | 0 | 34 | 3 | 0 | 3 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 86 | 1130 |
| 4:35 PM | 6 | 62 | 0 | 0 | 0 | 27 | 1 | 0 | 3 | 0 | 7 | 0 | 0 | 0 | 0 | 0 | 106 | 1153 |
| 4:40 PM | 9 | 47 | 0 | 0 | 0 | 30 | 5 | 0 | 2 | 0 | 10 | 0 | 0 | 0 | 0 | 0 | 103 | 1174 |
| 4:45 PM | 10 | 45 | 0 | 0 | 0 | 41 | 1 | 0 | 3 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 104 | 1186 |
| 4:50 PM | 1 | 45 | 0 | 0 | 0 | 30 | 5 | 0 | 4 | 0 | 10 | 0 | 0 | 0 | 0 | 0 | 95 | 1179 |
| 4:55 PM | 9 | 48 | 0 | 0 | 0 | 32 | 5 | 0 | 1 | 0 | 7 | 0 | 0 | 0 | 0 | 0 | 102 | 1188 |
| 5:00 PM | 12 | 60 | 0 | 0 | 0 | 38 | 5 | 0 | 1 | 0 | 6 | 0 | 0 | 0 | 0 | 0 | 122 | 1223 |
| 5:05 PM | 7 | 56 | 0 | 0 | 0 | 46 | 1 | 0 | 2 | 0 | 9 | 0 | 0 | 0 | 0 | 0 | 121 | 1233 |
| 5:10 PM | 5 | 53 | 0 | 0 | 0 | 37 | 5 | 0 | 6 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 110 | 1245 |
| 5:15 PM | 8 | 51 | 0 | 0 | 0 | 20 | 3 | 0 | 7 | 0 | 8 | 0 | 0 | 0 | 0 | 0 | 97 | 1237 |
| 5:20 PM | 9 | 42 | 0 | 0 | 0 | 38 | 5 | 0 | 7 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 102 | 1252 |
| 5:25 PM | 12 | 55 | 0 | 0 | 0 | 40 | 7 | 0 | 3 | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 120 | 1268 |
| 5:30 PM | 6 | 44 | 0 | 0 | 0 | 34 | 7 | 0 | 3 | 0 | 9 | 0 | 0 | 0 | 0 | 0 | 103 | 1285 |
| 5:35 PM | 10 | 66 | 0 | 0 | 0 | 25 | 6 | 0 | 2 | 0 | 7 | 0 | 0 | 0 | 0 | 0 | 116 | 1295 |
| 5:40 PM | 9 | 43 | 0 | 0 | 0 | 35 | 4 | 0 | 5 | 0 | 10 | 0 | 0 | 0 | 0 | 0 | 106 | 1298 |
| 5:45 PM | 5 | 59 | 0 | 0 | 0 | 38 | 4 | 0 | 2 | 0 | 7 | 0 | 0 | 0 | 0 | 0 | 115 | 1309 |
| 5:50 PM | 6 | 41 | 0 | 0 | 0 | 36 | 5 | 0 | 2 | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 93 | 1307 |
| 5:55 PM | 3 | 49 | 0 | 0 | 0 | 25 | 2 | 0 | 4 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 84 | 1289 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| All Vehicles | 96 | 676 | 0 | 0 | 0 | 484 | 44 | 0 | 36 | 0 | 76 | 0 | 0 | 0 | 0 | 0 | 1412 | |
| Heavy Trucks | 0 | 4 | 0 | 0 | 0 | 8 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 12 | |
| Pedestrians | | 4 | | | | 20 | | | | | | | 8 | | | | 32 | |
| Bicycles | 0 | 1 | 0 | | 0 | 1 | 0 | | 0 | 0 | 0 | | 0 | 0 | 0 | | 2 | |
| Railroad | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined






Method for determining peak hour: Total Entering Volume

LOCATION: SW Martinazzi Ave -- Existing Site Dwy
CITY/STATE: Tualatin, OR

QC JOB #: 10772119
DATE: Tue, Jun 05 2012



Peak-Hour: 4:35 PM -- 5:35 PM
Peak 15-Min: 5:00 PM -- 5:15 PM



| 5-Min Count Period Beginning At | SW Martinazzi Ave (Northbound) | | | | SW Martinazzi Ave (Southbound) | | | | Existing Site Dwy (Eastbound) | | | | Existing Site Dwy (Westbound) | | | | Total | Hourly Totals |
|------------------------------------|--------------------------------|------|-------|---|--------------------------------|------|-------|---|-------------------------------|------|-------|---|-------------------------------|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 4:00 PM | 0 | 48 | 0 | 0 | 0 | 29 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 78 | 978 |
| 4:05 PM | 0 | 72 | 1 | 0 | 0 | 34 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 108 | 1007 |
| 4:10 PM | 0 | 52 | 0 | 0 | 1 | 33 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 5 | 92 | 1013 |
| 4:15 PM | 0 | 63 | 1 | 0 | 1 | 37 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 103 | 1044 |
| 4:20 PM | 0 | 47 | 0 | 0 | 2 | 25 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 3 | 78 | 1037 |
| 4:25 PM | 0 | 62 | 0 | 0 | 0 | 34 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 4 | 101 | 1054 |
| 4:30 PM | 0 | 44 | 0 | 0 | 0 | 35 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 1 | 81 | 1051 |
| 4:35 PM | 0 | 61 | 1 | 0 | 1 | 33 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 7 | 103 | 1075 |
| 4:40 PM | 0 | 55 | 0 | 0 | 1 | 39 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 96 | 1095 |
| 4:45 PM | 0 | 54 | 0 | 0 | 0 | 45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 100 | 1117 |
| 4:50 PM | 0 | 42 | 1 | 0 | 1 | 39 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 87 | 1113 |
| 4:55 PM | 0 | 55 | 1 | 0 | 2 | 37 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 97 | 1124 |
| 5:00 PM | 0 | 71 | 0 | 0 | 0 | 44 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 116 | 1162 |
| 5:05 PM | 0 | 59 | 1 | 0 | 4 | 51 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 119 | 1173 |
| 5:10 PM | 0 | 55 | 0 | 0 | 1 | 40 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 99 | 1180 |
| 5:15 PM | 0 | 55 | 2 | 0 | 0 | 28 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 89 | 1166 |
| 5:20 PM | 0 | 48 | 0 | 0 | 0 | 39 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 90 | 1178 |
| 5:25 PM | 0 | 66 | 0 | 0 | 0 | 43 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 110 | 1187 |
| 5:30 PM | 0 | 49 | 0 | 0 | 0 | 43 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 93 | 1199 |
| 5:35 PM | 0 | 74 | 1 | 0 | 1 | 31 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 109 | 1205 |
| 5:40 PM | 0 | 47 | 0 | 0 | 2 | 43 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | 97 | 1206 |
| 5:45 PM | 0 | 62 | 0 | 0 | 0 | 45 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 109 | 1215 |
| 5:50 PM | 0 | 47 | 1 | 0 | 0 | 39 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 87 | 1215 |
| 5:55 PM | 0 | 52 | 0 | 0 | 0 | 26 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 78 | 1196 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| All Vehicles | 0 | 740 | 4 | 0 | 20 | 540 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 32 | 0 | 1336 | |
| Heavy Trucks | 0 | 4 | 0 | 0 | 0 | 8 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 12 | |
| Pedestrians | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 12 | 0 | 0 | 0 | 12 | |
| Bicycles | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | |
| Railroad | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined






Method for determining peak hour: Total Entering Volume

LOCATION: SW Martinazzi Ave -- Existing Right-Out Only Dwy
CITY/STATE: Tualatin, OR

QC JOB #: 10772117
DATE: Tue, Jun 05 2012



Peak-Hour: 4:35 PM -- 5:35 PM
Peak 15-Min: 5:00 PM -- 5:15 PM



| 5-Min Count Period Beginning At | SW Martinazzi Ave (Northbound) | | | | SW Martinazzi Ave (Southbound) | | | | Existing Right-Out Only Dwy (Eastbound) | | | | Existing Right-Out Only Dwy (Westbound) | | | | Total | Hourly Totals |
|------------------------------------|--------------------------------|------|-------|---|--------------------------------|------|-------|---|---|------|-------|---|---|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 4:00 PM | 0 | 51 | 0 | 0 | 0 | 28 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 79 | 962 |
| 4:05 PM | 0 | 70 | 0 | 0 | 0 | 35 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 106 | 989 |
| 4:10 PM | 0 | 50 | 0 | 0 | 0 | 34 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 84 | 990 |
| 4:15 PM | 0 | 61 | 0 | 0 | 0 | 35 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 97 | 1018 |
| 4:20 PM | 0 | 45 | 0 | 0 | 0 | 37 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 84 | 1009 |
| 4:25 PM | 0 | 62 | 0 | 0 | 0 | 41 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 103 | 1027 |
| 4:30 PM | 0 | 39 | 0 | 0 | 0 | 40 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 80 | 1029 |
| 4:35 PM | 0 | 62 | 0 | 0 | 0 | 30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 93 | 1041 |
| 4:40 PM | 0 | 52 | 0 | 0 | 0 | 39 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 92 | 1059 |
| 4:45 PM | 0 | 52 | 0 | 0 | 0 | 37 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 89 | 1074 |
| 4:50 PM | 0 | 43 | 0 | 0 | 0 | 44 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 87 | 1080 |
| 4:55 PM | 0 | 53 | 0 | 0 | 0 | 37 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 90 | 1084 |
| 5:00 PM | 0 | 66 | 0 | 0 | 0 | 46 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 114 | 1119 |
| 5:05 PM | 0 | 58 | 0 | 0 | 0 | 46 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 104 | 1117 |
| 5:10 PM | 0 | 55 | 0 | 0 | 0 | 52 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 107 | 1140 |
| 5:15 PM | 0 | 54 | 0 | 0 | 0 | 33 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 89 | 1132 |
| 5:20 PM | 0 | 46 | 0 | 0 | 0 | 33 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 81 | 1129 |
| 5:25 PM | 0 | 63 | 0 | 0 | 0 | 52 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 116 | 1142 |
| 5:30 PM | 0 | 49 | 0 | 0 | 0 | 42 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 94 | 1156 |
| 5:35 PM | 0 | 75 | 0 | 0 | 0 | 38 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 113 | 1176 |
| 5:40 PM | 0 | 45 | 0 | 0 | 0 | 38 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 83 | 1167 |
| 5:45 PM | 0 | 60 | 0 | 0 | 0 | 47 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 107 | 1185 |
| 5:50 PM | 0 | 48 | 0 | 0 | 0 | 37 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 85 | 1183 |
| 5:55 PM | 0 | 51 | 0 | 0 | 0 | 29 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 80 | 1173 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| All Vehicles | 0 | 716 | 0 | 0 | 0 | 576 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 8 | 0 | 1300 | |
| Heavy Trucks | 0 | 4 | 0 | 0 | 0 | 8 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 12 | |
| Pedestrians | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Bicycles | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | |
| Railroad | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Stopped Buses | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |


Comments: N

Type of peak hour being reported: User-Defined








Method for determining peak hour: Total Entering Volume

LOCATION: SW Martinazzi Ave -- SW Tualatin-Sherwood Rd
 CITY/STATE: Tualatin, OR

QC JOB #: 10772115
 DATE: Wed, Jun 06 2012



Peak-Hour: 4:35 PM -- 5:35 PM
 Peak 15-Min: 5:05 PM -- 5:20 PM



| 5-Min Count Period | SW Martinazzi Ave (Northbound) | | | | SW Martinazzi Ave (Southbound) | | | | SW Tualatin-Sherwood Rd (Eastbound) | | | | SW Tualatin-Sherwood Rd (Westbound) | | | | Total | Hourly Totals |
|-----------------------|--------------------------------|------|-------|---|--------------------------------|------|-------|---|-------------------------------------|------|-------|---|-------------------------------------|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 4:00 PM | 7 | 23 | 22 | 0 | 11 | 42 | 4 | 0 | 4 | 116 | 6 | 0 | 0 | 86 | 0 | 0 | 321 | 3812 |
| 4:05 PM | 5 | 16 | 25 | 0 | 10 | 42 | 5 | 0 | 4 | 109 | 8 | 0 | 0 | 119 | 0 | 0 | 343 | 3845 |
| 4:10 PM | 12 | 28 | 21 | 0 | 19 | 45 | 12 | 0 | 4 | 90 | 5 | 0 | 0 | 86 | 0 | 0 | 322 | 3893 |
| 4:15 PM | 6 | 16 | 25 | 0 | 16 | 39 | 5 | 0 | 5 | 141 | 11 | 0 | 0 | 106 | 0 | 0 | 370 | 3950 |
| 4:20 PM | 8 | 13 | 11 | 0 | 20 | 38 | 7 | 0 | 4 | 129 | 7 | 0 | 0 | 77 | 0 | 0 | 314 | 3971 |
| 4:25 PM | 7 | 23 | 33 | 0 | 5 | 58 | 9 | 0 | 8 | 114 | 4 | 0 | 0 | 83 | 0 | 0 | 344 | 4000 |
| 4:30 PM | 7 | 13 | 14 | 0 | 10 | 30 | 1 | 0 | 7 | 140 | 5 | 0 | 0 | 104 | 0 | 0 | 331 | 3990 |
| 4:35 PM | 8 | 27 | 35 | 0 | 17 | 71 | 7 | 0 | 2 | 100 | 8 | 0 | 0 | 79 | 0 | 0 | 354 | 4039 |
| 4:40 PM | 6 | 22 | 26 | 0 | 14 | 37 | 1 | 0 | 4 | 141 | 6 | 1 | 0 | 130 | 0 | 0 | 388 | 4058 |
| 4:45 PM | 10 | 17 | 20 | 0 | 18 | 32 | 6 | 0 | 1 | 112 | 3 | 0 | 0 | 73 | 0 | 0 | 292 | 4061 |
| 4:50 PM | 7 | 11 | 24 | 0 | 11 | 48 | 8 | 0 | 5 | 119 | 5 | 0 | 0 | 94 | 0 | 0 | 332 | 4060 |
| 4:55 PM | 11 | 18 | 18 | 0 | 26 | 53 | 11 | 0 | 0 | 109 | 4 | 0 | 0 | 69 | 0 | 0 | 319 | 4030 |
| 5:00 PM | 6 | 22 | 20 | 0 | 12 | 45 | 13 | 0 | 8 | 127 | 5 | 0 | 0 | 84 | 0 | 0 | 342 | 4051 |
| 5:05 PM | 12 | 22 | 33 | 0 | 15 | 45 | 4 | 0 | 2 | 127 | 6 | 0 | 0 | 103 | 0 | 0 | 369 | 4077 |
| 5:10 PM | 7 | 34 | 36 | 0 | 15 | 78 | 9 | 0 | 4 | 116 | 3 | 0 | 0 | 78 | 1 | 0 | 381 | 4136 |
| 5:15 PM | 6 | 25 | 22 | 0 | 11 | 43 | 7 | 0 | 5 | 133 | 7 | 0 | 0 | 111 | 0 | 0 | 370 | 4136 |
| 5:20 PM | 14 | 16 | 31 | 0 | 21 | 57 | 3 | 0 | 4 | 119 | 9 | 0 | 0 | 93 | 0 | 0 | 367 | 4189 |
| 5:25 PM | 0 | 17 | 27 | 0 | 13 | 83 | 10 | 0 | 4 | 123 | 15 | 0 | 0 | 91 | 0 | 0 | 383 | 4228 |
| 5:30 PM | 5 | 13 | 22 | 0 | 12 | 40 | 5 | 0 | 2 | 123 | 10 | 0 | 0 | 98 | 0 | 0 | 330 | 4227 |
| 5:35 PM | 12 | 19 | 29 | 0 | 19 | 66 | 5 | 0 | 5 | 59 | 2 | 0 | 0 | 94 | 0 | 0 | 310 | 4183 |
| 5:40 PM | 3 | 3 | 19 | 0 | 12 | 37 | 10 | 0 | 5 | 124 | 4 | 0 | 1 | 97 | 0 | 0 | 315 | 4110 |
| 5:45 PM | 8 | 17 | 25 | 0 | 21 | 51 | 8 | 0 | 6 | 79 | 13 | 0 | 0 | 79 | 0 | 0 | 307 | 4125 |
| 5:50 PM | 5 | 24 | 20 | 0 | 10 | 42 | 4 | 0 | 5 | 78 | 6 | 0 | 0 | 139 | 0 | 0 | 333 | 4126 |
| 5:55 PM | 9 | 18 | 15 | 1 | 17 | 50 | 11 | 0 | 5 | 80 | 7 | 0 | 0 | 69 | 0 | 0 | 282 | 4089 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| All Vehicles | 100 | 324 | 364 | 0 | 164 | 664 | 80 | 0 | 44 | 1504 | 64 | 0 | 0 | 1168 | 4 | 0 | | 4480 |
| Heavy Trucks | 0 | 4 | 4 | | 0 | 4 | 0 | | 4 | 40 | 0 | | 0 | 68 | 0 | | 124 | |
| Pedestrians | | 0 | | | | 4 | | | | 32 | | | | 0 | | | 36 | |
| Bicycles | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | |
| Railroad | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined










Method for determining peak hour: Total Entering Volume

LOCATION: SW Martinazzi Ave -- SW Nyberg St
CITY/STATE: Tualatin, OR

QC JOB #: 10772113
DATE: Tue, Jun 05 2012



Peak-Hour: 4:35 PM -- 5:35 PM
Peak 15-Min: 5:00 PM -- 5:15 PM



| 5-Min Count Period Beginning At | SW Martinazzi Ave (Northbound) | | | | SW Martinazzi Ave (Southbound) | | | | SW Nyberg St (Eastbound) | | | | SW Nyberg St (Westbound) | | | | Total | Hourly Totals |
|------------------------------------|--------------------------------|------|-------|---|--------------------------------|------|-------|---|--------------------------|------|-------|---|--------------------------|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 4:00 PM | 0 | 20 | 2 | 0 | 0 | 27 | 1 | 0 | 1 | 2 | 13 | 0 | 17 | 3 | 30 | 0 | 116 | 1367 |
| 4:05 PM | 1 | 27 | 3 | 0 | 0 | 32 | 1 | 0 | 4 | 0 | 8 | 0 | 24 | 2 | 39 | 0 | 141 | 1392 |
| 4:10 PM | 2 | 26 | 0 | 0 | 0 | 36 | 1 | 0 | 4 | 0 | 5 | 0 | 20 | 5 | 20 | 0 | 119 | 1395 |
| 4:15 PM | 2 | 31 | 2 | 0 | 0 | 30 | 2 | 0 | 2 | 0 | 13 | 0 | 25 | 3 | 28 | 0 | 138 | 1424 |
| 4:20 PM | 2 | 18 | 2 | 0 | 0 | 36 | 1 | 0 | 1 | 1 | 5 | 0 | 22 | 3 | 26 | 0 | 117 | 1417 |
| 4:25 PM | 1 | 28 | 0 | 0 | 0 | 32 | 3 | 0 | 2 | 0 | 6 | 0 | 32 | 3 | 32 | 0 | 139 | 1445 |
| 4:30 PM | 0 | 13 | 0 | 0 | 0 | 33 | 3 | 0 | 3 | 1 | 6 | 0 | 22 | 2 | 23 | 0 | 106 | 1441 |
| 4:35 PM | 3 | 32 | 0 | 0 | 0 | 34 | 3 | 0 | 3 | 2 | 8 | 0 | 23 | 2 | 27 | 0 | 137 | 1466 |
| 4:40 PM | 1 | 25 | 1 | 0 | 0 | 36 | 1 | 0 | 0 | 0 | 8 | 0 | 25 | 3 | 27 | 0 | 127 | 1489 |
| 4:45 PM | 3 | 22 | 3 | 0 | 0 | 41 | 1 | 0 | 5 | 2 | 10 | 0 | 25 | 5 | 25 | 0 | 142 | 1536 |
| 4:50 PM | 4 | 15 | 3 | 0 | 0 | 41 | 0 | 0 | 1 | 0 | 7 | 0 | 27 | 6 | 27 | 0 | 131 | 1547 |
| 4:55 PM | 0 | 21 | 0 | 0 | 0 | 34 | 1 | 0 | 2 | 0 | 11 | 0 | 35 | 5 | 30 | 0 | 139 | 1552 |
| 5:00 PM | 2 | 35 | 2 | 0 | 0 | 47 | 0 | 0 | 5 | 1 | 9 | 0 | 33 | 7 | 26 | 0 | 167 | 1603 |
| 5:05 PM | 1 | 30 | 0 | 0 | 0 | 42 | 1 | 0 | 1 | 1 | 9 | 0 | 31 | 6 | 27 | 0 | 149 | 1611 |
| 5:10 PM | 5 | 33 | 4 | 0 | 0 | 54 | 0 | 0 | 1 | 3 | 9 | 0 | 14 | 2 | 21 | 0 | 146 | 1638 |
| 5:15 PM | 1 | 20 | 1 | 0 | 0 | 33 | 1 | 0 | 2 | 0 | 6 | 0 | 27 | 7 | 32 | 0 | 130 | 1630 |
| 5:20 PM | 2 | 21 | 2 | 0 | 0 | 31 | 0 | 0 | 3 | 1 | 8 | 0 | 26 | 1 | 22 | 0 | 117 | 1630 |
| 5:25 PM | 1 | 27 | 2 | 0 | 0 | 50 | 1 | 0 | 4 | 0 | 10 | 0 | 32 | 6 | 32 | 0 | 165 | 1656 |
| 5:30 PM | 4 | 18 | 1 | 0 | 0 | 35 | 1 | 0 | 2 | 0 | 6 | 0 | 38 | 5 | 29 | 0 | 139 | 1689 |
| 5:35 PM | 3 | 40 | 1 | 0 | 0 | 45 | 1 | 0 | 6 | 0 | 8 | 0 | 24 | 6 | 29 | 0 | 163 | 1715 |
| 5:40 PM | 0 | 17 | 2 | 0 | 0 | 36 | 2 | 0 | 1 | 0 | 6 | 0 | 23 | 1 | 27 | 0 | 115 | 1703 |
| 5:45 PM | 2 | 24 | 2 | 0 | 0 | 48 | 0 | 0 | 2 | 0 | 7 | 0 | 32 | 4 | 34 | 0 | 155 | 1716 |
| 5:50 PM | 1 | 15 | 2 | 0 | 0 | 36 | 2 | 0 | 1 | 0 | 6 | 0 | 31 | 1 | 32 | 0 | 127 | 1712 |
| 5:55 PM | 2 | 17 | 0 | 0 | 0 | 26 | 1 | 0 | 1 | 2 | 12 | 0 | 31 | 4 | 33 | 0 | 129 | 1702 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| All Vehicles | 32 | 392 | 24 | 0 | 0 | 572 | 4 | 0 | 28 | 20 | 108 | 0 | 312 | 60 | 296 | 0 | 1848 | |
| Heavy Trucks | 0 | 0 | 0 | 0 | 0 | 12 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 4 | 0 | 20 | |
| Pedestrians | | 0 | | | | 8 | | | | 0 | | | | 16 | | | 24 | |
| Bicycles | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 2 | |
| Railroad | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined








Method for determining peak hour: Total Entering Volume

LOCATION: Unsignalized Site Dwy -- SW Nyberg St
CITY/STATE: Tualatin, OR

QC JOB #: 10772111
DATE: Tue, Jun 05 2012



Peak-Hour: 4:35 PM -- 5:35 PM
Peak 15-Min: 4:50 PM -- 5:05 PM



| 5-Min Count Period Beginning At | Unsignalized Site Dwy (Northbound) | | | | Unsignalized Site Dwy (Southbound) | | | | SW Nyberg St (Eastbound) | | | | SW Nyberg St (Westbound) | | | | Total | Hourly Totals |
|------------------------------------|------------------------------------|------|-------|---|------------------------------------|------|-------|---|--------------------------|------|-------|---|--------------------------|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 4:00 PM | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 4 | 0 | 0 | 0 | 0 | 48 | 5 | 0 | 60 | 668 |
| 4:05 PM | 0 | 0 | 0 | 0 | 0 | 0 | 13 | 0 | 3 | 0 | 0 | 0 | 0 | 51 | 5 | 0 | 72 | 696 |
| 4:10 PM | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 1 | 0 | 0 | 0 | 0 | 53 | 3 | 0 | 60 | 700 |
| 4:15 PM | 0 | 0 | 0 | 0 | 0 | 0 | 7 | 0 | 1 | 0 | 0 | 0 | 0 | 46 | 1 | 0 | 55 | 700 |
| 4:20 PM | 0 | 0 | 0 | 0 | 0 | 0 | 5 | 0 | 4 | 0 | 0 | 0 | 0 | 43 | 2 | 0 | 54 | 699 |
| 4:25 PM | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 65 | 2 | 0 | 71 | 715 |
| 4:30 PM | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 1 | 0 | 0 | 0 | 0 | 45 | 7 | 0 | 56 | 722 |
| 4:35 PM | 0 | 0 | 0 | 0 | 0 | 0 | 5 | 0 | 2 | 0 | 0 | 0 | 0 | 53 | 3 | 0 | 63 | 729 |
| 4:40 PM | 0 | 0 | 0 | 0 | 0 | 0 | 8 | 0 | 1 | 0 | 0 | 0 | 0 | 40 | 3 | 0 | 52 | 729 |
| 4:45 PM | 0 | 0 | 0 | 0 | 0 | 0 | 6 | 0 | 4 | 0 | 0 | 0 | 0 | 41 | 5 | 0 | 56 | 724 |
| 4:50 PM | 0 | 0 | 0 | 0 | 0 | 0 | 7 | 0 | 3 | 0 | 0 | 0 | 0 | 62 | 4 | 0 | 76 | 736 |
| 4:55 PM | 0 | 0 | 0 | 0 | 0 | 0 | 12 | 0 | 1 | 0 | 0 | 0 | 0 | 47 | 5 | 0 | 65 | 740 |
| 5:00 PM | 0 | 0 | 0 | 0 | 0 | 0 | 7 | 0 | 3 | 0 | 0 | 0 | 0 | 72 | 2 | 0 | 84 | 764 |
| 5:05 PM | 0 | 0 | 0 | 0 | 0 | 0 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 46 | 0 | 0 | 52 | 744 |
| 5:10 PM | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 6 | 0 | 0 | 0 | 0 | 53 | 8 | 0 | 69 | 753 |
| 5:15 PM | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 1 | 0 | 0 | 0 | 0 | 53 | 1 | 0 | 59 | 757 |
| 5:20 PM | 0 | 0 | 0 | 0 | 0 | 0 | 7 | 0 | 3 | 0 | 0 | 0 | 0 | 39 | 3 | 0 | 52 | 755 |
| 5:25 PM | 0 | 0 | 0 | 0 | 0 | 0 | 7 | 0 | 3 | 0 | 0 | 0 | 0 | 74 | 3 | 0 | 87 | 771 |
| 5:30 PM | 0 | 0 | 0 | 0 | 0 | 0 | 11 | 0 | 1 | 0 | 0 | 0 | 0 | 59 | 3 | 0 | 74 | 789 |
| 5:35 PM | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 2 | 0 | 0 | 0 | 0 | 56 | 5 | 0 | 66 | 792 |
| 5:40 PM | 0 | 0 | 0 | 0 | 0 | 0 | 5 | 0 | 2 | 0 | 0 | 0 | 0 | 53 | 4 | 0 | 64 | 804 |
| 5:45 PM | 0 | 0 | 0 | 0 | 0 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 62 | 2 | 0 | 69 | 817 |
| 5:50 PM | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 2 | 0 | 0 | 0 | 0 | 68 | 6 | 0 | 79 | 820 |
| 5:55 PM | 0 | 0 | 0 | 0 | 0 | 0 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 45 | 3 | 0 | 54 | 809 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| All Vehicles | 0 | 0 | 0 | 0 | 0 | 0 | 104 | 0 | 28 | 0 | 0 | 0 | 0 | 724 | 44 | 0 | 900 | |
| Heavy Trucks | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 12 | 0 | 0 | 12 | |
| Pedestrians | | 0 | | | | 4 | | | | 0 | | | | 0 | | | 4 | |
| Bicycles | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | 1 | 0 | | 1 | |
| Railroad | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined










Method for determining peak hour: Total Entering Volume

LOCATION: Fred Meyer/Site Dwy -- SW Nyberg St/SW Tualatin-Sherwood Rd
CITY/STATE: Tualatin, OR

QC JOB #: 10772109
DATE: Tue, Jun 05 2012



Peak-Hour: 4:35 PM -- 5:35 PM
Peak 15-Min: 5:20 PM -- 5:35 PM



| 5-Min Count Period Beginning At | Fred Meyer/Site Dwy (Northbound) | | | | Fred Meyer/Site Dwy (Southbound) | | | | SW Nyberg St/SW Tualatin-Sherwood Rd (Eastbound) | | | | SW Nyberg St/SW Tualatin-Sherwood Rd (Westbound) | | | | Total | Hourly Totals |
|------------------------------------|----------------------------------|------|-------|---|----------------------------------|------|-------|---|--|------|-------|---|--|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 4:00 PM | 5 | 3 | 15 | 0 | 15 | 1 | 1 | 0 | 1 | 133 | 0 | 0 | 16 | 115 | 6 | 0 | 311 | 4116 |
| 4:05 PM | 4 | 0 | 20 | 0 | 15 | 1 | 7 | 0 | 1 | 178 | 0 | 0 | 12 | 137 | 9 | 0 | 384 | 4156 |
| 4:10 PM | 2 | 3 | 25 | 0 | 19 | 3 | 3 | 0 | 1 | 124 | 8 | 0 | 26 | 133 | 6 | 0 | 353 | 4151 |
| 4:15 PM | 2 | 2 | 26 | 0 | 9 | 5 | 6 | 0 | 1 | 176 | 9 | 0 | 23 | 150 | 6 | 0 | 415 | 4256 |
| 4:20 PM | 4 | 5 | 27 | 0 | 6 | 4 | 3 | 0 | 6 | 133 | 0 | 1 | 28 | 138 | 11 | 0 | 366 | 4255 |
| 4:25 PM | 2 | 1 | 17 | 0 | 26 | 1 | 6 | 0 | 4 | 140 | 3 | 0 | 12 | 134 | 13 | 0 | 359 | 4289 |
| 4:30 PM | 3 | 0 | 15 | 0 | 7 | 2 | 2 | 0 | 1 | 180 | 8 | 0 | 16 | 162 | 5 | 0 | 401 | 4351 |
| 4:35 PM | 4 | 1 | 27 | 0 | 19 | 2 | 4 | 0 | 3 | 134 | 2 | 0 | 26 | 117 | 11 | 0 | 350 | 4340 |
| 4:40 PM | 1 | 2 | 16 | 0 | 7 | 0 | 2 | 0 | 5 | 185 | 5 | 0 | 7 | 168 | 4 | 0 | 402 | 4386 |
| 4:45 PM | 2 | 2 | 24 | 0 | 19 | 2 | 3 | 0 | 2 | 143 | 4 | 0 | 24 | 123 | 5 | 0 | 353 | 4422 |
| 4:50 PM | 3 | 3 | 16 | 0 | 15 | 2 | 2 | 0 | 5 | 176 | 2 | 0 | 13 | 145 | 5 | 0 | 387 | 4406 |
| 4:55 PM | 2 | 0 | 26 | 0 | 15 | 1 | 3 | 0 | 2 | 149 | 2 | 0 | 21 | 150 | 6 | 0 | 377 | 4458 |
| 5:00 PM | 7 | 0 | 23 | 0 | 20 | 3 | 3 | 0 | 5 | 155 | 2 | 0 | 14 | 137 | 4 | 0 | 373 | 4520 |
| 5:05 PM | 0 | 0 | 17 | 0 | 16 | 3 | 3 | 0 | 2 | 162 | 1 | 0 | 19 | 135 | 5 | 0 | 363 | 4499 |
| 5:10 PM | 2 | 1 | 23 | 0 | 12 | 2 | 3 | 0 | 1 | 155 | 5 | 0 | 27 | 150 | 3 | 0 | 384 | 4530 |
| 5:15 PM | 0 | 1 | 10 | 0 | 13 | 2 | 3 | 0 | 2 | 162 | 5 | 0 | 16 | 132 | 5 | 0 | 351 | 4466 |
| 5:20 PM | 5 | 0 | 25 | 0 | 13 | 2 | 4 | 0 | 0 | 141 | 3 | 0 | 22 | 137 | 7 | 0 | 359 | 4459 |
| 5:25 PM | 7 | 0 | 16 | 0 | 20 | 4 | 10 | 0 | 1 | 144 | 4 | 0 | 17 | 143 | 10 | 0 | 376 | 4476 |
| 5:30 PM | 3 | 0 | 13 | 0 | 13 | 1 | 4 | 0 | 4 | 182 | 7 | 0 | 26 | 154 | 7 | 0 | 414 | 4489 |
| 5:35 PM | 1 | 1 | 17 | 0 | 12 | 2 | 5 | 0 | 0 | 124 | 3 | 0 | 26 | 138 | 6 | 0 | 335 | 4474 |
| 5:40 PM | 1 | 2 | 11 | 0 | 16 | 0 | 2 | 0 | 5 | 156 | 5 | 0 | 17 | 163 | 8 | 0 | 386 | 4458 |
| 5:45 PM | 3 | 1 | 18 | 0 | 16 | 2 | 0 | 0 | 2 | 132 | 5 | 1 | 26 | 164 | 5 | 0 | 375 | 4480 |
| 5:50 PM | 4 | 3 | 11 | 0 | 8 | 6 | 6 | 0 | 4 | 117 | 2 | 0 | 9 | 155 | 3 | 0 | 328 | 4421 |
| 5:55 PM | 2 | 1 | 19 | 0 | 5 | 1 | 4 | 0 | 2 | 126 | 4 | 0 | 26 | 135 | 6 | 0 | 331 | 4375 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| All Vehicles | 60 | 0 | 216 | 0 | 184 | 28 | 72 | 0 | 20 | 1868 | 56 | 0 | 260 | 1736 | 96 | 0 | 4596 | |
| Heavy Trucks | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 112 | 0 | 0 | 0 | 60 | 0 | 0 | 172 | |
| Pedestrians | | | 0 | | | 24 | | | | 28 | | | | 0 | | | 52 | |
| Bicycles | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Railroad | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined








Method for determining peak hour: Total Entering Volume

LOCATION: SW 75th Ave -- SW Nyberg St
CITY/STATE: Tualatin, OR

QC JOB #: 10772107
DATE: Tue, Jun 05 2012



Peak-Hour: 4:35 PM -- 5:35 PM
Peak 15-Min: 4:50 PM -- 5:05 PM



| 5-Min Count Period Beginning At | SW 75th Ave (Northbound) | | | | SW 75th Ave (Southbound) | | | | SW Nyberg St (Eastbound) | | | | SW Nyberg St (Westbound) | | | | Total | Hourly Totals |
|------------------------------------|--------------------------|------|-------|---|--------------------------|------|-------|---|--------------------------|------|-------|---|--------------------------|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 4:00 PM | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 163 | 0 | 0 | 0 | 149 | 5 | 0 | 318 | 4008 |
| 4:05 PM | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 213 | 0 | 0 | 0 | 149 | 6 | 0 | 369 | 4056 |
| 4:10 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 168 | 0 | 0 | 0 | 177 | 9 | 0 | 354 | 4060 |
| 4:15 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 211 | 0 | 0 | 0 | 167 | 5 | 0 | 383 | 4136 |
| 4:20 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 166 | 0 | 0 | 0 | 164 | 3 | 0 | 333 | 4126 |
| 4:25 PM | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 183 | 0 | 0 | 0 | 184 | 1 | 0 | 369 | 4172 |
| 4:30 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 202 | 0 | 0 | 0 | 170 | 1 | 0 | 373 | 4213 |
| 4:35 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 180 | 0 | 0 | 0 | 181 | 1 | 0 | 362 | 4218 |
| 4:40 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 208 | 0 | 0 | 0 | 156 | 4 | 0 | 368 | 4257 |
| 4:45 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 186 | 0 | 0 | 0 | 153 | 5 | 0 | 344 | 4266 |
| 4:50 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 207 | 0 | 0 | 0 | 171 | 4 | 0 | 382 | 4259 |
| 4:55 PM | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 190 | 0 | 0 | 0 | 174 | 2 | 0 | 367 | 4322 |
| 5:00 PM | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 198 | 0 | 0 | 0 | 167 | 3 | 0 | 369 | 4373 |
| 5:05 PM | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 195 | 0 | 0 | 0 | 153 | 2 | 0 | 351 | 4355 |
| 5:10 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 190 | 0 | 0 | 0 | 169 | 5 | 0 | 364 | 4365 |
| 5:15 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 185 | 0 | 0 | 0 | 158 | 4 | 0 | 347 | 4329 |
| 5:20 PM | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 179 | 0 | 0 | 0 | 152 | 1 | 0 | 333 | 4329 |
| 5:25 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 180 | 0 | 0 | 0 | 171 | 1 | 0 | 352 | 4312 |
| 5:30 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 208 | 0 | 0 | 0 | 186 | 1 | 0 | 395 | 4334 |
| 5:35 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 153 | 0 | 0 | 0 | 167 | 4 | 0 | 324 | 4296 |
| 5:40 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 183 | 0 | 0 | 0 | 180 | 6 | 0 | 369 | 4297 |
| 5:45 PM | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 166 | 0 | 0 | 0 | 196 | 5 | 0 | 369 | 4322 |
| 5:50 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 136 | 0 | 0 | 0 | 168 | 2 | 0 | 306 | 4246 |
| 5:55 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 150 | 0 | 0 | 0 | 163 | 2 | 0 | 315 | 4194 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| All Vehicles | 0 | 0 | 0 | 0 | 0 | 0 | 8 | 0 | 0 | 2380 | 0 | 0 | 0 | 2048 | 36 | 0 | 4472 | |
| Heavy Trucks | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 72 | 0 | 0 | 0 | 84 | 0 | 0 | 156 | |
| Pedestrians | | | | | | 4 | | | | 0 | | | | 0 | | | 4 | |
| Bicycles | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 2 | |
| Railroad | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined







Method for determining peak hour: Total Entering Volume

LOCATION: I-5 SB Ramp Terminal -- SW Nyberg St
CITY/STATE: Tualatin, OR

QC JOB #: 10772105
DATE: Tue, Jun 05 2012



Peak-Hour: 4:35 PM -- 5:35 PM
Peak 15-Min: 5:20 PM -- 5:35 PM



| 5-Min Count Period Beginning At | I-5 SB Ramp Terminal (Northbound) | | | | I-5 SB Ramp Terminal (Southbound) | | | | SW Nyberg St (Eastbound) | | | | SW Nyberg St (Westbound) | | | | Total | Hourly Totals |
|------------------------------------|-----------------------------------|------|-------|---|-----------------------------------|------|-------|---|--------------------------|------|-------|---|--------------------------|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 4:00 PM | 0 | 0 | 0 | 0 | 42 | 0 | 66 | 0 | 0 | 104 | 55 | 0 | 15 | 86 | 0 | 0 | 368 | 4708 |
| 4:05 PM | 0 | 0 | 0 | 0 | 49 | 0 | 89 | 0 | 0 | 102 | 83 | 0 | 10 | 72 | 0 | 0 | 405 | 4759 |
| 4:10 PM | 0 | 0 | 0 | 0 | 34 | 0 | 65 | 0 | 0 | 154 | 67 | 0 | 13 | 107 | 0 | 0 | 440 | 4797 |
| 4:15 PM | 0 | 0 | 0 | 0 | 44 | 0 | 93 | 0 | 0 | 116 | 63 | 0 | 8 | 84 | 0 | 0 | 408 | 4837 |
| 4:20 PM | 0 | 0 | 0 | 0 | 47 | 0 | 82 | 0 | 0 | 128 | 64 | 0 | 15 | 80 | 0 | 0 | 416 | 4856 |
| 4:25 PM | 0 | 0 | 0 | 0 | 33 | 0 | 79 | 0 | 0 | 121 | 54 | 0 | 6 | 111 | 0 | 0 | 404 | 4851 |
| 4:30 PM | 0 | 0 | 0 | 0 | 54 | 1 | 105 | 0 | 0 | 103 | 65 | 0 | 12 | 64 | 0 | 0 | 404 | 4855 |
| 4:35 PM | 0 | 0 | 0 | 0 | 44 | 0 | 73 | 0 | 0 | 146 | 69 | 0 | 8 | 106 | 0 | 0 | 446 | 4902 |
| 4:40 PM | 0 | 0 | 0 | 0 | 68 | 2 | 84 | 0 | 0 | 115 | 76 | 0 | 8 | 76 | 0 | 0 | 429 | 4917 |
| 4:45 PM | 0 | 0 | 0 | 0 | 53 | 0 | 78 | 0 | 0 | 112 | 65 | 0 | 19 | 77 | 0 | 0 | 404 | 4908 |
| 4:50 PM | 0 | 0 | 0 | 0 | 39 | 0 | 76 | 0 | 0 | 162 | 69 | 0 | 9 | 97 | 0 | 0 | 452 | 4950 |
| 4:55 PM | 0 | 0 | 0 | 0 | 58 | 1 | 106 | 0 | 0 | 106 | 61 | 0 | 14 | 72 | 0 | 0 | 418 | 4994 |
| 5:00 PM | 0 | 0 | 0 | 0 | 41 | 0 | 69 | 0 | 0 | 131 | 72 | 0 | 12 | 102 | 0 | 0 | 427 | 5053 |
| 5:05 PM | 0 | 0 | 0 | 0 | 64 | 1 | 86 | 0 | 0 | 110 | 71 | 0 | 5 | 76 | 0 | 0 | 413 | 5081 |
| 5:10 PM | 0 | 0 | 0 | 0 | 36 | 1 | 95 | 0 | 0 | 131 | 71 | 0 | 11 | 83 | 0 | 0 | 428 | 5049 |
| 5:15 PM | 0 | 0 | 0 | 0 | 66 | 0 | 96 | 0 | 0 | 106 | 63 | 0 | 12 | 66 | 0 | 0 | 409 | 5050 |
| 5:20 PM | 0 | 0 | 0 | 0 | 57 | 0 | 89 | 0 | 0 | 128 | 70 | 0 | 11 | 65 | 0 | 0 | 420 | 5054 |
| 5:25 PM | 0 | 0 | 0 | 0 | 47 | 0 | 88 | 0 | 0 | 135 | 64 | 0 | 7 | 90 | 0 | 0 | 431 | 5081 |
| 5:30 PM | 0 | 0 | 0 | 0 | 70 | 0 | 114 | 0 | 0 | 100 | 81 | 0 | 4 | 79 | 0 | 0 | 448 | 5125 |
| 5:35 PM | 0 | 0 | 0 | 0 | 46 | 0 | 82 | 0 | 0 | 101 | 61 | 0 | 18 | 90 | 0 | 0 | 398 | 5077 |
| 5:40 PM | 0 | 0 | 0 | 0 | 64 | 1 | 84 | 0 | 0 | 127 | 66 | 0 | 10 | 101 | 0 | 0 | 453 | 5101 |
| 5:45 PM | 0 | 0 | 0 | 0 | 50 | 0 | 111 | 0 | 0 | 109 | 49 | 0 | 14 | 93 | 0 | 0 | 426 | 5123 |
| 5:50 PM | 0 | 0 | 0 | 0 | 64 | 0 | 96 | 0 | 0 | 119 | 56 | 0 | 10 | 78 | 0 | 0 | 423 | 5094 |
| 5:55 PM | 0 | 0 | 0 | 0 | 43 | 0 | 96 | 0 | 0 | 88 | 45 | 0 | 10 | 72 | 0 | 0 | 354 | 5030 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| All Vehicles | 0 | 0 | 0 | 0 | 696 | 0 | 1164 | 0 | 0 | 1452 | 860 | 0 | 88 | 936 | 0 | 0 | 5196 | |
| Heavy Trucks | 0 | 0 | 0 | 0 | 24 | 0 | 32 | 0 | 0 | 48 | 44 | 0 | 4 | 28 | 0 | 0 | 180 | |
| Pedestrians | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | |
| Bicycles | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Railroad | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Stopped Buses | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |


Comments: N

Type of peak hour being reported: User-Defined







Method for determining peak hour: Total Entering Volume

LOCATION: I-5 NB Ramp Terminal -- SW Nyberg St
CITY/STATE: Tualatin, OR

QC JOB #: 10772103
DATE: Tue, Jun 05 2012



Peak-Hour: 4:35 PM -- 5:35 PM
Peak 15-Min: 4:45 PM -- 5:00 PM



| 5-Min Count Period Beginning At | I-5 NB Ramp Terminal (Northbound) | | | | I-5 NB Ramp Terminal (Southbound) | | | | SW Nyberg St (Eastbound) | | | | SW Nyberg St (Westbound) | | | | Total | Hourly Totals |
|---------------------------------|-----------------------------------|------|-------|---|-----------------------------------|------|-------|---|--------------------------|------|-------|---|--------------------------|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 4:00 PM | 35 | 0 | 14 | 0 | 0 | 0 | 0 | 0 | 0 | 85 | 74 | 0 | 0 | 45 | 46 | 0 | 299 | 3767 |
| 4:05 PM | 51 | 0 | 9 | 0 | 0 | 0 | 0 | 0 | 0 | 92 | 54 | 0 | 0 | 41 | 48 | 0 | 295 | 3763 |
| 4:10 PM | 60 | 0 | 11 | 0 | 0 | 0 | 0 | 0 | 0 | 77 | 102 | 0 | 0 | 57 | 56 | 0 | 363 | 3795 |
| 4:15 PM | 44 | 0 | 8 | 0 | 0 | 0 | 0 | 0 | 0 | 69 | 90 | 0 | 0 | 39 | 52 | 0 | 302 | 3824 |
| 4:20 PM | 96 | 0 | 12 | 0 | 0 | 0 | 0 | 0 | 0 | 76 | 84 | 0 | 0 | 27 | 46 | 0 | 341 | 3829 |
| 4:25 PM | 46 | 1 | 12 | 0 | 0 | 0 | 0 | 0 | 0 | 89 | 85 | 0 | 0 | 39 | 52 | 0 | 324 | 3818 |
| 4:30 PM | 61 | 0 | 12 | 0 | 0 | 0 | 0 | 0 | 0 | 84 | 72 | 0 | 0 | 33 | 46 | 0 | 308 | 3823 |
| 4:35 PM | 63 | 1 | 10 | 0 | 0 | 0 | 0 | 0 | 0 | 82 | 96 | 0 | 0 | 33 | 46 | 0 | 331 | 3851 |
| 4:40 PM | 46 | 0 | 15 | 0 | 0 | 0 | 0 | 0 | 0 | 118 | 67 | 0 | 0 | 49 | 60 | 0 | 355 | 3852 |
| 4:45 PM | 67 | 1 | 10 | 0 | 0 | 0 | 0 | 0 | 0 | 80 | 85 | 0 | 0 | 39 | 58 | 0 | 338 | 3864 |
| 4:50 PM | 39 | 0 | 21 | 0 | 0 | 0 | 0 | 0 | 0 | 108 | 101 | 0 | 0 | 41 | 65 | 0 | 375 | 3918 |
| 4:55 PM | 75 | 1 | 16 | 0 | 0 | 0 | 0 | 0 | 0 | 96 | 77 | 0 | 0 | 30 | 64 | 0 | 359 | 3990 |
| 5:00 PM | 43 | 0 | 8 | 0 | 0 | 0 | 0 | 0 | 0 | 92 | 88 | 0 | 0 | 52 | 55 | 0 | 338 | 4029 |
| 5:05 PM | 49 | 0 | 20 | 0 | 0 | 0 | 0 | 0 | 0 | 106 | 68 | 0 | 0 | 37 | 62 | 0 | 342 | 4076 |
| 5:10 PM | 51 | 0 | 7 | 0 | 0 | 0 | 0 | 0 | 0 | 78 | 91 | 0 | 0 | 50 | 59 | 0 | 336 | 4049 |
| 5:15 PM | 30 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 104 | 62 | 0 | 0 | 49 | 56 | 0 | 306 | 4053 |
| 5:20 PM | 46 | 1 | 16 | 0 | 0 | 0 | 0 | 0 | 0 | 99 | 78 | 0 | 0 | 31 | 58 | 0 | 329 | 4041 |
| 5:25 PM | 54 | 1 | 17 | 0 | 0 | 0 | 0 | 0 | 0 | 88 | 79 | 0 | 0 | 41 | 47 | 0 | 327 | 4044 |
| 5:30 PM | 52 | 0 | 27 | 0 | 0 | 0 | 0 | 0 | 0 | 111 | 61 | 0 | 0 | 36 | 34 | 0 | 321 | 4057 |
| 5:35 PM | 72 | 0 | 25 | 0 | 0 | 0 | 0 | 0 | 0 | 75 | 64 | 0 | 0 | 40 | 44 | 0 | 320 | 4046 |
| 5:40 PM | 57 | 0 | 23 | 0 | 0 | 0 | 0 | 0 | 0 | 114 | 83 | 0 | 0 | 49 | 48 | 0 | 374 | 4065 |
| 5:45 PM | 70 | 0 | 17 | 0 | 0 | 0 | 0 | 0 | 0 | 92 | 57 | 0 | 0 | 35 | 47 | 0 | 318 | 4045 |
| 5:50 PM | 39 | 0 | 10 | 0 | 0 | 0 | 0 | 0 | 0 | 113 | 81 | 0 | 0 | 44 | 52 | 0 | 339 | 4009 |
| 5:55 PM | 45 | 0 | 17 | 0 | 0 | 0 | 0 | 0 | 0 | 76 | 53 | 0 | 0 | 35 | 52 | 0 | 278 | 3928 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| All Vehicles | 724 | 8 | 188 | 0 | 0 | 0 | 0 | 0 | 0 | 1136 | 1052 | 0 | 0 | 440 | 740 | 0 | 4288 | |
| Heavy Trucks | 56 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 8 | 20 | 0 | 0 | 0 | 20 | 0 | 108 | |
| Pedestrians | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 8 | |
| Bicycles | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 1 | |
| Railroad | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined









Method for determining peak hour: Total Entering Volume

LOCATION: Signalized Entrance to Nyberg Woods -- SW Nyberg St
CITY/STATE: Tualatin, OR

QC JOB #: 10772101
DATE: Tue, Jun 05 2012



Peak-Hour: 4:35 PM -- 5:35 PM
Peak 15-Min: 5:05 PM -- 5:20 PM



| 5-Min Count Period Beginning At | Signalized Entrance to Nyberg Woods (Northbound) | | | | Signalized Entrance to Nyberg Woods (Southbound) | | | | SW Nyberg St (Eastbound) | | | | SW Nyberg St (Westbound) | | | | Total | Hourly Totals |
|---------------------------------|--|------|-------|---|--|------|-------|---|--------------------------|------|-------|---|--------------------------|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 4:00 PM | 5 | 1 | 2 | 0 | 7 | 0 | 16 | 0 | 15 | 76 | 1 | 0 | 2 | 67 | 6 | 0 | 198 | 2420 |
| 4:05 PM | 13 | 1 | 2 | 0 | 11 | 0 | 18 | 0 | 20 | 64 | 5 | 0 | 3 | 66 | 4 | 0 | 207 | 2443 |
| 4:10 PM | 9 | 1 | 0 | 0 | 9 | 0 | 14 | 0 | 17 | 82 | 6 | 0 | 1 | 73 | 8 | 0 | 220 | 2454 |
| 4:15 PM | 3 | 0 | 1 | 0 | 9 | 0 | 19 | 0 | 28 | 38 | 2 | 0 | 1 | 60 | 5 | 1 | 167 | 2439 |
| 4:20 PM | 5 | 0 | 1 | 0 | 8 | 1 | 13 | 0 | 21 | 83 | 5 | 0 | 0 | 65 | 2 | 0 | 204 | 2445 |
| 4:25 PM | 6 | 0 | 2 | 0 | 4 | 1 | 15 | 0 | 20 | 64 | 4 | 0 | 1 | 52 | 5 | 0 | 174 | 2382 |
| 4:30 PM | 7 | 0 | 2 | 0 | 5 | 0 | 15 | 0 | 13 | 67 | 6 | 0 | 0 | 60 | 7 | 0 | 182 | 2375 |
| 4:35 PM | 9 | 1 | 0 | 0 | 9 | 0 | 13 | 0 | 22 | 85 | 6 | 0 | 1 | 66 | 5 | 0 | 217 | 2400 |
| 4:40 PM | 9 | 1 | 1 | 0 | 4 | 1 | 16 | 0 | 29 | 86 | 6 | 0 | 0 | 78 | 5 | 0 | 236 | 2415 |
| 4:45 PM | 13 | 0 | 1 | 0 | 5 | 1 | 13 | 0 | 16 | 70 | 1 | 0 | 0 | 64 | 7 | 0 | 191 | 2386 |
| 4:50 PM | 12 | 3 | 0 | 0 | 2 | 1 | 14 | 0 | 32 | 78 | 10 | 0 | 1 | 70 | 6 | 0 | 229 | 2427 |
| 4:55 PM | 12 | 0 | 1 | 0 | 7 | 0 | 19 | 0 | 23 | 82 | 4 | 0 | 0 | 61 | 13 | 0 | 222 | 2447 |
| 5:00 PM | 8 | 0 | 3 | 0 | 10 | 0 | 17 | 0 | 18 | 69 | 4 | 0 | 1 | 63 | 5 | 0 | 198 | 2447 |
| 5:05 PM | 9 | 0 | 4 | 0 | 4 | 1 | 19 | 0 | 28 | 89 | 5 | 0 | 1 | 69 | 6 | 0 | 235 | 2475 |
| 5:10 PM | 11 | 1 | 1 | 0 | 5 | 0 | 15 | 0 | 20 | 67 | 4 | 0 | 1 | 80 | 7 | 0 | 212 | 2467 |
| 5:15 PM | 8 | 1 | 0 | 0 | 11 | 0 | 21 | 0 | 18 | 85 | 2 | 0 | 1 | 76 | 7 | 0 | 230 | 2530 |
| 5:20 PM | 6 | 0 | 2 | 0 | 12 | 1 | 11 | 0 | 24 | 81 | 4 | 0 | 1 | 53 | 3 | 0 | 198 | 2524 |
| 5:25 PM | 9 | 0 | 1 | 0 | 6 | 0 | 19 | 0 | 25 | 89 | 7 | 1 | 3 | 59 | 3 | 0 | 222 | 2572 |
| 5:30 PM | 6 | 0 | 3 | 0 | 6 | 0 | 14 | 0 | 34 | 71 | 8 | 0 | 0 | 50 | 13 | 0 | 205 | 2595 |
| 5:35 PM | 8 | 0 | 0 | 0 | 3 | 2 | 21 | 0 | 25 | 101 | 7 | 0 | 2 | 52 | 7 | 0 | 228 | 2606 |
| 5:40 PM | 3 | 1 | 0 | 0 | 10 | 0 | 14 | 0 | 31 | 79 | 9 | 0 | 1 | 68 | 6 | 0 | 222 | 2592 |
| 5:45 PM | 4 | 1 | 1 | 0 | 7 | 1 | 17 | 0 | 35 | 88 | 7 | 0 | 0 | 48 | 3 | 0 | 212 | 2613 |
| 5:50 PM | 6 | 1 | 2 | 0 | 7 | 1 | 15 | 0 | 26 | 78 | 5 | 0 | 1 | 68 | 6 | 0 | 216 | 2600 |
| 5:55 PM | 8 | 0 | 3 | 0 | 17 | 2 | 16 | 0 | 21 | 61 | 4 | 0 | 0 | 59 | 9 | 0 | 200 | 2578 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| All Vehicles | 112 | 8 | 20 | 0 | 80 | 4 | 220 | 0 | 264 | 964 | 44 | 0 | 12 | 900 | 80 | 0 | 2708 | |
| Heavy Trucks | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 12 | 0 | 0 | 0 | 20 | 0 | 0 | 32 | |
| Pedestrians | 0 | 0 | 0 | 0 | 0 | 12 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 16 | |
| Bicycles | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 1 | |
| Railroad | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined









Method for determining peak hour: Total Entering Volume

LOCATION: SW Martinazzi Ave -- SW Boones Ferry Rd
 CITY/STATE: Tualatin, OR

QC JOB #: 10772126
 DATE: Sat, Jun 09 2012



Peak-Hour: 12:10 PM -- 1:10 PM
 Peak 15-Min: 12:50 PM -- 1:05 PM



| 5-Min Count Period | SW Martinazzi Ave (Northbound) | | | | SW Martinazzi Ave (Southbound) | | | | SW Boones Ferry Rd (Eastbound) | | | | SW Boones Ferry Rd (Westbound) | | | | Total | Hourly Totals |
|--------------------|--------------------------------|------|-------|---|--------------------------------|------|-------|---|--------------------------------|------|-------|---|--------------------------------|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| Beginning At | | | | | | | | | | | | | | | | | | |
| 11:40 AM | 16 | 0 | 17 | 0 | 0 | 0 | 0 | 0 | 0 | 41 | 5 | 0 | 31 | 38 | 0 | 0 | 148 | |
| 11:45 AM | 13 | 1 | 20 | 0 | 0 | 0 | 0 | 0 | 0 | 40 | 8 | 0 | 21 | 40 | 0 | 0 | 143 | |
| 11:50 AM | 18 | 0 | 30 | 0 | 0 | 0 | 0 | 0 | 0 | 39 | 10 | 0 | 26 | 39 | 0 | 0 | 162 | |
| 11:55 AM | 20 | 0 | 17 | 0 | 0 | 0 | 0 | 0 | 0 | 29 | 9 | 0 | 15 | 37 | 0 | 0 | 127 | 1525 |
| 12:00 PM | 15 | 0 | 20 | 0 | 0 | 0 | 0 | 0 | 0 | 39 | 9 | 0 | 21 | 35 | 0 | 0 | 139 | 1560 |
| 12:05 PM | 7 | 1 | 17 | 0 | 0 | 0 | 0 | 0 | 0 | 36 | 7 | 0 | 17 | 49 | 0 | 0 | 134 | 1576 |
| 12:10 PM | 8 | 0 | 34 | 0 | 1 | 0 | 0 | 0 | 0 | 32 | 14 | 0 | 22 | 26 | 1 | 0 | 138 | 1603 |
| 12:15 PM | 14 | 0 | 23 | 0 | 0 | 0 | 0 | 0 | 0 | 44 | 4 | 0 | 20 | 36 | 0 | 0 | 141 | 1631 |
| 12:20 PM | 12 | 0 | 23 | 0 | 0 | 0 | 0 | 0 | 0 | 37 | 6 | 0 | 20 | 35 | 0 | 0 | 133 | 1635 |
| 12:25 PM | 16 | 0 | 25 | 0 | 0 | 0 | 0 | 0 | 0 | 27 | 17 | 0 | 33 | 34 | 0 | 0 | 152 | 1663 |
| 12:30 PM | 21 | 0 | 24 | 0 | 0 | 0 | 1 | 0 | 0 | 30 | 9 | 0 | 20 | 32 | 0 | 0 | 137 | 1690 |
| 12:35 PM | 15 | 0 | 30 | 0 | 0 | 0 | 0 | 0 | 0 | 31 | 8 | 0 | 14 | 30 | 0 | 0 | 128 | 1682 |
| 12:40 PM | 7 | 0 | 17 | 0 | 0 | 0 | 0 | 0 | 0 | 33 | 8 | 0 | 16 | 33 | 0 | 0 | 114 | 1648 |
| 12:45 PM | 19 | 0 | 27 | 0 | 0 | 0 | 0 | 0 | 0 | 36 | 9 | 0 | 17 | 44 | 0 | 0 | 152 | 1657 |
| 12:50 PM | 16 | 0 | 24 | 0 | 0 | 0 | 0 | 0 | 0 | 31 | 10 | 0 | 21 | 40 | 0 | 0 | 142 | 1637 |
| 12:55 PM | 20 | 0 | 22 | 0 | 0 | 0 | 0 | 0 | 0 | 31 | 7 | 0 | 29 | 33 | 0 | 0 | 142 | 1652 |
| 1:00 PM | 22 | 0 | 22 | 0 | 0 | 0 | 0 | 0 | 0 | 37 | 13 | 0 | 22 | 42 | 0 | 0 | 158 | 1671 |
| 1:05 PM | 9 | 0 | 20 | 0 | 0 | 0 | 0 | 0 | 0 | 36 | 12 | 0 | 16 | 31 | 0 | 0 | 124 | 1661 |
| 1:10 PM | 9 | 0 | 17 | 0 | 0 | 0 | 0 | 0 | 0 | 38 | 4 | 0 | 18 | 38 | 0 | 0 | 124 | 1647 |
| 1:15 PM | 11 | 0 | 18 | 0 | 0 | 0 | 0 | 0 | 0 | 36 | 4 | 0 | 25 | 38 | 0 | 0 | 132 | 1638 |
| 1:20 PM | 18 | 0 | 20 | 0 | 0 | 0 | 0 | 0 | 0 | 25 | 3 | 0 | 24 | 39 | 0 | 0 | 129 | 1634 |
| 1:25 PM | 13 | 0 | 28 | 0 | 0 | 0 | 0 | 0 | 0 | 35 | 5 | 0 | 18 | 36 | 0 | 0 | 135 | 1617 |
| 1:30 PM | 19 | 0 | 19 | 0 | 0 | 0 | 0 | 0 | 0 | 33 | 9 | 0 | 18 | 40 | 0 | 0 | 138 | 1618 |
| 1:35 PM | 14 | 0 | 24 | 0 | 0 | 0 | 0 | 0 | 0 | 36 | 6 | 0 | 26 | 40 | 0 | 0 | 146 | 1636 |

| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total |
|-----------------------|------------|------|-------|---|------------|------|-------|---|-----------|------|-------|---|-----------|------|-------|---|-------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | |
| All Vehicles | 232 | 0 | 272 | 0 | 0 | 0 | 0 | 0 | 0 | 396 | 120 | 0 | 288 | 460 | 0 | 0 | 1768 |
| Heavy Trucks | 8 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 12 | 0 | 0 | 24 |
| Pedestrians | | 12 | | | | 0 | | | | 0 | | | | 4 | | | 16 |
| Bicycles | 1 | 0 | 0 | | 0 | 0 | 0 | | | 0 | 0 | | 0 | 1 | 0 | | 2 |
| Railroad | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined







Method for determining peak hour: Total Entering Volume

LOCATION: SW Martinazzi Ave -- Existing Site Dwy near City Hall
CITY/STATE: Tualatin, OR

QC JOB #: 10772124
DATE: Sat, Jun 09 2012



Peak-Hour: 12:10 PM -- 1:10 PM
Peak 15-Min: 12:20 PM -- 12:35 PM



| 5-Min Count Period | SW Martinazzi Ave (Northbound) | | | | SW Martinazzi Ave (Southbound) | | | | Existing Site Dwy near City Hall (Eastbound) | | | | Existing Site Dwy near City Hall (Westbound) | | | | Total | Hourly Totals |
|-----------------------|--------------------------------|------|-------|---|--------------------------------|------|-------|---|--|------|-------|---|--|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 11:40 AM | 0 | 31 | 10 | 0 | 11 | 22 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 5 | 0 | 81 | |
| 11:45 AM | 0 | 32 | 7 | 0 | 8 | 21 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 5 | 0 | 75 | |
| 11:50 AM | 0 | 31 | 5 | 0 | 13 | 23 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 8 | 0 | 84 | |
| 11:55 AM | 0 | 32 | 4 | 0 | 7 | 17 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 7 | 0 | 69 | 831 |
| 12:00 PM | 0 | 33 | 3 | 0 | 9 | 19 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 3 | 0 | 71 | 845 |
| 12:05 PM | 0 | 23 | 4 | 0 | 7 | 22 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 4 | 0 | 62 | 843 |
| 12:10 PM | 0 | 30 | 4 | 0 | 9 | 26 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 10 | 0 | 82 | 864 |
| 12:15 PM | 0 | 35 | 9 | 0 | 8 | 14 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 6 | 0 | 75 | 877 |
| 12:20 PM | 0 | 28 | 6 | 0 | 15 | 18 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | 0 | 6 | 0 | 78 | 885 |
| 12:25 PM | 0 | 38 | 6 | 0 | 17 | 28 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 11 | 0 | 104 | 913 |
| 12:30 PM | 0 | 39 | 3 | 0 | 14 | 21 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | 0 | 6 | 0 | 88 | 939 |
| 12:35 PM | 0 | 34 | 4 | 0 | 6 | 17 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 6 | 0 | 71 | 940 |
| 12:40 PM | 0 | 21 | 9 | 0 | 2 | 20 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 5 | 0 | 60 | 919 |
| 12:45 PM | 0 | 38 | 2 | 0 | 7 | 18 | 0 | 0 | 0 | 0 | 0 | 0 | 6 | 0 | 6 | 0 | 77 | 921 |
| 12:50 PM | 0 | 37 | 5 | 0 | 13 | 18 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 5 | 0 | 81 | 918 |
| 12:55 PM | 0 | 32 | 5 | 0 | 8 | 28 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 9 | 0 | 85 | 934 |
| 1:00 PM | 0 | 37 | 2 | 0 | 5 | 31 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 6 | 0 | 85 | 948 |
| 1:05 PM | 0 | 27 | 5 | 0 | 10 | 19 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 4 | 0 | 68 | 954 |
| 1:10 PM | 0 | 21 | 3 | 0 | 3 | 19 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 7 | 0 | 56 | 928 |
| 1:15 PM | 0 | 25 | 5 | 0 | 7 | 25 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 6 | 0 | 69 | 922 |
| 1:20 PM | 0 | 31 | 6 | 0 | 4 | 21 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 3 | 0 | 68 | 912 |
| 1:25 PM | 0 | 34 | 5 | 0 | 7 | 16 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 9 | 0 | 75 | 883 |
| 1:30 PM | 0 | 31 | 6 | 0 | 6 | 20 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 4 | 0 | 70 | 865 |
| 1:35 PM | 0 | 33 | 5 | 0 | 11 | 22 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 7 | 0 | 82 | 876 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| All Vehicles | 0 | 420 | 60 | 0 | 184 | 268 | 0 | 0 | 0 | 0 | 0 | 0 | 56 | 0 | 92 | 0 | 1080 | |
| Heavy Trucks | 0 | 4 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 8 | |
| Pedestrians | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 8 | 0 | 0 | 0 | 8 | |
| Bicycles | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Railroad | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined









Method for determining peak hour: Total Entering Volume

LOCATION: SW Martinazzi Ave -- SW Seneca St
 CITY/STATE: Tualatin, OR

QC JOB #: 10772122
 DATE: Sat, Jun 09 2012



Peak-Hour: 12:10 PM -- 1:10 PM
 Peak 15-Min: 12:45 PM -- 1:00 PM



| 5-Min Count Period Beginning At | SW Martinazzi Ave (Northbound) | | | | SW Martinazzi Ave (Southbound) | | | | SW Seneca St (Eastbound) | | | | SW Seneca St (Westbound) | | | | Total | Hourly Totals |
|------------------------------------|--------------------------------|------|-------|---|--------------------------------|------|-------|---|--------------------------|------|-------|---|--------------------------|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 11:40 AM | 4 | 35 | 0 | 0 | 0 | 28 | 0 | 0 | 2 | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 72 | |
| 11:45 AM | 4 | 41 | 0 | 0 | 0 | 24 | 1 | 0 | 3 | 0 | 2 | 0 | 0 | 0 | 0 | 0 | 75 | |
| 11:50 AM | 5 | 36 | 0 | 0 | 0 | 18 | 1 | 0 | 3 | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 66 | |
| 11:55 AM | 10 | 28 | 0 | 0 | 0 | 15 | 2 | 0 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 57 | 764 |
| 12:00 PM | 5 | 32 | 0 | 0 | 0 | 23 | 5 | 0 | 3 | 0 | 7 | 0 | 0 | 0 | 0 | 0 | 75 | 776 |
| 12:05 PM | 8 | 26 | 0 | 0 | 0 | 24 | 2 | 0 | 0 | 0 | 2 | 0 | 0 | 0 | 0 | 0 | 62 | 778 |
| 12:10 PM | 10 | 35 | 0 | 0 | 0 | 22 | 2 | 0 | 4 | 0 | 6 | 0 | 0 | 0 | 0 | 0 | 79 | 801 |
| 12:15 PM | 3 | 42 | 0 | 0 | 0 | 17 | 3 | 0 | 1 | 0 | 6 | 0 | 0 | 0 | 0 | 0 | 72 | 808 |
| 12:20 PM | 5 | 29 | 0 | 0 | 0 | 19 | 3 | 0 | 4 | 0 | 2 | 0 | 0 | 0 | 0 | 0 | 62 | 816 |
| 12:25 PM | 5 | 43 | 0 | 0 | 0 | 26 | 4 | 0 | 3 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 82 | 829 |
| 12:30 PM | 8 | 33 | 0 | 0 | 0 | 21 | 3 | 0 | 3 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 73 | 845 |
| 12:35 PM | 4 | 32 | 0 | 0 | 0 | 14 | 5 | 0 | 5 | 0 | 2 | 0 | 0 | 0 | 0 | 0 | 62 | 837 |
| 12:40 PM | 3 | 25 | 0 | 0 | 0 | 22 | 5 | 0 | 4 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 60 | 825 |
| 12:45 PM | 9 | 42 | 0 | 0 | 0 | 24 | 3 | 0 | 3 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 82 | 832 |
| 12:50 PM | 6 | 41 | 0 | 0 | 0 | 21 | 0 | 0 | 1 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 74 | 840 |
| 12:55 PM | 10 | 33 | 0 | 0 | 0 | 25 | 7 | 0 | 0 | 0 | 2 | 0 | 0 | 0 | 0 | 0 | 77 | 860 |
| 1:00 PM | 8 | 33 | 0 | 0 | 0 | 23 | 4 | 0 | 1 | 0 | 7 | 0 | 0 | 0 | 0 | 0 | 76 | 861 |
| 1:05 PM | 10 | 26 | 0 | 0 | 0 | 22 | 5 | 0 | 6 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 73 | 872 |
| 1:10 PM | 5 | 28 | 0 | 0 | 0 | 15 | 3 | 0 | 2 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 57 | 850 |
| 1:15 PM | 6 | 29 | 0 | 0 | 0 | 22 | 4 | 0 | 5 | 0 | 8 | 0 | 0 | 0 | 0 | 0 | 74 | 852 |
| 1:20 PM | 8 | 33 | 0 | 0 | 0 | 21 | 3 | 0 | 3 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 73 | 863 |
| 1:25 PM | 5 | 40 | 0 | 0 | 0 | 14 | 6 | 0 | 3 | 0 | 6 | 0 | 0 | 0 | 0 | 0 | 74 | 855 |
| 1:30 PM | 7 | 26 | 0 | 0 | 0 | 19 | 4 | 0 | 1 | 0 | 6 | 0 | 0 | 0 | 0 | 0 | 63 | 845 |
| 1:35 PM | 6 | 37 | 0 | 0 | 0 | 21 | 6 | 0 | 3 | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 76 | 859 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| All Vehicles | 100 | 464 | 0 | 0 | 0 | 280 | 40 | 0 | 16 | 0 | 32 | 0 | 0 | 0 | 0 | 0 | 932 | |
| Heavy Trucks | 4 | 16 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 20 | |
| Pedestrians | | 8 | | | | 12 | | | | 4 | | | 28 | | | | 52 | |
| Bicycles | 0 | 2 | 0 | | 0 | 1 | 0 | | 0 | 0 | 0 | | 0 | 0 | 0 | | 3 | |
| Railroad | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined








Method for determining peak hour: Total Entering Volume

LOCATION: SW Martinazzi Ave -- Existing Site Dwy
CITY/STATE: Tualatin, OR

QC JOB #: 10772120
DATE: Sat, Jun 09 2012



Peak-Hour: 12:10 PM -- 1:10 PM
Peak 15-Min: 12:45 PM -- 1:00 PM



| 5-Min Count Period | SW Martinazzi Ave (Northbound) | | | | SW Martinazzi Ave (Southbound) | | | | Existing Site Dwy (Eastbound) | | | | Existing Site Dwy (Westbound) | | | | Total | Hourly Totals | |
|-----------------------|--------------------------------|------|-------|---|--------------------------------|------|-------|---|-------------------------------|------|-------|---|-------------------------------|------|-------|---|-------|---------------|-----|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | | |
| 11:40 AM | 0 | 39 | 1 | 0 | 0 | 31 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 72 | |
| 11:45 AM | 0 | 44 | 0 | 0 | 0 | 26 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 71 | |
| 11:50 AM | 0 | 35 | 0 | 0 | 0 | 23 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 5 | 0 | 0 | 63 | |
| 11:55 AM | 0 | 37 | 2 | 0 | 0 | 16 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 57 | 725 |
| 12:00 PM | 0 | 35 | 1 | 0 | 0 | 29 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 3 | 0 | 0 | 69 | 738 |
| 12:05 PM | 0 | 34 | 0 | 0 | 0 | 24 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 58 | 736 |
| 12:10 PM | 0 | 41 | 1 | 0 | 0 | 28 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 72 | 761 |
| 12:15 PM | 0 | 49 | 2 | 0 | 1 | 22 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 74 | 772 |
| 12:20 PM | 0 | 33 | 1 | 0 | 1 | 21 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 1 | 0 | 0 | 58 | 781 |
| 12:25 PM | 0 | 43 | 0 | 0 | 0 | 28 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 0 | 74 | 789 |
| 12:30 PM | 0 | 37 | 1 | 0 | 0 | 25 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 67 | 800 |
| 12:35 PM | 0 | 33 | 2 | 0 | 0 | 16 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 2 | 0 | 0 | 54 | 789 |
| 12:40 PM | 0 | 31 | 0 | 0 | 0 | 24 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 56 | 773 |
| 12:45 PM | 0 | 50 | 0 | 0 | 0 | 25 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 77 | 779 |
| 12:50 PM | 0 | 45 | 1 | 0 | 1 | 25 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 76 | 792 |
| 12:55 PM | 0 | 42 | 2 | 0 | 0 | 27 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 73 | 808 |
| 1:00 PM | 0 | 37 | 0 | 0 | 0 | 29 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 2 | 0 | 0 | 69 | 808 |
| 1:05 PM | 0 | 37 | 0 | 0 | 0 | 26 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 2 | 0 | 0 | 66 | 816 |
| 1:10 PM | 0 | 26 | 0 | 0 | 0 | 19 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 47 | 791 |
| 1:15 PM | 0 | 34 | 0 | 0 | 0 | 32 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 66 | 783 |
| 1:20 PM | 0 | 43 | 1 | 0 | 0 | 26 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 71 | 796 |
| 1:25 PM | 0 | 41 | 0 | 0 | 1 | 18 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 0 | 63 | 785 |
| 1:30 PM | 0 | 33 | 0 | 0 | 0 | 25 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 1 | 0 | 0 | 60 | 778 |
| 1:35 PM | 0 | 41 | 0 | 0 | 0 | 24 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 66 | 790 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | | |
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | | |
| All Vehicles | 0 | 548 | 12 | 0 | 4 | 308 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 32 | 0 | 0 | 904 | |
| Heavy Trucks | 0 | 20 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 20 | |
| Pedestrians | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 12 | 0 | 0 | 36 | 0 | 0 | 0 | 52 | |
| Bicycles | 0 | 1 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | |
| Railroad | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Stopped Buses | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |


Comments: N

Type of peak hour being reported: User-Defined






Method for determining peak hour: Total Entering Volume

LOCATION: SW Martinazzi Ave -- Existing Right-Out Only Dwy
CITY/STATE: Tualatin, OR

QC JOB #: 10772118
DATE: Sat, Jun 09 2012



Peak-Hour: 12:10 PM -- 1:10 PM
Peak 15-Min: 12:50 PM -- 1:05 PM



| 5-Min Count Period Beginning At | SW Martinazzi Ave (Northbound) | | | | SW Martinazzi Ave (Southbound) | | | | Existing Right-Out Only Dwy (Eastbound) | | | | Existing Right-Out Only Dwy (Westbound) | | | | Total | Hourly Totals |
|---------------------------------|--------------------------------|------|-------|---|--------------------------------|------|-------|---|---|------|-------|---|---|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 11:40 AM | 0 | 35 | 0 | 0 | 0 | 30 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 65 | |
| 11:45 AM | 0 | 42 | 0 | 0 | 0 | 25 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 68 | |
| 11:50 AM | 0 | 35 | 0 | 0 | 0 | 23 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 58 | |
| 11:55 AM | 0 | 37 | 0 | 0 | 0 | 17 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 56 | 707 |
| 12:00 PM | 0 | 37 | 0 | 0 | 0 | 32 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 70 | 716 |
| 12:05 PM | 0 | 31 | 0 | 0 | 0 | 27 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 58 | 717 |
| 12:10 PM | 0 | 41 | 0 | 0 | 0 | 29 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 74 | 737 |
| 12:15 PM | 0 | 44 | 0 | 0 | 0 | 21 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 65 | 744 |
| 12:20 PM | 0 | 34 | 0 | 0 | 0 | 22 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 56 | 748 |
| 12:25 PM | 0 | 43 | 0 | 0 | 0 | 28 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 71 | 761 |
| 12:30 PM | 0 | 43 | 0 | 0 | 0 | 25 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 68 | 774 |
| 12:35 PM | 0 | 29 | 0 | 0 | 0 | 18 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 47 | 756 |
| 12:40 PM | 0 | 33 | 0 | 0 | 0 | 28 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 62 | 753 |
| 12:45 PM | 0 | 43 | 0 | 0 | 0 | 27 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 71 | 756 |
| 12:50 PM | 0 | 45 | 0 | 0 | 0 | 26 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 72 | 770 |
| 12:55 PM | 0 | 33 | 0 | 0 | 0 | 24 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 57 | 771 |
| 1:00 PM | 0 | 44 | 0 | 0 | 1 | 37 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 82 | 783 |
| 1:05 PM | 0 | 34 | 0 | 0 | 0 | 32 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 67 | 792 |
| 1:10 PM | 0 | 23 | 0 | 0 | 0 | 25 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 49 | 767 |
| 1:15 PM | 0 | 33 | 0 | 0 | 0 | 31 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 65 | 767 |
| 1:20 PM | 0 | 45 | 0 | 0 | 0 | 34 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 80 | 791 |
| 1:25 PM | 0 | 37 | 0 | 0 | 0 | 20 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 0 | 60 | 780 |
| 1:30 PM | 0 | 31 | 0 | 0 | 0 | 27 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 59 | 771 |
| 1:35 PM | 0 | 43 | 0 | 0 | 0 | 27 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 0 | 73 | 797 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| All Vehicles | 0 | 488 | 0 | 0 | 4 | 348 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 844 | |
| Heavy Trucks | 0 | 16 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 16 | |
| Pedestrians | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 24 | 0 | 0 | 0 | 28 | |
| Bicycles | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Railroad | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined









Method for determining peak hour: Total Entering Volume

LOCATION: SW Martinazzi Ave -- SW Tualatin-Sherwood Rd
CITY/STATE: Tualatin, OR

QC JOB #: 10772116
DATE: Sat, Jun 09 2012



Peak-Hour: 12:10 PM -- 1:10 PM
Peak 15-Min: 12:25 PM -- 12:40 PM



| 5-Min Count Period | SW Martinazzi Ave (Northbound) | | | | SW Martinazzi Ave (Southbound) | | | | SW Tualatin-Sherwood Rd (Eastbound) | | | | SW Tualatin-Sherwood Rd (Westbound) | | | | Total | Hourly Totals |
|-----------------------|--------------------------------|------|-------|---|--------------------------------|------|-------|---|-------------------------------------|------|-------|---|-------------------------------------|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 11:40 AM | 8 | 25 | 16 | 0 | 11 | 29 | 9 | 0 | 6 | 84 | 10 | 0 | 0 | 82 | 0 | 0 | 280 | |
| 11:45 AM | 6 | 14 | 27 | 0 | 10 | 38 | 6 | 0 | 7 | 83 | 9 | 0 | 0 | 100 | 0 | 0 | 300 | |
| 11:50 AM | 12 | 20 | 20 | 0 | 9 | 26 | 9 | 0 | 5 | 111 | 21 | 0 | 0 | 80 | 0 | 0 | 313 | |
| 11:55 AM | 6 | 14 | 23 | 0 | 8 | 24 | 8 | 0 | 6 | 87 | 7 | 0 | 0 | 104 | 0 | 0 | 287 | 3388 |
| 12:00 PM | 14 | 10 | 19 | 0 | 10 | 30 | 9 | 0 | 1 | 97 | 14 | 0 | 0 | 85 | 1 | 0 | 290 | 3416 |
| 12:05 PM | 3 | 17 | 23 | 0 | 8 | 35 | 9 | 0 | 1 | 88 | 7 | 0 | 0 | 86 | 0 | 0 | 277 | 3411 |
| 12:10 PM | 10 | 15 | 16 | 0 | 15 | 25 | 3 | 0 | 4 | 98 | 14 | 0 | 0 | 74 | 0 | 0 | 274 | 3429 |
| 12:15 PM | 10 | 16 | 12 | 0 | 9 | 46 | 5 | 0 | 6 | 93 | 10 | 0 | 0 | 106 | 0 | 0 | 313 | 3450 |
| 12:20 PM | 5 | 19 | 15 | 0 | 2 | 29 | 12 | 0 | 5 | 80 | 6 | 0 | 0 | 95 | 1 | 0 | 269 | 3452 |
| 12:25 PM | 10 | 13 | 19 | 0 | 5 | 35 | 9 | 0 | 7 | 114 | 17 | 0 | 0 | 90 | 0 | 0 | 319 | 3511 |
| 12:30 PM | 11 | 24 | 21 | 0 | 17 | 39 | 2 | 0 | 7 | 81 | 15 | 0 | 0 | 96 | 0 | 0 | 313 | 3547 |
| 12:35 PM | 8 | 18 | 21 | 0 | 14 | 29 | 4 | 0 | 6 | 87 | 8 | 0 | 0 | 97 | 0 | 0 | 292 | 3527 |
| 12:40 PM | 7 | 14 | 16 | 0 | 5 | 29 | 10 | 0 | 3 | 113 | 11 | 0 | 0 | 89 | 0 | 0 | 297 | 3544 |
| 12:45 PM | 4 | 27 | 20 | 0 | 10 | 36 | 7 | 0 | 5 | 81 | 14 | 0 | 0 | 74 | 0 | 0 | 278 | 3522 |
| 12:50 PM | 11 | 10 | 18 | 0 | 12 | 20 | 5 | 0 | 7 | 95 | 13 | 0 | 0 | 98 | 0 | 0 | 289 | 3498 |
| 12:55 PM | 8 | 15 | 17 | 0 | 7 | 36 | 4 | 0 | 7 | 95 | 3 | 0 | 0 | 97 | 0 | 0 | 289 | 3500 |
| 1:00 PM | 5 | 16 | 24 | 0 | 12 | 26 | 14 | 0 | 3 | 75 | 15 | 0 | 0 | 88 | 0 | 0 | 278 | 3488 |
| 1:05 PM | 8 | 20 | 19 | 0 | 13 | 17 | 6 | 0 | 3 | 114 | 11 | 0 | 0 | 91 | 0 | 0 | 302 | 3513 |
| 1:10 PM | 15 | 15 | 22 | 0 | 16 | 37 | 5 | 0 | 4 | 91 | 10 | 0 | 0 | 73 | 0 | 0 | 288 | 3527 |
| 1:15 PM | 10 | 13 | 12 | 0 | 11 | 39 | 4 | 0 | 5 | 74 | 7 | 0 | 0 | 75 | 0 | 0 | 250 | 3464 |
| 1:20 PM | 7 | 17 | 22 | 0 | 14 | 36 | 8 | 0 | 9 | 115 | 10 | 0 | 0 | 107 | 0 | 0 | 345 | 3540 |
| 1:25 PM | 7 | 11 | 16 | 0 | 11 | 30 | 4 | 0 | 6 | 102 | 16 | 0 | 0 | 108 | 0 | 0 | 311 | 3532 |
| 1:30 PM | 11 | 20 | 25 | 0 | 9 | 44 | 6 | 0 | 6 | 88 | 9 | 0 | 0 | 72 | 0 | 0 | 290 | 3509 |
| 1:35 PM | 14 | 17 | 19 | 0 | 9 | 25 | 5 | 0 | 4 | 108 | 8 | 0 | 0 | 104 | 0 | 0 | 313 | 3530 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| Beginning At | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| All Vehicles | 116 | 220 | 244 | 0 | 144 | 412 | 60 | 0 | 80 | 1128 | 160 | 0 | 0 | 1132 | 0 | 0 | 3696 | |
| Heavy Trucks | 0 | 0 | 4 | 0 | 4 | 4 | 0 | 0 | 0 | 44 | 0 | 0 | 0 | 24 | 0 | 0 | 80 | |
| Pedestrians | | 0 | | | | 8 | | | | 8 | | | | 4 | | | 20 | |
| Bicycles | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Railroad | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined










Method for determining peak hour: Total Entering Volume

LOCATION: SW Martinazzi Ave -- SW Nyberg St
CITY/STATE: Tualatin, OR

QC JOB #: 10772114
DATE: Sat, Jun 09 2012



Peak-Hour: 12:10 PM -- 1:10 PM
Peak 15-Min: 12:20 PM -- 12:35 PM



| 5-Min Count Period | SW Martinazzi Ave (Northbound) | | | | SW Martinazzi Ave (Southbound) | | | | SW Nyberg St (Eastbound) | | | | SW Nyberg St (Westbound) | | | | Total | Hourly Totals |
|-----------------------|--------------------------------|------|-------|---|--------------------------------|------|-------|---|--------------------------|------|-------|---|--------------------------|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 11:40 AM | 1 | 17 | 2 | 0 | 0 | 30 | 1 | 0 | 1 | 0 | 4 | 0 | 15 | 3 | 20 | 0 | 94 | |
| 11:45 AM | 2 | 16 | 5 | 0 | 0 | 27 | 0 | 0 | 1 | 0 | 5 | 0 | 25 | 4 | 22 | 0 | 107 | |
| 11:50 AM | 5 | 17 | 1 | 0 | 0 | 23 | 0 | 0 | 1 | 0 | 4 | 0 | 15 | 5 | 17 | 0 | 88 | |
| 11:55 AM | 2 | 15 | 2 | 0 | 0 | 19 | 0 | 0 | 1 | 0 | 7 | 0 | 15 | 3 | 23 | 0 | 87 | 1043 |
| 12:00 PM | 0 | 16 | 1 | 0 | 0 | 28 | 0 | 0 | 1 | 0 | 3 | 0 | 19 | 4 | 22 | 0 | 94 | 1052 |
| 12:05 PM | 0 | 15 | 0 | 0 | 0 | 32 | 0 | 0 | 1 | 0 | 7 | 0 | 16 | 4 | 16 | 0 | 91 | 1059 |
| 12:10 PM | 0 | 17 | 4 | 0 | 0 | 27 | 1 | 0 | 1 | 0 | 2 | 0 | 22 | 6 | 25 | 0 | 105 | 1086 |
| 12:15 PM | 4 | 26 | 1 | 0 | 1 | 22 | 2 | 0 | 3 | 0 | 6 | 0 | 11 | 2 | 11 | 0 | 89 | 1087 |
| 12:20 PM | 1 | 13 | 1 | 0 | 0 | 22 | 0 | 0 | 0 | 0 | 8 | 0 | 22 | 4 | 21 | 0 | 92 | 1107 |
| 12:25 PM | 2 | 21 | 4 | 0 | 0 | 25 | 1 | 0 | 3 | 0 | 2 | 0 | 21 | 1 | 18 | 0 | 98 | 1123 |
| 12:30 PM | 2 | 27 | 1 | 0 | 0 | 29 | 0 | 0 | 2 | 0 | 5 | 0 | 26 | 4 | 17 | 0 | 113 | 1151 |
| 12:35 PM | 1 | 17 | 1 | 0 | 0 | 16 | 0 | 0 | 1 | 0 | 9 | 0 | 22 | 1 | 12 | 0 | 80 | 1138 |
| 12:40 PM | 5 | 14 | 3 | 0 | 0 | 24 | 2 | 0 | 1 | 0 | 5 | 0 | 27 | 0 | 18 | 0 | 99 | 1143 |
| 12:45 PM | 2 | 21 | 7 | 0 | 0 | 26 | 0 | 0 | 0 | 1 | 6 | 0 | 14 | 4 | 22 | 0 | 103 | 1139 |
| 12:50 PM | 1 | 24 | 1 | 0 | 0 | 24 | 0 | 0 | 1 | 0 | 6 | 0 | 11 | 1 | 21 | 0 | 90 | 1141 |
| 12:55 PM | 3 | 16 | 1 | 0 | 0 | 30 | 1 | 0 | 3 | 0 | 3 | 0 | 14 | 1 | 26 | 0 | 98 | 1152 |
| 1:00 PM | 0 | 9 | 2 | 0 | 0 | 29 | 0 | 0 | 1 | 0 | 6 | 0 | 9 | 3 | 22 | 0 | 81 | 1139 |
| 1:05 PM | 2 | 23 | 5 | 0 | 0 | 27 | 1 | 0 | 0 | 0 | 5 | 0 | 18 | 5 | 13 | 0 | 99 | 1147 |
| 1:10 PM | 2 | 12 | 1 | 0 | 0 | 22 | 0 | 0 | 1 | 0 | 9 | 0 | 23 | 1 | 11 | 0 | 82 | 1124 |
| 1:15 PM | 1 | 18 | 1 | 0 | 0 | 31 | 0 | 0 | 1 | 0 | 3 | 0 | 25 | 1 | 15 | 0 | 96 | 1131 |
| 1:20 PM | 1 | 22 | 0 | 0 | 0 | 32 | 0 | 0 | 2 | 0 | 5 | 0 | 16 | 6 | 18 | 0 | 102 | 1141 |
| 1:25 PM | 0 | 24 | 4 | 0 | 0 | 18 | 0 | 0 | 1 | 0 | 6 | 0 | 27 | 5 | 12 | 0 | 97 | 1140 |
| 1:30 PM | 0 | 12 | 4 | 0 | 0 | 24 | 2 | 0 | 1 | 1 | 7 | 0 | 16 | 2 | 18 | 0 | 87 | 1114 |
| 1:35 PM | 1 | 24 | 2 | 0 | 0 | 28 | 2 | 0 | 2 | 1 | 4 | 0 | 16 | 2 | 18 | 0 | 100 | 1134 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| All Vehicles | 20 | 244 | 24 | 0 | 0 | 304 | 4 | 0 | 20 | 0 | 60 | 0 | 276 | 36 | 224 | 0 | 1212 | |
| Heavy Trucks | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 8 | 0 | 8 | 0 | 20 | |
| Pedestrians | | 0 | | | | 0 | | | | 4 | | | | 0 | | | 4 | |
| Bicycles | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Railroad | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined









Method for determining peak hour: Total Entering Volume

LOCATION: Unsignalized Site Dwy -- SW Nyberg St
 CITY/STATE: Tualatin, OR

QC JOB #: 10772112
 DATE: Sat, Jun 09 2012



Peak-Hour: 12:10 PM -- 1:10 PM
 Peak 15-Min: 12:20 PM -- 12:35 PM



| 5-Min Count Period Beginning At | Unsignalized Site Dwy (Northbound) | | | | Unsignalized Site Dwy (Southbound) | | | | SW Nyberg St (Eastbound) | | | | SW Nyberg St (Westbound) | | | | Total | Hourly Totals |
|------------------------------------|------------------------------------|------|-------|---|------------------------------------|------|-------|---|--------------------------|------|-------|---|--------------------------|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 11:40 AM | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 2 | 0 | 0 | 0 | 0 | 34 | 2 | 0 | 40 | |
| 11:45 AM | 0 | 0 | 0 | 0 | 0 | 0 | 10 | 0 | 2 | 0 | 0 | 0 | 0 | 37 | 5 | 0 | 54 | |
| 11:50 AM | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 3 | 0 | 0 | 0 | 0 | 31 | 4 | 0 | 41 | |
| 11:55 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 40 | 1 | 0 | 42 | 481 |
| 12:00 PM | 0 | 0 | 0 | 0 | 0 | 0 | 6 | 0 | 1 | 0 | 0 | 0 | 0 | 39 | 3 | 0 | 49 | 497 |
| 12:05 PM | 0 | 0 | 0 | 0 | 0 | 0 | 5 | 0 | 1 | 0 | 0 | 0 | 0 | 27 | 2 | 0 | 35 | 488 |
| 12:10 PM | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 2 | 0 | 0 | 0 | 0 | 48 | 4 | 0 | 57 | 508 |
| 12:15 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 0 | 0 | 35 | 4 | 0 | 41 | 515 |
| 12:20 PM | 0 | 0 | 0 | 0 | 0 | 0 | 8 | 0 | 1 | 0 | 0 | 0 | 0 | 33 | 5 | 0 | 47 | 527 |
| 12:25 PM | 0 | 0 | 0 | 0 | 0 | 0 | 9 | 0 | 2 | 0 | 0 | 0 | 0 | 38 | 6 | 0 | 55 | 540 |
| 12:30 PM | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 2 | 0 | 0 | 0 | 0 | 43 | 5 | 0 | 52 | 557 |
| 12:35 PM | 0 | 0 | 0 | 0 | 0 | 0 | 8 | 0 | 1 | 0 | 0 | 0 | 0 | 28 | 4 | 0 | 41 | 554 |
| 12:40 PM | 0 | 0 | 0 | 0 | 0 | 0 | 7 | 0 | 2 | 0 | 0 | 0 | 0 | 34 | 4 | 0 | 47 | 561 |
| 12:45 PM | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 5 | 0 | 0 | 0 | 0 | 34 | 3 | 0 | 46 | 553 |
| 12:50 PM | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 3 | 0 | 0 | 0 | 0 | 35 | 4 | 0 | 46 | 558 |
| 12:55 PM | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 3 | 0 | 0 | 0 | 0 | 35 | 4 | 0 | 46 | 562 |
| 1:00 PM | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 1 | 0 | 0 | 0 | 0 | 42 | 4 | 0 | 49 | 562 |
| 1:05 PM | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 29 | 5 | 0 | 36 | 563 |
| 1:10 PM | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 29 | 6 | 0 | 39 | 545 |
| 1:15 PM | 0 | 0 | 0 | 0 | 0 | 0 | 5 | 0 | 1 | 0 | 0 | 0 | 0 | 31 | 5 | 0 | 42 | 546 |
| 1:20 PM | 0 | 0 | 0 | 0 | 0 | 0 | 7 | 0 | 1 | 0 | 0 | 0 | 0 | 32 | 4 | 0 | 44 | 543 |
| 1:25 PM | 0 | 0 | 0 | 0 | 0 | 0 | 7 | 0 | 2 | 0 | 0 | 0 | 0 | 40 | 9 | 0 | 58 | 546 |
| 1:30 PM | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 5 | 0 | 0 | 0 | 0 | 39 | 2 | 0 | 50 | 544 |
| 1:35 PM | 0 | 0 | 0 | 0 | 0 | 0 | 3 | 0 | 4 | 0 | 0 | 0 | 0 | 31 | 5 | 0 | 43 | 546 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| All Vehicles | 0 | 0 | 0 | 0 | 0 | 0 | 76 | 0 | 20 | 0 | 0 | 0 | 0 | 456 | 64 | 0 | 616 | |
| Heavy Trucks | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 16 | 0 | 0 | 16 | |
| Pedestrians | | 0 | | | | 4 | | | | 0 | | | | 0 | | | 4 | |
| Bicycles | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | |
| Railroad | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined










Method for determining peak hour: Total Entering Volume

LOCATION: Fred Meyer/Site Dwy -- SW Nyberg St/SW Tualatin-Sherwood Rd
CITY/STATE: Tualatin, OR

QC JOB #: 10772110
DATE: Sat, Jun 09 2012



Peak-Hour: 12:10 PM -- 1:10 PM
Peak 15-Min: 12:25 PM -- 12:40 PM



| 5-Min Count Period Beginning At | Fred Meyer/Site Dwy (Northbound) | | | | Fred Meyer/Site Dwy (Southbound) | | | | SW Nyberg St/SW Tualatin-Sherwood Rd (Eastbound) | | | | SW Nyberg St/SW Tualatin-Sherwood Rd (Westbound) | | | | Hourly Totals | |
|---------------------------------|----------------------------------|------|-------|---|----------------------------------|------|-------|---|--|------|-------|---|--|------|-------|---|---------------|-------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | Total |
| 11:40 AM | 3 | 3 | 19 | 0 | 12 | 4 | 3 | 0 | 3 | 110 | 4 | 0 | 18 | 114 | 4 | 0 | 297 | |
| 11:45 AM | 4 | 2 | 21 | 0 | 10 | 2 | 4 | 0 | 4 | 101 | 6 | 0 | 18 | 143 | 9 | 1 | 325 | |
| 11:50 AM | 3 | 1 | 12 | 0 | 10 | 6 | 1 | 0 | 5 | 133 | 1 | 0 | 13 | 110 | 5 | 0 | 300 | |
| 11:55 AM | 4 | 2 | 20 | 0 | 14 | 3 | 5 | 0 | 6 | 118 | 5 | 0 | 21 | 124 | 13 | 1 | 336 | 3590 |
| 12:00 PM | 3 | 2 | 17 | 0 | 12 | 3 | 3 | 0 | 2 | 108 | 9 | 0 | 26 | 128 | 7 | 0 | 320 | 3602 |
| 12:05 PM | 3 | 1 | 12 | 0 | 13 | 3 | 3 | 0 | 5 | 115 | 4 | 0 | 17 | 106 | 9 | 0 | 291 | 3617 |
| 12:10 PM | 5 | 4 | 26 | 0 | 9 | 3 | 5 | 0 | 5 | 104 | 9 | 0 | 29 | 130 | 13 | 0 | 342 | 3663 |
| 12:15 PM | 1 | 1 | 15 | 0 | 14 | 3 | 7 | 0 | 5 | 99 | 10 | 0 | 20 | 122 | 10 | 0 | 307 | 3687 |
| 12:20 PM | 8 | 2 | 26 | 0 | 14 | 1 | 10 | 0 | 6 | 92 | 2 | 0 | 26 | 120 | 10 | 0 | 317 | 3717 |
| 12:25 PM | 7 | 2 | 17 | 0 | 14 | 3 | 4 | 0 | 4 | 127 | 3 | 0 | 19 | 130 | 8 | 0 | 338 | 3776 |
| 12:30 PM | 7 | 1 | 32 | 0 | 15 | 4 | 6 | 0 | 5 | 105 | 3 | 0 | 25 | 121 | 11 | 2 | 337 | 3803 |
| 12:35 PM | 6 | 3 | 27 | 0 | 17 | 6 | 2 | 0 | 4 | 113 | 5 | 0 | 20 | 129 | 10 | 0 | 342 | 3852 |
| 12:40 PM | 4 | 1 | 16 | 0 | 14 | 3 | 6 | 0 | 4 | 117 | 5 | 0 | 13 | 113 | 9 | 0 | 305 | 3860 |
| 12:45 PM | 4 | 3 | 23 | 0 | 19 | 1 | 4 | 0 | 4 | 102 | 4 | 0 | 26 | 103 | 4 | 0 | 297 | 3832 |
| 12:50 PM | 4 | 1 | 19 | 0 | 11 | 3 | 7 | 0 | 0 | 129 | 5 | 0 | 21 | 135 | 8 | 0 | 343 | 3875 |
| 12:55 PM | 3 | 2 | 19 | 0 | 11 | 4 | 2 | 0 | 6 | 102 | 4 | 0 | 13 | 131 | 5 | 0 | 302 | 3841 |
| 1:00 PM | 5 | 2 | 16 | 0 | 9 | 4 | 6 | 0 | 4 | 112 | 3 | 0 | 22 | 101 | 5 | 0 | 289 | 3810 |
| 1:05 PM | 3 | 3 | 12 | 0 | 7 | 5 | 3 | 0 | 3 | 133 | 6 | 0 | 21 | 116 | 8 | 0 | 320 | 3839 |
| 1:10 PM | 7 | 2 | 21 | 0 | 11 | 5 | 2 | 0 | 9 | 117 | 2 | 0 | 24 | 106 | 4 | 0 | 310 | 3807 |
| 1:15 PM | 4 | 0 | 21 | 0 | 8 | 4 | 4 | 0 | 3 | 105 | 7 | 0 | 19 | 108 | 7 | 0 | 290 | 3790 |
| 1:20 PM | 6 | 1 | 19 | 0 | 13 | 2 | 2 | 0 | 5 | 125 | 6 | 0 | 18 | 140 | 11 | 0 | 348 | 3821 |
| 1:25 PM | 1 | 1 | 17 | 0 | 12 | 0 | 4 | 0 | 5 | 134 | 2 | 0 | 12 | 137 | 5 | 0 | 330 | 3813 |
| 1:30 PM | 9 | 0 | 14 | 0 | 10 | 4 | 10 | 0 | 0 | 101 | 3 | 0 | 25 | 119 | 11 | 0 | 306 | 3782 |
| 1:35 PM | 5 | 1 | 18 | 0 | 4 | 3 | 4 | 0 | 3 | 126 | 10 | 0 | 22 | 121 | 5 | 0 | 322 | 3762 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| All Vehicles | 80 | 24 | 304 | 0 | 184 | 52 | 48 | 0 | 52 | 1380 | 44 | 0 | 256 | 1520 | 116 | 8 | 4068 | |
| Heavy Trucks | 0 | 0 | 0 | | 4 | 0 | 0 | | 8 | 48 | 0 | | 4 | 40 | 0 | | 104 | |
| Pedestrians | | | | | | 4 | | | | 12 | | | | 0 | | | 16 | |
| Bicycles | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | |
| Railroad | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined








Method for determining peak hour: Total Entering Volume

LOCATION: SW 75th Ave -- SW Nyberg St
CITY/STATE: Tualatin, OR

QC JOB #: 10772108
DATE: Sat, Jun 09 2012



Peak-Hour: 12:10 PM -- 1:10 PM
Peak 15-Min: 12:25 PM -- 12:40 PM



| 5-Min Count Period | SW 75th Ave (Northbound) | | | | SW 75th Ave (Southbound) | | | | SW Nyberg St (Eastbound) | | | | SW Nyberg St (Westbound) | | | | Total | Hourly Totals | |
|-----------------------|--------------------------|------|-------|---|--------------------------|------|-------|---|--------------------------|------|-------|---|--------------------------|------|-------|---|-------|---------------|------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | | |
| 11:40 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 141 | 0 | 0 | 0 | 147 | 6 | 0 | 294 | |
| 11:45 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 132 | 0 | 0 | 0 | 167 | 6 | 0 | 305 | |
| 11:50 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 155 | 0 | 0 | 0 | 137 | 5 | 0 | 297 | |
| 11:55 AM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 152 | 0 | 0 | 0 | 155 | 2 | 0 | 309 | 3418 |
| 12:00 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 137 | 0 | 0 | 0 | 161 | 1 | 0 | 299 | 3435 |
| 12:05 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 140 | 0 | 0 | 0 | 137 | 3 | 0 | 280 | 3449 |
| 12:10 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 139 | 0 | 0 | 0 | 157 | 5 | 0 | 301 | 3464 |
| 12:15 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 128 | 0 | 0 | 0 | 161 | 0 | 0 | 289 | 3510 |
| 12:20 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 132 | 0 | 0 | 0 | 145 | 2 | 0 | 280 | 3502 |
| 12:25 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 158 | 0 | 0 | 0 | 161 | 3 | 0 | 322 | 3554 |
| 12:30 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 152 | 0 | 0 | 0 | 164 | 4 | 0 | 321 | 3588 |
| 12:35 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 157 | 0 | 0 | 0 | 150 | 7 | 0 | 314 | 3611 |
| 12:40 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 147 | 0 | 0 | 0 | 125 | 4 | 0 | 277 | 3594 |
| 12:45 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 144 | 0 | 0 | 0 | 132 | 5 | 0 | 281 | 3570 |
| 12:50 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 159 | 0 | 0 | 0 | 159 | 2 | 0 | 321 | 3594 |
| 12:55 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 132 | 0 | 0 | 0 | 156 | 5 | 0 | 293 | 3578 |
| 1:00 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 137 | 0 | 0 | 0 | 114 | 6 | 0 | 258 | 3537 |
| 1:05 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 152 | 0 | 0 | 0 | 150 | 5 | 0 | 307 | 3564 |
| 1:10 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 149 | 0 | 0 | 0 | 133 | 5 | 0 | 287 | 3550 |
| 1:15 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 134 | 0 | 0 | 0 | 133 | 6 | 0 | 273 | 3534 |
| 1:20 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 157 | 0 | 0 | 0 | 165 | 4 | 0 | 326 | 3580 |
| 1:25 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 163 | 0 | 0 | 0 | 138 | 7 | 0 | 309 | 3567 |
| 1:30 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 125 | 0 | 0 | 0 | 152 | 3 | 0 | 280 | 3526 |
| 1:35 PM | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 2 | 0 | 0 | 148 | 0 | 0 | 0 | 133 | 5 | 0 | 288 | 3500 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | | |
| All Vehicles | 0 | 0 | 0 | 0 | 0 | 0 | 4 | 0 | 0 | 1868 | 0 | 0 | 0 | 1900 | 56 | 0 | 3828 | | |
| Heavy Trucks | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 52 | 0 | 0 | 0 | 44 | 0 | 0 | 96 | | |
| Pedestrians | | | | | | 4 | | | | 0 | | | | 0 | | | 4 | | |
| Bicycles | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | |
| Railroad | | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined






Method for determining peak hour: Total Entering Volume

LOCATION: I-5 SB Ramp Terminal -- SW Nyberg St
CITY/STATE: Tualatin, OR

QC JOB #: 10772106
DATE: Sat, Jun 16 2012



Peak-Hour: 12:10 PM -- 1:10 PM
Peak 15-Min: 12:50 PM -- 1:05 PM



| 5-Min Count Period Beginning At | I-5 SB Ramp Terminal (Northbound) | | | | I-5 SB Ramp Terminal (Southbound) | | | | SW Nyberg St (Eastbound) | | | | SW Nyberg St (Westbound) | | | | Total | Hourly Totals |
|------------------------------------|-----------------------------------|------|-------|---|-----------------------------------|------|-------|---|--------------------------|------|-------|---|--------------------------|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 11:40 AM | 0 | 0 | 0 | 0 | 39 | 0 | 82 | 0 | 0 | 80 | 57 | 0 | 6 | 77 | 0 | 0 | 341 | |
| 11:45 AM | 0 | 0 | 0 | 0 | 32 | 1 | 49 | 0 | 0 | 100 | 44 | 0 | 13 | 87 | 0 | 0 | 326 | |
| 11:50 AM | 0 | 0 | 0 | 0 | 54 | 0 | 90 | 0 | 0 | 103 | 55 | 0 | 10 | 80 | 0 | 0 | 392 | |
| 11:55 AM | 0 | 0 | 0 | 0 | 39 | 0 | 68 | 0 | 0 | 99 | 49 | 0 | 15 | 75 | 0 | 0 | 345 | 4077 |
| 12:00 PM | 0 | 0 | 0 | 0 | 30 | 0 | 58 | 0 | 0 | 109 | 52 | 0 | 12 | 99 | 0 | 0 | 360 | 4127 |
| 12:05 PM | 0 | 0 | 0 | 0 | 47 | 0 | 57 | 0 | 0 | 81 | 53 | 0 | 17 | 59 | 0 | 0 | 314 | 4126 |
| 12:10 PM | 0 | 0 | 0 | 0 | 47 | 0 | 75 | 0 | 0 | 136 | 50 | 0 | 11 | 92 | 0 | 0 | 411 | 4197 |
| 12:15 PM | 0 | 0 | 0 | 0 | 41 | 0 | 71 | 0 | 0 | 105 | 41 | 0 | 18 | 100 | 0 | 0 | 376 | 4216 |
| 12:20 PM | 0 | 0 | 0 | 0 | 49 | 0 | 74 | 0 | 0 | 90 | 44 | 0 | 19 | 79 | 0 | 0 | 355 | 4287 |
| 12:25 PM | 0 | 0 | 0 | 0 | 44 | 0 | 63 | 0 | 0 | 115 | 43 | 0 | 12 | 74 | 0 | 0 | 351 | 4287 |
| 12:30 PM | 0 | 0 | 0 | 0 | 55 | 1 | 55 | 0 | 0 | 90 | 54 | 0 | 20 | 60 | 0 | 0 | 335 | 4250 |
| 12:35 PM | 0 | 0 | 0 | 0 | 54 | 1 | 74 | 0 | 0 | 127 | 47 | 0 | 12 | 93 | 0 | 0 | 408 | 4314 |
| 12:40 PM | 0 | 0 | 0 | 0 | 51 | 0 | 67 | 0 | 0 | 112 | 54 | 0 | 15 | 102 | 0 | 0 | 401 | 4374 |
| 12:45 PM | 0 | 0 | 0 | 0 | 55 | 0 | 72 | 0 | 0 | 105 | 51 | 0 | 22 | 57 | 0 | 0 | 362 | 4410 |
| 12:50 PM | 0 | 0 | 0 | 0 | 39 | 0 | 64 | 0 | 0 | 144 | 60 | 0 | 13 | 89 | 0 | 0 | 409 | 4427 |
| 12:55 PM | 0 | 0 | 0 | 0 | 68 | 0 | 71 | 0 | 0 | 106 | 54 | 0 | 19 | 69 | 0 | 0 | 387 | 4469 |
| 1:00 PM | 0 | 0 | 0 | 0 | 34 | 1 | 58 | 0 | 0 | 131 | 62 | 0 | 8 | 103 | 0 | 0 | 397 | 4506 |
| 1:05 PM | 0 | 0 | 0 | 0 | 65 | 0 | 89 | 0 | 0 | 76 | 45 | 0 | 18 | 70 | 0 | 0 | 363 | 4555 |
| 1:10 PM | 0 | 0 | 0 | 0 | 48 | 1 | 67 | 0 | 0 | 102 | 64 | 0 | 10 | 89 | 0 | 0 | 381 | 4525 |
| 1:15 PM | 0 | 0 | 0 | 0 | 50 | 0 | 67 | 0 | 0 | 95 | 50 | 0 | 19 | 75 | 0 | 0 | 356 | 4505 |
| 1:20 PM | 0 | 0 | 0 | 0 | 64 | 0 | 74 | 0 | 0 | 92 | 56 | 0 | 13 | 63 | 0 | 0 | 362 | 4512 |
| 1:25 PM | 0 | 0 | 0 | 0 | 53 | 0 | 68 | 0 | 0 | 105 | 44 | 0 | 11 | 95 | 0 | 0 | 376 | 4537 |
| 1:30 PM | 0 | 0 | 0 | 0 | 59 | 0 | 74 | 0 | 0 | 112 | 49 | 0 | 11 | 81 | 0 | 0 | 386 | 4588 |
| 1:35 PM | 0 | 0 | 0 | 0 | 60 | 0 | 87 | 0 | 0 | 89 | 51 | 0 | 21 | 57 | 0 | 0 | 365 | 4545 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| All Vehicles | 0 | 0 | 0 | 0 | 564 | 4 | 772 | 0 | 0 | 1524 | 704 | 0 | 160 | 1044 | 0 | 0 | 4772 | |
| Heavy Trucks | 0 | 0 | 0 | 0 | 4 | 0 | 8 | 0 | 0 | 24 | 16 | 0 | 4 | 24 | 0 | 0 | 80 | |
| Pedestrians | | | | | | 16 | | | | 0 | | | | 0 | | | 16 | |
| Bicycles | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 1 | |
| Railroad | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined







Method for determining peak hour: Total Entering Volume

LOCATION: I-5 NB Ramp Terminal -- SW Nyberg St
 CITY/STATE: Tualatin, OR

QC JOB #: 10772104
 DATE: Sat, Jun 16 2012



Peak-Hour: 12:10 PM -- 1:10 PM
 Peak 15-Min: 12:45 PM -- 1:00 PM



| 5-Min Count Period Beginning At | I-5 NB Ramp Terminal (Northbound) | | | | I-5 NB Ramp Terminal (Southbound) | | | | SW Nyberg St (Eastbound) | | | | SW Nyberg St (Westbound) | | | | Total | Hourly Totals |
|------------------------------------|-----------------------------------|------|-------|---|-----------------------------------|------|-------|---|--------------------------|------|-------|---|--------------------------|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 11:40 AM | 40 | 0 | 23 | 0 | 0 | 0 | 0 | 0 | 0 | 55 | 62 | 0 | 0 | 43 | 50 | 0 | 273 | |
| 11:45 AM | 63 | 0 | 19 | 0 | 0 | 0 | 0 | 0 | 0 | 62 | 58 | 0 | 0 | 36 | 57 | 0 | 295 | |
| 11:50 AM | 49 | 0 | 15 | 0 | 0 | 0 | 0 | 0 | 0 | 82 | 72 | 0 | 0 | 42 | 58 | 0 | 318 | |
| 11:55 AM | 35 | 0 | 20 | 0 | 0 | 0 | 0 | 0 | 0 | 83 | 69 | 0 | 0 | 50 | 36 | 0 | 293 | 3449 |
| 12:00 PM | 63 | 0 | 17 | 0 | 0 | 0 | 0 | 0 | 0 | 69 | 66 | 0 | 0 | 46 | 55 | 0 | 316 | 3498 |
| 12:05 PM | 36 | 0 | 15 | 0 | 0 | 0 | 0 | 0 | 0 | 71 | 61 | 0 | 0 | 51 | 61 | 0 | 295 | 3558 |
| 12:10 PM | 55 | 0 | 17 | 0 | 0 | 0 | 0 | 0 | 0 | 82 | 81 | 0 | 0 | 40 | 50 | 0 | 325 | 3605 |
| 12:15 PM | 67 | 0 | 13 | 0 | 0 | 0 | 0 | 0 | 0 | 86 | 63 | 0 | 0 | 48 | 43 | 0 | 320 | 3616 |
| 12:20 PM | 36 | 0 | 15 | 0 | 0 | 0 | 0 | 0 | 0 | 82 | 64 | 0 | 0 | 62 | 41 | 0 | 300 | 3654 |
| 12:25 PM | 38 | 0 | 22 | 0 | 0 | 0 | 0 | 0 | 0 | 79 | 64 | 0 | 0 | 45 | 66 | 0 | 314 | 3687 |
| 12:30 PM | 28 | 0 | 13 | 0 | 0 | 0 | 0 | 0 | 0 | 99 | 63 | 0 | 0 | 58 | 66 | 0 | 327 | 3705 |
| 12:35 PM | 57 | 0 | 21 | 0 | 0 | 0 | 0 | 0 | 0 | 87 | 79 | 0 | 0 | 44 | 50 | 0 | 338 | 3714 |
| 12:40 PM | 60 | 0 | 13 | 0 | 0 | 0 | 0 | 0 | 0 | 83 | 57 | 0 | 0 | 55 | 55 | 0 | 323 | 3764 |
| 12:45 PM | 33 | 0 | 21 | 0 | 0 | 0 | 0 | 0 | 0 | 101 | 95 | 0 | 0 | 47 | 56 | 0 | 353 | 3822 |
| 12:50 PM | 53 | 0 | 25 | 0 | 0 | 0 | 0 | 0 | 0 | 66 | 91 | 0 | 0 | 41 | 60 | 0 | 336 | 3840 |
| 12:55 PM | 40 | 0 | 20 | 0 | 0 | 0 | 0 | 0 | 0 | 101 | 97 | 0 | 0 | 59 | 56 | 0 | 373 | 3920 |
| 1:00 PM | 59 | 0 | 15 | 0 | 0 | 0 | 0 | 0 | 0 | 84 | 73 | 0 | 0 | 48 | 44 | 0 | 323 | 3927 |
| 1:05 PM | 48 | 0 | 18 | 0 | 0 | 0 | 0 | 0 | 0 | 89 | 58 | 0 | 0 | 53 | 59 | 0 | 325 | 3957 |
| 1:10 PM | 42 | 0 | 18 | 0 | 0 | 0 | 0 | 0 | 0 | 72 | 72 | 0 | 0 | 47 | 51 | 0 | 302 | 3934 |
| 1:15 PM | 51 | 0 | 13 | 0 | 0 | 0 | 0 | 0 | 0 | 89 | 39 | 0 | 0 | 45 | 46 | 0 | 283 | 3897 |
| 1:20 PM | 41 | 0 | 23 | 0 | 0 | 0 | 0 | 0 | 0 | 100 | 81 | 0 | 0 | 43 | 59 | 0 | 347 | 3944 |
| 1:25 PM | 51 | 0 | 21 | 0 | 0 | 0 | 0 | 0 | 0 | 79 | 67 | 0 | 0 | 41 | 43 | 0 | 302 | 3932 |
| 1:30 PM | 49 | 0 | 15 | 0 | 0 | 0 | 0 | 0 | 0 | 91 | 67 | 0 | 0 | 43 | 49 | 0 | 314 | 3919 |
| 1:35 PM | 37 | 0 | 22 | 0 | 0 | 0 | 0 | 0 | 0 | 104 | 74 | 0 | 0 | 48 | 50 | 0 | 335 | 3916 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| All Vehicles | 504 | 0 | 264 | 0 | 0 | 0 | 0 | 0 | 0 | 1072 | 1132 | 0 | 0 | 588 | 688 | 0 | 4248 | |
| Heavy Trucks | 16 | 0 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 8 | 16 | 0 | 0 | 24 | 8 | 0 | 76 | |
| Pedestrians | | 4 | | | | 0 | | | | 4 | | | | 4 | | | 12 | |
| Bicycles | 0 | 0 | 0 | | 0 | 0 | 0 | | 0 | 1 | 0 | | 0 | 0 | 0 | | 1 | |
| Railroad | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | |


Comments: N

Type of peak hour being reported: User-Defined







Method for determining peak hour: Total Entering Volume

LOCATION: Signalized Entrance to Nyberg Woods -- SW Nyberg St
CITY/STATE: Tualatin, OR

QC JOB #: 10772102
DATE: Sat, Jun 09 2012



Peak-Hour: 12:10 PM -- 1:10 PM
Peak 15-Min: 12:35 PM -- 12:50 PM



| 5-Min Count Period Beginning At | Signalized Entrance to Nyberg Woods (Northbound) | | | | Signalized Entrance to Nyberg Woods (Southbound) | | | | SW Nyberg St (Eastbound) | | | | SW Nyberg St (Westbound) | | | | Total | Hourly Totals |
|------------------------------------|--|------|-------|---|--|------|-------|---|--------------------------|------|-------|---|--------------------------|------|-------|---|-------|---------------|
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| 11:40 AM | 3 | 0 | 1 | 0 | 13 | 0 | 21 | 0 | 41 | 41 | 4 | 0 | 1 | 49 | 8 | 0 | 182 | |
| 11:45 AM | 3 | 4 | 0 | 0 | 9 | 2 | 20 | 0 | 22 | 45 | 4 | 1 | 0 | 46 | 17 | 0 | 173 | |
| 11:50 AM | 7 | 1 | 0 | 0 | 8 | 0 | 23 | 0 | 32 | 43 | 5 | 0 | 2 | 54 | 12 | 0 | 187 | |
| 11:55 AM | 7 | 1 | 1 | 0 | 5 | 0 | 25 | 0 | 45 | 44 | 6 | 0 | 0 | 55 | 7 | 0 | 196 | 2141 |
| 12:00 PM | 10 | 1 | 1 | 0 | 6 | 3 | 31 | 0 | 27 | 47 | 3 | 0 | 0 | 64 | 11 | 0 | 204 | 2170 |
| 12:05 PM | 8 | 0 | 2 | 0 | 8 | 2 | 19 | 0 | 58 | 44 | 7 | 1 | 1 | 77 | 10 | 0 | 237 | 2239 |
| 12:10 PM | 12 | 1 | 0 | 0 | 5 | 0 | 28 | 0 | 34 | 38 | 4 | 0 | 0 | 82 | 11 | 0 | 215 | 2310 |
| 12:15 PM | 9 | 2 | 0 | 0 | 6 | 2 | 26 | 0 | 41 | 34 | 3 | 0 | 1 | 77 | 6 | 0 | 207 | 2327 |
| 12:20 PM | 5 | 1 | 0 | 0 | 13 | 1 | 28 | 0 | 46 | 39 | 6 | 0 | 1 | 56 | 14 | 0 | 210 | 2348 |
| 12:25 PM | 9 | 0 | 3 | 0 | 8 | 1 | 28 | 0 | 32 | 44 | 4 | 0 | 2 | 62 | 13 | 0 | 206 | 2377 |
| 12:30 PM | 8 | 2 | 2 | 0 | 5 | 0 | 26 | 0 | 39 | 42 | 6 | 0 | 0 | 53 | 8 | 0 | 191 | 2393 |
| 12:35 PM | 8 | 0 | 1 | 0 | 10 | 0 | 29 | 0 | 61 | 37 | 7 | 0 | 3 | 51 | 15 | 0 | 222 | 2430 |
| 12:40 PM | 11 | 1 | 1 | 0 | 13 | 1 | 33 | 0 | 44 | 54 | 4 | 0 | 1 | 42 | 8 | 0 | 213 | 2461 |
| 12:45 PM | 5 | 1 | 1 | 0 | 8 | 0 | 30 | 0 | 42 | 43 | 6 | 0 | 2 | 67 | 4 | 0 | 209 | 2497 |
| 12:50 PM | 10 | 1 | 0 | 0 | 11 | 1 | 29 | 0 | 57 | 53 | 2 | 0 | 1 | 33 | 8 | 0 | 206 | 2516 |
| 12:55 PM | 2 | 0 | 1 | 0 | 4 | 1 | 15 | 0 | 43 | 55 | 7 | 0 | 0 | 58 | 4 | 0 | 190 | 2510 |
| 1:00 PM | 12 | 1 | 2 | 0 | 12 | 2 | 25 | 0 | 44 | 51 | 3 | 0 | 2 | 42 | 5 | 0 | 201 | 2507 |
| 1:05 PM | 12 | 1 | 1 | 0 | 6 | 2 | 25 | 0 | 41 | 54 | 5 | 0 | 2 | 49 | 5 | 0 | 203 | 2473 |
| 1:10 PM | 10 | 3 | 3 | 0 | 5 | 0 | 31 | 0 | 34 | 50 | 2 | 0 | 0 | 38 | 6 | 0 | 182 | 2440 |
| 1:15 PM | 9 | 3 | 0 | 0 | 8 | 0 | 24 | 0 | 34 | 54 | 7 | 0 | 2 | 52 | 9 | 0 | 202 | 2435 |
| 1:20 PM | 5 | 2 | 1 | 0 | 2 | 1 | 32 | 0 | 46 | 47 | 1 | 0 | 2 | 48 | 12 | 0 | 199 | 2424 |
| 1:25 PM | 10 | 0 | 0 | 0 | 8 | 1 | 25 | 0 | 45 | 50 | 5 | 0 | 1 | 36 | 10 | 0 | 191 | 2409 |
| 1:30 PM | 6 | 1 | 1 | 0 | 5 | 0 | 32 | 0 | 26 | 58 | 1 | 0 | 2 | 44 | 5 | 0 | 181 | 2399 |
| 1:35 PM | 5 | 2 | 0 | 0 | 6 | 0 | 28 | 0 | 29 | 45 | 6 | 0 | 0 | 45 | 6 | 0 | 172 | 2349 |
| Peak 15-Min Flowrates | Northbound | | | | Southbound | | | | Eastbound | | | | Westbound | | | | Total | |
| | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | Left | Thru | Right | U | | |
| All Vehicles | 96 | 8 | 12 | 0 | 124 | 4 | 368 | 0 | 588 | 536 | 68 | 0 | 24 | 640 | 108 | 0 | 2576 | |
| Heavy Trucks | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 8 | 4 | 0 | 0 | 0 | 20 | 0 | 0 | 32 | |
| Pedestrians | | 4 | | | | 16 | | | | 0 | | | | 8 | | | 28 | |
| Bicycles | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| Railroad | | | | | | | | | | | | | | | | | | |
| Stopped Buses | | | | | | | | | | | | | | | | | | |

Comments: N

| Row | Count Date | Peak Hr Start | Total Vehicle Volumes | | | | | | | | | | | | PHF | Heavy Vehicle Percentages | | | | | | | | | | | | Pedestrian Volumes | | | | | | Bicycle Volumes | | | | | | | | | |
|---|------------|---------------|-----------------------|-----|-----|-----|------------|-----|-----|-------|-----------|-----|-------|-------|-------|---------------------------|------|-----|-----|------------|-----|-----|------------|-----|-----|------------|---|--------------------|-----------|---|----|------------------|----|-----------------|---|-------|---|---|-------|---|---|---|---|
| | | | Northbound | | | | Southbound | | | | Eastbound | | | | | Westbound | | | | Northbound | | | Southbound | | | En inbound | | | Westbound | | | Intersection Leg | | Approach Leg | | TOTAL | | | | | | | |
| | | | NBL | NBT | NBR | SBL | SBT | SBR | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR | EBL | EBT | EBR | WBL | WBT | WBR | N | S | E | W | N | S | E | W | N | S | E | W | TOTAL | | | | |
| H-5B Ramps & SW Whberg Rd | 10/18/11 | 4:03 PM | 0 | 0 | 0 | 822 | 1 | 950 | 0 | 1,178 | 750 | 137 | 870 | 0 | 4,548 | 0.87 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| SW Minicazzi Ave & SW Tualatin Sherwood Rd | 10/18/11 | 4:03 PM | 96 | 305 | 350 | 155 | 519 | 81 | 54 | 1,398 | 90 | 0 | 1,117 | 2 | 4,167 | 0.94 | 2 | 5 | 3 | 1 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| SW Boones Ferry Rd & SW Tualatin Sherwood Rd | 10/18/11 | 4:03 PM | 166 | 260 | 154 | 268 | 325 | 129 | 100 | 984 | 134 | 217 | 1,051 | 54 | 3,722 | 0.99 | 4 | 5 | 3 | 2 | 4 | 3 | 6 | 7 | 3 | 0 | 7 | 9 | 15 | 0 | 20 | 0 | 35 | 1 | 1 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| H-5B Ramps & SW Whberg Rd | 10/18/11 | 4:03 PM | 504 | 1 | 152 | 0 | 0 | 0 | 0 | 1,147 | 711 | 0 | 478 | 706 | 3,729 | 0.94 | 7 | 0 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| SW Boones Ferry Rd & SW Lower Boones Ferry Rd | 10/18/11 | 4:33 PM | 0 | 470 | 541 | 57 | 658 | 1 | 7 | 9 | 455 | 7 | 39 | 2,443 | 0.96 | 0 | 3 | 2 | 2 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| SW Boones Ferry Rd & SW Avery St | 10/18/11 | 4:33 PM | 167 | 494 | 29 | 13 | 654 | 80 | 168 | 107 | 246 | 36 | 53 | 12 | 2,458 | 0.94 | 3 | 2 | 2 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| SW Tilton Ave & SW Lower Boones Ferry Rd | 10/18/11 | 4:33 PM | 3 | 36 | 21 | 179 | 81 | 110 | 87 | 279 | 29 | 33 | 169 | 130 | 1,157 | 0.90 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | |
| H-5B Ramps & SW Whberg Rd | 10/18/11 | 4:40 PM | 552 | 3 | 565 | 0 | 0 | 0 | 652 | 1,142 | 0 | 0 | 1,398 | 585 | 4,697 | 0.91 | 1 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| SW Minicazzi Ave & SW Avery St | 10/18/11 | 4:55 PM | 8 | 138 | 1 | 29 | 301 | 59 | 82 | 8 | 20 | 4 | 7 | 20 | 676 | 0.90 | 0 | 2 | 0 | 1 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| SW 72nd Ave & Lower Boones Ferry Rd | 10/18/11 | 4:35 PM | 19 | 85 | 621 | 529 | 185 | 70 | 42 | 635 | 10 | 532 | 541 | 572 | 3,622 | 0.95 | 0 | 6 | 1 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| SW Tilton Ave & SW Tualatin Sherwood Rd | 10/18/11 | 4:25 PM | 13 | 185 | 114 | 229 | 210 | 15 | 28 | 694 | 22 | 136 | 722 | 202 | 2,570 | 0.93 | 0 | 5 | 4 | 6 | 1 | 20 | 11 | 4 | 0 | 4 | 5 | 12 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| SW 90th Ave & SW Tualatin Sherwood Rd | 10/18/11 | 4:10 PM | 11 | 20 | 48 | 106 | 6 | 82 | 101 | 1,054 | 9 | 23 | 941 | 147 | 2,548 | 0.94 | 0 | 0 | 2 | 0 | 2 | 0 | 6 | 11 | 13 | 6 | 3 | 2 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| SW 90th Ave & SW Tualatin Rd | 10/18/11 | 4:35 PM | 228 | 0 | 7 | 14 | 6 | 9 | 1 | 640 | 171 | 3 | 869 | 5 | 1,913 | 0.96 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| SW Boones Ferry Rd & SW Beggs St | 10/18/11 | 4:25 PM | 16 | 462 | 212 | 63 | 545 | 73 | 41 | 1,04 | 13 | 161 | 109 | 62 | 1,651 | 0.92 | 0 | 3 | 1 | 4 | 5 | 4 | 11 | 2 | 2 | 0 | 6 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| SW 124th Ave & SW Herman Rd | 10/18/11 | 4:35 PM | 0 | 139 | 0 | 0 | 0 | 0 | 0 | 256 | 166 | 160 | 135 | 0 | 909 | 0.89 | 0 | 1 | 4 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| SW Tualatin Rd & SW Boones Ferry Rd | 10/18/11 | 4:35 PM | 0 | 194 | 269 | 430 | 354 | 0 | 0 | 0 | 0 | 0 | 398 | 0 | 227 | 2,053 | 0.95 | 0 | 0 | 2 | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| SW Tualatin Rd & SW Boones Ferry Rd | 10/18/11 | 4:40 PM | 2 | 315 | 339 | 411 | 480 | 10 | 23 | 23 | 10 | 233 | 0 | 273 | 760 | 1,620 | 0.95 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | |
| SW 85th Ave & SW Boones Ferry Rd | 10/18/11 | 4:30 PM | 0 | 0 | 0 | 371 | 0 | 1 | 10 | 405 | 0 | 0 | 273 | 760 | 1,620 | 0.95 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | |
| SW Tualatin Rd & SW Sugar St | 10/18/11 | 4:35 PM | 208 | 0 | 69 | 0 | 0 | 0 | 0 | 318 | 93 | 34 | 694 | 0 | 1,569 | 0.95 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | |
| SW Tilton Ave & SW Tualatin Rd | 10/18/11 | 4:25 PM | 185 | 227 | 42 | 22 | 133 | 4 | 3 | 291 | 155 | 43 | 251 | 14 | 1,370 | 0.90 | 8 | 3 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | |
| SW 124th Ave & SW Herman Rd | 10/18/11 | 4:35 PM | 501 | 0 | 482 | 0 | 0 | 0 | 0 | 922 | 139 | 310 | 776 | 0 | 3,130 | 0.89 | 1 | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | |
| SW Minicazzi Ave & SW Boones Ferry Rd | 10/18/11 | 4:42 PM | 176 | 6 | 4 | 22 | 5 | 29 | 4 | 712 | 362 | 2 | 745 | 10 | 2,099 | 0.98 | 1 | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |
| SW 124th Ave & SW Sherman Rd | 10/18/11 | 4:35 PM | 60 | 531 | 2 | 4 | 689 | 243 | 154 | 0 | 130 | 0 | 0 | 2 | 1,874 | 0.93 | 0 | 2 | 0 | 1 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | |
| SW Boones Ferry Rd & SW Sherman Rd | 10/18/11 | 4:35 PM | 2 | 173 | 46 | 301 | 287 | 232 | 114 | 226 | 12 | 87 | 189 | 198 | 1,796 | 0.90 | 0 | 1 | 3 | 2 | 1 | 2 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | |
| SW Minicazzi Ave & SW Tualatin Rd | 10/18/11 | 4:35 PM | 0 | 465 | 42 | 538 | 204 | 0 | 0 | 0 | 0 | 10 | 0 | 587 | 1,622 | 0.84 | 0 | 1 | 2 | 5 | 4 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | | |
| H-5B Ramps & SW Lower Boones Ferry Rd | 10/18/11 | 4:57 PM | 0 | 0 | 0 | 538 | 0 | 580 | 0 | 1,200 | 579 | 670 | 1,386 | 0 | 4,603 | 0.91 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | |

Appendix C
Description of Level-of-Service
Methods and Criteria

APPENDIX C LEVEL-OF-SERVICE CONCEPT

Level of service (LOS) is a concept developed to quantify the degree of comfort (including such elements as travel time, number of stops, total amount of stopped delay, and impediments caused by other vehicles) afforded to drivers as they travel through an intersection or roadway segment. Six grades are used to denote the various level of service from “A” to “F”.¹

SIGNALIZED INTERSECTIONS

The six level-of-service grades are described qualitatively for signalized intersections in Table C1. Additionally, Table C2 identifies the relationship between level of service and average control delay per vehicle. Control delay is defined to include initial deceleration delay, queue move-up time, stopped delay, and final acceleration delay. Using this definition, Level of Service “D” is generally considered to represent the minimum acceptable design standard.

Table C-1 Level-of-Service Definitions (Signalized Intersections)

| Level of Service | Average Delay per Vehicle |
|------------------|---|
| A | Very low average control delay, less than 10 seconds per vehicle. This occurs when progression is extremely favorable, and most vehicles arrive during the green phase. Most vehicles do not stop at all. Short cycle lengths may also contribute to low delay. |
| B | Average control delay is greater than 10 seconds per vehicle and less than or equal to 20 seconds per vehicle. This generally occurs with good progression and/or short cycle lengths. More vehicles stop than for a level of service A, causing higher levels of average delay. |
| C | Average control delay is greater than 20 seconds per vehicle and less than or equal to 35 seconds per vehicle. These higher delays may result from fair progression and/or longer cycle lengths. Individual cycle failures may begin to appear at this level. The number of vehicles stopping is significant at this level, although many still pass through the intersection without stopping. |
| D | Average control delay is greater than 35 seconds per vehicle and less than or equal to 55 seconds per vehicle. The influence of congestion becomes more noticeable. Longer delays may result from some combination of unfavorable progression, long cycle length, or high volume/capacity ratios. Many vehicles stop, and the proportion of vehicles not stopping declines. Individual cycle failures are noticeable. |
| E | Average control delay is greater than 55 seconds per vehicle and less than or equal to 80 seconds per vehicle. This is usually considered to be the limit of acceptable delay. These high delay values generally (but not always) indicate poor progression, long cycle lengths, and high volume/capacity ratios. Individual cycle failures are frequent occurrences. |
| F | Average control delay is in excess of 80 seconds per vehicle. This is considered to be unacceptable to most drivers. This condition often occurs with oversaturation. It may also occur at high volume/capacity ratios below 1.0 with many individual cycle failures. Poor progression and long cycle lengths may also contribute to such high delay values. |

¹ Most of the material in this appendix is adapted from the Transportation Research Board, *Highway Capacity Manual*, (2000).

Table C2 Level-of-Service Criteria for Signalized Intersections

| Level of Service | Average Control Delay per Vehicle (Seconds) |
|------------------|---|
| A | <10.0 |
| B | >10 and ≤20 |
| C | >20 and ≤35 |
| D | >35 and ≤55 |
| E | >55 and ≤80 |
| F | >80 |

UNSIGNALIZED INTERSECTIONS

Unsignalized intersections include two-way stop-controlled (TWSC) and all-way stop-controlled (AWSC) intersections. The 2000 *Highway Capacity Manual* (HCM) provides models for estimating control delay at both TWSC and AWSC intersections. A qualitative description of the various service levels associated with an unsignalized intersection is presented in Table C3. A quantitative definition of level of service for unsignalized intersections is presented in Table C4. Using this definition, Level of Service “E” is generally considered to represent the minimum acceptable design standard.

Table C3 Level-of-Service Criteria for Unsignalized Intersections

| Level of Service | Average Delay per Vehicle to Minor Street |
|------------------|---|
| A | <ul style="list-style-type: none"> Nearly all drivers find freedom of operation. Very seldom is there more than one vehicle in queue. |
| B | <ul style="list-style-type: none"> Some drivers begin to consider the delay an inconvenience. Occasionally there is more than one vehicle in queue. |
| C | <ul style="list-style-type: none"> Many times there is more than one vehicle in queue. Most drivers feel restricted, but not objectionably so. |
| D | <ul style="list-style-type: none"> Often there is more than one vehicle in queue. Drivers feel quite restricted. |
| E | <ul style="list-style-type: none"> Represents a condition in which the demand is near or equal to the probable maximum number of vehicles that can be accommodated by the movement. There is almost always more than one vehicle in queue. Drivers find the delays approaching intolerable levels. |
| F | <ul style="list-style-type: none"> Forced flow. Represents an intersection failure condition that is caused by geometric and/or operational constraints external to the intersection. |

Table C4 Level-of-Service Criteria for Unsignalized Intersections

| Level of Service | Average Control Delay per Vehicle (Seconds) |
|------------------|---|
| A | <10.0 |
| B | >10.0 and ≤ 15.0 |
| C | >15.0 and ≤ 25.0 |
| D | >25.0 and ≤ 35.0 |
| E | >35.0 and ≤ 50.0 |
| F | >50.0 |

It should be noted that the level-of-service criteria for unsignalized intersections are somewhat different than the criteria used for signalized intersections. The primary reason for this difference is that drivers expect different levels of performance from different kinds of transportation facilities. The expectation is that a signalized intersection is designed to carry higher traffic volumes than an unsignalized intersection. Additionally, there are a number of driver behavior considerations that combine to make delays at signalized intersections less galling than at unsignalized intersections. For example, drivers at signalized intersections are able to relax during the red interval, while drivers on the minor street approaches to TWSC intersections must remain attentive to the task of identifying acceptable gaps and vehicle conflicts. Also, there is often much more variability in the amount of delay experienced by individual drivers at unsignalized intersections than signalized intersections. For these reasons, it is considered that the control delay threshold for any given level of service is less for an unsignalized intersection than for a signalized intersection. While overall intersection level of service is calculated for AWSC intersections, level of service is only calculated for the minor approaches and the major street left turn movements at TWSC intersections. No delay is assumed to the major street through movements. For TWSC intersections, the overall intersection level of service remains undefined: level of service is only calculated for each minor street lane.

In the performance evaluation of TWSC intersections, it is important to consider other measures of effectiveness (MOEs) in addition to delay, such as v/c ratios for individual movements, average queue lengths, and 95th-percentile queue lengths. By focusing on a single MOE for the worst movement only, such as delay for the minor-street left turn, users may make inappropriate traffic control decisions. The potential for making such inappropriate decisions is likely to be particularly pronounced when the HCM level-of-service thresholds are adopted as legal standards, as is the case in many public agencies.















Appendix D
Existing Operations Worksheets

HCM Signalized Intersection Capacity Analysis

1: Lower Boones Ferry Rd & SW Upper Boones Ferry Rd

4/15/2013

| |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | | ↕ | | ↕ | ↕ | | ↕ | ↑ | ↕ | ↕ | ↕ | ↕ |
| Volume (vph) | 1 | 7 | 9 | 455 | 7 | 39 | 0 | 470 | 541 | 57 | 656 | 1 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | | 3.5 | | 3.5 | 3.5 | | | 4.0 | 3.5 | 3.5 | 4.0 | |
| Lane Util. Factor | | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | |
| Frbp, ped/bikes | | 0.94 | | 1.00 | 1.00 | | | 1.00 | 0.99 | 1.00 | 1.00 | |
| Flpb, ped/bikes | | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | |
| Frt | | 0.93 | | 1.00 | 0.87 | | | 1.00 | 0.85 | 1.00 | 1.00 | |
| Flt Protected | | 1.00 | | 0.95 | 1.00 | | | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (prot) | | 1655 | | 1752 | 1657 | | | 1845 | 1567 | 1770 | 1881 | |
| Flt Permitted | | 1.00 | | 0.95 | 1.00 | | | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (perm) | | 1655 | | 1752 | 1657 | | | 1845 | 1567 | 1770 | 1881 | |
| Peak-hour factor, PHF | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 |
| Adj. Flow (vph) | 1 | 7 | 9 | 474 | 7 | 41 | 0 | 490 | 564 | 59 | 683 | 1 |
| RTOR Reduction (vph) | 0 | 9 | 0 | 0 | 25 | 0 | 0 | 0 | 153 | 0 | 0 | 0 |
| Lane Group Flow (vph) | 0 | 8 | 0 | 474 | 23 | 0 | 0 | 490 | 411 | 59 | 684 | 0 |
| Confl. Peds. (#/hr) | | | 5 | 5 | | | 12 | | 1 | 1 | | 12 |
| Heavy Vehicles (%) | 0% | 0% | 0% | 3% | 0% | 0% | 0% | 3% | 2% | 2% | 1% | 0% |
| Turn Type | Split | | | Split | | | Prot | | pm+ov | | Prot | |
| Protected Phases | 8 | 8 | | 4 | 4 | | 1 | 6 | 4 | 5 | 2 | |
| Permitted Phases | | | | | | | | | 6 | | | |
| Actuated Green, G (s) | | 1.7 | | 32.1 | 32.1 | | | 27.0 | 59.1 | 5.2 | 36.2 | |
| Effective Green, g (s) | | 2.2 | | 32.6 | 32.6 | | | 27.5 | 60.1 | 5.7 | 36.7 | |
| Actuated g/C Ratio | | 0.03 | | 0.40 | 0.40 | | | 0.33 | 0.73 | 0.07 | 0.44 | |
| Clearance Time (s) | | 4.0 | | 4.0 | 4.0 | | | 4.5 | 4.0 | 4.0 | 4.5 | |
| Vehicle Extension (s) | | 2.5 | | 2.2 | 2.2 | | | 3.5 | 2.2 | 2.2 | 3.5 | |
| Lane Grp Cap (vph) | | 44 | | 692 | 655 | | | 615 | 1142 | 122 | 837 | |
| v/s Ratio Prot | | c0.00 | | c0.27 | 0.01 | | | 0.27 | 0.14 | 0.03 | c0.36 | |
| v/s Ratio Perm | | | | | | | | | 0.12 | | | |
| v/c Ratio | | 0.19 | | 0.68 | 0.04 | | | 0.80 | 0.36 | 0.48 | 0.82 | |
| Uniform Delay, d1 | | 39.3 | | 20.7 | 15.3 | | | 25.0 | 4.1 | 37.0 | 20.0 | |
| Progression Factor | | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | |
| Incremental Delay, d2 | | 1.5 | | 2.4 | 0.0 | | | 7.3 | 0.1 | 1.5 | 6.4 | |
| Delay (s) | | 40.8 | | 23.1 | 15.3 | | | 32.3 | 4.2 | 38.5 | 26.4 | |
| Level of Service | | D | | C | B | | | C | A | D | C | |
| Approach Delay (s) | | 40.8 | | | 22.4 | | | 17.3 | | | 27.3 | |
| Approach LOS | | D | | | C | | | B | | | C | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 21.8 | | | HCM Level of Service | | | | C | | |
| HCM Volume to Capacity ratio | | | 0.74 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 82.5 | | | Sum of lost time (s) | | | 11.0 | | | |
| Intersection Capacity Utilization | | | 79.8% | | | ICU Level of Service | | | | D | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 2: SW Boones Ferry Rd & SW Tualatin Rd

4/15/2013

| Movement | WBL | WBR | NBT | NBR | SBL | SBT |
|-----------------------------------|------|-------|-------|-------|----------------------|------|
| Lane Configurations | | | | | | |
| Volume (vph) | 398 | 810 | 194 | 289 | 430 | 354 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 3.5 | 3.5 | 3.0 | 3.5 | 3.5 | 3.5 |
| Lane Util. Factor | 0.97 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Frbp, ped/bikes | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Flpb, ped/bikes | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Frt | 1.00 | 0.85 | 1.00 | 0.85 | 1.00 | 1.00 |
| Flt Protected | 0.95 | 1.00 | 1.00 | 1.00 | 0.95 | 1.00 |
| Satd. Flow (prot) | 3433 | 1583 | 1881 | 1553 | 1787 | 1881 |
| Flt Permitted | 0.95 | 1.00 | 1.00 | 1.00 | 0.95 | 1.00 |
| Satd. Flow (perm) | 3433 | 1583 | 1881 | 1553 | 1787 | 1881 |
| Peak-hour factor, PHF | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 |
| Adj. Flow (vph) | 415 | 844 | 202 | 301 | 448 | 369 |
| RTOR Reduction (vph) | 0 | 208 | 0 | 84 | 0 | 0 |
| Lane Group Flow (vph) | 415 | 636 | 202 | 217 | 448 | 369 |
| Confl. Peds. (#/hr) | 2 | | | | | |
| Heavy Vehicles (%) | 2% | 2% | 1% | 4% | 1% | 1% |
| Turn Type | | pm+ov | | pm+ov | Prot | |
| Protected Phases | 8 | 1 | 2 | 8 | 1 | 6 |
| Permitted Phases | | 8 | | 2 | | |
| Actuated Green, G (s) | 11.2 | 29.9 | 10.5 | 21.7 | 18.7 | 32.7 |
| Effective Green, g (s) | 11.7 | 30.9 | 11.0 | 22.7 | 19.2 | 33.2 |
| Actuated g/C Ratio | 0.23 | 0.60 | 0.21 | 0.44 | 0.37 | 0.64 |
| Clearance Time (s) | 4.0 | 4.0 | 3.5 | 4.0 | 4.0 | 4.0 |
| Vehicle Extension (s) | 3.0 | 2.0 | 5.0 | 3.0 | 2.0 | 2.0 |
| Lane Grp Cap (vph) | 774 | 1049 | 399 | 679 | 661 | 1203 |
| v/s Ratio Prot | 0.12 | c0.22 | c0.11 | 0.07 | 0.25 | 0.20 |
| v/s Ratio Perm | | 0.18 | | 0.07 | | |
| v/c Ratio | 0.54 | 0.61 | 0.51 | 0.32 | 0.68 | 0.31 |
| Uniform Delay, d1 | 17.7 | 6.6 | 18.1 | 9.6 | 13.7 | 4.2 |
| Progression Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Incremental Delay, d2 | 0.7 | 0.7 | 2.1 | 0.3 | 2.2 | 0.1 |
| Delay (s) | 18.4 | 7.3 | 20.2 | 9.8 | 15.9 | 4.2 |
| Level of Service | B | A | C | A | B | A |
| Approach Delay (s) | 11.0 | | 14.0 | | | 10.7 |
| Approach LOS | B | | B | | | B |
| Intersection Summary | | | | | | |
| HCM Average Control Delay | | | 11.5 | | HCM Level of Service | B |
| HCM Volume to Capacity ratio | | | 0.58 | | | |
| Actuated Cycle Length (s) | | | 51.9 | | Sum of lost time (s) | 6.5 |
| Intersection Capacity Utilization | | | 67.0% | | ICU Level of Service | C |
| Analysis Period (min) | | | 15 | | | |
| c Critical Lane Group | | | | | | |

HCM Signalized Intersection Capacity Analysis

3: SW Boones Fe & SW Martinazzi Ave

4/15/2013



| Movement | EBT | EBR | WBL | WBT | NBL | NBR |
|-----------------------------------|-------|------|-------|------|----------------------|-------|
| Lane Configurations | ↑ | ↗ | ↘ | ↑ | ↘ | ↗ |
| Volume (vph) | 645 | 170 | 410 | 903 | 320 | 380 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 4.5 | 4.5 | 4.5 | 4.5 | 4.5 |
| Lane Util. Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Frbp, ped/bikes | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 0.98 |
| Flpb, ped/bikes | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Frt | 1.00 | 0.85 | 1.00 | 1.00 | 1.00 | 0.85 |
| Flt Protected | 1.00 | 1.00 | 0.95 | 1.00 | 0.95 | 1.00 |
| Satd. Flow (prot) | 1863 | 1599 | 1787 | 1845 | 1770 | 1572 |
| Flt Permitted | 1.00 | 1.00 | 0.95 | 1.00 | 0.95 | 1.00 |
| Satd. Flow (perm) | 1863 | 1599 | 1787 | 1845 | 1770 | 1572 |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 679 | 179 | 432 | 951 | 337 | 400 |
| RTOR Reduction (vph) | 0 | 51 | 0 | 0 | 0 | 41 |
| Lane Group Flow (vph) | 679 | 128 | 432 | 951 | 337 | 359 |
| Confl. Peds. (#/hr) | | 7 | 7 | | 7 | 8 |
| Confl. Bikes (#/hr) | 4 | | 2 | 10 | 1 | |
| Heavy Vehicles (%) | 2% | 1% | 1% | 3% | 2% | 1% |
| Turn Type | | Prot | Prot | | | pm+ov |
| Protected Phases | 2 | 2 | 1 | 6 | 8 | 1 |
| Permitted Phases | | | | | 8 | 8 |
| Actuated Green, G (s) | 41.2 | 41.2 | 29.2 | 75.4 | 21.1 | 50.3 |
| Effective Green, g (s) | 41.7 | 41.7 | 29.7 | 75.9 | 21.6 | 51.3 |
| Actuated g/C Ratio | 0.39 | 0.39 | 0.28 | 0.71 | 0.20 | 0.48 |
| Clearance Time (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 |
| Lane Grp Cap (vph) | 729 | 626 | 498 | 1315 | 359 | 824 |
| v/s Ratio Prot | c0.36 | 0.08 | c0.24 | 0.52 | c0.19 | 0.12 |
| v/s Ratio Perm | | | | | | 0.11 |
| v/c Ratio | 0.93 | 0.20 | 0.87 | 0.72 | 0.94 | 0.44 |
| Uniform Delay, d1 | 31.0 | 21.4 | 36.5 | 9.1 | 41.8 | 18.1 |
| Progression Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Incremental Delay, d2 | 18.6 | 0.2 | 14.7 | 2.0 | 31.7 | 0.4 |
| Delay (s) | 49.6 | 21.6 | 51.3 | 11.1 | 73.5 | 18.5 |
| Level of Service | D | C | D | B | E | B |
| Approach Delay (s) | 43.8 | | | 23.6 | 43.6 | |
| Approach LOS | D | | | C | D | |
| Intersection Summary | | | | | | |
| HCM Average Control Delay | | | 34.4 | | HCM Level of Service | C |
| HCM Volume to Capacity ratio | | | 0.91 | | | |
| Actuated Cycle Length (s) | | | 106.5 | | Sum of lost time (s) | 13.5 |
| Intersection Capacity Utilization | | | 85.6% | | ICU Level of Service | E |
| Analysis Period (min) | | | 15 | | | |

c Critical Lane Group

HCM Unsignalized Intersection Capacity Analysis
 4: Site Entrance 1 & Martinazzi Ave

4/15/2013

| | ↙ | ↖ | ↑ | ↗ | ↘ | ↓ |
|-----------------------------------|------|------|-------|-------|----------------------|------|
| Movement | WBL | WBR | NBT | NBR | SBL | SBT |
| Lane Configurations | ↙ | ↖ | ↗ | | ↘ | ↙ |
| Volume (veh/h) | 30 | 100 | 580 | 60 | 142 | 438 |
| Sign Control | Stop | | Free | | Free | |
| Grade | 0% | | 0% | | 0% | |
| Peak Hour Factor | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 |
| Hourly flow rate (vph) | 33 | 110 | 637 | 66 | 156 | 481 |
| Pedestrians | 25 | | 16 | | 26 | |
| Lane Width (ft) | 12.0 | | 12.0 | | 12.0 | |
| Walking Speed (ft/s) | 4.0 | | 4.0 | | 4.0 | |
| Percent Blockage | 2 | | 1 | | 2 | |
| Right turn flare (veh) | | | | | | |
| Median type | None | | | TWLTL | | |
| Median storage (veh) | 2 | | | | | |
| Upstream signal (ft) | 428 | | | 355 | | |
| pX, platoon unblocked | 0.90 | 0.90 | | | 0.90 | |
| vC, conflicting volume | 1505 | 721 | | | 728 | |
| vC1, stage 1 conf vol | 695 | | | | | |
| vC2, stage 2 conf vol | 809 | | | | | |
| vCu, unblocked vol | 1505 | 630 | | | 638 | |
| tC, single (s) | 6.4 | 6.2 | | | 4.1 | |
| tC, 2 stage (s) | 5.4 | | | | | |
| tF (s) | 3.5 | 3.3 | | | 2.2 | |
| p0 queue free % | 89 | 74 | | | 81 | |
| cM capacity (veh/h) | 292 | 416 | | | 838 | |
| Direction, Lane # | WB 1 | WB 2 | NB 1 | SB 1 | SB 2 | |
| Volume Total | 33 | 110 | 703 | 156 | 481 | |
| Volume Left | 33 | 0 | 0 | 156 | 0 | |
| Volume Right | 0 | 110 | 66 | 0 | 0 | |
| cSH | 292 | 416 | 1700 | 838 | 1700 | |
| Volume to Capacity | 0.11 | 0.26 | 0.41 | 0.19 | 0.28 | |
| Queue Length 95th (ft) | 10 | 27 | 0 | 18 | 0 | |
| Control Delay (s) | 18.9 | 16.7 | 0.0 | 10.3 | 0.0 | |
| Lane LOS | C | C | | B | | |
| Approach Delay (s) | 17.2 | | 0.0 | 2.5 | | |
| Approach LOS | C | | | | | |
| Intersection Summary | | | | | | |
| Average Delay | | | 2.7 | | | |
| Intersection Capacity Utilization | | | 61.4% | | ICU Level of Service | B |
| Analysis Period (min) | | | 15 | | | |

HCM Unsignalized Intersection Capacity Analysis
 5: Seneca St & Martinazzi Ave

4/15/2013



| Movement | EBL | EBR | NBL | NBT | SBT | SBR |
|------------------------|------|------|------|------|------|------|
| Lane Configurations | ↙ | | ↘ | ↑ | ↓ | ↘ |
| Volume (veh/h) | 42 | 80 | 80 | 600 | 418 | 50 |
| Sign Control | Stop | | | Free | Free | |
| Grade | 0% | | | 0% | 0% | |
| Peak Hour Factor | 0.89 | 0.89 | 0.89 | 0.89 | 0.89 | 0.89 |
| Hourly flow rate (vph) | 47 | 90 | 90 | 674 | 470 | 56 |
| Pedestrians | | | | | | |
| Lane Width (ft) | | | | | | |
| Walking Speed (ft/s) | | | | | | |
| Percent Blockage | | | | | | |
| Right turn flare (veh) | | | | | | |
| Median type | | | | None | None | |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | | | 308 | 475 | |
| pX, platoon unblocked | 0.88 | | | | | |
| vC, conflicting volume | 1352 | 498 | 526 | | | |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 1332 | 498 | 526 | | | |
| tC, single (s) | 6.4 | 6.2 | 4.1 | | | |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 3.5 | 3.3 | 2.2 | | | |
| p0 queue free % | 66 | 84 | 91 | | | |
| cM capacity (veh/h) | 139 | 577 | 1051 | | | |

| Direction, Lane # | EB 1 | NB 1 | NB 2 | SB 1 |
|------------------------|------|------|------|------|
| Volume Total | 137 | 90 | 674 | 526 |
| Volume Left | 47 | 90 | 0 | 0 |
| Volume Right | 90 | 0 | 0 | 56 |
| cSH | 276 | 1051 | 1700 | 1700 |
| Volume to Capacity | 0.50 | 0.09 | 0.40 | 0.31 |
| Queue Length 95th (ft) | 67 | 7 | 0 | 0 |
| Control Delay (s) | 30.2 | 8.7 | 0.0 | 0.0 |
| Lane LOS | D | A | | |
| Approach Delay (s) | 30.2 | 1.0 | | 0.0 |
| Approach LOS | D | | | |

| Intersection Summary | | | |
|-----------------------------------|--|-------|------------------------|
| Average Delay | | 3.5 | |
| Intersection Capacity Utilization | | 46.7% | ICU Level of Service A |
| Analysis Period (min) | | 15 | |

HCM Unsignalized Intersection Capacity Analysis
 6: Site Entrance 2 & Martinazzi Ave

4/15/2013



| Movement | WBL | WBR | NBT | NBR | SBL | SBT |
|------------------------|------|------|------|------|------|------|
| Lane Configurations | ↔ | | ↔ | | | ↕↕ |
| Volume (veh/h) | 0 | 32 | 650 | 6 | 10 | 488 |
| Sign Control | Stop | | Free | | | Free |
| Grade | 0% | | 0% | | | 0% |
| Peak Hour Factor | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 |
| Hourly flow rate (vph) | 0 | 35 | 714 | 7 | 11 | 536 |
| Pedestrians | 25 | | 16 | | | 26 |
| Lane Width (ft) | 12.0 | | 12.0 | | | 12.0 |
| Walking Speed (ft/s) | 4.0 | | 4.0 | | | 4.0 |
| Percent Blockage | 2 | | 1 | | | 2 |
| Right turn flare (veh) | | | | | | |
| Median type | | | None | | | None |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | | 227 | | | 556 |
| pX, platoon unblocked | 0.85 | 0.85 | | | 0.85 | |
| vC, conflicting volume | 1049 | 769 | | | 746 | |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 969 | 639 | | | 612 | |
| tC, single (s) | 6.8 | 6.9 | | | 4.1 | |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 3.5 | 3.3 | | | 2.2 | |
| p0 queue free % | 100 | 90 | | | 99 | |
| cM capacity (veh/h) | 206 | 345 | | | 812 | |

| Direction, Lane # | WB 1 | NB 1 | SB 1 | SB 2 |
|------------------------|------|------|------|------|
| Volume Total | 35 | 721 | 190 | 358 |
| Volume Left | 0 | 0 | 11 | 0 |
| Volume Right | 35 | 7 | 0 | 0 |
| cSH | 345 | 1700 | 812 | 1700 |
| Volume to Capacity | 0.10 | 0.42 | 0.01 | 0.21 |
| Queue Length 95th (ft) | 9 | 0 | 1 | 0 |
| Control Delay (s) | 16.6 | 0.0 | 0.7 | 0.0 |
| Lane LOS | C | | A | |
| Approach Delay (s) | 16.6 | 0.0 | 0.2 | |
| Approach LOS | C | | | |

| Intersection Summary | | | |
|-----------------------------------|--|-------|------------------------|
| Average Delay | | 0.5 | |
| Intersection Capacity Utilization | | 50.8% | ICU Level of Service A |
| Analysis Period (min) | | 15 | |

HCM Unsignalized Intersection Capacity Analysis
7: RO Only & Martinazzi Ave


4/15/2013



| Movement | WBL | WBR | NBT | NBR | SBL | SBT |
|-----------------------------------|------|------|-------|----------------------|------|------|
| Lane Configurations | | ↗ | ↑ | | | ↖ |
| Volume (veh/h) | 0 | 12 | 655 | 0 | 0 | 488 |
| Sign Control | Stop | | Free | | | Free |
| Grade | 0% | | 0% | | | 0% |
| Peak Hour Factor | 0.89 | 0.89 | 0.89 | 0.89 | 0.89 | 0.89 |
| Hourly flow rate (vph) | 0 | 13 | 736 | 0 | 0 | 548 |
| Pedestrians | | | | | | |
| Lane Width (ft) | | | | | | |
| Walking Speed (ft/s) | | | | | | |
| Percent Blockage | | | | | | |
| Right turn flare (veh) | | | | | | |
| Median type | None | | | None | | |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | 125 | | | 658 | | |
| pX, platoon unblocked | 0.84 | 0.84 | | | 0.84 | |
| vC, conflicting volume | 1010 | 736 | | | 736 | |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 918 | 592 | | | 592 | |
| tC, single (s) | 6.8 | 6.9 | | | 4.1 | |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 3.5 | 3.3 | | | 2.2 | |
| p0 queue free % | 100 | 96 | | | 100 | |
| cM capacity (veh/h) | 231 | 382 | | | 836 | |
| Direction, Lane # | WB 1 | NB 1 | SB 1 | SB 2 | | |
| Volume Total | 13 | 736 | 274 | 274 | | |
| Volume Left | 0 | 0 | 0 | 0 | | |
| Volume Right | 13 | 0 | 0 | 0 | | |
| cSH | 382 | 1700 | 1700 | 1700 | | |
| Volume to Capacity | 0.04 | 0.43 | 0.16 | 0.16 | | |
| Queue Length 95th (ft) | 3 | 0 | 0 | 0 | | |
| Control Delay (s) | 14.8 | 0.0 | 0.0 | 0.0 | | |
| Lane LOS | B | | | | | |
| Approach Delay (s) | 14.8 | 0.0 | 0.0 | | | |
| Approach LOS | B | | | | | |
| Intersection Summary | | | | | | |
| Average Delay | | | 0.2 | | | |
| Intersection Capacity Utilization | | | 44.5% | ICU Level of Service | A | |
| Analysis Period (min) | | | 15 | | | |

HCM Signalized Intersection Capacity Analysis
 8: Nyberg St & Martinazzi Ave

4/15/2013



| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|------|------|-------|------|------|------|------|-------|------|------|------|
| Lane Configurations | ↶ | ↷ | | ↶ | ↷ | ↶ | ↶ | ↷ | | | ↶↷ | |
| Volume (vph) | 29 | 10 | 101 | 338 | 55 | 327 | 27 | 299 | 19 | 0 | 478 | 10 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 5.5 | 5.5 | | 5.5 | 5.5 | 5.5 | 5.5 | 5.5 | | | 5.5 | |
| Lane Util. Factor | 1.00 | 1.00 | | 0.95 | 0.95 | 1.00 | 1.00 | 1.00 | | | 0.95 | |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 0.96 | 1.00 | 1.00 | | | 1.00 | |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | 1.00 | |
| Frt | 1.00 | 0.86 | | 1.00 | 1.00 | 0.85 | 1.00 | 0.99 | | | 1.00 | |
| Fit Protected | 0.95 | 1.00 | | 0.95 | 0.97 | 1.00 | 0.95 | 1.00 | | | 1.00 | |
| Satd. Flow (prot) | 1805 | 1626 | | 1698 | 1730 | 1526 | 1681 | 1860 | | | 3562 | |
| Fit Permitted | 0.95 | 1.00 | | 0.95 | 0.97 | 1.00 | 0.43 | 1.00 | | | 1.00 | |
| Satd. Flow (perm) | 1805 | 1626 | | 1698 | 1730 | 1526 | 768 | 1860 | | | 3562 | |
| Peak-hour factor, PHF | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 |
| Adj. Flow (vph) | 32 | 11 | 111 | 371 | 60 | 359 | 30 | 329 | 21 | 0 | 525 | 11 |
| RTOR Reduction (vph) | 0 | 98 | 0 | 0 | 0 | 276 | 0 | 3 | 0 | 0 | 2 | 0 |
| Lane Group Flow (vph) | 32 | 24 | 0 | 215 | 216 | 83 | 30 | 347 | 0 | 0 | 534 | 0 |
| Confl. Peds. (#/hr) | 10 | | | | | 10 | 6 | | 19 | 19 | | 6 |
| Confl. Bikes (#/hr) | | | | | | 2 | | | | | | 3 |
| Heavy Vehicles (%) | 0% | 0% | 1% | 1% | 0% | 2% | 7% | 1% | 0% | 0% | 1% | 0% |
| Turn Type | Split | | | Split | | Perm | Perm | | | | | |
| Protected Phases | 8 | 8 | | 4 | 4 | | | 6 | | | | 2 |
| Permitted Phases | | | | | | 4 | 6 | | | | | |
| Actuated Green, G (s) | 4.8 | 4.8 | | 10.4 | 10.4 | 10.4 | 13.8 | 13.8 | | | | 13.8 |
| Effective Green, g (s) | 5.3 | 5.3 | | 10.9 | 10.9 | 10.9 | 14.3 | 14.3 | | | | 14.3 |
| Actuated g/C Ratio | 0.11 | 0.11 | | 0.23 | 0.23 | 0.23 | 0.30 | 0.30 | | | | 0.30 |
| Clearance Time (s) | 6.0 | 6.0 | | 6.0 | 6.0 | 6.0 | 6.0 | 6.0 | | | | 6.0 |
| Vehicle Extension (s) | 2.5 | 2.5 | | 2.5 | 2.5 | 2.5 | 5.0 | 5.0 | | | | 5.0 |
| Lane Grp Cap (vph) | 204 | 183 | | 394 | 401 | 354 | 234 | 566 | | | | 1084 |
| v/s Ratio Prot | c0.02 | 0.01 | | c0.13 | 0.12 | | | | c0.19 | | | 0.15 |
| v/s Ratio Perm | | | | | | 0.05 | 0.04 | | | | | |
| v/c Ratio | 0.16 | 0.13 | | 0.55 | 0.54 | 0.24 | 0.13 | 0.61 | | | | 0.49 |
| Uniform Delay, d1 | 18.8 | 18.8 | | 15.9 | 15.8 | 14.7 | 11.8 | 14.0 | | | | 13.4 |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | | 1.00 |
| Incremental Delay, d2 | 0.3 | 0.2 | | 1.2 | 1.1 | 0.3 | 0.5 | 2.8 | | | | 0.7 |
| Delay (s) | 19.1 | 19.0 | | 17.1 | 16.9 | 14.9 | 12.4 | 16.8 | | | | 14.1 |
| Level of Service | B | B | | B | B | B | B | B | | | | B |
| Approach Delay (s) | | 19.0 | | | 16.1 | | | 16.5 | | | | 14.1 |
| Approach LOS | | B | | | B | | | B | | | | B |

Intersection Summary

| | | | |
|-----------------------------------|-------|----------------------|------|
| HCM Average Control Delay | 15.8 | HCM Level of Service | B |
| HCM Volume to Capacity ratio | 0.51 | | |
| Actuated Cycle Length (s) | 47.0 | Sum of lost time (s) | 16.5 |
| Intersection Capacity Utilization | 58.8% | ICU Level of Service | B |
| Analysis Period (min) | 15 | | |

c Critical Lane Group

HCM Unsignalized Intersection Capacity Analysis
 9: Nyberg St & Site Entrance 3

4/15/2013



| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
|------------------------|------|------|------|------|------|------|
| Lane Configurations | ↵ | | ↕↕ | | | ↵ |
| Volume (veh/h) | 29 | 0 | 639 | 40 | 0 | 82 |
| Sign Control | | Free | Free | | Stop | |
| Grade | | 0% | 0% | | | |
| Peak Hour Factor | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 |
| Hourly flow rate (vph) | 33 | 0 | 726 | 45 | 0 | 93 |
| Pedestrians | | | | | 5 | |
| Lane Width (ft) | | | | | 12.0 | |
| Walking Speed (ft/s) | | | | | 4.0 | |
| Percent Blockage | | | | | 0 | |
| Right turn flare (veh) | | | | | | |
| Median type | | None | None | | | |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | 242 | | | | |
| pX, platoon unblocked | | | | | | |
| vC, conflicting volume | 777 | | | | 820 | 391 |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 777 | | | | 820 | 391 |
| tC, single (s) | 4.1 | | | | 6.8 | 6.9 |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 2.2 | | | | 3.5 | 3.3 |
| p0 queue free % | 96 | | | | 100 | 85 |
| cM capacity (veh/h) | 845 | | | | 304 | 611 |

| Direction, Lane # | EB 1 | WB 1 | WB 2 | SB 1 |
|------------------------|------|------|------|------|
| Volume Total | 33 | 484 | 288 | 93 |
| Volume Left | 33 | 0 | 0 | 0 |
| Volume Right | 0 | 0 | 45 | 93 |
| cSH | 845 | 1700 | 1700 | 611 |
| Volume to Capacity | 0.04 | 0.28 | 0.17 | 0.15 |
| Queue Length 95th (ft) | 3 | 0 | 0 | 14 |
| Control Delay (s) | 9.4 | 0.0 | 0.0 | 11.9 |
| Lane LOS | A | | | B |
| Approach Delay (s) | 9.4 | 0.0 | | 11.9 |
| Approach LOS | | | | B |

| Intersection Summary | | | |
|-----------------------------------|--|-------|------------------------|
| Average Delay | | 1.6 | |
| Intersection Capacity Utilization | | 30.7% | ICU Level of Service A |
| Analysis Period (min) | | 15 | |

HCM Signalized Intersection Capacity Analysis

10: Tualatin Sherwood Rd & Site Entrance 4

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|------|-------|-------|-------|------|----------------------|------|------|-------|------|-------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 32 | 1877 | 42 | 232 | 1691 | 72 | 36 | 10 | 236 | 182 | 24 | 44 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 6.0 | | 4.5 | 6.0 | | | 5.0 | 4.5 | | 5.0 | 5.0 |
| Lane Util. Factor | 1.00 | *0.75 | | 0.97 | 0.91 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 0.97 |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 0.99 | 1.00 | | 1.00 | 1.00 |
| Frt | 1.00 | 1.00 | | 1.00 | 0.99 | | | 1.00 | 0.85 | | 1.00 | 0.85 |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.96 | 1.00 | | 0.96 | 1.00 |
| Satd. Flow (prot) | 1805 | 4099 | | 3502 | 4956 | | | 1768 | 1599 | | 1803 | 1565 |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.54 | 1.00 | | 0.72 | 1.00 |
| Satd. Flow (perm) | 1805 | 4099 | | 3502 | 4956 | | | 1000 | 1599 | | 1350 | 1565 |
| Peak-hour factor, PHF | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 |
| Adj. Flow (vph) | 33 | 1915 | 43 | 237 | 1726 | 73 | 37 | 10 | 241 | 186 | 24 | 45 |
| RTOR Reduction (vph) | 0 | 1 | 0 | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 37 |
| Lane Group Flow (vph) | 33 | 1957 | 0 | 237 | 1796 | 0 | 0 | 47 | 241 | 0 | 210 | 8 |
| Confl. Peds. (#/hr) | | | 2 | | | 8 | 15 | | | | | 15 |
| Confl. Bikes (#/hr) | | | | | 1 | | | 1 | | 1 | | |
| Heavy Vehicles (%) | 0% | 4% | 0% | 0% | 4% | 0% | 3% | 0% | 1% | 1% | 0% | 0% |
| Turn Type | Prot | | | Prot | | | Perm | | pm+ov | Perm | | Perm |
| Protected Phases | 5 | 2 | | 1 | 6 | | | 8 | 1 | | 4 | |
| Permitted Phases | | | | | | | 8 | | 8 | 4 | | 4 |
| Actuated Green, G (s) | 5.4 | 73.7 | | 11.8 | 80.1 | | | 22.5 | 34.3 | | 22.5 | 22.5 |
| Effective Green, g (s) | 5.9 | 74.2 | | 12.3 | 80.6 | | | 23.0 | 35.3 | | 23.0 | 23.0 |
| Actuated g/C Ratio | 0.05 | 0.59 | | 0.10 | 0.64 | | | 0.18 | 0.28 | | 0.18 | 0.18 |
| Clearance Time (s) | 5.0 | 6.5 | | 5.0 | 6.5 | | | 5.5 | 5.0 | | 5.5 | 5.5 |
| Vehicle Extension (s) | 2.5 | 4.0 | | 2.5 | 4.0 | | | 2.5 | 2.5 | | 2.5 | 2.5 |
| Lane Grp Cap (vph) | 85 | 2433 | | 345 | 3196 | | | 184 | 452 | | 248 | 288 |
| v/s Ratio Prot | 0.02 | c0.48 | | c0.07 | 0.36 | | | | 0.05 | | | |
| v/s Ratio Perm | | | | | | | | 0.05 | 0.10 | | c0.16 | 0.01 |
| v/c Ratio | 0.39 | 0.80 | | 0.69 | 0.56 | | | 0.26 | 0.53 | | 0.85 | 0.03 |
| Uniform Delay, d1 | 57.8 | 19.8 | | 54.5 | 12.4 | | | 43.7 | 37.9 | | 49.3 | 41.8 |
| Progression Factor | 0.76 | 0.49 | | 0.99 | 0.98 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Incremental Delay, d2 | 1.2 | 1.6 | | 3.7 | 0.5 | | | 0.5 | 0.9 | | 22.2 | 0.0 |
| Delay (s) | 45.1 | 11.3 | | 57.7 | 12.7 | | | 44.2 | 38.8 | | 71.5 | 41.9 |
| Level of Service | D | B | | E | B | | | D | D | | E | D |
| Approach Delay (s) | | 11.8 | | | 17.9 | | | 39.7 | | | 66.3 | |
| Approach LOS | | B | | | B | | | D | | | E | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 19.3 | | | HCM Level of Service | | | | B | | |
| HCM Volume to Capacity ratio | | | 0.80 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 125.0 | | | Sum of lost time (s) | | | 15.5 | | | |
| Intersection Capacity Utilization | | | 81.1% | | | ICU Level of Service | | | D | | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |

c Critical Lane Group

HCM Unsignalized Intersection Capacity Analysis
 11: Tualatin Sherwood Rd & 75th Ave

4/15/2013















| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
|------------------------|------|------|------|------|------|------|
| Lane Configurations | | ↑↑↑ | ↑↑↑ | | | ↑ |
| Volume (veh/h) | 0 | 2295 | 1995 | 35 | 0 | 4 |
| Sign Control | | Free | Free | | Stop | |
| Grade | | 0% | 0% | | 0% | |
| Peak Hour Factor | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 |
| Hourly flow rate (vph) | 0 | 2318 | 2015 | 35 | 0 | 4 |
| Pedestrians | | | | | 1 | |
| Lane Width (ft) | | | | | 12.0 | |
| Walking Speed (ft/s) | | | | | 4.0 | |
| Percent Blockage | | | | | 0 | |
| Right turn flare (veh) | | | | | | |
| Median type | | None | None | | | |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | 373 | 260 | | | |
| pX, platoon unblocked | 0.81 | | | | 0.75 | 0.81 |
| vC, conflicting volume | 2052 | | | | 2807 | 690 |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 1465 | | | | 477 | 0 |
| tC, single (s) | 4.1 | | | | 6.8 | 7.0 |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 2.2 | | | | 3.5 | 3.3 |
| p0 queue free % | 100 | | | | 100 | 100 |
| cM capacity (veh/h) | 376 | | | | 385 | 872 |

| Direction, Lane # | EB 1 | EB 2 | EB 3 | WB 1 | WB 2 | WB 3 | SB 1 |
|------------------------|------|------|------|------|------|------|------|
| Volume Total | 773 | 773 | 773 | 806 | 806 | 438 | 4 |
| Volume Left | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Volume Right | 0 | 0 | 0 | 0 | 0 | 35 | 4 |
| cSH | 1700 | 1700 | 1700 | 1700 | 1700 | 1700 | 872 |
| Volume to Capacity | 0.45 | 0.45 | 0.45 | 0.47 | 0.47 | 0.26 | 0.00 |
| Queue Length 95th (ft) | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Control Delay (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 9.1 |
| Lane LOS | | | | | | | A |
| Approach Delay (s) | 0.0 | | | 0.0 | | | 9.1 |
| Approach LOS | | | | | | | A |

| Intersection Summary | | | |
|-----------------------------------|--|-------|------------------------|
| Average Delay | | 0.0 | |
| Intersection Capacity Utilization | | 49.3% | ICU Level of Service A |
| Analysis Period (min) | | 15 | |

HCM Signalized Intersection Capacity Analysis
 12: Tualatin Sherwood Rd & I-5 SB Ramps

4/15/2013

| |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | | ↑↑↑ | ↑ | ↑ | ↑↑ | | | | | ↑ | ↑ | ↑↑ |
| Volume (vph) | 0 | 1480 | 815 | 119 | 984 | 0 | 0 | 0 | 0 | 640 | 5 | 1045 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | | 5.5 | 5.5 | 5.5 | 5.5 | | | | | 5.5 | 5.5 | 5.5 |
| Lane Util. Factor | | *0.75 | 1.00 | 1.00 | 0.95 | | | | | 0.95 | 0.95 | 0.88 |
| Frbp, ped/bikes | | 1.00 | 1.00 | 1.00 | 1.00 | | | | | 1.00 | 1.00 | 1.00 |
| Flpb, ped/bikes | | 1.00 | 1.00 | 1.00 | 1.00 | | | | | 1.00 | 1.00 | 1.00 |
| Frt | | 1.00 | 0.85 | 1.00 | 1.00 | | | | | 1.00 | 1.00 | 0.85 |
| Flt Protected | | 1.00 | 1.00 | 0.95 | 1.00 | | | | | 0.95 | 0.95 | 1.00 |
| Satd. Flow (prot) | | 4150 | 1568 | 1787 | 3471 | | | | | 1681 | 1682 | 2760 |
| Flt Permitted | | 1.00 | 1.00 | 0.95 | 1.00 | | | | | 0.95 | 0.95 | 1.00 |
| Satd. Flow (perm) | | 4150 | 1568 | 1787 | 3471 | | | | | 1681 | 1682 | 2760 |
| Peak-hour factor, PHF | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 |
| Adj. Flow (vph) | 0 | 1495 | 823 | 120 | 994 | 0 | 0 | 0 | 0 | 646 | 5 | 1056 |
| RTOR Reduction (vph) | 0 | 0 | 346 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 32 |
| Lane Group Flow (vph) | 0 | 1495 | 477 | 120 | 994 | 0 | 0 | 0 | 0 | 323 | 328 | 1024 |
| Confl. Bikes (#/hr) | | 1 | | | 2 | | | | | | | |
| Heavy Vehicles (%) | 0% | 3% | 3% | 1% | 4% | 0% | 0% | 0% | 0% | 2% | 20% | 3% |
| Turn Type | | | Perm | Prot | | | | | | Split | | custom |
| Protected Phases | | 2 | | 1 | 6 | | | | | 4 | 4 | 4.5 |
| Permitted Phases | | | 2 | | | | | | | | | |
| Actuated Green, G (s) | | 58.8 | 58.8 | 11.0 | 53.8 | | | | | 37.2 | 37.2 | 59.2 |
| Effective Green, g (s) | | 59.3 | 59.3 | 11.5 | 54.3 | | | | | 37.7 | 37.7 | 59.7 |
| Actuated g/C Ratio | | 0.47 | 0.47 | 0.09 | 0.43 | | | | | 0.30 | 0.30 | 0.48 |
| Clearance Time (s) | | 6.0 | 6.0 | 6.0 | 6.0 | | | | | 6.0 | 6.0 | |
| Vehicle Extension (s) | | 6.1 | 6.1 | 2.3 | 6.1 | | | | | 2.3 | 2.3 | |
| Lane Grp Cap (vph) | | 1969 | 744 | 164 | 1508 | | | | | 507 | 507 | 1318 |
| v/s Ratio Prot | | c0.36 | | 0.07 | c0.29 | | | | | 0.19 | 0.20 | c0.37 |
| v/s Ratio Perm | | | 0.30 | | | | | | | | | |
| v/c Ratio | | 0.76 | 0.64 | 0.73 | 0.66 | | | | | 0.64 | 0.65 | 0.78 |
| Uniform Delay, d1 | | 27.0 | 24.8 | 55.2 | 28.0 | | | | | 37.7 | 37.9 | 27.1 |
| Progression Factor | | 0.71 | 0.50 | 1.26 | 0.62 | | | | | 1.00 | 1.00 | 1.00 |
| Incremental Delay, d2 | | 1.8 | 2.7 | 13.5 | 2.2 | | | | | 2.2 | 2.4 | 2.8 |
| Delay (s) | | 21.0 | 15.1 | 83.2 | 19.5 | | | | | 39.9 | 40.2 | 29.9 |
| Level of Service | | C | B | F | B | | | | | D | D | C |
| Approach Delay (s) | | 18.9 | | | 26.3 | | | 0.0 | | | 33.8 | |
| Approach LOS | | B | | | C | | | A | | | C | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 25.4 | | | HCM Level of Service | | | | | C | |
| HCM Volume to Capacity ratio | | | 0.80 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 125.0 | | | Sum of lost time (s) | | 16.5 | | | | |
| Intersection Capacity Utilization | | | 88.7% | | | ICU Level of Service | | E | | | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis

13: Tualatin Sherwood Rd & I-5 NB Ramps

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|------|-------|------|------|----------------------|------|-------|------|-------|------|------|------|
| Lane Configurations | | ↑↑ | ↑↑ | | ↑↑ | ↑ | ↑ | ↑ | ↑ | | | |
| Volume (vph) | 0 | 1161 | 952 | 0 | 488 | 662 | 615 | 5 | 172 | 0 | 0 | 0 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | | 5.5 | 5.5 | | 6.0 | 6.0 | 5.5 | 5.5 | 5.5 | | | |
| Lane Util. Factor | | 0.95 | 0.88 | | 0.95 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Frbp, ped/bikes | | 1.00 | 1.00 | | 1.00 | 0.95 | 1.00 | 1.00 | 0.96 | | | |
| Flpb, ped/bikes | | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Frt | | 1.00 | 0.85 | | 1.00 | 0.85 | 1.00 | 1.00 | 0.85 | | | |
| Flt Protected | | 1.00 | 1.00 | | 1.00 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Satd. Flow (prot) | | 3574 | 2760 | | 3574 | 1502 | 1618 | 1620 | 1512 | | | |
| Flt Permitted | | 1.00 | 1.00 | | 1.00 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Satd. Flow (perm) | | 3574 | 2760 | | 3574 | 1502 | 1618 | 1620 | 1512 | | | |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 0 | 1222 | 1002 | 0 | 514 | 697 | 647 | 5 | 181 | 0 | 0 | 0 |
| RTOR Reduction (vph) | 0 | 0 | 320 | 0 | 0 | 240 | 0 | 0 | 25 | 0 | 0 | 0 |
| Lane Group Flow (vph) | 0 | 1222 | 682 | 0 | 514 | 457 | 323 | 329 | 156 | 0 | 0 | 0 |
| Confl. Peds. (#/hr) | | | | | | 16 | | | 17 | | | |
| Confl. Bikes (#/hr) | | 1 | | | 5 | | | | | 1 | | |
| Heavy Vehicles (%) | 0% | 1% | 3% | 0% | 1% | 2% | 6% | 20% | 2% | 0% | 0% | 0% |
| Turn Type | | Perm | | | Perm | | Split | | Perm | | | |
| Protected Phases | | 2 | | | 6 | | 8 | | 8 | | | |
| Permitted Phases | | 2 | | | 6 | | | | 8 | | | |
| Actuated Green, G (s) | | 82.0 | 82.0 | | 81.5 | 81.5 | 31.0 | 31.0 | 31.0 | | | |
| Effective Green, g (s) | | 82.5 | 82.5 | | 82.0 | 82.0 | 31.5 | 31.5 | 31.5 | | | |
| Actuated g/C Ratio | | 0.66 | 0.66 | | 0.66 | 0.66 | 0.25 | 0.25 | 0.25 | | | |
| Clearance Time (s) | | 6.0 | 6.0 | | 6.5 | 6.5 | 6.0 | 6.0 | 6.0 | | | |
| Vehicle Extension (s) | | 6.1 | 6.1 | | 4.2 | 4.2 | 2.3 | 2.3 | 2.3 | | | |
| Lane Grp Cap (vph) | | 2359 | 1822 | | 2345 | 985 | 408 | 408 | 381 | | | |
| v/s Ratio Prot | | c0.34 | | | 0.14 | | 0.20 | | c0.20 | | | |
| v/s Ratio Perm | | 0.25 | | | 0.30 | | | | 0.10 | | | |
| v/c Ratio | | 0.52 | 0.37 | | 0.22 | 0.46 | 0.79 | 0.81 | 0.41 | | | |
| Uniform Delay, d1 | | 11.0 | 9.6 | | 8.6 | 10.6 | 43.7 | 43.9 | 39.0 | | | |
| Progression Factor | | 0.45 | 0.24 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Incremental Delay, d2 | | 0.6 | 0.4 | | 0.2 | 1.6 | 9.6 | 10.7 | 0.4 | | | |
| Delay (s) | | 5.5 | 2.8 | | 8.9 | 12.2 | 53.3 | 54.6 | 39.4 | | | |
| Level of Service | | A | A | | A | B | D | D | D | | | |
| Approach Delay (s) | | 4.3 | | | 10.8 | | | 50.8 | | | 0.0 | |
| Approach LOS | | A | | | B | | | D | | | A | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | 15.2 | | | HCM Level of Service | | | | B | | | |
| HCM Volume to Capacity ratio | | 0.60 | | | | | | | | | | |
| Actuated Cycle Length (s) | | 125.0 | | | Sum of lost time (s) | | | | 11.0 | | | |
| Intersection Capacity Utilization | | 69.3% | | | ICU Level of Service | | | | C | | | |
| Analysis Period (min) | | 15 | | | | | | | | | | |

c Critical Lane Group

HCM Signalized Intersection Capacity Analysis
 14: Tualatin Sherwood Rd & Nyberg Woods

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|-------|-------|-------|------|-------|----------------------|------|-------|------|------|------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 290 | 952 | 61 | 10 | 789 | 80 | 112 | 7 | 17 | 81 | 5 | 191 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 5.5 | 5.5 | | 5.5 | 5.5 | | | 5.5 | 5.5 | | 5.5 | 5.5 |
| Lane Util. Factor | 0.97 | 0.95 | | 1.00 | 0.95 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 0.98 | | 1.00 | 0.99 |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frt | 1.00 | 0.99 | | 1.00 | 0.99 | | | 1.00 | 0.85 | | 1.00 | 0.85 |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.95 | 1.00 | | 0.95 | 1.00 |
| Satd. Flow (prot) | 3502 | 3502 | | 1805 | 3522 | | | 1761 | 1590 | | 1793 | 1592 |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.67 | 1.00 | | 0.65 | 1.00 |
| Satd. Flow (perm) | 3502 | 3502 | | 1805 | 3522 | | | 1243 | 1590 | | 1221 | 1592 |
| Peak-hour factor, PHF | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 |
| Adj. Flow (vph) | 302 | 992 | 64 | 10 | 822 | 83 | 117 | 7 | 18 | 84 | 5 | 199 |
| RTOR Reduction (vph) | 0 | 4 | 0 | 0 | 7 | 0 | 0 | 0 | 15 | 0 | 0 | 164 |
| Lane Group Flow (vph) | 302 | 1052 | 0 | 10 | 898 | 0 | 0 | 124 | 3 | 0 | 89 | 35 |
| Confl. Peds. (#/hr) | 9 | | 2 | 2 | | 9 | 3 | | 4 | 4 | | 3 |
| Confl. Bikes (#/hr) | | 1 | | | 3 | | | | | | | |
| Heavy Vehicles (%) | 0% | 2% | 2% | 0% | 1% | 0% | 3% | 0% | 0% | 1% | 0% | 0% |
| Turn Type | Prot | | | Prot | | | Perm | | Perm | Perm | | Perm |
| Protected Phases | 5 | 2 | | 1 | 6 | | | 8 | | | 4 | |
| Permitted Phases | | | | | | | 8 | | 8 | 4 | | 4 |
| Actuated Green, G (s) | 8.9 | 32.0 | | 0.7 | 23.8 | | | 10.2 | 10.2 | | 10.2 | 10.2 |
| Effective Green, g (s) | 9.4 | 32.5 | | 1.2 | 24.3 | | | 10.7 | 10.7 | | 10.7 | 10.7 |
| Actuated g/C Ratio | 0.15 | 0.53 | | 0.02 | 0.40 | | | 0.18 | 0.18 | | 0.18 | 0.18 |
| Clearance Time (s) | 6.0 | 6.0 | | 6.0 | 6.0 | | | 6.0 | 6.0 | | 6.0 | 6.0 |
| Vehicle Extension (s) | 2.3 | 2.5 | | 2.4 | 2.5 | | | 2.4 | 2.4 | | 2.3 | 2.3 |
| Lane Grp Cap (vph) | 541 | 1869 | | 36 | 1405 | | | 218 | 279 | | 215 | 280 |
| v/s Ratio Prot | c0.09 | c0.30 | | 0.01 | c0.25 | | | | | | | |
| v/s Ratio Perm | | | | | | | | c0.10 | 0.00 | | 0.07 | 0.02 |
| v/c Ratio | 0.56 | 0.56 | | 0.28 | 0.64 | | | 0.57 | 0.01 | | 0.41 | 0.12 |
| Uniform Delay, d1 | 23.8 | 9.5 | | 29.4 | 14.8 | | | 23.0 | 20.7 | | 22.3 | 21.2 |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Incremental Delay, d2 | 0.9 | 0.3 | | 2.7 | 0.8 | | | 2.6 | 0.0 | | 0.8 | 0.1 |
| Delay (s) | 24.7 | 9.8 | | 32.2 | 15.6 | | | 25.6 | 20.7 | | 23.1 | 21.3 |
| Level of Service | C | A | | C | B | | | C | C | | C | C |
| Approach Delay (s) | | 13.1 | | | 15.8 | | | 25.0 | | | 21.8 | |
| Approach LOS | | B | | | B | | | C | | | C | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 15.6 | | | HCM Level of Service | | | | B | | |
| HCM Volume to Capacity ratio | | | 0.70 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 60.9 | | | Sum of lost time (s) | | | 22.0 | | | |
| Intersection Capacity Utilization | | | 60.3% | | | ICU Level of Service | | | B | | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |

c Critical Lane Group























HCM Signalized Intersection Capacity Analysis
 15: SW Nyberg St & SW Nyberg St

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|-------|-------|-------|------|------|------|-------|-------|------|------|-------|------------------------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 217 | 900 | 26 | 24 | 737 | 16 | 17 | 9 | 45 | 5 | 7 | 135 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.8 | 4.8 | | 4.8 | 4.8 | | | 5.6 | 5.6 | | 5.3 | 4.8 |
| Lane Util. Factor | 1.00 | 1.00 | | 1.00 | 0.95 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frt | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 0.85 | | 1.00 | 0.85 |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.97 | 1.00 | | 0.98 | 1.00 |
| Satd. Flow (prot) | 1805 | 1867 | | 1805 | 3563 | | | 1762 | 1583 | | 1861 | 1607 |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.97 | 1.00 | | 0.69 | 1.00 |
| Satd. Flow (perm) | 1805 | 1867 | | 1805 | 3563 | | | 1762 | 1583 | | 1313 | 1607 |
| Peak-hour factor, PHF | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 |
| Adj. Flow (vph) | 231 | 957 | 28 | 26 | 784 | 17 | 18 | 10 | 48 | 5 | 7 | 144 |
| RTOR Reduction (vph) | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 45 | 0 | 0 | 115 |
| Lane Group Flow (vph) | 231 | 985 | 0 | 26 | 800 | 0 | 0 | 28 | 3 | 0 | 12 | 29 |
| Confl. Peds. (#/hr) | | | 30 | 30 | | | 6 | | | | | 6 |
| Heavy Vehicles (%) | 0% | 1% | 5% | 0% | 1% | 1% | 7% | 0% | 2% | 0% | 0% | 0% |
| Turn Type | Prot | | | Prot | | | Split | | Perm | Perm | | pm+ov |
| Protected Phases | 5 | 2 | | 1 | 6 | | 8 | 8 | | | 4 | 5 |
| Permitted Phases | | | | | | | | | 8 | 4 | | 4 |
| Actuated Green, G (s) | 11.6 | 48.9 | | 1.7 | 39.0 | | | 4.1 | 4.1 | | 3.6 | 15.2 |
| Effective Green, g (s) | 12.1 | 49.4 | | 2.2 | 39.5 | | | 4.6 | 4.6 | | 4.1 | 16.2 |
| Actuated g/C Ratio | 0.15 | 0.61 | | 0.03 | 0.49 | | | 0.06 | 0.06 | | 0.05 | 0.20 |
| Clearance Time (s) | 5.3 | 5.3 | | 5.3 | 5.3 | | | 6.1 | 6.1 | | 5.8 | 5.3 |
| Vehicle Extension (s) | 2.5 | 3.0 | | 1.0 | 3.0 | | | 1.0 | 1.0 | | 2.0 | 2.5 |
| Lane Grp Cap (vph) | 270 | 1141 | | 49 | 1742 | | | 100 | 90 | | 67 | 322 |
| v/s Ratio Prot | c0.13 | c0.53 | | 0.01 | 0.22 | | | c0.02 | | | | 0.01 |
| v/s Ratio Perm | | | | | | | | | 0.00 | | c0.01 | 0.00 |
| v/c Ratio | 0.86 | 0.86 | | 0.53 | 0.46 | | | 0.28 | 0.03 | | 0.18 | 0.09 |
| Uniform Delay, d1 | 33.5 | 12.9 | | 38.8 | 13.6 | | | 36.5 | 36.0 | | 36.7 | 26.3 |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Incremental Delay, d2 | 22.1 | 6.9 | | 5.4 | 0.2 | | | 0.6 | 0.1 | | 0.5 | 0.1 |
| Delay (s) | 55.6 | 19.8 | | 44.2 | 13.8 | | | 37.1 | 36.0 | | 37.2 | 26.4 |
| Level of Service | E | B | | D | B | | | D | D | | D | C |
| Approach Delay (s) | | 26.6 | | | 14.8 | | | 36.4 | | | 27.2 | |
| Approach LOS | | C | | | B | | | D | | | C | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 22.7 | | | | | | | | | HCM Level of Service C |
| HCM Volume to Capacity ratio | | | 0.75 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 80.8 | | | | | | | 15.7 | | |
| Intersection Capacity Utilization | | | 73.9% | | | | | | | | | ICU Level of Service D |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 16: SW Tualatin Sherwood Rd & SW Boones Ferry Rd

4/15/2013

| |  |  |  |  |  |  |  |  |  |  |  |  | | |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|----------------------|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR | | |
| Lane Configurations |  |  | |  |  | |  |  |  |  |  |  | | |
| Volume (vph) | 100 | 984 | 134 | 217 | 1051 | 54 | 166 | 260 | 154 | 288 | 335 | 129 | | |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | | |
| Total Lost time (s) | 4.5 | 5.5 | | 4.5 | 5.5 | | 4.5 | 5.0 | 4.5 | 4.5 | 5.0 | | | |
| Lane Util. Factor | 1.00 | 0.95 | | 0.97 | 0.95 | | 1.00 | 1.00 | 1.00 | 1.00 | 0.95 | | | |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | 0.98 | 1.00 | 0.99 | | | |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Frt | 1.00 | 0.98 | | 1.00 | 0.99 | | 1.00 | 1.00 | 0.85 | 1.00 | 0.96 | | | |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | 0.95 | 1.00 | 1.00 | 0.95 | 1.00 | | | |
| Satd. Flow (prot) | 1703 | 3319 | | 3502 | 3338 | | 1732 | 1810 | 1542 | 1761 | 3313 | | | |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | | 0.42 | 1.00 | 1.00 | 0.60 | 1.00 | | | |
| Satd. Flow (perm) | 1703 | 3319 | | 3502 | 3338 | | 760 | 1810 | 1542 | 1107 | 3313 | | | |
| Peak-hour factor, PHF | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | | |
| Adj. Flow (vph) | 101 | 994 | 135 | 219 | 1062 | 55 | 168 | 263 | 156 | 291 | 338 | 130 | | |
| RTOR Reduction (vph) | 0 | 8 | 0 | 0 | 3 | 0 | 0 | 0 | 59 | 0 | 35 | 0 | | |
| Lane Group Flow (vph) | 101 | 1121 | 0 | 219 | 1114 | 0 | 168 | 263 | 97 | 291 | 433 | 0 | | |
| Confl. Peds. (#/hr) | | | 7 | | | 15 | 7 | | 8 | 8 | | 7 | | |
| Heavy Vehicles (%) | 6% | 7% | 3% | 0% | 7% | 6% | 4% | 5% | 3% | 2% | 4% | 3% | | |
| Turn Type | Prot | | | Prot | | | pm+pt | | pm+ov | pm+pt | | | | |
| Protected Phases | 5 | 2 | | 1 | 6 | | 3 | 8 | 1 | 7 | 4 | | | |
| Permitted Phases | | | | | | | 8 | | 8 | 4 | | | | |
| Actuated Green, G (s) | 10.0 | 56.7 | | 9.4 | 56.1 | | 20.9 | 20.9 | 30.3 | 26.6 | 26.1 | | | |
| Effective Green, g (s) | 10.5 | 57.2 | | 9.9 | 56.6 | | 21.4 | 21.4 | 31.3 | 27.1 | 26.6 | | | |
| Actuated g/C Ratio | 0.08 | 0.46 | | 0.08 | 0.45 | | 0.17 | 0.17 | 0.25 | 0.22 | 0.21 | | | |
| Clearance Time (s) | 5.0 | 6.0 | | 5.0 | 6.0 | | 5.0 | 5.5 | 5.0 | 5.0 | 5.5 | | | |
| Vehicle Extension (s) | 2.0 | 3.5 | | 2.0 | 3.5 | | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | | | |
| Lane Grp Cap (vph) | 143 | 1519 | | 277 | 1511 | | 222 | 310 | 386 | 329 | 705 | | | |
| v/s Ratio Prot | 0.06 | c0.34 | | 0.06 | c0.33 | | 0.07 | c0.15 | 0.02 | c0.12 | 0.13 | | | |
| v/s Ratio Perm | | | | | | | 0.06 | | 0.04 | c0.07 | | | | |
| v/c Ratio | 0.71 | 0.74 | | 0.79 | 0.74 | | 0.76 | 0.85 | 0.25 | 0.88 | 0.61 | | | |
| Uniform Delay, d1 | 55.7 | 27.8 | | 56.5 | 28.1 | | 47.7 | 50.2 | 37.5 | 46.2 | 44.6 | | | |
| Progression Factor | 1.00 | 1.00 | | 0.99 | 0.45 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Incremental Delay, d2 | 12.2 | 3.3 | | 9.0 | 2.1 | | 12.3 | 18.3 | 0.1 | 22.8 | 1.1 | | | |
| Delay (s) | 67.9 | 31.0 | | 64.9 | 14.7 | | 59.9 | 68.5 | 37.6 | 69.0 | 45.7 | | | |
| Level of Service | E | C | | E | B | | E | E | D | E | D | | | |
| Approach Delay (s) | | 34.1 | | | 22.9 | | | 57.8 | | | 54.6 | | | |
| Approach LOS | | C | | | C | | | E | | | D | | | |
| Intersection Summary | | | | | | | | | | | | | | |
| HCM Average Control Delay | | 37.8 | | | | | | | | | | HCM Level of Service | D | |
| HCM Volume to Capacity ratio | | 0.82 | | | | | | | | | | | | |
| Actuated Cycle Length (s) | | 125.0 | | | | | | | 20.5 | | | | Sum of lost time (s) | |
| Intersection Capacity Utilization | | 85.3% | | | | | | | | | | | ICU Level of Service | E |
| Analysis Period (min) | | 15 | | | | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | | | |













HCM Signalized Intersection Capacity Analysis
 17: Tualatin Sherwood Rd & Martinazzi Ave

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|------|-------|------|------|----------------------|------|------|------|-------|------|-------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 50 | 1440 | 81 | 0 | 1091 | 1 | 92 | 293 | 314 | 188 | 643 | 85 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 5.5 | | | 5.5 | | 4.5 | 5.5 | 5.5 | 4.5 | 5.5 | |
| Lane Util. Factor | 1.00 | *0.95 | | | 0.95 | | 1.00 | 1.00 | 1.00 | 1.00 | 0.95 | |
| Frbp, ped/bikes | 1.00 | 1.00 | | | 1.00 | | 1.00 | 1.00 | 0.98 | 1.00 | 1.00 | |
| Flpb, ped/bikes | 1.00 | 1.00 | | | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | |
| Frt | 1.00 | 0.99 | | | 1.00 | | 1.00 | 1.00 | 0.85 | 1.00 | 0.98 | |
| Flt Protected | 0.95 | 1.00 | | | 1.00 | | 0.95 | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (prot) | 1719 | 3447 | | | 3438 | | 1770 | 1863 | 1574 | 1787 | 3498 | |
| Flt Permitted | 0.95 | 1.00 | | | 1.00 | | 0.95 | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (perm) | 1719 | 3447 | | | 3438 | | 1770 | 1863 | 1574 | 1787 | 3498 | |
| Peak-hour factor, PHF | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 |
| Adj. Flow (vph) | 53 | 1532 | 86 | 0 | 1161 | 1 | 98 | 312 | 334 | 200 | 684 | 90 |
| RTOR Reduction (vph) | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 50 | 0 | 8 | 0 |
| Lane Group Flow (vph) | 53 | 1615 | 0 | 0 | 1162 | 0 | 98 | 312 | 284 | 200 | 766 | 0 |
| Confl. Peds. (#/hr) | | | 4 | | | 2 | | | 3 | | | 16 |
| Heavy Vehicles (%) | 5% | 4% | 0% | 0% | 5% | 0% | 2% | 2% | 1% | 1% | 1% | 1% |
| Turn Type | Prot | | | | | | Prot | | Perm | | Prot | |
| Protected Phases | 5 | 2 | | | 6 | | 3 | 8 | | 7 | 4 | |
| Permitted Phases | | | | | | | | | 8 | | | |
| Actuated Green, G (s) | 8.0 | 67.7 | | | 54.7 | | 9.0 | 23.5 | 23.5 | 16.8 | 31.3 | |
| Effective Green, g (s) | 8.5 | 68.2 | | | 55.2 | | 9.5 | 24.0 | 24.0 | 17.3 | 31.8 | |
| Actuated g/C Ratio | 0.07 | 0.55 | | | 0.44 | | 0.08 | 0.19 | 0.19 | 0.14 | 0.25 | |
| Clearance Time (s) | 5.0 | 6.0 | | | 6.0 | | 5.0 | 6.0 | 6.0 | 5.0 | 6.0 | |
| Vehicle Extension (s) | 2.0 | 3.5 | | | 3.5 | | 3.0 | 2.0 | 2.0 | 3.0 | 2.0 | |
| Lane Grp Cap (vph) | 117 | 1881 | | | 1518 | | 135 | 358 | 302 | 247 | 890 | |
| v/s Ratio Prot | 0.03 | c0.47 | | | 0.34 | | 0.06 | 0.17 | | 0.11 | c0.22 | |
| v/s Ratio Perm | | | | | | | | | c0.18 | | | |
| v/c Ratio | 0.45 | 0.86 | | | 0.77 | | 0.73 | 0.87 | 0.94 | 0.81 | 0.86 | |
| Uniform Delay, d1 | 56.0 | 24.3 | | | 29.4 | | 56.5 | 49.0 | 49.8 | 52.3 | 44.5 | |
| Progression Factor | 0.84 | 1.11 | | | 0.64 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | |
| Incremental Delay, d2 | 0.8 | 4.3 | | | 3.3 | | 17.6 | 19.5 | 35.8 | 17.5 | 8.2 | |
| Delay (s) | 47.6 | 31.1 | | | 22.0 | | 74.0 | 68.5 | 85.6 | 69.8 | 52.7 | |
| Level of Service | D | C | | | C | | E | E | F | E | D | |
| Approach Delay (s) | | 31.7 | | | 22.0 | | | 76.9 | | | 56.2 | |
| Approach LOS | | C | | | C | | | E | | | E | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | 41.8 | | | HCM Level of Service | | | | D | | | |
| HCM Volume to Capacity ratio | | 0.85 | | | | | | | | | | |
| Actuated Cycle Length (s) | | 125.0 | | | Sum of lost time (s) | | | | 11.0 | | | |
| Intersection Capacity Utilization | | 85.9% | | | ICU Level of Service | | | | E | | | |
| Analysis Period (min) | | 15 | | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |






















HCM Signalized Intersection Capacity Analysis
 18: SW Borland Rd & SW 65th Ave

4/15/2013

| |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | | ↔ | | | ↕ | ↗ | ↘ | ↕ | | ↘ | ↕ | |
| Volume (vph) | 23 | 23 | 10 | 233 | 0 | 227 | 2 | 324 | 349 | 411 | 460 | 10 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | | 5.6 | | | 5.3 | 5.6 | 4.8 | 4.8 | | 4.8 | 4.8 | |
| Lane Util. Factor | | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Frbp, ped/bikes | | 0.98 | | | 1.00 | 1.00 | 1.00 | 0.98 | | 1.00 | 1.00 | |
| Flpb, ped/bikes | | 1.00 | | | 1.00 | 1.00 | 0.99 | 1.00 | | 1.00 | 1.00 | |
| Frt | | 0.97 | | | 1.00 | 0.85 | 1.00 | 0.92 | | 1.00 | 1.00 | |
| Flt Protected | | 0.98 | | | 0.95 | 1.00 | 0.95 | 1.00 | | 0.95 | 1.00 | |
| Satd. Flow (prot) | | 1775 | | | 1787 | 1583 | 1794 | 1686 | | 1805 | 1838 | |
| Flt Permitted | | 0.98 | | | 0.95 | 1.00 | 0.48 | 1.00 | | 0.10 | 1.00 | |
| Satd. Flow (perm) | | 1775 | | | 1787 | 1583 | 911 | 1686 | | 189 | 1838 | |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 24 | 24 | 11 | 245 | 0 | 239 | 2 | 341 | 367 | 433 | 484 | 11 |
| RTOR Reduction (vph) | 0 | 6 | 0 | 0 | 0 | 226 | 0 | 25 | 0 | 0 | 0 | 0 |
| Lane Group Flow (vph) | 0 | 53 | 0 | 0 | 245 | 13 | 2 | 683 | 0 | 433 | 495 | 0 |
| Confl. Peds. (#/hr) | | | 11 | 11 | | | 7 | | 7 | 7 | | 7 |
| Heavy Vehicles (%) | 0% | 0% | 0% | 1% | 0% | 2% | 0% | 1% | 2% | 0% | 3% | 0% |
| Turn Type | Split | | | Split | | custom | pm+pt | | | pm+pt | | |
| Protected Phases | 8 | 8 | | 4 | 4 | | 1 | 6 | | 5 | 2 | |
| Permitted Phases | | | | | | 8 | 6 | | | 2 | | |
| Actuated Green, G (s) | | 7.4 | | | 20.0 | 7.4 | 64.4 | 63.4 | | 98.7 | 92.4 | |
| Effective Green, g (s) | | 7.9 | | | 20.5 | 7.9 | 65.4 | 63.9 | | 99.2 | 92.9 | |
| Actuated g/C Ratio | | 0.06 | | | 0.14 | 0.06 | 0.46 | 0.45 | | 0.69 | 0.65 | |
| Clearance Time (s) | | 6.1 | | | 5.8 | 6.1 | 5.3 | 5.3 | | 5.3 | 5.3 | |
| Vehicle Extension (s) | | 1.0 | | | 2.0 | 1.0 | 1.0 | 3.0 | | 2.5 | 0.2 | |
| Lane Grp Cap (vph) | | 98 | | | 256 | 87 | 425 | 752 | | 475 | 1192 | |
| v/s Ratio Prot | | c0.03 | | | c0.14 | | 0.00 | 0.41 | | c0.19 | 0.27 | |
| v/s Ratio Perm | | | | | | 0.01 | 0.00 | | | c0.44 | | |
| v/c Ratio | | 0.54 | | | 0.96 | 0.15 | 0.00 | 0.91 | | 0.91 | 0.41 | |
| Uniform Delay, d1 | | 65.9 | | | 61.0 | 64.5 | 21.2 | 37.0 | | 41.0 | 12.1 | |
| Progression Factor | | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Incremental Delay, d2 | | 3.3 | | | 43.7 | 0.3 | 0.0 | 14.7 | | 21.7 | 0.1 | |
| Delay (s) | | 69.2 | | | 104.7 | 64.8 | 21.2 | 51.7 | | 62.6 | 12.2 | |
| Level of Service | | E | | | F | E | C | D | | E | B | |
| Approach Delay (s) | | 69.2 | | | 85.0 | | | 51.6 | | | 35.7 | |
| Approach LOS | | E | | | F | | | D | | | D | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 52.7 | | | | HCM Level of Service | | | D | | |
| HCM Volume to Capacity ratio | | | 0.88 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 143.3 | | | | Sum of lost time (s) | | 15.7 | | | |
| Intersection Capacity Utilization | | | 93.6% | | | | ICU Level of Service | | F | | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 19: SW Sagert St & SW Boones Ferry Rd

4/15/2013

| |  |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR | |
| Lane Configurations |  |  | |  |  | |  |  | |  |  | | |
| Volume (vph) | 41 | 104 | 13 | 161 | 109 | 62 | 16 | 462 | 212 | 63 | 545 | 73 | |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | |
| Total Lost time (s) | 3.5 | 3.5 | | 3.5 | 3.5 | | 3.5 | 4.0 | | 3.5 | 4.0 | | |
| Lane Util. Factor | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | | |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 0.99 | | 1.00 | 0.99 | | 1.00 | 1.00 | | |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | | |
| Frt | 1.00 | 0.98 | | 1.00 | 0.95 | | 1.00 | 0.95 | | 1.00 | 0.98 | | |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | 0.95 | 1.00 | | 0.95 | 1.00 | | |
| Satd. Flow (prot) | 1797 | 1829 | | 1745 | 1754 | | 1804 | 1753 | | 1805 | 1843 | | |
| Flt Permitted | 0.64 | 1.00 | | 0.44 | 1.00 | | 0.26 | 1.00 | | 0.17 | 1.00 | | |
| Satd. Flow (perm) | 1212 | 1829 | | 806 | 1754 | | 490 | 1753 | | 327 | 1843 | | |
| Peak-hour factor, PHF | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 | |
| Adj. Flow (vph) | 45 | 113 | 14 | 175 | 118 | 67 | 17 | 502 | 230 | 68 | 592 | 79 | |
| RTOR Reduction (vph) | 0 | 4 | 0 | 0 | 18 | 0 | 0 | 11 | 0 | 0 | 3 | 0 | |
| Lane Group Flow (vph) | 45 | 123 | 0 | 175 | 167 | 0 | 17 | 721 | 0 | 68 | 668 | 0 | |
| Confl. Peds. (#/hr) | 5 | | 7 | 7 | | 5 | 9 | | 5 | 5 | | 9 | |
| Heavy Vehicles (%) | 0% | 2% | 0% | 3% | 1% | 2% | 0% | 3% | 1% | 0% | 1% | 0% | |
| Turn Type | pm+pt | | | pm+pt | | | pm+pt | | | pm+pt | | | |
| Protected Phases | 7 | 4 | | 3 | 8 | | 5 | 2 | | 1 | 6 | | |
| Permitted Phases | 4 | | | 8 | | | 2 | | | 6 | | | |
| Actuated Green, G (s) | 15.2 | 12.2 | | 25.8 | 18.8 | | 47.0 | 45.5 | | 51.6 | 47.8 | | |
| Effective Green, g (s) | 16.2 | 12.7 | | 26.3 | 19.3 | | 48.0 | 46.0 | | 52.6 | 48.3 | | |
| Actuated g/C Ratio | 0.18 | 0.14 | | 0.30 | 0.22 | | 0.55 | 0.53 | | 0.60 | 0.55 | | |
| Clearance Time (s) | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 | 4.5 | | 4.0 | 4.5 | | |
| Vehicle Extension (s) | 2.2 | 2.2 | | 2.2 | 2.2 | | 2.2 | 5.0 | | 2.2 | 5.0 | | |
| Lane Grp Cap (vph) | 248 | 265 | | 350 | 386 | | 298 | 921 | | 269 | 1016 | | |
| v/s Ratio Prot | 0.01 | 0.07 | | c0.06 | 0.10 | | 0.00 | c0.41 | | c0.01 | 0.36 | | |
| v/s Ratio Perm | 0.03 | | | c0.09 | | | 0.03 | | | 0.14 | | | |
| v/c Ratio | 0.18 | 0.46 | | 0.50 | 0.43 | | 0.06 | 0.78 | | 0.25 | 0.66 | | |
| Uniform Delay, d1 | 29.8 | 34.3 | | 24.1 | 29.4 | | 10.7 | 16.8 | | 11.8 | 13.8 | | |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | | |
| Incremental Delay, d2 | 0.2 | 0.7 | | 0.6 | 0.4 | | 0.0 | 5.1 | | 0.3 | 2.1 | | |
| Delay (s) | 30.0 | 35.0 | | 24.6 | 29.8 | | 10.8 | 21.8 | | 12.0 | 15.9 | | |
| Level of Service | C | C | | C | C | | B | C | | B | B | | |
| Approach Delay (s) | | 33.7 | | | 27.3 | | | 21.6 | | | 15.6 | | |
| Approach LOS | | C | | | C | | | C | | | B | | |
| Intersection Summary | | | | | | | | | | | | | |
| HCM Average Control Delay | | | 21.4 | | | HCM Level of Service | | | | C | | | |
| HCM Volume to Capacity ratio | | | 0.68 | | | | | | | | | | |
| Actuated Cycle Length (s) | | | 87.6 | | | Sum of lost time (s) | | | 14.5 | | | | |
| Intersection Capacity Utilization | | | 72.2% | | | ICU Level of Service | | | | C | | | |
| Analysis Period (min) | | | 15 | | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | | |

HCS+: Unsignalized Intersections Release 5.6

Phone:
E-Mail:

Fax:

ALL-WAY STOP CONTROL (AWSC) ANALYSIS

Analyst:
Agency/Co.:
Date Performed: 4/16/2013
Analysis Time Period: Weekday PM
Intersection: Sagert/Martinazzi
Jurisdiction:
Units: U. S. Customary
Analysis Year: Existing
Project ID:
East/West Street: Sagert
North/South Street: Martinazzi

Worksheet 2 - Volume Adjustments and Site Characteristics

| | Eastbound | | | Westbound | | | Northbound | | | Southbound | | |
|-------------------|-----------|-----|----|-----------|-----|-----|------------|-----|----|------------|-----|-----|
| | L | T | R | L | T | R | L | T | R | L | T | R |
| Volume | 114 | 226 | 12 | 87 | 189 | 159 | 2 | 175 | 74 | 201 | 287 | 232 |
| % Thrus Left Lane | | | | | | | | | | | | |

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|-------------------|-----------|------|-----------|------|------------|------|------------|------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Configuration | L | TR | L | TR | L | TR | L | TR |
| PHF | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 |
| Flow Rate | 126 | 264 | 96 | 386 | 2 | 276 | 223 | 575 |
| % Heavy Veh | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| No. Lanes | | 2 | | 2 | | 2 | | 2 |
| Opposing-Lanes | | 2 | | 2 | | 2 | | 2 |
| Conflicting-lanes | | 2 | | 2 | | 2 | | 2 |
| Geometry group | | 5 | | 5 | | 5 | | 5 |
| Duration, T | 0.25 hrs. | | | | | | | |

Worksheet 3 - Saturation Headway Adjustment Worksheet

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|----------------------------|-----------|-----|-----------|-----|------------|-----|------------|-----|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow Rates: | | | | | | | | |
| Total in Lane | 126 | 264 | 96 | 386 | 2 | 276 | 223 | 575 |
| Left-Turn | 126 | 0 | 96 | 0 | 2 | 0 | 223 | 0 |
| Right-Turn | 0 | 13 | 0 | 176 | 0 | 82 | 0 | 257 |
| Prop. Left-Turns | 1.0 | 0.0 | 1.0 | 0.0 | 1.0 | 0.0 | 1.0 | 0.0 |
| Prop. Right-Turns | 0.0 | 0.0 | 0.0 | 0.5 | 0.0 | 0.3 | 0.0 | 0.4 |
| Prop. Heavy Vehicle | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Geometry Group | | 5 | | 5 | | 5 | | 5 |
| Adjustments Exhibit 17-33: | | | | | | | | |
| hLT-adj | | 0.5 | | 0.5 | | 0.5 | | 0.5 |

| | | | | | | | | |
|----------------|------|------|------|------|------|------|------|------|
| hRT-adj | -0.7 | | -0.7 | | -0.7 | | -0.7 | |
| hHV-adj | 1.7 | | 1.7 | | 1.7 | | 1.7 | |
| hadj, computed | 0.5 | -0.0 | 0.5 | -0.3 | 0.5 | -0.2 | 0.5 | -0.3 |

Worksheet 4 - Departure Headway and Service Time

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|-------------------|-----------|------|-----------|------|------------|------|------------|------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow rate | 126 | 264 | 96 | 386 | 2 | 276 | 223 | 575 |
| hd, initial value | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 |
| x, initial | 0.11 | 0.23 | 0.09 | 0.34 | 0.00 | 0.25 | 0.20 | 0.51 |
| hd, final value | 9.14 | 8.60 | 8.93 | 8.11 | 9.32 | 8.61 | 8.67 | 7.86 |
| x, final value | 0.32 | 0.63 | 0.24 | 0.87 | 0.01 | 0.66 | 0.54 | 1.26 |
| Move-up time, m | | 2.3 | | 2.3 | | 2.3 | | 2.3 |
| Service Time | 6.8 | 6.3 | 6.6 | 5.8 | 7.0 | 6.3 | 6.4 | 5.6 |

Worksheet 5 - Capacity and Level of Service

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|--------------------|-----------|-------|-----------|-------|------------|-------|------------|--------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow Rate | 126 | 264 | 96 | 386 | 2 | 276 | 223 | 575 |
| Service Time | 6.8 | 6.3 | 6.6 | 5.8 | 7.0 | 6.3 | 6.4 | 5.6 |
| Utilization, x | 0.32 | 0.63 | 0.24 | 0.87 | 0.01 | 0.66 | 0.54 | 1.26 |
| Dep. headway, hd | 9.14 | 8.60 | 8.93 | 8.11 | 9.32 | 8.61 | 8.67 | 7.86 |
| Capacity | 376 | 413 | 346 | 442 | 252 | 411 | 413 | 575 |
| Delay | 16.08 | 24.90 | 14.39 | 44.90 | 12.07 | 26.51 | 20.99 | 155.89 |
| LOS | C | C | B | E | B | D | C | F |
| Approach: | | | | | | | | |
| Delay | | 22.05 | | 38.83 | | 26.41 | | 118.19 |
| LOS | | C | | E | | D | | F |
| Intersection Delay | 66.21 | | | | | | | |
| | | | | | | | | |

HCS+: Unsignalized Intersections Release 5.6

Phone:
E-Mail:

Fax:

ALL-WAY STOP CONTROL (AWSC) ANALYSIS

Analyst:
Agency/Co.:
Date Performed: 4/16/2013
Analysis Time Period: Weekday PM
Intersection: Sagert/65th
Jurisdiction:
Units: U. S. Customary
Analysis Year: Existing
Project ID:
East/West Street: Sagert
North/South Street: 65th

Worksheet 2 - Volume Adjustments and Site Characteristics

| | Eastbound | | | Westbound | | | Northbound | | | Southbound | | |
|-------------------|-----------|---|-----|-----------|---|---|------------|-----|---|------------|-----|---|
| | L | T | R | L | T | R | L | T | R | L | T | R |
| Volume | 389 | 2 | 131 | 2 | 7 | 6 | 56 | 280 | 3 | 3 | 326 | |
| % Thrus Left Lane | | | | | | | | | | | | |

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|-------------------|-----------|------|-----------|------|------------|------|------------|------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Configuration | L | TR | L | TR | L | TR | L | TR |
| PHF | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 |
| Flow Rate | 432 | 147 | 2 | 13 | 62 | 314 | 3 | 790 |
| % Heavy Veh | 1 | 1 | 0 | 0 | 1 | 2 | 1 | 2 |
| No. Lanes | | 2 | | 2 | | 2 | | 2 |
| Opposing-Lanes | | 2 | | 2 | | 2 | | 2 |
| Conflicting-lanes | | 2 | | 2 | | 2 | | 2 |
| Geometry group | | 5 | | 5 | | 5 | | 5 |
| Duration, T | 0.25 hrs. | | | | | | | |

Worksheet 3 - Saturation Headway Adjustment Worksheet

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|----------------------------|-----------|-----|-----------|-----|------------|-----|------------|-----|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow Rates: | | | | | | | | |
| Total in Lane | 432 | 147 | 2 | 13 | 62 | 314 | 3 | 790 |
| Left-Turn | 432 | 0 | 2 | 0 | 62 | 0 | 3 | 0 |
| Right-Turn | 0 | 145 | 0 | 6 | 0 | 3 | 0 | 428 |
| Prop. Left-Turns | 1.0 | 0.0 | 1.0 | 0.0 | 1.0 | 0.0 | 1.0 | 0.0 |
| Prop. Right-Turns | 0.0 | 1.0 | 0.0 | 0.5 | 0.0 | 0.0 | 0.0 | 0.5 |
| Prop. Heavy Vehicle | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Geometry Group | | 5 | | 5 | | 5 | | 5 |
| Adjustments Exhibit 17-33: | | | | | | | | |
| hLT-adj | | 0.5 | | 0.5 | | 0.5 | | 0.5 |

| | | | | | | | | |
|----------------|------|------|------|------|------|-----|------|------|
| hRT-adj | -0.7 | | -0.7 | | -0.7 | | -0.7 | |
| hHV-adj | 1.7 | | 1.7 | | 1.7 | | 1.7 | |
| hadj, computed | 0.5 | -0.7 | 0.5 | -0.3 | 0.5 | 0.0 | 0.5 | -0.3 |

Worksheet 4 - Departure Headway and Service Time

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|-------------------|-----------|------|-----------|------|------------|------|------------|------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow rate | 432 | 147 | 2 | 13 | 62 | 314 | 3 | 790 |
| hd, initial value | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 |
| x, initial | 0.38 | 0.13 | 0.00 | 0.01 | 0.06 | 0.28 | 0.00 | 0.70 |
| hd, final value | 7.70 | 6.51 | 9.15 | 8.33 | 7.93 | 7.44 | 7.69 | 6.83 |
| x, final value | 0.92 | 0.27 | 0.01 | 0.03 | 0.14 | 0.65 | 0.01 | 1.50 |
| Move-up time, m | | 2.3 | | 2.3 | | 2.3 | | 2.3 |
| Service Time | 5.4 | 4.2 | 6.8 | 6.0 | 5.6 | 5.1 | 5.4 | 4.5 |

Worksheet 5 - Capacity and Level of Service

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|--------------------|-----------|-------|-----------|-------|------------|-------|------------|--------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow Rate | 432 | 147 | 2 | 13 | 62 | 314 | 3 | 790 |
| Service Time | 5.4 | 4.2 | 6.8 | 6.0 | 5.6 | 5.1 | 5.4 | 4.5 |
| Utilization, x | 0.92 | 0.27 | 0.01 | 0.03 | 0.14 | 0.65 | 0.01 | 1.50 |
| Dep. headway, hd | 7.70 | 6.51 | 9.15 | 8.33 | 7.93 | 7.44 | 7.69 | 6.83 |
| Capacity | 467 | 397 | 252 | 263 | 312 | 479 | 253 | 790 |
| Delay | 52.42 | 11.55 | 11.90 | 11.28 | 11.89 | 22.90 | 10.44 | 252.56 |
| LOS | F | B | B | B | B | C | B | F |
| Approach: | | | | | | | | |
| Delay | | 42.04 | | 11.37 | | 21.08 | | 251.65 |
| LOS | | E | | B | | C | | F |
| Intersection Delay | 131.59 | | | | | | | |
| | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 3: SW Boones Ferry Road & SW Martinazzi Ave

4/17/2013



| Movement | EBT | EBR | WBL | WBT | NBL | NBR |
|------------------------|-------|------|-------|------|-------|-------|
| Lane Configurations | ↑ | ↗ | ↖ | ↑ | ↖ | ↗ |
| Volume (vph) | 405 | 121 | 250 | 416 | 180 | 295 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 4.5 | 4.5 | 4.5 | 4.5 | 4.5 |
| Lane Util. Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Frbp, ped/bikes | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 0.99 |
| Flpb, ped/bikes | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Frt | 1.00 | 0.85 | 1.00 | 1.00 | 1.00 | 0.85 |
| Flt Protected | 1.00 | 1.00 | 0.95 | 1.00 | 0.95 | 1.00 |
| Satd. Flow (prot) | 1863 | 1599 | 1787 | 1845 | 1770 | 1582 |
| Flt Permitted | 1.00 | 1.00 | 0.95 | 1.00 | 0.95 | 1.00 |
| Satd. Flow (perm) | 1863 | 1599 | 1787 | 1845 | 1770 | 1582 |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 426 | 127 | 263 | 438 | 189 | 311 |
| RTOR Reduction (vph) | 0 | 88 | 0 | 0 | 0 | 97 |
| Lane Group Flow (vph) | 426 | 39 | 263 | 438 | 189 | 214 |
| Confl. Peds. (#/hr) | | 11 | 11 | | 1 | 3 |
| Confl. Bikes (#/hr) | 4 | | 2 | 10 | 1 | |
| Heavy Vehicles (%) | 2% | 1% | 1% | 3% | 2% | 1% |
| Turn Type | | Prot | Prot | | | pm+ov |
| Protected Phases | 2 | 2 | 1 | 6 | 8 | 1 |
| Permitted Phases | | | | | 8 | 8 |
| Actuated Green, G (s) | 16.7 | 16.7 | 13.3 | 35.0 | 10.8 | 24.1 |
| Effective Green, g (s) | 17.2 | 17.2 | 13.8 | 35.5 | 11.3 | 25.1 |
| Actuated g/C Ratio | 0.31 | 0.31 | 0.25 | 0.64 | 0.20 | 0.45 |
| Clearance Time (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 |
| Lane Grp Cap (vph) | 574 | 493 | 442 | 1174 | 358 | 839 |
| v/s Ratio Prot | c0.23 | 0.02 | c0.15 | 0.24 | c0.11 | 0.06 |
| v/s Ratio Perm | | | | | | 0.07 |
| v/c Ratio | 0.74 | 0.08 | 0.60 | 0.37 | 0.53 | 0.25 |
| Uniform Delay, d1 | 17.3 | 13.7 | 18.5 | 4.8 | 19.9 | 9.5 |
| Progression Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Incremental Delay, d2 | 5.2 | 0.1 | 2.2 | 0.2 | 1.4 | 0.2 |
| Delay (s) | 22.5 | 13.8 | 20.7 | 5.0 | 21.3 | 9.7 |
| Level of Service | C | B | C | A | C | A |
| Approach Delay (s) | 20.5 | | | 10.9 | 14.1 | |
| Approach LOS | C | | | B | B | |

| Intersection Summary | | | |
|-----------------------------------|-------|----------------------|------|
| HCM Average Control Delay | 14.8 | HCM Level of Service | B |
| HCM Volume to Capacity ratio | 0.64 | | |
| Actuated Cycle Length (s) | 55.8 | Sum of lost time (s) | 13.5 |
| Intersection Capacity Utilization | 57.1% | ICU Level of Service | B |
| Analysis Period (min) | 15 | | |

c Critical Lane Group











HCM Unsignalized Intersection Capacity Analysis
 4: Site Entrance 1 & Martinazzi Ave

4/17/2013

| | ↙ | ↖ | ↑ | ↗ | ↘ | ↓ |
|-----------------------------------|------|------|-------|------|----------------------|-------|
| Movement | WBL | WBR | NBT | NBR | SBL | SBT |
| Lane Configurations | ↙ | ↖ | ↗ | | ↘ | ↓ |
| Volume (veh/h) | 46 | 80 | 396 | 60 | 110 | 261 |
| Sign Control | Stop | | Free | | | Free |
| Grade | 0% | | 0% | | | 0% |
| Peak Hour Factor | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 |
| Hourly flow rate (vph) | 50 | 87 | 430 | 65 | 120 | 284 |
| Pedestrians | 13 | | | | | 6 |
| Lane Width (ft) | 12.0 | | | | | 12.0 |
| Walking Speed (ft/s) | 4.0 | | | | | 4.0 |
| Percent Blockage | 1 | | | | | 1 |
| Right turn flare (veh) | | | | | | |
| Median type | | | None | | | TWLTL |
| Median storage (veh) | | | | | | 2 |
| Upstream signal (ft) | | | 428 | | | 355 |
| pX, platoon unblocked | 0.98 | 0.98 | | | 0.98 | |
| vC, conflicting volume | 999 | 482 | | | 509 | |
| vC1, stage 1 conf vol | 476 | | | | | |
| vC2, stage 2 conf vol | 523 | | | | | |
| vCu, unblocked vol | 988 | 460 | | | 488 | |
| tC, single (s) | 6.4 | 6.2 | | | 4.1 | |
| tC, 2 stage (s) | 5.4 | | | | | |
| tF (s) | 3.5 | 3.3 | | | 2.2 | |
| p0 queue free % | 89 | 85 | | | 89 | |
| cM capacity (veh/h) | 447 | 583 | | | 1052 | |
| Direction, Lane # | WB 1 | WB 2 | NB 1 | SB 1 | SB 2 | |
| Volume Total | 50 | 87 | 496 | 120 | 284 | |
| Volume Left | 50 | 0 | 0 | 120 | 0 | |
| Volume Right | 0 | 87 | 65 | 0 | 0 | |
| cSH | 447 | 583 | 1700 | 1052 | 1700 | |
| Volume to Capacity | 0.11 | 0.15 | 0.29 | 0.11 | 0.17 | |
| Queue Length 95th (ft) | 10 | 14 | 0 | 10 | 0 | |
| Control Delay (s) | 14.1 | 12.3 | 0.0 | 8.9 | 0.0 | |
| Lane LOS | B | B | | A | | |
| Approach Delay (s) | 12.9 | | 0.0 | 2.6 | | |
| Approach LOS | B | | | | | |
| Intersection Summary | | | | | | |
| Average Delay | | | 2.7 | | | |
| Intersection Capacity Utilization | | | 45.9% | | ICU Level of Service | A |
| Analysis Period (min) | | | 15 | | | |

HCM Unsignalized Intersection Capacity Analysis
5: Seneca St & Martinazzi Ave

4/17/2013

| |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|
| Movement | EBL | EBR | NBL | NBT | SBT | SBR |
| Lane Configurations |  | |  |  |  | |
| Volume (veh/h) | 37 | 45 | 81 | 419 | 263 | 44 |
| Sign Control | Stop | | | Free | Free | |
| Grade | 0% | | | 0% | 0% | |
| Peak Hour Factor | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 |
| Hourly flow rate (vph) | 41 | 49 | 89 | 460 | 289 | 48 |
| Pedestrians | 1 | | | 4 | 10 | |
| Lane Width (ft) | 12.0 | | | 12.0 | 12.0 | |
| Walking Speed (ft/s) | 4.0 | | | 4.0 | 4.0 | |
| Percent Blockage | 0 | | | 0 | 1 | |
| Right turn flare (veh) | | | | | | |
| Median type | | | | None | None | |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | | | 308 | 475 | |
| pX, platoon unblocked | 0.96 | | | | | |
| vC, conflicting volume | 963 | 318 | 338 | | | |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 942 | 318 | 338 | | | |
| tC, single (s) | 6.4 | 6.2 | 4.1 | | | |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 3.5 | 3.3 | 2.2 | | | |
| p0 queue free % | 84 | 93 | 93 | | | |
| cM capacity (veh/h) | 261 | 724 | 1231 | | | |
| Direction, Lane # | EB 1 | NB 1 | NB 2 | SB 1 | | |
| Volume Total | 90 | 89 | 460 | 337 | | |
| Volume Left | 41 | 89 | 0 | 0 | | |
| Volume Right | 49 | 0 | 0 | 48 | | |
| cSH | 402 | 1231 | 1700 | 1700 | | |
| Volume to Capacity | 0.22 | 0.07 | 0.27 | 0.20 | | |
| Queue Length 95th (ft) | 22 | 6 | 0 | 0 | | |
| Control Delay (s) | 16.5 | 8.2 | 0.0 | 0.0 | | |
| Lane LOS | C | A | | | | |
| Approach Delay (s) | 16.5 | 1.3 | | 0.0 | | |
| Approach LOS | C | | | | | |
| Intersection Summary | | | | | | |
| Average Delay | | | 2.3 | | | |
| Intersection Capacity Utilization | | | 37.1% | | ICU Level of Service | A |
| Analysis Period (min) | | | 15 | | | |

HCM Unsignalized Intersection Capacity Analysis
 6: Site Entrance 2 & Martinazzi Ave

4/17/2013

| Movement | WBL | WBR | NBT | NBR | SBL | SBT |
|-----------------------------------|------|------|-------|----------------------|------|------|
| Lane Configurations | | | | | | |
| Volume (veh/h) | 5 | 25 | 475 | 9 | 3 | 305 |
| Sign Control | Stop | | Free | | | Free |
| Grade | 0% | | 0% | | | 0% |
| Peak Hour Factor | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 |
| Hourly flow rate (vph) | 6 | 28 | 528 | 10 | 3 | 339 |
| Pedestrians | 19 | | | | | 2 |
| Lane Width (ft) | 12.0 | | | | | 12.0 |
| Walking Speed (ft/s) | 4.0 | | | | | 4.0 |
| Percent Blockage | 2 | | | | | 0 |
| Right turn flare (veh) | | | | | | |
| Median type | | | None | | | None |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | | 227 | | | 556 |
| pX, platoon unblocked | 0.90 | 0.90 | | | 0.90 | |
| vC, conflicting volume | 728 | 554 | | | 557 | |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 641 | 448 | | | 451 | |
| tC, single (s) | 6.8 | 6.9 | | | 4.1 | |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 3.5 | 3.3 | | | 2.2 | |
| p0 queue free % | 98 | 94 | | | 100 | |
| cM capacity (veh/h) | 363 | 498 | | | 991 | |
| Direction, Lane # | WB 1 | NB 1 | SB 1 | SB 2 | | |
| Volume Total | 33 | 538 | 116 | 226 | | |
| Volume Left | 6 | 0 | 3 | 0 | | |
| Volume Right | 28 | 10 | 0 | 0 | | |
| cSH | 469 | 1700 | 991 | 1700 | | |
| Volume to Capacity | 0.07 | 0.32 | 0.00 | 0.13 | | |
| Queue Length 95th (ft) | 6 | 0 | 0 | 0 | | |
| Control Delay (s) | 13.3 | 0.0 | 0.3 | 0.0 | | |
| Lane LOS | B | | A | | | |
| Approach Delay (s) | 13.3 | 0.0 | 0.1 | | | |
| Approach LOS | B | | | | | |
| Intersection Summary | | | | | | |
| Average Delay | | | 0.5 | | | |
| Intersection Capacity Utilization | | | 36.2% | ICU Level of Service | A | |
| Analysis Period (min) | | | 15 | | | |

HCM Unsignalized Intersection Capacity Analysis

7: RO Only & Martinazzi Ave

4/17/2013

| | ↙ | ↖ | ↑ | ↗ | ↘ | ↓ |
|-----------------------------------|------|------|-------|------|----------------------|------|
| Movement | WBL | WBR | NBT | NBR | SBL | SBT |
| Lane Configurations | | ↗ | ↑ | | | ↘↘ |
| Volume (veh/h) | 0 | 10 | 474 | 0 | 1 | 309 |
| Sign Control | Stop | | Free | | | Free |
| Grade | 0% | | 0% | | | 0% |
| Peak Hour Factor | 0.89 | 0.89 | 0.89 | 0.89 | 0.89 | 0.89 |
| Hourly flow rate (vph) | 0 | 11 | 533 | 0 | 1 | 347 |
| Pedestrians | 13 | | | | | |
| Lane Width (ft) | 12.0 | | | | | |
| Walking Speed (ft/s) | 4.0 | | | | | |
| Percent Blockage | 1 | | | | | |
| Right turn flare (veh) | | | | | | |
| Median type | | | None | | | None |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | | 125 | | | 658 |
| pX, platoon unblocked | 0.89 | 0.89 | | | 0.89 | |
| vC, conflicting volume | 721 | 546 | | | 546 | |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 623 | 425 | | | 425 | |
| tC, single (s) | 6.8 | 6.9 | | | 4.1 | |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 3.5 | 3.3 | | | 2.2 | |
| p0 queue free % | 100 | 98 | | | 100 | |
| cM capacity (veh/h) | 371 | 512 | | | 1006 | |
| Direction, Lane # | WB 1 | NB 1 | SB 1 | SB 2 | | |
| Volume Total | 11 | 533 | 117 | 231 | | |
| Volume Left | 0 | 0 | 1 | 0 | | |
| Volume Right | 11 | 0 | 0 | 0 | | |
| cSH | 512 | 1700 | 1006 | 1700 | | |
| Volume to Capacity | 0.02 | 0.31 | 0.00 | 0.14 | | |
| Queue Length 95th (ft) | 2 | 0 | 0 | 0 | | |
| Control Delay (s) | 12.2 | 0.0 | 0.1 | 0.0 | | |
| Lane LOS | B | | A | | | |
| Approach Delay (s) | 12.2 | 0.0 | 0.0 | | | |
| Approach LOS | B | | | | | |
| Intersection Summary | | | | | | |
| Average Delay | | | 0.2 | | | |
| Intersection Capacity Utilization | | | 34.9% | | ICU Level of Service | A |
| Analysis Period (min) | | | 15 | | | |

HCM Signalized Intersection Capacity Analysis
 8: Nyberg St & Martinazzi Ave

4/17/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|------|------|-------|-------|------|------|-------|------|------|------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 16 | 1 | 63 | 220 | 37 | 230 | 23 | 228 | 31 | 0 | 301 | 8 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 5.5 | 5.5 | | 5.5 | 5.5 | 5.5 | 5.5 | 5.5 | | | 5.5 | |
| Lane Util. Factor | 1.00 | 1.00 | | 0.95 | 0.95 | 1.00 | 1.00 | 1.00 | | | 0.95 | |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 0.97 | 1.00 | 1.00 | | | 1.00 | |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | 1.00 | |
| Frt | 1.00 | 0.85 | | 1.00 | 1.00 | 0.85 | 1.00 | 0.98 | | | 1.00 | |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 0.97 | 1.00 | 0.95 | 1.00 | | | 1.00 | |
| Satd. Flow (prot) | 1805 | 1603 | | 1698 | 1730 | 1542 | 1683 | 1841 | | | 3559 | |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 0.97 | 1.00 | 0.55 | 1.00 | | | 1.00 | |
| Satd. Flow (perm) | 1805 | 1603 | | 1698 | 1730 | 1542 | 970 | 1841 | | | 3559 | |
| Peak-hour factor, PHF | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 |
| Adj. Flow (vph) | 18 | 1 | 69 | 242 | 41 | 253 | 25 | 251 | 34 | 0 | 331 | 9 |
| RTOR Reduction (vph) | 0 | 63 | 0 | 0 | 0 | 198 | 0 | 7 | 0 | 0 | 3 | 0 |
| Lane Group Flow (vph) | 18 | 7 | 0 | 140 | 143 | 55 | 25 | 278 | 0 | 0 | 337 | 0 |
| Confl. Peds. (#/hr) | 2 | | | | | 2 | 3 | | 16 | 16 | | 3 |
| Confl. Bikes (#/hr) | | | | | | 2 | | | | | | 3 |
| Heavy Vehicles (%) | 0% | 0% | 1% | 1% | 0% | 2% | 7% | 1% | 0% | 0% | 1% | 0% |
| Turn Type | Split | | | Split | | Perm | Perm | | | | | |
| Protected Phases | 8 | 8 | | 4 | 4 | | | 6 | | | | 2 |
| Permitted Phases | | | | | | 4 | 6 | | | | | |
| Actuated Green, G (s) | 3.1 | 3.1 | | 8.9 | 8.9 | 8.9 | 13.6 | 13.6 | | | | 13.6 |
| Effective Green, g (s) | 3.6 | 3.6 | | 9.4 | 9.4 | 9.4 | 14.1 | 14.1 | | | | 14.1 |
| Actuated g/C Ratio | 0.08 | 0.08 | | 0.22 | 0.22 | 0.22 | 0.32 | 0.32 | | | | 0.32 |
| Clearance Time (s) | 6.0 | 6.0 | | 6.0 | 6.0 | 6.0 | 6.0 | 6.0 | | | | 6.0 |
| Vehicle Extension (s) | 2.5 | 2.5 | | 2.5 | 2.5 | 2.5 | 5.0 | 5.0 | | | | 5.0 |
| Lane Grp Cap (vph) | 149 | 132 | | 366 | 373 | 332 | 314 | 595 | | | | 1151 |
| v/s Ratio Prot | c0.01 | 0.00 | | 0.08 | c0.08 | | | c0.15 | | | | 0.09 |
| v/s Ratio Perm | | | | | | 0.04 | 0.03 | | | | | |
| v/c Ratio | 0.12 | 0.05 | | 0.38 | 0.38 | 0.16 | 0.08 | 0.47 | | | | 0.29 |
| Uniform Delay, d1 | 18.5 | 18.4 | | 14.6 | 14.6 | 13.9 | 10.2 | 11.8 | | | | 11.0 |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | | 1.00 |
| Incremental Delay, d2 | 0.3 | 0.1 | | 0.5 | 0.5 | 0.2 | 0.2 | 1.2 | | | | 0.3 |
| Delay (s) | 18.8 | 18.5 | | 15.1 | 15.1 | 14.1 | 10.5 | 13.0 | | | | 11.3 |
| Level of Service | B | B | | B | B | B | B | B | | | | B |
| Approach Delay (s) | | 18.6 | | | 14.6 | | | 12.8 | | | | 11.3 |
| Approach LOS | | B | | | B | | | B | | | | B |

| Intersection Summary | | | |
|-----------------------------------|-------|----------------------|------|
| HCM Average Control Delay | 13.6 | HCM Level of Service | B |
| HCM Volume to Capacity ratio | 0.39 | | |
| Actuated Cycle Length (s) | 43.6 | Sum of lost time (s) | 16.5 |
| Intersection Capacity Utilization | 47.4% | ICU Level of Service | A |
| Analysis Period (min) | 15 | | |

c Critical Lane Group

HCM Unsignalized Intersection Capacity Analysis
 9: Nyberg St & Site Entrance 3

4/17/2013



| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
|------------------------|------|------|------|------|------|------|
| Lane Configurations | ↵ | | ↵↵ | | | ↵ |
| Volume (veh/h) | 32 | 0 | 434 | 50 | 0 | 53 |
| Sign Control | | Free | Free | | Stop | |
| Grade | | 0% | 0% | | 0% | |
| Peak Hour Factor | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 |
| Hourly flow rate (vph) | 36 | 0 | 493 | 57 | 0 | 60 |
| Pedestrians | | | | | 4 | |
| Lane Width (ft) | | | | | 12.0 | |
| Walking Speed (ft/s) | | | | | 4.0 | |
| Percent Blockage | | | | | 0 | |
| Right turn flare (veh) | | | | | | |
| Median type | | None | None | | | |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | 245 | | | | |
| pX, platoon unblocked | | | | | | |
| vC, conflicting volume | 554 | | | | 598 | 279 |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 554 | | | | 598 | 279 |
| tC, single (s) | 4.1 | | | | 6.8 | 6.9 |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 2.2 | | | | 3.5 | 3.3 |
| p0 queue free % | 96 | | | | 100 | 92 |
| cM capacity (veh/h) | 1023 | | | | 421 | 722 |

| Direction, Lane # | EB 1 | WB 1 | WB 2 | SB 1 |
|------------------------|------|------|------|------|
| Volume Total | 36 | 329 | 221 | 60 |
| Volume Left | 36 | 0 | 0 | 0 |
| Volume Right | 0 | 0 | 57 | 60 |
| cSH | 1023 | 1700 | 1700 | 722 |
| Volume to Capacity | 0.04 | 0.19 | 0.13 | 0.08 |
| Queue Length 95th (ft) | 3 | 0 | 0 | 7 |
| Control Delay (s) | 8.6 | 0.0 | 0.0 | 10.4 |
| Lane LOS | A | | | B |
| Approach Delay (s) | 8.6 | 0.0 | | 10.4 |
| Approach LOS | | | | B |

| Intersection Summary | | | |
|-----------------------------------|--|-------|------------------------|
| Average Delay | | 1.5 | |
| Intersection Capacity Utilization | | 23.6% | ICU Level of Service A |
| Analysis Period (min) | | 15 | |

HCM Signalized Intersection Capacity Analysis
 10: Tualatin Sherwood Rd & Site Entrance 4

4/17/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|------|-------|-------|-------|------|----------------------|------|------|-------|------|-------|------|
| Lane Configurations | ↘ | ↗↔ | | ↘ | ↗↔ | | | ↕ | ↗ | | ↕ | ↗ |
| Volume (vph) | 50 | 1335 | 59 | 257 | 1451 | 101 | 57 | 25 | 248 | 154 | 40 | 62 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 6.0 | | 4.5 | 6.0 | | | 5.0 | 4.5 | | 5.0 | 5.0 |
| Lane Util. Factor | 1.00 | *0.75 | | 0.97 | 0.91 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 0.98 |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frt | 1.00 | 0.99 | | 1.00 | 0.99 | | | 1.00 | 0.85 | | 1.00 | 0.85 |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.97 | 1.00 | | 0.96 | 1.00 |
| Satd. Flow (prot) | 1805 | 4091 | | 3502 | 4941 | | | 1799 | 1599 | | 1813 | 1579 |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.50 | 1.00 | | 0.71 | 1.00 |
| Satd. Flow (perm) | 1805 | 4091 | | 3502 | 4941 | | | 925 | 1599 | | 1347 | 1579 |
| Peak-hour factor, PHF | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 |
| Adj. Flow (vph) | 51 | 1362 | 60 | 262 | 1481 | 103 | 58 | 26 | 253 | 157 | 41 | 63 |
| RTOR Reduction (vph) | 0 | 3 | 0 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 52 |
| Lane Group Flow (vph) | 51 | 1419 | 0 | 262 | 1579 | 0 | 0 | 84 | 253 | 0 | 198 | 11 |
| Confl. Peds. (#/hr) | | | | | | 4 | | | | | | 9 |
| Confl. Bikes (#/hr) | | | | | 1 | | | 1 | | 1 | | |
| Heavy Vehicles (%) | 0% | 4% | 0% | 0% | 4% | 0% | 3% | 0% | 1% | 1% | 0% | 0% |
| Turn Type | Prot | | | Prot | | | Perm | | pm+ov | Perm | | Perm |
| Protected Phases | 5 | 2 | | 1 | 6 | | | 8 | 1 | | 4 | |
| Permitted Phases | | | | | | | 8 | | 8 | 4 | | 4 |
| Actuated Green, G (s) | 5.9 | 66.0 | | 11.6 | 71.7 | | | 20.4 | 32.0 | | 20.4 | 20.4 |
| Effective Green, g (s) | 6.4 | 66.5 | | 12.1 | 72.2 | | | 20.9 | 33.0 | | 20.9 | 20.9 |
| Actuated g/C Ratio | 0.06 | 0.58 | | 0.11 | 0.63 | | | 0.18 | 0.29 | | 0.18 | 0.18 |
| Clearance Time (s) | 5.0 | 6.5 | | 5.0 | 6.5 | | | 5.5 | 5.0 | | 5.5 | 5.5 |
| Vehicle Extension (s) | 2.5 | 4.0 | | 2.5 | 4.0 | | | 2.5 | 2.5 | | 2.5 | 2.5 |
| Lane Grp Cap (vph) | 100 | 2366 | | 368 | 3102 | | | 168 | 459 | | 245 | 287 |
| v/s Ratio Prot | 0.03 | c0.35 | | c0.07 | 0.32 | | | | 0.06 | | | |
| v/s Ratio Perm | | | | | | | | 0.09 | 0.10 | | c0.15 | 0.01 |
| v/c Ratio | 0.51 | 0.60 | | 0.71 | 0.51 | | | 0.50 | 0.55 | | 0.81 | 0.04 |
| Uniform Delay, d1 | 52.8 | 15.7 | | 49.8 | 11.7 | | | 42.3 | 34.7 | | 45.1 | 38.8 |
| Progression Factor | 0.84 | 0.72 | | 1.01 | 0.63 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Incremental Delay, d2 | 2.6 | 0.9 | | 4.9 | 0.5 | | | 1.7 | 1.1 | | 17.1 | 0.0 |
| Delay (s) | 47.0 | 12.2 | | 55.2 | 7.8 | | | 44.0 | 35.9 | | 62.2 | 38.8 |
| Level of Service | D | B | | E | A | | | D | D | | E | D |
| Approach Delay (s) | | 13.4 | | | 14.6 | | | 37.9 | | | 56.5 | |
| Approach LOS | | B | | | B | | | D | | | E | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 18.9 | | | HCM Level of Service | | | | B | | |
| HCM Volume to Capacity ratio | | | 0.66 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 115.0 | | | Sum of lost time (s) | | 15.5 | | | | |
| Intersection Capacity Utilization | | | 69.5% | | | ICU Level of Service | | C | | | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |

c Critical Lane Group

HCM Unsignalized Intersection Capacity Analysis
 11: Tualatin Sherwood Rd & 75th Ave

4/17/2013















| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
|------------------------|------|------|------|------|------|------|
| Lane Configurations | | ↑↑↑ | ↑↑↑ | | | ↗ |
| Volume (veh/h) | 0 | 1737 | 1794 | 48 | 0 | 15 |
| Sign Control | | Free | Free | | Stop | |
| Grade | | 0% | 0% | | 0% | |
| Peak Hour Factor | 0.97 | 0.97 | 0.97 | 0.97 | 0.97 | 0.97 |
| Hourly flow rate (vph) | 0 | 1791 | 1849 | 49 | 0 | 15 |
| Pedestrians | | | | | 6 | |
| Lane Width (ft) | | | | | 12.0 | |
| Walking Speed (ft/s) | | | | | 4.0 | |
| Percent Blockage | | | | | 1 | |
| Right turn flare (veh) | | | | | | |
| Median type | | None | None | | | |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | 373 | 260 | | | |
| pX, platoon unblocked | 0.84 | | | | 0.88 | 0.84 |
| vC, conflicting volume | 1905 | | | | 2477 | 647 |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 1407 | | | | 982 | 0 |
| tC, single (s) | 4.1 | | | | 6.8 | 7.4 |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 2.2 | | | | 3.5 | 3.5 |
| p0 queue free % | 100 | | | | 100 | 98 |
| cM capacity (veh/h) | 410 | | | | 220 | 847 |

| Direction, Lane # | EB 1 | EB 2 | EB 3 | WB 1 | WB 2 | WB 3 | SB 1 |
|------------------------|------|------|------|------|------|------|------|
| Volume Total | 597 | 597 | 597 | 740 | 740 | 419 | 15 |
| Volume Left | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Volume Right | 0 | 0 | 0 | 0 | 0 | 49 | 15 |
| cSH | 1700 | 1700 | 1700 | 1700 | 1700 | 1700 | 847 |
| Volume to Capacity | 0.35 | 0.35 | 0.35 | 0.44 | 0.44 | 0.25 | 0.02 |
| Queue Length 95th (ft) | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| Control Delay (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 9.3 |
| Lane LOS | | | | | | | A |
| Approach Delay (s) | 0.0 | | | 0.0 | | | 9.3 |
| Approach LOS | | | | | | | A |

| Intersection Summary | | | |
|-----------------------------------|--|-------|------------------------|
| Average Delay | | 0.0 | |
| Intersection Capacity Utilization | | 45.7% | ICU Level of Service A |
| Analysis Period (min) | | 15 | |

HCM Signalized Intersection Capacity Analysis
 12: Tualatin Sherwood Rd & I-5 SB Ramps

4/17/2013

| |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | | ↑↑↑ | ↑ | ↓ | ↑↑ | | | | | ↓ | ↑ | ↑↑ |
| Volume (vph) | 0 | 1332 | 405 | 187 | 1000 | 0 | 0 | 0 | 0 | 602 | 3 | 840 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | | 5.5 | 5.5 | 3.5 | 5.5 | | | | | 5.5 | 5.5 | 5.5 |
| Lane Util. Factor | | *0.75 | 1.00 | 1.00 | 0.95 | | | | | 0.95 | 0.95 | 0.88 |
| Frbp, ped/bikes | | 1.00 | 1.00 | 1.00 | 1.00 | | | | | 1.00 | 1.00 | 1.00 |
| Flpb, ped/bikes | | 1.00 | 1.00 | 1.00 | 1.00 | | | | | 1.00 | 1.00 | 1.00 |
| Frt | | 1.00 | 0.85 | 1.00 | 1.00 | | | | | 1.00 | 1.00 | 0.85 |
| Flt Protected | | 1.00 | 1.00 | 0.95 | 1.00 | | | | | 0.95 | 0.95 | 1.00 |
| Satd. Flow (prot) | | 4150 | 1568 | 1787 | 3471 | | | | | 1681 | 1683 | 2760 |
| Flt Permitted | | 1.00 | 1.00 | 0.95 | 1.00 | | | | | 0.95 | 0.95 | 1.00 |
| Satd. Flow (perm) | | 4150 | 1568 | 1787 | 3471 | | | | | 1681 | 1683 | 2760 |
| Peak-hour factor, PHF | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 |
| Adj. Flow (vph) | 0 | 1345 | 409 | 189 | 1010 | 0 | 0 | 0 | 0 | 608 | 3 | 848 |
| RTOR Reduction (vph) | 0 | 0 | 199 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 68 |
| Lane Group Flow (vph) | 0 | 1345 | 210 | 189 | 1010 | 0 | 0 | 0 | 0 | 304 | 307 | 780 |
| Confl. Bikes (#/hr) | | 1 | | | 2 | | | | | | | |
| Heavy Vehicles (%) | 0% | 3% | 3% | 1% | 4% | 0% | 0% | 0% | 0% | 2% | 20% | 3% |
| Turn Type | | | Perm | Prot | | | | | | Split | | custom |
| Protected Phases | | 2 | | 1 | 6 | | | | | 4 | 4 | 4 |
| Permitted Phases | | | 2 | | | | | | | | | |
| Actuated Green, G (s) | | 57.4 | 57.4 | 14.7 | 59.1 | | | | | 26.9 | 26.9 | 43.9 |
| Effective Green, g (s) | | 57.9 | 57.9 | 15.2 | 59.6 | | | | | 27.4 | 27.4 | 40.9 |
| Actuated g/C Ratio | | 0.50 | 0.50 | 0.13 | 0.52 | | | | | 0.24 | 0.24 | 0.36 |
| Clearance Time (s) | | 6.0 | 6.0 | 4.0 | 6.0 | | | | | 6.0 | 6.0 | |
| Vehicle Extension (s) | | 6.1 | 6.1 | 2.3 | 6.1 | | | | | 2.3 | 2.3 | |
| Lane Grp Cap (vph) | | 2089 | 789 | 236 | 1799 | | | | | 401 | 401 | 982 |
| v/s Ratio Prot | | c0.32 | | c0.11 | 0.29 | | | | | 0.18 | 0.18 | c0.28 |
| v/s Ratio Perm | | | 0.13 | | | | | | | | | |
| v/c Ratio | | 0.64 | 0.27 | 0.80 | 0.56 | | | | | 0.76 | 0.77 | 0.79 |
| Uniform Delay, d1 | | 21.0 | 16.4 | 48.4 | 18.8 | | | | | 40.7 | 40.8 | 33.3 |
| Progression Factor | | 0.72 | 0.65 | 0.72 | 1.23 | | | | | 1.00 | 1.00 | 1.00 |
| Incremental Delay, d2 | | 1.3 | 0.7 | 16.2 | 1.2 | | | | | 7.4 | 7.9 | 4.3 |
| Delay (s) | | 16.3 | 11.3 | 51.0 | 24.5 | | | | | 48.1 | 48.7 | 37.6 |
| Level of Service | | B | B | D | C | | | | | D | D | D |
| Approach Delay (s) | | 15.1 | | | 28.6 | | | 0.0 | | | 42.1 | |
| Approach LOS | | B | | | C | | | A | | | D | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 27.7 | | | HCM Level of Service | | | | C | | |
| HCM Volume to Capacity ratio | | | 0.77 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 115.0 | | | Sum of lost time (s) | | | 20.0 | | | |
| Intersection Capacity Utilization | | | 66.2% | | | ICU Level of Service | | | | C | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 13: Tualatin Sherwood Rd & I-5 NB Ramps





















4/17/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR | |
|-----------------------------------|------|-------|-------|------|----------------------|------|-------|-------|------|------|------|------|--|
| Lane Configurations | | ↑↑ | ↑↑ | | ↑↑ | ↑ | ↑ | ↑ | ↑ | | | | |
| Volume (vph) | 0 | 1045 | 890 | 0 | 610 | 646 | 575 | 0 | 213 | 0 | 0 | 0 | |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | |
| Total Lost time (s) | | 5.5 | 5.5 | | 6.0 | 6.0 | 5.5 | 5.5 | 5.5 | | | | |
| Lane Util. Factor | | 0.95 | 0.88 | | 0.95 | 1.00 | 0.95 | 0.95 | 1.00 | | | | |
| Flpb, ped/bikes | | 1.00 | 0.98 | | 1.00 | 1.00 | 1.00 | 1.00 | 0.98 | | | | |
| Flpb, ped/bikes | | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | | |
| Frt | | 1.00 | 0.85 | | 1.00 | 0.85 | 1.00 | 1.00 | 0.85 | | | | |
| Flt Protected | | 1.00 | 1.00 | | 1.00 | 1.00 | 0.95 | 0.95 | 1.00 | | | | |
| Satd. Flow (prot) | | 3574 | 2694 | | 3574 | 1583 | 1618 | 1618 | 1559 | | | | |
| Flt Permitted | | 1.00 | 1.00 | | 1.00 | 1.00 | 0.95 | 0.95 | 1.00 | | | | |
| Satd. Flow (perm) | | 3574 | 2694 | | 3574 | 1583 | 1618 | 1618 | 1559 | | | | |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | |
| Adj. Flow (vph) | 0 | 1100 | 937 | 0 | 642 | 680 | 605 | 0 | 224 | 0 | 0 | 0 | |
| RTOR Reduction (vph) | 0 | 0 | 313 | 0 | 0 | 230 | 0 | 0 | 37 | 0 | 0 | 0 | |
| Lane Group Flow (vph) | 0 | 1100 | 624 | 0 | 642 | 450 | 302 | 303 | 187 | 0 | 0 | 0 | |
| Confl. Peds. (#/hr) | | | 1 | 1 | | | 1 | | 2 | 2 | | 1 | |
| Confl. Bikes (#/hr) | | 1 | | | 5 | | | | | 1 | | | |
| Heavy Vehicles (%) | 0% | 1% | 3% | 0% | 1% | 2% | 6% | 20% | 2% | 0% | 0% | 0% | |
| Turn Type | | | Perm | | | Perm | Split | | Perm | | | | |
| Protected Phases | | 2 | | | 6 | | 8 | 8 | | | | | |
| Permitted Phases | | | 2 | | | 6 | | | 8 | | | | |
| Actuated Green, G (s) | | 76.1 | 76.1 | | 75.6 | 75.6 | 26.9 | 26.9 | 26.9 | | | | |
| Effective Green, g (s) | | 76.6 | 76.6 | | 76.1 | 76.1 | 27.4 | 27.4 | 27.4 | | | | |
| Actuated g/C Ratio | | 0.67 | 0.67 | | 0.66 | 0.66 | 0.24 | 0.24 | 0.24 | | | | |
| Clearance Time (s) | | 6.0 | 6.0 | | 6.5 | 6.5 | 6.0 | 6.0 | 6.0 | | | | |
| Vehicle Extension (s) | | 6.1 | 6.1 | | 4.2 | 4.2 | 2.3 | 2.3 | 2.3 | | | | |
| Lane Grp Cap (vph) | | 2381 | 1794 | | 2365 | 1048 | 386 | 386 | 371 | | | | |
| v/s Ratio Prot | | c0.31 | | | 0.18 | | 0.19 | c0.19 | | | | | |
| v/s Ratio Perm | | | 0.23 | | | 0.28 | | | 0.12 | | | | |
| v/c Ratio | | 0.46 | 0.35 | | 0.27 | 0.43 | 0.78 | 0.78 | 0.51 | | | | |
| Uniform Delay, d1 | | 9.3 | 8.3 | | 8.0 | 9.2 | 41.0 | 41.0 | 37.9 | | | | |
| Progression Factor | | 1.29 | 5.34 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | | |
| Incremental Delay, d2 | | 0.5 | 0.4 | | 0.3 | 1.3 | 9.4 | 9.6 | 0.6 | | | | |
| Delay (s) | | 12.5 | 45.0 | | 8.3 | 10.5 | 50.4 | 50.6 | 38.6 | | | | |
| Level of Service | | B | D | | A | B | D | D | D | | | | |
| Approach Delay (s) | | 27.5 | | | 9.4 | | | 47.3 | | | 0.0 | | |
| Approach LOS | | C | | | A | | | D | | | A | | |
| Intersection Summary | | | | | | | | | | | | | |
| HCM Average Control Delay | | | 25.7 | | HCM Level of Service | | | | | C | | | |
| HCM Volume to Capacity ratio | | | 0.55 | | | | | | | | | | |
| Actuated Cycle Length (s) | | | 115.0 | | Sum of lost time (s) | | | | | 11.0 | | | |
| Intersection Capacity Utilization | | | 65.5% | | ICU Level of Service | | | | | C | | | |
| Analysis Period (min) | | | 15 | | | | | | | | | | |

c Critical Lane Group

HCM Signalized Intersection Capacity Analysis
 14: Tualatin Sherwood Rd & Nyberg Woods

4/17/2013

| |  |  |  |  |  |  |  |  |  |  |  |  |
|------------------------|---|---|---|---|---|---|---|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations |  |  | |  |  | | |  |  | |  |  |
| Volume (vph) | 524 | 544 | 57 | 15 | 672 | 101 | 103 | 11 | 12 | 101 | 11 | 322 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 5.5 | 5.5 | | 5.5 | 5.5 | | | 5.5 | 5.5 | | 5.5 | 5.5 |
| Lane Util. Factor | 0.97 | 0.95 | | 1.00 | 0.95 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 0.99 | | 1.00 | 0.99 |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frt | 1.00 | 0.99 | | 1.00 | 0.98 | | | 1.00 | 0.85 | | 1.00 | 0.85 |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.96 | 1.00 | | 0.96 | 1.00 |
| Satd. Flow (prot) | 3502 | 3481 | | 1805 | 3500 | | | 1768 | 1593 | | 1799 | 1594 |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.66 | 1.00 | | 0.66 | 1.00 |
| Satd. Flow (perm) | 3502 | 3481 | | 1805 | 3500 | | | 1229 | 1593 | | 1249 | 1594 |
| Peak-hour factor, PHF | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 |
| Adj. Flow (vph) | 546 | 567 | 59 | 16 | 700 | 105 | 107 | 11 | 12 | 105 | 11 | 335 |
| RTOR Reduction (vph) | 0 | 6 | 0 | 0 | 11 | 0 | 0 | 0 | 10 | 0 | 0 | 282 |
| Lane Group Flow (vph) | 546 | 620 | 0 | 16 | 794 | 0 | 0 | 118 | 2 | 0 | 116 | 53 |
| Confl. Peds. (#/hr) | 8 | | 2 | 2 | | 8 | 1 | | 2 | 2 | | 1 |
| Confl. Bikes (#/hr) | | 1 | | | 3 | | | | | | | |
| Heavy Vehicles (%) | 0% | 2% | 2% | 0% | 1% | 0% | 3% | 0% | 0% | 1% | 0% | 0% |
| Turn Type | Prot | | | Prot | | | Perm | | Perm | Perm | | Perm |
| Protected Phases | 5 | 2 | | 1 | 6 | | | 8 | | | 4 | |
| Permitted Phases | | | | | | | 8 | | 8 | 4 | | 4 |
| Actuated Green, G (s) | 13.8 | 35.6 | | 0.8 | 22.6 | | | 9.7 | 9.7 | | 9.7 | 9.7 |
| Effective Green, g (s) | 14.3 | 36.1 | | 1.3 | 23.1 | | | 10.2 | 10.2 | | 10.2 | 10.2 |
| Actuated g/C Ratio | 0.22 | 0.56 | | 0.02 | 0.36 | | | 0.16 | 0.16 | | 0.16 | 0.16 |
| Clearance Time (s) | 6.0 | 6.0 | | 6.0 | 6.0 | | | 6.0 | 6.0 | | 6.0 | 6.0 |
| Vehicle Extension (s) | 2.3 | 2.5 | | 2.4 | 2.5 | | | 2.4 | 2.4 | | 2.3 | 2.3 |
| Lane Grp Cap (vph) | 781 | 1960 | | 37 | 1261 | | | 196 | 253 | | 199 | 254 |
| v/s Ratio Prot | c0.16 | 0.18 | | 0.01 | c0.23 | | | | | | | |
| v/s Ratio Perm | | | | | | | | c0.10 | 0.00 | | 0.09 | 0.03 |
| v/c Ratio | 0.70 | 0.32 | | 0.43 | 0.63 | | | 0.60 | 0.01 | | 0.58 | 0.21 |
| Uniform Delay, d1 | 22.9 | 7.4 | | 31.0 | 17.0 | | | 25.1 | 22.7 | | 25.0 | 23.4 |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Incremental Delay, d2 | 2.4 | 0.1 | | 5.2 | 0.9 | | | 4.2 | 0.0 | | 3.3 | 0.2 |
| Delay (s) | 25.3 | 7.5 | | 36.3 | 17.8 | | | 29.2 | 22.7 | | 28.2 | 23.7 |
| Level of Service | C | A | | D | B | | | C | C | | C | C |
| Approach Delay (s) | | 15.8 | | | 18.2 | | | 28.6 | | | 24.9 | |
| Approach LOS | | B | | | B | | | C | | | C | |

| Intersection Summary | | | |
|-----------------------------------|-------|----------------------|------|
| HCM Average Control Delay | 18.8 | HCM Level of Service | B |
| HCM Volume to Capacity ratio | 0.64 | | |
| Actuated Cycle Length (s) | 64.1 | Sum of lost time (s) | 16.5 |
| Intersection Capacity Utilization | 63.9% | ICU Level of Service | B |
| Analysis Period (min) | 15 | | |

c Critical Lane Group

HCM Signalized Intersection Capacity Analysis
 17: Tualatin Sherwood Rd & Martinazzi Ave

4/17/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|------|-------|-------|------|-------|------|----------------------|-------|------|------|-------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 67 | 1110 | 137 | 0 | 1086 | 0 | 97 | 215 | 210 | 125 | 371 | 85 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 5.5 | | | 5.5 | | 4.5 | 5.5 | 5.5 | 4.5 | 5.5 | |
| Lane Util. Factor | 1.00 | 0.95 | | | 0.95 | | 1.00 | 1.00 | 1.00 | 1.00 | 0.95 | |
| Frbp, ped/bikes | 1.00 | 1.00 | | | 1.00 | | 1.00 | 1.00 | 0.96 | 1.00 | 1.00 | |
| Flpb, ped/bikes | 1.00 | 1.00 | | | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | |
| Frt | 1.00 | 0.98 | | | 1.00 | | 1.00 | 1.00 | 0.85 | 1.00 | 0.97 | |
| Flt Protected | 0.95 | 1.00 | | | 1.00 | | 0.95 | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (prot) | 1719 | 3428 | | | 3438 | | 1770 | 1863 | 1537 | 1787 | 3465 | |
| Flt Permitted | 0.95 | 1.00 | | | 1.00 | | 0.95 | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (perm) | 1719 | 3428 | | | 3438 | | 1770 | 1863 | 1537 | 1787 | 3465 | |
| Peak-hour factor, PHF | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 |
| Adj. Flow (vph) | 71 | 1181 | 146 | 0 | 1155 | 0 | 103 | 229 | 223 | 133 | 395 | 90 |
| RTOR Reduction (vph) | 0 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 113 | 0 | 20 | 0 |
| Lane Group Flow (vph) | 71 | 1321 | 0 | 0 | 1155 | 0 | 103 | 229 | 110 | 133 | 465 | 0 |
| Confl. Peds. (#/hr) | | | | | | | 6 | | 23 | | | 3 |
| Heavy Vehicles (%) | 5% | 4% | 0% | 0% | 5% | 0% | 2% | 2% | 1% | 1% | 1% | 1% |
| Turn Type | Prot | | | | | | Prot | | Perm | | Prot | |
| Protected Phases | 5 | 2 | | | 6 | | 3 | 8 | | 7 | 4 | |
| Permitted Phases | | | | | | | | | 8 | | | |
| Actuated Green, G (s) | 7.4 | 67.9 | | | 55.5 | | 10.4 | 17.4 | 17.4 | 12.7 | 19.7 | |
| Effective Green, g (s) | 7.9 | 68.4 | | | 56.0 | | 10.9 | 17.9 | 17.9 | 13.2 | 20.2 | |
| Actuated g/C Ratio | 0.07 | 0.59 | | | 0.49 | | 0.09 | 0.16 | 0.16 | 0.11 | 0.18 | |
| Clearance Time (s) | 5.0 | 6.0 | | | 6.0 | | 5.0 | 6.0 | 6.0 | 5.0 | 6.0 | |
| Vehicle Extension (s) | 2.0 | 3.5 | | | 3.5 | | 3.0 | 2.0 | 2.0 | 3.0 | 2.0 | |
| Lane Grp Cap (vph) | 118 | 2039 | | | 1674 | | 168 | 290 | 239 | 205 | 609 | |
| v/s Ratio Prot | 0.04 | c0.39 | | | c0.34 | | 0.06 | c0.12 | | 0.07 | c0.13 | |
| v/s Ratio Perm | | | | | | | | | 0.07 | | | |
| v/c Ratio | 0.60 | 0.65 | | | 0.69 | | 0.61 | 0.79 | 0.46 | 0.65 | 0.76 | |
| Uniform Delay, d1 | 52.0 | 15.4 | | | 22.8 | | 50.0 | 46.7 | 44.2 | 48.7 | 45.1 | |
| Progression Factor | 1.00 | 1.00 | | | 0.51 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | |
| Incremental Delay, d2 | 5.8 | 1.6 | | | 2.1 | | 6.5 | 12.4 | 0.5 | 6.9 | 5.1 | |
| Delay (s) | 57.8 | 17.0 | | | 13.9 | | 56.5 | 59.1 | 44.7 | 55.6 | 50.2 | |
| Level of Service | E | B | | | B | | E | E | D | E | D | |
| Approach Delay (s) | | 19.0 | | | 13.9 | | | 52.8 | | | 51.4 | |
| Approach LOS | | B | | | B | | | D | | | D | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 27.8 | | | | HCM Level of Service | | | C | | |
| HCM Volume to Capacity ratio | | | 0.76 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 115.0 | | | | Sum of lost time (s) | | | 22.0 | | |
| Intersection Capacity Utilization | | | 78.5% | | | | ICU Level of Service | | | D | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

Intersection Sign configuration not allowed in HCM analysis.

Appendix E
2014 Background Operations
Worksheets

HCM Signalized Intersection Capacity Analysis

1: SW Lower Boones Ferry Road & SW Upper Boones Ferry Road

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|-------|-------|-------|-------|------|----------------------|------|------|-------|------|-------|------|
| Lane Configurations | | ↔ | | ↔ | ↔ | | ↔ | ↔ | ↔ | ↔ | ↔ | ↔ |
| Volume (vph) | 1 | 7 | 9 | 469 | 7 | 40 | 0 | 484 | 557 | 59 | 676 | 1 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | | 3.5 | | 3.5 | 3.5 | | | 4.0 | 3.5 | 3.5 | 4.0 | |
| Lane Util. Factor | | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | |
| Frbp, ped/bikes | | 0.92 | | 1.00 | 0.96 | | | 1.00 | 0.98 | 1.00 | 1.00 | |
| Flpb, ped/bikes | | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | |
| Frt | | 0.93 | | 1.00 | 0.87 | | | 1.00 | 0.85 | 1.00 | 1.00 | |
| Flt Protected | | 1.00 | | 0.95 | 1.00 | | | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (prot) | | 1597 | | 1787 | 1575 | | | 1900 | 1571 | 1805 | 1900 | |
| Flt Permitted | | 1.00 | | 0.95 | 1.00 | | | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (perm) | | 1597 | | 1787 | 1575 | | | 1900 | 1571 | 1805 | 1900 | |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 1 | 7 | 9 | 494 | 7 | 42 | 0 | 509 | 586 | 62 | 712 | 1 |
| RTOR Reduction (vph) | 0 | 9 | 0 | 0 | 26 | 0 | 0 | 0 | 157 | 0 | 0 | 0 |
| Lane Group Flow (vph) | 0 | 8 | 0 | 494 | 23 | 0 | 0 | 509 | 429 | 62 | 713 | 0 |
| Confl. Peds. (#/hr) | 15 | | 7 | 7 | | 15 | 7 | | 8 | 8 | | 7 |
| Heavy Vehicles (%) | 0% | 2% | 1% | 1% | 3% | 0% | 2% | 0% | 1% | 0% | 0% | 0% |
| Turn Type | Split | | | Split | | | Prot | | pm+ov | | Prot | |
| Protected Phases | 8 | 8 | | 4 | 4 | | 1 | 6 | 4 | 5 | 2 | |
| Permitted Phases | | | | | | | | | 6 | | | |
| Actuated Green, G (s) | | 1.7 | | 32.0 | 32.0 | | | 28.3 | 60.3 | 5.3 | 37.6 | |
| Effective Green, g (s) | | 2.2 | | 32.5 | 32.5 | | | 28.8 | 61.3 | 5.8 | 38.1 | |
| Actuated g/C Ratio | | 0.03 | | 0.39 | 0.39 | | | 0.34 | 0.73 | 0.07 | 0.45 | |
| Clearance Time (s) | | 4.0 | | 4.0 | 4.0 | | | 4.5 | 4.0 | 4.0 | 4.5 | |
| Vehicle Extension (s) | | 2.5 | | 2.2 | 2.2 | | | 3.5 | 2.2 | 2.2 | 3.5 | |
| Lane Grp Cap (vph) | | 42 | | 693 | 611 | | | 653 | 1149 | 125 | 864 | |
| v/s Ratio Prot | | c0.01 | | c0.28 | 0.01 | | | 0.27 | 0.14 | 0.03 | c0.38 | |
| v/s Ratio Perm | | | | | | | | | 0.13 | | | |
| v/c Ratio | | 0.20 | | 0.71 | 0.04 | | | 0.78 | 0.37 | 0.50 | 0.83 | |
| Uniform Delay, d1 | | 39.9 | | 21.7 | 15.9 | | | 24.7 | 4.2 | 37.6 | 19.9 | |
| Progression Factor | | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | |
| Incremental Delay, d2 | | 1.7 | | 3.0 | 0.0 | | | 6.0 | 0.1 | 1.6 | 6.6 | |
| Delay (s) | | 41.6 | | 24.7 | 16.0 | | | 30.7 | 4.3 | 39.2 | 26.6 | |
| Level of Service | | D | | C | B | | | C | A | D | C | |
| Approach Delay (s) | | 41.6 | | | 23.9 | | | 16.5 | | | 27.6 | |
| Approach LOS | | D | | | C | | | B | | | C | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 21.9 | | | HCM Level of Service | | | | C | | |
| HCM Volume to Capacity ratio | | | 0.76 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 83.8 | | | Sum of lost time (s) | | | 11.0 | | | |
| Intersection Capacity Utilization | | | 81.6% | | | ICU Level of Service | | | | D | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis

2: SW Boones Ferry Rd & SW Tualatin Rd

4/15/2013



| Movement | WBL | WBR | NBT | NBR | SBL | SBT |
|------------------------|------|-------|-------|-------|------|------|
| Lane Configurations | ↙↙ | ↘ | ↑ | ↘ | ↙ | ↑ |
| Volume (vph) | 410 | 834 | 200 | 298 | 443 | 365 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 3.5 | 3.5 | 3.0 | 3.5 | 3.5 | 3.5 |
| Lane Util. Factor | 0.97 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Frbp, ped/bikes | 1.00 | 0.98 | 1.00 | 0.98 | 1.00 | 1.00 |
| Flpb, ped/bikes | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Frt | 1.00 | 0.85 | 1.00 | 0.85 | 1.00 | 1.00 |
| Flt Protected | 0.95 | 1.00 | 1.00 | 1.00 | 0.95 | 1.00 |
| Satd. Flow (prot) | 3467 | 1589 | 1900 | 1571 | 1805 | 1900 |
| Flt Permitted | 0.95 | 1.00 | 1.00 | 1.00 | 0.95 | 1.00 |
| Satd. Flow (perm) | 3467 | 1589 | 1900 | 1571 | 1805 | 1900 |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 432 | 878 | 211 | 314 | 466 | 384 |
| RTOR Reduction (vph) | 0 | 196 | 0 | 74 | 0 | 0 |
| Lane Group Flow (vph) | 432 | 682 | 211 | 240 | 466 | 384 |
| Confl. Peds. (#/hr) | 7 | 15 | | 8 | 8 | |
| Heavy Vehicles (%) | 1% | 0% | 0% | 1% | 0% | 0% |
| Turn Type | | pm+ov | | pm+ov | Prot | |
| Protected Phases | 8 | 1 | 2 | 8 | 1 | 6 |
| Permitted Phases | | 8 | | 2 | | |
| Actuated Green, G (s) | 11.6 | 32.0 | 13.4 | 25.0 | 20.4 | 37.3 |
| Effective Green, g (s) | 12.1 | 33.0 | 13.9 | 26.0 | 20.9 | 37.8 |
| Actuated g/C Ratio | 0.21 | 0.58 | 0.24 | 0.46 | 0.37 | 0.66 |
| Clearance Time (s) | 4.0 | 4.0 | 3.5 | 4.0 | 4.0 | 4.0 |
| Vehicle Extension (s) | 3.0 | 2.0 | 5.0 | 3.0 | 2.0 | 2.0 |
| Lane Grp Cap (vph) | 737 | 1019 | 464 | 718 | 663 | 1262 |
| v/s Ratio Prot | 0.12 | c0.25 | c0.11 | 0.07 | 0.26 | 0.20 |
| v/s Ratio Perm | | 0.18 | | 0.08 | | |
| v/c Ratio | 0.59 | 0.67 | 0.45 | 0.33 | 0.70 | 0.30 |
| Uniform Delay, d1 | 20.1 | 8.2 | 18.3 | 9.9 | 15.4 | 4.0 |
| Progression Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Incremental Delay, d2 | 1.2 | 1.3 | 1.5 | 0.3 | 2.8 | 0.0 |
| Delay (s) | 21.3 | 9.5 | 19.8 | 10.2 | 18.1 | 4.1 |
| Level of Service | C | A | B | B | B | A |
| Approach Delay (s) | 13.4 | | 14.0 | | | 11.8 |
| Approach LOS | B | | B | | | B |

| Intersection Summary | | | |
|-----------------------------------|-------|----------------------|-----|
| HCM Average Control Delay | 13.0 | HCM Level of Service | B |
| HCM Volume to Capacity ratio | 0.61 | | |
| Actuated Cycle Length (s) | 56.9 | Sum of lost time (s) | 6.5 |
| Intersection Capacity Utilization | 71.6% | ICU Level of Service | C |
| Analysis Period (min) | 15 | | |
| c Critical Lane Group | | | |

HCM Signalized Intersection Capacity Analysis
 3: SW Boones Fe & SW Martinazzi Ave

4/15/2013

| | → | ↘ | ↙ | ← | ↖ | ↗ |
|-----------------------------------|-------|------|-------|------|----------------------|-------|
| Movement | EBT | EBR | WBL | WBT | NBL | NBR |
| Lane Configurations | ↑ | ↗ | ↙ | ↑ | ↖ | ↗ |
| Volume (vph) | 664 | 175 | 422 | 930 | 325 | 385 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 4.5 | 4.5 | 4.5 | 4.5 | 4.5 |
| Lane Util. Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Frbp, ped/bikes | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 0.98 |
| Flpb, ped/bikes | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Frt | 1.00 | 0.85 | 1.00 | 1.00 | 1.00 | 0.85 |
| Flt Protected | 1.00 | 1.00 | 0.95 | 1.00 | 0.95 | 1.00 |
| Satd. Flow (prot) | 1863 | 1599 | 1787 | 1845 | 1770 | 1572 |
| Flt Permitted | 1.00 | 1.00 | 0.95 | 1.00 | 0.95 | 1.00 |
| Satd. Flow (perm) | 1863 | 1599 | 1787 | 1845 | 1770 | 1572 |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 699 | 184 | 444 | 979 | 342 | 405 |
| RTOR Reduction (vph) | 0 | 51 | 0 | 0 | 0 | 38 |
| Lane Group Flow (vph) | 699 | 133 | 444 | 979 | 342 | 367 |
| Confl. Peds. (#/hr) | | 7 | 7 | | 7 | 8 |
| Confl. Bikes (#/hr) | 4 | | 2 | 10 | 1 | |
| Heavy Vehicles (%) | 2% | 1% | 1% | 3% | 2% | 1% |
| Turn Type | | Prot | Prot | | | pm+ov |
| Protected Phases | 2 | 2 | 1 | 6 | 8 | 1 |
| Permitted Phases | | | | | 8 | 8 |
| Actuated Green, G (s) | 41.2 | 41.2 | 29.9 | 76.1 | 21.1 | 51.0 |
| Effective Green, g (s) | 41.7 | 41.7 | 30.4 | 76.6 | 21.6 | 52.0 |
| Actuated g/C Ratio | 0.39 | 0.39 | 0.28 | 0.71 | 0.20 | 0.49 |
| Clearance Time (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 |
| Lane Grp Cap (vph) | 725 | 622 | 507 | 1318 | 357 | 829 |
| v/s Ratio Prot | c0.38 | 0.08 | c0.25 | 0.53 | c0.19 | 0.13 |
| v/s Ratio Perm | | | | | | 0.11 |
| v/c Ratio | 0.96 | 0.21 | 0.88 | 0.74 | 0.96 | 0.44 |
| Uniform Delay, d1 | 32.0 | 21.8 | 36.6 | 9.3 | 42.4 | 18.1 |
| Progression Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Incremental Delay, d2 | 24.7 | 0.2 | 15.5 | 2.3 | 36.3 | 0.4 |
| Delay (s) | 56.7 | 22.0 | 52.1 | 11.6 | 78.6 | 18.5 |
| Level of Service | E | C | D | B | E | B |
| Approach Delay (s) | 49.5 | | | 24.2 | 46.0 | |
| Approach LOS | D | | | C | D | |
| Intersection Summary | | | | | | |
| HCM Average Control Delay | | | 36.9 | | HCM Level of Service | D |
| HCM Volume to Capacity ratio | | | 0.93 | | | |
| Actuated Cycle Length (s) | | | 107.2 | | Sum of lost time (s) | 13.5 |
| Intersection Capacity Utilization | | | 87.6% | | ICU Level of Service | E |
| Analysis Period (min) | | | 15 | | | |

c Critical Lane Group











HCM Unsignalized Intersection Capacity Analysis
 4: Site Entrance 1 & Martinazzi Ave

4/15/2013

| | ↙ | ↖ | ↑ | ↗ | ↘ | ↓ |
|-----------------------------------|-------|------|----------------------|-------|------|------|
| Movement | WBL | WBR | NBT | NBR | SBL | SBT |
| Lane Configurations | ↙ | ↖ | ↗ | | ↙ | ↑ |
| Volume (veh/h) | 30 | 110 | 598 | 70 | 145 | 450 |
| Sign Control | Stop | | Free | | Free | |
| Grade | 0% | | 0% | | 0% | |
| Peak Hour Factor | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 |
| Hourly flow rate (vph) | 33 | 121 | 657 | 77 | 159 | 495 |
| Pedestrians | 25 | | 16 | | 26 | |
| Lane Width (ft) | 12.0 | | 12.0 | | 12.0 | |
| Walking Speed (ft/s) | 4.0 | | 4.0 | | 4.0 | |
| Percent Blockage | 2 | | 1 | | 2 | |
| Right turn flare (veh) | | | | | | |
| Median type | None | | | TWLTL | | |
| Median storage (veh) | 2 | | | | | |
| Upstream signal (ft) | 428 | | | 355 | | |
| pX, platoon unblocked | 0.91 | 0.91 | | | 0.91 | |
| vC, conflicting volume | 1550 | 747 | | | 759 | |
| vC1, stage 1 conf vol | 721 | | | | | |
| vC2, stage 2 conf vol | 829 | | | | | |
| vCu, unblocked vol | 1555 | 668 | | | 682 | |
| tC, single (s) | 6.4 | 6.2 | | | 4.1 | |
| tC, 2 stage (s) | 5.4 | | | | | |
| tF (s) | 3.5 | 3.3 | | | 2.2 | |
| p0 queue free % | 88 | 69 | | | 80 | |
| cM capacity (veh/h) | 276 | 393 | | | 795 | |
| Direction, Lane # | WB 1 | WB 2 | NB 1 | SB 1 | SB 2 | |
| Volume Total | 33 | 121 | 734 | 159 | 495 | |
| Volume Left | 33 | 0 | 0 | 159 | 0 | |
| Volume Right | 0 | 121 | 77 | 0 | 0 | |
| cSH | 276 | 393 | 1700 | 795 | 1700 | |
| Volume to Capacity | 0.12 | 0.31 | 0.43 | 0.20 | 0.29 | |
| Queue Length 95th (ft) | 10 | 33 | 0 | 19 | 0 | |
| Control Delay (s) | 19.8 | 18.2 | 0.0 | 10.7 | 0.0 | |
| Lane LOS | C | | | B | | |
| Approach Delay (s) | 18.5 | | 0.0 | 2.6 | | |
| Approach LOS | C | | | | | |
| Intersection Summary | | | | | | |
| Average Delay | 3.0 | | | | | |
| Intersection Capacity Utilization | 63.1% | | ICU Level of Service | | B | |
| Analysis Period (min) | 15 | | | | | |

HCM Unsignalized Intersection Capacity Analysis
 5: Seneca St & Martinazzi Ave

4/15/2013

| |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|
| Movement | EBL | EBR | NBL | NBT | SBT | SBR |
| Lane Configurations |  | |  |  |  | |
| Volume (veh/h) | 40 | 80 | 85 | 628 | 431 | 50 |
| Sign Control | Stop | | | Free | Free | |
| Grade | 0% | | | 0% | 0% | |
| Peak Hour Factor | 0.89 | 0.89 | 0.89 | 0.89 | 0.89 | 0.89 |
| Hourly flow rate (vph) | 45 | 90 | 96 | 706 | 484 | 56 |
| Pedestrians | | | | | | |
| Lane Width (ft) | | | | | | |
| Walking Speed (ft/s) | | | | | | |
| Percent Blockage | | | | | | |
| Right turn flare (veh) | | | | | | |
| Median type | | | | None | None | |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | | | 308 | 475 | |
| pX, platoon unblocked | 0.89 | | | | | |
| vC, conflicting volume | 1409 | 512 | 540 | | | |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 1398 | 512 | 540 | | | |
| tC, single (s) | 6.4 | 6.2 | 4.1 | | | |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 3.5 | 3.3 | 2.2 | | | |
| p0 queue free % | 65 | 84 | 91 | | | |
| cM capacity (veh/h) | 127 | 566 | 1038 | | | |
| Direction, Lane # | EB 1 | NB 1 | NB 2 | SB 1 | | |
| Volume Total | 135 | 96 | 706 | 540 | | |
| Volume Left | 45 | 96 | 0 | 0 | | |
| Volume Right | 90 | 0 | 0 | 56 | | |
| cSH | 263 | 1038 | 1700 | 1700 | | |
| Volume to Capacity | 0.51 | 0.09 | 0.42 | 0.32 | | |
| Queue Length 95th (ft) | 70 | 8 | 0 | 0 | | |
| Control Delay (s) | 32.2 | 8.8 | 0.0 | 0.0 | | |
| Lane LOS | D | A | | | | |
| Approach Delay (s) | 32.2 | 1.1 | | 0.0 | | |
| Approach LOS | D | | | | | |
| Intersection Summary | | | | | | |
| Average Delay | | | 3.5 | | | |
| Intersection Capacity Utilization | | | 47.6% | | ICU Level of Service | A |
| Analysis Period (min) | | | 15 | | | |

HCM Unsignalized Intersection Capacity Analysis
 6: Site Entrance 2 & Martinazzi Ave

4/15/2013













| Movement | WBL | WBR | NBT | NBR | SBL | SBT |
|------------------------|------|------|------|------|------|------|
| Lane Configurations | YY | | P | | | 4↑ |
| Volume (veh/h) | 0 | 32 | 681 | 6 | 10 | 502 |
| Sign Control | Stop | | Free | | | Free |
| Grade | 0% | | 0% | | | 0% |
| Peak Hour Factor | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 |
| Hourly flow rate (vph) | 0 | 35 | 748 | 7 | 11 | 552 |
| Pedestrians | 25 | | 16 | | | 26 |
| Lane Width (ft) | 12.0 | | 12.0 | | | 12.0 |
| Walking Speed (ft/s) | 4.0 | | 4.0 | | | 4.0 |
| Percent Blockage | 2 | | 1 | | | 2 |
| Right turn flare (veh) | | | | | | |
| Median type | | | None | | | None |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | | 227 | | | 556 |
| pX, platoon unblocked | 0.86 | 0.86 | | | 0.86 | |
| vC, conflicting volume | 1090 | 803 | | | 780 | |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 1023 | 687 | | | 661 | |
| tC, single (s) | 6.9 | 7.0 | | | 4.2 | |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 3.5 | 3.3 | | | 2.2 | |
| p0 queue free % | 100 | 89 | | | 99 | |
| cM capacity (veh/h) | 185 | 314 | | | 759 | |

| Direction, Lane # | WB 1 | NB 1 | SB 1 | SB 2 |
|------------------------|------|------|------|------|
| Volume Total | 35 | 755 | 195 | 368 |
| Volume Left | 0 | 0 | 11 | 0 |
| Volume Right | 35 | 7 | 0 | 0 |
| cSH | 314 | 1700 | 759 | 1700 |
| Volume to Capacity | 0.11 | 0.44 | 0.01 | 0.22 |
| Queue Length 95th (ft) | 10 | 0 | 1 | 0 |
| Control Delay (s) | 17.9 | 0.0 | 0.7 | 0.0 |
| Lane LOS | C | | A | |
| Approach Delay (s) | 17.9 | 0.0 | 0.2 | |
| Approach LOS | C | | | |

| Intersection Summary | | | |
|-----------------------------------|--|-------|------------------------|
| Average Delay | | 0.6 | |
| Intersection Capacity Utilization | | 52.5% | ICU Level of Service A |
| Analysis Period (min) | | 15 | |

HCM Unsignalized Intersection Capacity Analysis
 7: RO Only & Martinazzi Ave

4/15/2013

| |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|--|
| Movement | WBL | WBR | NBT | NBR | SBL | SBT |
| Lane Configurations | |  |  | | |   |
| Volume (veh/h) | 0 | 12 | 675 | 0 | 0 | 502 |
| Sign Control | Stop | | Free | | | Free |
| Grade | 0% | | 0% | | | 0% |
| Peak Hour Factor | 0.89 | 0.89 | 0.89 | 0.89 | 0.89 | 0.89 |
| Hourly flow rate (vph) | 0 | 13 | 758 | 0 | 0 | 564 |
| Pedestrians | | | | | | |
| Lane Width (ft) | | | | | | |
| Walking Speed (ft/s) | | | | | | |
| Percent Blockage | | | | | | |
| Right turn flare (veh) | | | | | | |
| Median type | | | None | | | None |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | | 125 | | | 658 |
| pX, platoon unblocked | 0.85 | 0.85 | | | 0.85 | |
| vC, conflicting volume | 1040 | 758 | | | 758 | |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 960 | 629 | | | 629 | |
| tC, single (s) | 6.8 | 6.9 | | | 4.1 | |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 3.5 | 3.3 | | | 2.2 | |
| p0 queue free % | 100 | 96 | | | 100 | |
| cM capacity (veh/h) | 220 | 366 | | | 820 | |
| Direction, Lane # | WB 1 | NB 1 | SB 1 | SB 2 | | |
| Volume Total | 13 | 758 | 282 | 282 | | |
| Volume Left | 0 | 0 | 0 | 0 | | |
| Volume Right | 13 | 0 | 0 | 0 | | |
| cSH | 366 | 1700 | 1700 | 1700 | | |
| Volume to Capacity | 0.04 | 0.45 | 0.17 | 0.17 | | |
| Queue Length 95th (ft) | 3 | 0 | 0 | 0 | | |
| Control Delay (s) | 15.2 | 0.0 | 0.0 | 0.0 | | |
| Lane LOS | C | | | | | |
| Approach Delay (s) | 15.2 | 0.0 | 0.0 | | | |
| Approach LOS | C | | | | | |
| Intersection Summary | | | | | | |
| Average Delay | | | 0.2 | | | |
| Intersection Capacity Utilization | | | 45.5% | | ICU Level of Service | A |
| Analysis Period (min) | | | 15 | | | |

HCM Signalized Intersection Capacity Analysis
 8: Nyberg St & Martinazzi Ave

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|------|------|-------|-------|------|------|-------|------|------|------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 29 | 10 | 100 | 349 | 55 | 337 | 27 | 308 | 19 | 0 | 492 | 10 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.0 | 4.0 | | 4.0 | 4.0 | 4.0 | 4.0 | 4.0 | | | 4.0 | |
| Lane Util. Factor | 1.00 | 1.00 | | 0.95 | 0.95 | 1.00 | 1.00 | 1.00 | | | 0.95 | |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 0.96 | 1.00 | 1.00 | | | 1.00 | |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | 1.00 | |
| Frt | 1.00 | 0.86 | | 1.00 | 1.00 | 0.85 | 1.00 | 0.99 | | | 1.00 | |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 0.96 | 1.00 | 0.95 | 1.00 | | | 1.00 | |
| Satd. Flow (prot) | 1805 | 1626 | | 1698 | 1728 | 1528 | 1682 | 1861 | | | 3562 | |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 0.96 | 1.00 | 0.41 | 1.00 | | | 1.00 | |
| Satd. Flow (perm) | 1805 | 1626 | | 1698 | 1728 | 1528 | 719 | 1861 | | | 3562 | |
| Peak-hour factor, PHF | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 |
| Adj. Flow (vph) | 32 | 11 | 110 | 384 | 60 | 370 | 30 | 338 | 21 | 0 | 541 | 11 |
| RTOR Reduction (vph) | 0 | 97 | 0 | 0 | 0 | 279 | 0 | 3 | 0 | 0 | 2 | 0 |
| Lane Group Flow (vph) | 32 | 24 | 0 | 219 | 225 | 91 | 30 | 356 | 0 | 0 | 550 | 0 |
| Confl. Peds. (#/hr) | 10 | | | | | 10 | 6 | | 19 | 19 | | 6 |
| Confl. Bikes (#/hr) | | | | | | 2 | | | | | | 3 |
| Heavy Vehicles (%) | 0% | 0% | 1% | 1% | 0% | 2% | 7% | 1% | 0% | 0% | 1% | 0% |
| Turn Type | Split | | | Split | | Perm | Perm | | | | | |
| Protected Phases | 8 | 8 | | 4 | 4 | | | 6 | | | | 2 |
| Permitted Phases | | | | | | 4 | 6 | | | | | |
| Actuated Green, G (s) | 4.8 | 4.8 | | 10.5 | 10.5 | 10.5 | 15.9 | 15.9 | | | | 15.9 |
| Effective Green, g (s) | 5.3 | 5.3 | | 11.0 | 11.0 | 11.0 | 16.4 | 16.4 | | | | 16.4 |
| Actuated g/C Ratio | 0.12 | 0.12 | | 0.25 | 0.25 | 0.25 | 0.37 | 0.37 | | | | 0.37 |
| Clearance Time (s) | 4.5 | 4.5 | | 4.5 | 4.5 | 4.5 | 4.5 | 4.5 | | | | 4.5 |
| Vehicle Extension (s) | 2.5 | 2.5 | | 2.5 | 2.5 | 2.5 | 5.0 | 5.0 | | | | 5.0 |
| Lane Grp Cap (vph) | 214 | 193 | | 418 | 425 | 376 | 264 | 683 | | | | 1307 |
| v/s Ratio Prot | c0.02 | 0.01 | | 0.13 | c0.13 | | | c0.19 | | | | 0.15 |
| v/s Ratio Perm | | | | | | 0.06 | 0.04 | | | | | |
| v/c Ratio | 0.15 | 0.12 | | 0.52 | 0.53 | 0.24 | 0.11 | 0.52 | | | | 0.42 |
| Uniform Delay, d1 | 17.7 | 17.6 | | 14.6 | 14.6 | 13.5 | 9.3 | 11.1 | | | | 10.6 |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | | 1.00 |
| Incremental Delay, d2 | 0.2 | 0.2 | | 0.9 | 0.9 | 0.2 | 0.4 | 1.4 | | | | 0.5 |
| Delay (s) | 17.9 | 17.8 | | 15.5 | 15.5 | 13.8 | 9.7 | 12.4 | | | | 11.1 |
| Level of Service | B | B | | B | B | B | A | B | | | | B |
| Approach Delay (s) | | 17.9 | | | 14.7 | | | 12.2 | | | | 11.1 |
| Approach LOS | | B | | | B | | | B | | | | B |

| Intersection Summary | | | |
|-----------------------------------|-------|----------------------|------|
| HCM Average Control Delay | 13.4 | HCM Level of Service | B |
| HCM Volume to Capacity ratio | 0.46 | | |
| Actuated Cycle Length (s) | 44.7 | Sum of lost time (s) | 12.0 |
| Intersection Capacity Utilization | 56.1% | ICU Level of Service | B |
| Analysis Period (min) | 15 | | |

c Critical Lane Group

HCM Unsignalized Intersection Capacity Analysis
 9: Nyberg St & Site Entrance 3

4/15/2013



| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
|------------------------|------|------|------|------|------|------|
| Lane Configurations | ↰ | | ↱↰ | | | ↰ |
| Volume (veh/h) | 28 | 0 | 658 | 40 | 0 | 82 |
| Sign Control | | Free | Free | | Stop | |
| Grade | | 0% | 0% | | 0% | |
| Peak Hour Factor | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 |
| Hourly flow rate (vph) | 32 | 0 | 748 | 45 | 0 | 93 |
| Pedestrians | | | | | 5 | |
| Lane Width (ft) | | | | | 12.0 | |
| Walking Speed (ft/s) | | | | | 4.0 | |
| Percent Blockage | | | | | 0 | |
| Right turn flare (veh) | | | | | | |
| Median type | | None | None | | | |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | 243 | | | | |
| pX, platoon unblocked | | | | | | |
| vC, conflicting volume | 798 | | | | 839 | 402 |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 798 | | | | 839 | 402 |
| tC, single (s) | 4.1 | | | | 6.8 | 6.9 |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 2.2 | | | | 3.5 | 3.3 |
| p0 queue free % | 96 | | | | 100 | 85 |
| cM capacity (veh/h) | 830 | | | | 295 | 601 |

| Direction, Lane # | EB 1 | WB 1 | WB 2 | SB 1 |
|------------------------|------|------|------|------|
| Volume Total | 32 | 498 | 295 | 93 |
| Volume Left | 32 | 0 | 0 | 0 |
| Volume Right | 0 | 0 | 45 | 93 |
| cSH | 830 | 1700 | 1700 | 601 |
| Volume to Capacity | 0.04 | 0.29 | 0.17 | 0.15 |
| Queue Length 95th (ft) | 3 | 0 | 0 | 14 |
| Control Delay (s) | 9.5 | 0.0 | 0.0 | 12.1 |
| Lane LOS | A | | | B |
| Approach Delay (s) | 9.5 | 0.0 | | 12.1 |
| Approach LOS | | | | B |

| Intersection Summary | | | |
|-----------------------------------|--|-------|------------------------|
| Average Delay | | 1.6 | |
| Intersection Capacity Utilization | | 31.2% | ICU Level of Service A |
| Analysis Period (min) | | 15 | |

HCM Signalized Intersection Capacity Analysis
 10: Tualatin Sherwood Rd & Site Entrance 4

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|------|-------|------|-------|------|------|------|------|-------|------|-------|------|
| Lane Configurations | ↵ | ↕↕↕ | | ↵↵ | ↕↕↕ | | | ↕ | ↕ | | ↕ | ↕ |
| Volume (vph) | 30 | 1930 | 40 | 232 | 1725 | 72 | 36 | 10 | 236 | 182 | 24 | 44 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 6.0 | | 4.5 | 6.0 | | | 5.0 | 4.5 | | 5.0 | 5.0 |
| Lane Util. Factor | 1.00 | *0.75 | | 0.97 | 0.91 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 0.97 |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 0.99 | 1.00 | | 1.00 | 1.00 |
| Frt | 1.00 | 1.00 | | 1.00 | 0.99 | | | 1.00 | 0.85 | | 1.00 | 0.85 |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.96 | 1.00 | | 0.96 | 1.00 |
| Satd. Flow (prot) | 1805 | 4100 | | 3502 | 4957 | | | 1768 | 1599 | | 1803 | 1565 |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.54 | 1.00 | | 0.72 | 1.00 |
| Satd. Flow (perm) | 1805 | 4100 | | 3502 | 4957 | | | 1000 | 1599 | | 1350 | 1565 |
| Peak-hour factor, PHF | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 |
| Adj. Flow (vph) | 31 | 1969 | 41 | 237 | 1760 | 73 | 37 | 10 | 241 | 186 | 24 | 45 |
| RTOR Reduction (vph) | 0 | 1 | 0 | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 37 |
| Lane Group Flow (vph) | 31 | 2009 | 0 | 237 | 1830 | 0 | 0 | 47 | 241 | 0 | 210 | 8 |
| Confl. Peds. (#/hr) | | | 2 | | | 8 | 15 | | | | | 15 |
| Confl. Bikes (#/hr) | | | | | 1 | | | 1 | | 1 | | |
| Heavy Vehicles (%) | 0% | 4% | 0% | 0% | 4% | 0% | 3% | 0% | 1% | 1% | 0% | 0% |
| Turn Type | Prot | | | Prot | | | Perm | | pm+ov | Perm | | Perm |
| Protected Phases | 5 | 2 | | 1 | 6 | | | 8 | 1 | | 4 | |
| Permitted Phases | | | | | | | 8 | | 8 | 4 | | 4 |
| Actuated Green, G (s) | 5.4 | 73.7 | | 11.8 | 80.1 | | | 22.5 | 34.3 | | 22.5 | 22.5 |
| Effective Green, g (s) | 5.9 | 74.2 | | 12.3 | 80.6 | | | 23.0 | 35.3 | | 23.0 | 23.0 |
| Actuated g/C Ratio | 0.05 | 0.59 | | 0.10 | 0.64 | | | 0.18 | 0.28 | | 0.18 | 0.18 |
| Clearance Time (s) | 5.0 | 6.5 | | 5.0 | 6.5 | | | 5.5 | 5.0 | | 5.5 | 5.5 |
| Vehicle Extension (s) | 2.5 | 4.0 | | 2.5 | 4.0 | | | 2.5 | 2.5 | | 2.5 | 2.5 |
| Lane Grp Cap (vph) | 85 | 2434 | | 345 | 3196 | | | 184 | 452 | | 248 | 288 |
| v/s Ratio Prot | 0.02 | c0.49 | | c0.07 | 0.37 | | | | 0.05 | | c0.16 | 0.01 |
| v/s Ratio Perm | | | | | | | | 0.05 | 0.10 | | | 0.01 |
| v/c Ratio | 0.36 | 0.83 | | 0.69 | 0.57 | | | 0.26 | 0.53 | | 0.85 | 0.03 |
| Uniform Delay, d1 | 57.7 | 20.2 | | 54.5 | 12.5 | | | 43.7 | 37.9 | | 49.3 | 41.8 |
| Progression Factor | 0.75 | 0.48 | | 1.00 | 0.97 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Incremental Delay, d2 | 0.9 | 1.7 | | 3.7 | 0.5 | | | 0.5 | 0.9 | | 22.2 | 0.0 |
| Delay (s) | 44.1 | 11.5 | | 58.4 | 12.7 | | | 44.2 | 38.8 | | 71.5 | 41.9 |
| Level of Service | D | B | | E | B | | | D | D | | E | D |
| Approach Delay (s) | | 12.0 | | | 17.9 | | | 39.7 | | | 66.3 | |
| Approach LOS | | B | | | B | | | D | | | E | |

| Intersection Summary | | | |
|-----------------------------------|-------|----------------------|------|
| HCM Average Control Delay | 19.3 | HCM Level of Service | B |
| HCM Volume to Capacity ratio | 0.81 | | |
| Actuated Cycle Length (s) | 125.0 | Sum of lost time (s) | 15.5 |
| Intersection Capacity Utilization | 82.1% | ICU Level of Service | E |
| Analysis Period (min) | 15 | | |

c Critical Lane Group

HCM Unsignalized Intersection Capacity Analysis
 11: Tualatin Sherwood Rd & 75th Ave

4/15/2013



| Movement | EBL | EBT | WBT | WBR | SBL | SBR | |
|-----------------------------------|------|------|-------|------|----------------------|------|------|
| Lane Configurations | | ↑↑↑ | ↑↑↑ | | | ↑ | |
| Volume (veh/h) | 0 | 2295 | 1995 | 35 | 0 | 4 | |
| Sign Control | | Free | Free | | Stop | | |
| Grade | | 0% | 0% | | 0% | | |
| Peak Hour Factor | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | |
| Hourly flow rate (vph) | 0 | 2318 | 2015 | 35 | 0 | 4 | |
| Pedestrians | | | | | 1 | | |
| Lane Width (ft) | | | | | 12.0 | | |
| Walking Speed (ft/s) | | | | | 4.0 | | |
| Percent Blockage | | | | | 0 | | |
| Right turn flare (veh) | | | | | | | |
| Median type | | None | None | | | | |
| Median storage (veh) | | | | | | | |
| Upstream signal (ft) | | 373 | 260 | | | | |
| pX, platoon unblocked | 0.80 | | | | 0.73 | 0.80 | |
| vC, conflicting volume | 2052 | | | | 2807 | 690 | |
| vC1, stage 1 conf vol | | | | | | | |
| vC2, stage 2 conf vol | | | | | | | |
| vCu, unblocked vol | 1447 | | | | 355 | 0 | |
| tC, single (s) | 4.1 | | | | 6.8 | 7.0 | |
| tC, 2 stage (s) | | | | | | | |
| tF (s) | 2.2 | | | | 3.5 | 3.3 | |
| p0 queue free % | 100 | | | | 100 | 100 | |
| cM capacity (veh/h) | 380 | | | | 450 | 866 | |
| Direction, Lane # | EB 1 | EB 2 | EB 3 | WB 1 | WB 2 | WB 3 | SB 1 |
| Volume Total | 773 | 773 | 773 | 806 | 806 | 438 | 4 |
| Volume Left | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Volume Right | 0 | 0 | 0 | 0 | 0 | 35 | 4 |
| cSH | 1700 | 1700 | 1700 | 1700 | 1700 | 1700 | 866 |
| Volume to Capacity | 0.45 | 0.45 | 0.45 | 0.47 | 0.47 | 0.26 | 0.00 |
| Queue Length 95th (ft) | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Control Delay (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 9.2 |
| Lane LOS | | | | | | | A |
| Approach Delay (s) | 0.0 | | | 0.0 | | | 9.2 |
| Approach LOS | | | | | | | A |
| Intersection Summary | | | | | | | |
| Average Delay | | | 0.0 | | | | |
| Intersection Capacity Utilization | | | 49.3% | | ICU Level of Service | | A |
| Analysis Period (min) | | | 15 | | | | |













HCM Signalized Intersection Capacity Analysis
 12: Tualatin Sherwood Rd & I-5 SB Ramps

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|------|-------|-------|------|-------|----------------------|------|------|------|-------|------|--------|
| Lane Configurations | | ↑↑↑ | ↑ | ↑ | ↑↑ | | | | | ↑ | ↑ | ↑↑ |
| Volume (vph) | 0 | 1514 | 835 | 123 | 1001 | 0 | 0 | 0 | 0 | 659 | 5 | 1060 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | | 5.5 | 5.5 | 5.5 | 5.5 | | | | | 5.5 | 5.5 | 5.5 |
| Lane Util. Factor | | *0.75 | 1.00 | 1.00 | 0.95 | | | | | 0.95 | 0.95 | 0.88 |
| Frbp, ped/bikes | | 1.00 | 1.00 | 1.00 | 1.00 | | | | | 1.00 | 1.00 | 1.00 |
| Flpb, ped/bikes | | 1.00 | 1.00 | 1.00 | 1.00 | | | | | 1.00 | 1.00 | 1.00 |
| Frt | | 1.00 | 0.85 | 1.00 | 1.00 | | | | | 1.00 | 1.00 | 0.85 |
| Flt Protected | | 1.00 | 1.00 | 0.95 | 1.00 | | | | | 0.95 | 0.95 | 1.00 |
| Satd. Flow (prot) | | 4150 | 1568 | 1787 | 3471 | | | | | 1681 | 1682 | 2760 |
| Flt Permitted | | 1.00 | 1.00 | 0.95 | 1.00 | | | | | 0.95 | 0.95 | 1.00 |
| Satd. Flow (perm) | | 4150 | 1568 | 1787 | 3471 | | | | | 1681 | 1682 | 2760 |
| Peak-hour factor, PHF | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 |
| Adj. Flow (vph) | 0 | 1529 | 843 | 124 | 1011 | 0 | 0 | 0 | 0 | 666 | 5 | 1071 |
| RTOR Reduction (vph) | 0 | 0 | 350 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 30 |
| Lane Group Flow (vph) | 0 | 1529 | 493 | 124 | 1011 | 0 | 0 | 0 | 0 | 333 | 338 | 1041 |
| Confl. Bikes (#/hr) | | 1 | | | 2 | | | | | | | |
| Heavy Vehicles (%) | 0% | 3% | 3% | 1% | 4% | 0% | 0% | 0% | 0% | 2% | 20% | 3% |
| Turn Type | | | Perm | Prot | | | | | | Split | | custom |
| Protected Phases | | 2 | | 1 | 6 | | | | | 4 | 4 | 4.5 |
| Permitted Phases | | | 2 | | | | | | | | | |
| Actuated Green, G (s) | | 58.2 | 58.2 | 11.1 | 53.3 | | | | | 37.7 | 37.7 | 59.7 |
| Effective Green, g (s) | | 58.7 | 58.7 | 11.6 | 53.8 | | | | | 38.2 | 38.2 | 60.2 |
| Actuated g/C Ratio | | 0.47 | 0.47 | 0.09 | 0.43 | | | | | 0.31 | 0.31 | 0.48 |
| Clearance Time (s) | | 6.0 | 6.0 | 6.0 | 6.0 | | | | | 6.0 | 6.0 | |
| Vehicle Extension (s) | | 6.1 | 6.1 | 2.3 | 6.1 | | | | | 2.3 | 2.3 | |
| Lane Grp Cap (vph) | | 1949 | 736 | 166 | 1494 | | | | | 514 | 514 | 1329 |
| v/s Ratio Prot | | c0.37 | | 0.07 | c0.29 | | | | | 0.20 | 0.20 | c0.38 |
| v/s Ratio Perm | | | 0.31 | | | | | | | | | |
| v/c Ratio | | 0.78 | 0.67 | 0.75 | 0.68 | | | | | 0.65 | 0.66 | 0.78 |
| Uniform Delay, d1 | | 27.8 | 25.7 | 55.3 | 28.6 | | | | | 37.6 | 37.7 | 27.0 |
| Progression Factor | | 0.75 | 0.55 | 1.27 | 0.62 | | | | | 1.00 | 1.00 | 1.00 |
| Incremental Delay, d2 | | 2.1 | 3.1 | 14.7 | 2.4 | | | | | 2.3 | 2.6 | 2.9 |
| Delay (s) | | 22.9 | 17.3 | 85.1 | 20.1 | | | | | 39.9 | 40.3 | 29.9 |
| Level of Service | | C | B | F | C | | | | | D | D | C |
| Approach Delay (s) | | 20.9 | | | 27.2 | | | 0.0 | | | 33.8 | |
| Approach LOS | | C | | | C | | | A | | | C | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 26.6 | | | HCM Level of Service | | | | | C | |
| HCM Volume to Capacity ratio | | | 0.81 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 125.0 | | | Sum of lost time (s) | | | 16.5 | | | |
| Intersection Capacity Utilization | | | 90.7% | | | ICU Level of Service | | | | | E | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 13: Tualatin Sherwood Rd & I-5 NB Ramps





















4/15/2013

| |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | | ↑↑ | ↑↑ | | ↑↑ | ↑ | ↑ | ↑ | ↑ | | | |
| Volume (vph) | 0 | 1196 | 981 | 0 | 490 | 682 | 634 | 5 | 177 | 0 | 0 | 0 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | | 5.5 | 5.5 | | 6.0 | 6.0 | 5.5 | 5.5 | 5.5 | | | |
| Lane Util. Factor | | 0.95 | 0.88 | | 0.95 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Frbp, ped/bikes | | 1.00 | 1.00 | | 1.00 | 0.95 | 1.00 | 1.00 | 0.96 | | | |
| Flpb, ped/bikes | | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Frt | | 1.00 | 0.85 | | 1.00 | 0.85 | 1.00 | 1.00 | 0.85 | | | |
| Flt Protected | | 1.00 | 1.00 | | 1.00 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Satd. Flow (prot) | | 3574 | 2760 | | 3574 | 1502 | 1618 | 1620 | 1512 | | | |
| Flt Permitted | | 1.00 | 1.00 | | 1.00 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Satd. Flow (perm) | | 3574 | 2760 | | 3574 | 1502 | 1618 | 1620 | 1512 | | | |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 0 | 1259 | 1033 | 0 | 516 | 718 | 667 | 5 | 186 | 0 | 0 | 0 |
| RTOR Reduction (vph) | 0 | 0 | 327 | 0 | 0 | 252 | 0 | 0 | 23 | 0 | 0 | 0 |
| Lane Group Flow (vph) | 0 | 1259 | 706 | 0 | 516 | 466 | 333 | 339 | 163 | 0 | 0 | 0 |
| Confl. Peds. (#/hr) | | | | | | 16 | | | 17 | | | |
| Confl. Bikes (#/hr) | | 1 | | | 5 | | | | | 1 | | |
| Heavy Vehicles (%) | 0% | 1% | 3% | 0% | 1% | 2% | 6% | 20% | 2% | 0% | 0% | 0% |
| Turn Type | | Perm | | | Perm | | Split | | Perm | | | |
| Protected Phases | | 2 | | | 6 | | 8 | 8 | | | | |
| Permitted Phases | | | 2 | | | 6 | | | 8 | | | |
| Actuated Green, G (s) | | 81.1 | 81.1 | | 80.6 | 80.6 | 31.9 | 31.9 | 31.9 | | | |
| Effective Green, g (s) | | 81.6 | 81.6 | | 81.1 | 81.1 | 32.4 | 32.4 | 32.4 | | | |
| Actuated g/C Ratio | | 0.65 | 0.65 | | 0.65 | 0.65 | 0.26 | 0.26 | 0.26 | | | |
| Clearance Time (s) | | 6.0 | 6.0 | | 6.5 | 6.5 | 6.0 | 6.0 | 6.0 | | | |
| Vehicle Extension (s) | | 6.1 | 6.1 | | 4.2 | 4.2 | 2.3 | 2.3 | 2.3 | | | |
| Lane Grp Cap (vph) | | 2333 | 1802 | | 2319 | 974 | 419 | 420 | 392 | | | |
| v/s Ratio Prot | | c0.35 | | | 0.14 | | 0.21 | c0.21 | | | | |
| v/s Ratio Perm | | | 0.26 | | | 0.31 | | | 0.11 | | | |
| v/c Ratio | | 0.54 | 0.39 | | 0.22 | 0.48 | 0.79 | 0.81 | 0.42 | | | |
| Uniform Delay, d1 | | 11.6 | 10.1 | | 9.0 | 11.2 | 43.2 | 43.4 | 38.4 | | | |
| Progression Factor | | 0.44 | 0.20 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Incremental Delay, d2 | | 0.6 | 0.5 | | 0.2 | 1.7 | 9.6 | 10.4 | 0.4 | | | |
| Delay (s) | | 5.8 | 2.5 | | 9.2 | 12.9 | 52.8 | 53.8 | 38.9 | | | |
| Level of Service | | A | A | | A | B | D | D | D | | | |
| Approach Delay (s) | | 4.3 | | | 11.3 | | | 50.2 | | | 0.0 | |
| Approach LOS | | A | | | B | | | D | | | A | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | 15.2 | | | HCM Level of Service | | | | B | | | |
| HCM Volume to Capacity ratio | | 0.62 | | | | | | | | | | |
| Actuated Cycle Length (s) | | 125.0 | | | Sum of lost time (s) | | | | 11.0 | | | |
| Intersection Capacity Utilization | | 71.1% | | | ICU Level of Service | | | | C | | | |
| Analysis Period (min) | | 15 | | | | | | | | | | |

c Critical Lane Group

HCM Signalized Intersection Capacity Analysis
 14: Tualatin Sherwood Rd & Nyberg Woods

4/15/2013

| |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations |  |  | |  |  | | |  |  | |  |  |
| Volume (vph) | 290 | 981 | 61 | 10 | 813 | 80 | 112 | 7 | 17 | 81 | 5 | 191 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 5.5 | 5.5 | | 5.5 | 5.5 | | | 5.5 | 5.5 | | 5.5 | 5.5 |
| Lane Util. Factor | 0.97 | 0.95 | | 1.00 | 0.95 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 0.98 | | 1.00 | 0.99 |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frt | 1.00 | 0.99 | | 1.00 | 0.99 | | | 1.00 | 0.85 | | 1.00 | 0.85 |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.95 | 1.00 | | 0.95 | 1.00 |
| Satd. Flow (prot) | 3502 | 3503 | | 1805 | 3523 | | | 1761 | 1590 | | 1793 | 1592 |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.67 | 1.00 | | 0.65 | 1.00 |
| Satd. Flow (perm) | 3502 | 3503 | | 1805 | 3523 | | | 1243 | 1590 | | 1221 | 1592 |
| Peak-hour factor, PHF | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 |
| Adj. Flow (vph) | 302 | 1022 | 64 | 10 | 847 | 83 | 117 | 7 | 18 | 84 | 5 | 199 |
| RTOR Reduction (vph) | 0 | 3 | 0 | 0 | 7 | 0 | 0 | 0 | 15 | 0 | 0 | 165 |
| Lane Group Flow (vph) | 302 | 1083 | 0 | 10 | 923 | 0 | 0 | 124 | 3 | 0 | 89 | 34 |
| Confl. Peds. (#/hr) | 9 | | 2 | 2 | | 9 | 3 | | 4 | 4 | | 3 |
| Confl. Bikes (#/hr) | | 1 | | | 3 | | | | | | | |
| Heavy Vehicles (%) | 0% | 2% | 2% | 0% | 1% | 0% | 3% | 0% | 0% | 1% | 0% | 0% |
| Turn Type | Prot | | | Prot | | | Perm | | Perm | Perm | | Perm |
| Protected Phases | 5 | 2 | | 1 | 6 | | | 8 | | | 4 | |
| Permitted Phases | | | | | | | 8 | | 8 | 4 | | 4 |
| Actuated Green, G (s) | 9.1 | 33.8 | | 0.7 | 25.4 | | | 10.3 | 10.3 | | 10.3 | 10.3 |
| Effective Green, g (s) | 9.6 | 34.3 | | 1.2 | 25.9 | | | 10.8 | 10.8 | | 10.8 | 10.8 |
| Actuated g/C Ratio | 0.15 | 0.55 | | 0.02 | 0.41 | | | 0.17 | 0.17 | | 0.17 | 0.17 |
| Clearance Time (s) | 6.0 | 6.0 | | 6.0 | 6.0 | | | 6.0 | 6.0 | | 6.0 | 6.0 |
| Vehicle Extension (s) | 2.3 | 2.5 | | 2.4 | 2.5 | | | 2.4 | 2.4 | | 2.3 | 2.3 |
| Lane Grp Cap (vph) | 535 | 1913 | | 34 | 1453 | | | 214 | 273 | | 210 | 274 |
| v/s Ratio Prot | c0.09 | c0.31 | | 0.01 | c0.26 | | | | | | | |
| v/s Ratio Perm | | | | | | | | c0.10 | 0.00 | | 0.07 | 0.02 |
| v/c Ratio | 0.56 | 0.57 | | 0.29 | 0.64 | | | 0.58 | 0.01 | | 0.42 | 0.12 |
| Uniform Delay, d1 | 24.7 | 9.4 | | 30.4 | 14.7 | | | 23.9 | 21.6 | | 23.2 | 22.0 |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Incremental Delay, d2 | 1.0 | 0.3 | | 3.1 | 0.8 | | | 3.0 | 0.0 | | 0.8 | 0.1 |
| Delay (s) | 25.7 | 9.7 | | 33.5 | 15.5 | | | 26.9 | 21.6 | | 24.0 | 22.1 |
| Level of Service | C | A | | C | B | | | C | C | | C | C |
| Approach Delay (s) | | 13.2 | | | 15.7 | | | 26.2 | | | 22.7 | |
| Approach LOS | | B | | | B | | | C | | | C | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 15.7 | | | HCM Level of Service | | | | B | | |
| HCM Volume to Capacity ratio | | | 0.70 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 62.8 | | | Sum of lost time (s) | | | 22.0 | | | |
| Intersection Capacity Utilization | | | 61.0% | | | ICU Level of Service | | | B | | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |

c Critical Lane Group

HCM Signalized Intersection Capacity Analysis
 15: SW Nyberg St & SW Nyberg St

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|-------|-------|-------|----------------------|------|------|-------|-------|------|------|-------|-------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 217 | 927 | 26 | 24 | 759 | 16 | 17 | 9 | 45 | 5 | 7 | 135 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.8 | 4.8 | | 4.8 | 4.8 | | | 5.6 | 5.6 | | 5.3 | 4.8 |
| Lane Util. Factor | 1.00 | 1.00 | | 1.00 | 0.95 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 0.95 | | 1.00 | 1.00 |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frt | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 0.85 | | 1.00 | 0.85 |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.97 | 1.00 | | 0.98 | 1.00 |
| Satd. Flow (prot) | 1805 | 1854 | | 1805 | 3561 | | | 1803 | 1527 | | 1848 | 1609 |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.97 | 1.00 | | 0.69 | 1.00 |
| Satd. Flow (perm) | 1805 | 1854 | | 1805 | 3561 | | | 1803 | 1527 | | 1304 | 1609 |
| Peak-hour factor, PHF | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 |
| Adj. Flow (vph) | 226 | 966 | 27 | 25 | 791 | 17 | 18 | 9 | 47 | 5 | 7 | 141 |
| RTOR Reduction (vph) | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 44 | 0 | 0 | 113 |
| Lane Group Flow (vph) | 226 | 993 | 0 | 25 | 807 | 0 | 0 | 27 | 3 | 0 | 12 | 28 |
| Confl. Peds. (#/hr) | 9 | | 2 | 2 | | 9 | 3 | | 4 | 4 | | 3 |
| Heavy Vehicles (%) | 0% | 2% | 2% | 0% | 1% | 0% | 3% | 0% | 0% | 1% | 0% | 0% |
| Turn Type | Prot | | | Prot | | | Split | | Perm | Perm | | pm+ov |
| Protected Phases | 5 | 2 | | 1 | 6 | | 8 | 8 | | | 4 | 5 |
| Permitted Phases | | | | | | | | | 8 | 4 | | 4 |
| Actuated Green, G (s) | 11.5 | 48.9 | | 1.7 | 39.1 | | | 4.1 | 4.1 | | 3.6 | 15.1 |
| Effective Green, g (s) | 12.0 | 49.4 | | 2.2 | 39.6 | | | 4.6 | 4.6 | | 4.1 | 16.1 |
| Actuated g/C Ratio | 0.15 | 0.61 | | 0.03 | 0.49 | | | 0.06 | 0.06 | | 0.05 | 0.20 |
| Clearance Time (s) | 5.3 | 5.3 | | 5.3 | 5.3 | | | 6.1 | 6.1 | | 5.8 | 5.3 |
| Vehicle Extension (s) | 2.5 | 3.0 | | 1.0 | 3.0 | | | 1.0 | 1.0 | | 2.0 | 2.5 |
| Lane Grp Cap (vph) | 268 | 1134 | | 49 | 1745 | | | 103 | 87 | | 66 | 321 |
| v/s Ratio Prot | c0.13 | c0.54 | | 0.01 | 0.23 | | | c0.01 | | | | 0.01 |
| v/s Ratio Perm | | | | | | | | | 0.00 | | c0.01 | 0.00 |
| v/c Ratio | 0.84 | 0.88 | | 0.51 | 0.46 | | | 0.26 | 0.03 | | 0.18 | 0.09 |
| Uniform Delay, d1 | 33.5 | 13.1 | | 38.8 | 13.6 | | | 36.5 | 36.0 | | 36.7 | 26.4 |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Incremental Delay, d2 | 20.5 | 7.8 | | 3.7 | 0.2 | | | 0.5 | 0.1 | | 0.5 | 0.1 |
| Delay (s) | 54.0 | 20.9 | | 42.5 | 13.8 | | | 37.0 | 36.0 | | 37.2 | 26.4 |
| Level of Service | D | C | | D | B | | | D | D | | D | C |
| Approach Delay (s) | | 27.0 | | | 14.6 | | | 36.4 | | | 27.3 | |
| Approach LOS | | C | | | B | | | D | | | C | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 22.8 | HCM Level of Service | | | | C | | | | |
| HCM Volume to Capacity ratio | | | 0.81 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 80.8 | Sum of lost time (s) | | | | 20.5 | | | | |
| Intersection Capacity Utilization | | | 75.9% | ICU Level of Service | | | | D | | | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |






















HCM Signalized Intersection Capacity Analysis
 16: SW Tualatin Sherwood Rd & SW Boones Ferry Rd

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|------|-------|-------|------|-------|------|----------------------|-------|-------|-------|-------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 103 | 1014 | 138 | 224 | 1083 | 56 | 171 | 268 | 159 | 297 | 345 | 133 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 5.5 | | 4.5 | 5.5 | | 4.5 | 5.0 | 4.5 | 4.5 | 5.0 | |
| Lane Util. Factor | 1.00 | 0.95 | | 0.97 | 0.95 | | 1.00 | 1.00 | 1.00 | 1.00 | 0.95 | |
| Frpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | 0.98 | 1.00 | 0.99 | |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | |
| Frt | 1.00 | 0.98 | | 1.00 | 0.99 | | 1.00 | 1.00 | 0.85 | 1.00 | 0.96 | |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | 0.95 | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (prot) | 1703 | 3319 | | 3502 | 3338 | | 1733 | 1810 | 1542 | 1761 | 3313 | |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | | 0.40 | 1.00 | 1.00 | 0.59 | 1.00 | |
| Satd. Flow (perm) | 1703 | 3319 | | 3502 | 3338 | | 737 | 1810 | 1542 | 1099 | 3313 | |
| Peak-hour factor, PHF | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 |
| Adj. Flow (vph) | 104 | 1024 | 139 | 226 | 1094 | 57 | 173 | 271 | 161 | 300 | 348 | 134 |
| RTOR Reduction (vph) | 0 | 8 | 0 | 0 | 3 | 0 | 0 | 0 | 54 | 0 | 34 | 0 |
| Lane Group Flow (vph) | 104 | 1155 | 0 | 226 | 1148 | 0 | 173 | 271 | 107 | 300 | 448 | 0 |
| Confl. Peds. (#/hr) | | | 7 | | | 15 | 7 | | 8 | 8 | | 7 |
| Heavy Vehicles (%) | 6% | 7% | 3% | 0% | 7% | 6% | 4% | 5% | 3% | 2% | 4% | 3% |
| Turn Type | Prot | | | Prot | | | pm+pt | | pm+ov | | pm+pt | |
| Protected Phases | 5 | 2 | | 1 | 6 | | 3 | 8 | 1 | 7 | 4 | |
| Permitted Phases | | | | | | | 8 | | 8 | 4 | | |
| Actuated Green, G (s) | 10.0 | 55.9 | | 9.4 | 55.3 | | 21.3 | 21.3 | 30.7 | 27.3 | 26.8 | |
| Effective Green, g (s) | 10.5 | 56.4 | | 9.9 | 55.8 | | 21.8 | 21.8 | 31.7 | 27.8 | 27.3 | |
| Actuated g/C Ratio | 0.08 | 0.45 | | 0.08 | 0.45 | | 0.17 | 0.17 | 0.25 | 0.22 | 0.22 | |
| Clearance Time (s) | 5.0 | 6.0 | | 5.0 | 6.0 | | 5.0 | 5.5 | 5.0 | 5.0 | 5.5 | |
| Vehicle Extension (s) | 2.0 | 3.5 | | 2.0 | 3.5 | | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | |
| Lane Grp Cap (vph) | 143 | 1498 | | 277 | 1490 | | 223 | 316 | 391 | 337 | 724 | |
| v/s Ratio Prot | 0.06 | c0.35 | | 0.06 | c0.34 | | 0.07 | c0.15 | 0.02 | c0.12 | 0.14 | |
| v/s Ratio Perm | | | | | | | 0.06 | | 0.05 | c0.07 | | |
| v/c Ratio | 0.73 | 0.77 | | 0.82 | 0.77 | | 0.78 | 0.86 | 0.27 | 0.89 | 0.62 | |
| Uniform Delay, d1 | 55.9 | 28.9 | | 56.7 | 29.2 | | 47.5 | 50.1 | 37.4 | 45.8 | 44.1 | |
| Progression Factor | 1.00 | 1.00 | | 1.26 | 0.41 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | |
| Incremental Delay, d2 | 14.4 | 3.9 | | 10.4 | 2.4 | | 14.2 | 19.3 | 0.1 | 23.5 | 1.1 | |
| Delay (s) | 70.3 | 32.8 | | 82.0 | 14.3 | | 61.7 | 69.3 | 37.5 | 69.4 | 45.3 | |
| Level of Service | E | C | | F | B | | E | E | D | E | D | |
| Approach Delay (s) | | 35.9 | | | 25.4 | | | 58.7 | | | 54.5 | |
| Approach LOS | | D | | | C | | | E | | | D | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 39.3 | | | | HCM Level of Service | | | | D | |
| HCM Volume to Capacity ratio | | | 0.85 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 125.0 | | | | Sum of lost time (s) | | | 20.5 | | |
| Intersection Capacity Utilization | | | 87.3% | | | | ICU Level of Service | | | E | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 17: Tualatin Sherwood Rd & Martinazzi Ave

4/15/2013

| |  |  |  |  |  |  |  |  |  |  |  |  | | |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|----------------------|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR | | |
| Lane Configurations |  |  | | |  | |  |  |  |  |  |  | | |
| Volume (vph) | 52 | 1484 | 83 | 0 | 1110 | 0 | 95 | 302 | 323 | 194 | 663 | 88 | | |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | | |
| Total Lost time (s) | 4.5 | 5.5 | | | 5.5 | | 4.5 | 5.5 | 5.5 | 4.5 | 5.5 | | | |
| Lane Util. Factor | 1.00 | *0.95 | | | 0.95 | | 1.00 | 1.00 | 1.00 | 1.00 | 0.95 | | | |
| Frbp, ped/bikes | 1.00 | 1.00 | | | 1.00 | | 1.00 | 1.00 | 0.98 | 1.00 | 1.00 | | | |
| Flpb, ped/bikes | 1.00 | 1.00 | | | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Frt | 1.00 | 0.99 | | | 1.00 | | 1.00 | 1.00 | 0.85 | 1.00 | 0.98 | | | |
| Flt Protected | 0.95 | 1.00 | | | 1.00 | | 0.95 | 1.00 | 1.00 | 0.95 | 1.00 | | | |
| Satd. Flow (prot) | 1719 | 3447 | | | 3438 | | 1770 | 1863 | 1574 | 1787 | 3497 | | | |
| Flt Permitted | 0.95 | 1.00 | | | 1.00 | | 0.95 | 1.00 | 1.00 | 0.95 | 1.00 | | | |
| Satd. Flow (perm) | 1719 | 3447 | | | 3438 | | 1770 | 1863 | 1574 | 1787 | 3497 | | | |
| Peak-hour factor, PHF | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | | |
| Adj. Flow (vph) | 55 | 1579 | 88 | 0 | 1181 | 0 | 101 | 321 | 344 | 206 | 705 | 94 | | |
| RTOR Reduction (vph) | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 82 | 0 | 9 | 0 | | |
| Lane Group Flow (vph) | 55 | 1664 | 0 | 0 | 1181 | 0 | 101 | 321 | 262 | 206 | 790 | 0 | | |
| Confl. Peds. (#/hr) | | | 4 | | | 2 | | | 3 | | | 16 | | |
| Heavy Vehicles (%) | 5% | 4% | 0% | 0% | 5% | 0% | 2% | 2% | 1% | 1% | 1% | 1% | | |
| Turn Type | Prot | | | | | | Prot | | Perm | Prot | | | | |
| Protected Phases | 5 | 2 | | | 6 | | 3 | 8 | | 7 | 4 | | | |
| Permitted Phases | | | | | | | | | 8 | | | | | |
| Actuated Green, G (s) | 7.8 | 65.5 | | | 52.7 | | 10.0 | 23.5 | 23.5 | 19.0 | 32.5 | | | |
| Effective Green, g (s) | 8.3 | 66.0 | | | 53.2 | | 10.5 | 24.0 | 24.0 | 19.5 | 33.0 | | | |
| Actuated g/C Ratio | 0.07 | 0.53 | | | 0.43 | | 0.08 | 0.19 | 0.19 | 0.16 | 0.26 | | | |
| Clearance Time (s) | 5.0 | 6.0 | | | 6.0 | | 5.0 | 6.0 | 6.0 | 5.0 | 6.0 | | | |
| Vehicle Extension (s) | 2.0 | 3.5 | | | 3.5 | | 3.0 | 2.0 | 2.0 | 3.0 | 2.0 | | | |
| Lane Grp Cap (vph) | 114 | 1820 | | | 1463 | | 149 | 358 | 302 | 279 | 923 | | | |
| v/s Ratio Prot | 0.03 | c0.48 | | | 0.34 | | 0.06 | c0.17 | | 0.12 | c0.23 | | | |
| v/s Ratio Perm | | | | | | | | | 0.17 | | | | | |
| v/c Ratio | 0.48 | 0.91 | | | 0.81 | | 0.68 | 0.90 | 0.87 | 0.74 | 0.86 | | | |
| Uniform Delay, d1 | 56.3 | 26.9 | | | 31.4 | | 55.6 | 49.3 | 49.0 | 50.3 | 43.7 | | | |
| Progression Factor | 0.74 | 1.13 | | | 0.56 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Incremental Delay, d2 | 0.9 | 6.8 | | | 4.3 | | 11.6 | 23.3 | 21.6 | 9.8 | 7.6 | | | |
| Delay (s) | 42.5 | 37.2 | | | 21.9 | | 67.2 | 72.6 | 70.6 | 60.1 | 51.3 | | | |
| Level of Service | D | D | | | C | | E | E | E | E | D | | | |
| Approach Delay (s) | | 37.4 | | | 21.9 | | | 71.0 | | | 53.1 | | | |
| Approach LOS | | D | | | C | | | E | | | D | | | |
| Intersection Summary | | | | | | | | | | | | | | |
| HCM Average Control Delay | | 42.4 | | | | | | | | | | HCM Level of Service | D | |
| HCM Volume to Capacity ratio | | 0.88 | | | | | | | | | | | | |
| Actuated Cycle Length (s) | | 125.0 | | | | | | | | | 11.0 | | Sum of lost time (s) | |
| Intersection Capacity Utilization | | 88.0% | | | | | | | | | | | ICU Level of Service | E |
| Analysis Period (min) | | 15 | | | | | | | | | | | | |
| c | Critical Lane Group | | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 18: SW Borland Rd & SW 65th Ave

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR | |
|-----------------------------------|-------|-------|-------|-------|-------|--------|-------|------|------|-------|------|----------------------|------|
| Lane Configurations | | ↔ | | | ↔ | ↔ | ↔ | ↔ | | ↔ | ↔ | | |
| Volume (vph) | 23 | 23 | 10 | 240 | 0 | 234 | 2 | 334 | 359 | 423 | 474 | 10 | |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | |
| Total Lost time (s) | | 5.6 | | | 5.3 | 5.6 | 4.8 | 4.8 | | 4.8 | 4.8 | | |
| Lane Util. Factor | | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | | |
| Frbp, ped/bikes | | 0.99 | | | 1.00 | 0.90 | 1.00 | 0.98 | | 1.00 | 1.00 | | |
| Flpb, ped/bikes | | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | | |
| Frt | | 0.98 | | | 1.00 | 0.85 | 1.00 | 0.92 | | 1.00 | 1.00 | | |
| Flt Protected | | 0.98 | | | 0.95 | 1.00 | 0.95 | 1.00 | | 0.95 | 1.00 | | |
| Satd. Flow (prot) | | 1786 | | | 1805 | 1457 | 1748 | 1721 | | 1787 | 1893 | | |
| Flt Permitted | | 0.98 | | | 0.95 | 1.00 | 0.48 | 1.00 | | 0.09 | 1.00 | | |
| Satd. Flow (perm) | | 1786 | | | 1805 | 1457 | 880 | 1721 | | 165 | 1893 | | |
| Peak-hour factor, PHF | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | |
| Adj. Flow (vph) | 24 | 24 | 10 | 250 | 0 | 244 | 2 | 348 | 374 | 441 | 494 | 10 | |
| RTOR Reduction (vph) | 0 | 6 | 0 | 0 | 0 | 230 | 0 | 24 | 0 | 0 | 0 | 0 | |
| Lane Group Flow (vph) | 0 | 52 | 0 | 0 | 250 | 14 | 2 | 698 | 0 | 441 | 504 | 0 | |
| Confl. Peds. (#/hr) | 9 | | 2 | 2 | | 9 | 3 | | 4 | 4 | | 3 | |
| Heavy Vehicles (%) | 0% | 2% | 2% | 0% | 1% | 0% | 3% | 0% | 0% | 1% | 0% | 0% | |
| Turn Type | Split | | | Split | | custom | pm+pt | | | pm+pt | | | |
| Protected Phases | 8 | 8 | | 4 | 4 | | 1 | 6 | | 5 | 2 | | |
| Permitted Phases | | | | | | 8 | 6 | | | 2 | | | |
| Actuated Green, G (s) | | 7.6 | | | 20.0 | 7.6 | 64.4 | 63.4 | | 98.7 | 92.4 | | |
| Effective Green, g (s) | | 8.1 | | | 20.5 | 8.1 | 65.4 | 63.9 | | 99.2 | 92.9 | | |
| Actuated g/C Ratio | | 0.06 | | | 0.14 | 0.06 | 0.46 | 0.45 | | 0.69 | 0.65 | | |
| Clearance Time (s) | | 6.1 | | | 5.8 | 6.1 | 5.3 | 5.3 | | 5.3 | 5.3 | | |
| Vehicle Extension (s) | | 1.0 | | | 2.0 | 1.0 | 1.0 | 3.0 | | 2.5 | 0.2 | | |
| Lane Grp Cap (vph) | | 101 | | | 258 | 82 | 410 | 766 | | 459 | 1226 | | |
| v/s Ratio Prot | | c0.03 | | | c0.14 | | 0.00 | 0.41 | | c0.20 | 0.27 | | |
| v/s Ratio Perm | | | | | | 0.01 | 0.00 | | | c0.46 | | | |
| v/c Ratio | | 0.52 | | | 0.97 | 0.17 | 0.00 | 0.91 | | 0.96 | 0.41 | | |
| Uniform Delay, d1 | | 65.8 | | | 61.2 | 64.5 | 21.3 | 37.1 | | 43.9 | 12.2 | | |
| Progression Factor | | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | | |
| Incremental Delay, d2 | | 1.9 | | | 46.6 | 0.4 | 0.0 | 15.0 | | 32.0 | 0.1 | | |
| Delay (s) | | 67.7 | | | 107.8 | 64.8 | 21.3 | 52.1 | | 75.9 | 12.2 | | |
| Level of Service | | E | | | F | E | C | D | | E | B | | |
| Approach Delay (s) | | 67.7 | | | 86.6 | | | 52.0 | | | 41.9 | | |
| Approach LOS | | E | | | F | | | D | | | D | | |
| Intersection Summary | | | | | | | | | | | | | |
| HCM Average Control Delay | | | 55.8 | | | | | | | | | HCM Level of Service | E |
| HCM Volume to Capacity ratio | | | 0.92 | | | | | | | | | | |
| Actuated Cycle Length (s) | | | 143.5 | | | | | | | | | Sum of lost time (s) | 15.7 |
| Intersection Capacity Utilization | | | 95.6% | | | | | | | | | ICU Level of Service | F |
| Analysis Period (min) | | | 15 | | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 19: SW Sagert St & SW Boones Ferry Rd

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|-------|------|-------|-------|------|----------------------|-------|-------|------|-------|------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 42 | 107 | 13 | 166 | 112 | 64 | 16 | 476 | 218 | 65 | 561 | 75 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 3.5 | 3.5 | | 3.5 | 3.5 | | 3.5 | 4.0 | | 3.5 | 4.0 | |
| Lane Util. Factor | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 0.98 | | 1.00 | 0.99 | | 1.00 | 1.00 | |
| Flpb, ped/bikes | 0.99 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Frt | 1.00 | 0.98 | | 1.00 | 0.95 | | 1.00 | 0.95 | | 1.00 | 0.98 | |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | 0.95 | 1.00 | | 0.95 | 1.00 | |
| Satd. Flow (prot) | 1781 | 1827 | | 1780 | 1733 | | 1768 | 1787 | | 1804 | 1860 | |
| Flt Permitted | 0.64 | 1.00 | | 0.44 | 1.00 | | 0.26 | 1.00 | | 0.17 | 1.00 | |
| Satd. Flow (perm) | 1202 | 1827 | | 825 | 1733 | | 482 | 1787 | | 331 | 1860 | |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 44 | 113 | 14 | 175 | 118 | 67 | 17 | 501 | 229 | 68 | 591 | 79 |
| RTOR Reduction (vph) | 0 | 4 | 0 | 0 | 18 | 0 | 0 | 11 | 0 | 0 | 3 | 0 |
| Lane Group Flow (vph) | 44 | 123 | 0 | 175 | 167 | 0 | 17 | 719 | 0 | 68 | 667 | 0 |
| Confl. Peds. (#/hr) | 15 | | 7 | 7 | | 15 | 7 | | 8 | 8 | | 7 |
| Heavy Vehicles (%) | 0% | 2% | 1% | 1% | 3% | 0% | 2% | 0% | 1% | 0% | 0% | 0% |
| Turn Type | pm+pt | | | pm+pt | | | pm+pt | | | pm+pt | | |
| Protected Phases | 7 | 4 | | 3 | 8 | | 5 | 2 | | 1 | 6 | |
| Permitted Phases | 4 | | | 8 | | | 2 | | | 6 | | |
| Actuated Green, G (s) | 15.3 | 12.3 | | 25.7 | 18.7 | | 47.0 | 45.5 | | 51.6 | 47.8 | |
| Effective Green, g (s) | 16.3 | 12.8 | | 26.2 | 19.2 | | 48.0 | 46.0 | | 52.6 | 48.3 | |
| Actuated g/C Ratio | 0.19 | 0.15 | | 0.30 | 0.22 | | 0.55 | 0.53 | | 0.60 | 0.55 | |
| Clearance Time (s) | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 | 4.5 | | 4.0 | 4.5 | |
| Vehicle Extension (s) | 2.2 | 2.2 | | 2.2 | 2.2 | | 2.2 | 5.0 | | 2.2 | 5.0 | |
| Lane Grp Cap (vph) | 247 | 267 | | 355 | 380 | | 294 | 939 | | 271 | 1027 | |
| v/s Ratio Prot | 0.01 | 0.07 | | c0.06 | 0.10 | | 0.00 | c0.40 | | c0.01 | 0.36 | |
| v/s Ratio Perm | 0.03 | | | c0.09 | | | 0.03 | | | 0.14 | | |
| v/c Ratio | 0.18 | 0.46 | | 0.49 | 0.44 | | 0.06 | 0.77 | | 0.25 | 0.65 | |
| Uniform Delay, d1 | 29.7 | 34.2 | | 24.0 | 29.5 | | 10.7 | 16.5 | | 11.7 | 13.7 | |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Incremental Delay, d2 | 0.2 | 0.6 | | 0.6 | 0.4 | | 0.0 | 4.4 | | 0.2 | 1.9 | |
| Delay (s) | 29.9 | 34.8 | | 24.6 | 29.9 | | 10.7 | 20.9 | | 11.9 | 15.6 | |
| Level of Service | C | C | | C | C | | B | C | | B | B | |
| Approach Delay (s) | | 33.6 | | | 27.3 | | | 20.7 | | | 15.3 | |
| Approach LOS | | C | | | C | | | C | | | B | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 21.0 | | | HCM Level of Service | | | | C | | |
| HCM Volume to Capacity ratio | | | 0.67 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 87.5 | | | Sum of lost time (s) | | | 14.5 | | | |
| Intersection Capacity Utilization | | | 73.9% | | | ICU Level of Service | | | | D | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCS+: Unsignalized Intersections Release 5.6

Phone:
E-Mail:

Fax:

ALL-WAY STOP CONTROL(AWSC) ANALYSIS

Analyst:
Agency/Co.:
Date Performed: 4/16/2013
Analysis Time Period: Weekday PM
Intersection: Sagert/Martinazzi
Jurisdiction:
Units: U. S. Customary
Analysis Year: Background
Project ID:
East/West Street: Sagert
North/South Street: Martinazzi

Worksheet 2 - Volume Adjustments and Site Characteristics

| | Eastbound | | | Westbound | | | Northbound | | | Southbound | | |
|-------------------|-----------|-----|----|-----------|-----|-----|------------|-----|----|------------|-----|---|
| | L | T | R | L | T | R | L | T | R | L | T | R |
| Volume | 117 | 233 | 12 | 90 | 195 | 164 | 2 | 180 | 76 | 207 | 296 | |
| % Thrus Left Lane | | | | | | | | | | | | |

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|-------------------|-----------|------|-----------|------|------------|------|------------|------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Configuration | L | TR | L | TR | L | TR | L | TR |
| PHF | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 |
| Flow Rate | 130 | 271 | 100 | 398 | 2 | 284 | 230 | 585 |
| % Heavy Veh | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| No. Lanes | | 2 | | 2 | | 2 | | 2 |
| Opposing-Lanes | | 2 | | 2 | | 2 | | 2 |
| Conflicting-lanes | | 2 | | 2 | | 2 | | 2 |
| Geometry group | | 5 | | 5 | | 5 | | 5 |
| Duration, T | 0.25 hrs. | | | | | | | |

Worksheet 3 - Saturation Headway Adjustment Worksheet

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|----------------------------|-----------|-----|-----------|-----|------------|-----|------------|-----|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow Rates: | | | | | | | | |
| Total in Lane | 130 | 271 | 100 | 398 | 2 | 284 | 230 | 585 |
| Left-Turn | 130 | 0 | 100 | 0 | 2 | 0 | 230 | 0 |
| Right-Turn | 0 | 13 | 0 | 182 | 0 | 84 | 0 | 257 |
| Prop. Left-Turns | 1.0 | 0.0 | 1.0 | 0.0 | 1.0 | 0.0 | 1.0 | 0.0 |
| Prop. Right-Turns | 0.0 | 0.0 | 0.0 | 0.5 | 0.0 | 0.3 | 0.0 | 0.4 |
| Prop. Heavy Vehicle | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Geometry Group | | 5 | | 5 | | 5 | | 5 |
| Adjustments Exhibit 17-33: | | | | | | | | |
| hLT-adj | | 0.5 | | 0.5 | | 0.5 | | 0.5 |

| | | | | | | | | |
|----------------|------|------|------|------|------|------|------|------|
| hRT-adj | -0.7 | | -0.7 | | -0.7 | | -0.7 | |
| hHV-adj | 1.7 | | 1.7 | | 1.7 | | 1.7 | |
| hadj, computed | 0.5 | -0.0 | 0.5 | -0.3 | 0.5 | -0.2 | 0.5 | -0.3 |

Worksheet 4 - Departure Headway and Service Time

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|-------------------|-----------|------|-----------|------|------------|------|------------|------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow rate | 130 | 271 | 100 | 398 | 2 | 284 | 230 | 585 |
| hd, initial value | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 |
| x, initial | 0.12 | 0.24 | 0.09 | 0.35 | 0.00 | 0.25 | 0.20 | 0.52 |
| hd, final value | 9.23 | 8.70 | 9.00 | 8.18 | 9.42 | 8.71 | 8.80 | 7.99 |
| x, final value | 0.33 | 0.65 | 0.25 | 0.90 | 0.01 | 0.69 | 0.56 | 1.30 |
| Move-up time, m | | 2.3 | | 2.3 | | 2.3 | | 2.3 |
| Service Time | 6.9 | 6.4 | 6.7 | 5.9 | 7.1 | 6.4 | 6.5 | 5.7 |

Worksheet 5 - Capacity and Level of Service

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|--------------------|-----------|-------|-----------|-------|------------|-------|------------|--------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow Rate | 130 | 271 | 100 | 398 | 2 | 284 | 230 | 585 |
| Service Time | 6.9 | 6.4 | 6.7 | 5.9 | 7.1 | 6.4 | 6.5 | 5.7 |
| Utilization, x | 0.33 | 0.65 | 0.25 | 0.90 | 0.01 | 0.69 | 0.56 | 1.30 |
| Dep. headway, hd | 9.23 | 8.70 | 9.00 | 8.18 | 9.42 | 8.71 | 8.80 | 7.99 |
| Capacity | 380 | 408 | 350 | 439 | 252 | 406 | 407 | 585 |
| Delay | 16.48 | 26.44 | 14.68 | 51.04 | 12.17 | 28.50 | 22.21 | 173.73 |
| LOS | C | D | B | F | B | D | C | F |
| Approach: | | | | | | | | |
| Delay | | 23.21 | | 43.74 | | 28.38 | | 130.97 |
| LOS | | C | | E | | D | | F |
| Intersection Delay | 72.97 | | | | | | | |
| | | | | | | | | |

HCS+: Unsignalized Intersections Release 5.6

Phone:
E-Mail:

Fax:

ALL-WAY STOP CONTROL (AWSC) ANALYSIS

Analyst:
Agency/Co.:
Date Performed: 4/16/2013
Analysis Time Period: Weekday PM
Intersection: Sagert/65th
Jurisdiction:
Units: U. S. Customary
Analysis Year: Background
Project ID:
East/West Street: Sagert
North/South Street: 65th

Worksheet 2 - Volume Adjustments and Site Characteristics

| | Eastbound | | | Westbound | | | Northbound | | | Southbound | | |
|-------------------|-----------|---|-----|-----------|---|---|------------|-----|---|------------|-----|-----|
| | L | T | R | L | T | R | L | T | R | L | T | R |
| Volume | 401 | 2 | 135 | 2 | 7 | 6 | 158 | 288 | 3 | 13 | 335 | 386 |
| % Thrus Left Lane | | | | | | | | | | | | |

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|-------------------|-----------|------|-----------|------|------------|------|------------|------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Configuration | L | TR | L | TR | L | TR | L | TR |
| PHF | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 |
| Flow Rate | 445 | 152 | 2 | 13 | 64 | 323 | 3 | 800 |
| % Heavy Veh | 1 | 1 | 0 | 0 | 1 | 2 | 1 | 2 |
| No. Lanes | | 2 | | 2 | | 2 | | 2 |
| Opposing-Lanes | | 2 | | 2 | | 2 | | 2 |
| Conflicting-lanes | | 2 | | 2 | | 2 | | 2 |
| Geometry group | | 5 | | 5 | | 5 | | 5 |
| Duration, T | 0.25 hrs. | | | | | | | |

Worksheet 3 - Saturation Headway Adjustment Worksheet

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|----------------------------|-----------|-----|-----------|-----|------------|-----|------------|-----|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow Rates: | | | | | | | | |
| Total in Lane | 445 | 152 | 2 | 13 | 64 | 323 | 3 | 800 |
| Left-Turn | 445 | 0 | 2 | 0 | 64 | 0 | 3 | 0 |
| Right-Turn | 0 | 150 | 0 | 6 | 0 | 3 | 0 | 428 |
| Prop. Left-Turns | 1.0 | 0.0 | 1.0 | 0.0 | 1.0 | 0.0 | 1.0 | 0.0 |
| Prop. Right-Turns | 0.0 | 1.0 | 0.0 | 0.5 | 0.0 | 0.0 | 0.0 | 0.5 |
| Prop. Heavy Vehicle | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Geometry Group | | 5 | | 5 | | 5 | | 5 |
| Adjustments Exhibit 17-33: | | | | | | | | |
| hLT-adj | | 0.5 | | 0.5 | | 0.5 | | 0.5 |

| | | | | | | | | |
|----------------|------|------|------|------|------|-----|------|------|
| hRT-adj | -0.7 | | -0.7 | | -0.7 | | -0.7 | |
| hHV-adj | 1.7 | | 1.7 | | 1.7 | | 1.7 | |
| hadj, computed | 0.5 | -0.7 | 0.5 | -0.3 | 0.5 | 0.0 | 0.5 | -0.3 |

Worksheet 4 - Departure Headway and Service Time

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|-------------------|-----------|------|-----------|------|------------|------|------------|------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow rate | 445 | 152 | 2 | 13 | 64 | 323 | 3 | 800 |
| hd, initial value | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 |
| x, initial | 0.40 | 0.14 | 0.00 | 0.01 | 0.06 | 0.29 | 0.00 | 0.71 |
| hd, final value | 7.73 | 6.54 | 9.23 | 8.40 | 8.00 | 7.51 | 7.77 | 6.91 |
| x, final value | 0.96 | 0.28 | 0.01 | 0.03 | 0.14 | 0.67 | 0.01 | 1.54 |
| Move-up time, m | | 2.3 | | 2.3 | | 2.3 | | 2.3 |
| Service Time | 5.4 | 4.2 | 6.9 | 6.1 | 5.7 | 5.2 | 5.5 | 4.6 |

Worksheet 5 - Capacity and Level of Service

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|--------------------|-----------|-------|-----------|-------|------------|-------|------------|--------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow Rate | 445 | 152 | 2 | 13 | 64 | 323 | 3 | 800 |
| Service Time | 5.4 | 4.2 | 6.9 | 6.1 | 5.7 | 5.2 | 5.5 | 4.6 |
| Utilization, x | 0.96 | 0.28 | 0.01 | 0.03 | 0.14 | 0.67 | 0.01 | 1.54 |
| Dep. headway, hd | 7.73 | 6.54 | 9.23 | 8.40 | 8.00 | 7.51 | 7.77 | 6.91 |
| Capacity | 466 | 402 | 252 | 263 | 314 | 475 | 253 | 800 |
| Delay | 58.85 | 11.71 | 11.98 | 11.37 | 12.02 | 24.33 | 10.52 | 269.49 |
| LOS | F | B | B | B | B | C | B | F |
| Approach: | | | | | | | | |
| Delay | | 46.85 | | 11.45 | | 22.29 | | 268.52 |
| LOS | | E | | B | | C | | F |
| Intersection Delay | 140.06 | | | | | | | |
| | | | | | | | | |

Intersection: 12: Tualatin Sherwood Rd & I-5 SB Ramps

| Movement | EB | EB | EB | EB | WB | WB | WB | SB | SB | SB | SB |
|-----------------------|-----|-----|-----|-----|-----|-----|-----|-----|------|------|-----|
| Directions Served | T | T | T | R | L | T | T | L | LT | R | R |
| Maximum Queue (ft) | 284 | 274 | 264 | 152 | 433 | 501 | 537 | 275 | 719 | 625 | 476 |
| Average Queue (ft) | 172 | 189 | 171 | 14 | 133 | 250 | 270 | 190 | 349 | 304 | 173 |
| 95th Queue (ft) | 265 | 285 | 246 | 89 | 324 | 483 | 512 | 304 | 664 | 552 | 387 |
| Link Distance (ft) | 181 | 181 | 181 | 181 | 635 | 635 | 635 | | 1148 | 1148 | |
| Upstream Blk Time (%) | 6 | 8 | 8 | 0 | 1 | 2 | 2 | | 0 | 0 | |
| Queuing Penalty (veh) | 32 | 48 | 45 | 1 | 2 | 7 | 7 | | 0 | 0 | |
| Storage Bay Dist (ft) | | | | | | | | 200 | | | 700 |
| Storage Blk Time (%) | | | | | | | | 7 | 25 | 1 | 0 |
| Queuing Penalty (veh) | | | | | | | | 22 | 82 | 4 | 0 |

Queuing and Blocking Report
 Bkground Weekday PM Peak Hour

4/12/2013

Intersection: 13: Tualatin Sherwood Rd & I-5 NB Ramps

| Movement | EB | EB | WB | WB | WB | NB | NB | NB | B33 |
|-----------------------|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| Directions Served | T | T | T | T | R | L | LT | R | T |
| Maximum Queue (ft) | 469 | 436 | 198 | 301 | 225 | 356 | 441 | 299 | 54 |
| Average Queue (ft) | 186 | 174 | 82 | 101 | 14 | 222 | 238 | 102 | 10 |
| 95th Queue (ft) | 384 | 364 | 166 | 218 | 103 | 336 | 401 | 225 | 93 |
| Link Distance (ft) | 635 | 635 | 468 | 468 | | | 463 | | 253 |
| Upstream Blk Time (%) | | | | 0 | | | 2 | | 2 |
| Queuing Penalty (veh) | | | | 1 | | | 0 | | 0 |
| Storage Bay Dist (ft) | | | | | 150 | 300 | | 225 | |
| Storage Blk Time (%) | | | | 3 | 0 | 3 | 10 | 0 | |
| Queuing Penalty (veh) | | | | 18 | 0 | 15 | 51 | 2 | |

HCM Signalized Intersection Capacity Analysis
 3: SW Boones Ferry Road & SW Martinazzi Ave

4/17/2013

| | → | ↘ | ↙ | ← | ↖ | ↗ |
|-----------------------------------|-------|------|-------|------|----------------------|-------|
| Movement | EBT | EBR | WBL | WBT | NBL | NBR |
| Lane Configurations | ↑ | ↗ | ↙ | ↑ | ↙ | ↗ |
| Volume (vph) | 417 | 125 | 258 | 429 | 185 | 304 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 4.5 | 4.5 | 4.5 | 4.5 | 4.5 |
| Lane Util. Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Frbp, ped/bikes | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 0.99 |
| Flpb, ped/bikes | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Frt | 1.00 | 0.85 | 1.00 | 1.00 | 1.00 | 0.85 |
| Flt Protected | 1.00 | 1.00 | 0.95 | 1.00 | 0.95 | 1.00 |
| Satd. Flow (prot) | 1863 | 1599 | 1787 | 1845 | 1770 | 1581 |
| Flt Permitted | 1.00 | 1.00 | 0.95 | 1.00 | 0.95 | 1.00 |
| Satd. Flow (perm) | 1863 | 1599 | 1787 | 1845 | 1770 | 1581 |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 439 | 132 | 272 | 452 | 195 | 320 |
| RTOR Reduction (vph) | 0 | 90 | 0 | 0 | 0 | 93 |
| Lane Group Flow (vph) | 439 | 42 | 272 | 452 | 195 | 227 |
| Confl. Peds. (#/hr) | | 11 | 11 | | 1 | 3 |
| Confl. Bikes (#/hr) | 4 | | 2 | 10 | 1 | |
| Heavy Vehicles (%) | 2% | 1% | 1% | 3% | 2% | 1% |
| Turn Type | | Prot | Prot | | | pm+ov |
| Protected Phases | 2 | 2 | 1 | 6 | 8 | 1 |
| Permitted Phases | | | | | 8 | 8 |
| Actuated Green, G (s) | 17.1 | 17.1 | 12.7 | 34.8 | 11.0 | 23.7 |
| Effective Green, g (s) | 17.6 | 17.6 | 13.2 | 35.3 | 11.5 | 24.7 |
| Actuated g/C Ratio | 0.32 | 0.32 | 0.24 | 0.63 | 0.21 | 0.44 |
| Clearance Time (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 |
| Lane Grp Cap (vph) | 588 | 504 | 423 | 1167 | 365 | 827 |
| v/s Ratio Prot | c0.24 | 0.03 | c0.15 | 0.25 | c0.11 | 0.06 |
| v/s Ratio Perm | | | | | | 0.08 |
| v/c Ratio | 0.75 | 0.08 | 0.64 | 0.39 | 0.53 | 0.27 |
| Uniform Delay, d1 | 17.1 | 13.4 | 19.2 | 5.0 | 19.8 | 9.9 |
| Progression Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Incremental Delay, d2 | 5.1 | 0.1 | 3.3 | 0.2 | 1.5 | 0.2 |
| Delay (s) | 22.2 | 13.5 | 22.5 | 5.2 | 21.3 | 10.0 |
| Level of Service | C | B | C | A | C | B |
| Approach Delay (s) | 20.2 | | | 11.7 | 14.3 | |
| Approach LOS | C | | | B | B | |
| Intersection Summary | | | | | | |
| HCM Average Control Delay | | | 15.1 | | HCM Level of Service | B |
| HCM Volume to Capacity ratio | | | 0.66 | | | |
| Actuated Cycle Length (s) | | | 55.8 | | Sum of lost time (s) | 13.5 |
| Intersection Capacity Utilization | | | 58.4% | | ICU Level of Service | B |
| Analysis Period (min) | | | 15 | | | |

c Critical Lane Group











HCM Unsignalized Intersection Capacity Analysis
 4: Site Entrance 1 & Martinazzi Ave

4/17/2013

| | ↙ | ↘ | ↑ | ↗ | ↘ | ↓ |
|-----------------------------------|------|------|-------|----------------------|------|------|
| Movement | WBL | WBR | NBT | NBR | SBL | SBT |
| Lane Configurations | ↙ | ↘ | ↗ | | ↙ | ↗ |
| Volume (veh/h) | 46 | 80 | 408 | 60 | 110 | 269 |
| Sign Control | Stop | | Free | | Free | |
| Grade | 0% | | 0% | | 0% | |
| Peak Hour Factor | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 |
| Hourly flow rate (vph) | 50 | 87 | 443 | 65 | 120 | 292 |
| Pedestrians | 13 | | | | 6 | |
| Lane Width (ft) | 12.0 | | | | 12.0 | |
| Walking Speed (ft/s) | 4.0 | | | | 4.0 | |
| Percent Blockage | 1 | | | | 1 | |
| Right turn flare (veh) | | | | | | |
| Median type | None | | | TWLTL | | |
| Median storage (veh) | | | | 2 | | |
| Upstream signal (ft) | 428 | | | 355 | | |
| pX, platoon unblocked | 0.97 | 0.97 | | | 0.97 | |
| vC, conflicting volume | 1021 | 495 | | | 522 | |
| vC1, stage 1 conf vol | 489 | | | | | |
| vC2, stage 2 conf vol | 532 | | | | | |
| vCu, unblocked vol | 1007 | 467 | | | 494 | |
| tC, single (s) | 6.4 | 6.2 | | | 4.1 | |
| tC, 2 stage (s) | 5.4 | | | | | |
| tF (s) | 3.5 | 3.3 | | | 2.2 | |
| p0 queue free % | 89 | 85 | | | 88 | |
| cM capacity (veh/h) | 441 | 574 | | | 1039 | |
| Direction, Lane # | WB 1 | WB 2 | NB 1 | SB 1 | SB 2 | |
| Volume Total | 50 | 87 | 509 | 120 | 292 | |
| Volume Left | 50 | 0 | 0 | 120 | 0 | |
| Volume Right | 0 | 87 | 65 | 0 | 0 | |
| cSH | 441 | 574 | 1700 | 1039 | 1700 | |
| Volume to Capacity | 0.11 | 0.15 | 0.30 | 0.12 | 0.17 | |
| Queue Length 95th (ft) | 10 | 14 | 0 | 10 | 0 | |
| Control Delay (s) | 14.2 | 12.4 | 0.0 | 8.9 | 0.0 | |
| Lane LOS | B | B | | A | | |
| Approach Delay (s) | 13.1 | | 0.0 | 2.6 | | |
| Approach LOS | B | | | | | |
| Intersection Summary | | | | | | |
| Average Delay | | | 2.7 | | | |
| Intersection Capacity Utilization | | | 46.5% | ICU Level of Service | A | |
| Analysis Period (min) | | | 15 | | | |

HCM Unsignalized Intersection Capacity Analysis
 5: Seneca St & Martinazzi Ave

4/17/2013

| |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|
| Movement | EBL | EBR | NBL | NBT | SBT | SBR |
| Lane Configurations |  | |  |  |  | |
| Volume (veh/h) | 37 | 45 | 81 | 432 | 271 | 44 |
| Sign Control | Stop | | | Free | Free | |
| Grade | 0% | | | 0% | 0% | |
| Peak Hour Factor | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 |
| Hourly flow rate (vph) | 41 | 49 | 89 | 475 | 298 | 48 |
| Pedestrians | 1 | | | 4 | 10 | |
| Lane Width (ft) | 12.0 | | | 12.0 | 12.0 | |
| Walking Speed (ft/s) | 4.0 | | | 4.0 | 4.0 | |
| Percent Blockage | 0 | | | 0 | 1 | |
| Right turn flare (veh) | | | | | | |
| Median type | | | | None | None | |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | | | 308 | 475 | |
| pX, platoon unblocked | 0.96 | | | | | |
| vC, conflicting volume | 986 | 327 | 347 | | | |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 962 | 327 | 347 | | | |
| tC, single (s) | 6.4 | 6.2 | 4.1 | | | |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 3.5 | 3.3 | 2.2 | | | |
| p0 queue free % | 84 | 93 | 93 | | | |
| cM capacity (veh/h) | 251 | 716 | 1222 | | | |
| Direction, Lane # | EB 1 | NB 1 | NB 2 | SB 1 | | |
| Volume Total | 90 | 89 | 475 | 346 | | |
| Volume Left | 41 | 89 | 0 | 0 | | |
| Volume Right | 49 | 0 | 0 | 48 | | |
| cSH | 391 | 1222 | 1700 | 1700 | | |
| Volume to Capacity | 0.23 | 0.07 | 0.28 | 0.20 | | |
| Queue Length 95th (ft) | 23 | 6 | 0 | 0 | | |
| Control Delay (s) | 17.0 | 8.2 | 0.0 | 0.0 | | |
| Lane LOS | C | A | | | | |
| Approach Delay (s) | 17.0 | 1.3 | | 0.0 | | |
| Approach LOS | C | | | | | |
| Intersection Summary | | | | | | |
| Average Delay | | | 2.3 | | | |
| Intersection Capacity Utilization | | | 37.5% | | ICU Level of Service | A |
| Analysis Period (min) | | | 15 | | | |

HCM Unsignalized Intersection Capacity Analysis
6: Site Entrance 2 & Martinazzi Ave

4/17/2013



| Movement | WBL | WBR | NBT | NBR | SBL | SBT |
|------------------------|------|------|------|------|------|------|
| Lane Configurations | Y | | B | | | ↑↑ |
| Volume (veh/h) | 5 | 25 | 489 | 9 | 3 | 314 |
| Sign Control | Stop | | Free | | | Free |
| Grade | 0% | | 0% | | | 0% |
| Peak Hour Factor | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 |
| Hourly flow rate (vph) | 6 | 28 | 543 | 10 | 3 | 349 |
| Pedestrians | 19 | | | | | 2 |
| Lane Width (ft) | 12.0 | | | | | 12.0 |
| Walking Speed (ft/s) | 4.0 | | | | | 4.0 |
| Percent Blockage | 2 | | | | | 0 |
| Right turn flare (veh) | | | | | | |
| Median type | | | None | | | None |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | | 227 | | | 556 |
| pX, platoon unblocked | 0.90 | 0.90 | | | 0.90 | |
| vC, conflicting volume | 748 | 569 | | | 572 | |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 660 | 460 | | | 464 | |
| tC, single (s) | 6.8 | 6.9 | | | 4.1 | |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 3.5 | 3.3 | | | 2.2 | |
| p0 queue free % | 98 | 94 | | | 100 | |
| cM capacity (veh/h) | 352 | 487 | | | 976 | |

| Direction, Lane # | WB 1 | NB 1 | SB 1 | SB 2 |
|------------------------|------|------|------|------|
| Volume Total | 33 | 553 | 120 | 233 |
| Volume Left | 6 | 0 | 3 | 0 |
| Volume Right | 28 | 10 | 0 | 0 |
| cSH | 457 | 1700 | 976 | 1700 |
| Volume to Capacity | 0.07 | 0.33 | 0.00 | 0.14 |
| Queue Length 95th (ft) | 6 | 0 | 0 | 0 |
| Control Delay (s) | 13.5 | 0.0 | 0.3 | 0.0 |
| Lane LOS | B | | A | |
| Approach Delay (s) | 13.5 | 0.0 | 0.1 | |
| Approach LOS | B | | | |

| Intersection Summary | | | |
|-----------------------------------|--|-------|------------------------|
| Average Delay | | 0.5 | |
| Intersection Capacity Utilization | | 37.0% | ICU Level of Service A |
| Analysis Period (min) | | 15 | |

HCM Unsignalized Intersection Capacity Analysis
 7: RO Only & Martinazzi Ave

4/17/2013

| | ↙ | ↖ | ↑ | ↗ | ↘ | ↓ |
|-----------------------------------|-------------|-------------|-------------|-------------|----------------------|------|
| Movement | WBL | WBR | NBT | NBR | SBL | SBT |
| Lane Configurations | | ↗ | ↑ | | | ↘↘ |
| Volume (veh/h) | 0 | 10 | 488 | 0 | 0 | 318 |
| Sign Control | Stop | | Free | | | Free |
| Grade | 0% | | 0% | | | 0% |
| Peak Hour Factor | 0.89 | 0.89 | 0.89 | 0.89 | 0.89 | 0.89 |
| Hourly flow rate (vph) | 0 | 11 | 548 | 0 | 0 | 357 |
| Pedestrians | 13 | | | | | |
| Lane Width (ft) | 12.0 | | | | | |
| Walking Speed (ft/s) | 4.0 | | | | | |
| Percent Blockage | 1 | | | | | |
| Right turn flare (veh) | | | | | | |
| Median type | | | None | | | None |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | | 125 | | | 658 |
| pX, platoon unblocked | 0.88 | 0.88 | | | 0.88 | |
| vC, conflicting volume | 740 | 561 | | | 561 | |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 640 | 438 | | | 438 | |
| tC, single (s) | 6.8 | 6.9 | | | 4.1 | |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 3.5 | 3.3 | | | 2.2 | |
| p0 queue free % | 100 | 98 | | | 100 | |
| cM capacity (veh/h) | 361 | 500 | | | 990 | |
| Direction, Lane # | WB 1 | NB 1 | SB 1 | SB 2 | | |
| Volume Total | 11 | 548 | 179 | 179 | | |
| Volume Left | 0 | 0 | 0 | 0 | | |
| Volume Right | 11 | 0 | 0 | 0 | | |
| cSH | 500 | 1700 | 1700 | 1700 | | |
| Volume to Capacity | 0.02 | 0.32 | 0.11 | 0.11 | | |
| Queue Length 95th (ft) | 2 | 0 | 0 | 0 | | |
| Control Delay (s) | 12.4 | 0.0 | 0.0 | 0.0 | | |
| Lane LOS | B | | | | | |
| Approach Delay (s) | 12.4 | 0.0 | 0.0 | | | |
| Approach LOS | B | | | | | |
| Intersection Summary | | | | | | |
| Average Delay | | | 0.2 | | | |
| Intersection Capacity Utilization | | | 35.7% | | ICU Level of Service | A |
| Analysis Period (min) | | | 15 | | | |

HCM Signalized Intersection Capacity Analysis
 8: Nyberg St & Martinazzi Ave

4/17/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR | |
|-----------------------------------|-------|------|-------|-------|------|------|------|------|-------|------|------|----------------------|------|
| Lane Configurations | | | | | | | | | | | | | |
| Volume (vph) | 16 | 1 | 63 | 227 | 37 | 237 | 23 | 235 | 31 | 0 | 310 | 8 | |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | |
| Total Lost time (s) | 5.5 | 5.5 | | 5.5 | 5.5 | 5.5 | 5.5 | 5.5 | | | 5.5 | | |
| Lane Util. Factor | 1.00 | 1.00 | | 0.95 | 0.95 | 1.00 | 1.00 | 1.00 | | | 0.95 | | |
| Frpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 0.97 | 1.00 | 1.00 | | | 1.00 | | |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | 1.00 | | |
| Frt | 1.00 | 0.85 | | 1.00 | 1.00 | 0.85 | 1.00 | 0.98 | | | 1.00 | | |
| Fit Protected | 0.95 | 1.00 | | 0.95 | 0.97 | 1.00 | 0.95 | 1.00 | | | 1.00 | | |
| Satd. Flow (prot) | 1805 | 1603 | | 1698 | 1730 | 1542 | 1683 | 1842 | | | 3559 | | |
| Fit Permitted | 0.95 | 1.00 | | 0.95 | 0.97 | 1.00 | 0.54 | 1.00 | | | 1.00 | | |
| Satd. Flow (perm) | 1805 | 1603 | | 1698 | 1730 | 1542 | 960 | 1842 | | | 3559 | | |
| Peak-hour factor, PHF | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | |
| Adj. Flow (vph) | 18 | 1 | 69 | 249 | 41 | 260 | 25 | 258 | 34 | 0 | 341 | 9 | |
| RTOR Reduction (vph) | 0 | 63 | 0 | 0 | 0 | 204 | 0 | 7 | 0 | 0 | 3 | 0 | |
| Lane Group Flow (vph) | 18 | 7 | 0 | 144 | 146 | 56 | 25 | 285 | 0 | 0 | 347 | 0 | |
| Confl. Peds. (#/hr) | 2 | | | | | 2 | 3 | | 16 | 16 | | 3 | |
| Confl. Bikes (#/hr) | | | | | | 2 | | | | | | 3 | |
| Heavy Vehicles (%) | 0% | 0% | 1% | 1% | 0% | 2% | 7% | 1% | 0% | 0% | 1% | 0% | |
| Turn Type | Split | | | Split | | | Perm | Perm | | | | | |
| Protected Phases | 8 | 8 | | 4 | 4 | | | | 6 | | | 2 | |
| Permitted Phases | | | | | | 4 | 6 | | | | | | |
| Actuated Green, G (s) | 3.1 | 3.1 | | 8.9 | 8.9 | 8.9 | 13.8 | 13.8 | | | | 13.8 | |
| Effective Green, g (s) | 3.6 | 3.6 | | 9.4 | 9.4 | 9.4 | 14.3 | 14.3 | | | | 14.3 | |
| Actuated g/C Ratio | 0.08 | 0.08 | | 0.21 | 0.21 | 0.21 | 0.33 | 0.33 | | | | 0.33 | |
| Clearance Time (s) | 6.0 | 6.0 | | 6.0 | 6.0 | 6.0 | 6.0 | 6.0 | | | | 6.0 | |
| Vehicle Extension (s) | 2.5 | 2.5 | | 2.5 | 2.5 | 2.5 | 5.0 | 5.0 | | | | 5.0 | |
| Lane Grp Cap (vph) | 148 | 132 | | 364 | 371 | 331 | 313 | 601 | | | | 1162 | |
| v/s Ratio Prot | c0.01 | 0.00 | | c0.08 | 0.08 | | | | c0.15 | | | 0.10 | |
| v/s Ratio Perm | | | | | | 0.04 | 0.03 | | | | | | |
| v/c Ratio | 0.12 | 0.05 | | 0.40 | 0.39 | 0.17 | 0.08 | 0.47 | | | | 0.30 | |
| Uniform Delay, d1 | 18.6 | 18.5 | | 14.8 | 14.8 | 14.0 | 10.2 | 11.8 | | | | 11.0 | |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | | 1.00 | |
| Incremental Delay, d2 | 0.3 | 0.1 | | 0.5 | 0.5 | 0.2 | 0.2 | 1.2 | | | | 0.3 | |
| Delay (s) | 18.9 | 18.6 | | 15.3 | 15.3 | 14.2 | 10.4 | 13.0 | | | | 11.3 | |
| Level of Service | B | B | | B | B | B | B | B | | | | B | |
| Approach Delay (s) | | 18.7 | | | 14.8 | | | 12.8 | | | | 11.3 | |
| Approach LOS | | B | | | B | | | B | | | | B | |
| Intersection Summary | | | | | | | | | | | | | |
| HCM Average Control Delay | | | 13.6 | | | | | | | | | HCM Level of Service | B |
| HCM Volume to Capacity ratio | | | 0.40 | | | | | | | | | | |
| Actuated Cycle Length (s) | | | 43.8 | | | | | | | | | Sum of lost time (s) | 16.5 |
| Intersection Capacity Utilization | | | 48.1% | | | | | | | | | ICU Level of Service | A |
| Analysis Period (min) | | | 15 | | | | | | | | | | |

c Critical Lane Group

HCM Unsignalized Intersection Capacity Analysis
 9: Nyberg St & Site Entrance 3

4/17/2013



| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
|------------------------|------|------|------|------|------|------|
| Lane Configurations | ↵ | | ↕↕ | | | ↵ |
| Volume (veh/h) | 32 | 0 | 447 | 50 | 0 | 53 |
| Sign Control | | Free | Free | | Stop | |
| Grade | | 0% | 0% | | 0% | |
| Peak Hour Factor | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 |
| Hourly flow rate (vph) | 36 | 0 | 508 | 57 | 0 | 60 |
| Pedestrians | | | | | 4 | |
| Lane Width (ft) | | | | | 12.0 | |
| Walking Speed (ft/s) | | | | | 4.0 | |
| Percent Blockage | | | | | 0 | |
| Right turn flare (veh) | | | | | | |
| Median type | | None | None | | | |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | 248 | | | | |
| pX, platoon unblocked | | | | | | |
| vC, conflicting volume | 569 | | | | 613 | 286 |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 569 | | | | 613 | 286 |
| tC, single (s) | 4.1 | | | | 6.8 | 6.9 |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 2.2 | | | | 3.5 | 3.3 |
| p0 queue free % | 96 | | | | 100 | 92 |
| cM capacity (veh/h) | 1010 | | | | 412 | 714 |

| Direction, Lane # | EB 1 | WB 1 | WB 2 | SB 1 |
|------------------------|------|------|------|------|
| Volume Total | 36 | 339 | 226 | 60 |
| Volume Left | 36 | 0 | 0 | 0 |
| Volume Right | 0 | 0 | 57 | 60 |
| cSH | 1010 | 1700 | 1700 | 714 |
| Volume to Capacity | 0.04 | 0.20 | 0.13 | 0.08 |
| Queue Length 95th (ft) | 3 | 0 | 0 | 7 |
| Control Delay (s) | 8.7 | 0.0 | 0.0 | 10.5 |
| Lane LOS | A | | | B |
| Approach Delay (s) | 8.7 | 0.0 | | 10.5 |
| Approach LOS | | | | B |

| Intersection Summary | | | |
|-----------------------------------|--|-------|------------------------|
| Average Delay | | 1.4 | |
| Intersection Capacity Utilization | | 24.0% | ICU Level of Service A |
| Analysis Period (min) | | 15 | |

HCM Signalized Intersection Capacity Analysis
 10: Tualatin Sherwood Rd & Site Entrance 4

4/17/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|------|-------|------|-------|------|------|------|------|-------|------|-------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 50 | 1375 | 59 | 257 | 1498 | 101 | 57 | 25 | 248 | 154 | 40 | 62 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 6.0 | | 4.5 | 6.0 | | | 5.0 | 4.5 | | 5.0 | 5.0 |
| Lane Util. Factor | 1.00 | *0.75 | | 0.97 | 0.91 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 0.98 |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frt | 1.00 | 0.99 | | 1.00 | 0.99 | | | 1.00 | 0.85 | | 1.00 | 0.85 |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.97 | 1.00 | | 0.96 | 1.00 |
| Satd. Flow (prot) | 1805 | 4092 | | 3502 | 4943 | | | 1799 | 1599 | | 1813 | 1579 |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.50 | 1.00 | | 0.71 | 1.00 |
| Satd. Flow (perm) | 1805 | 4092 | | 3502 | 4943 | | | 925 | 1599 | | 1347 | 1579 |
| Peak-hour factor, PHF | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 |
| Adj. Flow (vph) | 51 | 1403 | 60 | 262 | 1529 | 103 | 58 | 26 | 253 | 157 | 41 | 63 |
| RTOR Reduction (vph) | 0 | 3 | 0 | 0 | 5 | 0 | 0 | 0 | 0 | 0 | 0 | 52 |
| Lane Group Flow (vph) | 51 | 1460 | 0 | 262 | 1627 | 0 | 0 | 84 | 253 | 0 | 198 | 11 |
| Confl. Peds. (#/hr) | | | | | | 4 | | | | | | 9 |
| Confl. Bikes (#/hr) | | | | | 1 | | | 1 | | 1 | | |
| Heavy Vehicles (%) | 0% | 4% | 0% | 0% | 4% | 0% | 3% | 0% | 1% | 1% | 0% | 0% |
| Turn Type | Prot | | | Prot | | | Perm | | pm+ov | Perm | | Perm |
| Protected Phases | 5 | 2 | | 1 | 6 | | | 8 | 1 | | 4 | |
| Permitted Phases | | | | | | | 8 | | 8 | 4 | | 4 |
| Actuated Green, G (s) | 8.0 | 65.9 | | 11.7 | 69.6 | | | 20.4 | 32.1 | | 20.4 | 20.4 |
| Effective Green, g (s) | 8.5 | 66.4 | | 12.2 | 70.1 | | | 20.9 | 33.1 | | 20.9 | 20.9 |
| Actuated g/C Ratio | 0.07 | 0.58 | | 0.11 | 0.61 | | | 0.18 | 0.29 | | 0.18 | 0.18 |
| Clearance Time (s) | 5.0 | 6.5 | | 5.0 | 6.5 | | | 5.5 | 5.0 | | 5.5 | 5.5 |
| Vehicle Extension (s) | 2.5 | 4.0 | | 2.5 | 4.0 | | | 2.5 | 2.5 | | 2.5 | 2.5 |
| Lane Grp Cap (vph) | 133 | 2363 | | 372 | 3013 | | | 168 | 460 | | 245 | 287 |
| v/s Ratio Prot | 0.03 | c0.36 | | c0.07 | 0.33 | | | | 0.06 | | | |
| v/s Ratio Perm | | | | | | | | 0.09 | 0.10 | | c0.15 | 0.01 |
| v/c Ratio | 0.38 | 0.62 | | 0.70 | 0.54 | | | 0.50 | 0.55 | | 0.81 | 0.04 |
| Uniform Delay, d1 | 50.8 | 16.0 | | 49.7 | 13.1 | | | 42.3 | 34.6 | | 45.1 | 38.8 |
| Progression Factor | 0.84 | 0.72 | | 0.98 | 0.68 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Incremental Delay, d2 | 1.1 | 1.0 | | 4.4 | 0.6 | | | 1.7 | 1.1 | | 17.1 | 0.0 |
| Delay (s) | 43.8 | 12.5 | | 52.9 | 9.4 | | | 44.0 | 35.8 | | 62.2 | 38.8 |
| Level of Service | D | B | | D | A | | | D | D | | E | D |
| Approach Delay (s) | | 13.6 | | | 15.5 | | | 37.8 | | | 56.5 | |
| Approach LOS | | B | | | B | | | D | | | E | |

| Intersection Summary | | | |
|-----------------------------------|-------|----------------------|------|
| HCM Average Control Delay | 19.3 | HCM Level of Service | B |
| HCM Volume to Capacity ratio | 0.67 | | |
| Actuated Cycle Length (s) | 115.0 | Sum of lost time (s) | 15.5 |
| Intersection Capacity Utilization | 70.3% | ICU Level of Service | C |
| Analysis Period (min) | 15 | | |

c Critical Lane Group

HCM Unsignalized Intersection Capacity Analysis
 11: Tualatin Sherwood Rd & 75th Ave

4/17/2013



| Movement | EBL | EBT | WBT | WBR | SBL | SBR | |
|-----------------------------------|------|------|-------|------|----------------------|------|------|
| Lane Configurations | | ↑↑↑ | ↑↑↑ | | | ↗ | |
| Volume (veh/h) | 0 | 1785 | 1847 | 48 | 0 | 15 | |
| Sign Control | | Free | Free | | Stop | | |
| Grade | | 0% | 0% | | 0% | | |
| Peak Hour Factor | 0.97 | 0.97 | 0.97 | 0.97 | 0.97 | 0.97 | |
| Hourly flow rate (vph) | 0 | 1840 | 1904 | 49 | 0 | 15 | |
| Pedestrians | | | | | 6 | | |
| Lane Width (ft) | | | | | 12.0 | | |
| Walking Speed (ft/s) | | | | | 4.0 | | |
| Percent Blockage | | | | | 1 | | |
| Right turn flare (veh) | | | | | | | |
| Median type | | None | None | | | | |
| Median storage (veh) | | | | | | | |
| Upstream signal (ft) | | 373 | 260 | | | | |
| pX, platoon unblocked | 0.83 | | | | 0.88 | 0.83 | |
| vC, conflicting volume | 1960 | | | | 2548 | 665 | |
| vC1, stage 1 conf vol | | | | | | | |
| vC2, stage 2 conf vol | | | | | | | |
| vCu, unblocked vol | 1432 | | | | 956 | 0 | |
| tC, single (s) | 4.1 | | | | 6.8 | 7.4 | |
| tC, 2 stage (s) | | | | | | | |
| tF (s) | 2.2 | | | | 3.5 | 3.5 | |
| p0 queue free % | 100 | | | | 100 | 98 | |
| cM capacity (veh/h) | 396 | | | | 227 | 835 | |
| Direction, Lane # | EB 1 | EB 2 | EB 3 | WB 1 | WB 2 | WB 3 | SB 1 |
| Volume Total | 613 | 613 | 613 | 762 | 762 | 430 | 15 |
| Volume Left | 0 | 0 | 0 | 0 | 0 | 0 | 0 |
| Volume Right | 0 | 0 | 0 | 0 | 0 | 49 | 15 |
| cSH | 1700 | 1700 | 1700 | 1700 | 1700 | 1700 | 835 |
| Volume to Capacity | 0.36 | 0.36 | 0.36 | 0.45 | 0.45 | 0.25 | 0.02 |
| Queue Length 95th (ft) | 0 | 0 | 0 | 0 | 0 | 0 | 1 |
| Control Delay (s) | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 9.4 |
| Lane LOS | | | | | | | A |
| Approach Delay (s) | 0.0 | | | 0.0 | | | 9.4 |
| Approach LOS | | | | | | | A |
| Intersection Summary | | | | | | | |
| Average Delay | | | 0.0 | | | | |
| Intersection Capacity Utilization | | | 46.8% | | ICU Level of Service | | A |
| Analysis Period (min) | | | 15 | | | | |













HCM Signalized Intersection Capacity Analysis
 12: Tualatin Sherwood Rd & I-5 SB Ramps

4/17/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|------|-------|-------|-------|------|----------------------|------|------|------|-------|------|--------|
| Lane Configurations | | ↑↑↑ | ↑ | ↑ | ↑↑ | | | | | ↑ | ↑ | ↑↑ |
| Volume (vph) | 0 | 1370 | 415 | 193 | 1030 | 0 | 0 | 0 | 0 | 620 | 3 | 865 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | | 5.5 | 5.5 | 5.5 | 5.5 | | | | | 5.5 | 5.5 | 5.5 |
| Lane Util. Factor | | *0.75 | 1.00 | 1.00 | 0.95 | | | | | 0.95 | 0.95 | 0.88 |
| Frpb, ped/bikes | | 1.00 | 1.00 | 1.00 | 1.00 | | | | | 1.00 | 1.00 | 1.00 |
| Flpb, ped/bikes | | 1.00 | 1.00 | 1.00 | 1.00 | | | | | 1.00 | 1.00 | 1.00 |
| Frt | | 1.00 | 0.85 | 1.00 | 1.00 | | | | | 1.00 | 1.00 | 0.85 |
| Flt Protected | | 1.00 | 1.00 | 0.95 | 1.00 | | | | | 0.95 | 0.95 | 1.00 |
| Satd. Flow (prot) | | 4150 | 1568 | 1787 | 3471 | | | | | 1681 | 1683 | 2760 |
| Flt Permitted | | 1.00 | 1.00 | 0.95 | 1.00 | | | | | 0.95 | 0.95 | 1.00 |
| Satd. Flow (perm) | | 4150 | 1568 | 1787 | 3471 | | | | | 1681 | 1683 | 2760 |
| Peak-hour factor, PHF | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 |
| Adj. Flow (vph) | 0 | 1384 | 419 | 195 | 1040 | 0 | 0 | 0 | 0 | 626 | 3 | 874 |
| RTOR Reduction (vph) | 0 | 0 | 208 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 61 |
| Lane Group Flow (vph) | 0 | 1384 | 211 | 195 | 1040 | 0 | 0 | 0 | 0 | 313 | 316 | 813 |
| Confl. Bikes (#/hr) | | 1 | | | 2 | | | | | | | |
| Heavy Vehicles (%) | 0% | 3% | 3% | 1% | 4% | 0% | 0% | 0% | 0% | 2% | 20% | 3% |
| Turn Type | | | Perm | Prot | | | | | | Split | | custom |
| Protected Phases | | 2 | | 1 | 6 | | | | | 4 | 4 | 4.5 |
| Permitted Phases | | | 2 | | | | | | | | | |
| Actuated Green, G (s) | | 54.8 | 54.8 | 14.6 | 58.4 | | | | | 27.6 | 27.6 | 44.6 |
| Effective Green, g (s) | | 55.3 | 55.3 | 15.1 | 58.9 | | | | | 28.1 | 28.1 | 41.6 |
| Actuated g/C Ratio | | 0.48 | 0.48 | 0.13 | 0.51 | | | | | 0.24 | 0.24 | 0.36 |
| Clearance Time (s) | | 6.0 | 6.0 | 6.0 | 6.0 | | | | | 6.0 | 6.0 | |
| Vehicle Extension (s) | | 6.1 | 6.1 | 2.3 | 6.1 | | | | | 2.3 | 2.3 | |
| Lane Grp Cap (vph) | | 1996 | 754 | 235 | 1778 | | | | | 411 | 411 | 998 |
| v/s Ratio Prot | | c0.33 | | c0.11 | 0.30 | | | | | 0.19 | 0.19 | c0.29 |
| v/s Ratio Perm | | | 0.13 | | | | | | | | | |
| v/c Ratio | | 0.69 | 0.28 | 0.83 | 0.58 | | | | | 0.76 | 0.77 | 0.81 |
| Uniform Delay, d1 | | 23.2 | 17.9 | 48.7 | 19.5 | | | | | 40.3 | 40.4 | 33.2 |
| Progression Factor | | 0.71 | 0.55 | 0.74 | 1.22 | | | | | 1.00 | 1.00 | 1.00 |
| Incremental Delay, d2 | | 1.6 | 0.8 | 19.4 | 1.3 | | | | | 7.6 | 7.9 | 5.0 |
| Delay (s) | | 18.1 | 10.6 | 55.5 | 25.2 | | | | | 47.9 | 48.3 | 38.2 |
| Level of Service | | B | B | E | C | | | | | D | D | D |
| Approach Delay (s) | | 16.4 | | | 30.0 | | | 0.0 | | | 42.4 | |
| Approach LOS | | B | | | C | | | A | | | D | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 28.7 | | | HCM Level of Service | | | | C | | |
| HCM Volume to Capacity ratio | | | 0.81 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 115.0 | | | Sum of lost time (s) | | | 22.0 | | | |
| Intersection Capacity Utilization | | | 68.2% | | | ICU Level of Service | | | | C | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 13: Tualatin Sherwood Rd & I-5 NB Ramps

4/17/2013

| |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | | ↑↑ | ↑↑ | | ↑↑ | ↑ | ↑ | ↑ | ↑ | | | |
| Volume (vph) | 0 | 1077 | 917 | 0 | 628 | 666 | 592 | 0 | 219 | 0 | 0 | 0 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | | 5.5 | 5.5 | | 6.0 | 6.0 | 5.5 | 5.5 | 5.5 | | | |
| Lane Util. Factor | | 0.95 | 0.88 | | 0.95 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Frbp, ped/bikes | | 1.00 | 0.98 | | 1.00 | 1.00 | 1.00 | 1.00 | 0.98 | | | |
| Flpb, ped/bikes | | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Frt | | 1.00 | 0.85 | | 1.00 | 0.85 | 1.00 | 1.00 | 0.85 | | | |
| Flt Protected | | 1.00 | 1.00 | | 1.00 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Satd. Flow (prot) | | 3574 | 2694 | | 3574 | 1583 | 1618 | 1618 | 1559 | | | |
| Flt Permitted | | 1.00 | 1.00 | | 1.00 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Satd. Flow (perm) | | 3574 | 2694 | | 3574 | 1583 | 1618 | 1618 | 1559 | | | |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 0 | 1134 | 965 | 0 | 661 | 701 | 623 | 0 | 231 | 0 | 0 | 0 |
| RTOR Reduction (vph) | 0 | 0 | 328 | 0 | 0 | 241 | 0 | 0 | 32 | 0 | 0 | 0 |
| Lane Group Flow (vph) | 0 | 1134 | 637 | 0 | 661 | 460 | 311 | 312 | 199 | 0 | 0 | 0 |
| Confl. Peds. (#/hr) | | | 1 | 1 | | | 1 | | 2 | 2 | | 1 |
| Confl. Bikes (#/hr) | | 1 | | | 5 | | | | | 1 | | |
| Heavy Vehicles (%) | 0% | 1% | 3% | 0% | 1% | 2% | 6% | 20% | 2% | 0% | 0% | 0% |
| Turn Type | | | Perm | | | Perm | Split | | Perm | | | |
| Protected Phases | | 2 | | | 6 | | 8 | 8 | | | | |
| Permitted Phases | | | 2 | | | 6 | | | 8 | | | |
| Actuated Green, G (s) | | 75.4 | 75.4 | | 74.9 | 74.9 | 27.6 | 27.6 | 27.6 | | | |
| Effective Green, g (s) | | 75.9 | 75.9 | | 75.4 | 75.4 | 28.1 | 28.1 | 28.1 | | | |
| Actuated g/C Ratio | | 0.66 | 0.66 | | 0.66 | 0.66 | 0.24 | 0.24 | 0.24 | | | |
| Clearance Time (s) | | 6.0 | 6.0 | | 6.5 | 6.5 | 6.0 | 6.0 | 6.0 | | | |
| Vehicle Extension (s) | | 6.1 | 6.1 | | 4.2 | 4.2 | 2.3 | 2.3 | 2.3 | | | |
| Lane Grp Cap (vph) | | 2359 | 1778 | | 2343 | 1038 | 395 | 395 | 381 | | | |
| v/s Ratio Prot | | c0.32 | | | 0.18 | | 0.19 | c0.19 | | | | |
| v/s Ratio Perm | | | 0.24 | | | 0.29 | | | 0.13 | | | |
| v/c Ratio | | 0.48 | 0.36 | | 0.28 | 0.44 | 0.79 | 0.79 | 0.52 | | | |
| Uniform Delay, d1 | | 9.7 | 8.7 | | 8.4 | 9.6 | 40.7 | 40.7 | 37.6 | | | |
| Progression Factor | | 1.39 | 6.09 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Incremental Delay, d2 | | 0.5 | 0.4 | | 0.3 | 1.4 | 9.5 | 9.6 | 0.8 | | | |
| Delay (s) | | 14.0 | 53.5 | | 8.7 | 11.0 | 50.1 | 50.3 | 38.5 | | | |
| Level of Service | | B | D | | A | B | D | D | D | | | |
| Approach Delay (s) | | 32.2 | | | 9.9 | | | 47.0 | | | 0.0 | |
| Approach LOS | | C | | | A | | | D | | | A | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 28.1 | | | | | | | | | HCM Level of Service C |
| HCM Volume to Capacity ratio | | | 0.56 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 115.0 | | | | | | | | 11.0 | Sum of lost time (s) |
| Intersection Capacity Utilization | | | 67.2% | | | | | | | | | ICU Level of Service C |
| Analysis Period (min) | | | 15 | | | | | | | | | |

c Critical Lane Group

HCM Signalized Intersection Capacity Analysis
 14: Tualatin Sherwood Rd & Nyberg Woods

4/17/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|-------|------|-------|------|-------|------|------|-------|------|------|------|------------------------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 524 | 560 | 57 | 15 | 692 | 101 | 103 | 11 | 12 | 101 | 11 | 322 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 5.5 | 5.5 | | 5.5 | 5.5 | | | 5.5 | 5.5 | | 5.5 | 5.5 |
| Lane Util. Factor | 0.97 | 0.95 | | 1.00 | 0.95 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 0.99 | | 1.00 | 0.99 |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frt | 1.00 | 0.99 | | 1.00 | 0.98 | | | 1.00 | 0.85 | | 1.00 | 0.85 |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.96 | 1.00 | | 0.96 | 1.00 |
| Satd. Flow (prot) | 3502 | 3483 | | 1805 | 3502 | | | 1768 | 1593 | | 1799 | 1594 |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.66 | 1.00 | | 0.66 | 1.00 |
| Satd. Flow (perm) | 3502 | 3483 | | 1805 | 3502 | | | 1229 | 1593 | | 1249 | 1594 |
| Peak-hour factor, PHF | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 |
| Adj. Flow (vph) | 546 | 583 | 59 | 16 | 721 | 105 | 107 | 11 | 12 | 105 | 11 | 335 |
| RTOR Reduction (vph) | 0 | 5 | 0 | 0 | 10 | 0 | 0 | 0 | 10 | 0 | 0 | 282 |
| Lane Group Flow (vph) | 546 | 637 | 0 | 16 | 816 | 0 | 0 | 118 | 2 | 0 | 116 | 53 |
| Confl. Peds. (#/hr) | 8 | | 2 | 2 | | 8 | 1 | | 2 | 2 | | 1 |
| Confl. Bikes (#/hr) | | 1 | | | 3 | | | | | | | |
| Heavy Vehicles (%) | 0% | 2% | 2% | 0% | 1% | 0% | 3% | 0% | 0% | 1% | 0% | 0% |
| Turn Type | Prot | | | Prot | | | Perm | | Perm | Perm | | Perm |
| Protected Phases | 5 | 2 | | 1 | 6 | | | 8 | | | 4 | |
| Permitted Phases | | | | | | | 8 | | 8 | 4 | | 4 |
| Actuated Green, G (s) | 13.9 | 36.2 | | 0.8 | 23.1 | | | 9.8 | 9.8 | | 9.8 | 9.8 |
| Effective Green, g (s) | 14.4 | 36.7 | | 1.3 | 23.6 | | | 10.3 | 10.3 | | 10.3 | 10.3 |
| Actuated g/C Ratio | 0.22 | 0.57 | | 0.02 | 0.36 | | | 0.16 | 0.16 | | 0.16 | 0.16 |
| Clearance Time (s) | 6.0 | 6.0 | | 6.0 | 6.0 | | | 6.0 | 6.0 | | 6.0 | 6.0 |
| Vehicle Extension (s) | 2.3 | 2.5 | | 2.4 | 2.5 | | | 2.4 | 2.4 | | 2.3 | 2.3 |
| Lane Grp Cap (vph) | 778 | 1973 | | 36 | 1275 | | | 195 | 253 | | 199 | 253 |
| v/s Ratio Prot | c0.16 | 0.18 | | 0.01 | c0.23 | | | | | | | |
| v/s Ratio Perm | | | | | | | | c0.10 | 0.00 | | 0.09 | 0.03 |
| v/c Ratio | 0.70 | 0.32 | | 0.44 | 0.64 | | | 0.61 | 0.01 | | 0.58 | 0.21 |
| Uniform Delay, d1 | 23.2 | 7.5 | | 31.4 | 17.1 | | | 25.4 | 22.9 | | 25.3 | 23.7 |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Incremental Delay, d2 | 2.5 | 0.1 | | 5.6 | 0.9 | | | 4.3 | 0.0 | | 3.3 | 0.2 |
| Delay (s) | 25.8 | 7.5 | | 37.0 | 18.0 | | | 29.6 | 23.0 | | 28.5 | 24.0 |
| Level of Service | C | A | | D | B | | | C | C | | C | C |
| Approach Delay (s) | | 15.9 | | | 18.4 | | | 29.0 | | | 25.1 | |
| Approach LOS | | B | | | B | | | C | | | C | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 18.9 | | | | | | | | | HCM Level of Service B |
| HCM Volume to Capacity ratio | | | 0.65 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 64.8 | | | | | | | | 16.5 | Sum of lost time (s) |
| Intersection Capacity Utilization | | | 64.5% | | | | | | | | | ICU Level of Service C |
| Analysis Period (min) | | | 15 | | | | | | | | | |

c Critical Lane Group

HCM Signalized Intersection Capacity Analysis
 17: Tualatin Sherwood Rd & Martinazzi Ave

4/17/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|------|-------|------|------|-------|------|----------------------|-------|------|------|-------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 69 | 1140 | 141 | 0 | 1119 | 0 | 100 | 221 | 216 | 129 | 382 | 88 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 5.5 | | | 5.5 | | 4.5 | 5.5 | 5.5 | 4.5 | 5.5 | |
| Lane Util. Factor | 1.00 | 0.95 | | | 0.95 | | 1.00 | 1.00 | 1.00 | 1.00 | 0.95 | |
| Frbp, ped/bikes | 1.00 | 1.00 | | | 1.00 | | 1.00 | 1.00 | 0.96 | 1.00 | 1.00 | |
| Flpb, ped/bikes | 1.00 | 1.00 | | | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | |
| Frt | 1.00 | 0.98 | | | 1.00 | | 1.00 | 1.00 | 0.85 | 1.00 | 0.97 | |
| Flt Protected | 0.95 | 1.00 | | | 1.00 | | 0.95 | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (prot) | 1719 | 3428 | | | 3438 | | 1770 | 1863 | 1537 | 1787 | 3463 | |
| Flt Permitted | 0.95 | 1.00 | | | 1.00 | | 0.95 | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (perm) | 1719 | 3428 | | | 3438 | | 1770 | 1863 | 1537 | 1787 | 3463 | |
| Peak-hour factor, PHF | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 |
| Adj. Flow (vph) | 73 | 1213 | 150 | 0 | 1190 | 0 | 106 | 235 | 230 | 137 | 406 | 94 |
| RTOR Reduction (vph) | 0 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 108 | 0 | 20 | 0 |
| Lane Group Flow (vph) | 73 | 1357 | 0 | 0 | 1190 | 0 | 106 | 235 | 122 | 137 | 480 | 0 |
| Confl. Peds. (#/hr) | | | | | | 6 | | | 23 | | | 3 |
| Heavy Vehicles (%) | 5% | 4% | 0% | 0% | 5% | 0% | 2% | 2% | 1% | 1% | 1% | 1% |
| Turn Type | Prot | | | Prot | | | Perm | | | Prot | | |
| Protected Phases | 5 | 2 | | | 6 | | 3 | 8 | | 7 | 4 | |
| Permitted Phases | | | | | | | | | 8 | | | |
| Actuated Green, G (s) | 7.4 | 67.3 | | | 54.9 | | 10.6 | 17.7 | 17.7 | 13.0 | 20.1 | |
| Effective Green, g (s) | 7.9 | 67.8 | | | 55.4 | | 11.1 | 18.2 | 18.2 | 13.5 | 20.6 | |
| Actuated g/C Ratio | 0.07 | 0.59 | | | 0.48 | | 0.10 | 0.16 | 0.16 | 0.12 | 0.18 | |
| Clearance Time (s) | 5.0 | 6.0 | | | 6.0 | | 5.0 | 6.0 | 6.0 | 5.0 | 6.0 | |
| Vehicle Extension (s) | 2.0 | 3.5 | | | 3.5 | | 3.0 | 2.0 | 2.0 | 3.0 | 2.0 | |
| Lane Grp Cap (vph) | 118 | 2021 | | | 1656 | | 171 | 295 | 243 | 210 | 620 | |
| v/s Ratio Prot | 0.04 | c0.40 | | | c0.35 | | 0.06 | c0.13 | | 0.08 | c0.14 | |
| v/s Ratio Perm | | | | | | | | | 0.08 | | | |
| v/c Ratio | 0.62 | 0.67 | | | 0.72 | | 0.62 | 0.80 | 0.50 | 0.65 | 0.77 | |
| Uniform Delay, d1 | 52.1 | 16.0 | | | 23.6 | | 49.9 | 46.6 | 44.3 | 48.5 | 45.0 | |
| Progression Factor | 1.00 | 1.00 | | | 0.46 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | |
| Incremental Delay, d2 | 6.6 | 1.8 | | | 2.4 | | 6.5 | 13.0 | 0.6 | 7.1 | 5.5 | |
| Delay (s) | 58.7 | 17.8 | | | 13.3 | | 56.5 | 59.6 | 44.9 | 55.6 | 50.5 | |
| Level of Service | E | B | | | B | | E | E | D | E | D | |
| Approach Delay (s) | | 19.9 | | | 13.3 | | | 53.1 | | | 51.6 | |
| Approach LOS | | B | | | B | | | D | | | D | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | 28.1 | | | | | HCM Level of Service | | | C | | |
| HCM Volume to Capacity ratio | | 0.78 | | | | | | | | | | |
| Actuated Cycle Length (s) | | 115.0 | | | | | Sum of lost time (s) | | | 22.0 | | |
| Intersection Capacity Utilization | | 79.8% | | | | | ICU Level of Service | | | D | | |
| Analysis Period (min) | | 15 | | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

Intersection: 12: Tualatin Sherwood Rd & I-5 SB Ramps

| Movement | EB | EB | EB | EB | WB | WB | WB | SB | SB | SB | SB |
|-----------------------|-----|-----|-----|-----|-----|-----|-----|-----|------|------|-----|
| Directions Served | T | T | T | R | L | T | T | L | LT | R | R |
| Maximum Queue (ft) | 187 | 219 | 211 | 107 | 391 | 526 | 506 | 275 | 592 | 473 | 336 |
| Average Queue (ft) | 137 | 147 | 148 | 8 | 191 | 283 | 312 | 185 | 295 | 210 | 120 |
| 95th Queue (ft) | 209 | 216 | 215 | 47 | 324 | 418 | 437 | 285 | 540 | 396 | 270 |
| Link Distance (ft) | 169 | 169 | 169 | 169 | 625 | 625 | 625 | | 1146 | 1146 | |
| Upstream Blk Time (%) | 5 | 6 | 6 | 0 | | | | | | | |
| Queuing Penalty (veh) | 22 | 25 | 26 | 0 | | | | | | | |
| Storage Bay Dist (ft) | | | | | | | | 200 | | | 700 |
| Storage Blk Time (%) | | | | | | | | 4 | 19 | 0 | 0 |
| Queuing Penalty (veh) | | | | | | | | 12 | 60 | 1 | 0 |

Queuing and Blocking Report
 Saturday Mid-Day Peak


4/17/2013

Intersection: 13: Tualatin Sherwood Rd & I-5 NB Ramps

| Movement | EB | EB | EB | EB | WB | WB | WB | NB | NB | NB | B33 |
|-----------------------|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|-----|
| Directions Served | T | T | R | R | T | T | R | L | LT | R | T |
| Maximum Queue (ft) | 474 | 446 | 57 | 55 | 269 | 381 | 223 | 323 | 444 | 296 | 61 |
| Average Queue (ft) | 289 | 252 | 2 | 2 | 104 | 138 | 19 | 174 | 232 | 101 | 4 |
| 95th Queue (ft) | 442 | 397 | 44 | 43 | 209 | 265 | 120 | 275 | 372 | 229 | 51 |
| Link Distance (ft) | 625 | 625 | 625 | 625 | 459 | 459 | | | 467 | | 253 |
| Upstream Blk Time (%) | | | | | | 0 | | | 0 | | 0 |
| Queuing Penalty (veh) | | | | | | 1 | | | 0 | | 0 |
| Storage Bay Dist (ft) | | | | | | | 150 | 300 | | 225 | |
| Storage Blk Time (%) | | | | | | 5 | | 0 | 8 | 0 | |
| Queuing Penalty (veh) | | | | | | 33 | | 1 | 41 | 1 | |

Appendix F
Year 2014 Total Traffic
Operations Worksheets

2010 Network: Select Zone Vehicles (Total PM Peak 1-Hour Vehicles)



| | | |
|-------------------------------------|---|-------------------------------------|
| Washington County Steve L Kelley | Westside Focus Model 2010_PM2veh_SZ_Tualatin.ver | 2010 Existing Network 15.06.2012 |
|-------------------------------------|---|-------------------------------------|

HCM Signalized Intersection Capacity Analysis
 1: Lower Boones Ferry Road & SW Upper Boones Ferry Road

4/15/2013



| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR | |
|-----------------------------------|-------|-------|-------|-------|------|------|------|------|-------|------|-------|----------------------|------|
| Lane Configurations | | ↔ | | ↔ | ↔ | | ↔ | ↑ | ↔ | ↔ | ↔ | | |
| Volume (vph) | 1 | 7 | 9 | 479 | 7 | 40 | 0 | 504 | 567 | 59 | 697 | 1 | |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | |
| Total Lost time (s) | | 3.5 | | 3.5 | 3.5 | | | 4.0 | 3.5 | 3.5 | 4.0 | | |
| Lane Util. Factor | | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | | |
| Frbp, ped/bikes | | 0.92 | | 1.00 | 0.95 | | | 1.00 | 0.98 | 1.00 | 1.00 | | |
| Flpb, ped/bikes | | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | | |
| Frt | | 0.93 | | 1.00 | 0.87 | | | 1.00 | 0.85 | 1.00 | 1.00 | | |
| Flt Protected | | 1.00 | | 0.95 | 1.00 | | | 1.00 | 1.00 | 0.95 | 1.00 | | |
| Satd. Flow (prot) | | 1596 | | 1787 | 1574 | | | 1900 | 1570 | 1805 | 1900 | | |
| Flt Permitted | | 1.00 | | 0.95 | 1.00 | | | 1.00 | 1.00 | 0.95 | 1.00 | | |
| Satd. Flow (perm) | | 1596 | | 1787 | 1574 | | | 1900 | 1570 | 1805 | 1900 | | |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | |
| Adj. Flow (vph) | 1 | 7 | 9 | 504 | 7 | 42 | 0 | 531 | 597 | 62 | 734 | 1 | |
| RTOR Reduction (vph) | 0 | 9 | 0 | 0 | 26 | 0 | 0 | 0 | 158 | 0 | 0 | 0 | |
| Lane Group Flow (vph) | 0 | 8 | 0 | 504 | 23 | 0 | 0 | 531 | 439 | 62 | 735 | 0 | |
| Confl. Peds. (#/hr) | 15 | | 7 | 7 | | 15 | 7 | | 8 | 8 | | 7 | |
| Heavy Vehicles (%) | 0% | 2% | 1% | 1% | 3% | 0% | 2% | 0% | 1% | 0% | 0% | 0% | |
| Turn Type | Split | | | Split | | | Prot | | pm+ov | | Prot | | |
| Protected Phases | 8 | 8 | | 4 | 4 | | 1 | 6 | 4 | 5 | 2 | | |
| Permitted Phases | | | | | | | | | 6 | | | | |
| Actuated Green, G (s) | | 1.7 | | 31.9 | 31.9 | | | 29.5 | 61.4 | 5.3 | 38.8 | | |
| Effective Green, g (s) | | 2.2 | | 32.4 | 32.4 | | | 30.0 | 62.4 | 5.8 | 39.3 | | |
| Actuated g/C Ratio | | 0.03 | | 0.38 | 0.38 | | | 0.35 | 0.73 | 0.07 | 0.46 | | |
| Clearance Time (s) | | 4.0 | | 4.0 | 4.0 | | | 4.5 | 4.0 | 4.0 | 4.5 | | |
| Vehicle Extension (s) | | 2.5 | | 2.2 | 2.2 | | | 3.5 | 2.2 | 2.2 | 3.5 | | |
| Lane Grp Cap (vph) | | 41 | | 682 | 601 | | | 671 | 1154 | 123 | 880 | | |
| v/s Ratio Prot | | c0.01 | | c0.28 | 0.01 | | | 0.28 | 0.15 | 0.03 | c0.39 | | |
| v/s Ratio Perm | | | | | | | | | 0.13 | | | | |
| v/c Ratio | | 0.20 | | 0.74 | 0.04 | | | 0.79 | 0.38 | 0.50 | 0.84 | | |
| Uniform Delay, d1 | | 40.5 | | 22.6 | 16.5 | | | 24.6 | 4.1 | 38.2 | 20.0 | | |
| Progression Factor | | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | | |
| Incremental Delay, d2 | | 1.8 | | 3.8 | 0.0 | | | 6.5 | 0.1 | 1.7 | 7.1 | | |
| Delay (s) | | 42.2 | | 26.4 | 16.5 | | | 31.2 | 4.2 | 39.8 | 27.0 | | |
| Level of Service | | D | | C | B | | | C | A | D | C | | |
| Approach Delay (s) | | 42.2 | | | 25.5 | | | 16.9 | | | 28.0 | | |
| Approach LOS | | D | | | C | | | B | | | C | | |
| Intersection Summary | | | | | | | | | | | | | |
| HCM Average Control Delay | | | 22.5 | | | | | | | | | HCM Level of Service | C |
| HCM Volume to Capacity ratio | | | 0.77 | | | | | | | | | | |
| Actuated Cycle Length (s) | | | 84.9 | | | | | | | | | Sum of lost time (s) | 11.0 |
| Intersection Capacity Utilization | | | 83.3% | | | | | | | | | ICU Level of Service | E |
| Analysis Period (min) | | | 15 | | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 2: SW Boones Ferry Rd & SW Tualatin Rd

4/15/2013



| Movement | WBL | WBR | NBT | NBR | SBL | SBT |
|-----------------------------------|------|-------|-------|-------|----------------------|------|
| Lane Configurations | ↙↘ | ↗ | ↑ | ↗ | ↙ | ↑ |
| Volume (vph) | 410 | 844 | 200 | 298 | 453 | 365 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 3.5 | 3.5 | 3.0 | 3.5 | 3.5 | 3.5 |
| Lane Util. Factor | 0.97 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Frbp, ped/bikes | 1.00 | 0.98 | 1.00 | 0.98 | 1.00 | 1.00 |
| Flpb, ped/bikes | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Frt | 1.00 | 0.85 | 1.00 | 0.85 | 1.00 | 1.00 |
| Flt Protected | 0.95 | 1.00 | 1.00 | 1.00 | 0.95 | 1.00 |
| Satd. Flow (prot) | 3467 | 1590 | 1900 | 1574 | 1805 | 1900 |
| Flt Permitted | 0.95 | 1.00 | 1.00 | 1.00 | 0.95 | 1.00 |
| Satd. Flow (perm) | 3467 | 1590 | 1900 | 1574 | 1805 | 1900 |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 432 | 888 | 211 | 314 | 477 | 384 |
| RTOR Reduction (vph) | 0 | 182 | 0 | 75 | 0 | 0 |
| Lane Group Flow (vph) | 432 | 706 | 211 | 239 | 477 | 384 |
| Confl. Peds. (#/hr) | 7 | 15 | | 8 | 8 | |
| Heavy Vehicles (%) | 1% | 0% | 0% | 1% | 0% | 0% |
| Turn Type | | pm+ov | | pm+ov | Prot | |
| Protected Phases | 8 | 1 | 2 | 8 | 1 | 6 |
| Permitted Phases | | 8 | | 2 | | |
| Actuated Green, G (s) | 11.4 | 32.2 | 10.7 | 22.1 | 20.8 | 35.0 |
| Effective Green, g (s) | 11.9 | 33.2 | 11.2 | 23.1 | 21.3 | 35.5 |
| Actuated g/C Ratio | 0.22 | 0.61 | 0.21 | 0.42 | 0.39 | 0.65 |
| Clearance Time (s) | 4.0 | 4.0 | 3.5 | 4.0 | 4.0 | 4.0 |
| Vehicle Extension (s) | 3.0 | 2.0 | 5.0 | 3.0 | 2.0 | 2.0 |
| Lane Grp Cap (vph) | 758 | 1073 | 391 | 668 | 707 | 1240 |
| v/s Ratio Prot | 0.12 | c0.26 | c0.11 | 0.08 | 0.26 | 0.20 |
| v/s Ratio Perm | | 0.19 | | 0.07 | | |
| v/c Ratio | 0.57 | 0.66 | 0.54 | 0.36 | 0.67 | 0.31 |
| Uniform Delay, d1 | 19.0 | 6.9 | 19.3 | 10.6 | 13.7 | 4.1 |
| Progression Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Incremental Delay, d2 | 1.0 | 1.1 | 2.6 | 0.3 | 2.0 | 0.1 |
| Delay (s) | 20.0 | 8.0 | 21.9 | 10.9 | 15.7 | 4.2 |
| Level of Service | B | A | C | B | B | A |
| Approach Delay (s) | 11.9 | | 15.4 | | | 10.6 |
| Approach LOS | B | | B | | | B |
| Intersection Summary | | | | | | |
| HCM Average Control Delay | | | 12.2 | | HCM Level of Service | B |
| HCM Volume to Capacity ratio | | | 0.63 | | | |
| Actuated Cycle Length (s) | | | 54.4 | | Sum of lost time (s) | 6.5 |
| Intersection Capacity Utilization | | | 72.2% | | ICU Level of Service | C |
| Analysis Period (min) | | | 15 | | | |
| c Critical Lane Group | | | | | | |

HCM Signalized Intersection Capacity Analysis
 3: SW Boones Fe & SW Martinazzi Ave

28/03/2013



| Mo | EBT | EBR | WBL | WBT | NBL | NBR |
|---------------|------|------|-------|------|------|------|
| Lo | ↑ | ↑ | ↑ | ↑ | ↑ | ↑ |
| V | 664 | 18 | 43 | 930 | 33 | 41 |
| Id F | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| T L | 4. | 4. | 4. | 4. | 4. | 4. |
| L U .F r | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Fr , d/ | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 0.98 |
| F , d/ | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Fr | 1.00 | 0.8 | 1.00 | 1.00 | 1.00 | 0.8 |
| FPr d | 1.00 | 1.00 | 0.9 | 1.00 | 0.9 | 1.00 |
| Sd.F r | 1863 | 199 | 18 | 184 | 10 | 11 |
| FPr d | 1.00 | 1.00 | 0.9 | 1.00 | 0.9 | 1.00 |
| Sd.F r | 1863 | 199 | 18 | 184 | 10 | 11 |
| P r r,PHF | 0.9 | 0.9 | 0.9 | 0.9 | 0.9 | 0.9 |
| Ad.F | 699 | 19 | 4 | 99 | 33 | 43 |
| RTOR R d | 0 | 6 | 0 | 0 | 0 | 33 |
| L Gr F | 699 | 130 | 4 | 99 | 33 | 404 |
| C .P d. / r | | | | | | 8 |
| H V | 2 | 1 | 1 | 3 | 2 | 1 |
| Tr T | | Pr | Pr | | | |
| Pr dP | 2 | 2 | 1 | 6 | 8 | 1 |
| P r dP | | | | | 8 | 8 |
| A dGr ,G | 41.2 | 41.2 | 31.8 | 8.0 | 24.1 | .9 |
| E Gr , | 41. | 41. | 32.3 | 8. | 24.6 | 6.9 |
| A d /CR | 0.3 | 0.3 | 0.29 | 0.0 | 0.22 | 0.1 |
| C r T | .0 | .0 | .0 | .0 | .0 | .0 |
| V E | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 |
| L Gr C | 693 | 9 | 1 | 1292 | 388 | 860 |
| / R Pr | 0.38 | 0.08 | 0.2 | 0.3 | 0.20 | 0.14 |
| / R Pr | | | | | | 0.12 |
| / R | 1.01 | 0.22 | 0.93 | 0.6 | 0.91 | 0.4 |
| Ur D ,d1 | 3.2 | 24.1 | 38. | 10. | 42. | 1.8 |
| Pr r F r | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| l r D ,d2 | 36.3 | 0.2 | 22. | 2.6 | 24. | 0.4 |
| D | 1. | 24.2 | 61. | 13.3 | 6.2 | 18.2 |
| L Sr | E | C | E | B | E | B |
| A r D | 61.2 | | | 29.1 | 40.1 | |
| A r LOS | E | | | C | D | |
| I r S r | | | | | | |
| HCM A r C r D | | | 41.0 | HCML | S r | D |
| HCM V C r | | | 0.96 | | | |
| A dC L | | | 112.1 | S | | 13. |
| I r C U | | | 89.9 | ICUL | S r | E |
| A Pr d | | | 1 | | | |
| Cr L Gr | | | | | | |

HCM Unsignalized Intersection Capacity Analysis
 4: SW Martinazzi Ave &

28/03/2013



| M | WBL | WBR | NBT | NBR | SBL | SBT |
|-----------|------|------|------|------|------|------|
| L C r | ↙ | ↗ | ↘ | | ↙ | ↗ |
| V / | 3 | 166 | 82 | 93 | 202 | 434 |
| S C r | S | | Fr | | | Fr |
| Grd | 0 | | 0 | | | 0 |
| P H r F r | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 |
| H r r | 8 | 180 | 633 | 101 | 220 | 42 |
| P d r | | | | | | |
| L W d | | | | | | |
| W S d / | | | | | | |
| Pr B | | | | | | |
| R r r | | | | | | |
| M d | | | N | | | TWLT |
| M d r | | | | | | 2 |
| U r | | | 4 | | | 306 |
| , d | 0.91 | 0.91 | | | 0.91 | |
| C, | 194 | 683 | | | 34 | |
| C1, 1 | 683 | | | | | |
| C2, 2 | 911 | | | | | |
| C, d | 1603 | 604 | | | 660 | |
| C, | 6.4 | 6.2 | | | 4.1 | |
| C, 2 | .4 | | | | | |
| F | 3. | 3.3 | | | 2.2 | |
| o r | | 60 | | | 4 | |
| M / | 23 | 44 | | | 84 | |
| Dr ,L | WB 1 | WB 2 | NB 1 | SB 1 | SB 2 | |
| V T | 8 | 180 | 34 | 220 | 42 | |
| V L | 8 | 0 | 0 | 220 | 0 | |
| V R | 0 | 180 | 101 | 0 | 0 | |
| SH | 23 | 44 | 100 | 84 | 100 | |
| V C | 0.23 | 0.40 | 0.43 | 0.26 | 0.28 | |
| L 9 | 21 | 4 | 0 | 26 | 0 | |
| C r D | 23.3 | 18.0 | 0.0 | 10. | 0.0 | |
| L LOS | C | C | | B | | |
| A r D | 19.3 | | 0.0 | 3.4 | | |
| A r LOS | C | | | | | |
| I r S r | | | | | | |
| A r D | | | 4.2 | | | |
| I r C U | | | 60.8 | ICUL | S r | B |
| A Prd | | | 1 | | | |

HCM Unsignalized Intersection Capacity Analysis
 5: Seneca St & Martinazzi Ave

28/03/2013



| M | EBL | EBR | NBL | NBT | SBT | SBR |
|-----------|------|------|------|------|------|------|
| L C r | 40 | 80 | 8 | 642 | 446 | 0 |
| V / | | | | | | |
| S C r | S | | | Fr | Fr | |
| Grd | 0 | | | 0 | 0 | |
| P H r F r | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 |
| H r r | 44 | 88 | 93 | 0 | 490 | |
| P d r | | | | 16 | 26 | |
| L Wd | 12.0 | | | 12.0 | 12.0 | |
| W S d / | 4.0 | | | 4.0 | 4.0 | |
| Pr B | 0 | | | 1 | 2 | |
| R r r | | | | | | |
| Md | | | | N | N | |
| Md r | | | | | | |
| Ur | | | | 316 | 46 | |
| d | 0.89 | | | | | |
| C, | 1441 | 39 | 0 | | | |
| C1, 1 | | | | | | |
| C2, 2 | | | | | | |
| C, d | 1434 | 39 | 0 | | | |
| C, | 6.4 | 6.2 | 4.1 | | | |
| C, 2 | | | | | | |
| F | 3. | 3.3 | 2.2 | | | |
| 0 r | 63 | 84 | 91 | | | |
| M / | 118 | 3 | 1026 | | | |
| Dr, L | EB 1 | NB 1 | NB 2 | SB 1 | | |
| V T | 132 | 93 | 0 | 4 | | |
| V L | 44 | 93 | 0 | 0 | | |
| V R | 88 | 0 | 0 | | | |
| SH | 24 | 1026 | 100 | 100 | | |
| V C | 0.4 | 0.09 | 0.41 | 0.32 | | |
| L 9 | 2 | | 0 | 0 | | |
| C r D | 3. | 8.9 | 0.0 | 0.0 | | |
| L LOS | E | A | | | | |
| A r D | 3. | 1.0 | | 0.0 | | |
| A r LOS | E | | | | | |
| I r S r | | | | | | |
| A r D | | | 3. | | | |
| I r C U | | | 1.6 | ICUL | S r | A |
| A Prd | | | 1 | | | |

HCM Unsignalized Intersection Capacity Analysis
 6: Martinazzi Ave &

28/03/2013



| M | WBL | WBR | NBT | NBR | SBL | SBT |
|-----------|------|------|------|------|------|------|
| L C r | | ↑ | ↑ | | | ↑↑ |
| V / | 0 | 32 | 69 | 6 | 10 | 1 |
| S C r | S | | Fr | | | Fr |
| Grd | 0 | | 0 | | | 0 |
| P H r F r | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 |
| H r r | 0 | 3 | 64 | | 11 | 68 |
| P d r | 26 | | | | | 2 |
| L Wd | 12.0 | | | | | 12.0 |
| W S d / | 4.0 | | | | | 4.0 |
| Pr B | 2 | | | | | 2 |
| R r r | | | | | | |
| Md | | | N | | | N |
| Md r | | | | | | |
| U r | | | 223 | | | 60 |
| d | 0.8 | 0.8 | | | 0.8 | |
| C, | 1099 | 818 | | | 96 | |
| C1, 1 | | | | | | |
| C2, 2 | | | | | | |
| C, d | 1029 | 699 | | | 64 | |
| C, | 6.8 | 6.9 | | | 4.1 | |
| C, 2 | | | | | | |
| F | 3. | 3.3 | | | 2.2 | |
| O r | 100 | 89 | | | 99 | |
| M / | 188 | 312 | | | 61 | |
| Dr ,L | WB 1 | NB 1 | SB 1 | SB 2 | | |
| V T | 3 | 0 | 200 | 39 | | |
| V L | 0 | 0 | 11 | 0 | | |
| V R | 3 | | 0 | 0 | | |
| SH | 312 | 100 | 61 | 100 | | |
| V C | 0.11 | 0.4 | 0.01 | 0.22 | | |
| L 9 | 9 | 0 | 1 | 0 | | |
| C r D | 18.0 | 0.0 | 0. | 0.0 | | |
| L LOS | C | | A | | | |
| A r D | 18.0 | 0.0 | 0.2 | | | |
| A r LOS | C | | | | | |
| I r S r | | | | | | |
| A r D | | | 0.6 | | | |
| I r C U | | | 3.0 | ICUL | S r | A |
| A Prd | | | 1 | | | |

HCM Unsignalized Intersection Capacity Analysis
 7: Martinazzi Ave &

28/03/2013



| M | WBL | WBR | NBT | NBR | SBL | SBT |
|-----------|------|------|------|------|------|------|
| L C r | | | | | | |
| V / | 0 | 12 | 682 | 0 | 0 | 09 |
| S C r | S | | Fr | | | Fr |
| Grd | 0 | | 0 | | | 0 |
| P H r F r | 0.89 | 0.89 | 0.89 | 0.89 | 0.89 | 0.89 |
| H r r | 0 | 13 | 66 | 0 | 0 | 2 |
| P d r | | | | | | |
| L W d | | | | | | |
| W S d / | | | | | | |
| Pr B | | | | | | |
| R r r | | | | | | |
| M d | | | N | | | N |
| M d r | | | | | | |
| U r | | | 101 | | | 682 |
| d | 0.84 | 0.84 | | | 0.84 | |
| C, | 10.2 | 66 | | | 66 | |
| C1, 1 | | | | | | |
| C2, 2 | | | | | | |
| C, d | 9.0 | 632 | | | 632 | |
| C, | 6.8 | 6.9 | | | 4.1 | |
| C, 2 | | | | | | |
| F | 3. | 3.3 | | | 2.2 | |
| O r | 100 | 96 | | | 100 | |
| M / | 212 | 38 | | | 800 | |
| Dr , L | WB 1 | NB 1 | SB 1 | SB 2 | | |
| V T | 13 | 66 | 286 | 286 | | |
| V L | 0 | 0 | 0 | 0 | | |
| V R | 13 | 0 | 0 | 0 | | |
| SH | 38 | 100 | 100 | 100 | | |
| V C | 0.04 | 0.4 | 0.1 | 0.1 | | |
| L 9 | 3 | 0 | 0 | 0 | | |
| C r D | 1. | 0.0 | 0.0 | 0.0 | | |
| L LOS | C | | | | | |
| A r D | 1. | 0.0 | 0.0 | | | |
| A r LOS | C | | | | | |
| I r S r | | | | | | |
| A r D | | | 0.2 | | | |
| I r C U | | | 4.9 | ICUL | S r | A |
| A Prd | | | 1 | | | |

HCM Signalized Intersection Capacity Analysis
 8: Nyberg St & Martinazzi Ave

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR | |
|-----------------------------------|-------|------|-------|-------|-------|------|------|-------|------|------|------|----------------------|---|
| Lane Configurations | | | | | | | | | | | | | |
| Volume (vph) | 29 | 10 | 100 | 357 | 55 | 337 | 27 | 315 | 26 | 0 | 499 | 10 | |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | |
| Total Lost time (s) | 4.0 | 4.0 | | 4.0 | 4.0 | 4.0 | 4.0 | 4.0 | | | 4.0 | | |
| Lane Util. Factor | 1.00 | 1.00 | | 0.95 | 0.95 | 1.00 | 1.00 | 1.00 | | | 0.95 | | |
| Frpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 0.97 | 1.00 | 1.00 | | | 1.00 | | |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | 1.00 | | |
| Frt | 1.00 | 0.86 | | 1.00 | 1.00 | 0.85 | 1.00 | 0.99 | | | 1.00 | | |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 0.96 | 1.00 | 0.95 | 1.00 | | | 1.00 | | |
| Satd. Flow (prot) | 1805 | 1626 | | 1698 | 1728 | 1533 | 1682 | 1855 | | | 3563 | | |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 0.96 | 1.00 | 0.40 | 1.00 | | | 1.00 | | |
| Satd. Flow (perm) | 1805 | 1626 | | 1698 | 1728 | 1533 | 701 | 1855 | | | 3563 | | |
| Peak-hour factor, PHF | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | |
| Adj. Flow (vph) | 32 | 11 | 110 | 392 | 60 | 370 | 30 | 346 | 29 | 0 | 548 | 11 | |
| RTOR Reduction (vph) | 0 | 96 | 0 | 0 | 0 | 276 | 0 | 4 | 0 | 0 | 2 | 0 | |
| Lane Group Flow (vph) | 32 | 25 | 0 | 223 | 229 | 94 | 30 | 371 | 0 | 0 | 557 | 0 | |
| Confl. Peds. (#/hr) | 10 | | | | | 10 | 6 | | 19 | 19 | | 6 | |
| Heavy Vehicles (%) | 0% | 0% | 1% | 1% | 0% | 2% | 7% | 1% | 0% | 0% | 1% | 0% | |
| Turn Type | Split | | | Split | | | Perm | Perm | | | | | |
| Protected Phases | 8 | 8 | | 4 | 4 | | | | 6 | | | 2 | |
| Permitted Phases | | | | | | 4 | 6 | | | | | | |
| Actuated Green, G (s) | 4.8 | 4.8 | | 10.3 | 10.3 | 10.3 | 13.7 | 13.7 | | | | 13.7 | |
| Effective Green, g (s) | 5.3 | 5.3 | | 10.8 | 10.8 | 10.8 | 14.2 | 14.2 | | | | 14.2 | |
| Actuated g/C Ratio | 0.13 | 0.13 | | 0.26 | 0.26 | 0.26 | 0.34 | 0.34 | | | | 0.34 | |
| Clearance Time (s) | 4.5 | 4.5 | | 4.5 | 4.5 | 4.5 | 4.5 | 4.5 | | | | 4.5 | |
| Vehicle Extension (s) | 2.5 | 2.5 | | 2.5 | 2.5 | 2.5 | 5.0 | 5.0 | | | | 5.0 | |
| Lane Grp Cap (vph) | 226 | 204 | | 434 | 441 | 391 | 235 | 623 | | | | 1196 | |
| v/s Ratio Prot | c0.02 | 0.02 | | 0.13 | c0.13 | | | c0.20 | | | | 0.16 | |
| v/s Ratio Perm | | | | | | 0.06 | 0.04 | | | | | | |
| v/c Ratio | 0.14 | 0.12 | | 0.51 | 0.52 | 0.24 | 0.13 | 0.60 | | | | 0.47 | |
| Uniform Delay, d1 | 16.5 | 16.4 | | 13.5 | 13.5 | 12.5 | 9.8 | 11.7 | | | | 11.1 | |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | | 1.00 | |
| Incremental Delay, d2 | 0.2 | 0.2 | | 0.8 | 0.8 | 0.2 | 0.5 | 2.3 | | | | 0.6 | |
| Delay (s) | 16.7 | 16.6 | | 14.3 | 14.3 | 12.7 | 10.3 | 14.0 | | | | 11.7 | |
| Level of Service | B | B | | B | B | B | B | B | | | | B | |
| Approach Delay (s) | | 16.6 | | | 13.6 | | | 13.7 | | | | 11.7 | |
| Approach LOS | | B | | | B | | | B | | | | B | |
| Intersection Summary | | | | | | | | | | | | | |
| HCM Average Control Delay | | | 13.3 | | | | | | | | | HCM Level of Service | B |
| HCM Volume to Capacity ratio | | | 0.49 | | | | | | | | | | |
| Actuated Cycle Length (s) | | | 42.3 | | | | | | | | 12.0 | Sum of lost time (s) | |
| Intersection Capacity Utilization | | | 56.9% | | | | | | | | | ICU Level of Service | B |
| Analysis Period (min) | | | 15 | | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | | |

HCM Unsignalized Intersection Capacity Analysis
 9: Nyberg St & Site Entrance 3

4/15/2013



| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
|------------------------|------|------|------|------|------|------|
| Lane Configurations | ↖ | | ↗ | | | ↘ |
| Volume (veh/h) | 35 | 0 | 648 | 51 | 0 | 100 |
| Sign Control | | Free | Free | | Stop | |
| Grade | | 0% | 0% | | 0% | |
| Peak Hour Factor | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 |
| Hourly flow rate (vph) | 40 | 0 | 736 | 58 | 0 | 114 |
| Pedestrians | | | | | 5 | |
| Lane Width (ft) | | | | | 12.0 | |
| Walking Speed (ft/s) | | | | | 4.0 | |
| Percent Blockage | | | | | 0 | |
| Right turn flare (veh) | | | | | | |
| Median type | | None | None | | | |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | 278 | | | | |
| pX, platoon unblocked | | | | | | |
| vC, conflicting volume | 799 | | | | 850 | 402 |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 799 | | | | 850 | 402 |
| tC, single (s) | 4.1 | | | | 6.8 | 6.9 |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 2.2 | | | | 3.5 | 3.3 |
| p0 queue free % | 95 | | | | 100 | 81 |
| cM capacity (veh/h) | 829 | | | | 288 | 601 |

| Direction, Lane # | EB 1 | WB 1 | WB 2 | SB 1 |
|------------------------|------|------|------|------|
| Volume Total | 40 | 491 | 303 | 114 |
| Volume Left | 40 | 0 | 0 | 0 |
| Volume Right | 0 | 0 | 58 | 114 |
| cSH | 829 | 1700 | 1700 | 601 |
| Volume to Capacity | 0.05 | 0.29 | 0.18 | 0.19 |
| Queue Length 95th (ft) | 4 | 0 | 0 | 17 |
| Control Delay (s) | 9.6 | 0.0 | 0.0 | 12.4 |
| Lane LOS | A | | | B |
| Approach Delay (s) | 9.6 | 0.0 | | 12.4 |
| Approach LOS | | | | B |

| Intersection Summary | | | |
|-----------------------------------|--|-------|------------------------|
| Average Delay | | 1.9 | |
| Intersection Capacity Utilization | | 32.4% | ICU Level of Service A |
| Analysis Period (min) | | 15 | |

HCM Signalized Intersection Capacity Analysis
 10: Tualatin Sherwood Rd & Site Entrance 4

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR | | |
|-----------------------------------|------|-------|------|------|------|------|-------|------|-------|-------|------|----------------------|----------------------|---|
| Lane Configurations | | | | | | | | | | | | | | |
| Volume (vph) | 99 | 1899 | 40 | 232 | 1694 | 251 | 36 | 10 | 236 | 323 | 24 | 113 | | |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | | |
| Total Lost time (s) | 4.5 | 6.0 | | 4.5 | 6.0 | 6.0 | | 5.0 | 4.5 | 5.0 | 5.0 | | | |
| Lane Util. Factor | 1.00 | *0.75 | | 0.97 | 0.91 | 1.00 | | 1.00 | 1.00 | 0.97 | 1.00 | | | |
| Frpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 0.96 | | 1.00 | 1.00 | 1.00 | 0.97 | | | |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Frt | 1.00 | 1.00 | | 1.00 | 1.00 | 0.85 | | 1.00 | 0.85 | 1.00 | 0.88 | | | |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | 1.00 | | 0.96 | 1.00 | 0.95 | 1.00 | | | |
| Satd. Flow (prot) | 1805 | 4100 | | 3502 | 4988 | 1545 | | 1786 | 1599 | 3502 | 1622 | | | |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | 1.00 | | 0.96 | 1.00 | 0.95 | 1.00 | | | |
| Satd. Flow (perm) | 1805 | 4100 | | 3502 | 4988 | 1545 | | 1786 | 1599 | 3502 | 1622 | | | |
| Peak-hour factor, PHF | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | | |
| Adj. Flow (vph) | 101 | 1938 | 41 | 237 | 1729 | 256 | 37 | 10 | 241 | 330 | 24 | 115 | | |
| RTOR Reduction (vph) | 0 | 1 | 0 | 0 | 0 | 126 | 0 | 0 | 0 | 0 | 99 | 0 | | |
| Lane Group Flow (vph) | 101 | 1978 | 0 | 237 | 1729 | 130 | 0 | 47 | 241 | 330 | 40 | 0 | | |
| Confl. Peds. (#/hr) | | | 2 | | | 8 | | | | | | 15 | | |
| Heavy Vehicles (%) | 0% | 4% | 0% | 0% | 4% | 0% | 3% | 0% | 1% | 0% | 0% | 0% | | |
| Turn Type | Prot | | | Prot | | Perm | Split | | pt+ov | Split | | | | |
| Protected Phases | 5 | 2 | | 1 | 6 | | 8 | 8 | 18 | 4 | 4 | | | |
| Permitted Phases | | | | | | 6 | | | | | | | | |
| Actuated Green, G (s) | 14.1 | 61.1 | | 16.1 | 63.1 | 63.1 | | 8.6 | 24.7 | 16.7 | 16.7 | | | |
| Effective Green, g (s) | 14.6 | 61.6 | | 16.6 | 63.6 | 63.6 | | 9.1 | 25.7 | 17.2 | 17.2 | | | |
| Actuated g/C Ratio | 0.12 | 0.49 | | 0.13 | 0.51 | 0.51 | | 0.07 | 0.21 | 0.14 | 0.14 | | | |
| Clearance Time (s) | 5.0 | 6.5 | | 5.0 | 6.5 | 6.5 | | 5.5 | | 5.5 | 5.5 | | | |
| Vehicle Extension (s) | 2.5 | 4.0 | | 2.5 | 4.0 | 4.0 | | 2.5 | | 2.5 | 2.5 | | | |
| Lane Grp Cap (vph) | 211 | 2020 | | 465 | 2538 | 786 | | 130 | 329 | 482 | 223 | | | |
| v/s Ratio Prot | 0.06 | c0.48 | | 0.07 | 0.35 | | | 0.03 | c0.15 | c0.09 | 0.02 | | | |
| v/s Ratio Perm | | | | | | 0.08 | | | | | | | | |
| v/c Ratio | 0.48 | 0.98 | | 0.51 | 0.68 | 0.17 | | 0.36 | 0.73 | 0.68 | 0.18 | | | |
| Uniform Delay, d1 | 51.6 | 31.1 | | 50.4 | 23.1 | 16.5 | | 55.2 | 46.4 | 51.3 | 47.7 | | | |
| Progression Factor | 0.88 | 0.56 | | 1.04 | 0.86 | 1.12 | | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Incremental Delay, d2 | 0.6 | 9.4 | | 0.4 | 1.0 | 0.3 | | 1.2 | 7.7 | 3.7 | 0.3 | | | |
| Delay (s) | 46.2 | 26.6 | | 53.0 | 20.9 | 18.7 | | 56.4 | 54.2 | 55.0 | 47.9 | | | |
| Level of Service | D | C | | D | C | B | | E | D | D | D | | | |
| Approach Delay (s) | | 27.6 | | | 24.1 | | | 54.5 | | | 52.9 | | | |
| Approach LOS | | C | | | C | | | D | | | D | | | |
| Intersection Summary | | | | | | | | | | | | | | |
| HCM Average Control Delay | | 29.9 | | | | | | | | | | HCM Level of Service | C | |
| HCM Volume to Capacity ratio | | 0.83 | | | | | | | | | | | | |
| Actuated Cycle Length (s) | | 125.0 | | | | | | | 15.5 | | | | Sum of lost time (s) | |
| Intersection Capacity Utilization | | 81.5% | | | | | | | | | | | ICU Level of Service | D |
| Analysis Period (min) | | 15 | | | | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 12: Tualatin Sherwood Rd & I-5 SB Ramps

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|------|-------|-------|------|----------------------|------|------|------|------|-------|------|--------|
| Lane Configurations | | ↑↑↑ | ↑ | ↑ | ↑↑ | | | | | ↑ | ↑ | ↑↑ |
| Volume (vph) | 0 | 1590 | 875 | 123 | 1063 | 0 | 0 | 0 | 0 | 659 | 5 | 1111 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | | 5.5 | 5.5 | 5.5 | 5.5 | | | | | 5.5 | 5.5 | 5.5 |
| Lane Util. Factor | | *0.75 | 1.00 | 1.00 | 0.95 | | | | | 0.95 | 0.95 | 0.88 |
| Frt | | 1.00 | 0.85 | 1.00 | 1.00 | | | | | 1.00 | 1.00 | 0.85 |
| Flt Protected | | 1.00 | 1.00 | 0.95 | 1.00 | | | | | 0.95 | 0.95 | 1.00 |
| Satd. Flow (prot) | | 4150 | 1568 | 1787 | 3471 | | | | | 1681 | 1682 | 2760 |
| Flt Permitted | | 1.00 | 1.00 | 0.95 | 1.00 | | | | | 0.95 | 0.95 | 1.00 |
| Satd. Flow (perm) | | 4150 | 1568 | 1787 | 3471 | | | | | 1681 | 1682 | 2760 |
| Peak-hour factor, PHF | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 |
| Adj. Flow (vph) | 0 | 1606 | 884 | 124 | 1074 | 0 | 0 | 0 | 0 | 666 | 5 | 1122 |
| RTOR Reduction (vph) | 0 | 0 | 476 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 23 |
| Lane Group Flow (vph) | 0 | 1606 | 408 | 124 | 1074 | 0 | 0 | 0 | 0 | 333 | 338 | 1099 |
| Heavy Vehicles (%) | 0% | 3% | 3% | 1% | 4% | 0% | 0% | 0% | 0% | 2% | 20% | 3% |
| Turn Type | | | Perm | Prot | | | | | | Split | | custom |
| Protected Phases | | 2 | | 1 | 6 | | | | | 4 | 4 | 4 |
| Permitted Phases | | | 2 | | | | | | | | | |
| Actuated Green, G (s) | | 56.5 | 56.5 | 11.1 | 51.5 | | | | | 39.4 | 39.4 | 61.5 |
| Effective Green, g (s) | | 57.0 | 57.0 | 11.6 | 52.0 | | | | | 39.9 | 39.9 | 62.0 |
| Actuated g/C Ratio | | 0.46 | 0.46 | 0.09 | 0.42 | | | | | 0.32 | 0.32 | 0.50 |
| Clearance Time (s) | | 6.0 | 6.0 | 6.0 | 6.0 | | | | | 6.0 | 6.0 | |
| Vehicle Extension (s) | | 6.1 | 6.1 | 2.3 | 6.1 | | | | | 2.3 | 2.3 | |
| Lane Grp Cap (vph) | | 1892 | 715 | 166 | 1444 | | | | | 537 | 537 | 1369 |
| v/s Ratio Prot | | c0.39 | | 0.07 | c0.31 | | | | | 0.20 | 0.20 | c0.40 |
| v/s Ratio Perm | | | 0.26 | | | | | | | | | |
| v/c Ratio | | 0.85 | 0.57 | 0.75 | 0.74 | | | | | 0.62 | 0.63 | 0.80 |
| Uniform Delay, d1 | | 30.2 | 25.0 | 55.3 | 30.9 | | | | | 36.1 | 36.3 | 26.4 |
| Progression Factor | | 0.50 | 2.46 | 0.79 | 0.64 | | | | | 1.00 | 1.00 | 1.00 |
| Incremental Delay, d2 | | 2.5 | 1.6 | 14.5 | 3.3 | | | | | 1.8 | 1.9 | 3.4 |
| Delay (s) | | 17.6 | 63.1 | 58.3 | 23.1 | | | | | 37.9 | 38.1 | 29.8 |
| Level of Service | | B | E | E | C | | | | | D | D | C |
| Approach Delay (s) | | 33.7 | | | 26.8 | | | 0.0 | | | 32.8 | |
| Approach LOS | | C | | | C | | | A | | | C | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 31.9 | | HCM Level of Service | | | | | C | | |
| HCM Volume to Capacity ratio | | | 0.82 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 125.0 | | Sum of lost time (s) | | | 11.0 | | | | |
| Intersection Capacity Utilization | | | 93.1% | | ICU Level of Service | | | F | | | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |

c Critical Lane Group

HCM Signalized Intersection Capacity Analysis
 13: Tualatin Sherwood Rd & I-5 NB Ramps

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|------|-------|------|------|----------------------|------|-------|-------|------|------|------|------|
| Lane Configurations | | ↑↑ | ↑↑ | | ↑↑ | ↑ | ↑ | ↑ | ↑ | | | |
| Volume (vph) | 0 | 1216 | 1031 | 0 | 511 | 682 | 675 | 5 | 177 | 0 | 0 | 0 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | | 5.5 | 5.5 | | 6.0 | 6.0 | 5.5 | 5.5 | 5.5 | | | |
| Lane Util. Factor | | 0.95 | 0.88 | | 0.95 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Frpb, ped/bikes | | 1.00 | 1.00 | | 1.00 | 0.95 | 1.00 | 1.00 | 0.96 | | | |
| Flpb, ped/bikes | | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Frt | | 1.00 | 0.85 | | 1.00 | 0.85 | 1.00 | 1.00 | 0.85 | | | |
| Flt Protected | | 1.00 | 1.00 | | 1.00 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Satd. Flow (prot) | | 3574 | 2760 | | 3574 | 1502 | 1618 | 1620 | 1512 | | | |
| Flt Permitted | | 1.00 | 1.00 | | 1.00 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Satd. Flow (perm) | | 3574 | 2760 | | 3574 | 1502 | 1618 | 1620 | 1512 | | | |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 0 | 1280 | 1085 | 0 | 538 | 718 | 711 | 5 | 186 | 0 | 0 | 0 |
| RTOR Reduction (vph) | 0 | 0 | 352 | 0 | 0 | 263 | 0 | 0 | 21 | 0 | 0 | 0 |
| Lane Group Flow (vph) | 0 | 1280 | 733 | 0 | 538 | 455 | 355 | 361 | 165 | 0 | 0 | 0 |
| Confl. Peds. (#/hr) | | | | | | 16 | | | 17 | | | |
| Heavy Vehicles (%) | 0% | 1% | 3% | 0% | 1% | 2% | 6% | 20% | 2% | 0% | 0% | 0% |
| Turn Type | | Perm | | | Perm | | Split | | Perm | | | |
| Protected Phases | | 2 | | | 6 | | 8 | 8 | | | | |
| Permitted Phases | | 2 | | | 6 | | | | 8 | | | |
| Actuated Green, G (s) | | 79.3 | 79.3 | | 78.8 | 78.8 | 33.7 | 33.7 | 33.7 | | | |
| Effective Green, g (s) | | 79.8 | 79.8 | | 79.3 | 79.3 | 34.2 | 34.2 | 34.2 | | | |
| Actuated g/C Ratio | | 0.64 | 0.64 | | 0.63 | 0.63 | 0.27 | 0.27 | 0.27 | | | |
| Clearance Time (s) | | 6.0 | 6.0 | | 6.5 | 6.5 | 6.0 | 6.0 | 6.0 | | | |
| Vehicle Extension (s) | | 6.1 | 6.1 | | 4.2 | 4.2 | 2.3 | 2.3 | 2.3 | | | |
| Lane Grp Cap (vph) | | 2282 | 1762 | | 2267 | 953 | 443 | 443 | 414 | | | |
| v/s Ratio Prot | | c0.36 | | | 0.15 | | 0.22 | c0.22 | | | | |
| v/s Ratio Perm | | 0.27 | | | 0.30 | | | | 0.11 | | | |
| v/c Ratio | | 0.56 | 0.42 | | 0.24 | 0.48 | 0.80 | 0.81 | 0.40 | | | |
| Uniform Delay, d1 | | 12.7 | 11.1 | | 9.8 | 12.0 | 42.2 | 42.4 | 37.0 | | | |
| Progression Factor | | 0.72 | 1.20 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Incremental Delay, d2 | | 0.7 | 0.5 | | 0.2 | 1.7 | 9.6 | 10.6 | 0.4 | | | |
| Delay (s) | | 9.9 | 13.8 | | 10.1 | 13.7 | 51.9 | 53.1 | 37.4 | | | |
| Level of Service | | A | B | | B | B | D | D | D | | | |
| Approach Delay (s) | | 11.7 | | | 12.2 | | | 49.4 | | 0.0 | | |
| Approach LOS | | B | | | B | | | D | | A | | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | 19.3 | | | HCM Level of Service | | | B | | | | |
| HCM Volume to Capacity ratio | | 0.64 | | | | | | | | | | |
| Actuated Cycle Length (s) | | 125.0 | | | Sum of lost time (s) | | | 11.0 | | | | |
| Intersection Capacity Utilization | | 72.2% | | | ICU Level of Service | | | C | | | | |
| Analysis Period (min) | | 15 | | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 14: Tualatin Sherwood Rd & Nyberg Woods

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|-------|-------|-------|----------------------|-------|------|------|-------|------|------|------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 290 | 995 | 61 | 10 | 834 | 80 | 112 | 7 | 17 | 81 | 5 | 191 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 5.5 | 5.5 | | 5.5 | 5.5 | | | 5.5 | 5.5 | | 5.5 | 5.5 |
| Lane Util. Factor | 0.97 | 0.95 | | 1.00 | 0.95 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 0.98 | | 1.00 | 0.99 |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frt | 1.00 | 0.99 | | 1.00 | 0.99 | | | 1.00 | 0.85 | | 1.00 | 0.85 |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.95 | 1.00 | | 0.95 | 1.00 |
| Satd. Flow (prot) | 3502 | 3504 | | 1805 | 3525 | | | 1761 | 1590 | | 1793 | 1592 |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.67 | 1.00 | | 0.65 | 1.00 |
| Satd. Flow (perm) | 3502 | 3504 | | 1805 | 3525 | | | 1243 | 1590 | | 1221 | 1592 |
| Peak-hour factor, PHF | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 |
| Adj. Flow (vph) | 302 | 1036 | 64 | 10 | 869 | 83 | 117 | 7 | 18 | 84 | 5 | 199 |
| RTOR Reduction (vph) | 0 | 3 | 0 | 0 | 7 | 0 | 0 | 0 | 15 | 0 | 0 | 165 |
| Lane Group Flow (vph) | 302 | 1097 | 0 | 10 | 945 | 0 | 0 | 124 | 3 | 0 | 89 | 34 |
| Confl. Peds. (#/hr) | 9 | | 2 | 2 | | 9 | 3 | | 4 | 4 | | 3 |
| Heavy Vehicles (%) | 0% | 2% | 2% | 0% | 1% | 0% | 3% | 0% | 0% | 1% | 0% | 0% |
| Turn Type | Prot | | | Prot | | | Perm | | Perm | Perm | | Perm |
| Protected Phases | 5 | 2 | | 1 | 6 | | | 8 | | | 4 | |
| Permitted Phases | | | | | | | 8 | | 8 | 4 | | 4 |
| Actuated Green, G (s) | 9.0 | 33.1 | | 0.7 | 24.8 | | | 10.2 | 10.2 | | 10.2 | 10.2 |
| Effective Green, g (s) | 9.5 | 33.6 | | 1.2 | 25.3 | | | 10.7 | 10.7 | | 10.7 | 10.7 |
| Actuated g/C Ratio | 0.15 | 0.54 | | 0.02 | 0.41 | | | 0.17 | 0.17 | | 0.17 | 0.17 |
| Clearance Time (s) | 6.0 | 6.0 | | 6.0 | 6.0 | | | 6.0 | 6.0 | | 6.0 | 6.0 |
| Vehicle Extension (s) | 2.3 | 2.5 | | 2.4 | 2.5 | | | 2.4 | 2.4 | | 2.3 | 2.3 |
| Lane Grp Cap (vph) | 537 | 1899 | | 35 | 1438 | | | 215 | 274 | | 211 | 275 |
| v/s Ratio Prot | c0.09 | c0.31 | | 0.01 | c0.27 | | | | | | | |
| v/s Ratio Perm | | | | | | | | c0.10 | 0.00 | | 0.07 | 0.02 |
| v/c Ratio | 0.56 | 0.58 | | 0.29 | 0.66 | | | 0.58 | 0.01 | | 0.42 | 0.12 |
| Uniform Delay, d1 | 24.3 | 9.5 | | 30.0 | 14.8 | | | 23.6 | 21.3 | | 22.9 | 21.7 |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Incremental Delay, d2 | 1.0 | 0.4 | | 2.9 | 1.0 | | | 2.9 | 0.0 | | 0.8 | 0.1 |
| Delay (s) | 25.3 | 9.8 | | 32.9 | 15.8 | | | 26.5 | 21.3 | | 23.7 | 21.8 |
| Level of Service | C | A | | C | B | | | C | C | | C | C |
| Approach Delay (s) | | 13.2 | | | 16.0 | | | 25.8 | | | 22.4 | |
| Approach LOS | | B | | | B | | | C | | | C | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 15.7 | HCM Level of Service | | | | B | | | | |
| HCM Volume to Capacity ratio | | | 0.71 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 62.0 | Sum of lost time (s) | | | | 22.0 | | | | |
| Intersection Capacity Utilization | | | 61.6% | ICU Level of Service | | | | B | | | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 15: SW Nyberg St & SW Nyberg St

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|-------|-------|----------------------|------|------|------|-------|-------|------|------|-------|-------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 221 | 943 | 26 | 24 | 775 | 16 | 17 | 9 | 45 | 5 | 7 | 139 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.8 | 4.8 | | 4.8 | 4.8 | | | 5.6 | 5.6 | | 5.3 | 4.8 |
| Lane Util. Factor | 1.00 | 1.00 | | 1.00 | 0.95 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 0.95 | | 1.00 | 1.00 |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frt | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 0.85 | | 1.00 | 0.85 |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.97 | 1.00 | | 0.98 | 1.00 |
| Satd. Flow (prot) | 1805 | 1854 | | 1805 | 3561 | | | 1803 | 1527 | | 1848 | 1609 |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.97 | 1.00 | | 0.69 | 1.00 |
| Satd. Flow (perm) | 1805 | 1854 | | 1805 | 3561 | | | 1803 | 1527 | | 1304 | 1609 |
| Peak-hour factor, PHF | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 |
| Adj. Flow (vph) | 230 | 982 | 27 | 25 | 807 | 17 | 18 | 9 | 47 | 5 | 7 | 145 |
| RTOR Reduction (vph) | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 44 | 0 | 0 | 116 |
| Lane Group Flow (vph) | 230 | 1009 | 0 | 25 | 823 | 0 | 0 | 27 | 3 | 0 | 12 | 29 |
| Confl. Peds. (#/hr) | 9 | | 2 | 2 | | 9 | 3 | | 4 | 4 | | 3 |
| Heavy Vehicles (%) | 0% | 2% | 2% | 0% | 1% | 0% | 3% | 0% | 0% | 1% | 0% | 0% |
| Turn Type | Prot | | | Prot | | | Split | | Perm | Perm | | pm+ov |
| Protected Phases | 5 | 2 | | 1 | 6 | | 8 | 8 | | | 4 | 5 |
| Permitted Phases | | | | | | | | | 8 | 4 | | 4 |
| Actuated Green, G (s) | 11.5 | 48.8 | | 1.7 | 39.0 | | | 4.1 | 4.1 | | 3.6 | 15.1 |
| Effective Green, g (s) | 12.0 | 49.3 | | 2.2 | 39.5 | | | 4.6 | 4.6 | | 4.1 | 16.1 |
| Actuated g/C Ratio | 0.15 | 0.61 | | 0.03 | 0.49 | | | 0.06 | 0.06 | | 0.05 | 0.20 |
| Clearance Time (s) | 5.3 | 5.3 | | 5.3 | 5.3 | | | 6.1 | 6.1 | | 5.8 | 5.3 |
| Vehicle Extension (s) | 2.5 | 3.0 | | 1.0 | 3.0 | | | 1.0 | 1.0 | | 2.0 | 2.5 |
| Lane Grp Cap (vph) | 268 | 1133 | | 49 | 1743 | | | 103 | 87 | | 66 | 321 |
| v/s Ratio Prot | c0.13 | c0.54 | | 0.01 | 0.23 | | | c0.01 | | | | 0.01 |
| v/s Ratio Perm | | | | | | | | | 0.00 | | c0.01 | 0.00 |
| v/c Ratio | 0.86 | 0.89 | | 0.51 | 0.47 | | | 0.26 | 0.03 | | 0.18 | 0.09 |
| Uniform Delay, d1 | 33.5 | 13.4 | | 38.7 | 13.7 | | | 36.4 | 35.9 | | 36.7 | 26.3 |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Incremental Delay, d2 | 22.5 | 9.0 | | 3.7 | 0.2 | | | 0.5 | 0.1 | | 0.5 | 0.1 |
| Delay (s) | 56.1 | 22.4 | | 42.4 | 13.9 | | | 36.9 | 36.0 | | 37.2 | 26.4 |
| Level of Service | E | C | | D | B | | | D | D | | D | C |
| Approach Delay (s) | | 28.6 | | | 14.7 | | | 36.3 | | | 27.2 | |
| Approach LOS | | C | | | B | | | D | | | C | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | 23.7 | | HCM Level of Service | | | | C | | | | | |
| HCM Volume to Capacity ratio | 0.83 | | | | | | | | | | | |
| Actuated Cycle Length (s) | 80.7 | | Sum of lost time (s) | | | | 20.5 | | | | | |
| Intersection Capacity Utilization | 76.8% | | ICU Level of Service | | | | D | | | | | |
| Analysis Period (min) | 15 | | | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 16: SW Tualatin Sherwood Rd & SW Boones Ferry Rd

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|------|-------|-------|------|-------|------|----------------------|-------|-------|-------|------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 103 | 1035 | 138 | 234 | 1103 | 56 | 171 | 268 | 169 | 297 | 345 | 133 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 5.5 | | 4.5 | 5.5 | | 4.5 | 5.0 | 4.5 | 4.5 | 5.0 | |
| Lane Util. Factor | 1.00 | 0.95 | | 0.97 | 0.95 | | 1.00 | 1.00 | 1.00 | 1.00 | 0.95 | |
| Frpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | 0.98 | 1.00 | 0.99 | |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | |
| Frt | 1.00 | 0.98 | | 1.00 | 0.99 | | 1.00 | 1.00 | 0.85 | 1.00 | 0.96 | |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | 0.95 | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (prot) | 1703 | 3320 | | 3502 | 3339 | | 1732 | 1810 | 1543 | 1761 | 3313 | |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | | 0.41 | 1.00 | 1.00 | 0.59 | 1.00 | |
| Satd. Flow (perm) | 1703 | 3320 | | 3502 | 3339 | | 744 | 1810 | 1543 | 1099 | 3313 | |
| Peak-hour factor, PHF | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 |
| Adj. Flow (vph) | 104 | 1045 | 139 | 236 | 1114 | 57 | 173 | 271 | 171 | 300 | 348 | 134 |
| RTOR Reduction (vph) | 0 | 7 | 0 | 0 | 3 | 0 | 0 | 0 | 55 | 0 | 34 | 0 |
| Lane Group Flow (vph) | 104 | 1177 | 0 | 236 | 1168 | 0 | 173 | 271 | 116 | 300 | 448 | 0 |
| Confl. Peds. (#/hr) | | | 7 | | | 15 | 7 | | 8 | 8 | | 7 |
| Heavy Vehicles (%) | 6% | 7% | 3% | 0% | 7% | 6% | 4% | 5% | 3% | 2% | 4% | 3% |
| Turn Type | Prot | | | Prot | | | pm+pt | | pm+ov | pm+pt | | |
| Protected Phases | 5 | 2 | | 1 | 6 | | 3 | 8 | 1 | 7 | 4 | |
| Permitted Phases | | | | | | | 8 | | 8 | 4 | | |
| Actuated Green, G (s) | 10.0 | 54.6 | | 10.7 | 55.3 | | 21.2 | 21.2 | 31.9 | 27.3 | 26.8 | |
| Effective Green, g (s) | 10.5 | 55.1 | | 11.2 | 55.8 | | 21.7 | 21.7 | 32.9 | 27.8 | 27.3 | |
| Actuated g/C Ratio | 0.08 | 0.44 | | 0.09 | 0.45 | | 0.17 | 0.17 | 0.26 | 0.22 | 0.22 | |
| Clearance Time (s) | 5.0 | 6.0 | | 5.0 | 6.0 | | 5.0 | 5.5 | 5.0 | 5.0 | 5.5 | |
| Vehicle Extension (s) | 2.0 | 3.5 | | 2.0 | 3.5 | | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | |
| Lane Grp Cap (vph) | 143 | 1463 | | 314 | 1491 | | 223 | 314 | 406 | 337 | 724 | |
| v/s Ratio Prot | 0.06 | c0.35 | | 0.07 | c0.35 | | 0.07 | c0.15 | 0.03 | c0.12 | 0.14 | |
| v/s Ratio Perm | | | | | | | 0.06 | | 0.05 | c0.07 | | |
| v/c Ratio | 0.73 | 0.80 | | 0.75 | 0.78 | | 0.78 | 0.86 | 0.29 | 0.89 | 0.62 | |
| Uniform Delay, d1 | 55.9 | 30.3 | | 55.5 | 29.5 | | 47.6 | 50.2 | 36.7 | 45.8 | 44.1 | |
| Progression Factor | 1.00 | 1.00 | | 0.61 | 0.96 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | |
| Incremental Delay, d2 | 14.4 | 4.8 | | 5.3 | 2.5 | | 14.2 | 20.3 | 0.1 | 23.5 | 1.1 | |
| Delay (s) | 70.3 | 35.1 | | 39.2 | 30.9 | | 61.8 | 70.5 | 36.8 | 69.4 | 45.3 | |
| Level of Service | E | D | | D | C | | E | E | D | E | D | |
| Approach Delay (s) | | 37.9 | | | 32.3 | | | 58.7 | | | 54.5 | |
| Approach LOS | | D | | | C | | | E | | | D | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 42.3 | | | | HCM Level of Service | | | | D | |
| HCM Volume to Capacity ratio | | | 0.87 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 125.0 | | | | Sum of lost time (s) | | | 20.5 | | |
| Intersection Capacity Utilization | | | 88.2% | | | | ICU Level of Service | | | E | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |




















HCM Signalized Intersection Capacity Analysis
 17: Tualatin Sherwood Rd & Martinazzi Ave

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|------|-------|------|------|------|------|------|-------|------|------|----------------------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 55 | 1515 | 83 | 0 | 1146 | 0 | 95 | 312 | 333 | 194 | 673 | 90 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 5.5 | | | 5.5 | | 4.5 | 5.5 | 5.5 | 4.5 | 5.5 | |
| Lane Util. Factor | 1.00 | 0.95 | | | 0.95 | | 1.00 | 1.00 | 1.00 | 1.00 | 0.95 | |
| Frbp, ped/bikes | 1.00 | 1.00 | | | 1.00 | | 1.00 | 1.00 | 0.98 | 1.00 | 1.00 | |
| Flpb, ped/bikes | 1.00 | 1.00 | | | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | |
| Frt | 1.00 | 0.99 | | | 1.00 | | 1.00 | 1.00 | 0.85 | 1.00 | 0.98 | |
| Flt Protected | 0.95 | 1.00 | | | 1.00 | | 0.95 | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (prot) | 1719 | 3448 | | | 3438 | | 1770 | 1863 | 1574 | 1787 | 3497 | |
| Flt Permitted | 0.95 | 1.00 | | | 1.00 | | 0.95 | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (perm) | 1719 | 3448 | | | 3438 | | 1770 | 1863 | 1574 | 1787 | 3497 | |
| Peak-hour factor, PHF | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 |
| Adj. Flow (vph) | 59 | 1612 | 88 | 0 | 1219 | 0 | 101 | 332 | 354 | 206 | 716 | 96 |
| RTOR Reduction (vph) | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 80 | 0 | 10 | 0 |
| Lane Group Flow (vph) | 59 | 1697 | 0 | 0 | 1219 | 0 | 101 | 332 | 274 | 206 | 802 | 0 |
| Confl. Peds. (#/hr) | | | 4 | | | 2 | | | 3 | | | 16 |
| Heavy Vehicles (%) | 5% | 4% | 0% | 0% | 5% | 0% | 2% | 2% | 1% | 1% | 1% | 1% |
| Turn Type | Prot | | | | | | Prot | | Perm | Prot | | |
| Protected Phases | 5 | 2 | | | 6 | | 3 | 8 | | 7 | 4 | |
| Permitted Phases | | | | | | | | | 8 | | | |
| Actuated Green, G (s) | 7.2 | 65.2 | | | 53.0 | | 9.9 | 24.1 | 24.1 | 18.7 | 32.9 | |
| Effective Green, g (s) | 7.7 | 65.7 | | | 53.5 | | 10.4 | 24.6 | 24.6 | 19.2 | 33.4 | |
| Actuated g/C Ratio | 0.06 | 0.53 | | | 0.43 | | 0.08 | 0.20 | 0.20 | 0.15 | 0.27 | |
| Clearance Time (s) | 5.0 | 6.0 | | | 6.0 | | 5.0 | 6.0 | 6.0 | 5.0 | 6.0 | |
| Vehicle Extension (s) | 2.0 | 3.5 | | | 3.5 | | 3.0 | 2.0 | 2.0 | 3.0 | 2.0 | |
| Lane Grp Cap (vph) | 106 | 1812 | | | 1471 | | 147 | 367 | 310 | 274 | 934 | |
| v/s Ratio Prot | 0.03 | c0.49 | | | 0.35 | | 0.06 | c0.18 | | 0.12 | c0.23 | |
| v/s Ratio Perm | | | | | | | | | 0.17 | | | |
| v/c Ratio | 0.56 | 0.94 | | | 0.83 | | 0.69 | 0.90 | 0.88 | 0.75 | 0.86 | |
| Uniform Delay, d1 | 57.0 | 27.7 | | | 31.7 | | 55.7 | 49.1 | 48.8 | 50.6 | 43.6 | |
| Progression Factor | 1.20 | 0.74 | | | 1.09 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | |
| Incremental Delay, d2 | 2.7 | 8.5 | | | 4.4 | | 12.5 | 24.3 | 23.7 | 11.0 | 7.7 | |
| Delay (s) | 70.9 | 29.0 | | | 38.9 | | 68.3 | 73.4 | 72.5 | 61.7 | 51.2 | |
| Level of Service | E | C | | | D | | E | E | E | E | D | |
| Approach Delay (s) | | 30.4 | | | 38.9 | | | 72.3 | | | 53.3 | |
| Approach LOS | | C | | | D | | | E | | | D | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | 44.4 | | | | | | | | | HCM Level of Service | D |
| HCM Volume to Capacity ratio | | 0.89 | | | | | | | | | | |
| Actuated Cycle Length (s) | | 125.0 | | | | | | | 11.0 | | Sum of lost time (s) | |
| Intersection Capacity Utilization | | 89.5% | | | | | | | | | ICU Level of Service | E |
| Analysis Period (min) | | 15 | | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 18: SW Borland Rd & SW 65th Ave

4/15/2013

| |  |  |  |  |  |  |  |  |  |  |  |  | |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|------|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR | |
| Lane Configurations | |  | | |  |  |  |  | |  |  | | |
| Volume (vph) | 23 | 23 | 10 | 240 | 0 | 244 | 2 | 334 | 369 | 433 | 474 | 10 | |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | |
| Total Lost time (s) | | 5.6 | | | 5.3 | 5.6 | 4.8 | 4.8 | | 4.8 | 4.8 | | |
| Lane Util. Factor | | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | | |
| Frbp, ped/bikes | | 0.99 | | | 1.00 | 0.90 | 1.00 | 0.98 | | 1.00 | 1.00 | | |
| Flpb, ped/bikes | | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | | |
| Frt | | 0.98 | | | 1.00 | 0.85 | 1.00 | 0.92 | | 1.00 | 1.00 | | |
| Flt Protected | | 0.98 | | | 0.95 | 1.00 | 0.95 | 1.00 | | 0.95 | 1.00 | | |
| Satd. Flow (prot) | | 1785 | | | 1805 | 1456 | 1748 | 1719 | | 1787 | 1893 | | |
| Flt Permitted | | 0.98 | | | 0.95 | 1.00 | 0.48 | 1.00 | | 0.08 | 1.00 | | |
| Satd. Flow (perm) | | 1785 | | | 1805 | 1456 | 880 | 1719 | | 157 | 1893 | | |
| Peak-hour factor, PHF | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | |
| Adj. Flow (vph) | 24 | 24 | 10 | 250 | 0 | 254 | 2 | 348 | 384 | 451 | 494 | 10 | |
| RTOR Reduction (vph) | 0 | 6 | 0 | 0 | 0 | 240 | 0 | 25 | 0 | 0 | 0 | 0 | |
| Lane Group Flow (vph) | 0 | 52 | 0 | 0 | 250 | 14 | 2 | 707 | 0 | 451 | 504 | 0 | |
| Confl. Peds. (#/hr) | 9 | | 2 | 2 | | 9 | 3 | | 4 | 4 | | 3 | |
| Heavy Vehicles (%) | 0% | 2% | 2% | 0% | 1% | 0% | 3% | 0% | 0% | 1% | 0% | 0% | |
| Turn Type | Split | | | Split | | custom | pm+pt | | | pm+pt | | | |
| Protected Phases | 8 | 8 | | 4 | 4 | | 1 | 6 | | 5 | 2 | | |
| Permitted Phases | | | | | | 8 | 6 | | | 2 | | | |
| Actuated Green, G (s) | | 7.6 | | | 20.0 | 7.6 | 65.3 | 64.3 | | 99.6 | 93.3 | | |
| Effective Green, g (s) | | 8.1 | | | 20.5 | 8.1 | 66.3 | 64.8 | | 100.1 | 93.8 | | |
| Actuated g/C Ratio | | 0.06 | | | 0.14 | 0.06 | 0.46 | 0.45 | | 0.69 | 0.65 | | |
| Clearance Time (s) | | 6.1 | | | 5.8 | 6.1 | 5.3 | 5.3 | | 5.3 | 5.3 | | |
| Vehicle Extension (s) | | 1.0 | | | 2.0 | 1.0 | 1.0 | 3.0 | | 2.5 | 0.2 | | |
| Lane Grp Cap (vph) | | 100 | | | 256 | 82 | 413 | 771 | | 453 | 1230 | | |
| v/s Ratio Prot | | c0.03 | | | c0.14 | | 0.00 | 0.41 | | c0.21 | 0.27 | | |
| v/s Ratio Perm | | | | | | 0.01 | 0.00 | | | c0.48 | | | |
| v/c Ratio | | 0.52 | | | 0.98 | 0.17 | 0.00 | 0.92 | | 1.00 | 0.41 | | |
| Uniform Delay, d1 | | 66.3 | | | 61.7 | 65.0 | 21.1 | 37.3 | | 45.6 | 12.1 | | |
| Progression Factor | | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | | |
| Incremental Delay, d2 | | 2.3 | | | 49.0 | 0.4 | 0.0 | 15.5 | | 40.9 | 0.1 | | |
| Delay (s) | | 68.5 | | | 110.8 | 65.3 | 21.1 | 52.8 | | 86.5 | 12.2 | | |
| Level of Service | | E | | | F | E | C | D | | F | B | | |
| Approach Delay (s) | | 68.5 | | | 87.9 | | | 52.7 | | | 47.2 | | |
| Approach LOS | | E | | | F | | | D | | | D | | |
| Intersection Summary | | | | | | | | | | | | | |
| HCM Average Control Delay | | | 58.7 | | | | | | | | | HCM Level of Service | E |
| HCM Volume to Capacity ratio | | | 0.95 | | | | | | | | | | |
| Actuated Cycle Length (s) | | | 144.4 | | | | | | | | | Sum of lost time (s) | 15.7 |
| Intersection Capacity Utilization | | | 96.8% | | | | | | | | | ICU Level of Service | F |
| Analysis Period (min) | | | 15 | | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 19: SW Sagert St & SW Boones Ferry Rd

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|-------|------|-------|-------|------|----------------------|-------|-------|------|-------|------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 42 | 117 | 13 | 166 | 122 | 64 | 16 | 486 | 218 | 65 | 571 | 75 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 3.5 | 3.5 | | 3.5 | 3.5 | | 3.5 | 4.0 | | 3.5 | 4.0 | |
| Lane Util. Factor | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 0.98 | | 1.00 | 0.99 | | 1.00 | 1.00 | |
| Flpb, ped/bikes | 0.99 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Frt | 1.00 | 0.98 | | 1.00 | 0.95 | | 1.00 | 0.95 | | 1.00 | 0.98 | |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | 0.95 | 1.00 | | 0.95 | 1.00 | |
| Satd. Flow (prot) | 1782 | 1830 | | 1781 | 1739 | | 1769 | 1789 | | 1804 | 1860 | |
| Flt Permitted | 0.64 | 1.00 | | 0.42 | 1.00 | | 0.25 | 1.00 | | 0.17 | 1.00 | |
| Satd. Flow (perm) | 1191 | 1830 | | 785 | 1739 | | 468 | 1789 | | 319 | 1860 | |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 44 | 123 | 14 | 175 | 128 | 67 | 17 | 512 | 229 | 68 | 601 | 79 |
| RTOR Reduction (vph) | 0 | 4 | 0 | 0 | 16 | 0 | 0 | 11 | 0 | 0 | 3 | 0 |
| Lane Group Flow (vph) | 44 | 133 | 0 | 175 | 179 | 0 | 17 | 730 | 0 | 68 | 677 | 0 |
| Confl. Peds. (#/hr) | 15 | | 7 | 7 | | 15 | 7 | | 8 | 8 | | 7 |
| Heavy Vehicles (%) | 0% | 2% | 1% | 1% | 3% | 0% | 2% | 0% | 1% | 0% | 0% | 0% |
| Turn Type | pm+pt | | | pm+pt | | | pm+pt | | | pm+pt | | |
| Protected Phases | 7 | 4 | | 3 | 8 | | 5 | 2 | | 1 | 6 | |
| Permitted Phases | 4 | | | 8 | | | 2 | | | 6 | | |
| Actuated Green, G (s) | 15.3 | 12.4 | | 25.7 | 18.8 | | 47.1 | 45.6 | | 51.5 | 47.8 | |
| Effective Green, g (s) | 16.3 | 12.9 | | 26.2 | 19.3 | | 48.1 | 46.1 | | 52.5 | 48.3 | |
| Actuated g/C Ratio | 0.19 | 0.15 | | 0.30 | 0.22 | | 0.55 | 0.53 | | 0.60 | 0.55 | |
| Clearance Time (s) | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 | 4.5 | | 4.0 | 4.5 | |
| Vehicle Extension (s) | 2.2 | 2.2 | | 2.2 | 2.2 | | 2.2 | 5.0 | | 2.2 | 5.0 | |
| Lane Grp Cap (vph) | 245 | 270 | | 347 | 384 | | 287 | 943 | | 263 | 1027 | |
| v/s Ratio Prot | 0.01 | 0.07 | | c0.06 | 0.10 | | 0.00 | c0.41 | | c0.01 | 0.36 | |
| v/s Ratio Perm | 0.03 | | | c0.09 | | | 0.03 | | | 0.14 | | |
| v/c Ratio | 0.18 | 0.49 | | 0.50 | 0.47 | | 0.06 | 0.77 | | 0.26 | 0.66 | |
| Uniform Delay, d1 | 29.7 | 34.3 | | 24.1 | 29.6 | | 10.8 | 16.5 | | 11.9 | 13.8 | |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Incremental Delay, d2 | 0.2 | 0.7 | | 0.6 | 0.5 | | 0.0 | 4.7 | | 0.3 | 2.1 | |
| Delay (s) | 29.9 | 35.0 | | 24.7 | 30.1 | | 10.8 | 21.2 | | 12.2 | 15.9 | |
| Level of Service | C | D | | C | C | | B | C | | B | B | |
| Approach Delay (s) | | 33.8 | | | 27.5 | | | 21.0 | | | 15.5 | |
| Approach LOS | | C | | | C | | | C | | | B | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 21.3 | | | HCM Level of Service | | | | C | | |
| HCM Volume to Capacity ratio | | | 0.68 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 87.5 | | | Sum of lost time (s) | | | 14.5 | | | |
| Intersection Capacity Utilization | | | 74.8% | | | ICU Level of Service | | | | D | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

Intersection: 12: Tualatin Sherwood Rd & I-5 SB Ramps

| Movement | EB | EB | EB | EB | WB | WB | WB | SB | SB | SB | SB |
|-----------------------|-----|-----|-----|-----|-----|-----|-----|-----|------|------|-----|
| Directions Served | T | T | T | R | L | T | T | L | LT | R | R |
| Maximum Queue (ft) | 410 | 477 | 487 | 381 | 515 | 642 | 679 | 225 | 801 | 538 | 436 |
| Average Queue (ft) | 190 | 187 | 192 | 61 | 167 | 391 | 435 | 177 | 393 | 280 | 209 |
| 95th Queue (ft) | 352 | 369 | 372 | 232 | 422 | 641 | 680 | 267 | 703 | 449 | 373 |
| Link Distance (ft) | 507 | 507 | 507 | | 641 | 641 | 641 | | 1156 | 1156 | |
| Upstream Blk Time (%) | 0 | 0 | 1 | | 1 | 2 | 3 | | | | |
| Queuing Penalty (veh) | 1 | 3 | 4 | | 2 | 9 | 13 | | | | |
| Storage Bay Dist (ft) | | | | 400 | | | | 200 | | | 700 |
| Storage Blk Time (%) | | | 1 | 0 | | | | 6 | 23 | 0 | |
| Queuing Penalty (veh) | | | 6 | 0 | | | | 21 | 77 | 0 | |

Queuing and Blocking Report
 2014 Total Weekday PM Peak

4/12/2013

Intersection: 13: Tualatin Sherwood Rd & I-5 NB Ramps

| Movement | EB | EB | EB | EB | WB | WB | WB | NB | NB | NB |
|-----------------------|-----|-----|-----|-----|-----|-----|-----|-----|------|-----|
| Directions Served | T | T | R | R | T | T | R | L | LT | R |
| Maximum Queue (ft) | 634 | 555 | 111 | 105 | 194 | 328 | 223 | 357 | 652 | 300 |
| Average Queue (ft) | 336 | 215 | 11 | 7 | 83 | 119 | 18 | 237 | 295 | 121 |
| 95th Queue (ft) | 589 | 466 | 146 | 110 | 164 | 235 | 116 | 350 | 628 | 267 |
| Link Distance (ft) | 641 | 641 | 641 | 641 | 478 | 478 | | | 1328 | |
| Upstream Blk Time (%) | 1 | 0 | 0 | 0 | | 0 | | | 0 | |
| Queuing Penalty (veh) | 7 | 1 | 0 | 0 | | 1 | | | 0 | |
| Storage Bay Dist (ft) | | | | | | | 150 | 300 | | 225 |
| Storage Blk Time (%) | | | | | | 3 | 0 | 3 | 13 | 0 |
| Queuing Penalty (veh) | | | | | | 21 | 0 | 16 | 67 | 3 |

HCS+: Unsignalized Intersections Release 5.6

Phone:
E-Mail:

Fax:

ALL-WAY STOP CONTROL (AWSC) ANALYSIS

Analyst:
Agency/Co.:
Date Performed: 4/16/2013
Analysis Time Period: Weekday PM
Intersection: Sagert/Martinazzi
Jurisdiction:
Units: U. S. Customary
Analysis Year: Total
Project ID:
East/West Street: Sagert
North/South Street: Martinazzi

Worksheet 2 - Volume Adjustments and Site Characteristics

| | Eastbound | | | Westbound | | | Northbound | | | Southbound | | |
|-------------------|-----------|-----|----|-----------|-----|-----|------------|---|----|------------|-----|---|
| | L | T | R | L | T | R | L | T | R | L | T | R |
| Volume | 127 | 233 | 12 | 90 | 195 | 164 | 2 | | 76 | 207 | 306 | 0 |
| % Thrus Left Lane | | | | | | | | | | | | |

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|-------------------|-----------|------|-----------|------|------------|------|------------|------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Configuration | L | TR | L | TR | L | TR | L | TR |
| PHF | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 |
| Flow Rate | 141 | 271 | 100 | 398 | 2 | 284 | 230 | 340 |
| % Heavy Veh | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| No. Lanes | | 2 | | 2 | | 2 | | 2 |
| Opposing-Lanes | | 2 | | 2 | | 2 | | 2 |
| Conflicting-lanes | | 2 | | 2 | | 2 | | 2 |
| Geometry group | | 5 | | 5 | | 5 | | 5 |
| Duration, T | 0.25 hrs. | | | | | | | |

Worksheet 3 - Saturation Headway Adjustment Worksheet

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|----------------------------|-----------|-----|-----------|-----|------------|-----|------------|-----|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow Rates: | | | | | | | | |
| Total in Lane | 141 | 271 | 100 | 398 | 2 | 284 | 230 | 340 |
| Left-Turn | 141 | 0 | 100 | 0 | 2 | 0 | 230 | 0 |
| Right-Turn | 0 | 13 | 0 | 182 | 0 | 84 | 0 | 0 |
| Prop. Left-Turns | 1.0 | 0.0 | 1.0 | 0.0 | 1.0 | 0.0 | 1.0 | 0.0 |
| Prop. Right-Turns | 0.0 | 0.0 | 0.0 | 0.5 | 0.0 | 0.3 | 0.0 | 0.0 |
| Prop. Heavy Vehicle | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Geometry Group | | 5 | | 5 | | 5 | | 5 |
| Adjustments Exhibit 17-33: | | | | | | | | |
| hLT-adj | | 0.5 | | 0.5 | | 0.5 | | 0.5 |

| | | | | |
|----------------|------|------|------|------|
| hRT-adj | -0.7 | -0.7 | -0.7 | -0.7 |
| hHV-adj | 1.7 | 1.7 | 1.7 | 1.7 |
| hadj, computed | 0.5 | -0.0 | 0.5 | -0.3 |
| | 0.5 | -0.2 | 0.5 | 0.0 |

Worksheet 4 - Departure Headway and Service Time

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|-------------------|-----------|------|-----------|------|------------|------|------------|------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow rate | 141 | 271 | 100 | 398 | 2 | 284 | 230 | 340 |
| hd, initial value | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 |
| x, initial | 0.13 | 0.24 | 0.09 | 0.35 | 0.00 | 0.25 | 0.20 | 0.30 |
| hd, final value | 8.96 | 8.42 | 8.76 | 7.94 | 9.19 | 8.48 | 8.72 | 8.22 |
| x, final value | 0.35 | 0.63 | 0.24 | 0.88 | 0.01 | 0.67 | 0.56 | 0.78 |
| Move-up time, m | | 2.3 | | 2.3 | | 2.3 | | 2.3 |
| Service Time | 6.7 | 6.1 | 6.5 | 5.6 | 6.9 | 6.2 | 6.4 | 5.9 |

Worksheet 5 - Capacity and Level of Service

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|--------------------|-----------|-------|-----------|-------|------------|-------|------------|-------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow Rate | 141 | 271 | 100 | 398 | 2 | 284 | 230 | 340 |
| Service Time | 6.7 | 6.1 | 6.5 | 5.6 | 6.9 | 6.2 | 6.4 | 5.9 |
| Utilization, x | 0.35 | 0.63 | 0.24 | 0.88 | 0.01 | 0.67 | 0.56 | 0.78 |
| Dep. headway, hd | 8.96 | 8.42 | 8.76 | 7.94 | 9.19 | 8.48 | 8.72 | 8.22 |
| Capacity | 391 | 418 | 350 | 450 | 252 | 413 | 407 | 433 |
| Delay | 16.42 | 24.61 | 14.25 | 45.54 | 11.93 | 26.70 | 21.85 | 34.14 |
| LOS | C | C | B | E | B | D | C | D |
| Approach: | | | | | | | | |
| Delay | | 21.81 | | 39.26 | | 26.59 | | 29.18 |
| LOS | | C | | E | | D | | D |
| Intersection Delay | 29.88 | | | | | | | |
| | | | | | | | | |

HCS+: Unsignalized Intersections Release 5.6

Phone:
E-Mail:

Fax:

ALL-WAY STOP CONTROL (AWSC) ANALYSIS

Analyst:
Agency/Co.:
Date Performed: 4/16/2013
Analysis Time Period: Weekday PM
Intersection: Sagert/65th
Jurisdiction:
Units: U. S. Customary
Analysis Year: Total
Project ID:
East/West Street: Sagert
North/South Street: 65th

Worksheet 2 - Volume Adjustments and Site Characteristics

| | Eastbound | | | Westbound | | | Northbound | | | Southbound | | |
|-------------------|-----------|---|-----|-----------|---|---|------------|---|---|------------|-----|-----|
| | L | T | R | L | T | R | L | T | R | L | T | R |
| Volume | 401 | 2 | 135 | 2 | 7 | 6 | 58 | | 3 | 3 | 340 | 386 |
| % Thrus Left Lane | | | | | | | | | | | | |

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|-------------------|-----------|------|-----------|------|------------|------|------------|------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Configuration | L | TR | L | TR | L | TR | L | TR |
| PHF | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 |
| Flow Rate | 445 | 152 | 2 | 13 | 64 | 323 | 3 | 805 |
| % Heavy Veh | 1 | 1 | 0 | 0 | 1 | 2 | 1 | 2 |
| No. Lanes | | 2 | | 2 | | 2 | | 2 |
| Opposing-Lanes | | 2 | | 2 | | 2 | | 2 |
| Conflicting-lanes | | 2 | | 2 | | 2 | | 2 |
| Geometry group | | 5 | | 5 | | 5 | | 5 |
| Duration, T | 0.25 hrs. | | | | | | | |

Worksheet 3 - Saturation Headway Adjustment Worksheet

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|----------------------------|-----------|-----|-----------|-----|------------|-----|------------|-----|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow Rates: | | | | | | | | |
| Total in Lane | 445 | 152 | 2 | 13 | 64 | 323 | 3 | 805 |
| Left-Turn | 445 | 0 | 2 | 0 | 64 | 0 | 3 | 0 |
| Right-Turn | 0 | 150 | 0 | 6 | 0 | 3 | 0 | 428 |
| Prop. Left-Turns | 1.0 | 0.0 | 1.0 | 0.0 | 1.0 | 0.0 | 1.0 | 0.0 |
| Prop. Right-Turns | 0.0 | 1.0 | 0.0 | 0.5 | 0.0 | 0.0 | 0.0 | 0.5 |
| Prop. Heavy Vehicle | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Geometry Group | | 5 | | 5 | | 5 | | 5 |
| Adjustments Exhibit 17-33: | | | | | | | | |
| hLT-adj | | 0.5 | | 0.5 | | 0.5 | | 0.5 |

| | | | | | | | | |
|----------------|------|------|------|------|------|-----|------|------|
| hRT-adj | -0.7 | | -0.7 | | -0.7 | | -0.7 | |
| hHV-adj | 1.7 | | 1.7 | | 1.7 | | 1.7 | |
| hadj, computed | 0.5 | -0.7 | 0.5 | -0.3 | 0.5 | 0.0 | 0.5 | -0.3 |

Worksheet 4 - Departure Headway and Service Time

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|-------------------|-----------|------|-----------|------|------------|------|------------|------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow rate | 445 | 152 | 2 | 13 | 64 | 323 | 3 | 805 |
| hd, initial value | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 |
| x, initial | 0.40 | 0.14 | 0.00 | 0.01 | 0.06 | 0.29 | 0.00 | 0.72 |
| hd, final value | 7.73 | 6.54 | 9.23 | 8.40 | 8.00 | 7.51 | 7.77 | 6.92 |
| x, final value | 0.96 | 0.28 | 0.01 | 0.03 | 0.14 | 0.67 | 0.01 | 1.55 |
| Move-up time, m | | 2.3 | | 2.3 | | 2.3 | | 2.3 |
| Service Time | 5.4 | 4.2 | 6.9 | 6.1 | 5.7 | 5.2 | 5.5 | 4.6 |

Worksheet 5 - Capacity and Level of Service

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|--------------------|-----------|-------|-----------|-------|------------|-------|------------|--------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow Rate | 445 | 152 | 2 | 13 | 64 | 323 | 3 | 805 |
| Service Time | 5.4 | 4.2 | 6.9 | 6.1 | 5.7 | 5.2 | 5.5 | 4.6 |
| Utilization, x | 0.96 | 0.28 | 0.01 | 0.03 | 0.14 | 0.67 | 0.01 | 1.55 |
| Dep. headway, hd | 7.73 | 6.54 | 9.23 | 8.40 | 8.00 | 7.51 | 7.77 | 6.92 |
| Capacity | 466 | 402 | 252 | 263 | 314 | 475 | 253 | 805 |
| Delay | 58.85 | 11.71 | 11.98 | 11.37 | 12.02 | 24.33 | 10.52 | 273.87 |
| LOS | F | B | B | B | B | C | B | F |
| Approach: | | | | | | | | |
| Delay | | 46.85 | | 11.45 | | 22.29 | | 272.89 |
| LOS | | E | | B | | C | | F |
| Intersection Delay | 142.37 | | | | | | | |
| | | | | | | | | |

HCM Unsignalized Intersection Capacity Analysis
 22: SW Boones Fe &

4/15/2013



| Movement | EBT | EBR | WBL | WBT | NWL | NWR |
|------------------------|-------|------|------|------|------|------|
| Lane Configurations | ↑ | | | ↑↑ | | ↑ |
| Volume (veh/h) | 1051 | 10 | 0 | 1384 | 0 | 35 |
| Sign Control | Free | | | Free | Stop | |
| Grade | 0% | | | 0% | 0% | |
| Peak Hour Factor | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 |
| Hourly flow rate (vph) | 1142 | 11 | 0 | 1504 | 0 | 38 |
| Pedestrians | | | | | | |
| Lane Width (ft) | | | | | | |
| Walking Speed (ft/s) | | | | | | |
| Percent Blockage | | | | | | |
| Right turn flare (veh) | | | | | | |
| Median type | TWLTL | | None | | | |
| Median storage (veh) | 2 | | | | | |
| Upstream signal (ft) | 252 | | | | | |
| pX, platoon unblocked | | | 0.63 | 0.63 | 0.63 | |
| vC, conflicting volume | | | 1153 | 1900 | 1148 | |
| vC1, stage 1 conf vol | | | | 1148 | | |
| vC2, stage 2 conf vol | | | | 752 | | |
| vCu, unblocked vol | | | 949 | 2136 | 940 | |
| tC, single (s) | | | 4.1 | 6.8 | 6.9 | |
| tC, 2 stage (s) | | | | 5.8 | | |
| tF (s) | | | 2.2 | 3.5 | 3.3 | |
| p0 queue free % | | | 100 | 100 | 77 | |
| cM capacity (veh/h) | | | 453 | 185 | 167 | |

| Direction, Lane # | EB 1 | WB 1 | WB 2 | NW 1 |
|------------------------|------|------|------|------|
| Volume Total | 1153 | 752 | 752 | 38 |
| Volume Left | 0 | 0 | 0 | 0 |
| Volume Right | 11 | 0 | 0 | 38 |
| cSH | 1700 | 1700 | 1700 | 167 |
| Volume to Capacity | 0.68 | 0.44 | 0.44 | 0.23 |
| Queue Length 95th (ft) | 0 | 0 | 0 | 21 |
| Control Delay (s) | 0.0 | 0.0 | 0.0 | 32.9 |
| Lane LOS | | | | D |
| Approach Delay (s) | 0.0 | 0.0 | | 32.9 |
| Approach LOS | | | | D |

| Intersection Summary | | | |
|-----------------------------------|--|-------|------------------------|
| Average Delay | | 0.5 | |
| Intersection Capacity Utilization | | 65.9% | ICU Level of Service C |
| Analysis Period (min) | | 15 | |

HCM Signalized Intersection Capacity Analysis
 3: SW Boones Ferry Rd & SW Martinazzi Ave

2/03/2013



| M | EBT | EBR | WBL | WBT | NBL | NBR |
|--------------|------|------|------|------|------|------|
| L C r | ↑ | ↗ | ↖ | ↑ | ↘ | ↗ |
| V | 41 | 14 | 318 | 429 | 201 | 33 |
| Id F | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| T L | 4. | 4. | 4. | 4. | 4. | 4. |
| L U .F r | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Fr , d/ | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 0.99 |
| F , d/ | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Fr | 1.00 | 0.8 | 1.00 | 1.00 | 1.00 | 0.8 |
| FPr d | 1.00 | 1.00 | 0.9 | 1.00 | 0.9 | 1.00 |
| Sd.F r | 1863 | 199 | 18 | 184 | 10 | 181 |
| FPr d | 1.00 | 1.00 | 0.9 | 1.00 | 0.9 | 1.00 |
| Sd.F r | 1863 | 199 | 18 | 184 | 10 | 181 |
| P r r,PHF | 0.9 | 0.9 | 0.9 | 0.9 | 0.9 | 0.9 |
| Ad.F | 439 | 13 | 33 | 42 | 212 | 32 |
| RTORR d | 0 | 10 | 0 | 0 | 0 | 96 |
| L Gr F | 439 | 48 | 33 | 42 | 212 | 26 |
| C .P d. /r | | 11 | 11 | | 1 | 3 |
| C.B /r | 4 | | 2 | 10 | 1 | |
| H V | 2 | 1 | 1 | 3 | 2 | 1 |
| Tr T | | Pr | Pr | | | |
| Pr dP | 2 | 2 | 1 | 6 | 8 | 1 |
| Pr dP | | | | | 8 | 8 |
| A dGr ,G | 20.4 | 20.4 | 1.3 | 42. | 14.1 | 31.4 |
| E Gr , | 20.9 | 20.9 | 1.8 | 43.2 | 14.6 | 32.4 |
| A d /CR | 0.31 | 0.31 | 0.2 | 0.6 | 0.22 | 0.49 |
| Cr T | .0 | .0 | .0 | .0 | .0 | .0 |
| V E | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 |
| L Gr C | 83 | 00 | 46 | 1193 | 38 | 83 |
| / R Pr | 0.24 | 0.03 | 0.19 | 0.2 | 0.12 | 0.08 |
| / R Pr | | | | | | 0.09 |
| / R | 0. | 0.10 | 0.0 | 0.38 | 0. | 0.32 |
| Ur D ,d1 | 20.6 | 16.3 | 22.1 | . | 23.2 | 10. |
| Pr r F r | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| l r D ,d2 | . | 0.1 | 4. | 0.2 | 1.6 | 0.2 |
| D | 26.1 | 16.3 | 26.8 | . | 24.8 | 10. |
| L Sr | C | B | C | A | C | B |
| A r D | 23.6 | | | 14. | 1.8 | |
| A r LOS | C | | | B | B | |
| l r S r | | | | | | |
| HCM A r Cr D | | | 1. | HCML | S r | B |
| HCM V C r | | | 0.68 | | | |
| A dC L | | | 66.8 | S | | 13. |
| l r C U | | | 62.6 | ICUL | S r | B |
| A Prd | | | 1 | | | |
| Cr L Gr | | | | | | |

HCM Unsignalized Intersection Capacity Analysis
 4: SW Martinazzi Ave &

2/03/2013



| M | WBL | WBR | NBT | NBR | SBL | SBT |
|-----------|------|------|------|------|------|-------|
| L C r | ↙ | ↗ | ↖ | | ↙ | ↗ |
| V / | 62 | 1 | 396 | | 202 | 2 |
| S C r | S | | Fr | | | Fr |
| Grd | 0 | | 0 | | | 0 |
| P H r F r | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 |
| H r r | 6 | 1 1 | 430 | 84 | 220 | 2 9 |
| P d r | | | | | | |
| L W d | | | | | | |
| W S d / | | | | | | |
| Pr B | | | | | | |
| R r r | | | | | | |
| M d | | | N | | | TWLTL |
| M d r | | | | | | 2 |
| U r | | | 46 | | | 31 |
| , d | 1.00 | 1.00 | | | 1.00 | |
| C, | 1191 | 4 2 | | | 14 | |
| C1, 1 | 4 2 | | | | | |
| C2, 2 | 18 | | | | | |
| C, d | 1191 | 4 2 | | | 14 | |
| C, | 6.4 | 6.2 | | | 4.1 | |
| C, 2 | .4 | | | | | |
| F | 3. | 3.3 | | | 2.2 | |
| o r | 80 | 1 | | | 9 | |
| M / | 34 | 92 | | | 101 | |
| Dr ,L | WB 1 | WB 2 | NB 1 | SB 1 | SB 2 | |
| V T | 6 | 11 | 14 | 220 | 29 | |
| V L | 6 | 0 | 0 | 220 | 0 | |
| V R | 0 | 1 1 | 84 | 0 | 0 | |
| SH | 34 | 92 | 100 | 101 | 100 | |
| V C | 0.20 | 0.29 | 0.30 | 0.21 | 0.16 | |
| L 9 | 19 | 31 | 0 | 20 | 0 | |
| C r D | 1.9 | 13. | 0.0 | 9.3 | 0.0 | |
| L LOS | C | B | | A | | |
| A r D | 14.8 | | 0.0 | 4.1 | | |
| A r LOS | B | | | | | |
| l r S r | | | | | | |
| A r D | | | 4.4 | | | |
| l r C U | | | 0.1 | ICUL | S r | A |
| A Prd | | | 1 | | | |

HCM Unsignalized Intersection Capacity Analysis
 5: Seneca St & Martinazzi Ave

2/03/2013



| M | EBL | EBR | NBL | NBT | SBT | SBR |
|-----------|------|------|------|------|------|------|
| L C r | 3 | 4 | 81 | 43 | 2 | 44 |
| V / | | | | | | |
| S C r | S | | | Fr | Fr | |
| Grd | 0 | | | 0 | 0 | |
| P H r F r | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 |
| H r r | 41 | 49 | 89 | 480 | 302 | 48 |
| P d r | 1 | | | 4 | 10 | |
| L Wd | 12.0 | | | 12.0 | 12.0 | |
| W S d / | 4.0 | | | 4.0 | 4.0 | |
| Pr B | 0 | | | 0 | 1 | |
| R r r | | | | | | |
| Md | | | | N | N | |
| Md r | | | | | | |
| U r | | | | 30 | 4 | |
| d | 0.9 | | | | | |
| C, | 996 | 331 | 3 2 | | | |
| C1, 1 | | | | | | |
| C2, 2 | | | | | | |
| C, d | 9 9 | 331 | 3 2 | | | |
| C, | 6.4 | 6.2 | 4.1 | | | |
| C, 2 | | | | | | |
| F | 3. | 3.3 | 2.2 | | | |
| o r | 84 | 93 | 93 | | | |
| M / | 249 | 12 | 121 | | | |
| Dr ,L | EB 1 | NB 1 | NB 2 | SB 1 | | |
| V T | 90 | 89 | 480 | 31 | | |
| V L | 41 | 89 | 0 | 0 | | |
| V R | 49 | 0 | 0 | 48 | | |
| SH | 38 | 121 | 100 | 100 | | |
| V C | 0.23 | 0.0 | 0.28 | 0.21 | | |
| L 9 | 23 | 6 | 0 | 0 | | |
| C r D | 1.1 | 8.2 | 0.0 | 0.0 | | |
| L LOS | C | A | | | | |
| A r D | 1.1 | 1.3 | | 0.0 | | |
| A r LOS | C | | | | | |
| I r S r | | | | | | |
| A r D | | | 2.2 | | | |
| I r C U | | 3 . | | ICUL | S r | A |
| A Prd | | | 1 | | | |

HCM Unsignalized Intersection Capacity Analysis
 6: Martinazzi Ave &

2/03/2013



| M | WBL | WBR | NBT | NBR | SBL | SBT |
|-----------|------|------|------|------|------|------|
| L C r | Y | | ↑↑ | | | ↑↑ |
| V / | | 2 | 494 | 9 | 3 | 318 |
| S C r | S | | Fr | | | Fr |
| Grd | 0 | | 0 | | | 0 |
| P H r F r | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 |
| H r r | | 2 | 3 | 10 | 3 | 346 |
| P d r | | | | | | |
| L W d | | | | | | |
| W S d / | | | | | | |
| Pr B | | | | | | |
| R r r | | | | | | |
| M d | | | N | | | N |
| M d r | | | | | | |
| U r | | | 239 | | | 43 |
| C, d | 21 | 23 | | | 4 | |
| C1, 1 | | | | | | |
| C2, 2 | | | | | | |
| C, d | 21 | 23 | | | 4 | |
| C, | 6.8 | 6.9 | | | 4.1 | |
| C, 2 | | | | | | |
| F | 3. | 3.3 | | | 2.2 | |
| o r | 98 | 96 | | | 100 | |
| M / | 361 | 24 | | | 1019 | |
| Dr, L | WB 1 | NB 1 | NB 2 | SB 1 | SB 2 | |
| V T | 33 | 38 | 189 | 118 | 230 | |
| V L | | 0 | 0 | 3 | 0 | |
| V R | 2 | 0 | 10 | 0 | 0 | |
| SH | 620 | 100 | 100 | 1019 | 100 | |
| V C | 0.0 | 0.21 | 0.11 | 0.00 | 0.14 | |
| L 9 | 4 | 0 | 0 | 0 | 0 | |
| C r D | 11.1 | 0.0 | 0.0 | 0.3 | 0.0 | |
| L LOS | B | | | A | | |
| A r D | 11.1 | 0.0 | | 0.1 | | |
| A r LOS | B | | | | | |
| I r S r | | | | | | |
| A r D | | | 0.4 | | | |
| I r C U | | | 23.9 | ICUL | S r | A |
| A Prd | | | 1 | | | |

HCM Unsignalized Intersection Capacity Analysis
 7: Martinazzi Ave &

2/03/2013



| M | WBL | WBR | NBT | NBR | SBL | SBT |
|-----------|------|------|------|------|------|------|
| L C r | | | | | | |
| V / | 0 | 10 | 493 | 0 | 0 | 322 |
| S C r | S | | Fr | | | Fr |
| Grd | 0 | | 0 | | | 0 |
| P H r F r | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 |
| H r r | 0 | 11 | 36 | 0 | 0 | 3 0 |
| P d r | | | | | | |
| L Wd | | | | | | |
| W S d / | | | | | | |
| Pr B | | | | | | |
| R r r | | | | | | |
| Md | | | N | | | N |
| Md r | | | | | | |
| U r | | | 111 | | | 6 1 |
| d | 0.89 | 0.89 | | | 0.89 | |
| C, | 11 | 36 | | | 36 | |
| C1, 1 | | | | | | |
| C2, 2 | | | | | | |
| C, d | 610 | 412 | | | 412 | |
| C, | 6.8 | 6.9 | | | 4.1 | |
| C, 2 | | | | | | |
| F | 3. | 3.3 | | | 2.2 | |
| o r | 100 | 98 | | | 100 | |
| M / | 3 8 | 22 | | | 1013 | |
| Dr ,L | WB 1 | NB 1 | SB 1 | SB 2 | | |
| V T | 11 | 36 | 1 | 1 | | |
| V L | 0 | 0 | 0 | 0 | | |
| V R | 11 | 0 | 0 | 0 | | |
| SH | 22 | 100 | 100 | 100 | | |
| V C | 0.02 | 0.32 | 0.10 | 0.10 | | |
| L 9 | 2 | 0 | 0 | 0 | | |
| C r D | 12.0 | 0.0 | 0.0 | 0.0 | | |
| L LOS | B | | | | | |
| A r D | 12.0 | 0.0 | 0.0 | | | |
| A r LOS | B | | | | | |
| I r S r | | | | | | |
| A r D | | | 0.1 | | | |
| I r C U | | | 3.9 | ICUL | S r | A |
| A Prd | | | 1 | | | |

HCM Signalized Intersection Capacity Analysis
 8: Nyberg St & Martinazzi Ave

4/17/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|------|------|-------|------|------|------|-------|------|------|------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 16 | 1 | 63 | 260 | 37 | 237 | 23 | 240 | 36 | 0 | 314 | 8 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 5.5 | 5.5 | | 5.5 | 5.5 | 5.5 | 5.5 | 5.5 | | | 5.5 | |
| Lane Util. Factor | 1.00 | 1.00 | | 0.95 | 0.95 | 1.00 | 1.00 | 1.00 | | | 0.95 | |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 0.97 | 1.00 | 0.99 | | | 1.00 | |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | 1.00 | |
| Frt | 1.00 | 0.85 | | 1.00 | 1.00 | 0.85 | 1.00 | 0.98 | | | 1.00 | |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 0.96 | 1.00 | 0.95 | 1.00 | | | 1.00 | |
| Satd. Flow (prot) | 1805 | 1603 | | 1698 | 1727 | 1543 | 1683 | 1837 | | | 3559 | |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 0.96 | 1.00 | 0.54 | 1.00 | | | 1.00 | |
| Satd. Flow (perm) | 1805 | 1603 | | 1698 | 1727 | 1543 | 957 | 1837 | | | 3559 | |
| Peak-hour factor, PHF | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 |
| Adj. Flow (vph) | 18 | 1 | 69 | 286 | 41 | 260 | 25 | 264 | 40 | 0 | 345 | 9 |
| RTOR Reduction (vph) | 0 | 63 | 0 | 0 | 0 | 202 | 0 | 8 | 0 | 0 | 3 | 0 |
| Lane Group Flow (vph) | 18 | 7 | 0 | 163 | 164 | 58 | 25 | 296 | 0 | 0 | 351 | 0 |
| Confl. Peds. (#/hr) | 2 | | | | | 2 | 3 | | 16 | 16 | | 3 |
| Confl. Bikes (#/hr) | | | | | | 2 | | | | | | 3 |
| Heavy Vehicles (%) | 0% | 0% | 1% | 1% | 0% | 2% | 7% | 1% | 0% | 0% | 1% | 0% |
| Turn Type | Split | | | Split | | Perm | Perm | | | | | |
| Protected Phases | 8 | 8 | | 4 | 4 | | | 6 | | | | 2 |
| Permitted Phases | | | | | | 4 | 6 | | | | | |
| Actuated Green, G (s) | 3.1 | 3.1 | | 9.1 | 9.1 | 9.1 | 12.5 | 12.5 | | | 12.5 | |
| Effective Green, g (s) | 3.6 | 3.6 | | 9.6 | 9.6 | 9.6 | 13.0 | 13.0 | | | 13.0 | |
| Actuated g/C Ratio | 0.08 | 0.08 | | 0.22 | 0.22 | 0.22 | 0.30 | 0.30 | | | 0.30 | |
| Clearance Time (s) | 6.0 | 6.0 | | 6.0 | 6.0 | 6.0 | 6.0 | 6.0 | | | 6.0 | |
| Vehicle Extension (s) | 2.5 | 2.5 | | 2.5 | 2.5 | 2.5 | 5.0 | 5.0 | | | 5.0 | |
| Lane Grp Cap (vph) | 152 | 135 | | 382 | 388 | 347 | 291 | 559 | | | 1084 | |
| v/s Ratio Prot | c0.01 | 0.00 | | c0.10 | 0.09 | | | c0.16 | | | 0.10 | |
| v/s Ratio Perm | | | | | | 0.04 | 0.03 | | | | | |
| v/c Ratio | 0.12 | 0.05 | | 0.43 | 0.42 | 0.17 | 0.09 | 0.53 | | | 0.32 | |
| Uniform Delay, d1 | 18.1 | 18.0 | | 14.2 | 14.2 | 13.3 | 10.6 | 12.3 | | | 11.5 | |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | 1.00 | |
| Incremental Delay, d2 | 0.3 | 0.1 | | 0.6 | 0.5 | 0.2 | 0.3 | 1.8 | | | 0.4 | |
| Delay (s) | 18.3 | 18.1 | | 14.8 | 14.7 | 13.5 | 10.9 | 14.1 | | | 11.8 | |
| Level of Service | B | B | | B | B | B | B | B | | | B | |
| Approach Delay (s) | | 18.1 | | | 14.2 | | | 13.8 | | | 11.8 | |
| Approach LOS | | B | | | B | | | B | | | B | |

| Intersection Summary | | | |
|-----------------------------------|-------|----------------------|------|
| HCM Average Control Delay | 13.7 | HCM Level of Service | B |
| HCM Volume to Capacity ratio | 0.44 | | |
| Actuated Cycle Length (s) | 42.7 | Sum of lost time (s) | 16.5 |
| Intersection Capacity Utilization | 48.7% | ICU Level of Service | A |
| Analysis Period (min) | 15 | | |

c Critical Lane Group

HCM Unsignalized Intersection Capacity Analysis
 9: Nyberg St & Site Entrance 3

4/17/2013



| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
|------------------------|------|------|------|------|------|------|
| Lane Configurations | ↰ | | ↱↰ | | | ↰ |
| Volume (veh/h) | 37 | 0 | 466 | 60 | 0 | 67 |
| Sign Control | | Free | Free | | Stop | |
| Grade | | 0% | 0% | | 0% | |
| Peak Hour Factor | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 |
| Hourly flow rate (vph) | 42 | 0 | 530 | 68 | 0 | 76 |
| Pedestrians | | | | | 4 | |
| Lane Width (ft) | | | | | 12.0 | |
| Walking Speed (ft/s) | | | | | 4.0 | |
| Percent Blockage | | | | | 0 | |
| Right turn flare (veh) | | | | | | |
| Median type | | None | None | | | |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | 232 | | | | |
| pX, platoon unblocked | | | | | | |
| vC, conflicting volume | 602 | | | | 652 | 303 |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 602 | | | | 652 | 303 |
| tC, single (s) | 4.1 | | | | 6.8 | 6.9 |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 2.2 | | | | 3.5 | 3.3 |
| p0 queue free % | 96 | | | | 100 | 89 |
| cM capacity (veh/h) | 982 | | | | 387 | 697 |

| Direction, Lane # | EB 1 | WB 1 | WB 2 | SB 1 |
|------------------------|------|------|------|------|
| Volume Total | 42 | 353 | 245 | 76 |
| Volume Left | 42 | 0 | 0 | 0 |
| Volume Right | 0 | 0 | 68 | 76 |
| cSH | 982 | 1700 | 1700 | 697 |
| Volume to Capacity | 0.04 | 0.21 | 0.14 | 0.11 |
| Queue Length 95th (ft) | 3 | 0 | 0 | 10 |
| Control Delay (s) | 8.8 | 0.0 | 0.0 | 10.8 |
| Lane LOS | A | | | B |
| Approach Delay (s) | 8.8 | 0.0 | | 10.8 |
| Approach LOS | | | | B |

| Intersection Summary | | | |
|-----------------------------------|--|-------|------------------------|
| Average Delay | | 1.7 | |
| Intersection Capacity Utilization | | 25.7% | ICU Level of Service A |
| Analysis Period (min) | | 15 | |

HCM Signalized Intersection Capacity Analysis
 10: Tualatin Sherwood Rd & Site Entrance 4

4/17/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|------|-------|------|------|-------|------|-------|------|-------|-------|------|------|
| Lane Configurations | ↖ | ↗↖↗ | | ↖↗ | ↗↖↗ | ↖ | | ↖ | ↗ | ↖↗ | ↗ | ↖ |
| Volume (vph) | 180 | 1335 | 59 | 257 | 1458 | 361 | 57 | 25 | 248 | 373 | 40 | 190 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 6.0 | | 4.5 | 6.0 | 6.0 | | 5.0 | 4.5 | 5.0 | 5.0 | |
| Lane Util. Factor | 1.00 | *0.75 | | 0.97 | 0.91 | 1.00 | | 1.00 | 1.00 | 0.97 | 1.00 | |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 0.97 | | 1.00 | 1.00 | 1.00 | 0.98 | |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | |
| Frt | 1.00 | 0.99 | | 1.00 | 1.00 | 0.85 | | 1.00 | 0.85 | 1.00 | 0.88 | |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | 1.00 | | 0.97 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (prot) | 1805 | 4091 | | 3502 | 4988 | 1565 | | 1799 | 1599 | 3467 | 1634 | |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | 1.00 | | 0.97 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (perm) | 1805 | 4091 | | 3502 | 4988 | 1565 | | 1799 | 1599 | 3467 | 1634 | |
| Peak-hour factor, PHF | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 |
| Adj. Flow (vph) | 184 | 1362 | 60 | 262 | 1488 | 368 | 58 | 26 | 253 | 381 | 41 | 194 |
| RTOR Reduction (vph) | 0 | 3 | 0 | 0 | 0 | 201 | 0 | 0 | 0 | 0 | 164 | 0 |
| Lane Group Flow (vph) | 184 | 1419 | 0 | 262 | 1488 | 167 | 0 | 84 | 253 | 381 | 71 | 0 |
| Confl. Peds. (#/hr) | | | | | | 4 | | | | | | 9 |
| Confl. Bikes (#/hr) | | | | | 1 | | | 1 | | 1 | | |
| Heavy Vehicles (%) | 0% | 4% | 0% | 0% | 4% | 0% | 3% | 0% | 1% | 1% | 0% | 0% |
| Turn Type | Prot | | | Prot | | Perm | Split | | pt+ov | Split | | |
| Protected Phases | 5 | 2 | | 1 | 6 | | 8 | 8 | 18 | 4 | 4 | |
| Permitted Phases | | | | | | 6 | | | | | | |
| Actuated Green, G (s) | 14.8 | 49.6 | | 17.0 | 51.8 | 51.8 | | 8.5 | 25.5 | 17.4 | 17.4 | |
| Effective Green, g (s) | 15.3 | 50.1 | | 17.5 | 52.3 | 52.3 | | 9.0 | 26.5 | 17.9 | 17.9 | |
| Actuated g/C Ratio | 0.13 | 0.44 | | 0.15 | 0.45 | 0.45 | | 0.08 | 0.23 | 0.16 | 0.16 | |
| Clearance Time (s) | 5.0 | 6.5 | | 5.0 | 6.5 | 6.5 | | 5.5 | | 5.5 | 5.5 | |
| Vehicle Extension (s) | 2.5 | 4.0 | | 2.5 | 4.0 | 4.0 | | 2.5 | | 2.5 | 2.5 | |
| Lane Grp Cap (vph) | 240 | 1782 | | 533 | 2268 | 712 | | 141 | 368 | 540 | 254 | |
| v/s Ratio Prot | 0.10 | c0.35 | | 0.07 | c0.30 | | | 0.05 | c0.16 | c0.11 | 0.04 | |
| v/s Ratio Perm | | | | | | 0.11 | | | | | | |
| v/c Ratio | 0.77 | 0.80 | | 0.49 | 0.66 | 0.24 | | 0.60 | 0.69 | 0.71 | 0.28 | |
| Uniform Delay, d1 | 48.1 | 28.0 | | 44.7 | 24.4 | 19.1 | | 51.2 | 40.5 | 46.1 | 42.9 | |
| Progression Factor | 0.90 | 1.35 | | 0.96 | 0.90 | 1.07 | | 1.00 | 1.00 | 1.00 | 1.00 | |
| Incremental Delay, d2 | 10.1 | 2.9 | | 0.3 | 1.0 | 0.5 | | 5.5 | 4.8 | 3.9 | 0.4 | |
| Delay (s) | 53.6 | 40.7 | | 43.3 | 23.0 | 20.9 | | 56.8 | 45.3 | 49.9 | 43.3 | |
| Level of Service | D | D | | D | C | C | | E | D | D | D | |
| Approach Delay (s) | | 42.2 | | | 25.2 | | | 48.2 | | | 47.4 | |
| Approach LOS | | D | | | C | | | D | | | D | |














| Intersection Summary | | |
|-----------------------------------|-------|---------------------------|
| HCM Average Control Delay | 35.6 | HCM Level of Service D |
| HCM Volume to Capacity ratio | 0.71 | |
| Actuated Cycle Length (s) | 115.0 | Sum of lost time (s) 15.5 |
| Intersection Capacity Utilization | 77.3% | ICU Level of Service D |
| Analysis Period (min) | 15 | |

c Critical Lane Group

HCM Signalized Intersection Capacity Analysis













12: Tualatin Sherwood Rd & I-5 SB Ramps

4/17/2013

| |  |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR | |
| Lane Configurations | | ↑↑↑ | ↗ | ↖ | ↑↑ | | | | | ↘ | ↙ | ↗↗ | |
| Volume (vph) | 0 | 1484 | 480 | 193 | 1150 | 0 | 0 | 0 | 0 | 620 | 3 | 965 | |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | |
| Total Lost time (s) | | 5.5 | 5.5 | 5.5 | 5.5 | | | | | 5.5 | 5.5 | 5.5 | |
| Lane Util. Factor | | *0.75 | 1.00 | 1.00 | 0.95 | | | | | 0.95 | 0.95 | 0.88 | |
| Frbp, ped/bikes | | 1.00 | 1.00 | 1.00 | 1.00 | | | | | 1.00 | 1.00 | 1.00 | |
| Flpb, ped/bikes | | 1.00 | 1.00 | 1.00 | 1.00 | | | | | 1.00 | 1.00 | 1.00 | |
| Frt | | 1.00 | 0.85 | 1.00 | 1.00 | | | | | 1.00 | 1.00 | 0.85 | |
| Flt Protected | | 1.00 | 1.00 | 0.95 | 1.00 | | | | | 0.95 | 0.95 | 1.00 | |
| Satd. Flow (prot) | | 4150 | 1568 | 1787 | 3471 | | | | | 1681 | 1683 | 2760 | |
| Flt Permitted | | 1.00 | 1.00 | 0.95 | 1.00 | | | | | 0.95 | 0.95 | 1.00 | |
| Satd. Flow (perm) | | 4150 | 1568 | 1787 | 3471 | | | | | 1681 | 1683 | 2760 | |
| Peak-hour factor, PHF | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | |
| Adj. Flow (vph) | 0 | 1499 | 485 | 195 | 1162 | 0 | 0 | 0 | 0 | 626 | 3 | 975 | |
| RTOR Reduction (vph) | 0 | 0 | 242 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 40 | |
| Lane Group Flow (vph) | 0 | 1499 | 243 | 195 | 1162 | 0 | 0 | 0 | 0 | 313 | 316 | 935 | |
| Confl. Bikes (#/hr) | | 1 | | | 2 | | | | | | | | |
| Heavy Vehicles (%) | 0% | 3% | 3% | 1% | 4% | 0% | 0% | 0% | 0% | 2% | 20% | 3% | |
| Turn Type | | | Perm | Prot | | | | | | Split | | custom | |
| Protected Phases | | 2 | | 1 | 6 | | | | | 4 | 4 | 4 | |
| Permitted Phases | | | 2 | | | | | | | | | | |
| Actuated Green, G (s) | | 49.4 | 49.4 | 17.0 | 55.4 | | | | | 30.6 | 30.6 | 47.6 | |
| Effective Green, g (s) | | 49.9 | 49.9 | 17.5 | 55.9 | | | | | 31.1 | 31.1 | 44.6 | |
| Actuated g/C Ratio | | 0.43 | 0.43 | 0.15 | 0.49 | | | | | 0.27 | 0.27 | 0.39 | |
| Clearance Time (s) | | 6.0 | 6.0 | 6.0 | 6.0 | | | | | 6.0 | 6.0 | | |
| Vehicle Extension (s) | | 6.1 | 6.1 | 2.3 | 6.1 | | | | | 2.3 | 2.3 | | |
| Lane Grp Cap (vph) | | 1801 | 680 | 272 | 1687 | | | | | 455 | 455 | 1070 | |
| v/s Ratio Prot | | c0.36 | | c0.11 | 0.33 | | | | | 0.19 | 0.19 | c0.34 | |
| v/s Ratio Perm | | | 0.16 | | | | | | | | | | |
| v/c Ratio | | 0.83 | 0.36 | 0.72 | 0.69 | | | | | 0.69 | 0.69 | 0.87 | |
| Uniform Delay, d1 | | 28.8 | 21.8 | 46.4 | 22.8 | | | | | 37.6 | 37.7 | 32.6 | |
| Progression Factor | | 0.60 | 0.38 | 0.88 | 0.62 | | | | | 1.00 | 1.00 | 1.00 | |
| Incremental Delay, d2 | | 3.3 | 1.0 | 7.3 | 2.2 | | | | | 3.7 | 4.0 | 7.9 | |
| Delay (s) | | 20.5 | 9.4 | 48.1 | 16.3 | | | | | 41.3 | 41.7 | 40.5 | |
| Level of Service | | C | A | D | B | | | | | D | D | D | |
| Approach Delay (s) | | 17.8 | | | 20.9 | | | 0.0 | | | 40.9 | | |
| Approach LOS | | B | | | C | | | A | | | D | | |
| Intersection Summary | | | | | | | | | | | | | |
| HCM Average Control Delay | | | 26.1 | | | HCM Level of Service | | | | C | | | |
| HCM Volume to Capacity ratio | | | 0.89 | | | | | | | | | | |
| Actuated Cycle Length (s) | | | 115.0 | | | Sum of lost time (s) | | | 22.0 | | | | |
| Intersection Capacity Utilization | | | 74.7% | | | ICU Level of Service | | | | D | | | |
| Analysis Period (min) | | | 15 | | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 13: Tualatin Sherwood Rd & I-5 NB Ramps

4/17/2013

| |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | | ↑↑ | ↑↑ | | ↑↑ | ↑↑ | ↑ | ↑ | ↑ | | | |
| Volume (vph) | 0 | 1110 | 998 | 0 | 668 | 666 | 672 | 0 | 219 | 0 | 0 | 0 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | | 5.5 | 5.5 | | 6.0 | 6.0 | 5.5 | 5.5 | 5.5 | | | |
| Lane Util. Factor | | 0.95 | 0.88 | | 0.95 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Frbp, ped/bikes | | 1.00 | 0.98 | | 1.00 | 1.00 | 1.00 | 1.00 | 0.98 | | | |
| Flpb, ped/bikes | | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Frt | | 1.00 | 0.85 | | 1.00 | 0.85 | 1.00 | 1.00 | 0.85 | | | |
| Flt Protected | | 1.00 | 1.00 | | 1.00 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Satd. Flow (prot) | | 3574 | 2694 | | 3574 | 1583 | 1618 | 1618 | 1559 | | | |
| Flt Permitted | | 1.00 | 1.00 | | 1.00 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Satd. Flow (perm) | | 3574 | 2694 | | 3574 | 1583 | 1618 | 1618 | 1559 | | | |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 0 | 1168 | 1051 | 0 | 703 | 701 | 707 | 0 | 231 | 0 | 0 | 0 |
| RTOR Reduction (vph) | 0 | 0 | 388 | 0 | 0 | 262 | 0 | 0 | 28 | 0 | 0 | 0 |
| Lane Group Flow (vph) | 0 | 1168 | 663 | 0 | 703 | 439 | 353 | 354 | 203 | 0 | 0 | 0 |
| Confl. Peds. (#/hr) | | | 1 | 1 | | | 1 | | 2 | 2 | | 1 |
| Confl. Bikes (#/hr) | | 1 | | | 5 | | | | | 1 | | |
| Heavy Vehicles (%) | 0% | 1% | 3% | 0% | 1% | 2% | 6% | 20% | 2% | 0% | 0% | 0% |
| Turn Type | | Perm | | | Perm | | Split | | Perm | | | |
| Protected Phases | | 2 | | | 6 | | 8 | | 8 | | | |
| Permitted Phases | | 2 | | | 6 | | | | 8 | | | |
| Actuated Green, G (s) | | 72.0 | 72.0 | | 71.5 | 71.5 | 31.0 | 31.0 | 31.0 | | | |
| Effective Green, g (s) | | 72.5 | 72.5 | | 72.0 | 72.0 | 31.5 | 31.5 | 31.5 | | | |
| Actuated g/C Ratio | | 0.63 | 0.63 | | 0.63 | 0.63 | 0.27 | 0.27 | 0.27 | | | |
| Clearance Time (s) | | 6.0 | 6.0 | | 6.5 | 6.5 | 6.0 | 6.0 | 6.0 | | | |
| Vehicle Extension (s) | | 6.1 | 6.1 | | 4.2 | 4.2 | 2.3 | 2.3 | 2.3 | | | |
| Lane Grp Cap (vph) | | 2253 | 1698 | | 2238 | 991 | 443 | 443 | 427 | | | |
| v/s Ratio Prot | | c0.33 | | | 0.20 | | 0.22 | c0.22 | | | | |
| v/s Ratio Perm | | 0.25 | | | 0.28 | | | | 0.13 | | | |
| v/c Ratio | | 0.52 | 0.39 | | 0.31 | 0.44 | 0.80 | 0.80 | 0.47 | | | |
| Uniform Delay, d1 | | 11.7 | 10.4 | | 10.0 | 11.1 | 38.8 | 38.8 | 34.8 | | | |
| Progression Factor | | 1.39 | 3.10 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Incremental Delay, d2 | | 0.6 | 0.4 | | 0.4 | 1.4 | 9.2 | 9.3 | 0.5 | | | |
| Delay (s) | | 16.7 | 32.8 | | 10.4 | 12.6 | 48.0 | 48.1 | 35.3 | | | |
| Level of Service | | B | C | | B | B | D | D | D | | | |
| Approach Delay (s) | | 24.3 | | | 11.5 | | | 44.9 | | | 0.0 | |
| Approach LOS | | C | | | B | | | D | | | A | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | 24.6 | | | HCM Level of Service | | | | C | | | |
| HCM Volume to Capacity ratio | | 0.60 | | | | | | | | | | |
| Actuated Cycle Length (s) | | 115.0 | | | Sum of lost time (s) | | | | 11.0 | | | |
| Intersection Capacity Utilization | | 69.4% | | | ICU Level of Service | | | | C | | | |
| Analysis Period (min) | | 15 | | | | | | | | | | |

c Critical Lane Group

HCM Signalized Intersection Capacity Analysis
 14: Tualatin Sherwood Rd & Nyberg Woods

4/17/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|-------|------|-------|------|-------|----------------------|------|-------|------|------|------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 524 | 593 | 57 | 15 | 732 | 101 | 103 | 11 | 12 | 101 | 11 | 322 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 5.5 | 5.5 | | 5.5 | 5.5 | | | 5.5 | 5.5 | | 5.5 | 5.5 |
| Lane Util. Factor | 0.97 | 0.95 | | 1.00 | 0.95 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 0.99 | | 1.00 | 0.99 |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frt | 1.00 | 0.99 | | 1.00 | 0.98 | | | 1.00 | 0.85 | | 1.00 | 0.85 |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.96 | 1.00 | | 0.96 | 1.00 |
| Satd. Flow (prot) | 3502 | 3486 | | 1805 | 3505 | | | 1768 | 1593 | | 1799 | 1594 |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.66 | 1.00 | | 0.66 | 1.00 |
| Satd. Flow (perm) | 3502 | 3486 | | 1805 | 3505 | | | 1229 | 1593 | | 1248 | 1594 |
| Peak-hour factor, PHF | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 |
| Adj. Flow (vph) | 546 | 618 | 59 | 16 | 762 | 105 | 107 | 11 | 12 | 105 | 11 | 335 |
| RTOR Reduction (vph) | 0 | 5 | 0 | 0 | 9 | 0 | 0 | 0 | 10 | 0 | 0 | 279 |
| Lane Group Flow (vph) | 546 | 672 | 0 | 16 | 858 | 0 | 0 | 118 | 2 | 0 | 116 | 56 |
| Confl. Peds. (#/hr) | 8 | | 2 | 2 | | 8 | 1 | | 2 | 2 | | 1 |
| Confl. Bikes (#/hr) | | 1 | | | 3 | | | | | | | |
| Heavy Vehicles (%) | 0% | 2% | 2% | 0% | 1% | 0% | 3% | 0% | 0% | 1% | 0% | 0% |
| Turn Type | Prot | | Prot | | Perm | | Perm | | Perm | | Perm | |
| Protected Phases | 5 | 2 | | 1 | 6 | | | 8 | | | 4 | |
| Permitted Phases | | | | | | 8 | | 8 | | 4 | | 4 |
| Actuated Green, G (s) | 14.5 | 38.4 | | 0.8 | 24.7 | | | 10.9 | 10.9 | | 10.9 | 10.9 |
| Effective Green, g (s) | 15.0 | 38.9 | | 1.3 | 25.2 | | | 11.4 | 11.4 | | 11.4 | 11.4 |
| Actuated g/C Ratio | 0.22 | 0.57 | | 0.02 | 0.37 | | | 0.17 | 0.17 | | 0.17 | 0.17 |
| Clearance Time (s) | 6.0 | 6.0 | | 6.0 | 6.0 | | | 6.0 | 6.0 | | 6.0 | 6.0 |
| Vehicle Extension (s) | 2.3 | 2.5 | | 2.4 | 2.5 | | | 2.4 | 2.4 | | 2.3 | 2.3 |
| Lane Grp Cap (vph) | 771 | 1991 | | 34 | 1297 | | | 206 | 267 | | 209 | 267 |
| v/s Ratio Prot | c0.16 | 0.19 | | 0.01 | c0.24 | | | | | | | |
| v/s Ratio Perm | | | | | | | | c0.10 | 0.00 | | 0.09 | 0.04 |
| v/c Ratio | 0.71 | 0.34 | | 0.47 | 0.66 | | | 0.57 | 0.01 | | 0.56 | 0.21 |
| Uniform Delay, d1 | 24.5 | 7.8 | | 33.1 | 17.9 | | | 26.1 | 23.6 | | 26.0 | 24.5 |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Incremental Delay, d2 | 2.6 | 0.1 | | 6.6 | 1.2 | | | 3.0 | 0.0 | | 2.3 | 0.2 |
| Delay (s) | 27.2 | 7.8 | | 39.7 | 19.0 | | | 29.1 | 23.6 | | 28.3 | 24.7 |
| Level of Service | C | A | | D | B | | | C | C | | C | C |
| Approach Delay (s) | | 16.5 | | | 19.4 | | | 28.6 | | | 25.6 | |
| Approach LOS | | B | | | B | | | C | | | C | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 19.6 | | | HCM Level of Service | | | | B | | |
| HCM Volume to Capacity ratio | | | 0.66 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 68.1 | | | Sum of lost time (s) | | | 16.5 | | | |
| Intersection Capacity Utilization | | | 65.6% | | | ICU Level of Service | | | C | | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |

c Critical Lane Group

HCM Signalized Intersection Capacity Analysis
 17: Tualatin Sherwood Rd & Martinazzi Ave

4/17/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|------|-------|-------|------|-------|------|----------------------|-------|------|------|-------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 75 | 1194 | 141 | 0 | 1163 | 0 | 100 | 225 | 252 | 129 | 415 | 93 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 5.5 | | | 5.5 | | 4.5 | 5.5 | 5.5 | 4.5 | 5.5 | |
| Lane Util. Factor | 1.00 | 0.95 | | | 0.95 | | 1.00 | 1.00 | 1.00 | 1.00 | 0.95 | |
| Frbp, ped/bikes | 1.00 | 1.00 | | | 1.00 | | 1.00 | 1.00 | 0.96 | 1.00 | 1.00 | |
| Flpb, ped/bikes | 1.00 | 1.00 | | | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | |
| Frt | 1.00 | 0.98 | | | 1.00 | | 1.00 | 1.00 | 0.85 | 1.00 | 0.97 | |
| Flt Protected | 0.95 | 1.00 | | | 1.00 | | 0.95 | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (prot) | 1719 | 3430 | | | 3438 | | 1770 | 1863 | 1537 | 1787 | 3466 | |
| Flt Permitted | 0.95 | 1.00 | | | 1.00 | | 0.95 | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (perm) | 1719 | 3430 | | | 3438 | | 1770 | 1863 | 1537 | 1787 | 3466 | |
| Peak-hour factor, PHF | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 |
| Adj. Flow (vph) | 80 | 1270 | 150 | 0 | 1237 | 0 | 106 | 239 | 268 | 137 | 441 | 99 |
| RTOR Reduction (vph) | 0 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 104 | 0 | 19 | 0 |
| Lane Group Flow (vph) | 80 | 1414 | 0 | 0 | 1237 | 0 | 106 | 239 | 164 | 137 | 521 | 0 |
| Confl. Peds. (#/hr) | | | | | | 6 | | | 23 | | | 3 |
| Heavy Vehicles (%) | 5% | 4% | 0% | 0% | 5% | 0% | 2% | 2% | 1% | 1% | 1% | 1% |
| Turn Type | Prot | | | | | | Prot | | Perm | Prot | | |
| Protected Phases | 5 | 2 | | | 6 | | 3 | 8 | | 7 | 4 | |
| Permitted Phases | | | | | | | | | 8 | | | |
| Actuated Green, G (s) | 8.6 | 66.5 | | | 52.9 | | 10.6 | 17.9 | 17.9 | 13.6 | 20.9 | |
| Effective Green, g (s) | 9.1 | 67.0 | | | 53.4 | | 11.1 | 18.4 | 18.4 | 14.1 | 21.4 | |
| Actuated g/C Ratio | 0.08 | 0.58 | | | 0.46 | | 0.10 | 0.16 | 0.16 | 0.12 | 0.19 | |
| Clearance Time (s) | 5.0 | 6.0 | | | 6.0 | | 5.0 | 6.0 | 6.0 | 5.0 | 6.0 | |
| Vehicle Extension (s) | 2.0 | 3.5 | | | 3.5 | | 3.0 | 2.0 | 2.0 | 3.0 | 2.0 | |
| Lane Grp Cap (vph) | 136 | 1998 | | | 1596 | | 171 | 298 | 246 | 219 | 645 | |
| v/s Ratio Prot | 0.05 | c0.41 | | | c0.36 | | 0.06 | c0.13 | | 0.08 | c0.15 | |
| v/s Ratio Perm | | | | | | | | | 0.11 | | | |
| v/c Ratio | 0.59 | 0.71 | | | 0.78 | | 0.62 | 0.80 | 0.67 | 0.63 | 0.81 | |
| Uniform Delay, d1 | 51.1 | 17.0 | | | 25.8 | | 49.9 | 46.5 | 45.4 | 47.9 | 44.8 | |
| Progression Factor | 1.00 | 1.00 | | | 0.56 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | |
| Incremental Delay, d2 | 4.1 | 2.1 | | | 3.0 | | 6.5 | 13.6 | 5.2 | 5.5 | 7.0 | |
| Delay (s) | 55.3 | 19.2 | | | 17.5 | | 56.5 | 60.1 | 50.6 | 53.4 | 51.8 | |
| Level of Service | E | B | | | B | | E | E | D | D | D | |
| Approach Delay (s) | | 21.1 | | | 17.5 | | | 55.3 | | | 52.1 | |
| Approach LOS | | C | | | B | | | E | | | D | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 30.4 | | | | HCM Level of Service | | | C | | |
| HCM Volume to Capacity ratio | | | 0.83 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 115.0 | | | | Sum of lost time (s) | | 22.0 | | | |
| Intersection Capacity Utilization | | | 81.1% | | | | ICU Level of Service | | D | | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

SIGNALIZED QUEUE ANALYSIS

Project Name: Nyberg Rivers
Project Number: 12116
Analyst: CLB
Date: 4/16/2013
Filename: C:\Users\mrvandehey\Documents\SIGNALIZED Queue FM Driveway2.xls\SIGQUE



KITTELSON & ASSOCIATES, INC.
 610 SW Alder, Suite 700
 Portland, Oregon 97205
 (503) 228-5230
 Fax: (503) 273-8169

Intersection: Fred Meyer Access/Nyberg Road
Conditions (yr, alt., etc.): Weekday

GENERAL INPUT PARAMETERS:

| | |
|--------------------------|---------|
| Cycle Length: | 125 sec |
| Confidence Level (C.L.): | 95% |
| Storage length/vehicle: | 25 feet |

| | APPROACH/MOVEMENT | | | | | | | |
|-------------------------------|-------------------|----------|----------|----------|----------|----------|----|----|
| | #1 | #2 | #3 | #4 | #5 | #6 | #7 | #8 |
| | EB LT EX | EB LT BK | EB LT WS | EX SB LT | BK SB LT | WS SB LT | | |
| INPUT PARAMETERS: | | | | | | | | |
| Volume (pre-PHF) (vph): | 30 | 30 | 100 | 182 | 182 | 323 | | |
| G/C for movement: | 0.05 | 0.05 | 0.12 | 0.18 | 0.18 | 0.14 | | |
| Number of lanes: | 1 | 1 | 1 | 1 | 1 | 2 | 2 | 2 |
| CALCULATIONS: | | | | | | | | |
| Length of red interval (sec): | 118.8 | 118.8 | 110.0 | 102.5 | 102.5 | 107.5 | | |
| Average total queue (veh): | 1.0 | 1.0 | 3.1 | 5.2 | 5.2 | 9.6 | | |
| Maximum total queue (veh): | 3 | 3 | 6 | 9 | 9 | 15 | | |
| Total queue length (feet): | 75 | 75 | 150 | 225 | 225 | 375 | | |
| Required storage/lane (feet): | 75 | 75 | 150 | 225 | 225 | 200 | | |
| PERMITTED LEFT TURNS: | | | | | | | | |
| Opposing volume (pre-PHF): | | | | | | | | |
| Opposing sat. flow rate: | | | | | | | | |
| CALCULATIONS: | | | | | | | | |
| Opposing flow ratio (Yo): | | | | | | | | |
| Unblocked G/C: | | | | | | | | |
| Effective red interval (sec): | | | | | | | | |
| Average total queue (veh): | | | | | | | | |
| Maximum total queue (veh): | | | | | | | | |
| Total queue length (feet): | | | | | | | | |
| Required storage/lane (feet): | | | | | | | | |

METHODOLOGY AND FORMULAS USED:

Length of red interval = (1 - G/C) * Cycle length

Queue length = Maximum queue * Storage length per vehicle

Average queue/lane = Volume * Red Interval / 3600

Required storage per lane = Queue length / Number of lanes, rounded up to the next highest whole vehicle

Maximum queue: Random arrival/Constant service

Opposing flow ratio Yo = opposing volume vo / opposing sat. flow rate sop

Random arrivals behave according to a Poisson distribution. There is a probability equal to the confidence level desired (e.g. 95%) that the queue formed during each red interval will be less than or equal to the maximum queue.

Unblocked G/C (gu/C) = (g/C - Yo)/(1-Yo)

(Prob. of arrivals = N) = (Red Interval)^N * exp(-N) / N! (the Poisson distribution)

(Prob. of arrivals >= N) = 1 - Sum of probabilities for vehicles 0, 1, ..., N-1

Max N: Highest N such that the sum of probabilities > (1 - confidence level)

SIGNALIZED QUEUE ANALYSIS

Project Name: Nyberg Rivers
Project Number: 12116
Analyst: CLB
Date: 4/16/2013
Filename: C:\Users\mvandehey\AppData\Local\Microsoft\Windows\Temporary Internet Files\Content.IE5\...



KITTELSON & ASSOCIATES, INC.
 610 SW Alder, Suite 700
 Portland, Oregon 97205
 (503) 228-5230
 Fax: (503) 273-8169

Intersection: Fred Meyer Access/Nyberg Road
Conditions (yr, alt., etc.):

GENERAL INPUT PARAMETERS:

| | |
|--------------------------|---------|
| Cycle Length: | 125 sec |
| Confidence Level (C.L.): | 95% |
| Storage length/vehicle: | 25 feet |

| | APPROACH/MOVEMENT | | | | | | | |
|-------------------------------|-------------------|----------|----------|-----------|----------|----------|----------|----------|
| | #1 | #2 | #3 | #4 | #5 | #6 | #7 | #8 |
| | NB RT EX P | NB RT BK | NB RT WS | NB 2RT WS | EX WB LT | WB LT EX | WB LT BK | WB LT WS |
| INPUT PARAMETERS: | | | | | | | | |
| Volume (pre-PHF) (vph): | 236 | 236 | 236 | 236 | 232 | 232 | 232 | 232 |
| G/C for movement: | 0.28 | 0.28 | 0.21 | 0.17 | 0.10 | 0.10 | 0.10 | 0.13 |
| Number of lanes: | 1 | 1 | 1 | 2 | 2 | 2 | 2 | 2 |
| CALCULATIONS: | | | | | | | | |
| Length of red interval (sec): | 90.0 | 90.0 | 98.8 | 103.8 | 112.5 | 112.5 | 112.5 | 108.8 |
| Average total queue (veh): | 5.9 | 5.9 | 6.5 | 6.8 | 7.3 | 7.3 | 7.3 | 7.0 |
| Maximum total queue (veh): | 10 | 10 | 11 | 11 | 12 | 12 | 12 | 12 |
| Total queue length (feet): | 250 | 250 | 275 | 275 | 300 | 300 | 300 | 300 |
| Required storage/lane (feet): | 250 | 250 | 275 | 150 | 150 | 150 | 150 | 150 |
| PERMITTED LEFT TURNS: | | | | | | | | |
| Opposing volume (pre-PHF): | | | | | | | | |
| Opposing sat. flow rate: | | | | | | | | |
| CALCULATIONS: | | | | | | | | |
| Opposing flow ratio (Yo): | | | | | | | | |
| Unblocked G/C: | | | | | | | | |
| Effective red interval (sec): | | | | | | | | |
| Average total queue (veh): | | | | | | | | |
| Maximum total queue (veh): | | | | | | | | |
| Total queue length (feet): | | | | | | | | |
| Required storage/lane (feet): | | | | | | | | |

METHODOLOGY AND FORMULAS USED:

Length of red interval = $(1 - G/C) \cdot \text{Cycle length}$

Queue length = Maximum queue * Storage length per vehicle

Average queue/lane = Volume * Red Interval / 3600

Required storage per lane = Queue length / Number of lanes, rounded up to the next highest whole vehicle.

Maximum queue: Random arrival/Constant service
 Random arrivals behave according to a Poisson distribution.
 There is a probability equal to the confidence level desired (e.g. 95%)
 that the queue formed during each red interval will be less than
 or equal to the maximum queue.

Opposing flow ratio $Y_o = \text{opposing volume } v_o / \text{opposing sat. flow rate } s_o$

Unblocked G/C $(g_u/C) = (g/C - Y_o)/(1 - Y_o)$

(Prob. of arrivals = N) = $(\text{Red Interval})^N \cdot \exp(-N) / N!$ (the Poisson distribution)

(Prob. of arrivals $\geq N$) = $1 - \text{Sum of probabilities for vehicles } 0, 1, \dots, N-1$

Max N: Highest N such that the sum of probabilities > (1 - confidence level)

SIGNALIZED QUEUE ANALYSIS

Project Name: Nyberg Rivers
Project Number: 12116
Analyst: CLB
Date: 4/17/2013
Filename: C:\Users\mvandehey\Documents\Signalized Queue FM Driveway saturday2.xls



KITTELSON & ASSOCIATES, INC.
 610 SW Alder, Suite 700
 Portland, Oregon 97205
 (503) 228-5230
 Fax: (503) 273-8169

Intersection: Fred Meyer Access/Nyberg Road
Conditions (yr, alt., etc.): Saturday

GENERAL INPUT PARAMETERS:

| | |
|--------------------------|---------|
| Cycle Length: | 115 sec |
| Confidence Level (C.L.): | 95% |
| Storage length/vehicle: | 25 feet |

| | APPROACH/MOVEMENT | | | | | | |
|-------------------------------|-------------------|----------|----------|----|----------|----------|----------|
| | #1 | #2 | #3 | #4 | #5 | #6 | #7 |
| | EX EB LT | BK EB LT | WS EB LT | | EX SB LT | BK SB LT | WS SB LT |
| INPUT PARAMETERS: | | | | | | | |
| Volume (pre-PHF) (vph): | 50 | 50 | 180 | | 154 | 154 | 373 |
| G/C for movement: | 0.06 | 0.07 | 0.13 | | 0.18 | 0.18 | 0.16 |
| Number of lanes: | 1 | 1 | 1 | | 2 | 2 | 2 |
| CALCULATIONS: | | | | | | | |
| Length of red interval (sec): | 108.1 | 107.0 | 100.1 | | 94.3 | 94.3 | 96.6 |
| Average total queue (veh): | 1.5 | 1.5 | 5.0 | | 4.0 | 4.0 | 10.0 |
| Maximum total queue (veh): | 4 | 4 | 9 | | 8 | 8 | 15 |
| Total queue length (feet): | 100 | 100 | 225 | | 200 | 200 | 375 |
| Required storage/lane (feet): | 100 | 100 | 225 | | 100 | 100 | 200 |
| PERMITTED LEFT TURNS: | | | | | | | |
| Opposing volume (pre-PHF): | | | | | | | |
| Opposing sat. flow rate: | | | | | | | |
| CALCULATIONS: | | | | | | | |
| Opposing flow ratio (Yo): | | | | | | | |
| Unblocked G/C: | | | | | | | |
| Effective red interval (sec): | | | | | | | |
| Average total queue (veh): | | | | | | | |
| Maximum total queue (veh): | | | | | | | |
| Total queue length (feet): | | | | | | | |
| Required storage/lane (feet): | | | | | | | |

METHODOLOGY AND FORMULAS USED:

Length of red interval = (1 - G/C) * Cycle length

Average queue/lane = Volume * Red Interval / 3600

Maximum queue: Random arrival/Constant service

Random arrivals behave according to a Poisson distribution.

There is a probability equal to the confidence level desired (e.g. 95%)

that the queue formed during each red interval will be less than

or equal to the maximum queue.

(Prob. of arrivals = N) = (Red Interval)^N * exp(-N) / N! (the Poisson distribution)

(Prob. of arrivals >= N) = 1 - Sum of probabilities for vehicles 0, 1, ..., N-1

Max N: Highest N such that the sum of probabilities > (1 - confidence level)

Queue length = Maximum queue * Storage length per vehicle

Required storage per lane = Queue length / Number of lanes, rounded up to the next highest whole vehicle

Opposing flow ratio Yo = opposing volume vo / opposing sat. flow rate sop

Unblocked G/C (gu/C) = (g/C - Yo)/(1-Yo)

SIGNALIZED QUEUE ANALYSIS

Project Name: Nyberg Rivers
Project Number: 12116
Analyst: CLB
Date: 4/17/2013
Filename: C:\Users\mvandehey\Documents\SIGNALIZED Queue FM Driveway saturday2.xls



KITTELSON & ASSOCIATES, INC.
 610 SW Alder, Suite 700
 Portland, Oregon 97205
 (503) 228-5230
 Fax: (503) 273-8169

Intersection: Fred Meyer Access/Nyberg Road
Conditions (yr, alt., etc.): Saturday

GENERAL INPUT PARAMETERS:

| | |
|--------------------------|---------|
| Cycle Length: | 115 sec |
| Confidence Level (C.L.): | 95% |
| Storage length/vehicle: | 25 feet |

| | APPROACH/MOVEMENT | | | | | | |
|-------------------------------|-------------------|----------|----------|----|----------|----------|----------|
| | #1 | #2 | #3 | #4 | #5 | #6 | #7 |
| | NB RT EX P | NB RT BK | NB RT WS | | EX WB LT | WB LT EX | WB LT BK |
| INPUT PARAMETERS: | | | | | | | |
| Volume (pre-PHF) (vph): | 248 | 248 | 248 | | 257 | 257 | 257 |
| G/C for movement: | 0.29 | 0.29 | 0.23 | | 0.11 | 0.11 | 0.15 |
| Number of lanes: | 1 | 1 | 1 | | 2 | 2 | 2 |
| CALCULATIONS: | | | | | | | |
| Length of red interval (sec): | 81.7 | 81.7 | 88.6 | | 102.4 | 102.4 | 97.8 |
| Average total queue (veh): | 5.6 | 5.6 | 6.1 | | 7.3 | 7.3 | 7.0 |
| Maximum total queue (veh): | 10 | 10 | 10 | | 12 | 12 | 12 |
| Total queue length (feet): | 250 | 250 | 250 | | 300 | 300 | 300 |
| Required storage/lane (feet): | 250 | 250 | 250 | | 150 | 150 | 150 |
| PERMITTED LEFT TURNS: | | | | | | | |
| Opposing volume (pre-PHF): | | | | | | | |
| Opposing sat. flow rate: | | | | | | | |
| CALCULATIONS: | | | | | | | |
| Opposing flow ratio (Yo): | | | | | | | |
| Unblocked G/C: | | | | | | | |
| Effective red interval (sec): | | | | | | | |
| Average total queue (veh): | | | | | | | |
| Maximum total queue (veh): | | | | | | | |
| Total queue length (feet): | | | | | | | |
| Required storage/lane (feet): | | | | | | | |

METHODOLOGY AND FORMULAS USED:

Length of red interval = (1 - G/C) * Cycle length

Queue length = Maximum queue * Storage length per vehicle

Average queue/lane = Volume * Red Interval / 3600

Required storage per lane = Queue length / Number of lanes, rounded up to the next highest whole vehicle

Maximum queue: Random arrival/Constant service
 Random arrivals behave according to a Poisson distribution.
 There is a probability equal to the confidence level desired (e.g. 95%)
 that the queue formed during each red interval will be less than
 or equal to the maximum queue.

Opposing flow ratio Yo = opposing volume vo / opposing sat. flow rate sop

Unblocked G/C (gu/C) = (g/C - Yo)/(1-Yo)

(Prob. of arrivals = N) = (Red Interval)*N * exp(-N) / N! (the Poisson distribution)
 (Prob. of arrivals >= N) = 1 - Sum of probabilities for vehicles 0, 1, ..., N-1
 Max N: Highest N such that the sum of probabilities > (1 - confidence level)

Intersection: 12: Tualatin Sherwood Rd & I-5 SB Ramps

| Movement | EB | EB | EB | EB | WB | WB | WB | SB | SB | SB | SB |
|-----------------------|-----|-----|-----|-----|-----|-----|-----|-----|------|------|-----|
| Directions Served | T | T | T | R | L | T | T | L | LT | R | R |
| Maximum Queue (ft) | 445 | 482 | 482 | 299 | 653 | 651 | 680 | 274 | 654 | 570 | 440 |
| Average Queue (ft) | 193 | 214 | 224 | 43 | 275 | 371 | 393 | 196 | 348 | 281 | 203 |
| 95th Queue (ft) | 342 | 374 | 385 | 164 | 614 | 671 | 659 | 296 | 631 | 476 | 355 |
| Link Distance (ft) | 522 | 522 | 522 | 522 | 616 | 616 | 616 | | 1139 | 1139 | |
| Upstream Blk Time (%) | 0 | 0 | 0 | | 4 | 3 | 2 | | | | |
| Queuing Penalty (veh) | 0 | 1 | 1 | | 19 | 12 | 11 | | | | |
| Storage Bay Dist (ft) | | | | | | | | 200 | | | 700 |
| Storage Blk Time (%) | | | | | | | | 7 | 25 | 0 | |
| Queuing Penalty (veh) | | | | | | | | 23 | 79 | 0 | |

Queuing and Blocking Report
 2014 Total Saturday Mid-Day Peak

4/17/2013

Intersection: 13: Tualatin Sherwood Rd & I-5 NB Ramps

| Movement | EB | EB | EB | WB | WB | WB | NB | NB | NB |
|-----------------------|-----|-----|-----|-----|-----|-----|-----|------|-----|
| Directions Served | T | T | R | T | T | R | L | LT | R |
| Maximum Queue (ft) | 616 | 590 | 356 | 335 | 450 | 225 | 374 | 924 | 300 |
| Average Queue (ft) | 383 | 352 | 16 | 124 | 165 | 49 | 214 | 332 | 136 |
| 95th Queue (ft) | 610 | 578 | 161 | 251 | 323 | 201 | 354 | 675 | 287 |
| Link Distance (ft) | 616 | 616 | 616 | 459 | 459 | | | 1328 | |
| Upstream Blk Time (%) | 0 | 0 | 0 | 0 | 0 | | | | |
| Queuing Penalty (veh) | 1 | 1 | 0 | 0 | 1 | | | | |
| Storage Bay Dist (ft) | | | | | | 150 | 300 | | 225 |
| Storage Blk Time (%) | | | | | 10 | 0 | 1 | 16 | 0 |
| Queuing Penalty (veh) | | | | | 64 | 0 | 6 | 90 | 1 |

Appendix G
Year 2014 Operations
Worksheets (for Alternative
Access Scenario)

HCM Signalized Intersection Capacity Analysis

1: Lower Boones Ferry Road & SW Upper Boones Ferry Road

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|-------|-------|-------|-------|------|----------------------|------|------|-------|------|-------|------|
| Lane Configurations | | ↕ | | ↕ | ↕ | | ↕ | ↕ | ↕ | ↕ | ↕ | ↕ |
| Volume (vph) | 1 | 7 | 9 | 479 | 7 | 40 | 0 | 504 | 567 | 59 | 697 | 1 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | | 3.5 | | 3.5 | 3.5 | | | 4.0 | 3.5 | 3.5 | 4.0 | |
| Lane Util. Factor | | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | |
| Frbp, ped/bikes | | 0.92 | | 1.00 | 0.95 | | | 1.00 | 0.98 | 1.00 | 1.00 | |
| Flpb, ped/bikes | | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | |
| Frt | | 0.93 | | 1.00 | 0.87 | | | 1.00 | 0.85 | 1.00 | 1.00 | |
| Flt Protected | | 1.00 | | 0.95 | 1.00 | | | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (prot) | | 1596 | | 1787 | 1574 | | | 1900 | 1570 | 1805 | 1900 | |
| Flt Permitted | | 1.00 | | 0.95 | 1.00 | | | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (perm) | | 1596 | | 1787 | 1574 | | | 1900 | 1570 | 1805 | 1900 | |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 1 | 7 | 9 | 504 | 7 | 42 | 0 | 531 | 597 | 62 | 734 | 1 |
| RTOR Reduction (vph) | 0 | 9 | 0 | 0 | 26 | 0 | 0 | 0 | 158 | 0 | 0 | 0 |
| Lane Group Flow (vph) | 0 | 8 | 0 | 504 | 23 | 0 | 0 | 531 | 439 | 62 | 735 | 0 |
| Confl. Peds. (#/hr) | 15 | | 7 | 7 | | 15 | 7 | | 8 | 8 | | 7 |
| Heavy Vehicles (%) | 0% | 2% | 1% | 1% | 3% | 0% | 2% | 0% | 1% | 0% | 0% | 0% |
| Turn Type | Split | | | Split | | | Prot | | pm+ov | | Prot | |
| Protected Phases | 8 | 8 | | 4 | 4 | | 1 | 6 | 4 | 5 | 2 | |
| Permitted Phases | | | | | | | | | 6 | | | |
| Actuated Green, G (s) | | 1.7 | | 31.9 | 31.9 | | | 29.5 | 61.4 | 5.3 | 38.8 | |
| Effective Green, g (s) | | 2.2 | | 32.4 | 32.4 | | | 30.0 | 62.4 | 5.8 | 39.3 | |
| Actuated g/C Ratio | | 0.03 | | 0.38 | 0.38 | | | 0.35 | 0.73 | 0.07 | 0.46 | |
| Clearance Time (s) | | 4.0 | | 4.0 | 4.0 | | | 4.5 | 4.0 | 4.0 | 4.5 | |
| Vehicle Extension (s) | | 2.5 | | 2.2 | 2.2 | | | 3.5 | 2.2 | 2.2 | 3.5 | |
| Lane Grp Cap (vph) | | 41 | | 682 | 601 | | | 671 | 1154 | 123 | 880 | |
| v/s Ratio Prot | | c0.01 | | c0.28 | 0.01 | | | 0.28 | 0.15 | 0.03 | c0.39 | |
| v/s Ratio Perm | | | | | | | | | 0.13 | | | |
| v/c Ratio | | 0.20 | | 0.74 | 0.04 | | | 0.79 | 0.38 | 0.50 | 0.84 | |
| Uniform Delay, d1 | | 40.5 | | 22.6 | 16.5 | | | 24.6 | 4.1 | 38.2 | 20.0 | |
| Progression Factor | | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | |
| Incremental Delay, d2 | | 1.8 | | 3.8 | 0.0 | | | 6.5 | 0.1 | 1.7 | 7.1 | |
| Delay (s) | | 42.2 | | 26.4 | 16.5 | | | 31.2 | 4.2 | 39.8 | 27.0 | |
| Level of Service | | D | | C | B | | | C | A | D | C | |
| Approach Delay (s) | | 42.2 | | | 25.5 | | | 16.9 | | | 28.0 | |
| Approach LOS | | D | | | C | | | B | | | C | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 22.5 | | | HCM Level of Service | | | | C | | |
| HCM Volume to Capacity ratio | | | 0.77 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 84.9 | | | Sum of lost time (s) | | | 11.0 | | | |
| Intersection Capacity Utilization | | | 83.3% | | | ICU Level of Service | | | | E | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 2: SW Boones Ferry Rd & SW Tualatin Rd

4/15/2013

| Movement | WBL | WBR | NBT | NBR | SBL | SBT |
|-----------------------------------|------|-------|-------|-------|----------------------|------|
| Lane Configurations | | | | | | |
| Volume (vph) | 410 | 844 | 200 | 298 | 453 | 365 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 3.5 | 3.5 | 3.0 | 3.5 | 3.5 | 3.5 |
| Lane Util. Factor | 0.97 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Frbp, ped/bikes | 1.00 | 0.98 | 1.00 | 0.98 | 1.00 | 1.00 |
| Flpb, ped/bikes | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Frt | 1.00 | 0.85 | 1.00 | 0.85 | 1.00 | 1.00 |
| Flt Protected | 0.95 | 1.00 | 1.00 | 1.00 | 0.95 | 1.00 |
| Satd. Flow (prot) | 3467 | 1590 | 1900 | 1574 | 1805 | 1900 |
| Flt Permitted | 0.95 | 1.00 | 1.00 | 1.00 | 0.95 | 1.00 |
| Satd. Flow (perm) | 3467 | 1590 | 1900 | 1574 | 1805 | 1900 |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 432 | 888 | 211 | 314 | 477 | 384 |
| RTOR Reduction (vph) | 0 | 182 | 0 | 75 | 0 | 0 |
| Lane Group Flow (vph) | 432 | 706 | 211 | 239 | 477 | 384 |
| Confl. Peds. (#/hr) | 7 | 15 | | 8 | 8 | |
| Heavy Vehicles (%) | 1% | 0% | 0% | 1% | 0% | 0% |
| Turn Type | | pm+ov | | pm+ov | Prot | |
| Protected Phases | 8 | 1 | 2 | 8 | 1 | 6 |
| Permitted Phases | | 8 | | 2 | | |
| Actuated Green, G (s) | 11.4 | 32.2 | 10.7 | 22.1 | 20.8 | 35.0 |
| Effective Green, g (s) | 11.9 | 33.2 | 11.2 | 23.1 | 21.3 | 35.5 |
| Actuated g/C Ratio | 0.22 | 0.61 | 0.21 | 0.42 | 0.39 | 0.65 |
| Clearance Time (s) | 4.0 | 4.0 | 3.5 | 4.0 | 4.0 | 4.0 |
| Vehicle Extension (s) | 3.0 | 2.0 | 5.0 | 3.0 | 2.0 | 2.0 |
| Lane Grp Cap (vph) | 758 | 1073 | 391 | 668 | 707 | 1240 |
| v/s Ratio Prot | 0.12 | c0.26 | c0.11 | 0.08 | 0.26 | 0.20 |
| v/s Ratio Perm | | 0.19 | | 0.07 | | |
| v/c Ratio | 0.57 | 0.66 | 0.54 | 0.36 | 0.67 | 0.31 |
| Uniform Delay, d1 | 19.0 | 6.9 | 19.3 | 10.6 | 13.7 | 4.1 |
| Progression Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Incremental Delay, d2 | 1.0 | 1.1 | 2.6 | 0.3 | 2.0 | 0.1 |
| Delay (s) | 20.0 | 8.0 | 21.9 | 10.9 | 15.7 | 4.2 |
| Level of Service | B | A | C | B | B | A |
| Approach Delay (s) | 11.9 | | 15.4 | | | 10.6 |
| Approach LOS | B | | B | | | B |
| Intersection Summary | | | | | | |
| HCM Average Control Delay | | | 12.2 | | HCM Level of Service | B |
| HCM Volume to Capacity ratio | | | 0.63 | | | |
| Actuated Cycle Length (s) | | | 54.4 | | Sum of lost time (s) | 6.5 |
| Intersection Capacity Utilization | | | 72.2% | | ICU Level of Service | C |
| Analysis Period (min) | | | 15 | | | |
| c Critical Lane Group | | | | | | |





















HCM Signalized Intersection Capacity Analysis
 3: SW Boones Fe & SW Martinazzi Ave

4/15/2013

| | → | ↘ | ↙ | ← | ↖ | ↗ |
|-----------------------------------|-------|-------|-------|----------------------|-------|------|
| Movement | EBT | EBR | WBL | WBT | NBL | NBR |
| Lane Configurations | ↑ | ↗ | ↘ | ↑ | ↘ | ↗ |
| Volume (vph) | 674 | 175 | 453 | 930 | 335 | 385 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 4.5 | 4.5 | 4.5 | 4.5 | 4.5 |
| Lane Util. Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Frbp, ped/bikes | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 0.98 |
| Flpb, ped/bikes | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Frt | 1.00 | 0.85 | 1.00 | 1.00 | 1.00 | 0.85 |
| Flt Protected | 1.00 | 1.00 | 0.95 | 1.00 | 0.95 | 1.00 |
| Satd. Flow (prot) | 1863 | 1599 | 1787 | 1845 | 1770 | 1571 |
| Flt Permitted | 1.00 | 1.00 | 0.95 | 1.00 | 0.95 | 1.00 |
| Satd. Flow (perm) | 1863 | 1599 | 1787 | 1845 | 1770 | 1571 |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 709 | 184 | 477 | 979 | 353 | 405 |
| RTOR Reduction (vph) | 0 | 61 | 0 | 0 | 0 | 34 |
| Lane Group Flow (vph) | 709 | 123 | 477 | 979 | 353 | 371 |
| Confl. Peds. (#/hr) | | 7 | 7 | | 7 | 8 |
| Heavy Vehicles (%) | 2% | 1% | 1% | 3% | 2% | 1% |
| Turn Type | | Prot | Prot | | pm+ov | |
| Protected Phases | 2 | 2 | 1 | 6 | 8 | 1 |
| Permitted Phases | | | | | 8 | 8 |
| Actuated Green, G (s) | 42.2 | 42.2 | 33.1 | 80.3 | 24.1 | 57.2 |
| Effective Green, g (s) | 42.7 | 42.7 | 33.6 | 80.8 | 24.6 | 58.2 |
| Actuated g/C Ratio | 0.37 | 0.37 | 0.29 | 0.71 | 0.22 | 0.51 |
| Clearance Time (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 |
| Lane Grp Cap (vph) | 695 | 597 | 525 | 1303 | 381 | 861 |
| v/s Ratio Prot | c0.38 | 0.08 | c0.27 | 0.53 | c0.20 | 0.13 |
| v/s Ratio Perm | | | | | | 0.11 |
| v/c Ratio | 1.02 | 0.21 | 0.91 | 0.75 | 0.93 | 0.43 |
| Uniform Delay, d1 | 35.9 | 24.3 | 38.9 | 10.5 | 44.0 | 17.7 |
| Progression Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Incremental Delay, d2 | 39.3 | 0.2 | 19.4 | 2.5 | 28.1 | 0.3 |
| Delay (s) | 75.2 | 24.5 | 58.4 | 13.0 | 72.1 | 18.0 |
| Level of Service | E | C | E | B | E | B |
| Approach Delay (s) | 64.7 | | | 27.9 | 43.2 | |
| Approach LOS | E | | | C | D | |
| Intersection Summary | | | | | | |
| HCM Average Control Delay | | 42.2 | | HCM Level of Service | | D |
| HCM Volume to Capacity ratio | | 0.96 | | | | |
| Actuated Cycle Length (s) | | 114.4 | | Sum of lost time (s) | | 13.5 |
| Intersection Capacity Utilization | | 90.4% | | ICU Level of Service | | E |
| Analysis Period (min) | | 15 | | | | |
| c Critical Lane Group | | | | | | |

HCM Signalized Intersection Capacity Analysis
5: Seneca St & Martinazzi Ave

4/15/2013

| |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations |  |  | | |  |  |  |  | |  |  | |
| Volume (vph) | 40 | 0 | 80 | 53 | 0 | 163 | 85 | 516 | 99 | 202 | 376 | 50 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 3.5 | 3.5 | | | 3.5 | 3.5 | 3.5 | 3.5 | | 3.5 | 3.5 | |
| Lane Util. Factor | 1.00 | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Frbp, ped/bikes | 1.00 | 0.97 | | | 1.00 | 0.97 | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Flpb, ped/bikes | 0.96 | 1.00 | | | 0.99 | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Frt | 1.00 | 0.85 | | | 1.00 | 0.85 | 1.00 | 0.98 | | 1.00 | 0.98 | |
| Flt Protected | 0.95 | 1.00 | | | 0.95 | 1.00 | 0.95 | 1.00 | | 0.95 | 1.00 | |
| Satd. Flow (prot) | 1739 | 1573 | | | 1747 | 1540 | 1802 | 1825 | | 1769 | 1828 | |
| Flt Permitted | 0.72 | 1.00 | | | 0.70 | 1.00 | 0.47 | 1.00 | | 0.20 | 1.00 | |
| Satd. Flow (perm) | 1317 | 1573 | | | 1287 | 1540 | 895 | 1825 | | 370 | 1828 | |
| Peak-hour factor, PHF | 0.91 | 0.92 | 0.91 | 0.92 | 0.92 | 0.92 | 0.91 | 0.91 | 0.92 | 0.92 | 0.91 | 0.91 |
| Adj. Flow (vph) | 44 | 0 | 88 | 58 | 0 | 177 | 93 | 567 | 108 | 220 | 413 | 55 |
| RTOR Reduction (vph) | 0 | 76 | 0 | 0 | 0 | 127 | 0 | 9 | 0 | 0 | 6 | 0 |
| Lane Group Flow (vph) | 44 | 12 | 0 | 0 | 58 | 50 | 93 | 667 | 0 | 220 | 462 | 0 |
| Confl. Peds. (#/hr) | 26 | | 16 | 16 | | 26 | 5 | | 5 | 5 | | 5 |
| Heavy Vehicles (%) | 0% | 2% | 0% | 2% | 2% | 2% | 0% | 1% | 2% | 2% | 2% | 0% |
| Turn Type | Perm | | | Perm | | pm+ov | pm+pt | | | | pm+pt | |
| Protected Phases | | 4 | | | 8 | 1 | 5 | 2 | | 1 | 6 | |
| Permitted Phases | 4 | | | 8 | | 8 | 2 | | | 6 | | |
| Actuated Green, G (s) | 5.9 | 5.9 | | | 5.9 | 12.8 | 27.8 | 23.8 | | 33.6 | 26.7 | |
| Effective Green, g (s) | 6.4 | 6.4 | | | 6.4 | 13.8 | 28.8 | 24.3 | | 34.6 | 27.2 | |
| Actuated g/C Ratio | 0.13 | 0.13 | | | 0.13 | 0.28 | 0.59 | 0.50 | | 0.71 | 0.56 | |
| Clearance Time (s) | 4.0 | 4.0 | | | 4.0 | 4.0 | 4.0 | 4.0 | | 4.0 | 4.0 | |
| Vehicle Extension (s) | 3.0 | 3.0 | | | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 | 3.0 | |
| Lane Grp Cap (vph) | 173 | 207 | | | 169 | 548 | 614 | 913 | | 476 | 1023 | |
| v/s Ratio Prot | | 0.01 | | | | 0.01 | 0.01 | c0.37 | | c0.07 | 0.25 | |
| v/s Ratio Perm | 0.03 | | | c0.05 | 0.02 | 0.08 | | | | 0.26 | | |
| v/c Ratio | 0.25 | 0.06 | | 0.34 | 0.09 | 0.15 | 0.73 | | | 0.46 | 0.45 | |
| Uniform Delay, d1 | 19.0 | 18.5 | | | 19.2 | 12.8 | 4.3 | 9.6 | | 5.1 | 6.3 | |
| Progression Factor | 1.00 | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Incremental Delay, d2 | 0.8 | 0.1 | | | 1.2 | 0.1 | 0.1 | 3.0 | | 0.7 | 0.3 | |
| Delay (s) | 19.7 | 18.6 | | | 20.4 | 12.9 | 4.4 | 12.6 | | 5.8 | 6.6 | |
| Level of Service | B | B | | | C | B | A | B | | A | A | |
| Approach Delay (s) | | 19.0 | | | 14.7 | | | 11.6 | | | 6.4 | |
| Approach LOS | | B | | | B | | | B | | | A | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | 10.6 | | | | | | | | | | |
| HCM Volume to Capacity ratio | | 0.68 | | | | | | | | | | |
| Actuated Cycle Length (s) | | 48.6 | | | | | | | 14.0 | | | |
| Intersection Capacity Utilization | | 66.2% | | | | | | | | | | |
| Analysis Period (min) | | 15 | | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 8: Nyberg St & Martinazzi Ave

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|-------|------|-------|-------|-------|----------------------|------|-------|------|------|------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 29 | 10 | 100 | 357 | 55 | 337 | 27 | 315 | 26 | 0 | 499 | 10 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.0 | 4.0 | | 4.0 | 4.0 | 4.0 | 4.0 | 4.0 | | | 4.0 | |
| Lane Util. Factor | 1.00 | 1.00 | | 0.95 | 0.95 | 1.00 | 1.00 | 1.00 | | | 0.95 | |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 0.97 | 1.00 | 1.00 | | | 1.00 | |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | 1.00 | |
| Frt | 1.00 | 0.86 | | 1.00 | 1.00 | 0.85 | 1.00 | 0.99 | | | 1.00 | |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 0.96 | 1.00 | 0.95 | 1.00 | | | 1.00 | |
| Satd. Flow (prot) | 1805 | 1626 | | 1698 | 1728 | 1533 | 1682 | 1855 | | | 3563 | |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 0.96 | 1.00 | 0.40 | 1.00 | | | 1.00 | |
| Satd. Flow (perm) | 1805 | 1626 | | 1698 | 1728 | 1533 | 701 | 1855 | | | 3563 | |
| Peak-hour factor, PHF | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 |
| Adj. Flow (vph) | 32 | 11 | 110 | 392 | 60 | 370 | 30 | 346 | 29 | 0 | 548 | 11 |
| RTOR Reduction (vph) | 0 | 96 | 0 | 0 | 0 | 276 | 0 | 4 | 0 | 0 | 2 | 0 |
| Lane Group Flow (vph) | 32 | 25 | 0 | 223 | 229 | 94 | 30 | 371 | 0 | 0 | 557 | 0 |
| Confl. Peds. (#/hr) | 10 | | | | | 10 | 6 | | 19 | 19 | | 6 |
| Heavy Vehicles (%) | 0% | 0% | 1% | 1% | 0% | 2% | 7% | 1% | 0% | 0% | 1% | 0% |
| Turn Type | Split | | | Split | | Perm | Perm | | | | | |
| Protected Phases | 8 | 8 | | 4 | 4 | | | 6 | | | | 2 |
| Permitted Phases | | | | | | 4 | 6 | | | | | |
| Actuated Green, G (s) | 4.8 | 4.8 | | 10.3 | 10.3 | 10.3 | 13.7 | 13.7 | | | | 13.7 |
| Effective Green, g (s) | 5.3 | 5.3 | | 10.8 | 10.8 | 10.8 | 14.2 | 14.2 | | | | 14.2 |
| Actuated g/C Ratio | 0.13 | 0.13 | | 0.26 | 0.26 | 0.26 | 0.34 | 0.34 | | | | 0.34 |
| Clearance Time (s) | 4.5 | 4.5 | | 4.5 | 4.5 | 4.5 | 4.5 | 4.5 | | | | 4.5 |
| Vehicle Extension (s) | 2.5 | 2.5 | | 2.5 | 2.5 | 2.5 | 5.0 | 5.0 | | | | 5.0 |
| Lane Grp Cap (vph) | 226 | 204 | | 434 | 441 | 391 | 235 | 623 | | | | 1196 |
| v/s Ratio Prot | c0.02 | 0.02 | | 0.13 | c0.13 | | | c0.20 | | | | 0.16 |
| v/s Ratio Perm | | | | | | 0.06 | 0.04 | | | | | |
| v/c Ratio | 0.14 | 0.12 | | 0.51 | 0.52 | 0.24 | 0.13 | 0.60 | | | | 0.47 |
| Uniform Delay, d1 | 16.5 | 16.4 | | 13.5 | 13.5 | 12.5 | 9.8 | 11.7 | | | | 11.1 |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | | 1.00 |
| Incremental Delay, d2 | 0.2 | 0.2 | | 0.8 | 0.8 | 0.2 | 0.5 | 2.3 | | | | 0.6 |
| Delay (s) | 16.7 | 16.6 | | 14.3 | 14.3 | 12.7 | 10.3 | 14.0 | | | | 11.7 |
| Level of Service | B | B | | B | B | B | B | B | | | | B |
| Approach Delay (s) | | 16.6 | | | 13.6 | | | 13.7 | | | | 11.7 |
| Approach LOS | | B | | | B | | | B | | | | B |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 13.3 | | | HCM Level of Service | | | | | B | |
| HCM Volume to Capacity ratio | | | 0.49 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 42.3 | | | Sum of lost time (s) | | | 12.0 | | | |
| Intersection Capacity Utilization | | | 56.9% | | | ICU Level of Service | | | | | B | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCM Unsignalized Intersection Capacity Analysis
 9: Nyberg St & Site Entrance 3

4/15/2013



| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
|------------------------|------|------|------|------|------|------|
| Lane Configurations | ↵ | | ↕ | | | ↵ |
| Volume (veh/h) | 35 | 0 | 648 | 51 | 0 | 100 |
| Sign Control | | Free | Free | | Stop | |
| Grade | | 0% | 0% | | | |
| Peak Hour Factor | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 |
| Hourly flow rate (vph) | 40 | 0 | 736 | 58 | 0 | 114 |
| Pedestrians | | | | | 5 | |
| Lane Width (ft) | | | | | 12.0 | |
| Walking Speed (ft/s) | | | | | 4.0 | |
| Percent Blockage | | | | | 0 | |
| Right turn flare (veh) | | | | | | |
| Median type | | None | None | | | |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | 278 | | | | |
| pX, platoon unblocked | | | | | | |
| vC, conflicting volume | 799 | | | | 850 | 402 |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 799 | | | | 850 | 402 |
| tC, single (s) | 4.1 | | | | 6.8 | 6.9 |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 2.2 | | | | 3.5 | 3.3 |
| p0 queue free % | 95 | | | | 100 | 81 |
| cM capacity (veh/h) | 829 | | | | 288 | 601 |

| Direction, Lane # | EB 1 | WB 1 | WB 2 | SB 1 |
|------------------------|------|------|------|------|
| Volume Total | 40 | 491 | 303 | 114 |
| Volume Left | 40 | 0 | 0 | 0 |
| Volume Right | 0 | 0 | 58 | 114 |
| cSH | 829 | 1700 | 1700 | 601 |
| Volume to Capacity | 0.05 | 0.29 | 0.18 | 0.19 |
| Queue Length 95th (ft) | 4 | 0 | 0 | 17 |
| Control Delay (s) | 9.6 | 0.0 | 0.0 | 12.4 |
| Lane LOS | A | | | B |
| Approach Delay (s) | 9.6 | 0.0 | | 12.4 |
| Approach LOS | | | | B |

| Intersection Summary | | | |
|-----------------------------------|--|-------|------------------------|
| Average Delay | | 1.9 | |
| Intersection Capacity Utilization | | 32.4% | ICU Level of Service A |
| Analysis Period (min) | | 15 | |














HCM Signalized Intersection Capacity Analysis
 10: Tualatin Sherwood Rd & Site Entrance 4

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR | |
|-----------------------------------|------|-------|------|------|------|------|-------|------|-------|-------|------|----------------------|------|
| Lane Configurations | | | | | | | | | | | | | |
| Volume (vph) | 99 | 1899 | 40 | 232 | 1694 | 251 | 36 | 10 | 236 | 323 | 24 | 113 | |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | |
| Total Lost time (s) | 4.5 | 6.0 | | 4.5 | 6.0 | 6.0 | | 5.0 | 4.5 | 5.0 | 5.0 | | |
| Lane Util. Factor | 1.00 | *0.75 | | 0.97 | 0.91 | 1.00 | | 1.00 | 1.00 | 0.97 | 1.00 | | |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 0.96 | | 1.00 | 1.00 | 1.00 | 0.97 | | |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | | |
| Frt | 1.00 | 1.00 | | 1.00 | 1.00 | 0.85 | | 1.00 | 0.85 | 1.00 | 0.88 | | |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | 1.00 | | 0.96 | 1.00 | 0.95 | 1.00 | | |
| Satd. Flow (prot) | 1805 | 4100 | | 3502 | 4988 | 1545 | | 1786 | 1599 | 3502 | 1622 | | |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | 1.00 | | 0.96 | 1.00 | 0.95 | 1.00 | | |
| Satd. Flow (perm) | 1805 | 4100 | | 3502 | 4988 | 1545 | | 1786 | 1599 | 3502 | 1622 | | |
| Peak-hour factor, PHF | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | |
| Adj. Flow (vph) | 101 | 1938 | 41 | 237 | 1729 | 256 | 37 | 10 | 241 | 330 | 24 | 115 | |
| RTOR Reduction (vph) | 0 | 1 | 0 | 0 | 0 | 126 | 0 | 0 | 0 | 0 | 99 | 0 | |
| Lane Group Flow (vph) | 101 | 1978 | 0 | 237 | 1729 | 130 | 0 | 47 | 241 | 330 | 40 | 0 | |
| Confl. Peds. (#/hr) | | | 2 | | | 8 | | | | | | 15 | |
| Heavy Vehicles (%) | 0% | 4% | 0% | 0% | 4% | 0% | 3% | 0% | 1% | 0% | 0% | 0% | |
| Turn Type | Prot | | | Prot | | Perm | Split | | pt+ov | Split | | | |
| Protected Phases | 5 | 2 | | 1 | 6 | | 8 | 8 | 18 | 4 | 4 | | |
| Permitted Phases | | | | | | 6 | | | | | | | |
| Actuated Green, G (s) | 14.1 | 61.1 | | 16.1 | 63.1 | 63.1 | | 8.6 | 24.7 | 16.7 | 16.7 | | |
| Effective Green, g (s) | 14.6 | 61.6 | | 16.6 | 63.6 | 63.6 | | 9.1 | 25.7 | 17.2 | 17.2 | | |
| Actuated g/C Ratio | 0.12 | 0.49 | | 0.13 | 0.51 | 0.51 | | 0.07 | 0.21 | 0.14 | 0.14 | | |
| Clearance Time (s) | 5.0 | 6.5 | | 5.0 | 6.5 | 6.5 | | 5.5 | | 5.5 | 5.5 | | |
| Vehicle Extension (s) | 2.5 | 4.0 | | 2.5 | 4.0 | 4.0 | | 2.5 | | 2.5 | 2.5 | | |
| Lane Grp Cap (vph) | 211 | 2020 | | 465 | 2538 | 786 | | 130 | 329 | 482 | 223 | | |
| v/s Ratio Prot | 0.06 | c0.48 | | 0.07 | 0.35 | | | 0.03 | c0.15 | c0.09 | 0.02 | | |
| v/s Ratio Perm | | | | | | 0.08 | | | | | | | |
| v/c Ratio | 0.48 | 0.98 | | 0.51 | 0.68 | 0.17 | | 0.36 | 0.73 | 0.68 | 0.18 | | |
| Uniform Delay, d1 | 51.6 | 31.1 | | 50.4 | 23.1 | 16.5 | | 55.2 | 46.4 | 51.3 | 47.7 | | |
| Progression Factor | 0.88 | 0.56 | | 1.04 | 0.86 | 1.12 | | 1.00 | 1.00 | 1.00 | 1.00 | | |
| Incremental Delay, d2 | 0.6 | 9.4 | | 0.4 | 1.0 | 0.3 | | 1.2 | 7.7 | 3.7 | 0.3 | | |
| Delay (s) | 46.2 | 26.6 | | 53.0 | 20.9 | 18.7 | | 56.4 | 54.2 | 55.0 | 47.9 | | |
| Level of Service | D | C | | D | C | B | | E | D | D | D | | |
| Approach Delay (s) | | 27.6 | | | 24.1 | | | 54.5 | | | 52.9 | | |
| Approach LOS | | C | | | C | | | D | | | D | | |
| Intersection Summary | | | | | | | | | | | | | |
| HCM Average Control Delay | | 29.9 | | | | | | | | | | HCM Level of Service | C |
| HCM Volume to Capacity ratio | | 0.83 | | | | | | | | | | | |
| Actuated Cycle Length (s) | | 125.0 | | | | | | | | | | Sum of lost time (s) | 15.5 |
| Intersection Capacity Utilization | | 81.5% | | | | | | | | | | ICU Level of Service | D |
| Analysis Period (min) | | 15 | | | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 12: Tualatin Sherwood Rd & I-5 SB Ramps

4/15/2013

| |  |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR | |
| Lane Configurations | | ↑↑↑ | ↗ | ↖ | ↑↑ | | | | | ↘ | ↙ | ↖↖ | |
| Volume (vph) | 0 | 1590 | 875 | 123 | 1063 | 0 | 0 | 0 | 0 | 659 | 5 | 1111 | |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | |
| Total Lost time (s) | | 5.5 | 5.5 | 5.5 | 5.5 | | | | | 5.5 | 5.5 | 5.5 | |
| Lane Util. Factor | | *0.75 | 1.00 | 1.00 | 0.95 | | | | | 0.95 | 0.95 | 0.88 | |
| Frt | | 1.00 | 0.85 | 1.00 | 1.00 | | | | | 1.00 | 1.00 | 0.85 | |
| Flt Protected | | 1.00 | 1.00 | 0.95 | 1.00 | | | | | 0.95 | 0.95 | 1.00 | |
| Satd. Flow (prot) | | 4150 | 1568 | 1787 | 3471 | | | | | 1681 | 1682 | 2760 | |
| Flt Permitted | | 1.00 | 1.00 | 0.95 | 1.00 | | | | | 0.95 | 0.95 | 1.00 | |
| Satd. Flow (perm) | | 4150 | 1568 | 1787 | 3471 | | | | | 1681 | 1682 | 2760 | |
| Peak-hour factor, PHF | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | |
| Adj. Flow (vph) | 0 | 1606 | 884 | 124 | 1074 | 0 | 0 | 0 | 0 | 666 | 5 | 1122 | |
| RTOR Reduction (vph) | 0 | 0 | 476 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 23 | |
| Lane Group Flow (vph) | 0 | 1606 | 408 | 124 | 1074 | 0 | 0 | 0 | 0 | 333 | 338 | 1099 | |
| Heavy Vehicles (%) | 0% | 3% | 3% | 1% | 4% | 0% | 0% | 0% | 0% | 2% | 20% | 3% | |
| Turn Type | | | Perm | Prot | | | | | | Split | | custom | |
| Protected Phases | | 2 | | 1 | 6 | | | | | 4 | 4 | 4 | |
| Permitted Phases | | | 2 | | | | | | | | | | |
| Actuated Green, G (s) | | 56.5 | 56.5 | 11.1 | 51.5 | | | | | 39.4 | 39.4 | 61.5 | |
| Effective Green, g (s) | | 57.0 | 57.0 | 11.6 | 52.0 | | | | | 39.9 | 39.9 | 62.0 | |
| Actuated g/C Ratio | | 0.46 | 0.46 | 0.09 | 0.42 | | | | | 0.32 | 0.32 | 0.50 | |
| Clearance Time (s) | | 6.0 | 6.0 | 6.0 | 6.0 | | | | | 6.0 | 6.0 | | |
| Vehicle Extension (s) | | 6.1 | 6.1 | 2.3 | 6.1 | | | | | 2.3 | 2.3 | | |
| Lane Grp Cap (vph) | | 1892 | 715 | 166 | 1444 | | | | | 537 | 537 | 1369 | |
| v/s Ratio Prot | | c0.39 | | 0.07 | c0.31 | | | | | 0.20 | 0.20 | c0.40 | |
| v/s Ratio Perm | | | 0.26 | | | | | | | | | | |
| v/c Ratio | | 0.85 | 0.57 | 0.75 | 0.74 | | | | | 0.62 | 0.63 | 0.80 | |
| Uniform Delay, d1 | | 30.2 | 25.0 | 55.3 | 30.9 | | | | | 36.1 | 36.3 | 26.4 | |
| Progression Factor | | 0.50 | 2.46 | 0.79 | 0.64 | | | | | 1.00 | 1.00 | 1.00 | |
| Incremental Delay, d2 | | 2.5 | 1.6 | 14.5 | 3.3 | | | | | 1.8 | 1.9 | 3.4 | |
| Delay (s) | | 17.6 | 63.1 | 58.3 | 23.1 | | | | | 37.9 | 38.1 | 29.8 | |
| Level of Service | | B | E | E | C | | | | | D | D | C | |
| Approach Delay (s) | | 33.7 | | | 26.8 | | | 0.0 | | | 32.8 | | |
| Approach LOS | | C | | | C | | | A | | | C | | |
| Intersection Summary | | | | | | | | | | | | | |
| HCM Average Control Delay | | | 31.9 | | | | | | | | | | HCM Level of Service C |
| HCM Volume to Capacity ratio | | | 0.82 | | | | | | | | | | |
| Actuated Cycle Length (s) | | | 125.0 | | | | | | | 11.0 | | | Sum of lost time (s) |
| Intersection Capacity Utilization | | | 93.1% | | | | | | | | | | ICU Level of Service F |
| Analysis Period (min) | | | 15 | | | | | | | | | | |

c Critical Lane Group

HCM Signalized Intersection Capacity Analysis
 13: Tualatin Sherwood Rd & I-5 NB Ramps

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|------|-------|------|------|----------------------|------|-------|-------|------|------|------|------|
| Lane Configurations | | ↑↑ | ↑↑ | | ↑↑ | ↑ | ↑ | ↑ | ↑ | | | |
| Volume (vph) | 0 | 1216 | 1031 | 0 | 511 | 682 | 675 | 5 | 177 | 0 | 0 | 0 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | | 5.5 | 5.5 | | 6.0 | 6.0 | 5.5 | 5.5 | 5.5 | | | |
| Lane Util. Factor | | 0.95 | 0.88 | | 0.95 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Frbp, ped/bikes | | 1.00 | 1.00 | | 1.00 | 0.95 | 1.00 | 1.00 | 0.96 | | | |
| Flpb, ped/bikes | | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Frt | | 1.00 | 0.85 | | 1.00 | 0.85 | 1.00 | 1.00 | 0.85 | | | |
| Flt Protected | | 1.00 | 1.00 | | 1.00 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Satd. Flow (prot) | | 3574 | 2760 | | 3574 | 1502 | 1618 | 1620 | 1512 | | | |
| Flt Permitted | | 1.00 | 1.00 | | 1.00 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Satd. Flow (perm) | | 3574 | 2760 | | 3574 | 1502 | 1618 | 1620 | 1512 | | | |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 0 | 1280 | 1085 | 0 | 538 | 718 | 711 | 5 | 186 | 0 | 0 | 0 |
| RTOR Reduction (vph) | 0 | 0 | 352 | 0 | 0 | 263 | 0 | 0 | 21 | 0 | 0 | 0 |
| Lane Group Flow (vph) | 0 | 1280 | 733 | 0 | 538 | 455 | 355 | 361 | 165 | 0 | 0 | 0 |
| Confl. Peds. (#/hr) | | | | | | 16 | | | 17 | | | |
| Heavy Vehicles (%) | 0% | 1% | 3% | 0% | 1% | 2% | 6% | 20% | 2% | 0% | 0% | 0% |
| Turn Type | | Perm | | | Perm | | Split | Perm | | | | |
| Protected Phases | | 2 | | | 6 | | 8 | 8 | | | | |
| Permitted Phases | | 2 | | | 6 | | | 8 | | | | |
| Actuated Green, G (s) | | 79.3 | 79.3 | | 78.8 | 78.8 | 33.7 | 33.7 | 33.7 | | | |
| Effective Green, g (s) | | 79.8 | 79.8 | | 79.3 | 79.3 | 34.2 | 34.2 | 34.2 | | | |
| Actuated g/C Ratio | | 0.64 | 0.64 | | 0.63 | 0.63 | 0.27 | 0.27 | 0.27 | | | |
| Clearance Time (s) | | 6.0 | 6.0 | | 6.5 | 6.5 | 6.0 | 6.0 | 6.0 | | | |
| Vehicle Extension (s) | | 6.1 | 6.1 | | 4.2 | 4.2 | 2.3 | 2.3 | 2.3 | | | |
| Lane Grp Cap (vph) | | 2282 | 1762 | | 2267 | 953 | 443 | 443 | 414 | | | |
| v/s Ratio Prot | | c0.36 | | | 0.15 | | 0.22 | c0.22 | | | | |
| v/s Ratio Perm | | 0.27 | | | 0.30 | | | 0.11 | | | | |
| v/c Ratio | | 0.56 | 0.42 | | 0.24 | 0.48 | 0.80 | 0.81 | 0.40 | | | |
| Uniform Delay, d1 | | 12.7 | 11.1 | | 9.8 | 12.0 | 42.2 | 42.4 | 37.0 | | | |
| Progression Factor | | 0.72 | 1.20 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Incremental Delay, d2 | | 0.7 | 0.5 | | 0.2 | 1.7 | 9.6 | 10.6 | 0.4 | | | |
| Delay (s) | | 9.9 | 13.8 | | 10.1 | 13.7 | 51.9 | 53.1 | 37.4 | | | |
| Level of Service | | A | B | | B | B | D | D | D | | | |
| Approach Delay (s) | | 11.7 | | | 12.2 | | 49.4 | | | 0.0 | | |
| Approach LOS | | B | | | B | | D | | | A | | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | 19.3 | | | HCM Level of Service | | B | | | | | |
| HCM Volume to Capacity ratio | | 0.64 | | | | | | | | | | |
| Actuated Cycle Length (s) | | 125.0 | | | Sum of lost time (s) | | 11.0 | | | | | |
| Intersection Capacity Utilization | | 72.2% | | | ICU Level of Service | | C | | | | | |
| Analysis Period (min) | | 15 | | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 14: Tualatin Sherwood Rd & Nyberg Woods

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR | |
|-----------------------------------|---------------------|-------|------|------|-------|------|------|-------|------|------|------|----------------------|---|
| Lane Configurations | | | | | | | | | | | | | |
| Volume (vph) | 290 | 995 | 61 | 10 | 834 | 80 | 112 | 7 | 17 | 81 | 5 | 191 | |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | |
| Total Lost time (s) | 5.5 | 5.5 | | 5.5 | 5.5 | | | 5.5 | 5.5 | | 5.5 | 5.5 | |
| Lane Util. Factor | 0.97 | 0.95 | | 1.00 | 0.95 | | | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 0.98 | | 1.00 | 0.99 | |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Frt | 1.00 | 0.99 | | 1.00 | 0.99 | | | 1.00 | 0.85 | | 1.00 | 0.85 | |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.95 | 1.00 | | 0.95 | 1.00 | |
| Satd. Flow (prot) | 3502 | 3504 | | 1805 | 3525 | | | 1761 | 1590 | | 1793 | 1592 | |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.67 | 1.00 | | 0.65 | 1.00 | |
| Satd. Flow (perm) | 3502 | 3504 | | 1805 | 3525 | | | 1243 | 1590 | | 1221 | 1592 | |
| Peak-hour factor, PHF | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | |
| Adj. Flow (vph) | 302 | 1036 | 64 | 10 | 869 | 83 | 117 | 7 | 18 | 84 | 5 | 199 | |
| RTOR Reduction (vph) | 0 | 3 | 0 | 0 | 7 | 0 | 0 | 0 | 15 | 0 | 0 | 165 | |
| Lane Group Flow (vph) | 302 | 1097 | 0 | 10 | 945 | 0 | 0 | 124 | 3 | 0 | 89 | 34 | |
| Confl. Peds. (#/hr) | 9 | | 2 | 2 | | 9 | 3 | | 4 | 4 | | 3 | |
| Heavy Vehicles (%) | 0% | 2% | 2% | 0% | 1% | 0% | 3% | 0% | 0% | 1% | 0% | 0% | |
| Turn Type | Prot | | | Prot | | | Perm | | Perm | Perm | | Perm | |
| Protected Phases | 5 | 2 | | 1 | 6 | | | 8 | 8 | | 4 | 4 | |
| Permitted Phases | | | | | | | 8 | | 8 | 4 | | 4 | |
| Actuated Green, G (s) | 9.0 | 33.1 | | 0.7 | 24.8 | | | 10.2 | 10.2 | | 10.2 | 10.2 | |
| Effective Green, g (s) | 9.5 | 33.6 | | 1.2 | 25.3 | | | 10.7 | 10.7 | | 10.7 | 10.7 | |
| Actuated g/C Ratio | 0.15 | 0.54 | | 0.02 | 0.41 | | | 0.17 | 0.17 | | 0.17 | 0.17 | |
| Clearance Time (s) | 6.0 | 6.0 | | 6.0 | 6.0 | | | 6.0 | 6.0 | | 6.0 | 6.0 | |
| Vehicle Extension (s) | 2.3 | 2.5 | | 2.4 | 2.5 | | | 2.4 | 2.4 | | 2.3 | 2.3 | |
| Lane Grp Cap (vph) | 537 | 1899 | | 35 | 1438 | | | 215 | 274 | | 211 | 275 | |
| v/s Ratio Prot | c0.09 | c0.31 | | 0.01 | c0.27 | | | | | | | | |
| v/s Ratio Perm | | | | | | | | c0.10 | 0.00 | | 0.07 | 0.02 | |
| v/c Ratio | 0.56 | 0.58 | | 0.29 | 0.66 | | | 0.58 | 0.01 | | 0.42 | 0.12 | |
| Uniform Delay, d1 | 24.3 | 9.5 | | 30.0 | 14.8 | | | 23.6 | 21.3 | | 22.9 | 21.7 | |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Incremental Delay, d2 | 1.0 | 0.4 | | 2.9 | 1.0 | | | 2.9 | 0.0 | | 0.8 | 0.1 | |
| Delay (s) | 25.3 | 9.8 | | 32.9 | 15.8 | | | 26.5 | 21.3 | | 23.7 | 21.8 | |
| Level of Service | C | A | | C | B | | | C | C | | C | C | |
| Approach Delay (s) | | 13.2 | | | 16.0 | | | 25.8 | | | 22.4 | | |
| Approach LOS | | B | | | B | | | C | | | C | | |
| Intersection Summary | | | | | | | | | | | | | |
| HCM Average Control Delay | | 15.7 | | | | | | | | | | HCM Level of Service | B |
| HCM Volume to Capacity ratio | | 0.71 | | | | | | | | | | | |
| Actuated Cycle Length (s) | | 62.0 | | | | | | | 22.0 | | | Sum of lost time (s) | |
| Intersection Capacity Utilization | | 61.6% | | | | | | | | | | ICU Level of Service | B |
| Analysis Period (min) | | 15 | | | | | | | | | | | |
| c | Critical Lane Group | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 15: SW Nyberg St & SW Nyberg St

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|-------|-------|-------|------|------|----------------------|-------|-------|------|------|-------|-------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 221 | 943 | 26 | 24 | 775 | 16 | 17 | 9 | 45 | 5 | 7 | 139 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.8 | 4.8 | | 4.8 | 4.8 | | | 5.6 | 5.6 | | 5.3 | 4.8 |
| Lane Util. Factor | 1.00 | 1.00 | | 1.00 | 0.95 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 0.95 | | 1.00 | 1.00 |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frt | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 0.85 | | 1.00 | 0.85 |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.97 | 1.00 | | 0.98 | 1.00 |
| Satd. Flow (prot) | 1805 | 1854 | | 1805 | 3561 | | | 1803 | 1527 | | 1848 | 1609 |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.97 | 1.00 | | 0.69 | 1.00 |
| Satd. Flow (perm) | 1805 | 1854 | | 1805 | 3561 | | | 1803 | 1527 | | 1304 | 1609 |
| Peak-hour factor, PHF | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 |
| Adj. Flow (vph) | 230 | 982 | 27 | 25 | 807 | 17 | 18 | 9 | 47 | 5 | 7 | 145 |
| RTOR Reduction (vph) | 0 | 0 | 0 | 0 | 1 | 0 | 0 | 0 | 44 | 0 | 0 | 116 |
| Lane Group Flow (vph) | 230 | 1009 | 0 | 25 | 823 | 0 | 0 | 27 | 3 | 0 | 12 | 29 |
| Confl. Peds. (#/hr) | 9 | | 2 | 2 | | 9 | 3 | | 4 | 4 | | 3 |
| Heavy Vehicles (%) | 0% | 2% | 2% | 0% | 1% | 0% | 3% | 0% | 0% | 1% | 0% | 0% |
| Turn Type | Prot | | | Prot | | | Split | | Perm | Perm | | pm+ov |
| Protected Phases | 5 | 2 | | 1 | 6 | | 8 | 8 | | | 4 | 5 |
| Permitted Phases | | | | | | | | | 8 | 4 | | 4 |
| Actuated Green, G (s) | 11.5 | 48.8 | | 1.7 | 39.0 | | | 4.1 | 4.1 | | 3.6 | 15.1 |
| Effective Green, g (s) | 12.0 | 49.3 | | 2.2 | 39.5 | | | 4.6 | 4.6 | | 4.1 | 16.1 |
| Actuated g/C Ratio | 0.15 | 0.61 | | 0.03 | 0.49 | | | 0.06 | 0.06 | | 0.05 | 0.20 |
| Clearance Time (s) | 5.3 | 5.3 | | 5.3 | 5.3 | | | 6.1 | 6.1 | | 5.8 | 5.3 |
| Vehicle Extension (s) | 2.5 | 3.0 | | 1.0 | 3.0 | | | 1.0 | 1.0 | | 2.0 | 2.5 |
| Lane Grp Cap (vph) | 268 | 1133 | | 49 | 1743 | | | 103 | 87 | | 66 | 321 |
| v/s Ratio Prot | c0.13 | c0.54 | | 0.01 | 0.23 | | | c0.01 | | | | 0.01 |
| v/s Ratio Perm | | | | | | | | | 0.00 | | c0.01 | 0.00 |
| v/c Ratio | 0.86 | 0.89 | | 0.51 | 0.47 | | | 0.26 | 0.03 | | 0.18 | 0.09 |
| Uniform Delay, d1 | 33.5 | 13.4 | | 38.7 | 13.7 | | | 36.4 | 35.9 | | 36.7 | 26.3 |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Incremental Delay, d2 | 22.5 | 9.0 | | 3.7 | 0.2 | | | 0.5 | 0.1 | | 0.5 | 0.1 |
| Delay (s) | 56.1 | 22.4 | | 42.4 | 13.9 | | | 36.9 | 36.0 | | 37.2 | 26.4 |
| Level of Service | E | C | | D | B | | | D | D | | D | C |
| Approach Delay (s) | | 28.6 | | | 14.7 | | | 36.3 | | | 27.2 | |
| Approach LOS | | C | | | B | | | D | | | C | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 23.7 | | | HCM Level of Service | | | | C | | |
| HCM Volume to Capacity ratio | | | 0.83 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 80.7 | | | Sum of lost time (s) | | 20.5 | | | | |
| Intersection Capacity Utilization | | | 76.8% | | | ICU Level of Service | | | | D | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |





















HCM Signalized Intersection Capacity Analysis
 16: SW Tualatin Sherwood Rd & SW Boones Ferry Rd

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|------|-------|-------|------|-------|----------------------|-------|-------|-------|-------|------|------|
| Lane Configurations | ↙ | ↕ | | ↙ | ↕ | | ↙ | ↕ | ↗ | ↙ | ↕ | ↗ |
| Volume (vph) | 103 | 1035 | 138 | 234 | 1103 | 56 | 171 | 268 | 169 | 297 | 345 | 133 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 5.5 | | 4.5 | 5.5 | | 4.5 | 5.0 | 4.5 | 4.5 | 5.0 | |
| Lane Util. Factor | 1.00 | 0.95 | | 0.97 | 0.95 | | 1.00 | 1.00 | 1.00 | 1.00 | 0.95 | |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | 0.98 | 1.00 | 0.99 | |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | |
| Frt | 1.00 | 0.98 | | 1.00 | 0.99 | | 1.00 | 1.00 | 0.85 | 1.00 | 0.96 | |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | 0.95 | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (prot) | 1703 | 3320 | | 3502 | 3339 | | 1732 | 1810 | 1543 | 1761 | 3313 | |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | | 0.41 | 1.00 | 1.00 | 0.59 | 1.00 | |
| Satd. Flow (perm) | 1703 | 3320 | | 3502 | 3339 | | 744 | 1810 | 1543 | 1099 | 3313 | |
| Peak-hour factor, PHF | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 |
| Adj. Flow (vph) | 104 | 1045 | 139 | 236 | 1114 | 57 | 173 | 271 | 171 | 300 | 348 | 134 |
| RTOR Reduction (vph) | 0 | 7 | 0 | 0 | 3 | 0 | 0 | 0 | 55 | 0 | 34 | 0 |
| Lane Group Flow (vph) | 104 | 1177 | 0 | 236 | 1168 | 0 | 173 | 271 | 116 | 300 | 448 | 0 |
| Confl. Peds. (#/hr) | | | 7 | | | 15 | 7 | | 8 | 8 | | 7 |
| Heavy Vehicles (%) | 6% | 7% | 3% | 0% | 7% | 6% | 4% | 5% | 3% | 2% | 4% | 3% |
| Turn Type | Prot | | | Prot | | | pm+pt | | pm+ov | pm+pt | | |
| Protected Phases | 5 | 2 | | 1 | 6 | | 3 | 8 | 1 | 7 | 4 | |
| Permitted Phases | | | | | | | 8 | | 8 | 4 | | |
| Actuated Green, G (s) | 10.0 | 54.6 | | 10.7 | 55.3 | | 21.2 | 21.2 | 31.9 | 27.3 | 26.8 | |
| Effective Green, g (s) | 10.5 | 55.1 | | 11.2 | 55.8 | | 21.7 | 21.7 | 32.9 | 27.8 | 27.3 | |
| Actuated g/C Ratio | 0.08 | 0.44 | | 0.09 | 0.45 | | 0.17 | 0.17 | 0.26 | 0.22 | 0.22 | |
| Clearance Time (s) | 5.0 | 6.0 | | 5.0 | 6.0 | | 5.0 | 5.5 | 5.0 | 5.0 | 5.5 | |
| Vehicle Extension (s) | 2.0 | 3.5 | | 2.0 | 3.5 | | 2.0 | 2.0 | 2.0 | 2.0 | 2.0 | |
| Lane Grp Cap (vph) | 143 | 1463 | | 314 | 1491 | | 223 | 314 | 406 | 337 | 724 | |
| v/s Ratio Prot | 0.06 | c0.35 | | 0.07 | c0.35 | | 0.07 | c0.15 | 0.03 | c0.12 | 0.14 | |
| v/s Ratio Perm | | | | | | | 0.06 | | 0.05 | c0.07 | | |
| v/c Ratio | 0.73 | 0.80 | | 0.75 | 0.78 | | 0.78 | 0.86 | 0.29 | 0.89 | 0.62 | |
| Uniform Delay, d1 | 55.9 | 30.3 | | 55.5 | 29.5 | | 47.6 | 50.2 | 36.7 | 45.8 | 44.1 | |
| Progression Factor | 1.00 | 1.00 | | 0.61 | 0.96 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | |
| Incremental Delay, d2 | 14.4 | 4.8 | | 5.3 | 2.5 | | 14.2 | 20.3 | 0.1 | 23.5 | 1.1 | |
| Delay (s) | 70.3 | 35.1 | | 39.2 | 30.9 | | 61.8 | 70.5 | 36.8 | 69.4 | 45.3 | |
| Level of Service | E | D | | D | C | | E | E | D | E | D | |
| Approach Delay (s) | | 37.9 | | | 32.3 | | | 58.7 | | | 54.5 | |
| Approach LOS | | D | | | C | | | E | | | D | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 42.3 | | | HCM Level of Service | | | | D | | |
| HCM Volume to Capacity ratio | | | 0.87 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 125.0 | | | Sum of lost time (s) | | | 20.5 | | | |
| Intersection Capacity Utilization | | | 88.2% | | | ICU Level of Service | | | E | | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 17: Tualatin Sherwood Rd & Martinazzi Ave

4/15/2013

| |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|---|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations |  |  | | |  | |  |  |  |  |  | |
| Volume (vph) | 55 | 1515 | 83 | 0 | 1146 | 0 | 95 | 312 | 333 | 194 | 673 | 90 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 5.5 | | | 5.5 | | 4.5 | 5.5 | 5.5 | 4.5 | 5.5 | |
| Lane Util. Factor | 1.00 | 0.95 | | | 0.95 | | 1.00 | 1.00 | 1.00 | 1.00 | 0.95 | |
| Frbp, ped/bikes | 1.00 | 1.00 | | | 1.00 | | 1.00 | 1.00 | 0.98 | 1.00 | 1.00 | |
| Flpb, ped/bikes | 1.00 | 1.00 | | | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | |
| Frt | 1.00 | 0.99 | | | 1.00 | | 1.00 | 1.00 | 0.85 | 1.00 | 0.98 | |
| Flt Protected | 0.95 | 1.00 | | | 1.00 | | 0.95 | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (prot) | 1719 | 3448 | | | 3438 | | 1770 | 1863 | 1574 | 1787 | 3497 | |
| Flt Permitted | 0.95 | 1.00 | | | 1.00 | | 0.95 | 1.00 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (perm) | 1719 | 3448 | | | 3438 | | 1770 | 1863 | 1574 | 1787 | 3497 | |
| Peak-hour factor, PHF | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 |
| Adj. Flow (vph) | 59 | 1612 | 88 | 0 | 1219 | 0 | 101 | 332 | 354 | 206 | 716 | 96 |
| RTOR Reduction (vph) | 0 | 3 | 0 | 0 | 0 | 0 | 0 | 0 | 80 | 0 | 10 | 0 |
| Lane Group Flow (vph) | 59 | 1697 | 0 | 0 | 1219 | 0 | 101 | 332 | 274 | 206 | 802 | 0 |
| Confl. Peds. (#/hr) | | | 4 | | | 2 | | | 3 | | | 16 |
| Heavy Vehicles (%) | 5% | 4% | 0% | 0% | 5% | 0% | 2% | 2% | 1% | 1% | 1% | 1% |
| Turn Type | Prot | | | | | | Prot | | Perm | | Prot | |
| Protected Phases | 5 | 2 | | | 6 | | 3 | 8 | | 7 | 4 | |
| Permitted Phases | | | | | | | | | 8 | | | |
| Actuated Green, G (s) | 7.2 | 65.2 | | | 53.0 | | 9.9 | 24.1 | 24.1 | 18.7 | 32.9 | |
| Effective Green, g (s) | 7.7 | 65.7 | | | 53.5 | | 10.4 | 24.6 | 24.6 | 19.2 | 33.4 | |
| Actuated g/C Ratio | 0.06 | 0.53 | | | 0.43 | | 0.08 | 0.20 | 0.20 | 0.15 | 0.27 | |
| Clearance Time (s) | 5.0 | 6.0 | | | 6.0 | | 5.0 | 6.0 | 6.0 | 5.0 | 6.0 | |
| Vehicle Extension (s) | 2.0 | 3.5 | | | 3.5 | | 3.0 | 2.0 | 2.0 | 3.0 | 2.0 | |
| Lane Grp Cap (vph) | 106 | 1812 | | | 1471 | | 147 | 367 | 310 | 274 | 934 | |
| v/s Ratio Prot | 0.03 | c0.49 | | | 0.35 | | 0.06 | c0.18 | | 0.12 | c0.23 | |
| v/s Ratio Perm | | | | | | | | | 0.17 | | | |
| v/c Ratio | 0.56 | 0.94 | | | 0.83 | | 0.69 | 0.90 | 0.88 | 0.75 | 0.86 | |
| Uniform Delay, d1 | 57.0 | 27.7 | | | 31.7 | | 55.7 | 49.1 | 48.8 | 50.6 | 43.6 | |
| Progression Factor | 1.20 | 0.74 | | | 1.09 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | |
| Incremental Delay, d2 | 2.7 | 8.5 | | | 4.4 | | 12.5 | 24.3 | 23.7 | 11.0 | 7.7 | |
| Delay (s) | 70.9 | 29.0 | | | 38.9 | | 68.3 | 73.4 | 72.5 | 61.7 | 51.2 | |
| Level of Service | E | C | | | D | | E | E | E | E | D | |
| Approach Delay (s) | | 30.4 | | | 38.9 | | | 72.3 | | | 53.3 | |
| Approach LOS | | C | | | D | | | E | | | D | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | 44.4 | | | | | HCM Level of Service | | D | | | |
| HCM Volume to Capacity ratio | | 0.89 | | | | | | | | | | |
| Actuated Cycle Length (s) | | 125.0 | | | | | Sum of lost time (s) | | 11.0 | | | |
| Intersection Capacity Utilization | | 89.5% | | | | | ICU Level of Service | | E | | | |
| Analysis Period (min) | | 15 | | | | | | | | | | |
| c | Critical Lane Group | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 18: SW Borland Rd & SW 65th Ave

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|-------|-------|-------|-------|-------|--------|-------|------|------|-------|------|------------------------|
| Lane Configurations | | ↔ | | | ↕ | ↗ | ↖ | ↗ | ↖ | ↖ | ↗ | ↖ |
| Volume (vph) | 23 | 23 | 10 | 240 | 0 | 244 | 2 | 334 | 369 | 433 | 474 | 10 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | | 5.6 | | | 5.3 | 5.6 | 4.8 | 4.8 | | 4.8 | 4.8 | |
| Lane Util. Factor | | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Frbp, ped/bikes | | 0.99 | | | 1.00 | 0.90 | 1.00 | 0.98 | | 1.00 | 1.00 | |
| Flpb, ped/bikes | | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Frt | | 0.98 | | | 1.00 | 0.85 | 1.00 | 0.92 | | 1.00 | 1.00 | |
| Flt Protected | | 0.98 | | | 0.95 | 1.00 | 0.95 | 1.00 | | 0.95 | 1.00 | |
| Satd. Flow (prot) | | 1785 | | | 1805 | 1456 | 1748 | 1719 | | 1787 | 1893 | |
| Flt Permitted | | 0.98 | | | 0.95 | 1.00 | 0.48 | 1.00 | | 0.08 | 1.00 | |
| Satd. Flow (perm) | | 1785 | | | 1805 | 1456 | 880 | 1719 | | 157 | 1893 | |
| Peak-hour factor, PHF | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 |
| Adj. Flow (vph) | 24 | 24 | 10 | 250 | 0 | 254 | 2 | 348 | 384 | 451 | 494 | 10 |
| RTOR Reduction (vph) | 0 | 6 | 0 | 0 | 0 | 240 | 0 | 25 | 0 | 0 | 0 | 0 |
| Lane Group Flow (vph) | 0 | 52 | 0 | 0 | 250 | 14 | 2 | 707 | 0 | 451 | 504 | 0 |
| Confl. Peds. (#/hr) | 9 | | 2 | 2 | | 9 | 3 | | 4 | 4 | | 3 |
| Heavy Vehicles (%) | 0% | 2% | 2% | 0% | 1% | 0% | 3% | 0% | 0% | 1% | 0% | 0% |
| Turn Type | Split | | | Split | | custom | pm+pt | | | pm+pt | | |
| Protected Phases | 8 | 8 | | 4 | 4 | | 1 | 6 | | 5 | 2 | |
| Permitted Phases | | | | | | 8 | 6 | | | 2 | | |
| Actuated Green, G (s) | | 7.6 | | | 20.0 | 7.6 | 65.3 | 64.3 | | 99.6 | 93.3 | |
| Effective Green, g (s) | | 8.1 | | | 20.5 | 8.1 | 66.3 | 64.8 | | 100.1 | 93.8 | |
| Actuated g/C Ratio | | 0.06 | | | 0.14 | 0.06 | 0.46 | 0.45 | | 0.69 | 0.65 | |
| Clearance Time (s) | | 6.1 | | | 5.8 | 6.1 | 5.3 | 5.3 | | 5.3 | 5.3 | |
| Vehicle Extension (s) | | 1.0 | | | 2.0 | 1.0 | 1.0 | 3.0 | | 2.5 | 0.2 | |
| Lane Grp Cap (vph) | | 100 | | | 256 | 82 | 413 | 771 | | 453 | 1230 | |
| v/s Ratio Prot | | c0.03 | | | c0.14 | | 0.00 | 0.41 | | c0.21 | 0.27 | |
| v/s Ratio Perm | | | | | | 0.01 | 0.00 | | | c0.48 | | |
| v/c Ratio | | 0.52 | | | 0.98 | 0.17 | 0.00 | 0.92 | | 1.00 | 0.41 | |
| Uniform Delay, d1 | | 66.3 | | | 61.7 | 65.0 | 21.1 | 37.3 | | 45.6 | 12.1 | |
| Progression Factor | | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Incremental Delay, d2 | | 2.3 | | | 49.0 | 0.4 | 0.0 | 15.5 | | 40.9 | 0.1 | |
| Delay (s) | | 68.5 | | | 110.8 | 65.3 | 21.1 | 52.8 | | 86.5 | 12.2 | |
| Level of Service | | E | | | F | E | C | D | | F | B | |
| Approach Delay (s) | | 68.5 | | | 87.9 | | | 52.7 | | | 47.2 | |
| Approach LOS | | E | | | F | | | D | | | D | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 58.7 | | | | | | | | | HCM Level of Service E |
| HCM Volume to Capacity ratio | | | 0.95 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 144.4 | | | | | | | | 15.7 | Sum of lost time (s) |
| Intersection Capacity Utilization | | | 96.8% | | | | | | | | | ICU Level of Service F |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis

19: SW Sagert St & SW Boones Ferry Rd

4/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|-------|------|-------|-------|------|----------------------|-------|-------|------|-------|------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 42 | 117 | 13 | 166 | 122 | 64 | 16 | 486 | 218 | 65 | 571 | 75 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 3.5 | 3.5 | | 3.5 | 3.5 | | 3.5 | 4.0 | | 3.5 | 4.0 | |
| Lane Util. Factor | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Frbp, ped/bikes | 1.00 | 1.00 | | 1.00 | 0.98 | | 1.00 | 0.99 | | 1.00 | 1.00 | |
| Flpb, ped/bikes | 0.99 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Frt | 1.00 | 0.98 | | 1.00 | 0.95 | | 1.00 | 0.95 | | 1.00 | 0.98 | |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | 0.95 | 1.00 | | 0.95 | 1.00 | |
| Satd. Flow (prot) | 1782 | 1830 | | 1781 | 1739 | | 1769 | 1789 | | 1804 | 1860 | |
| Flt Permitted | 0.64 | 1.00 | | 0.42 | 1.00 | | 0.25 | 1.00 | | 0.17 | 1.00 | |
| Satd. Flow (perm) | 1191 | 1830 | | 785 | 1739 | | 468 | 1789 | | 319 | 1860 | |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 44 | 123 | 14 | 175 | 128 | 67 | 17 | 512 | 229 | 68 | 601 | 79 |
| RTOR Reduction (vph) | 0 | 4 | 0 | 0 | 16 | 0 | 0 | 11 | 0 | 0 | 3 | 0 |
| Lane Group Flow (vph) | 44 | 133 | 0 | 175 | 179 | 0 | 17 | 730 | 0 | 68 | 677 | 0 |
| Confl. Peds. (#/hr) | 15 | | 7 | 7 | | 15 | 7 | | 8 | 8 | | 7 |
| Heavy Vehicles (%) | 0% | 2% | 1% | 1% | 3% | 0% | 2% | 0% | 1% | 0% | 0% | 0% |
| Turn Type | pm+pt | | | pm+pt | | | pm+pt | | | pm+pt | | |
| Protected Phases | 7 | 4 | | 3 | 8 | | 5 | 2 | | 1 | 6 | |
| Permitted Phases | 4 | | | 8 | | | 2 | | | 6 | | |
| Actuated Green, G (s) | 15.3 | 12.4 | | 25.7 | 18.8 | | 47.1 | 45.6 | | 51.5 | 47.8 | |
| Effective Green, g (s) | 16.3 | 12.9 | | 26.2 | 19.3 | | 48.1 | 46.1 | | 52.5 | 48.3 | |
| Actuated g/C Ratio | 0.19 | 0.15 | | 0.30 | 0.22 | | 0.55 | 0.53 | | 0.60 | 0.55 | |
| Clearance Time (s) | 4.0 | 4.0 | | 4.0 | 4.0 | | 4.0 | 4.5 | | 4.0 | 4.5 | |
| Vehicle Extension (s) | 2.2 | 2.2 | | 2.2 | 2.2 | | 2.2 | 5.0 | | 2.2 | 5.0 | |
| Lane Grp Cap (vph) | 245 | 270 | | 347 | 384 | | 287 | 943 | | 263 | 1027 | |
| v/s Ratio Prot | 0.01 | 0.07 | | c0.06 | 0.10 | | 0.00 | c0.41 | | c0.01 | 0.36 | |
| v/s Ratio Perm | 0.03 | | | c0.09 | | | 0.03 | | | 0.14 | | |
| v/c Ratio | 0.18 | 0.49 | | 0.50 | 0.47 | | 0.06 | 0.77 | | 0.26 | 0.66 | |
| Uniform Delay, d1 | 29.7 | 34.3 | | 24.1 | 29.6 | | 10.8 | 16.5 | | 11.9 | 13.8 | |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Incremental Delay, d2 | 0.2 | 0.7 | | 0.6 | 0.5 | | 0.0 | 4.7 | | 0.3 | 2.1 | |
| Delay (s) | 29.9 | 35.0 | | 24.7 | 30.1 | | 10.8 | 21.2 | | 12.2 | 15.9 | |
| Level of Service | C | D | | C | C | | B | C | | B | B | |
| Approach Delay (s) | | 33.8 | | | 27.5 | | | 21.0 | | | 15.5 | |
| Approach LOS | | C | | | C | | | C | | | B | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 21.3 | | | HCM Level of Service | | | C | | | |
| HCM Volume to Capacity ratio | | | 0.68 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 87.5 | | | Sum of lost time (s) | | 14.5 | | | | |
| Intersection Capacity Utilization | | | 74.8% | | | ICU Level of Service | | | D | | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCS+: Unsignalized Intersections Release 5.6

Phone:
E-Mail:

Fax:

ALL-WAY STOP CONTROL (AWSC) ANALYSIS

Analyst:
Agency/Co.:
Date Performed: 4/16/2013
Analysis Time Period: Weekday PM
Intersection: Sagert/Martinazzi
Jurisdiction:
Units: U. S. Customary
Analysis Year: Total
Project ID:
East/West Street: Sagert
North/South Street: Martinazzi

Worksheet 2 - Volume Adjustments and Site Characteristics

| | Eastbound | | | Westbound | | | Northbound | | | Southbound | | |
|-------------------|-----------|-----|----|-----------|-----|-----|------------|---|----|------------|-----|---|
| | L | T | R | L | T | R | L | T | R | L | T | R |
| Volume | 127 | 233 | 12 | 90 | 195 | 164 | 2 | | 76 | 207 | 306 | 0 |
| % Thrus Left Lane | | | | | | | | | | | | |

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|-------------------|-----------|------|-----------|------|------------|------|------------|------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Configuration | L | TR | L | TR | L | TR | L | TR |
| PHF | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 |
| Flow Rate | 141 | 271 | 100 | 398 | 2 | 284 | 230 | 340 |
| % Heavy Veh | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| No. Lanes | | 2 | | 2 | | 2 | | 2 |
| Opposing-Lanes | | 2 | | 2 | | 2 | | 2 |
| Conflicting-lanes | | 2 | | 2 | | 2 | | 2 |
| Geometry group | | 5 | | 5 | | 5 | | 5 |
| Duration, T | 0.25 hrs. | | | | | | | |

Worksheet 3 - Saturation Headway Adjustment Worksheet

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|----------------------------|-----------|-----|-----------|-----|------------|-----|------------|-----|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow Rates: | | | | | | | | |
| Total in Lane | 141 | 271 | 100 | 398 | 2 | 284 | 230 | 340 |
| Left-Turn | 141 | 0 | 100 | 0 | 2 | 0 | 230 | 0 |
| Right-Turn | 0 | 13 | 0 | 182 | 0 | 84 | 0 | 0 |
| Prop. Left-Turns | 1.0 | 0.0 | 1.0 | 0.0 | 1.0 | 0.0 | 1.0 | 0.0 |
| Prop. Right-Turns | 0.0 | 0.0 | 0.0 | 0.5 | 0.0 | 0.3 | 0.0 | 0.0 |
| Prop. Heavy Vehicle | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Geometry Group | | 5 | | 5 | | 5 | | 5 |
| Adjustments Exhibit 17-33: | | | | | | | | |
| hLT-adj | | 0.5 | | 0.5 | | 0.5 | | 0.5 |

| | | | | | | | | |
|----------------|------|------|------|------|------|------|------|-----|
| hRT-adj | -0.7 | | -0.7 | | -0.7 | | -0.7 | |
| hHV-adj | 1.7 | | 1.7 | | 1.7 | | 1.7 | |
| hadj, computed | 0.5 | -0.0 | 0.5 | -0.3 | 0.5 | -0.2 | 0.5 | 0.0 |

Worksheet 4 - Departure Headway and Service Time

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|-------------------|-----------|------|-----------|------|------------|------|------------|------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow rate | 141 | 271 | 100 | 398 | 2 | 284 | 230 | 340 |
| hd, initial value | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 |
| x, initial | 0.13 | 0.24 | 0.09 | 0.35 | 0.00 | 0.25 | 0.20 | 0.30 |
| hd, final value | 8.96 | 8.42 | 8.76 | 7.94 | 9.19 | 8.48 | 8.72 | 8.22 |
| x, final value | 0.35 | 0.63 | 0.24 | 0.88 | 0.01 | 0.67 | 0.56 | 0.78 |
| Move-up time, m | | 2.3 | | 2.3 | | 2.3 | | 2.3 |
| Service Time | 6.7 | 6.1 | 6.5 | 5.6 | 6.9 | 6.2 | 6.4 | 5.9 |

Worksheet 5 - Capacity and Level of Service

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|--------------------|-----------|-------|--------------------|-------|------------|-------|------------|-------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow Rate | 141 | 271 | 100 | 398 | 2 | 284 | 230 | 340 |
| Service Time | 6.7 | 6.1 | 6.5 | 5.6 | 6.9 | 6.2 | 6.4 | 5.9 |
| Utilization, x | 0.35 | 0.63 | 0.24 | 0.88 | 0.01 | 0.67 | 0.56 | 0.78 |
| Dep. headway, hd | 8.96 | 8.42 | 8.76 | 7.94 | 9.19 | 8.48 | 8.72 | 8.22 |
| Capacity | 391 | 418 | 350 | 450 | 252 | 413 | 407 | 433 |
| Delay | 16.42 | 24.61 | 14.25 | 45.54 | 11.93 | 26.70 | 21.85 | 34.14 |
| LOS | C | C | B | E | B | D | C | D |
| Approach: | | | | | | | | |
| Delay | | 21.81 | | 39.26 | | 26.59 | | 29.18 |
| LOS | | C | | E | | D | | D |
| Intersection Delay | 29.88 | | Intersection LOS D | | | | | |

HCS+: Unsignalized Intersections Release 5.6

Phone:
E-Mail:

Fax:

ALL-WAY STOP CONTROL (AWSC) ANALYSIS

Analyst:
Agency/Co.:
Date Performed: 4/16/2013
Analysis Time Period: Weekday PM
Intersection: Sagert/65th
Jurisdiction:
Units: U. S. Customary
Analysis Year: Total
Project ID:
East/West Street: Sagert
North/South Street: 65th

Worksheet 2 - Volume Adjustments and Site Characteristics

| | Eastbound | | | Westbound | | | Northbound | | | Southbound | | |
|-------------------|-----------|---|-----|-----------|---|---|------------|---|---|------------|-----|-----|
| | L | T | R | L | T | R | L | T | R | L | T | R |
| Volume | 401 | 2 | 135 | 2 | 7 | 6 | 58 | | 3 | 3 | 340 | 386 |
| % Thrus Left Lane | | | | | | | | | | | | |

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|-------------------|-----------|------|-----------|------|------------|------|------------|------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Configuration | L | TR | L | TR | L | TR | L | TR |
| PHF | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 | 0.90 |
| Flow Rate | 445 | 152 | 2 | 13 | 64 | 323 | 3 | 805 |
| % Heavy Veh | 1 | 1 | 0 | 0 | 1 | 2 | 1 | 2 |
| No. Lanes | | 2 | | 2 | | 2 | | 2 |
| Opposing-Lanes | | 2 | | 2 | | 2 | | 2 |
| Conflicting-lanes | | 2 | | 2 | | 2 | | 2 |
| Geometry group | | 5 | | 5 | | 5 | | 5 |
| Duration, T | 0.25 hrs. | | | | | | | |

Worksheet 3 - Saturation Headway Adjustment Worksheet

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|----------------------------|-----------|-----|-----------|-----|------------|-----|------------|-----|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow Rates: | | | | | | | | |
| Total in Lane | 445 | 152 | 2 | 13 | 64 | 323 | 3 | 805 |
| Left-Turn | 445 | 0 | 2 | 0 | 64 | 0 | 3 | 0 |
| Right-Turn | 0 | 150 | 0 | 6 | 0 | 3 | 0 | 428 |
| Prop. Left-Turns | 1.0 | 0.0 | 1.0 | 0.0 | 1.0 | 0.0 | 1.0 | 0.0 |
| Prop. Right-Turns | 0.0 | 1.0 | 0.0 | 0.5 | 0.0 | 0.0 | 0.0 | 0.5 |
| Prop. Heavy Vehicle | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 | 0.0 |
| Geometry Group | | 5 | | 5 | | 5 | | 5 |
| Adjustments Exhibit 17-33: | | | | | | | | |
| hLT-adj | | 0.5 | | 0.5 | | 0.5 | | 0.5 |

| | | | | | | | | |
|----------------|------|------|------|------|------|-----|------|------|
| hRT-adj | -0.7 | | -0.7 | | -0.7 | | -0.7 | |
| hHV-adj | 1.7 | | 1.7 | | 1.7 | | 1.7 | |
| hadj, computed | 0.5 | -0.7 | 0.5 | -0.3 | 0.5 | 0.0 | 0.5 | -0.3 |

Worksheet 4 - Departure Headway and Service Time

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|-------------------|-----------|------|-----------|------|------------|------|------------|------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow rate | 445 | 152 | 2 | 13 | 64 | 323 | 3 | 805 |
| hd, initial value | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 | 3.20 |
| x, initial | 0.40 | 0.14 | 0.00 | 0.01 | 0.06 | 0.29 | 0.00 | 0.72 |
| hd, final value | 7.73 | 6.54 | 9.23 | 8.40 | 8.00 | 7.51 | 7.77 | 6.92 |
| x, final value | 0.96 | 0.28 | 0.01 | 0.03 | 0.14 | 0.67 | 0.01 | 1.55 |
| Move-up time, m | | 2.3 | | 2.3 | | 2.3 | | 2.3 |
| Service Time | 5.4 | 4.2 | 6.9 | 6.1 | 5.7 | 5.2 | 5.5 | 4.6 |

Worksheet 5 - Capacity and Level of Service

| | Eastbound | | Westbound | | Northbound | | Southbound | |
|--------------------|-----------|-------|-----------|-------|--------------|-------|------------|--------|
| | L1 | L2 | L1 | L2 | L1 | L2 | L1 | L2 |
| Flow Rate | 445 | 152 | 2 | 13 | 64 | 323 | 3 | 805 |
| Service Time | 5.4 | 4.2 | 6.9 | 6.1 | 5.7 | 5.2 | 5.5 | 4.6 |
| Utilization, x | 0.96 | 0.28 | 0.01 | 0.03 | 0.14 | 0.67 | 0.01 | 1.55 |
| Dep. headway, hd | 7.73 | 6.54 | 9.23 | 8.40 | 8.00 | 7.51 | 7.77 | 6.92 |
| Capacity | 466 | 402 | 252 | 263 | 314 | 475 | 253 | 805 |
| Delay | 58.85 | 11.71 | 11.98 | 11.37 | 12.02 | 24.33 | 10.52 | 273.87 |
| LOS | F | B | B | B | B | C | B | F |
| Approach: | | | | | | | | |
| Delay | | 46.85 | | 11.45 | | 22.29 | | 272.89 |
| LOS | | E | | B | | C | | F |
| Intersection Delay | 142.37 | | | | Intersection | LOS | F | |

HCM Unsignalized Intersection Capacity Analysis
 22: SW Boones Fe &

4/15/2013

| | → | ↘ | ↙ | ← | ↖ | ↗ |
|-----------------------------------|-------|------|-------|------|----------------------|------|
| Movement | EBT | EBR | WBL | WBT | NWL | NWR |
| Lane Configurations | ↘ | | | ↖ | | ↗ |
| Volume (veh/h) | 1051 | 10 | 0 | 1384 | 0 | 35 |
| Sign Control | Free | | | Free | Stop | |
| Grade | 0% | | | 0% | 0% | |
| Peak Hour Factor | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 |
| Hourly flow rate (vph) | 1142 | 11 | 0 | 1504 | 0 | 38 |
| Pedestrians | | | | | | |
| Lane Width (ft) | | | | | | |
| Walking Speed (ft/s) | | | | | | |
| Percent Blockage | | | | | | |
| Right turn flare (veh) | | | | | | |
| Median type | TWLTL | | None | | | |
| Median storage (veh) | 2 | | | | | |
| Upstream signal (ft) | 252 | | | | | |
| pX, platoon unblocked | | | 0.63 | | 0.63 | 0.63 |
| vC, conflicting volume | | | 1153 | | 1900 | 1148 |
| vC1, stage 1 conf vol | | | | | 1148 | |
| vC2, stage 2 conf vol | | | | | 752 | |
| vCu, unblocked vol | | | 949 | | 2136 | 940 |
| tC, single (s) | | | 4.1 | | 6.8 | 6.9 |
| tC, 2 stage (s) | | | | | 5.8 | |
| tF (s) | | | 2.2 | | 3.5 | 3.3 |
| p0 queue free % | | | 100 | | 100 | 77 |
| cM capacity (veh/h) | | | 453 | | 185 | 167 |
| Direction, Lane # | EB 1 | WB 1 | WB 2 | NW 1 | | |
| Volume Total | 1153 | 752 | 752 | 38 | | |
| Volume Left | 0 | 0 | 0 | 0 | | |
| Volume Right | 11 | 0 | 0 | 38 | | |
| cSH | 1700 | 1700 | 1700 | 167 | | |
| Volume to Capacity | 0.68 | 0.44 | 0.44 | 0.23 | | |
| Queue Length 95th (ft) | 0 | 0 | 0 | 21 | | |
| Control Delay (s) | 0.0 | 0.0 | 0.0 | 32.9 | | |
| Lane LOS | | | | D | | |
| Approach Delay (s) | 0.0 | 0.0 | | 32.9 | | |
| Approach LOS | | | | D | | |
| Intersection Summary | | | | | | |
| Average Delay | | | 0.5 | | | |
| Intersection Capacity Utilization | | | 65.9% | | ICU Level of Service | C |
| Analysis Period (min) | | | 15 | | | |

HCM Signalized Intersection Capacity Analysis
 3: SW Boones Ferry Rd & SW Martinazzi Ave

4/17/2013

| | → | ↘ | ↙ | ← | ↖ | ↗ |
|-----------------------------------|-------|------|-------|------|----------------------|-------|
| Movement | EBT | EBR | WBL | WBT | NBL | NBR |
| Lane Configurations | ↑ | ↗ | ↙ | ↑ | ↙ | ↗ |
| Volume (vph) | 435 | 127 | 318 | 429 | 201 | 309 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 4.5 | 4.5 | 4.5 | 4.5 | 4.5 |
| Lane Util. Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Frbp, ped/bikes | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 0.99 |
| Flpb, ped/bikes | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Frt | 1.00 | 0.85 | 1.00 | 1.00 | 1.00 | 0.85 |
| Flt Protected | 1.00 | 1.00 | 0.95 | 1.00 | 0.95 | 1.00 |
| Satd. Flow (prot) | 1863 | 1599 | 1787 | 1845 | 1770 | 1582 |
| Flt Permitted | 1.00 | 1.00 | 0.95 | 1.00 | 0.95 | 1.00 |
| Satd. Flow (perm) | 1863 | 1599 | 1787 | 1845 | 1770 | 1582 |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 458 | 134 | 335 | 452 | 212 | 325 |
| RTOR Reduction (vph) | 0 | 89 | 0 | 0 | 0 | 86 |
| Lane Group Flow (vph) | 458 | 45 | 335 | 452 | 212 | 239 |
| Confl. Peds. (#/hr) | | 11 | 11 | | 1 | 3 |
| Confl. Bikes (#/hr) | 4 | | 2 | 10 | 1 | |
| Heavy Vehicles (%) | 2% | 1% | 1% | 3% | 2% | 1% |
| Turn Type | | Prot | Prot | | | pm+ov |
| Protected Phases | 2 | 2 | 1 | 6 | 8 | 1 |
| Permitted Phases | | | | | 8 | 8 |
| Actuated Green, G (s) | 20.0 | 20.0 | 16.8 | 41.8 | 12.6 | 29.4 |
| Effective Green, g (s) | 20.5 | 20.5 | 17.3 | 42.3 | 13.1 | 30.4 |
| Actuated g/C Ratio | 0.32 | 0.32 | 0.27 | 0.66 | 0.20 | 0.47 |
| Clearance Time (s) | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 | 5.0 |
| Vehicle Extension (s) | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 | 3.0 |
| Lane Grp Cap (vph) | 593 | 509 | 480 | 1212 | 360 | 857 |
| v/s Ratio Prot | c0.25 | 0.03 | c0.19 | 0.25 | c0.12 | 0.07 |
| v/s Ratio Perm | | | | | | 0.08 |
| v/c Ratio | 0.77 | 0.09 | 0.70 | 0.37 | 0.59 | 0.28 |
| Uniform Delay, d1 | 19.8 | 15.4 | 21.2 | 5.0 | 23.2 | 10.3 |
| Progression Factor | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 |
| Incremental Delay, d2 | 6.2 | 0.1 | 4.4 | 0.2 | 2.5 | 0.2 |
| Delay (s) | 26.0 | 15.5 | 25.6 | 5.2 | 25.7 | 10.5 |
| Level of Service | C | B | C | A | C | B |
| Approach Delay (s) | 23.6 | | | 13.9 | 16.5 | |
| Approach LOS | C | | | B | B | |
| Intersection Summary | | | | | | |
| HCM Average Control Delay | | | 17.6 | | HCM Level of Service | B |
| HCM Volume to Capacity ratio | | | 0.70 | | | |
| Actuated Cycle Length (s) | | | 64.4 | | Sum of lost time (s) | 13.5 |
| Intersection Capacity Utilization | | | 63.5% | | ICU Level of Service | B |
| Analysis Period (min) | | | 15 | | | |

c Critical Lane Group

HCM Signalized Intersection Capacity Analysis
5: Seneca St & Martinazzi Ave

4/17/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|------|------|------|-------|------|------|-------|-------|------|-------|------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 37 | 0 | 45 | 65 | 0 | 136 | 81 | 337 | 84 | 185 | 212 | 44 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 1.5 | 1.5 | | | 1.5 | 1.5 | 1.5 | 1.5 | | 1.5 | 1.5 | |
| Lane Util. Factor | 1.00 | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Frbp, ped/bikes | 1.00 | 0.99 | | | 1.00 | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Flpb, ped/bikes | 0.99 | 1.00 | | | 1.00 | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | |
| Frt | 1.00 | 0.85 | | | 1.00 | 0.85 | 1.00 | 0.97 | | 1.00 | 0.97 | |
| Flt Protected | 0.95 | 1.00 | | | 0.95 | 1.00 | 0.95 | 1.00 | | 0.95 | 1.00 | |
| Satd. Flow (prot) | 1790 | 1592 | | | 1770 | 1583 | 1804 | 1822 | | 1770 | 1815 | |
| Flt Permitted | 0.75 | 1.00 | | | 0.75 | 1.00 | 0.59 | 1.00 | | 0.34 | 1.00 | |
| Satd. Flow (perm) | 1422 | 1592 | | | 1406 | 1583 | 1115 | 1822 | | 638 | 1815 | |
| Peak-hour factor, PHF | 0.91 | 0.92 | 0.91 | 0.92 | 0.92 | 0.92 | 0.91 | 0.91 | 0.92 | 0.92 | 0.91 | 0.91 |
| Adj. Flow (vph) | 41 | 0 | 49 | 71 | 0 | 148 | 89 | 370 | 91 | 201 | 233 | 48 |
| RTOR Reduction (vph) | 0 | 40 | 0 | 0 | 0 | 121 | 0 | 11 | 0 | 0 | 10 | 0 |
| Lane Group Flow (vph) | 41 | 9 | 0 | 0 | 71 | 27 | 89 | 450 | 0 | 201 | 271 | 0 |
| Confl. Peds. (#/hr) | 10 | | 4 | | | | 1 | | | | | 1 |
| Confl. Bikes (#/hr) | | | | | | | | 2 | | | 3 | |
| Heavy Vehicles (%) | 0% | 2% | 0% | 2% | 2% | 2% | 0% | 1% | 2% | 2% | 2% | 0% |
| Turn Type | Perm | | | Perm | | Perm | pm+pt | | | pm+pt | | |
| Protected Phases | | 4 | | | 8 | | 5 | 2 | | 1 | 6 | |
| Permitted Phases | 4 | | | 8 | | 8 | 2 | | | 6 | | |
| Actuated Green, G (s) | 4.8 | 4.8 | | | 4.8 | 4.8 | 17.1 | 14.2 | | 20.1 | 15.7 | |
| Effective Green, g (s) | 5.3 | 5.3 | | | 5.3 | 5.3 | 18.1 | 14.7 | | 21.1 | 16.2 | |
| Actuated g/C Ratio | 0.18 | 0.18 | | | 0.18 | 0.18 | 0.62 | 0.50 | | 0.72 | 0.55 | |
| Clearance Time (s) | 2.0 | 2.0 | | | 2.0 | 2.0 | 2.0 | 2.0 | | 2.0 | 2.0 | |
| Vehicle Extension (s) | 3.0 | 3.0 | | | 3.0 | 3.0 | 3.0 | 3.0 | | 3.0 | 3.0 | |
| Lane Grp Cap (vph) | 256 | 287 | | | 253 | 285 | 766 | 911 | | 647 | 1000 | |
| v/s Ratio Prot | | 0.01 | | | | | 0.01 | c0.25 | | c0.05 | 0.15 | |
| v/s Ratio Perm | 0.03 | | | c0.05 | 0.02 | 0.06 | | | | 0.17 | | |
| v/c Ratio | 0.16 | 0.03 | | 0.28 | 0.09 | 0.12 | 0.49 | | | 0.31 | 0.27 | |
| Uniform Delay, d1 | 10.2 | 9.9 | | 10.4 | 10.0 | 2.3 | 4.9 | | | 1.9 | 3.5 | |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | | | 1.00 | 1.00 | |
| Incremental Delay, d2 | 0.3 | 0.0 | | 0.6 | 0.1 | 0.1 | 0.4 | | | 0.3 | 0.1 | |
| Delay (s) | 10.5 | 10.0 | | 11.0 | 10.2 | 2.4 | 5.3 | | | 2.2 | 3.6 | |
| Level of Service | B | A | | B | B | A | A | | | A | A | |
| Approach Delay (s) | | 10.2 | | | 10.5 | | | 4.8 | | | 3.0 | |
| Approach LOS | | B | | | B | | | A | | | A | |

Intersection Summary

| | | | |
|-----------------------------------|-------|----------------------|-----|
| HCM Average Control Delay | 5.5 | HCM Level of Service | A |
| HCM Volume to Capacity ratio | 0.37 | | |
| Actuated Cycle Length (s) | 29.4 | Sum of lost time (s) | 4.5 |
| Intersection Capacity Utilization | 53.4% | ICU Level of Service | A |
| Analysis Period (min) | 15 | | |

c Critical Lane Group

HCM Signalized Intersection Capacity Analysis
 8: Nyberg St & Martinazzi Ave

4/17/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|-------|------|------|-------|------|------|------|------|-------|------|------|------|
| Lane Configurations | ↵ | ↶ | | ↵ | ↶ | ↷ | ↵ | ↶ | | | ↶↷ | |
| Volume (vph) | 16 | 1 | 63 | 260 | 37 | 237 | 23 | 240 | 36 | 0 | 314 | 8 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 5.5 | 5.5 | | 5.5 | 5.5 | 5.5 | 5.5 | 5.5 | | | 5.5 | |
| Lane Util. Factor | 1.00 | 1.00 | | 0.95 | 0.95 | 1.00 | 1.00 | 1.00 | | | 0.95 | |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 0.97 | 1.00 | 0.99 | | | 1.00 | |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | 1.00 | |
| Frt | 1.00 | 0.85 | | 1.00 | 1.00 | 0.85 | 1.00 | 0.98 | | | 1.00 | |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 0.96 | 1.00 | 0.95 | 1.00 | | | 1.00 | |
| Satd. Flow (prot) | 1805 | 1603 | | 1698 | 1727 | 1543 | 1683 | 1837 | | | 3559 | |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 0.96 | 1.00 | 0.54 | 1.00 | | | 1.00 | |
| Satd. Flow (perm) | 1805 | 1603 | | 1698 | 1727 | 1543 | 957 | 1837 | | | 3559 | |
| Peak-hour factor, PHF | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 | 0.91 |
| Adj. Flow (vph) | 18 | 1 | 69 | 286 | 41 | 260 | 25 | 264 | 40 | 0 | 345 | 9 |
| RTOR Reduction (vph) | 0 | 63 | 0 | 0 | 0 | 202 | 0 | 8 | 0 | 0 | 3 | 0 |
| Lane Group Flow (vph) | 18 | 7 | 0 | 163 | 164 | 58 | 25 | 296 | 0 | 0 | 351 | 0 |
| Confl. Peds. (#/hr) | 2 | | | | | 2 | 3 | | 16 | 16 | | 3 |
| Confl. Bikes (#/hr) | | | | | | 2 | | | | | | 3 |
| Heavy Vehicles (%) | 0% | 0% | 1% | 1% | 0% | 2% | 7% | 1% | 0% | 0% | 1% | 0% |
| Turn Type | Split | | | Split | | Perm | Perm | | | | | |
| Protected Phases | 8 | 8 | | 4 | 4 | | | 6 | | | 2 | |
| Permitted Phases | | | | | | 4 | 6 | | | | | |
| Actuated Green, G (s) | 3.1 | 3.1 | | 9.1 | 9.1 | 9.1 | 12.5 | 12.5 | | | 12.5 | |
| Effective Green, g (s) | 3.6 | 3.6 | | 9.6 | 9.6 | 9.6 | 13.0 | 13.0 | | | 13.0 | |
| Actuated g/C Ratio | 0.08 | 0.08 | | 0.22 | 0.22 | 0.22 | 0.30 | 0.30 | | | 0.30 | |
| Clearance Time (s) | 6.0 | 6.0 | | 6.0 | 6.0 | 6.0 | 6.0 | 6.0 | | | 6.0 | |
| Vehicle Extension (s) | 2.5 | 2.5 | | 2.5 | 2.5 | 2.5 | 5.0 | 5.0 | | | 5.0 | |
| Lane Grp Cap (vph) | 152 | 135 | | 382 | 388 | 347 | 291 | 559 | | | 1084 | |
| v/s Ratio Prot | c0.01 | 0.00 | | c0.10 | 0.09 | | | | c0.16 | | 0.10 | |
| v/s Ratio Perm | | | | | | 0.04 | 0.03 | | | | | |
| v/c Ratio | 0.12 | 0.05 | | 0.43 | 0.42 | 0.17 | 0.09 | 0.53 | | | 0.32 | |
| Uniform Delay, d1 | 18.1 | 18.0 | | 14.2 | 14.2 | 13.3 | 10.6 | 12.3 | | | 11.5 | |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | 1.00 | |
| Incremental Delay, d2 | 0.3 | 0.1 | | 0.6 | 0.5 | 0.2 | 0.3 | 1.8 | | | 0.4 | |
| Delay (s) | 18.3 | 18.1 | | 14.8 | 14.7 | 13.5 | 10.9 | 14.1 | | | 11.8 | |
| Level of Service | B | B | | B | B | B | B | B | | | B | |
| Approach Delay (s) | | 18.1 | | | 14.2 | | | 13.8 | | | 11.8 | |
| Approach LOS | | B | | | B | | | B | | | B | |

Intersection Summary

| | | | |
|-----------------------------------|-------|----------------------|------|
| HCM Average Control Delay | 13.7 | HCM Level of Service | B |
| HCM Volume to Capacity ratio | 0.44 | | |
| Actuated Cycle Length (s) | 42.7 | Sum of lost time (s) | 16.5 |
| Intersection Capacity Utilization | 48.7% | ICU Level of Service | A |
| Analysis Period (min) | 15 | | |

c Critical Lane Group

HCM Unsignalized Intersection Capacity Analysis
 9: Nyberg St & Site Entrance 3

4/17/2013



| Movement | EBL | EBT | WBT | WBR | SBL | SBR |
|-----------------------------------|------|------|-------|------|----------------------|------|
| Lane Configurations | ↖ | | ↗ | | | ↘ |
| Volume (veh/h) | 37 | 0 | 466 | 60 | 0 | 67 |
| Sign Control | | Free | Free | | Stop | |
| Grade | | 0% | 0% | | 0% | |
| Peak Hour Factor | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 |
| Hourly flow rate (vph) | 42 | 0 | 530 | 68 | 0 | 76 |
| Pedestrians | | | | | 4 | |
| Lane Width (ft) | | | | | 12.0 | |
| Walking Speed (ft/s) | | | | | 4.0 | |
| Percent Blockage | | | | | 0 | |
| Right turn flare (veh) | | | | | | |
| Median type | | None | None | | | |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | | 232 | | | | |
| pX, platoon unblocked | | | | | | |
| vC, conflicting volume | 602 | | | | 652 | 303 |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | 602 | | | | 652 | 303 |
| tC, single (s) | 4.1 | | | | 6.8 | 6.9 |
| tC, 2 stage (s) | | | | | | |
| tF (s) | 2.2 | | | | 3.5 | 3.3 |
| p0 queue free % | 96 | | | | 100 | 89 |
| cM capacity (veh/h) | 982 | | | | 387 | 697 |
| Direction, Lane # | EB 1 | WB 1 | WB 2 | SB 1 | | |
| Volume Total | 42 | 353 | 245 | 76 | | |
| Volume Left | 42 | 0 | 0 | 0 | | |
| Volume Right | 0 | 0 | 68 | 76 | | |
| cSH | 982 | 1700 | 1700 | 697 | | |
| Volume to Capacity | 0.04 | 0.21 | 0.14 | 0.11 | | |
| Queue Length 95th (ft) | 3 | 0 | 0 | 10 | | |
| Control Delay (s) | 8.8 | 0.0 | 0.0 | 10.8 | | |
| Lane LOS | A | | | B | | |
| Approach Delay (s) | 8.8 | 0.0 | | 10.8 | | |
| Approach LOS | | | | B | | |
| Intersection Summary | | | | | | |
| Average Delay | | | 1.7 | | | |
| Intersection Capacity Utilization | | | 25.7% | | ICU Level of Service | A |
| Analysis Period (min) | | | 15 | | | |

HCM Signalized Intersection Capacity Analysis
 10: Tualatin Sherwood Rd & Site Entrance 4













4/17/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|------|-------|-------|------|-------|------|----------------------|------|-------|-------|------|------|
| Lane Configurations | ↵ | ↕↕ | | ↵↵ | ↕↕ | ↵ | | ↕ | ↵ | ↵↵ | ↕ | |
| Volume (vph) | 180 | 1335 | 59 | 257 | 1458 | 361 | 57 | 25 | 248 | 373 | 40 | 190 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 6.0 | | 4.5 | 6.0 | 6.0 | | 5.0 | 4.5 | 5.0 | 5.0 | |
| Lane Util. Factor | 1.00 | *0.75 | | 0.97 | 0.91 | 1.00 | | 1.00 | 1.00 | 0.97 | 1.00 | |
| Frpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 0.97 | | 1.00 | 1.00 | 1.00 | 0.98 | |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | |
| Frt | 1.00 | 0.99 | | 1.00 | 1.00 | 0.85 | | 1.00 | 0.85 | 1.00 | 0.88 | |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | 1.00 | | 0.97 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (prot) | 1805 | 4091 | | 3502 | 4988 | 1565 | | 1799 | 1599 | 3467 | 1634 | |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | 1.00 | | 0.97 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (perm) | 1805 | 4091 | | 3502 | 4988 | 1565 | | 1799 | 1599 | 3467 | 1634 | |
| Peak-hour factor, PHF | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 |
| Adj. Flow (vph) | 184 | 1362 | 60 | 262 | 1488 | 368 | 58 | 26 | 253 | 381 | 41 | 194 |
| RTOR Reduction (vph) | 0 | 3 | 0 | 0 | 0 | 201 | 0 | 0 | 0 | 0 | 164 | 0 |
| Lane Group Flow (vph) | 184 | 1419 | 0 | 262 | 1488 | 167 | 0 | 84 | 253 | 381 | 71 | 0 |
| Confl. Peds. (#/hr) | | | | | | | 4 | | | | | 9 |
| Confl. Bikes (#/hr) | | | | | 1 | | | 1 | | 1 | | |
| Heavy Vehicles (%) | 0% | 4% | 0% | 0% | 4% | 0% | 3% | 0% | 1% | 1% | 0% | 0% |
| Turn Type | Prot | | | Prot | | Perm | Split | | pt+ov | Split | | |
| Protected Phases | 5 | 2 | | 1 | 6 | | 8 | 8 | 18 | 4 | 4 | |
| Permitted Phases | | | | | | 6 | | | | | | |
| Actuated Green, G (s) | 14.8 | 49.6 | | 17.0 | 51.8 | 51.8 | | 8.5 | 25.5 | 17.4 | 17.4 | |
| Effective Green, g (s) | 15.3 | 50.1 | | 17.5 | 52.3 | 52.3 | | 9.0 | 26.5 | 17.9 | 17.9 | |
| Actuated g/C Ratio | 0.13 | 0.44 | | 0.15 | 0.45 | 0.45 | | 0.08 | 0.23 | 0.16 | 0.16 | |
| Clearance Time (s) | 5.0 | 6.5 | | 5.0 | 6.5 | 6.5 | | 5.5 | | 5.5 | 5.5 | |
| Vehicle Extension (s) | 2.5 | 4.0 | | 2.5 | 4.0 | 4.0 | | 2.5 | | 2.5 | 2.5 | |
| Lane Grp Cap (vph) | 240 | 1782 | | 533 | 2268 | 712 | | 141 | 368 | 540 | 254 | |
| v/s Ratio Prot | 0.10 | c0.35 | | 0.07 | c0.30 | | | 0.05 | c0.16 | c0.11 | 0.04 | |
| v/s Ratio Perm | | | | | | 0.11 | | | | | | |
| v/c Ratio | 0.77 | 0.80 | | 0.49 | 0.66 | 0.24 | | 0.60 | 0.69 | 0.71 | 0.28 | |
| Uniform Delay, d1 | 48.1 | 28.0 | | 44.7 | 24.4 | 19.1 | | 51.2 | 40.5 | 46.1 | 42.9 | |
| Progression Factor | 0.90 | 1.35 | | 0.96 | 0.90 | 1.07 | | 1.00 | 1.00 | 1.00 | 1.00 | |
| Incremental Delay, d2 | 10.1 | 2.9 | | 0.3 | 1.0 | 0.5 | | 5.5 | 4.8 | 3.9 | 0.4 | |
| Delay (s) | 53.6 | 40.7 | | 43.3 | 23.0 | 20.9 | | 56.8 | 45.3 | 49.9 | 43.3 | |
| Level of Service | D | D | | D | C | C | | E | D | D | D | |
| Approach Delay (s) | | 42.2 | | | 25.2 | | | 48.2 | | | 47.4 | |
| Approach LOS | | D | | | C | | | D | | | D | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 35.6 | | | | HCM Level of Service | | | | D | |
| HCM Volume to Capacity ratio | | | 0.71 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 115.0 | | | | Sum of lost time (s) | | 15.5 | | | |
| Intersection Capacity Utilization | | | 77.3% | | | | ICU Level of Service | | D | | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |

c Critical Lane Group

HCM Signalized Intersection Capacity Analysis
 12: Tualatin Sherwood Rd & I-5 SB Ramps

4/17/2013

| |  |  |  |  |  |  |  |  |  |  |  |  |
|-----------------------------------|---|---|---|---|---|---|--|---|---|---|---|---|
| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
| Lane Configurations | | ↑↑↑ | ↑ | ↑ | ↑↑ | | | | | ↑ | ↑ | ↑↑ |
| Volume (vph) | 0 | 1484 | 480 | 193 | 1150 | 0 | 0 | 0 | 0 | 620 | 3 | 965 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | | 5.5 | 5.5 | 5.5 | 5.5 | | | | | 5.5 | 5.5 | 5.5 |
| Lane Util. Factor | | *0.75 | 1.00 | 1.00 | 0.95 | | | | | 0.95 | 0.95 | 0.88 |
| Frbp, ped/bikes | | 1.00 | 1.00 | 1.00 | 1.00 | | | | | 1.00 | 1.00 | 1.00 |
| Flpb, ped/bikes | | 1.00 | 1.00 | 1.00 | 1.00 | | | | | 1.00 | 1.00 | 1.00 |
| Frt | | 1.00 | 0.85 | 1.00 | 1.00 | | | | | 1.00 | 1.00 | 0.85 |
| Flt Protected | | 1.00 | 1.00 | 0.95 | 1.00 | | | | | 0.95 | 0.95 | 1.00 |
| Satd. Flow (prot) | | 4150 | 1568 | 1787 | 3471 | | | | | 1681 | 1683 | 2760 |
| Flt Permitted | | 1.00 | 1.00 | 0.95 | 1.00 | | | | | 0.95 | 0.95 | 1.00 |
| Satd. Flow (perm) | | 4150 | 1568 | 1787 | 3471 | | | | | 1681 | 1683 | 2760 |
| Peak-hour factor, PHF | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 | 0.99 |
| Adj. Flow (vph) | 0 | 1499 | 485 | 195 | 1162 | 0 | 0 | 0 | 0 | 626 | 3 | 975 |
| RTOR Reduction (vph) | 0 | 0 | 242 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 0 | 40 |
| Lane Group Flow (vph) | 0 | 1499 | 243 | 195 | 1162 | 0 | 0 | 0 | 0 | 313 | 316 | 935 |
| Confl. Bikes (#/hr) | | 1 | | | 2 | | | | | | | |
| Heavy Vehicles (%) | 0% | 3% | 3% | 1% | 4% | 0% | 0% | 0% | 0% | 2% | 20% | 3% |
| Turn Type | | | Perm | Prot | | | | | | Split | | custom |
| Protected Phases | | 2 | | 1 | 6 | | | | | 4 | 4 | 4.5 |
| Permitted Phases | | | 2 | | | | | | | | | |
| Actuated Green, G (s) | | 49.4 | 49.4 | 17.0 | 55.4 | | | | | 30.6 | 30.6 | 47.6 |
| Effective Green, g (s) | | 49.9 | 49.9 | 17.5 | 55.9 | | | | | 31.1 | 31.1 | 44.6 |
| Actuated g/C Ratio | | 0.43 | 0.43 | 0.15 | 0.49 | | | | | 0.27 | 0.27 | 0.39 |
| Clearance Time (s) | | 6.0 | 6.0 | 6.0 | 6.0 | | | | | 6.0 | 6.0 | |
| Vehicle Extension (s) | | 6.1 | 6.1 | 2.3 | 6.1 | | | | | 2.3 | 2.3 | |
| Lane Grp Cap (vph) | | 1801 | 680 | 272 | 1687 | | | | | 455 | 455 | 1070 |
| v/s Ratio Prot | | c0.36 | | c0.11 | 0.33 | | | | | 0.19 | 0.19 | c0.34 |
| v/s Ratio Perm | | | 0.16 | | | | | | | | | |
| v/c Ratio | | 0.83 | 0.36 | 0.72 | 0.69 | | | | | 0.69 | 0.69 | 0.87 |
| Uniform Delay, d1 | | 28.8 | 21.8 | 46.4 | 22.8 | | | | | 37.6 | 37.7 | 32.6 |
| Progression Factor | | 0.60 | 0.38 | 0.88 | 0.62 | | | | | 1.00 | 1.00 | 1.00 |
| Incremental Delay, d2 | | 3.3 | 1.0 | 7.3 | 2.2 | | | | | 3.7 | 4.0 | 7.9 |
| Delay (s) | | 20.5 | 9.4 | 48.1 | 16.3 | | | | | 41.3 | 41.7 | 40.5 |
| Level of Service | | C | A | D | B | | | | | D | D | D |
| Approach Delay (s) | | 17.8 | | | 20.9 | | | 0.0 | | | 40.9 | |
| Approach LOS | | B | | | C | | | A | | | D | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 26.1 | | | HCM Level of Service | | | | C | | |
| HCM Volume to Capacity ratio | | | 0.89 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 115.0 | | | Sum of lost time (s) | | | 22.0 | | | |
| Intersection Capacity Utilization | | | 74.7% | | | ICU Level of Service | | | | D | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |
| c Critical Lane Group | | | | | | | | | | | | |

HCM Signalized Intersection Capacity Analysis
 13: Tualatin Sherwood Rd & I-5 NB Ramps

4/17/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|------|-------|-------|------|------|------|----------------------|-------|------|------|------|------|
| Lane Configurations | | ↑↑ | ↑↑ | | ↑↑ | ↑ | ↑ | ↑ | ↑ | | | |
| Volume (vph) | 0 | 1110 | 998 | 0 | 668 | 666 | 672 | 0 | 219 | 0 | 0 | 0 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | | 5.5 | 5.5 | | 6.0 | 6.0 | 5.5 | 5.5 | 5.5 | | | |
| Lane Util. Factor | | 0.95 | 0.88 | | 0.95 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Frbp, ped/bikes | | 1.00 | 0.98 | | 1.00 | 1.00 | 1.00 | 1.00 | 0.98 | | | |
| Flpb, ped/bikes | | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Frt | | 1.00 | 0.85 | | 1.00 | 0.85 | 1.00 | 1.00 | 0.85 | | | |
| Flt Protected | | 1.00 | 1.00 | | 1.00 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Satd. Flow (prot) | | 3574 | 2694 | | 3574 | 1583 | 1618 | 1618 | 1559 | | | |
| Flt Permitted | | 1.00 | 1.00 | | 1.00 | 1.00 | 0.95 | 0.95 | 1.00 | | | |
| Satd. Flow (perm) | | 3574 | 2694 | | 3574 | 1583 | 1618 | 1618 | 1559 | | | |
| Peak-hour factor, PHF | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 | 0.95 |
| Adj. Flow (vph) | 0 | 1168 | 1051 | 0 | 703 | 701 | 707 | 0 | 231 | 0 | 0 | 0 |
| RTOR Reduction (vph) | 0 | 0 | 388 | 0 | 0 | 262 | 0 | 0 | 28 | 0 | 0 | 0 |
| Lane Group Flow (vph) | 0 | 1168 | 663 | 0 | 703 | 439 | 353 | 354 | 203 | 0 | 0 | 0 |
| Confl. Peds. (#/hr) | | | 1 | 1 | | | 1 | | 2 | 2 | | 1 |
| Confl. Bikes (#/hr) | | 1 | | | 5 | | | | | 1 | | |
| Heavy Vehicles (%) | 0% | 1% | 3% | 0% | 1% | 2% | 6% | 20% | 2% | 0% | 0% | 0% |
| Turn Type | | | Perm | | | Perm | Split | | Perm | | | |
| Protected Phases | | 2 | | | 6 | | 8 | 8 | | | | |
| Permitted Phases | | | 2 | | | 6 | | | 8 | | | |
| Actuated Green, G (s) | | 72.0 | 72.0 | | 71.5 | 71.5 | 31.0 | 31.0 | 31.0 | | | |
| Effective Green, g (s) | | 72.5 | 72.5 | | 72.0 | 72.0 | 31.5 | 31.5 | 31.5 | | | |
| Actuated g/C Ratio | | 0.63 | 0.63 | | 0.63 | 0.63 | 0.27 | 0.27 | 0.27 | | | |
| Clearance Time (s) | | 6.0 | 6.0 | | 6.5 | 6.5 | 6.0 | 6.0 | 6.0 | | | |
| Vehicle Extension (s) | | 6.1 | 6.1 | | 4.2 | 4.2 | 2.3 | 2.3 | 2.3 | | | |
| Lane Grp Cap (vph) | | 2253 | 1698 | | 2238 | 991 | 443 | 443 | 427 | | | |
| v/s Ratio Prot | | c0.33 | | | 0.20 | | 0.22 | c0.22 | | | | |
| v/s Ratio Perm | | | 0.25 | | | 0.28 | | | 0.13 | | | |
| v/c Ratio | | 0.52 | 0.39 | | 0.31 | 0.44 | 0.80 | 0.80 | 0.47 | | | |
| Uniform Delay, d1 | | 11.7 | 10.4 | | 10.0 | 11.1 | 38.8 | 38.8 | 34.8 | | | |
| Progression Factor | | 1.39 | 3.10 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Incremental Delay, d2 | | 0.6 | 0.4 | | 0.4 | 1.4 | 9.2 | 9.3 | 0.5 | | | |
| Delay (s) | | 16.7 | 32.8 | | 10.4 | 12.6 | 48.0 | 48.1 | 35.3 | | | |
| Level of Service | | B | C | | B | B | D | D | D | | | |
| Approach Delay (s) | | 24.3 | | | 11.5 | | | 44.9 | | | 0.0 | |
| Approach LOS | | C | | | B | | | D | | | A | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 24.6 | | | | HCM Level of Service | | | | | C |
| HCM Volume to Capacity ratio | | | 0.60 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 115.0 | | | | Sum of lost time (s) | | | | | 11.0 |
| Intersection Capacity Utilization | | | 69.4% | | | | ICU Level of Service | | | | | C |
| Analysis Period (min) | | | 15 | | | | | | | | | |

c Critical Lane Group

HCM Signalized Intersection Capacity Analysis
 14: Tualatin Sherwood Rd & Nyberg Woods

4/17/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|-----------------------------------|-------|------|-------|------|-------|----------------------|------|-------|------|------|------|------|
| Lane Configurations | | | | | | | | | | | | |
| Volume (vph) | 524 | 593 | 57 | 15 | 732 | 101 | 103 | 11 | 12 | 101 | 11 | 322 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 5.5 | 5.5 | | 5.5 | 5.5 | | | 5.5 | 5.5 | | 5.5 | 5.5 |
| Lane Util. Factor | 0.97 | 0.95 | | 1.00 | 0.95 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 0.99 | | 1.00 | 0.99 |
| Flpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Frt | 1.00 | 0.99 | | 1.00 | 0.98 | | | 1.00 | 0.85 | | 1.00 | 0.85 |
| Flt Protected | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.96 | 1.00 | | 0.96 | 1.00 |
| Satd. Flow (prot) | 3502 | 3486 | | 1805 | 3505 | | | 1768 | 1593 | | 1799 | 1594 |
| Flt Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | | | 0.66 | 1.00 | | 0.66 | 1.00 |
| Satd. Flow (perm) | 3502 | 3486 | | 1805 | 3505 | | | 1229 | 1593 | | 1248 | 1594 |
| Peak-hour factor, PHF | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 | 0.96 |
| Adj. Flow (vph) | 546 | 618 | 59 | 16 | 762 | 105 | 107 | 11 | 12 | 105 | 11 | 335 |
| RTOR Reduction (vph) | 0 | 5 | 0 | 0 | 9 | 0 | 0 | 0 | 10 | 0 | 0 | 279 |
| Lane Group Flow (vph) | 546 | 672 | 0 | 16 | 858 | 0 | 0 | 118 | 2 | 0 | 116 | 56 |
| Confl. Peds. (#/hr) | 8 | | 2 | 2 | | 8 | 1 | | 2 | 2 | | 1 |
| Confl. Bikes (#/hr) | | 1 | | | 3 | | | | | | | |
| Heavy Vehicles (%) | 0% | 2% | 2% | 0% | 1% | 0% | 3% | 0% | 0% | 1% | 0% | 0% |
| Turn Type | Prot | | | Prot | | | Perm | | Perm | Perm | | Perm |
| Protected Phases | 5 | 2 | | 1 | 6 | | | 8 | | | 4 | |
| Permitted Phases | | | | | | | 8 | | 8 | 4 | | 4 |
| Actuated Green, G (s) | 14.5 | 38.4 | | 0.8 | 24.7 | | | 10.9 | 10.9 | | 10.9 | 10.9 |
| Effective Green, g (s) | 15.0 | 38.9 | | 1.3 | 25.2 | | | 11.4 | 11.4 | | 11.4 | 11.4 |
| Actuated g/C Ratio | 0.22 | 0.57 | | 0.02 | 0.37 | | | 0.17 | 0.17 | | 0.17 | 0.17 |
| Clearance Time (s) | 6.0 | 6.0 | | 6.0 | 6.0 | | | 6.0 | 6.0 | | 6.0 | 6.0 |
| Vehicle Extension (s) | 2.3 | 2.5 | | 2.4 | 2.5 | | | 2.4 | 2.4 | | 2.3 | 2.3 |
| Lane Grp Cap (vph) | 771 | 1991 | | 34 | 1297 | | | 206 | 267 | | 209 | 267 |
| v/s Ratio Prot | c0.16 | 0.19 | | 0.01 | c0.24 | | | | | | | |
| v/s Ratio Perm | | | | | | | | c0.10 | 0.00 | | 0.09 | 0.04 |
| v/c Ratio | 0.71 | 0.34 | | 0.47 | 0.66 | | | 0.57 | 0.01 | | 0.56 | 0.21 |
| Uniform Delay, d1 | 24.5 | 7.8 | | 33.1 | 17.9 | | | 26.1 | 23.6 | | 26.0 | 24.5 |
| Progression Factor | 1.00 | 1.00 | | 1.00 | 1.00 | | | 1.00 | 1.00 | | 1.00 | 1.00 |
| Incremental Delay, d2 | 2.6 | 0.1 | | 6.6 | 1.2 | | | 3.0 | 0.0 | | 2.3 | 0.2 |
| Delay (s) | 27.2 | 7.8 | | 39.7 | 19.0 | | | 29.1 | 23.6 | | 28.3 | 24.7 |
| Level of Service | C | A | | D | B | | | C | C | | C | C |
| Approach Delay (s) | | 16.5 | | | 19.4 | | | 28.6 | | | 25.6 | |
| Approach LOS | | B | | | B | | | C | | | C | |
| Intersection Summary | | | | | | | | | | | | |
| HCM Average Control Delay | | | 19.6 | | | HCM Level of Service | | | | B | | |
| HCM Volume to Capacity ratio | | | 0.66 | | | | | | | | | |
| Actuated Cycle Length (s) | | | 68.1 | | | Sum of lost time (s) | | | 16.5 | | | |
| Intersection Capacity Utilization | | | 65.6% | | | ICU Level of Service | | | C | | | |
| Analysis Period (min) | | | 15 | | | | | | | | | |

c Critical Lane Group

HCM Signalized Intersection Capacity Analysis
 17: Tualatin Sherwood Rd & Martinazzi Ave

4/17/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR | | |
|-----------------------------------|---------------------|-------|------|------|-------|------|------|-------|------|------|-------|----------------------|----------------------|---|
| Lane Configurations | | | | | | | | | | | | | | |
| Volume (vph) | 75 | 1194 | 141 | 0 | 1163 | 0 | 100 | 225 | 252 | 129 | 415 | 93 | | |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | | |
| Total Lost time (s) | 4.5 | 5.5 | | | 5.5 | | 4.5 | 5.5 | 5.5 | 4.5 | 5.5 | | | |
| Lane Util. Factor | 1.00 | 0.95 | | | 0.95 | | 1.00 | 1.00 | 1.00 | 1.00 | 0.95 | | | |
| Frbp, ped/bikes | 1.00 | 1.00 | | | 1.00 | | 1.00 | 1.00 | 0.96 | 1.00 | 1.00 | | | |
| Flpb, ped/bikes | 1.00 | 1.00 | | | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Frt | 1.00 | 0.98 | | | 1.00 | | 1.00 | 1.00 | 0.85 | 1.00 | 0.97 | | | |
| Flt Protected | 0.95 | 1.00 | | | 1.00 | | 0.95 | 1.00 | 1.00 | 0.95 | 1.00 | | | |
| Satd. Flow (prot) | 1719 | 3430 | | | 3438 | | 1770 | 1863 | 1537 | 1787 | 3466 | | | |
| Flt Permitted | 0.95 | 1.00 | | | 1.00 | | 0.95 | 1.00 | 1.00 | 0.95 | 1.00 | | | |
| Satd. Flow (perm) | 1719 | 3430 | | | 3438 | | 1770 | 1863 | 1537 | 1787 | 3466 | | | |
| Peak-hour factor, PHF | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | 0.94 | | |
| Adj. Flow (vph) | 80 | 1270 | 150 | 0 | 1237 | 0 | 106 | 239 | 268 | 137 | 441 | 99 | | |
| RTOR Reduction (vph) | 0 | 6 | 0 | 0 | 0 | 0 | 0 | 0 | 104 | 0 | 19 | 0 | | |
| Lane Group Flow (vph) | 80 | 1414 | 0 | 0 | 1237 | 0 | 106 | 239 | 164 | 137 | 521 | 0 | | |
| Confl. Peds. (#/hr) | | | | | | 6 | | | 23 | | | 3 | | |
| Heavy Vehicles (%) | 5% | 4% | 0% | 0% | 5% | 0% | 2% | 2% | 1% | 1% | 1% | 1% | | |
| Turn Type | Prot | | | | | | Prot | | Perm | | Prot | | | |
| Protected Phases | 5 | 2 | | | 6 | | 3 | 8 | | 7 | 4 | | | |
| Permitted Phases | | | | | | | | | 8 | | | | | |
| Actuated Green, G (s) | 8.6 | 66.5 | | | 52.9 | | 10.6 | 17.9 | 17.9 | 13.6 | 20.9 | | | |
| Effective Green, g (s) | 9.1 | 67.0 | | | 53.4 | | 11.1 | 18.4 | 18.4 | 14.1 | 21.4 | | | |
| Actuated g/C Ratio | 0.08 | 0.58 | | | 0.46 | | 0.10 | 0.16 | 0.16 | 0.12 | 0.19 | | | |
| Clearance Time (s) | 5.0 | 6.0 | | | 6.0 | | 5.0 | 6.0 | 6.0 | 5.0 | 6.0 | | | |
| Vehicle Extension (s) | 2.0 | 3.5 | | | 3.5 | | 3.0 | 2.0 | 2.0 | 3.0 | 2.0 | | | |
| Lane Grp Cap (vph) | 136 | 1998 | | | 1596 | | 171 | 298 | 246 | 219 | 645 | | | |
| v/s Ratio Prot | 0.05 | c0.41 | | | c0.36 | | 0.06 | c0.13 | | 0.08 | c0.15 | | | |
| v/s Ratio Perm | | | | | | | | | 0.11 | | | | | |
| v/c Ratio | 0.59 | 0.71 | | | 0.78 | | 0.62 | 0.80 | 0.67 | 0.63 | 0.81 | | | |
| Uniform Delay, d1 | 51.1 | 17.0 | | | 25.8 | | 49.9 | 46.5 | 45.4 | 47.9 | 44.8 | | | |
| Progression Factor | 1.00 | 1.00 | | | 0.56 | | 1.00 | 1.00 | 1.00 | 1.00 | 1.00 | | | |
| Incremental Delay, d2 | 4.1 | 2.1 | | | 3.0 | | 6.5 | 13.6 | 5.2 | 5.5 | 7.0 | | | |
| Delay (s) | 55.3 | 19.2 | | | 17.5 | | 56.5 | 60.1 | 50.6 | 53.4 | 51.8 | | | |
| Level of Service | E | B | | | B | | E | E | D | D | D | | | |
| Approach Delay (s) | | 21.1 | | | 17.5 | | | 55.3 | | | 52.1 | | | |
| Approach LOS | | C | | | B | | | E | | | D | | | |
| Intersection Summary | | | | | | | | | | | | | | |
| HCM Average Control Delay | | 30.4 | | | | | | | | | | HCM Level of Service | C | |
| HCM Volume to Capacity ratio | | 0.83 | | | | | | | | | | | | |
| Actuated Cycle Length (s) | | 115.0 | | | | | | | 22.0 | | | | Sum of lost time (s) | |
| Intersection Capacity Utilization | | 81.1% | | | | | | | | | | | ICU Level of Service | D |
| Analysis Period (min) | | 15 | | | | | | | | | | | | |
| c | Critical Lane Group | | | | | | | | | | | | | |

HCM Unsignalized Intersection Capacity Analysis
 22: SW Boones Ferry Rd & RIRO North Access

4/17/2013



| Movement | EBL | EBR | NBL | NBR | SWL | SWR |
|-----------------------------------|-------------|-------------|-------------|----------------------|------|------|
| Lane Configurations | RT | | | LT | | RT |
| Volume (veh/h) | 822 | 23 | 0 | 49 | 0 | 747 |
| Sign Control | Free | | Stop | | Free | |
| Grade | 0% | | 0% | | 0% | |
| Peak Hour Factor | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 | 0.92 |
| Hourly flow rate (vph) | 893 | 25 | 0 | 53 | 0 | 812 |
| Pedestrians | | | | | | |
| Lane Width (ft) | | | | | | |
| Walking Speed (ft/s) | | | | | | |
| Percent Blockage | | | | | | |
| Right turn flare (veh) | | | | | | |
| Median type | None | | | | None | |
| Median storage (veh) | | | | | | |
| Upstream signal (ft) | 324 | | | | | |
| pX, platoon unblocked | | | 0.77 | 0.77 | 0.77 | |
| vC, conflicting volume | | | 1718 | 906 | 918 | |
| vC1, stage 1 conf vol | | | | | | |
| vC2, stage 2 conf vol | | | | | | |
| vCu, unblocked vol | | | 1783 | 728 | 745 | |
| tC, single (s) | | | 6.4 | 6.2 | 4.1 | |
| tC, 2 stage (s) | | | | | | |
| tF (s) | | | 3.5 | 3.3 | 2.2 | |
| p0 queue free % | | | 100 | 84 | 100 | |
| cM capacity (veh/h) | | | 69 | 326 | 664 | |
| Direction, Lane # | EB 1 | NB 1 | SW 1 | | | |
| Volume Total | 918 | 53 | 812 | | | |
| Volume Left | 0 | 0 | 0 | | | |
| Volume Right | 25 | 53 | 0 | | | |
| cSH | 1700 | 326 | 1700 | | | |
| Volume to Capacity | 0.54 | 0.16 | 0.48 | | | |
| Queue Length 95th (ft) | 0 | 15 | 0 | | | |
| Control Delay (s) | 0.0 | 18.2 | 0.0 | | | |
| Lane LOS | | C | | | | |
| Approach Delay (s) | 0.0 | 18.2 | 0.0 | | | |
| Approach LOS | | C | | | | |
| Intersection Summary | | | | | | |
| Average Delay | | | 0.5 | | | |
| Intersection Capacity Utilization | | | 50.3% | ICU Level of Service | | A |
| Analysis Period (min) | | | 15 | | | |



KITTELSON & ASSOCIATES, INC.

TRANSPORTATION ENGINEERING / PLANNING

610 SW Alder Street, Suite 700, Portland, OR 97205 P 503.228.5230 F 503.273.8169

May 16, 2013

Project #: 12116

Kaaren Hofmann/Tony Doran
City of Tualatin
18880 SW Martinazzi Avenue
Tualatin, OR 97062

RE: Additional Nyberg Rivers Traffic Analysis

Dear Kaaren/Tony,

At your request, we have prepared the following traffic analysis to supplement our *April 2013 Nyberg Rivers Transportation Impact Analysis (TIA)*. The request for supplemental information was initially outlined in your May 6, 2013 e-mail and discussed in more detail at our follow up meeting on May 7, 2013. For documentation purposes, your request is shown in italics followed by our response:

Comment/Request #1

We would still like to see the following scenarios run-

- 1. Shows Seneca Street extension with signal – other driveways on Martinazzi Avenue closed.*
- 2. Shows no Seneca Street extension but shows true LOS at City Hall driveway.*
- 3. Shows no Seneca Street extension and no driveway access for the development.*

Response to Scenario Request #1:

The first scenario (Seneca Street extension with signal) has been completed and is included in the April 2013 TIA. Figures 11A and 11B provide the volume assignments for this scenario and Table 12 summarizes the operational results of this analysis. In this scenario the only driveway on SW Martinazzi Avenue that is assumed to remain open is the driveway closest to Nyberg Road that serves the retail development that is not part of the Nyberg Rivers development application.

Response to Scenario Request #2

In an effort to provide more detailed information regarding the second scenario (no Seneca Street extension) the operation of the SW Martinazzi Avenue/City Library driveway, a more precise measurement of delay and capacity was calculated for each of the three critical unsignalized movements during the weekday p.m. peak hour based on extracted video data. Table 1 below summarizes the results of the analysis. As shown in the table, field-measured delay and capacity for

the three critical unsignalized movements indicate that the intersection is operating relatively consistent with the operations reported in the April 2013 TIA.

Table 1 – Detailed Operations of the SW Martinazzi Avenue/City Library Driveway (Existing Conditions)

| | Existing Traffic Conditions SW Martinazzi Avenue/ City Library Driveway |
|----------------|---|
| SB LT Movement | LOS = B |
| | Control Delay = 11.3 sec |
| | V/C = 0.18 |
| WB LT Movement | LOS = D |
| | Control Delay = 30.3 sec |
| | V/C = 0.16 |
| WB RT Movement | LOS = B |
| | Control Delay = 14.1 sec |
| | V/C = 0.18 |

Since the project is adding very little additional conflicting traffic for the three movements identified above, the field measured capacity represents a reasonable estimate of capacity for the total traffic condition for the major street left and minor street right turn movements. The minor street westbound left turn capacity will be slightly lower given the increased southbound left turn demand. Table 2 below illustrates the estimated LOS for total traffic conditions based on the field measurements. As indicated in Table 2, the intersection will meet City standards for unsignalized intersection operations. *Appendix A contains the calculation worksheets.*

Table 2 – Detailed Operations of the SW Martinazzi Avenue/City Library Driveway (2014 Total Conditions)

| | 2014 Total Traffic Conditions SW Martinazzi Avenue/ City Library Driveway |
|----------------|---|
| SB LT Movement | LOS = B |
| | Control Delay = 12.1 sec |
| | V/C = 0.26 |
| WB LT Movement | LOS = E |
| | Control Delay = 43.8 sec |
| | V/C = 0.29 |
| WB RT Movement | LOS = C |
| | Control Delay = 15.7 |
| | V/C = 0.30 |

In addition to the field measured operations analysis, the impacts of vehicle queue spillback from the SW Martinazzi Avenue/SW Boones Ferry Intersection were also examined in more detail in attempt to provide City staff with additional operational and safety information as requested. During the weekday

p.m. peak hour, it was noted that there are instances when the northbound left-turn vehicle queue at the SW Martinazzi Avenue/SW Boones Ferry Road intersection spills back to and beyond the SW Martinazzi Avenue/City Library driveway. When this occurs, the majority of queued vehicles leave a gap so that southbound left-turn vehicles can enter the City Library driveway (this is expected as most drivers try to avoid blocking movements at intersections). However, there are instances where the vehicle queue blocks the driveway.

Based on observations taken from video data, the existing percentage of time when a southbound left-turning vehicle is blocked is approximately 1.4% of the peak hour (less than one minute). With the additional traffic estimated to be generated by the proposed redevelopment project, it is estimated that the percentage of blockage time will increase 40 seconds to approximately 2.1%, which represents an insignificant change relative to existing conditions. In lay terms, the driveway will perform in a manner that is quite similar to existing conditions. The only movement that will experience a significant increase in delay is the westbound left turn. This movement will continue to meet City standards. Further, the project is only anticipated to add 5 five vehicles during a typical weekday p.m. peak hour, and drivers have several alternative routes to avoid this movement (i.e. turning right from the development's two access driveways onto Nyberg Road).

Response to Scenario Request #3

With regard to the third scenario (no Seneca extension and no access to the City Hall/Library driveway from the Nyberg Rivers development), this site layout and access scenario was not studied. In general, it was felt that the scenario would be contrary to good planning, it does not advance the City's connectivity goals, and is contrary to the City's recently adopted Transportation System Plan concept of a "Loop Road" and Seneca Street extension.

Comment/Request #2

The intersections of Nyberg/Martinazzi, Tualatin-Sherwood/Martinazzi, Boones Ferry Road/Martinazzi, Seneca/Martinazzi, and development driveways were not added to the queuing report. There was only a brief footnote that if you did the queuing the LOS may be different. Also no discussion of safety at these intersections with additional trips and no revisions made.

Response: Table 3 summarizes the estimated 95th percentile queuing information along the SW Martinazzi Avenue corridor for background and total traffic conditions. As indicated, the Nyberg Rivers project will have an insignificant to no impact on queuing at the intersections along SW Martinazzi Avenue. The additional traffic added by the project to the intersections along SW Martinazzi Avenue is not expected to change the safety performance characteristics of these intersections relative to existing conditions beyond a small increase in exposure due to the small increase in traffic volumes. *Appendix B contains the queuing work sheets.*

Table 3 – SW Martinazzi Avenue Corridor Queuing

| Intersection | Movement | Estimated 95 th Percentile Queue (ft) | | | |
|--|----------|--|---------------|---------------------------|---------------|
| | | Weekday PM Peak Hour | | Saturday Midday Peak Hour | |
| | | Background Traffic | Total Traffic | Background Traffic | Total Traffic |
| SW Martinazzi Avenue/ SW Boones Ferry Road | NB LT | 325 | 325 | 125 | 150 |
| | NB RT | 250 | 275 | 150 | 175 |
| | WB LT | 350 | 375 | 150 | 200 |
| | EB RT | 150 | 175 | 75 | 100 |
| SW Martinazzi Avenue/ Site Driveway (library) | SB LT | 75 | 100 | 25 | 50 |
| | WB LT | 75 | 100 | 25 | 50 |
| | WB RT | 50 | 50 | 25 | 50 |
| SW Martinazzi Avenue/ SW Seneca Street/ Potential Site Access Driveway* | SB LT | - | 50 | - | 50 |
| | SB THRT | - | 125 | - | 75 |
| | WB RT | - | 100 | - | 75 |
| | WB THLT | - | 50 | - | 50 |
| | NB THRT | - | 200 | - | 100 |
| | NB LT | - | 50 | - | 25 |
| SW Martinazzi Avenue/ Nyberg Road | SB TH | 100 | 100 | 75 | 75 |
| | NB THRT | 125 | 150 | 125 | 125 |
| | WB LT | 100 | 100 | 75 | 75 |
| | WB RT | 150 | 150 | 125 | 125 |
| SW Martinazzi Avenue/ SW Tuafatin-Sherwood Road | SB THRT | 350 | 350 | 225 | 225 |
| | SB LT | 250 | 250 | 175 | 175 |
| | NB THRT | 350 | 350 | 250 | 250 |
| | EB LT | 100 | 100 | 125 | 125 |

NB = Northbound; SB = Southbound; EB = Eastbound; WB = Westbound

LT = Left-Turn; TH = Through; RT = Right-Turn

* - Under the assumption that scenario that includes a Seneca Street extension into the project site

Comment/Request #3

The report assumes that all of the driveways on Martinazzi Avenue remain open.

Response: As discussed at our follow-up meeting on May 7, the report does not assume that all the Martinazzi Avenue driveways remain open. The April 2013 TIA included the following assumptions regarding the existing site driveways along SW Martinazzi Avenue:

Existing and Background Conditions (represented in Figures 4A/4B and 5A/5B)

- All three site driveways (driveways #4, #6, and #7 in the TIA) continue to remain open.

2014 Total Traffic Conditions (represented in Figures 9A/9B)

- This scenario looks at maintaining the existing SW Martinazzi Avenue driveways. As such, all three site driveways continue to remain open in this scenario.

2014 Total Traffic Conditions Alternative Access Scenario (represented in Figure 11A/11B)

- This scenario evaluates the impact of adding a fourth leg to the SW Martinazzi Avenue/SW Seneca Street intersection. As such, the following driveway modifications were assumed:
 - The existing driveway adjacent to the library (#4) was closed and the traffic was rerouted to the modified SW Martinazzi Avenue/SW Seneca Street intersection (#5).
 - The existing driveway (#6) was assumed to be closed given its close proximity to the new SW Martinazzi Avenue/SW Seneca Street intersection. Existing traffic at this driveway was rerouted to the modified SW Martinazzi Avenue/SW Seneca Street intersection (#5).
 - The existing southernmost site driveway (#7) was assumed to remain open.

Comment/Request #4

There is no mention in the report of on-site queuing either. Will the configuration proposed work?

Response: During our May 7th follow-up discussion, City staff clarified this request is regarding the operation of the first right-in/right-out drive aisle on the main driveway serving the site (opposite the Fred Meyer driveway). Under existing conditions this first drive aisle allows for both left and right turns and creates a conflict with standing queues exiting the site. Under the proposed configuration, a raised median will be constructed along the main driveway that will limit turn movements at the first drive aisle to right turns only. This will eliminate any queuing conflicts and represents a significant improvement relative to the existing condition.

Comment/Request #5

Shopping Center ITE (3.75) code was used. No mention in the TIA about another drive-thru (34.64) or the health club (4.05).

Response: The April 2013 TIA summarizes the trip generation methodology while Table 8 provides the summary trip generation calculations for the proposed Nyberg Rivers redevelopment. To estimate the additional traffic generated by the variety of potential uses on the Nyberg Rivers site, the 'Shopping Center' land use category in ITE *Trip Generation* was used. The Shopping Center category is typically used for projects such as the Nyberg Rivers development. The 'Shopping Center' category includes an integrated group of small and large commercial uses as well as non-retail facilities (office, restaurants,

health clubs, drive-in banks, sit down and fast food restaurants, etc.). This mix of uses is consistent with CenterCal’s overall vision for the site.

Another point worth noting is that CenterCal is still working to formalize leases with potential tenants. The use of the ‘Shopping Center’ category provides CenterCal and the City of Tualatin flexibility to accommodate a variety of uses so long as the total development size (gross square feet of development) stays approximately the same as or less than the amount assumed in the TIA.

The above notwithstanding, at your request we’ve provided some additional analysis regarding the sensitivity of adding another fast food restaurant with a drive-thru above and beyond what has already been studied (i.e. assuming it is part of the currently planned shopping center). Table 4 below shows the impact of a 4,500 square-foot fast-food restaurant with drive-through window.

Table 4 – Nyberg Rivers Trip Generation (Assuming the Addition of a 4,500 square foot Fast-Food Restaurant with Drive-Through Window)

| | ITE Code | Size (sq. ft.) | Weekday PM Peak Hour | | | Saturday Midday Peak Hour | | |
|--|----------|----------------------|----------------------|------------|------------|---------------------------|------------|------------|
| | | | Total | In | Out | Total | In | Out |
| Existing Site | | | | | | | | |
| Existing Site Driveways ¹ | - | - | 945 | 435 | 510 | 970 | 490 | 480 |
| Less Existing Library ² | 590 | 22,123 | (160) | (75) | (85) | (150) | (80) | (70) |
| Less Existing Civic Uses ³ | 715 | ~10,000 | (50) | (10) | (40) | - | - | - |
| Total Existing Retail | | | 735 | 350 | 385 | 820 | 410 | 410 |
| Future Site | | | | | | | | |
| Shopping Center | 820 | 307,000 ⁴ | 1,350 | 660 | 690 | 1,775 | 925 | 850 |
| Less Existing Retail Driveway Counts | | | (735) | (350) | (385) | (820) | (410) | (410) |
| Sub Total | | | 615 | 310 | 305 | 955 | 515 | 440 |
| Pass-by Trips (Weekday 34%, Saturday 26%) | | | (210) | (105) | (105) | (230) | (115) | (115) |
| Net New Trips | | | 405 | 205 | 200 | 725 | 400 | 325 |
| Fast-Food Restaurant with Drive-Through Window | 934 | 4,500 | 145 | 75 | 70 | 265 | 135 | 130 |
| Internal Trips (10%) | | | (10) | (5) | (5) | (30) | (15) | (15) |
| Pass-by Trips (50%) | | | (60) | (30) | (30) | (120) | (60) | (60) |
| Fast Food Net New Trips | | | 75 | 40 | 35 | 115 | 60 | 55 |

¹Represents the total site driveway counts during the weekday p.m. peak hour of 4:35-5:35 p.m. and Saturday midday peak hour of 12:10-1:10 p.m. This is the traffic volume being generated by the existing 158,343 square feet of shopping center currently residing on the site prior to Kmart’s closure.

²The library traffic counts were estimated using the *Library* land use in *ITE Trip Generation*.

³The City Hall traffic counts were estimated using the *Single Tenant Office Building* land use in *ITE Trip Generation*. The existing City Hall square footage was estimated to be approximately 10,000 square feet in size.

⁴Includes the 158,343 square feet of existing shopping center (minus the 96,799 square foot former K-Mart) plus the 245,456 square feet of proposed shopping center uses.

As shown in Table 4, a 4,500 square-foot fast-food restaurant with drive-through window (if evaluated as a separate use) would add approximately 75 net new trips to the overall study network and 135 additional trips (when accounting for pass-by trips) to the driveways serving the site. Assuming similar trip assignments to those used in the April 2013 TIA, a fast-food restaurant would have the following impacts:

- The SW Nyberg Road/SW Tualatin-Sherwood Road/Fred Meyer Driveway/Site Driveway intersection (#10) is estimated to convey an additional 86 p.m. peak hour trips (represents a 1.7 percent increase in total entering volumes during the critical weekday p.m. peak hour). With this additional traffic, the intersection is forecast to continue to operate acceptably at a v/c ratio of 0.84 during the critical weekday p.m. peak hour. *Appendix C contains the operations summary worksheet for this intersection.*
- The SW Martinazzi Avenue/Site Driveway (near the library) is estimated to experience a 17 trip increase which represents a 1.1 percent increase in total entering volumes during the critical weekday p.m. peak hour. Sufficient capacity exists at this intersection to accommodate the additional traffic impacts.
- At any other off-site intersection the additional trip generation would have a negligible traffic impact and would not change any of the key findings in the original TIA.
- In summary, even if evaluated separately from a Shopping Center, all agency operating standards would be met with the addition of a 4,500 fast food restaurant with a drive-thru.

We trust this additional information in addition to the information included in the original TIA adequately addresses any traffic related concerns regarding an additional fast food restaurant with a drive-through window.

Comment/Request #6

You should explain more about why all of the intersections were not evaluated for Saturday.

Response: As documented in the April 22, 2012 Scoping Memorandum, it was agreed that the TIA would investigate the proposed development's impact at select study area intersections during the Saturday midday period. Given that the traffic volumes at the study area intersections are anywhere from 20-50% lower during the Saturday midday time period, the analysis only focused on the site driveways, immediately adjacent intersections, and those intersections that are forecast to experience a significant increase in site-generated traffic such as the I-5 ramp terminal intersections. At all other study intersections (due to the 20-50% reduction in background traffic relative to existing conditions), it necessarily follows that operations will be better on Saturday than during the weekday p.m. peak hour. Accordingly, the intersections studied under Saturday conditions were limited to those in the TIA.

Comment/Request #7

There is nothing in the report about adding dual right turns at Fred Meyer.

Response: The TIA demonstrates that with the proposed transportation improvements (both on-site and off-site) associated with the proposed development all applicable agency standards will be met relative to transportation facilities with full build out of the proposed development. At the request of, and in cooperation with Fred Meyer, CenterCal is exploring an improvement to the SW Nyberg Road/SW Tualatin-Sherwood Road/Fred Meyer/Site Access. This improvement is not required to maintain agency operating standards. Rather, it will mitigate the small increase in on-site queuing for the right turn movement exiting the Fred Meyer site that will result from the proposed signal phasing modification. The proposed improvement, which would add an additional exiting right turn lane from the Fred Meyer site, would result in a net improvement (reduction) in on-site queuing relative to the existing condition, and further improve the v/c and LOS at the intersection.

Given that the details of this modification are still being investigated between CenterCal and Fred Meyer, the improvement scenario was not formally included in the April 2013 TIA. If CenterCal decides to formally move forward with the improvement, an operations and queuing analysis will be submitted to the City of Tualatin, Washington County, and ODOT for review.

This memorandum addresses each of your requests for additional information. If you have any questions, please contact us.

Sincerely,
KITTELSON & ASSOCIATES, INC.

Mark Vandehey, P.E.

Appendix A SW Martinazzi Avenue/City
Library Field Calculation
Worksheets

EX SB LT
capacity= 774
volume= 140

delay = 11.33
v/c= 0.18

TTSB LT
capacity= 774
volume= 200

delay = 12.05
v/c= 0.26

EX WB LT
capacity= 188
volume= 30

delay = 30.31
v/c= 0.16

TT WB LT
capacity= 158
volume= 55

delay = 43.77
v/c= 0.35

EX WB RT
capacity= 542
volume= 100

delay = 14.09
v/c= 0.18

TT WB RT
capacity= 542
volume= 165

delay = 15.68
v/c= 0.30

SW Martinazzi Avenue/City Library Driveway (peak 15-minute period 5:00-5:15)

| Service Time for SB LT | Service Time for WB RT | Service Time for WB LT | |
|------------------------|------------------------|------------------------|-------|
| 0 | 11 | 10 | |
| 0 | 12 | 10 | |
| 1 | 2 | 21 | |
| 0 | 9 | 36 | |
| 0 | 2 | 30 | |
| 3 | 1 | 21 | |
| 0 | 2 | 30 | |
| 3 | 1 | 50 | |
| 0 | 1 | 3 | |
| 0 | 1 | 48 | |
| 0 | 1 | 4 | |
| 30 | 5 | 4 | |
| 27 | 1 | 6 | |
| 3 | 29 | 6 | |
| 0 | 5 | 2 | |
| 1 | 14 | 10 | |
| 10 | 1 | 6 | |
| 1 | 3 | 2 | |
| 0 | 3 | 24 | |
| 0 | 12 | 69 | |
| 10 | 5 | 21 | |
| 13 | 9 | 9 | |
| 17 | 4 | <u>422</u> | |
| 0 | 7 | | |
| 10 | <u>25</u> | Avg Service Time = | 19.18 |
| 20 | 166 | Capacity= | 188 |
| 2 | | | |
| 0 | Avg Service Time = | 6.64 | |
| 0 | Capacity= | 542 | |
| 17 | | | |
| 1 | | | |
| 0 | | | |
| 2 | | | |
| 0 | | | |
| 0 | | | |
| 6 | | | |
| 6 | | | |
| 3 | | | |
| 0 | | | |
| <u>0</u> | | | |
| 186 | | | |

Avg Service Time = 4.65
Capacity= 774

Appendix B Queuing Worksheets

SIGNALIZED QUEUE ANALYSIS

Project Name: Nyberg Rivers
Project Number: 12116
Analyst: jxh
Date: 5/16/2013
Filename: H:\profile\12116 - K-Mart Tualatin Redevelopment\quoting\Martinazzi Corridor\12116_051613.qd



KITTELSON & ASSOCIATES, INC.
 610 SW Alder, Suite 700
 Portland, Oregon 97205
 (503) 228-5230
 Fax: (503) 273-8169

Intersection: Martinazzi/Tualatin-Sherwood SAT
Conditions (yr, alt., etc.): BK

GENERAL INPUT PARAMETERS:

| | |
|--------------------------|---------|
| Cycle Length: | 115 sec |
| Confidence Level (C.L.): | 95% |
| Storage length/vehicle: | 25 feet |

| | APPROACH/MOVEMENT | | | | | | | |
|-------------------------------|-------------------|-------|-------|---------|----|----|----|----|
| | #1 | #2 | #3 | #4 | #5 | #6 | #7 | #8 |
| | SB THRT | SB LT | EB LT | NB THRT | | | | |
| INPUT PARAMETERS: | | | | | | | | |
| Volume (pre-PHF) (vph): | 470 | 129 | 69 | 221 | | | | |
| G/C for movement: | 0.18 | 0.12 | 0.07 | 0.16 | | | | |
| Number of lanes: | 2 | 1 | 1 | 1 | | | | |
| CALCULATIONS: | | | | | | | | |
| Length of red interval (sec): | 94.3 | 101.2 | 107.0 | 96.6 | | | | |
| Average total queue (veh): | 12.3 | 3.6 | 2.0 | 5.9 | | | | |
| Maximum total queue (veh): | 18 | 7 | 5 | 10 | | | | |
| Total queue length (feet): | 450 | 175 | 125 | 250 | | | | |
| Required storage/lane (feet): | 225 | 175 | 125 | 250 | | | | |
| PERMITTED LEFT TURNS: | | | | | | | | |
| Opposing volume (pre-PHF): | | | | | | | | |
| Opposing sat. flow rate: | | | | | | | | |
| CALCULATIONS: | | | | | | | | |
| Opposing flow ratio (Yo): | | | | | | | | |
| Unblocked G/C: | | | | | | | | |
| Effective red interval (sec): | | | | | | | | |
| Average total queue (veh): | | | | | | | | |
| Maximum total queue (veh): | | | | | | | | |
| Total queue length (feet): | | | | | | | | |
| Required storage/lane (feet): | | | | | | | | |

METHODOLOGY AND FORMULAS USED:

Length of red interval = $(1 - G/C) * \text{Cycle length}$
 Average queue/lane = $\text{Volume} * \text{Red Interval} / 3600$
 Maximum queue: Random arrival/Constant service
 Random arrivals behave according to a Poisson distribution.
 There is a probability equal to the confidence level desired (e.g. 95%)
 that the queue formed during each red interval will be less than
 or equal to the maximum queue.
 $(\text{Prob. of arrivals} = N) = (\text{Red Interval})^N * \exp(-N) / N!$ (the Poisson distribution)
 $(\text{Prob. of arrivals} \geq N) = 1 - \text{Sum of probabilities for vehicles } 0, 1, \dots, N-1$
 Max N: Highest N such that the sum of probabilities > (1 - confidence level)

Queue length = $\text{Maximum queue} * \text{Storage length per vehicle}$
 Required storage per lane = $\text{Queue length} / \text{Number of lanes}$, rounded
 up to the next highest whole vehicle
 Opposing flow ratio $Y_o = \text{opposing volume } v_o / \text{opposing sat. flow rate } s_o$
 Unblocked G/C $(g_u/C) = (g/C - Y_o)/(1 - Y_o)$

SIGNALIZED QUEUE ANALYSIS

Project Name: Nyberg Rivers
 Project Number: 12116
 Analyst: jxh
 Date: 5/16/2013
 Filename: H:\projfile\12116 - K-Marl Tualatin Redevelopment\queuing\Martinazzi Corridor (Signalized).xls



KITTELSON & ASSOCIATES, INC.
 610 SW Alder, Suite 700
 Portland, Oregon 97205
 (503) 228-5230
 Fax: (503) 273-8169

Intersection: Martinazzi/Tualatin-Sherwood Weekday PM
 Conditions (yr, alt., etc.): BK

GENERAL INPUT PARAMETERS:

| | |
|--------------------------|---------|
| Cycle Length: | 125 sec |
| Confidence Level (C.L.): | 95% |
| Storage length/vehicle: | 25 feet |

| | APPROACH/MOVEMENT | | | | | | | |
|-------------------------------|-------------------|-------|-------|---------|----|----|----|----|
| | #1 | #2 | #3 | #4 | #5 | #6 | #7 | #8 |
| | SB THRT | SB LT | EB LT | NB THRT | | | | |
| INPUT PARAMETERS: | | | | | | | | |
| Volume (pre-PHF) (vph): | 751 | 194 | 52 | 302 | | | | |
| G/C for movement: | 0.26 | 0.16 | 0.07 | 0.19 | | | | |
| Number of lanes: | 2 | 1 | 1 | 1 | | | | |
| CALCULATIONS: | | | | | | | | |
| Length of red interval (sec): | 92.5 | 105.0 | 116.3 | 101.3 | | | | |
| Average total queue (veh): | 19.3 | 5.7 | 1.7 | 8.5 | | | | |
| Maximum total queue (veh): | 27 | 10 | 4 | 14 | | | | |
| Total queue length (feet): | 675 | 250 | 100 | 350 | | | | |
| Required storage/lane (feet): | 350 | 250 | 100 | 350 | | | | |
| PERMITTED LEFT TURNS: | | | | | | | | |
| Opposing volume (pre-PHF): | | | | | | | | |
| Opposing sat. flow rate: | | | | | | | | |
| CALCULATIONS: | | | | | | | | |
| Opposing flow ratio (Yo): | | | | | | | | |
| Unblocked G/C: | | | | | | | | |
| Effective red interval (sec): | | | | | | | | |
| Average total queue (veh): | | | | | | | | |
| Maximum total queue (veh): | | | | | | | | |
| Total queue length (feet): | | | | | | | | |
| Required storage/lane (feet): | | | | | | | | |

METHODOLOGY AND FORMULAS USED:

Length of red interval = (1 - G/C) * Cycle length

Average queue/lane = Volume * Red Interval / 3600

Maximum queue: Random arrival/Constant service
 Random arrivals behave according to a Poisson distribution.
 There is a probability equal to the confidence level desired (e.g. 95%)
 that the queue formed during each red interval will be less than
 or equal to the maximum queue.

(Prob. of arrivals = N) = (Red Interval)^N * exp(-N) / N! (the Poisson distribution)

(Prob. of arrivals >= N) = 1 - Sum of probabilities for vehicles 0, 1, ..., N-1

Max N: Highest N such that the sum of probabilities > (1 - confidence level)

Queue length = Maximum queue * Storage length per vehicle

Required storage per lane = Queue length / Number of lanes, rounded
 up to the next highest whole vehicle

Opposing flow ratio Yo = opposing volume vo / opposing sat. flow rate sop

Unblocked G/C (gu/C) = (g/C * Yo) / (1 - Yo)

SIGNALIZED QUEUE ANALYSIS

Project Name: Nyberg Rivers
Project Number: 12116
Analyst: jxh
Date: 5/16/2013
Filename: H:\profile\12116 - K-Mart Tualatin Redevelopment\queuing\Martinazzi Corridor (Signalized).xls



KITTELSON & ASSOCIATES, INC.
 610 SW Alder, Suite 700
 Portland, Oregon 97205
 (503) 228-5230
 Fax: (503) 273-8169

Intersection: Martinazzi/Nyberg SAT
Conditions (yr, alt., etc.): BK

GENERAL INPUT PARAMETERS:

| | |
|--------------------------|---------|
| Cycle Length: | 44 sec |
| Confidence Level (C.L.): | 95% |
| Storage length/vehicle: | 25 feet |

| | APPROACH/MOVEMENT | | | | | | | |
|-------------------------------|-------------------|-------|-------|-------|----|----|----|----|
| | #1 | #2 | #3 | #4 | #5 | #6 | #7 | #8 |
| | NB TH | SB TH | WB LT | WB RT | | | | |
| INPUT PARAMETERS: | | | | | | | | |
| Volume (pre-PHF) (vph): | 266 | 318 | 264 | 237 | | | | |
| G/C for movement: | 0.33 | 0.33 | 0.21 | 0.21 | | | | |
| Number of lanes: | 1 | 2 | 2 | 1 | | | | |
| CALCULATIONS: | | | | | | | | |
| Length of red interval (sec): | 29.5 | 29.5 | 34.8 | 34.8 | | | | |
| Average total queue (veh): | 2.2 | 2.6 | 2.5 | 2.3 | | | | |
| Maximum total queue (veh): | 5 | 5 | 5 | 5 | | | | |
| Total queue length (feet): | 125 | 125 | 125 | 125 | | | | |
| Required storage/lane (feet): | 125 | 75 | 75 | 125 | | | | |
| PERMITTED LEFT TURNS: | | | | | | | | |
| Opposing volume (pre-PHF): | | | | | | | | |
| Opposing sat. flow rate: | | | | | | | | |
| CALCULATIONS: | | | | | | | | |
| Opposing flow ratio (Yo): | | | | | | | | |
| Unblocked G/C: | | | | | | | | |
| Effective red interval (sec): | | | | | | | | |
| Average total queue (veh): | | | | | | | | |
| Maximum total queue (veh): | | | | | | | | |
| Total queue length (feet): | | | | | | | | |
| Required storage/lane (feet): | | | | | | | | |

METHODOLOGY AND FORMULAS USED:

Length of red interval = $(1 - G/C) \cdot \text{Cycle length}$

Queue length = Maximum queue * Storage length per vehicle

Average queue/lane = Volume * Red Interval / 3600

Required storage per lane = Queue length / Number of lanes, rounded up to the next highest whole vehicle

Maximum queue: Random arrival/Constant service
 Random arrivals behave according to a Poisson distribution.
 There is a probability equal to the confidence level desired (e.g. 95%) that the queue formed during each red interval will be less than or equal to the maximum queue.

Opposing flow ratio $Y_o = \text{opposing volume } v_o / \text{opposing sat. flow rate } s_o$

Unblocked G/C $(g_u/C) = (g/C - Y_o)/(1 - Y_o)$

(Prob. of arrivals = N) = $(\text{Red Interval})^N \cdot \exp(-N) / N!$ (the Poisson distribution)

(Prob. of arrivals >= N) = 1 - Sum of probabilities for vehicles 0, 1, ..., N-1

Max N: Highest N such that the sum of probabilities > (1 - confidence level)

SIGNALIZED QUEUE ANALYSIS

Project Name: Nyberg Rivers
Project Number: 12116
Analyst: jxh
Date: 5/16/2013
Filename: H:\projfile\12116 - K-Mart Tualatin Redevelopment\quouing\Martinazzi Corridor\origme\12116



KITTELSON & ASSOCIATES, INC.
 610 SW Alder, Suite 700
 Portland, Oregon 97205
 (503) 228-5230
 Fax: (503) 273-8169

Intersection: Martinazzi/Nyberg Weekday PM
Conditions (yr, alt., etc.): BK

GENERAL INPUT PARAMETERS:

| | |
|--------------------------|---------|
| Cycle Length: | 45 sec |
| Confidence Level (C.L.): | 95% |
| Storage length/vehicle: | 25 feet |

| | APPROACH/MOVEMENT | | | | | | | |
|-------------------------------|-------------------|-------|-------|-------|----|----|----|----|
| | #1 | #2 | #3 | #4 | #5 | #6 | #7 | #8 |
| | NB TH | SB TH | WB LT | WB RT | | | | |
| INPUT PARAMETERS: | | | | | | | | |
| Volume (pre-PHF) (vph): | 327 | 502 | 404 | 337 | | | | |
| G/C for movement: | 0.37 | 0.37 | 0.25 | 0.25 | | | | |
| Number of lanes: | 1 | 2 | 2 | 1 | | | | |
| CALCULATIONS: | | | | | | | | |
| Length of red interval (sec): | 28.4 | 28.4 | 33.8 | 33.8 | | | | |
| Average total queue (veh): | 2.6 | 4.0 | 3.8 | 3.2 | | | | |
| Maximum total queue (veh): | 5 | 7 | 7 | 6 | | | | |
| Total queue length (feet): | 125 | 175 | 175 | 150 | | | | |
| Required storage/lane (feet): | 125 | 100 | 100 | 150 | | | | |
| PERMITTED LEFT TURNS: | | | | | | | | |
| Opposing volume (pre-PHF): | | | | | | | | |
| Opposing sat. flow rate: | | | | | | | | |
| CALCULATIONS: | | | | | | | | |
| Opposing flow ratio (Yo): | | | | | | | | |
| Unblocked G/C: | | | | | | | | |
| Effective red interval (sec): | | | | | | | | |
| Average total queue (veh): | | | | | | | | |
| Maximum total queue (veh): | | | | | | | | |
| Total queue length (feet): | | | | | | | | |
| Required storage/lane (feet): | | | | | | | | |

METHODOLOGY AND FORMULAS USED:

Length of red interval = (1 - G/C) * Cycle length

Average queue/lane = Volume * Red Interval / 3600

Maximum queue: Random arrival/Constant service

Random arrivals behave according to a Poisson distribution.

There is a probability equal to the confidence level desired (e.g. 95%)

that the queue formed during each red interval will be less than

or equal to the maximum queue.

(Prob. of arrivals = N) = (Red Interval)^N * exp(-N) / N! (the Poisson distribution)

(Prob. of arrivals >= N) = 1 - Sum of probabilities for vehicles 0, 1, ..., N-1

Max N: Highest N such that the sum of probabilities > (1 - confidence level)

Queue length = Maximum queue * Storage length per vehicle

Required storage per lane = Queue length / Number of lanes, rounded up to the next highest whole vehicle

Opposing flow ratio Yo = opposing volume vo / opposing sat. flow rate sop

Unblocked G/C (gu/C) = (g/C - Yo)/(1-Yo)

SIGNALIZED QUEUE ANALYSIS

Project Name: Nyberg Rivers
Project Number: 12116
Analyst: jxh
Date: 5/16/2013
Filename: H:\proj\file\12116 - K-Mart Tualatin Redevelopment\queuing\Martinazzi Corridor\logme\Excel



KITTELSON & ASSOCIATES, INC.
 610 SW Alder, Suite 700
 Portland, Oregon 97205
 (503) 228-5230
 Fax: (503) 273-8169

Intersection: Martinazzi/Boones Ferry Weekday SAT
Conditions (yr, alt., etc.): BK

GENERAL INPUT PARAMETERS:

| | |
|--------------------------|---------|
| Cycle Length: | 56 sec |
| Confidence Level (C.L.): | 95% |
| Storage length/vehicle: | 25 feet |

| | APPROACH/MOVEMENT | | | | | | | |
|-------------------------------|-------------------|-------|-------|-------|----|----|----|----|
| | #1 | #2 | #3 | #4 | #5 | #6 | #7 | #8 |
| | NB LT | NB RT | WB LT | EB RT | | | | |
| INPUT PARAMETERS: | | | | | | | | |
| Volume (pre-PHF) (vph): | 185 | 304 | 258 | 125 | | | | |
| G/C for movement: | 0.21 | 0.44 | 0.24 | 0.32 | | | | |
| Number of lanes: | 1 | 1 | 1 | 1 | | | | |
| CALCULATIONS: | | | | | | | | |
| Length of red interval (sec): | 44.2 | 31.4 | 42.6 | 38.1 | | | | |
| Average total queue (veh): | 2.3 | 2.6 | 3.1 | 1.3 | | | | |
| Maximum total queue (veh): | 5 | 6 | 6 | 3 | | | | |
| Total queue length (feet): | 125 | 150 | 150 | 75 | | | | |
| Required storage/lane (feet): | 125 | 150 | 150 | 75 | | | | |
| PERMITTED LEFT TURNS: | | | | | | | | |
| Opposing volume (pre-PHF): | | | | | | | | |
| Opposing sat. flow rate: | | | | | | | | |
| CALCULATIONS: | | | | | | | | |
| Opposing flow ratio (Yo): | | | | | | | | |
| Unblocked G/C: | | | | | | | | |
| Effective red interval (sec): | | | | | | | | |
| Average total queue (veh): | | | | | | | | |
| Maximum total queue (veh): | | | | | | | | |
| Total queue length (feet): | | | | | | | | |
| Required storage/lane (feet): | | | | | | | | |

METHODOLOGY AND FORMULAS USED:

Length of red interval = (1 - G/C) * Cycle length

Queue length = Maximum queue * Storage length per vehicle

Average queue/lane = Volume * Red Interval / 3600

Required storage per lane = Queue length / Number of lanes, rounded up to the next highest whole vehicle

Maximum queue: Random arrival/Constant service
 Random arrivals behave according to a Poisson distribution.
 There is a probability equal to the confidence level desired (e.g. 95%)
 that the queue formed during each red interval will be less than
 or equal to the maximum queue.

Opposing flow ratio Yo = opposing volume vo / opposing sat. flow rate sop

Unblocked G/C (gu/C) = (g/C - Yo)/(1-Yo)

(Prob. of arrivals = N) = (Red Interval)^N * exp(-N) / N! (the Poisson distribution)

(Prob. of arrivals >= N) = 1 - Sum of probabilities for vehicles 0, 1, ..., N-1

Max N: Highest N such that the sum of probabilities > (1 - confidence level)

SIGNALIZED QUEUE ANALYSIS

Project Name: Nyberg Rivers
Project Number: 12116
Analyst: jxh
Date: 5/16/2013
Filename: H:\projfile\12116 - K-Mart Tualatin Redevelopment\queuing\Martinazzi Corridor\qgma12116.d



KITTELSON & ASSOCIATES, INC.
 610 SW Alder, Suite 700
 Portland, Oregon 97205
 (503) 228-5230
 Fax: (503) 273-8169

Intersection: Martinazzi/Boones Ferry Weekday PM
Conditions (yr, alt., etc.): BK

GENERAL INPUT PARAMETERS:

| | |
|--------------------------|---------|
| Cycle Length: | 107 sec |
| Confidence Level (C.L.): | 95% |
| Storage length/vehicle: | 25 feet |

| | APPROACH/MOEMENT | | | | | | | |
|-------------------------------|------------------|-------|-------|-------|----|----|----|----|
| | #1 | #2 | #3 | #4 | #5 | #6 | #7 | #8 |
| | NB LT | NB RT | WB LT | EB RT | | | | |
| INPUT PARAMETERS: | | | | | | | | |
| Volume (pre-PHF) (vph): | 325 | 385 | 422 | 175 | | | | |
| G/C for movement: | 0.20 | 0.49 | 0.28 | 0.39 | | | | |
| Number of lanes: | 1 | 1 | 1 | 1 | | | | |
| CALCULATIONS: | | | | | | | | |
| Length of red interval (sec): | 85.6 | 54.6 | 77.0 | 65.3 | | | | |
| Average total queue (veh): | 7.7 | 5.8 | 9.0 | 3.2 | | | | |
| Maximum total queue (veh): | 13 | 10 | 14 | 6 | | | | |
| Total queue length (feet): | 325 | 250 | 350 | 150 | | | | |
| Required storage/lane (feet): | 325 | 250 | 350 | 150 | | | | |
| PERMITTED LEFT TURNS: | | | | | | | | |
| Opposing volume (pre-PHF): | | | | | | | | |
| Opposing sat. flow rate: | | | | | | | | |
| CALCULATIONS: | | | | | | | | |
| Opposing flow ratio (Yo): | | | | | | | | |
| Unblocked G/C: | | | | | | | | |
| Effective red interval (sec): | | | | | | | | |
| Average total queue (veh): | | | | | | | | |
| Maximum total queue (veh): | | | | | | | | |
| Total queue length (feet): | | | | | | | | |
| Required storage/lane (feet): | | | | | | | | |

METHODOLOGY AND FORMULAS USED:

Length of red interval = (1 - G/C) * Cycle length

Queue length = Maximum queue * Storage length per vehicle

Average queue/lane = Volume * Red Interval / 3600

Required storage per lane = Queue length / Number of lanes, rounded up to the next highest whole vehicle

Maximum queue: Random arrival/Constant service

Opposing flow ratio Yo = opposing volume vo / opposing sat. flow rate sop

Random arrivals behave according to a Poisson distribution. There is a probability equal to the confidence level desired (e.g. 95%) that the queue formed during each red interval will be less than or equal to the maximum queue.

Unblocked G/C (gu/C) = (g/C - Yo)/(1-Yo)

(Prob. of arrivals = N) = (Red Interval)^N * exp(-N) / N! (the Poisson distribution)

(Prob. of arrivals >= N) = 1 - Sum of probabilities for vehicles 0, 1, ..., N-1

Max N: Highest N such that the sum of probabilities > (1 - confidence level)

SIGNALIZED QUEUE ANALYSIS

Project Name: Nyberg Rivers
Project Number: 12116
Analyst: jxh
Date: 5/16/2013
Filename: H:\profile\12116 - K-Mart Tualatin Redevelopment\queuing\Martinazzi Corridor\



KITTELSON & ASSOCIATES, INC.
 610 SW Alder, Suite 700
 Portland, Oregon 97205
 (503) 228-5230
 Fax: (503) 273-8169

Intersection: Martinazzi/Tualatin-Sherwood SAT
Conditions (yr, alt., etc.): WS

GENERAL INPUT PARAMETERS:

| | |
|--------------------------|---------|
| Cycle Length: | 115 sec |
| Confidence Level (C.L.): | 95% |
| Storage length/vehicle: | 25 feet |

| | APPROACH/MOEMENT | | | | | | | |
|-------------------------------|------------------|-------|-------|---------|----|----|----|----|
| | #1 | #2 | #3 | #4 | #5 | #6 | #7 | #8 |
| | SB THRT | SB LT | EB LT | NB THRT | | | | |
| INPUT PARAMETERS: | | | | | | | | |
| Volume (pre-PHF) (vph): | 470 | 129 | 69 | 221 | | | | |
| G/C for movement: | 0.18 | 0.12 | 0.07 | 0.16 | | | | |
| Number of lanes: | 2 | 1 | 1 | 1 | | | | |
| CALCULATIONS: | | | | | | | | |
| Length of red interval (sec): | 94.3 | 101.2 | 107.0 | 96.6 | | | | |
| Average total queue (veh): | 12.3 | 3.6 | 2.0 | 5.9 | | | | |
| Maximum total queue (veh): | 18 | 7 | 5 | 10 | | | | |
| Total queue length (feet): | 450 | 175 | 125 | 250 | | | | |
| Required storage/lane (feet): | 225 | 175 | 125 | 250 | | | | |
| PERMITTED LEFT TURNS: | | | | | | | | |
| Opposing volume (pre-PHF): | | | | | | | | |
| Opposing sat. flow rate: | | | | | | | | |
| CALCULATIONS: | | | | | | | | |
| Opposing flow ratio (Yo): | | | | | | | | |
| Unblocked G/C: | | | | | | | | |
| Effective red interval (sec): | | | | | | | | |
| Average total queue (veh): | | | | | | | | |
| Maximum total queue (veh): | | | | | | | | |
| Total queue length (feet): | | | | | | | | |
| Required storage/lane (feet): | | | | | | | | |

METHODOLOGY AND FORMULAS USED:

Length of red interval = $(1 - G/C) \cdot \text{Cycle length}$

Queue length = Maximum queue * Storage length per vehicle

Average queue/lane = Volume * Red Interval / 3600

Required storage per lane = Queue length / Number of lanes, rounded up to the next highest whole vehicle

Maximum queue: Random arrival/Constant service
 Random arrivals behave according to a Poisson distribution.
 There is a probability equal to the confidence level desired (e.g. 95%) that the queue formed during each red interval will be less than or equal to the maximum queue.

Opposing flow ratio $Y_o = \text{opposing volume } v_o / \text{opposing sat. flow rate } s_o$

Unblocked G/C $(g_u/C) = (g/C - Y_o)/(1 - Y_o)$

(Prob. of arrivals = N) = $(\text{Red Interval})^N \cdot \exp(-N) / N!$ (the Poisson distribution)

(Prob. of arrivals >= N) = $1 - \text{Sum of probabilities for vehicles } 0, 1, \dots, N-1$

Max N: Highest N such that the sum of probabilities > (1 - confidence level)

SIGNALIZED QUEUE ANALYSIS

Project Name: Nyberg Rivers
Project Number: 12116
Analyst: jxh
Date: 5/16/2013
Filename: H:\projfile\12116 - K-Mart Tualatin Redevelopment\queuing\Martinazzi Corridor\



KITTELSON & ASSOCIATES, INC.
 610 SW Alder, Suite 700
 Portland, Oregon 97205
 (503) 228-5230
 Fax: (503) 273-8169

Intersection: Martinazzi/Seneca SAT
Conditions (yr, alt., etc.): WS

GENERAL INPUT PARAMETERS:

| | |
|--------------------------|---------|
| Cycle Length: | 30 sec |
| Confidence Level (C.L.): | 95% |
| Storage length/vehicle: | 25 feet |

| | APPROACH/MOVEMENT | | | | | | | |
|-------------------------------|-------------------|---------|---------|-------|---------|-------|----|----|
| | #1 | #2 | #3 | #4 | #5 | #6 | #7 | #8 |
| | NB LT | NB THRT | SB THRT | SB LT | WB THLT | WB RT | | |
| INPUT PARAMETERS: | | | | | | | | |
| Volume (pre-PHF) (vph): | 81 | 421 | 256 | 185 | 65 | 136 | | |
| G/C for movement: | 0.62 | 0.50 | 0.55 | 0.72 | 0.18 | 0.18 | | |
| Number of lanes: | 1 | 1 | 1 | 1 | 1 | 1 | | |
| CALCULATIONS: | | | | | | | | |
| Length of red interval (sec): | 11.4 | 15.0 | 13.5 | 8.4 | 24.6 | 24.6 | | |
| Average total queue (veh): | 0.3 | 1.8 | 1.0 | 0.4 | 0.4 | 0.9 | | |
| Maximum total queue (veh): | 1 | 4 | 3 | 2 | 2 | 3 | | |
| Total queue length (feet): | 25 | 100 | 75 | 50 | 50 | 75 | | |
| Required storage/lane (feet): | 25 | 100 | 75 | 50 | 50 | 75 | | |
| PERMITTED LEFT TURNS: | | | | | | | | |
| Opposing volume (pre-PHF): | | | | | | | | |
| Opposing sat. flow rate: | | | | | | | | |
| CALCULATIONS: | | | | | | | | |
| Opposing flow ratio (Yo): | | | | | | | | |
| Unblocked G/C: | | | | | | | | |
| Effective red interval (sec): | | | | | | | | |
| Average total queue (veh): | | | | | | | | |
| Maximum total queue (veh): | | | | | | | | |
| Total queue length (feet): | | | | | | | | |
| Required storage/lane (feet): | | | | | | | | |

METHODOLOGY AND FORMULAS USED:

Length of red interval = $(1 - G/C) \cdot \text{Cycle length}$

Queue length = Maximum queue * Storage length per vehicle

Average queue/lane = Volume * Red Interval / 3600

Required storage per lane = Queue length / Number of lanes, rounded up to the next highest whole vehicle

Maximum queue: Random arrival/Constant service
 Random arrivals behave according to a Poisson distribution.
 There is a probability equal to the confidence level desired (e.g. 95%) that the queue formed during each red interval will be less than or equal to the maximum queue.

Opposing flow ratio $Y_o = \text{opposing volume } v_o / \text{opposing sat. flow rate } s_o$

Unblocked G/C $(g_u/C) = (g/C - Y_o)/(1 - Y_o)$

$(\text{Prob. of arrivals} = N) = (\text{Red Interval})^N \cdot \exp(-N) / N!$ (the Poisson distribution)

$(\text{Prob. of arrivals} \geq N) = 1 - \text{Sum of probabilities for vehicles } 0, 1, \dots, N-1$

Max N: Highest N such that the sum of probabilities > (1 - confidence level)

SIGNALIZED QUEUE ANALYSIS

Project Name: Nyberg Rivers
Project Number: 12116
Analyst: jxh
Date: 5/16/2013
Filename: H:\profile\12116 - K-Mart Tualatin Redevelopment\queuing\Martinazzi Corridor\



KITTELSON & ASSOCIATES, INC.
 610 SW Alder, Suite 700
 Portland, Oregon 97205
 (503) 228-5230
 Fax: (503) 273-8169

Intersection: Martinazzi/Seneca Weekday PM
Conditions (yr, alt., etc.): WS

GENERAL INPUT PARAMETERS:

| | |
|--------------------------|---------|
| Cycle Length: | 49 sec |
| Confidence Level (C.L.): | 95% |
| Storage length/vehicle: | 25 feet |

| | APPROACH/MOVEMENT | | | | | | | |
|-------------------------------|-------------------|---------|---------|-------|---------|-------|----|----|
| | #1 | #2 | #3 | #4 | #5 | #6 | #7 | #8 |
| | NB LT | NB THRT | SB THRT | SB LT | WB THLT | WB RT | | |
| INPUT PARAMETERS: | | | | | | | | |
| Volume (pre-PHF) (vph): | 85 | 615 | 426 | 202 | 53 | 163 | | |
| G/C for movement: | 0.59 | 0.50 | 0.56 | 0.71 | 0.13 | 0.28 | | |
| Number of lanes: | 1 | 1 | 1 | 1 | 1 | 1 | | |
| CALCULATIONS: | | | | | | | | |
| Length of red interval (sec): | 20.1 | 24.5 | 21.6 | 14.2 | 42.6 | 35.3 | | |
| Average total queue (veh): | 0.5 | 4.2 | 2.6 | 0.8 | 0.6 | 1.6 | | |
| Maximum total queue (veh): | 2 | 8 | 5 | 2 | 2 | 4 | | |
| Total queue length (feet): | 50 | 200 | 125 | 50 | 50 | 100 | | |
| Required storage/lane (feet): | 50 | 200 | 125 | 50 | 50 | 100 | | |
| PERMITTED LEFT TURNS: | | | | | | | | |
| Opposing volume (pre-PHF): | | | | | | | | |
| Opposing sat. flow rate: | | | | | | | | |
| CALCULATIONS: | | | | | | | | |
| Opposing flow ratio (Yo): | | | | | | | | |
| Unblocked G/C: | | | | | | | | |
| Effective red interval (sec): | | | | | | | | |
| Average total queue (veh): | | | | | | | | |
| Maximum total queue (veh): | | | | | | | | |
| Total queue length (feet): | | | | | | | | |
| Required storage/lane (feet): | | | | | | | | |

METHODOLOGY AND FORMULAS USED:

Length of red interval = $(1 - G/C) \cdot \text{Cycle length}$

Queue length = Maximum queue * Storage length per vehicle

Average queue/lane = Volume * Red Interval / 3600

Required storage per lane = Queue length / Number of lanes, rounded up to the next highest whole vehicle

Maximum queue: Random arrival/Constant service

Opposing flow ratio Yo = opposing volume vo / opposing sat. flow rate sop

Random arrivals behave according to a Poisson distribution.
 There is a probability equal to the confidence level desired (e.g. 95%) that the queue formed during each red interval will be less than or equal to the maximum queue.

Unblocked G/C (gu/C) = $(g/C - Yo)/(1 - Yo)$

(Prob. of arrivals = N) = $(\text{Red Interval})^N \cdot \exp(-N) / N!$ (the Poisson distribution)

(Prob. of arrivals >= N) = 1 - Sum of probabilities for vehicles 0, 1, ..., N-1

Max N: Highest N such that the sum of probabilities > (1 - confidence level)

SIGNALIZED QUEUE ANALYSIS

Project Name: Nyberg Rivers
Project Number: 12116
Analyst: jxh
Date: 5/16/2013
Filename: H:\projfile\12116 - K-Mart Tualatin Redevlopment\queuing\Martinazzi Corridor\12116_051613.qub



KITTELSON & ASSOCIATES, INC.
 610 SW Alder, Suite 700
 Portland, Oregon 97205
 (503) 228-5230
 Fax: (503) 273-8169

Intersection: Martinazzi/Nyberg SAT
Conditions (yr, alt., etc.): WS

GENERAL INPUT PARAMETERS:

| | |
|--------------------------|---------|
| Cycle Length: | 42 sec |
| Confidence Level (C.L.): | 95% |
| Storage length/vehicle: | 25 feet |

| | APPROACH/MOVEMENT | | | | | | | |
|-------------------------------|-------------------|-------|-------|-------|----|----|----|----|
| | #1 | #2 | #3 | #4 | #5 | #6 | #7 | #8 |
| | NB TH | SB TH | WB LT | WB RT | | | | |
| INPUT PARAMETERS: | | | | | | | | |
| Volume (pre-PHF) (vph): | 276 | 322 | 297 | 237 | | | | |
| G/C for movement: | 0.30 | 0.30 | 0.22 | 0.22 | | | | |
| Number of lanes: | 1 | 2 | 2 | 1 | | | | |
| CALCULATIONS: | | | | | | | | |
| Length of red interval (sec): | 29.4 | 29.4 | 32.8 | 32.8 | | | | |
| Average total queue (veh): | 2.3 | 2.6 | 2.7 | 2.2 | | | | |
| Maximum total queue (veh): | 5 | 6 | 6 | 5 | | | | |
| Total queue length (feet): | 125 | 150 | 150 | 125 | | | | |
| Required storage/lane (feet): | 125 | 75 | 75 | 125 | | | | |
| PERMITTED LEFT TURNS: | | | | | | | | |
| Opposing volume (pre-PHF): | | | | | | | | |
| Opposing sat. flow rate: | | | | | | | | |
| CALCULATIONS: | | | | | | | | |
| Opposing flow ratio (Yo): | | | | | | | | |
| Unblocked G/C: | | | | | | | | |
| Effective red interval (sec): | | | | | | | | |
| Average total queue (veh): | | | | | | | | |
| Maximum total queue (veh): | | | | | | | | |
| Total queue length (feet): | | | | | | | | |
| Required storage/lane (feet): | | | | | | | | |

METHODOLOGY AND FORMULAS USED:

Length of red interval = (1 - G/C) * Cycle length

Queue length = Maximum queue * Storage length per vehicle

Average queue/lane = Volume * Red Interval / 3600

Required storage per lane = Queue length / Number of lanes, rounded up to the next highest whole vehicle

Maximum queue: Random arrival/Constant service
 Random arrivals behave according to a Poisson distribution.
 There is a probability equal to the confidence level desired (e.g. 95%)
 that the queue formed during each red interval will be less than
 or equal to the maximum queue.

Opposing flow ratio Yo = opposing volume vo / opposing sat. flow rate sop

Unblocked G/C (gu/C) = (g/C - Yo)/(1 - Yo)

(Prob. of arrivals = N) = (Red Interval)^N * exp(-N) / N! (the Poisson distribution)

(Prob. of arrivals >= N) = 1 - Sum of probabilities for vehicles 0, 1, ..., N-1

Max N: Highest N such that the sum of probabilities > (1 - confidence level)

SIGNALIZED QUEUE ANALYSIS

Project Name:
Project Number:
Analyst:
Date:
Filename:

Nyberg Rivers
12116
jxh
5/16/2013
H:\projfile\12116 - K-Mart Tualatin Redevelopment\queuing\Martinazzi Corridor\12116_051613.qm



KITTELSON & ASSOCIATES, INC.
610 SW Alder, Suite 700
Portland, Oregon 97205
(503) 228-5230
Fax: (503) 273-8169

Intersection:
Conditions (yr, alt., etc.):

Martinazzi/Nyberg Weekday PM
WS

GENERAL INPUT PARAMETERS:

| | |
|--------------------------|---------|
| Cycle Length: | 42 sec |
| Confidence Level (C.L.): | 95% |
| Storage length/vehicle: | 25 feet |

| | APPROACH/MOVEMENT | | | | | | | |
|-------------------------------|-------------------|-------|-------|-------|----|----|----|----|
| | #1 | #2 | #3 | #4 | #5 | #6 | #7 | #8 |
| | NB TH | SB TH | WB LT | WB RT | | | | |
| INPUT PARAMETERS: | | | | | | | | |
| Volume (pre-PHF) (vph): | 341 | 509 | 412 | 337 | | | | |
| G/C for movement: | 0.34 | 0.34 | 0.26 | 0.26 | | | | |
| Number of lanes: | 1 | 2 | 2 | 1 | | | | |
| CALCULATIONS: | | | | | | | | |
| Length of red interval (sec): | 27.7 | 27.7 | 31.1 | 31.1 | | | | |
| Average total queue (veh): | 2.6 | 3.9 | 3.6 | 2.9 | | | | |
| Maximum total queue (veh): | 6 | 7 | 7 | 6 | | | | |
| Total queue length (feet): | 150 | 175 | 175 | 150 | | | | |
| Required storage/lane (feet): | 150 | 100 | 100 | 150 | | | | |
| PERMITTED LEFT TURNS: | | | | | | | | |
| Opposing volume (pre-PHF): | | | | | | | | |
| Opposing sat. flow rate: | | | | | | | | |
| CALCULATIONS: | | | | | | | | |
| Opposing flow ratio (Yo): | | | | | | | | |
| Unblocked G/C: | | | | | | | | |
| Effective red interval (sec): | | | | | | | | |
| Average total queue (veh): | | | | | | | | |
| Maximum total queue (veh): | | | | | | | | |
| Total queue length (feet): | | | | | | | | |
| Required storage/lane (feet): | | | | | | | | |

METHODOLOGY AND FORMULAS USED:

Length of red interval = (1 - G/C) * Cycle length

Queue length = Maximum queue * Storage length per vehicle

Average queue/lane = Volume * Red Interval / 3600

Required storage per lane = Queue length / Number of lanes, rounded up to the next highest whole vehicle

Maximum queue: Random arrival/Constant service
Random arrivals behave according to a Poisson distribution.
There is a probability equal to the confidence level desired (e.g. 95%) that the queue formed during each red interval will be less than or equal to the maximum queue.

Opposing flow ratio Yo = opposing volume vo / opposing sat. flow rate sop

Unblocked G/C (gu/C) = (g/C - Yo)/(1-Yo)

(Prob. of arrivals = N) = (Red Interval)^N * exp(-N) / N! (the Poisson distribution)
(Prob. of arrivals >= N) = 1 - Sum of probabilities for vehicles 0, 1, ..., N-1
Max N: Highest N such that the sum of probabilities > (1 - confidence level)

SIGNALIZED QUEUE ANALYSIS

Project Name: Nyberg Rivers
Project Number: 12116
Analyst: jxh
Date: 5/16/2013
Filename: #N/A



KITTELSON & ASSOCIATES, INC.
 610 SW Alder, Suite 700
 Portland, Oregon 97205
 (503) 228-5230
 Fax: (503) 273-8169

Intersection: Martinazzi/Boones Ferry Weekday SAT
Conditions (yr, alt., etc.): WS

GENERAL INPUT PARAMETERS:

| | |
|--------------------------|---------|
| Cycle Length: | 67 sec |
| Confidence Level (C.L.): | 95% |
| Storage length/vehicle: | 25 feet |

| | APPROACH/MOVEMENT | | | | | | | |
|-------------------------------|-------------------|-------|-------|-------|-----------|-----------|-----------|-----------|
| | #1 | #2 | #3 | #4 | #5 | #6 | #7 | #8 |
| | NB LT | NB RT | WB LT | EB RT | NB LT WDW | NB RT WDW | WB LT WDW | EB RT WDW |
| INPUT PARAMETERS: | | | | | | | | |
| Volume (pre-PHF) (vph): | 201 | 353 | 318 | 145 | 201 | 309 | 318 | 127 |
| G/C for movement: | 0.22 | 0.49 | 0.27 | 0.31 | 0.20 | 0.47 | 0.27 | 0.32 |
| Number of lanes: | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| CALCULATIONS: | | | | | | | | |
| Length of red interval (sec): | 52.3 | 34.2 | 48.9 | 46.2 | 53.6 | 35.5 | 48.9 | 45.6 |
| Average total queue (veh): | 2.9 | 3.4 | 4.3 | 1.9 | 3.0 | 3.0 | 4.3 | 1.6 |
| Maximum total queue (veh): | 6 | 7 | 8 | 4 | 6 | 6 | 8 | 4 |
| Total queue length (feet): | 150 | 175 | 200 | 100 | 150 | 150 | 200 | 100 |
| Required storage/lane (feet): | 150 | 175 | 200 | 100 | 150 | 150 | 200 | 100 |
| PERMITTED LEFT TURNS: | | | | | | | | |
| Opposing volume (pre-PHF): | | | | | | | | |
| Opposing sat. flow rate: | | | | | | | | |
| CALCULATIONS: | | | | | | | | |
| Opposing flow ratio (Yo): | | | | | | | | |
| Unblocked G/C: | | | | | | | | |
| Effective red interval (sec): | | | | | | | | |
| Average total queue (veh): | | | | | | | | |
| Maximum total queue (veh): | | | | | | | | |
| Total queue length (feet): | | | | | | | | |
| Required storage/lane (feet): | | | | | | | | |

METHODOLOGY AND FORMULAS USED:

Length of red interval = $(1 - G/C) \cdot \text{Cycle length}$

Queue length = Maximum queue * Storage length per vehicle

Average queue/lane = Volume * Red Interval / 3600

Required storage per lane = Queue length / Number of lanes, rounded up to the next highest whole vehicle

Maximum queue: Random arrival/Constant service
 Random arrivals behave according to a Poisson distribution.
 There is a probability equal to the confidence level desired (e.g. 95%)
 that the queue formed during each red interval will be less than
 or equal to the maximum queue.

Opposing flow ratio Yo = opposing volume vo / opposing sat. flow rate sop

Unblocked G/C (gu/C) = $(g/C - Yo)/(1 - Yo)$

(Prob. of arrivals = N) = $(\text{Red Interval})^N \cdot \exp(-N) / N!$ (the Poisson distribution)

(Prob. of arrivals >= N) = 1 - Sum of probabilities for vehicles 0, 1, ..., N-1

Max N: Highest N such that the sum of probabilities > (1 - confidence level)

SIGNALIZED QUEUE ANALYSIS

Project Name: Nyberg Rivers
Project Number: 12116
Analyst: jxh
Date: 5/16/2013
Filename: H:\profile\12116 - K-Mart Tualatin Redevelopment\queuing\Martinazzi Corridor\12116_051613.qm



KITTELSON & ASSOCIATES, INC.
 610 SW Alder, Suite 700
 Portland, Oregon 97205
 (503) 228-5230
 Fax: (503) 273-8169

Intersection: Martinazzi/Boones Ferry Weekday PM
Conditions (yr, alt., etc.): WS

GENERAL INPUT PARAMETERS:

| | |
|--------------------------|---------|
| Cycle Length: | 112 sec |
| Confidence Level (C.L.): | 95% |
| Storage length/vehicle: | 25 feet |

| | APPROACH/MOEMENT | | | | | | | |
|-------------------------------|------------------|-------|-------|-------|-----------|-----------|-----------|-----------|
| | #1 | #2 | #3 | #4 | #5 | #6 | #7 | #8 |
| | NB LT | NB RT | WB LT | EB RT | NB LT WDW | NB RT WDW | WB LT WDW | EB RT WDW |
| INPUT PARAMETERS: | | | | | | | | |
| Volume (pre-PHF) (vph): | 335 | 415 | 453 | 185 | 335 | 385 | 453 | 175 |
| G/C for movement: | 0.22 | 0.51 | 0.29 | 0.37 | 0.22 | 0.51 | 0.29 | 0.37 |
| Number of lanes: | 1 | 1 | 1 | 1 | 1 | 1 | 1 | 1 |
| CALCULATIONS: | | | | | | | | |
| Length of red interval (sec): | 87.4 | 54.9 | 79.5 | 70.6 | 87.4 | 54.9 | 79.5 | 70.6 |
| Average total queue (veh): | 8.1 | 6.3 | 10.0 | 3.6 | 8.1 | 5.9 | 10.0 | 3.4 |
| Maximum total queue (veh): | 13 | 11 | 15 | 7 | 13 | 10 | 15 | 7 |
| Total queue length (feet): | 325 | 275 | 375 | 175 | 325 | 250 | 375 | 175 |
| Required storage/lane (feet): | 325 | 275 | 375 | 175 | 325 | 250 | 375 | 175 |
| PERMITTED LEFT TURNS: | | | | | | | | |
| Opposing volume (pre-PHF): | | | | | | | | |
| Opposing sat. flow rate: | | | | | | | | |
| CALCULATIONS: | | | | | | | | |
| Opposing flow ratio (Yo): | | | | | | | | |
| Unblocked G/C: | | | | | | | | |
| Effective red interval (sec): | | | | | | | | |
| Average total queue (veh): | | | | | | | | |
| Maximum total queue (veh): | | | | | | | | |
| Total queue length (feet): | | | | | | | | |
| Required storage/lane (feet): | | | | | | | | |

METHODOLOGY AND FORMULAS USED:

Length of red interval = (1 - G/C) * Cycle length

Average queue/lane = Volume * Red Interval / 3600

Maximum queue: Random arrival/Constant service

Random arrivals behave according to a Poisson distribution.

There is a probability equal to the confidence level desired (e.g. 95%)

that the queue formed during each red interval will be less than

or equal to the maximum queue.

(Prob. of arrivals = N) = (Red Interval)^N * exp(-N) / N! (the Poisson distribution)

(Prob. of arrivals >= N) = 1 - Sum of probabilities for vehicles 0, 1, ..., N-1

Max N: Highest N such that the sum of probabilities > (1 - confidence level)

Queue length = Maximum queue * Storage length per vehicle

Required storage per lane = Queue length / Number of lanes, rounded up to the next highest whole vehicle

Opposing flow ratio Yo = opposing volume vo / opposing sat. flow rate sop

Unblocked G/C (gu/C) = (g/C - Yo)/(1-Yo)

Appendix C Nyberg Road/Fred Meyer/Site
Access Driveway Operations
(Assuming a Fast-Food
Restaurant)

HCM Signalized Intersection Capacity Analysis
 10: Tualatin Sherwood Rd & Site Entrance 4

5/15/2013

| Movement | EBL | EBT | EBR | WBL | WBT | WBR | NBL | NBT | NBR | SBL | SBT | SBR |
|------------------------|------|-------|------|------|------|------|-------|------|-------|-------|------|------|
| Lane Configurations | ↵ | ↑↑↑ | | ↵↵ | ↑↑↑ | ↵ | | ↵ | ↵ | ↵↵ | ↑ | |
| Volume (vph) | 122 | 1884 | 40 | 232 | 1679 | 288 | 36 | 10 | 236 | 358 | 24 | 134 |
| Ideal Flow (vphpl) | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 | 1900 |
| Total Lost time (s) | 4.5 | 6.0 | | 4.5 | 6.0 | 6.0 | | 5.0 | 4.5 | 5.0 | 5.0 | |
| Lane Util. Factor | 1.00 | 0.75 | | 0.97 | 0.91 | 1.00 | | 1.00 | 1.00 | 0.97 | 1.00 | |
| Frb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 0.96 | | 1.00 | 1.00 | 1.00 | 0.97 | |
| Fpb, ped/bikes | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | | 1.00 | 1.00 | 1.00 | 1.00 | |
| Frt | 1.00 | 1.00 | | 1.00 | 1.00 | 0.85 | | 1.00 | 0.85 | 1.00 | 0.87 | |
| Fit Protected | 0.95 | 1.00 | | 0.95 | 1.00 | 1.00 | | 0.96 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (prot) | 1805 | 4100 | | 3502 | 4988 | 1545 | | 1786 | 1599 | 3502 | 1614 | |
| Fit Permitted | 0.95 | 1.00 | | 0.95 | 1.00 | 1.00 | | 0.96 | 1.00 | 0.95 | 1.00 | |
| Satd. Flow (perm) | 1805 | 4100 | | 3502 | 4988 | 1545 | | 1786 | 1599 | 3502 | 1614 | |
| Peak-hour factor, PHF | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 | 0.98 |
| Adj. Flow (vph) | 124 | 1922 | 41 | 237 | 1713 | 294 | 37 | 10 | 241 | 365 | 24 | 137 |
| RTOR Reduction (vph) | 0 | 1 | 0 | 0 | 0 | 146 | 0 | 0 | 0 | 0 | 117 | 0 |
| Lane Group Flow (vph) | 124 | 1962 | 0 | 237 | 1713 | 148 | 0 | 47 | 241 | 365 | 44 | 0 |
| Confl. Peds. (#/hr) | | | 2 | | | 8 | | | | | | 15 |
| Heavy Vehicles (%) | 0% | 4% | 0% | 0% | 4% | 0% | 3% | 0% | 1% | 0% | 0% | 0% |
| Turn Type | Prot | | | Prot | | Perm | Split | | pt+ov | Split | | |
| Protected Phases | 5 | 2 | | 1 | 6 | | 8 | 8 | 18 | 4 | 4 | |
| Permitted Phases | | | | | | 6 | | | | | | |
| Actuated Green, G (s) | 13.9 | 60.3 | | 15.9 | 62.3 | 62.3 | | 8.7 | 24.6 | 17.6 | 17.6 | |
| Effective Green, g (s) | 14.4 | 60.8 | | 16.4 | 62.8 | 62.8 | | 9.2 | 25.6 | 18.1 | 18.1 | |
| Actuated g/C Ratio | 0.12 | 0.49 | | 0.13 | 0.50 | 0.50 | | 0.07 | 0.20 | 0.14 | 0.14 | |
| Clearance Time (s) | 5.0 | 6.5 | | 5.0 | 6.5 | 6.5 | | 5.5 | | 5.5 | 5.5 | |
| Vehicle Extension (s) | 2.5 | 4.0 | | 2.5 | 4.0 | 4.0 | | 2.5 | | 2.5 | 2.5 | |
| Lane Grp Cap (vph) | 208 | 1994 | | 459 | 2506 | 776 | | 131 | 327 | 507 | 234 | |
| v/s Ratio Prot | 0.07 | c0.48 | | 0.07 | 0.34 | | | 0.03 | c0.15 | c0.10 | 0.03 | |
| v/s Ratio Perm | | | | | | 0.10 | | | | | | |
| v/c Ratio | 0.60 | 0.98 | | 0.52 | 0.68 | 0.19 | | 0.36 | 0.74 | 0.72 | 0.19 | |
| Uniform Delay, d1 | 52.5 | 31.6 | | 50.6 | 23.6 | 17.1 | | 55.1 | 46.5 | 51.0 | 47.0 | |
| Progression Factor | 0.89 | 0.56 | | 1.04 | 0.87 | 1.15 | | 1.00 | 1.00 | 1.00 | 1.00 | |
| Incremental Delay, d2 | 1.7 | 10.2 | | 0.5 | 1.0 | 0.4 | | 1.2 | 7.9 | 4.5 | 0.3 | |
| Delay (s) | 48.4 | 28.1 | | 53.3 | 21.4 | 20.0 | | 56.3 | 54.5 | 55.6 | 47.3 | |
| Level of Service | D | C | | D | C | B | | E | D | E | D | |
| Approach Delay (s) | | 29.3 | | | 24.6 | | | 54.8 | | | 53.0 | |
| Approach LOS | | C | | | C | | | D | | | D | |

| Intersection Summary | | | |
|-----------------------------------|-------|----------------------|------|
| HCM Average Control Delay | 31.1 | HCM Level of Service | C |
| HCM Volume to Capacity ratio | 0.84 | | |
| Actuated Cycle Length (s) | 125.0 | Sum of lost time (s) | 15.5 |
| Intersection Capacity Utilization | 82.1% | ICU Level of Service | E |
| Analysis Period (min) | 15 | | |
| c Critical Lane Group | | | |



July 22, 2013

Project #: 12116.0

Sherilyn Lombos, City Manager
City of Tualatin
18880 SW Martinazzi Ave.
Tualatin, OR 97062

RE: Response to DKS Supplemental Traffic Analysis Included in City of Tualatin's Staff Report for the Nyberg Rivers Master Plan

As a follow-up to your correspondence with Fred Bruning, Centercal Properties, LLC, this letter addresses the July 11, 2013 *Nyberg Rivers Supplemental Traffic Analysis* prepared by DKS Associates (herein referred to as the *Supplemental Traffic Analysis Review*) for the Nyberg Rivers project in Tualatin, Oregon. An executive summary is presented below followed by additional details. Please include this as part of the formal record for the Nyberg Rivers Master Plan application.

EXECUTIVE SUMMARY

The *Supplemental Traffic Analysis Review* identifies two fundamental issues, trip generation and access.

Trip Generation:

The *Supplemental Traffic Analysis Review* opines that the April 2013 Transportation Impact Analysis (April 2013 TIA) underestimates site trip generation and should have individually accounted for a grocery store and fast-food restaurant.

- In our professional opinion, we conclude the April 2013 TIA trip generation offers the most reliable trip generation estimate. We base this conclusion on:
 - Comparison of the April 2013 TIA methodology to two other existing sites in Tualatin including Nyberg Woods to the east and Bridgeport Village to the north; and
 - Calculation errors and no traffic engineering basis for the approach taken by DKS in the *Supplemental Traffic Analysis Review* trip generation.

Access to SW Martinazzi Avenue:

The *Supplemental Traffic Analysis Review* compares the April 2013 TIA queuing with the probable gap acceptance of left-turn vehicles and queuing on SW Martinazzi Avenue at a theoretical level.

- The review assessment is based on outdated information. The Applicant provided a May 16, 2013 supplemental analysis relying on additional field-collected data on site at the existing

City Hall/Library driveway that is specifically calibrated to the available gaps and capacity on SW Martinazzi Avenue. This is a far more accurate method than that used by DKS.

- The *Supplemental Traffic Analysis Review* methodology uses software-based simulation analysis that relies upon 1) unreasonably high site trip generation estimates and 2) an assumption that drivers won't use other available site driveways with less delay and queuing, which is clearly unreasonable.

The specific Comments/Conclusions made in the *Supplemental Traffic Analysis Review* are included in *italics* below followed by our response and any necessary supporting documentation.

ISSUE 1 - REFINED TRIP GENERATION

DKS Comment: *Based on our review of the Nyberg Rivers Master Plan, we recommend an alternative trip generation estimate be used for the proposed development. Rather than treating all uses the same (i.e., part of a single "shopping center" land use category), as was done in the April 2013 TIA, we recommend treating several uses separately since they are significantly different from typical shopping center use. When these uses are treated separately, the resulting net increase in peak hour traffic generation is 405 to 435 trips higher than the estimates in the applicant's TIA report.*

Response Refined Trip Generation Comment:

Kittelson & Associates, Inc. prepared and submitted a June 21, 2013 letter that provided a detailed summary of trip generation considerations in response to City staff questions regarding the April 2013 TIA. For reasons previously stated in our June 21, 2013 letter, we continue to strongly disagree with the premise that some uses should be separated from the shopping center for the purposes of the TIA.

In our professional opinion, there is no traffic engineering basis for separating the highest trip generating uses from the shopping center as the *Supplemental Traffic Analysis Review* suggested and then continuing to apply the shopping center trip generation rate for the lower trip generating uses (which assumes a blend of higher and lower trip generating uses). The result of the DKS approach is in an unreasonably high trip generation estimate. To support this opinion, two case studies of local shopping centers are presented for illustrative purposes.

Case Study 1) Bridgeport Village Trip Generation Comparison

To provide further evidence that the using the ITE shopping center trip generation rate results in a reasonable yet conservative estimate of trip generation, we reviewed the trip of Bridgeport Village as described below.

- Traffic counts were completed at all of the driveways serving Bridgeport Village in 2007.
- At the time Bridgeport Village had approximately 440,000 gross square feet of leasable retail floor area (GLA) which included a Wild Oats supermarket.

Table 1 compares the traffic count results with ITE *Trip Generation, 9th Edition* data.

Table 1 – Bridgeport Village Site Traffic Counts Compared ITE Shopping Center Trip Data

| Data Source | PM Peak Hour Trip Rate (Trips/1,000 Square Feet of Gross Leasable Area) | Comments |
|--|--|------------------------|
| On-site Field Traffic Counts | 2.99 | Actual Trip Generation |
| ITE Trip Generation <i>Shopping Center</i> | 3.67 | 23% Higher Than Actual |

As shown in Table 1, use of ITE Shopping Center data (*without breaking out the grocery store separately*) overestimates the actual site trip generation by over 20%. As detailed in our June 21, 2013 letter, similar comparison of Saturday peak hour data found the actual trip rate was approximately 25 percent lower than that forecast with the ITE Shopping Center trip generation rate.

Clearly, further increasing the site trip generation estimate by breaking out the grocery store and other individual pad buildings at Bridgeport Village would exacerbate the over-estimation of trips.

Case Study 2) Nyberg Woods Trip Generation Comparison

Similar to Case Study 1, we reviewed the trip of Nyberg Woods (located directly across I-5 to the east of the site) as described below.

- Traffic counts were completed at all of the Nyberg Woods driveways in 2012.
- At the time Nyberg Woods had approximately 207,000 gross square feet of leasable retail floor area (GLA).

Table 2 compares the traffic count results with ITE *Trip Generation, 9th Edition* data.

Table 2 – Nyberg Woods Site Traffic Counts Compared ITE Shopping Center Trip Data

| Data Source | PM Peak Hour Trip Rate (Trips/1,000 Square Feet of GLA) | Comments |
|--|--|------------------------|
| On-site Field Traffic Counts | 3.74 | Actual Trip Generation |
| ITE Trip Generation <i>Shopping Center</i> | 4.71 | 26% Higher Than Actual |

As shown in Table 2, the ITE Shopping Center trip generation rate was also over 20 percent higher than the actual trip generation rate during the weekday p.m. peak hour. The actual Saturday midday peak hour trip rate was found to be approximately 7 percent lower than the ITE Shopping Center trip generation rate.

Based on the three case studies above and the mix of uses they reflect, we remain confident that use of the ITE Shopping Center data as applied in the April 2013 TIA is not only appropriate, but likely *overestimates* the impact of the proposed development.

Other Considerations:

The *Supplemental Traffic Analysis Review* states that a separation of the grocery and fast food land uses would result in a net increase of 435 weekday p.m. peak hour trips and 405 Saturday midday peak hour trips compared the April 2013 TIA trip generation estimates.

In addition to the case study examples, we further note that is not possible to directly compare the trip estimates provided in the April 2013 TIA and the *Supplemental Traffic Analysis Review* for the following reasons:

- The two methodologies are fundamentally different in how they account for existing uses that are proposed to remain on the site after redevelopment occurs (the *Supplemental Traffic Analysis Review* is not reflective of the actual building area changes proposed).
 - The shopping center square footage is overestimated in the *Supplemental Traffic Analysis Review* methodology. The actual proposed shopping center square footage is approximately 190,931 square feet, not the 232,043 square feet used in the *Supplemental Traffic Analysis Review*.
- The *DKS Supplemental Traffic Analysis Review* assumed a 10% internalization reduction whereas the April 2013 TIA methodology assumed a 20% reduction. DKS offers no basis or research to support the 10% internalization assumption whereas there are multiple research studies supporting the 20% internalization reduction including the *ITE Trip Generation*. Further, their internal trip reduction did not account for the existing retail development on site.
- The *DKS Supplemental Traffic Analysis Review* assumed no trip reduction for the vacant K-mart and Jiggles uses. Data collected on-site when the original traffic counts were conducted (used in the April 2013 TIA) revealed these uses accounted for approximately 200 weekday p.m. peak hour trips (this oversight alone accounts for approximately half the difference they reported).

Because of the above discrepancies and the fundamental difference in structure of the two methodologies, a meaningful side-by-side comparison cannot be made.

ISSUE 2- SW MARTINAZZI AVENUE DRIVEWAY OPERATIONS

The *Supplemental Traffic Analysis Review* included the refined trip generation analysis and a Synchro-based operations assessment of the SW Martinazzi Avenue site driveways. Particular emphasis was made regarding the April 2013 TIA's use of two-stage gap acceptance and queuing analyses that didn't consider the interaction with adjacent upstream and downstream traffic signals.

Response #1 to the SW Martinazzi Avenue Driveway Operations Comment

Kittelson & Associates, Inc. provided a revised assessment of driveway operations along SW Martinazzi Avenue in the May 16, 2013 *Additional Nyberg Rivers Traffic Analysis* and the June 21, 2013 *Response*

to City of Tualatin June 3, 2013 letter (*Preliminary Review Comments: Nyberg Rivers Master Plan*). This revised assessment included a detailed calculation of SW Martinazzi Avenue driveway operations using field-calibrated capacity calculations. This field-calibrated data takes into consideration the two-stage gap acceptance concerns noted in the *Supplemental Traffic Analysis Review* and is a more reliable assessment of future conditions.

The comments provided in the *Supplemental Traffic Analysis Review* address the April 2013 TIA, not the subsequent detailed analyses prepared and presented responding to initial City staff-provided comments. The May and June 2013 materials cited above and provided by Kittelson & Associates, Inc. address the issues raised in the *Supplemental Traffic Analysis Review* and provide reliable site-specific data. Accordingly, we stand by our findings from the May and June 2013 supplemental letters and conclude that the SW Martinazzi Avenue/City Hall driveway can continue to operate within standards with the proposed project.

Response #2 to the SW Martinazzi Avenue Driveway Operations Comment

The *Supplemental Traffic Analysis Review* methodology relies upon SimTraffic simulation software to produce queuing results at the site driveways to SW Martinazzi Avenue. The reported findings indicate that the site will incur extreme vehicle queue lengths during the peak time periods; however, no technical documentation of the software analysis results is provided.


Notwithstanding the reported but undocumented simulation results in the *Supplemental Traffic Analysis Review*, the findings (including a reported queue of 2,000 feet (almost ½ mile) at one driveway) are clearly not reasonable and suggest no attempt was made to calibrate the simulation model to existing conditions (a significant modeling oversight) and/or conduct a more reasonable future conditions analysis. The proposed redevelopment site has multiple driveways that provide alternative egress routes. Given most drivers naturally identify and drive routes with the least delay/shortest path, it is unreasonable to suggest the extreme vehicle queue lengths being reported in the *Supplemental Traffic Analysis Review* will ever be realized. Furthermore, the *Supplemental Traffic Analysis Review* is predicated on site trip generation estimates that we believe are grossly over-estimated as documented in the response to Issue #1.

Thank you for the opportunity to respond to the *Supplemental Traffic Analysis Review* comments. Please contact us with any questions you may have.

Sincerely,
KITTELSON & ASSOCIATES, INC.



Mark Vandehey, P.E.



June 21, 2013

Project #: 12116

Christe White
Radler, White, Parks & Alexander, LLP
111 SW Columbia Street, Suite 1100
Portland, OR 97201

RE: Response to City of Tualatin June 3, 2013 letter (Preliminary Review Comments: Nyberg Rivers Master Plan)

Dear Christe,

This letter addresses the Transportation Impact Analysis comments included in the City of Tualatin's *June 3, 2013 Preliminary Review Comments: Nyberg Rivers Master Plan (MP-13-01)*. Our response focuses on the City's comments regarding Central Urban Renewal District Plan (CURD) Goal 5: Transportation and specifically the Traffic Impact Analysis (TIA) comments on pages 3-5 of the City's letter. The City's comment/request for additional information is included in italics followed by our response.

TIA Comment #1

ODOT reviewed the submitted information for their facilities (I-5 and Nyberg Street). Although, the underlying model artificially limits queues and the settings do not meet ODOT standards, ODOT reran the analysis using the correct settings. Based on this analysis the proposed improvements mitigate the impact of the development on ODOT facilities (see attached comments from ODOT). City staff provides comments below on the TIA, which will require the applicant to revise the TIA. ODOT will need to review the updated TIA to confirm whether the proposed improvements still mitigate the impact of the development on ODOT facilities. Final design may indicate the need for additional right-of-way.

Response to Comment #1:

The City is correct that the signalized intersection operational analysis model used to for the TIA deviated from ODOT's Analysis Procedures Manual (APM). The changes made to the model were needed to accurately model the adaptive signal control system that operates the traffic signals that were studied along SW Tualatin-Sherwood Road. The statement "the underlying model artificially limits queues" is incorrect. The changes made to the model were implemented to more reasonably reflect queues resulting from the adaptive signal control system (adaptive traffic signal control is a relatively new technology implementation and is not currently explicitly analyzed by the model or the ODOT APM procedures).

ODOT has completed their independent review of the TIA and also conducted their own sensitivity analysis by applying the standard method outlined in the ODOT APM. ODOT staff concurred with the TIA findings and recommendations as it relates to ODOT facilities.

We respectfully disagree with the statement "*City staff provides comments below on the TIA, which will require the applicant to revise the TIA. ODOT will need to review the updated TIA to confirm whether the proposed improvements still mitigate the impact of the development on ODOT facilities*". The remainder of this letter addresses each of the City staff comments and provides additional information requested where appropriate. As will be evidenced by our responses herein, none of the comments provided by the City warrant revising the TIA. Further, none of the City comments warrant any change to the results presented relative to ODOT facilities reviewed in the original TIA. As such, no new comments from ODOT staff are anticipated.

TIA Comment #2

Washington County also reviewed the information and they have provided a list of conditions and measures to mitigate impacts on Nyberg Street and Tualatin Sherwood Road (please see attached comments from Washington County). City staff provided comments below on the TIA, which will require the applicant to revise the TIA. Washington County will need to review the updated TIA to confirm whether the proposed improvements still mitigate the impact of the development on Washington County facilities. Final design may indicate the need for additional right-of-way.

Response to TIA Comment #2

Similar to the response above relative to ODOT, Washington County staff conducted an independent review of the TIA and concurred with the key findings and recommendations. No changes to the TIA were requested by County staff.

Similar to our response to TIA Comment #1, none of the City comments warrant any change to the results presented relative to Washington County facilities reviewed in the original TIA. As such, no new comments from Washington County staff are anticipated.

TIA Comment #3a

The City reviewed the TIA to ensure that internal circulation is consistent with the TSP and that the new development improves traffic circulation on Martinazzi, the City's portion of Nyberg, Boones Ferry and other nearby roadways. After the Master Plan was submitted, a list of questions and concerns was sent and a meeting was held with Kittelson & Associates to review the issues. Kittelson submitted information to address some of those concerns on May 16, 2013. Even with both submittals, the City still has the following concerns with the information provided:

- a) *On Page 44 of the TIA submitted with the Master Plan, the applicant provides queuing analysis for Nyberg Road and the freeway. This same level of analysis is needed for Martinazzi, Boones*

Ferry Road the proposed Seneca Street, Street A and the existing driveway easement from the driveway to Martinazzi. The submitted analysis should include:

- i. -Existing queue storage length*
- ii. -Proposed queue storage length that is required for new development; and*
- iii. -An analysis of whether additional queue space is needed.*

Response to TIA Comment #3a

The original TIA and supplemental analysis provided queuing information for key locations serving the proposed development where queuing impacts could be pronounced. Queuing data was not provided at other locations in the original TIA because it was clear from the operational evaluation conducted at these intersections that the project would have either have a negligible impact on queues or (in the case of new intersections such as the Seneca extension or Street A) the proposed design provided more than sufficient queue storage.

The intent of the information provided to City staff in our May 16, 2013 letter was to confirm for the City's benefit the project's impact to queuing at the identified intersections. The information provided in the May 16, 2013 letter confirmed the project would have either have a negligible impact on queues or (in the case of new intersections such as the Seneca extension or Street A) the proposed design provided more than sufficient queue storage.

Table 1 below presents the existing available storage at each of the study intersections along with the 95th percentile queues documented in Table 3 of our May 16, 2013 letter. As confirmed once again in Table 1 below, the added traffic from the Nyberg Rivers project results in a negligible change in queuing at the study intersections.

Table 1 – 95th Percentile Queue Projections at the Study Intersections

| Intersection | Movement | Estimated 95 th Percentile Queue (ft) | | | | Storage Length |
|--|----------|--|---------------|---------------------------|---------------|------------------|
| | | Weekday PM Peak Hour | | Saturday Midday Peak Hour | | |
| | | Background Traffic | Total Traffic | Background Traffic | Total Traffic | |
| SW Martinazzi Avenue/ SW Boones Ferry Road | NB LT | 325 | 325 | 125 | 150 | 275 ¹ |
| | NB RT | 250 | 275 | 150 | 175 | 275 |
| | WB LT | 350 | 375 | 150 | 200 | 150 ² |
| | EB RT | 150 | 175 | 75 | 100 | 200 |
| SW Martinazzi Avenue/ City Library Driveway (Driveway #4) | SB LT | 75 | 100 | 25 | 50 | 275 ¹ |
| | WB LT | 75 | 100 | 25 | 50 | 200 |
| | WB RT | 50 | 50 | 25 | 50 | 200 |
| SW Martinazzi Avenue/ City Library Driveway (Driveway #4) (Assuming Driveway #6 is Closed) | SB LT | 75 | 100 | 25 | 50 | 75 |
| | WB LT | 75 | 100 | 25 | 50 | 200 |
| | WB RT | 50 | 50 | 25 | 50 | 200 |
| SW Martinazzi Avenue/ SW Seneca Street/ Potential Site Access Driveway* | SB LT | - | 50 | - | 50 | 150 |
| | SB THRT | - | 125 | - | 75 | 200 |
| | WB RT | - | 100 | - | 75 | 200 |
| | WB THLT | - | 50 | - | 50 | 200 |
| | NB THRT | - | 200 | - | 100 | 225 |
| | NB LT | - | 50 | - | 25 | 75 |
| SW Martinazzi Avenue/ Nyberg Road | SB TH | 100 | 100 | 75 | 75 | 225 |
| | NB THRT | 125 | 150 | 125 | 125 | 275 |
| | WB LT | 100 | 100 | 75 | 75 | 275 |
| | WB RT | 150 | 150 | 125 | 125 | 275 |
| SW Martinazzi Avenue/ SW Tualatin-Sherwood Road | SB THRT | 350 | 350 | 225 | 225 | 325 |
| | SB LT | 250 | 250 | 175 | 175 | 275 |
| | NB THRT | 350 | 350 | 250 | 250 | 400 |
| | EB LT | 100 | 100 | 125 | 125 | 150 |
| SW Boones Ferry Road/ Proposed Street A | NB RT | - | 25 | - | 25 | 150 |

NB = Northbound; SB = Southbound; EB = Eastbound; WB = Westbound

LT = Left-Turn; TH = Through; RT = Right-Turn

* - Under the scenario that includes a Seneca Street extension into the project site

¹Represents the distance of the two-way center left-turn lane along SW Martinazzi Avenue and Driveway #4.

²Represents the striped WB LT storage distance. An additional 175 feet of full width storage distance is available before the lane narrows over the Tualatin River.

As shown in Table 1, adequate storage length exists for all but the following movements:

- The northbound left-turn at the SW Boones Ferry Road/SW Martinazzi Avenue intersection and the southbound left-turn at the SW Martinazzi Avenue/City Library Driveway #4.
 - Both of these movements share the same 275 feet of center left-turn lane. Field observations noted that there are periods of vehicle queue overlap between these two intersections during peak time periods. This situation was described in more detail on pages 2 and 3 of the May 16, 2013 letter. The Nyberg Rivers project has a negligible impact on this existing condition.
- The westbound left-turn movement at the SW Boones Ferry Road/SW Martinazzi Avenue intersection.
 - The total available full width storage for this movement is approximately 325 feet whereas the background 95th percentile queue is 350 feet. With the proposed development, the 95th percentile queue is forecast to marginally increase by an additional 25 feet (one car length) beyond background traffic conditions. There is no opportunity to increase westbound left-turn storage at the intersection short of widening the SW Boones Ferry Road bridge. There does not appear to be any turn lane extensions [proposed in the recently adopted City Transportation System Plan.
- The 95th percentile queue on the southbound shared through/right-turn movement at the SW Martinazzi Avenue/SW Tualatin-Sherwood Road intersection is forecast to exceed the available storage by one vehicle length.
 - This condition occurs under background traffic conditions regardless of site development. The proposed development does not increase the southbound queue length.

TIA Comment #3b

- b) The report assumes that very little traffic will use Martinazzi Avenue and Street A to access the development. Based on existing conditions, the City believes that is inaccurate. Most people coming from/going to the west and south will not access the site from Nyberg Street but will use Martinazzi Avenue or Boones Ferry Road. Additionally, the report does not assume truck traffic on those roadways which is inconsistent with the submitted Master Plan that shows those roadways being the main truck route. Please revise the TIA with assumptions that better match expected travel patterns.*

Response to TIA Comment #3b

We disagree with the City's assertion that the assignment of trips to SW Martinazzi and Street A is inaccurate. In our professional opinion, the trips assigned to both facilities represent a reasonable estimate of travel patterns upon build-out of the proposed Nyberg Rivers project.

As documented in the August 2012 scoping memo and the April 2013 TIA, we estimated that approximately 20 percent of the new trips will come from the north via SW Boones Ferry Road or SW Upper Boones Ferry Road. All of this traffic was assigned to either SW Martinazzi or Street A. Only five percent of the new trips are estimated to come from SW Martinazzi (south of SW Tualatin Sherwood Road). Of that five percent approximately half were assumed to use SW Martinazzi south of SW Nyberg Street to enter or egress the site and approximately half would enter or egress use travel to and/from the site from SW Tualatin Sherwood Road/SW Nyberg Street.

All of the assumptions discussed above and documented in the TIA are reasonable based on existing and estimated future travel patterns and can be relied upon by the City staff as they develop their own transportation findings and recommendations for the Nyberg Rivers project.

With respect to truck traffic, truck vehicle percentages were assumed on each of the roadways based on existing truck traffic counts. Delivery vehicles to and from commercial sites typically occur outside the weekday a.m. and p.m. peak hours and thus are not expected to have any material impact on the peak hour analysis results presented in the TIA.

TIA Comment #3c

- c) *The report utilizes conflicting assumptions of the driveway access on Martinazzi Avenue. Part of the evaluations assumes all three driveways remain open, yet another section assumes only one access connects to Martinazzi Avenue. The TIA needs to be consistent throughout the study. Any revisions may impact the queue length analysis listed above. Please make this change before completing the new queue length analysis.*

Response to TIA Comment #3c

As noted in the April 2013 TIA and reiterated in the supplemental information provided in the May 20, 2013 letter, the driveway assumptions for the two access scenarios on SW Martinazzi (with and without the SW Seneca Street extension) only differ relative to the treatment of the driveway immediately south of SW Seneca Street (indicated as driveway 6 in the April 2013 TIA).

With the SW Seneca Street extension it was assumed driveway 6 would be closed. Without the SW Seneca Street extension, driveway 6 was assumed to remain open because the project has would have no impact on this driveway (driveway 6 is not part of the proposed development site).

If the City desires to close driveway 6 regardless of the SW Seneca Street extension, the impact would be a small increase in traffic to the existing City Hall driveway (indicated as driveway 4 in the April 2013 TIA) on SW Martinazzi. Table 2 below shows the impact of the reassignment of traffic at driveway 4.

Table 2 - Detailed Operations of the Driveway #4 SW Martinazzi Avenue/City Library Driveway Assuming Driveway #6 is Closed (2014 Total Conditions)

| | 2014 Total Traffic Conditions SW Martinazzi Avenue/ City Library Driveway (Driveway #4) | 2014 Total Traffic Conditions SW Martinazzi Avenue/ City Library Driveway (Driveway #4) (Assuming Driveway #6 is closed) |
|----------------|---|---|
| SB LT Movement | LOS = B | LOS = B |
| | Control Delay = 12.1 sec | Control Delay = 12.2 sec |
| | V/C = 0.26 | V/C = 0.27 |
| WB LT Movement | LOS = E | LOS = E |
| | Control Delay = 43.4 sec | Control Delay = 44.3 sec |
| | V/C = 0.35 | V/C = 0.35 |
| WB RT Movement | LOS = C | LOS = C |
| | Control Delay = 15.7 | Control Delay = 16.4 |
| | V/C = 0.30 | V/C = 0.36 |

As indicated in Table 2, closure of driveway 6 will have a very small impact to driveway 4 and driveway 4 will continue to meet City standards for unsignalized intersection operations.

TIA Comment #3d

d) More information is needed on the timing of the traffic studies. It is unclear if the studies were completed when Kmart was open or closed (or both) and which data set was used.

Response to TIA Comment #3d

The traffic counts used in the April 2013 TIA were collected when Kmart was open. The majority of the information presented in the supplemental May 16, 2013 letter also relied on the traffic counts taken when Kmart was open.

The supplemental field observations and capacity estimates conducted for the City Hall driveway on SW Martinazzi (documented on pages 2 and 3 of the May 16, 2013 letter) were collected after the Kmart had closed. However, the capacity estimates presented in Tables 1 and 2 in the May 16, 2013 letter are considered reasonable as the northbound and southbound through traffic on SW Martinazzi has the most significant impact on the capacity of the turning movements at the driveway. The closure of Kmart has likely resulted in very little change to the northbound and southbound through traffic on Martinazzi (most Kmart customers using Martinazzi would have turned left in or right out of the City Hall driveway and that total demand is represented in the existing traffic counts (from the April 2013 TIA) and factored into the total traffic projections.

TIA Comment #3e

- e) *The applicant's traffic consultant does not draw any conclusions on the adequacy of the existing City driveway/easement taking into account the traffic generation from the proposed development, other driveway closures, and queuing issues on Martinazzi Avenue. The applicant needs to analyze this and make a conclusion about the adequacy of the existing driveway to serve this development.*

Response to TIA Comment #3e

We believe several conclusions have been presented to the City regarding the operation of the City driveway (driveway 4 in the TIA). The most substantive conclusions are as follows:

- The City driveway currently meets the City of Tualatin's Level of Service standard and will continue to meet the standard with the added traffic from Nyberg Rivers.
- There are some existing operational deficiencies that exist at the City driveway under existing conditions due to the presence of standing queues on SW Martinazzi that occasionally extend to and beyond the City Hall driveway. The analysis presented to date has demonstrated that the Nyberg Rivers development will have very little impact on this existing condition.
- An option that would eliminate the City driveway and replace it with the extension of SW Seneca Street has also been studied. Under this scenario the new SW Seneca/SW Martinazzi intersection would be signalized and would result in a significant operational improvement relative to the existing condition at the aforementioned City driveway.

None of the above conclusions suggest that the City hall driveway "must" be closed as a result of the Nyberg Rivers development as this conclusion is not supported by the traffic engineering evidence. Representatives from CenterCal remain very willing to work with the City to implement solutions that improve the operations at the driveway (including helping to implement the Seneca Street extension).

TIA Comment #3f

- f) *On Page 7 of the Master Plan, the applicant has indicated that the Primary Development Area will be redeveloped to support traditional shopping center related uses. The applicant has used a trip generation rate for Shopping Centers throughout the TIA. This is applied to all of the uses on the site. City staff questions if this results in a lower than expected trip generation. In informal discussions with the applicant, staff is aware that a specialty grocery tenant is proposed for Bldg. 1005, a stand-alone 45,000 fitness club is proposed for Building N-100 and a new drive-through restaurant use is proposed in Building H-100 – in addition to the applicant's proposal to retain drive-through uses on Buildings A, B, C, and a relocated F-100 (we believe that retaining drive-through uses on Bldg B is in error, as stated above). Staff believes it is inappropriate to apply a Shopping Center trip generation rate when so many of these proposed uses are auto-intensive and don't have traditional shopping center characteristics. In the revised submittal, please clarify the proposed uses for each building so that an accurate trip generation can be*

analyzed on the site. Based on our understanding of the proposed uses from informal conversations, staff believes that the following uses should analyzed separately from the Shopping Center trip generation rate:

- i. The two drive-through restaurants (Buildings F-100 and H-100);
 - ii. The grocery store (Bldg 1005); and
 - iii. The 45,000 square foot stand-alone health club (N-100)
- Please apply the correct trip generation rates in the revised submittal.

Response to TIA Comment #3f

We strongly disagree with the premise that the above uses should be separated from the shopping center for the purposes of the TIA. As noted in *Trip Generation, 9th Edition* (published by the Institute of Transportation Engineers), "A shopping center is an integrated group of commercial establishments that is planned, developed, owned and managed as a unit. Many shopping centers, in addition to the integrated unit of shops in one building or enclosed around a mall, include outparcels (peripheral buildings or pads located on the perimeter of the center adjacent to the streets and major access points."

Separating the higher trip generating uses from the shopping center as the City suggests and continuing to apply the shopping center trip generation rate for the lower trip generating uses (which assumes a blend of higher and lower trip generating uses) would result in an unreasonably conservative estimate of trip generation. ITE practice would then dictate application of internal trip reductions between each of the site uses to account for internal trips that are inherently addressed in the shopping center trip data. To emphasize this point, a weekday p.m. peak hour trip generation calculation was performed where all of the major site uses were separated. A summary table of these calculations is shown in Table 3 below and the detailed breakout calculations are summarized in Appendix A.

Table 3 - Nyberg Rivers Trip Generation (with uses separated)

| | ITE Code | Size (sq. ft.) | Weekday PM Peak Hour | | |
|---------------------------------------|----------|----------------------|----------------------|------------|------------|
| | | | Total | In | Out |
| Existing Site Driveways ¹ | - | - | 945 | 435 | 510 |
| Less Existing Library ² | 590 | 22,123 | (160) | (75) | (85) |
| Less Existing Civic Uses ³ | 715 | ~10,000 | (50) | (10) | (40) |
| Total Existing Retail | | | 735 | 350 | 385 |
| Proposed Site ⁵ | 820 | 307,000 ⁴ | 1,465 | 750 | 715 |
| Less Existing Retail Driveway Counts | | | (735) | (350) | (385) |
| Sub Total | | | 730 | 400 | 330 |
| Less Internal Trips (20%) | | | (295) | (150) | (145) |
| Pass-by Trips (varies) | | | (310) | (155) | (155) |
| Net New Trips | | | 125 | 95 | 30 |

Table 4 below compares Table 3 above with the original Trip Generation calculations in the *April 2013 Nyberg Rivers Traffic Impact Study*. The following key points can be taken from the comparison:

- Separating out the uses results in a total gross trip generation that is approximately nine percent higher during the weekday p.m. peak hour.
- However, the total driveway trips are approximately 15 percent lower when the uses are separated. The reason for the reduction is due to the assumption that 20 percent of the trips are captured internally when we separate the uses. There is no internal trip reduction for the shopping center because it is already incorporated in the trip generation rate.
- The total net new trips are substantially lower when separating out the uses. The reason for the substantial difference is related to the fact that the higher trip generating uses (banks and fast food restaurant) have a much higher pass-by rate than what is included in the shopping center rate.

Table 4 – Summary Comparison of Trip Generation Methodologies

| | Trip Generation Summary from the Original April 2013 Traffic Impact Study (Weekday PM Peak Hour Trips) | Trip Generation Summary Separating All Proposed Site Uses (Weekday PM Peak Hour Trips) |
|-----------------------------|--|--|
| Total Gross Trip Generation | 1,350 | 1,465 |
| Total Driveway Trips | 1,350 | 1,170 |
| Net New Trips | 405 | 125 |

In summary, Table 4 clearly shows that separating out the site uses would result in a lower number of total driveway trips and a lower number of net new driveway trips. As such, the trip generation methodology used in the April 2013 is more conservative and provides a more robust estimate of the transportation related impacts associated with the proposed Nyberg Rivers development.

To provide further evidence that the using the ITE shopping center trip generation rate results in a reasonable yet conservative estimate of trip generation two local examples (Nyberg Woods and Bridgeport Village) were evaluated.

- In 2007 the total volume of driveway trips were counted for the three driveways serving Bridgeport Village. At the time Bridgeport Village had approximately 440,000 gross square feet of leasable retail floor area (GLA) which included a Wild Oats supermarket. The actual driveway counts revealed a total trip generation rate of 2.99 trips per thousand square feet of GLA during the weekday p.m. peak hour (4-6 p.m.). *Trip Generation, 9th Edition* suggests a 440,000 square foot shopping center would result in a trip generation rate of approximately 3.67 trips per thousand square feet of GLA evaluation, which is approximately 20 percent higher than the actual trip generation rate. On a Saturday peak hour the actual trip rate was found to be approximately 25 percent less than the ITE Shopping Center trip generation rate.

- Nyberg Woods (directly across the site from I-5) includes approximately 207,000 gross square feet of leasable floor area (GLA). Actual traffic counts were collected in 2012 which revealed a total trip generation rate of 3.74 trips per thousand square feet of GLA during the weekday p.m. peak hour (4-6 p.m.). *Trip Generation, 9th Edition* suggests a 207,000 square foot shopping center would result in a trip generation rate of approximately 4.71 trips per thousand square feet of GLA evaluation, which, similar to Bridgeport Village is approximately 20 percent higher than the actual trip generation rate. On a Saturday peak hour the actual trip rate was found to be approximately 7 percent lower than the ITE Shopping Center trip generation rate.

Based on these two local retail centers and the mix of uses they reflect, we remain confident that use of the ITE shopping center data is not only appropriate, but likely represents a conservative (overestimates) the impact of the proposed development.

We trust this local trip generation data helps City staff to confirm the reasonableness of applying the Shopping Center trip generation rate for the proposed Nyberg Rivers project.

Thank you for the opportunity to respond to staffs questions and comments. We would be happy to further discuss these or other issues as needed and look forward to finalizing the on- and off-site mitigation needs associated with the project.

If you have any questions, please contact us.

Sincerely,
KITTELSON & ASSOCIATES, INC.



Mark Vandehey, P.E.

Appendix A Detailed Trip Generation
Calculations

Nyberg Rivers Calculated Trip Generation Values for Weekday PM Peak, Including Existing Development

| Land Use | ITE Code | Size (SF) | Discount Rate | Total Trips | Trips In | Trips Out |
|--|----------|-----------|----------------------------|-------------|----------|-----------|
| Sporting Goods Superstore | | | | 185 | 89 | 96 |
| Internal Trips | 861 | 110,093 | 0.2 | 37 | 18 | 19 |
| Pass-by Trips | | | 0 | 0 | 0 | 0 |
| Net New Trips | | | | 148 | 71 | 77 |
| Furniture Store | | | | 10 | 5 | 5 |
| Internal Trips | 890 | 21,750 | 0.2 | 2 | 1 | 1 |
| Pass-by Trips | | | 0.53 | 4 | 2 | 2 |
| Net New Trips | | | | 4 | 2 | 2 |
| Specialty Retail | | | | 182 | 80 | 102 |
| Internal Trips | 826 | 66,777 | 0.2 | 36 | 16 | 20 |
| Pass-by Trips | | | 0 | 0 | 0 | 0 |
| Net New Trips | | | | 145 | 64 | 81 |
| Drive-in Bank | | | | 230 | 115 | 115 |
| Internal Trips | 912 | 9,485 | 0.2 | 46 | 23 | 23 |
| Pass-by Trips | | | 0.47 | 87 | 43 | 43 |
| Net New Trips | | | | 98 | 49 | 49 |
| Fast-Food Restaurant with Drive-Through Window | | | | 262 | 136 | 126 |
| Internal Trips | 934 | 8,026 | 0.2 | 52 | 27 | 25 |
| Pass-by Trips | | | 0.5 | 101 | 50 | 50 |
| Net New Trips | | | | 109 | 59 | 50 |
| High-Turnover Sit-Down Restaurant | | | | 121 | 73 | 48 |
| Internal Trips | 932 | 12,297 | 0.2 | 24 | 15 | 10 |
| Pass-by Trips | | | 0.43 | 33 | 17 | 17 |
| Net New Trips | | | | 64 | 41 | 22 |
| New Seasons Grocery Store | | | | 318 | 162 | 156 |
| Internal Trips | 850 | 33,572 | 0.2 | 64 | 32 | 31 |
| Pass-by Trips | | | 0.36 | 90 | 45 | 45 |
| Net New Trips | | | | 165 | 85 | 80 |
| Health/Fitness Club | | | | 159 | 91 | 68 |
| Internal Trips | 492 | 45,000 | 0.2 | 32 | 18 | 14 |
| Pass-by Trips | | | 0 | 0 | 0 | 0 |
| Net New Trips | | | | 127 | 72 | 55 |
| Total SF | | 307,000 | Total Net New Trips | 859 | 443 | 416 |

Summary of Nyberg Rivers Calculated Trip Generation Values for Weekday PM Peak

| Land Use | ITE Code | Size (SF) | Total Trips | Trips In | Trips Out |
|--|--|-----------|-------------|------------|------------|
| Existing Site | | | | | |
| Existing Site Driveways | - | - | 945 | 435 | 510 |
| Less Existing Library | 590 | 22,123 | 160 | 75 | 85 |
| Less Existing Civic Uses | 715 | ~10,000 | 50 | 10 | 40 |
| Total Existing Retail | | | 735 | 350 | 385 |
| Future Site | | | | | |
| Future Site Driveways (sporting goods superstore, furniture store, specialty retail, drive-in bank, fast-food restaurant, sit-down restaurant, supermarket, health/fitness club) | 861, 890, 826, 912, 934, 932, 850, 492 | 307,000 | 1467 | 750 | 717 |
| Less Existing Driveway Counts | | | 735 | 350 | 385 |
| Sub-Total | | | 732 | 400 | 332 |
| Less Total Internal Trips | | | 293 | 150 | 143 |
| Less Total Pass-by Trips | | | 314 | 157 | 157 |
| Total Net New Trips | | | 124 | 93 | 31 |



KITTELSON & ASSOCIATES, INC.

TRANSPORTATION ENGINEERING / PLANNING

610 SW Alder Street, Suite 700, Portland, OR 97205 P 503.228.5230 F 503.273.8169

July 30, 2013

Project #: 12116

Christe White
Radler, White, Parks & Alexander, LLP
111 SW Columbia Street, Suite 1100
Portland, OR 97062

RE: Response to Mackenzie Nyberg Rivers Transportation Review Letter

This letter addresses the transportation issues identified in the July 22, 2013 letter from Brent Ahrend to Bob Durgan. Each of the Mackenzie comments are italicized followed by our response.

Comment: *A corridor analysis should be provided to replicate the effects of adjacent intersections on delay and vehicle queues.*

Response: We disagree. The Kittelson analysis conducted in the April 2013 TIA and supplemental material reasonably estimate the traffic impacts associated with the Nyberg Rivers proposed development plan. The operations analysis conducted at the study intersections was performed using Synchro and SimTraffic. For the SW Tualatin-Sherwood Road corridor which operates under an adaptive signal control, these programs are sufficient at capturing and assessing the effects of traffic interaction between adjacent intersections.

At the intersection where the project is anticipated to have the most significant impact (SW Nyberg Road/SW Tualatin-Sherwood/Fred Meyer/Site driveway), field observations confirmed that deterministic queuing estimates presented in the TIA are reasonable and can be relied upon for future operational and design considerations.

Comment: *Effects of WES rail crossings should be addressed (it has been ignored in the analysis), notably for queue spillback to other intersections.*

Response: We disagree. First, it should be noted that the Nyberg Rivers project is forecast to have an insignificant impact to the SW Boones Ferry/SW Tualatin-Sherwood Road intersection (less than two percent increase in traffic and less than one vehicle per signal cycle on any approach). Regardless, during the 4 to 5 times per peak hour WES pre-empts the eastbound and westbound movements, additional green time is allocated to the north-south through movements on SW Boones Ferry Road. Depending on when the pre-emption occurs, additional green time is then provided to the east-west through movements in the subsequent signal phase to attempt to compensate for lost green time in the previous phase. As a result of WES, the average control delay results shown at this intersection for all conditions (existing, background and total) may be slightly underestimated for some movements

FILENAME: *K:\H_PORTLAND\PROJFILE\12116 - K-MART TUALATIN REDEVELOPMENT\HEARING\MACKENZIE TRAFFIC RESPONSE.DOCX\KITTELSON.COM\FS\H_PORTLAND\PROJFILE\12116 - K-MART TUALATIN REDEVELOPMENT\HEARING\MACKENZIE TRAFFIC RESPONSE.DOCX*

**Exhibit 1
Attachment L**

and slightly overestimated for others. Under any scenario, the intersection meets or exceeds Washington County's operating standards.

Comment: *Signal timing parameters need to be adjusted, specifically to address the longer travel times for eastbound traffic which must stop behind the rail crossing.*

Response: Detailed signal timing parameters may provide an added level of precision to the operational assessment of the SW Tualatin-Sherwood Road/SW Boones Ferry Road intersection. This level of additional analysis is clearly not warranted given the minimal impacts that the proposed Nyberg Rivers project is forecast to have. The project is projected to add approximately 20 vehicles to this eastbound through movement during the weekday p.m. peak hour which is less than one vehicle every signal cycle. Overall the project will result in less than a 2 percent increase in traffic at this intersection. This impact by any traffic engineering standard can be considered insignificant and is well below an impact level that would be perceived by anyone who regularly travels through the intersection.

Comment: *Trucks have been observed slowing at the rail crossing, which will impact available capacity. This should be accounted for in the analysis.*

Response: As noted previously, we believe this added level of precision in the analysis is unwarranted given the project's insignificant impact to the SW Tualatin-Sherwood Road/SW Boones Ferry Road intersection and the fact that the capacity impact of trucks is already reflected in the analysis methodology. No evidence has been offered to suggest that the "observed slowing" would result in a greater capacity impact than is already reflected in the analysis methodology.

Comment: *Traffic counts should include those vehicles arriving at the back of a queue, not just those making it through the intersection at peak times (HCM 2010 requires this in congested corridors).*

Response: The traffic count issue described above only applies to situations where demand exceeds capacity over the entire analysis period. There is no evidence to suggest that the demand exceeds capacity over the entire study period for the study intersections on SW Tualatin-Sherwood Road. Occasional cycle failures do occur as is common on high volume arterials similar to SW Tualatin-Sherwood Road. To the extent there is some residual demand from one peak 15 minute interval it will be captured in the next 15 minute interval. The volumes used in the TIA are an adequate representation of the demand for the peak hours that were studied.

Thank you for the opportunity to respond to the Mackenzie comments. Please contact us with any questions you may have.

Sincerely,
KITTELSON & ASSOCIATES, INC.



Mark Vandehey, P.E.

**Nyberg Rivers – Tualatin, Oregon
Tree Assessment Report
September 5, 2013**

MHA1324

Purpose

This Tree Assessment Report for the Nyberg Rivers project site in Tualatin, Oregon, is provided pursuant to City of Tualatin Development Code Chapter 34. This report describes the existing trees located on the project site, as well as recommendations for tree removal, retention, and protection during construction. This report is based on observations made by International Society of Arboriculture (ISA) Certified Arborist Morgan Holen (PN-6145A) during a site visit conducted on July 29, 2013. A complete description of individual trees is provided in the enclosed tree inventory data.

Scope of Work and Limitations

Morgan Holen & Associates, LLC, was contracted by Cardno to collect tree inventory data for individual trees measuring eight inches and larger in diameter and to develop an arborist report and tree plan for the project. The site is planned for commercial redevelopment. A site plan was provided by Cardno illustrating the location of existing trees and potential construction impacts; the required Tree Preservation Site Plan is enclosed.

Visual Tree Assessment (VTA) was performed on individual trees located across the site. The enclosed tree inventory data and site plan demonstrate that all trees on site were physically identified; additionally, existing trees were identified in the field with aluminum tags corresponding with tree identification numbers provided in the tree inventory data and illustrated on the site plan. VTA is the standard process developed by the ISA whereby the inspector visually assesses the tree from a distance and up close, looking for defect symptoms and evaluating overall condition and vitality of individual trees. Trees were evaluated in terms of general condition and potential construction impacts. Following the inventory fieldwork, we coordinated with Cardno to discuss and finalize treatment recommendations.

The client may choose to accept or disregard the recommendations contained herein, or seek additional advice. Neither this author nor Morgan Holen & Associates, LLC, have assumed any responsibility for liability associated with the trees on or adjacent to this site.

General Description

The Nyberg Rivers project site is heavily developed with existing commercial buildings and asphalt parking lots. In all, 607 individual trees are included in the inventory and shown on the site plan. However, 59 (10%) trees measured less than eight inches in diameter, the City's threshold diameter for regulated trees. Therefore, 548 (90%) non-exempt trees measuring eight inches and larger were inventoried, representing 41 different tree species. A complete description of individual trees is provided in the enclosed tree inventory data.

Except for the relatively natural area in the northeast portion of the site, the trees were primarily planted for landscaping purposes and include a variety of species and trees in variable condition. The trees located within parking lot islands and directly adjacent to buildings are in mostly moderate to poor condition; common defects include sunscald, stem decay, and crown dieback. Many of these trees appeared with inadequate soil volume and drought stress.

The oaks (*Quercus* spp.) and Douglas-firs (*Pseudotsuga menziesii*) are the most prominent trees on the site, but also exhibit variable condition. Many of the oaks have not received regular maintenance over time and have broad crowns and numerous low-lying branches, and some of the Douglas-firs appear with defects that increase their potential for failure including codominant stems with included bark.

Black locust (*Robinia pseudoacacia*), English hawthorn (*Crataegus monogyna*), English holly (*Ilex aquifolium*), European white birch (*Betula pendula*), Norway maple (*Acer platanoides*), sweet cherry (*Prunus avium*), and tree-of-heaven (*Ailanthus altissima*) are widely accepted as being invasive tree species in our region and account for approximately 18-percent of the non-exempt inventoried trees. Invasive species are broadly defined as species that were introduced by humans to locations outside of their native range that spread and persist over large areas, outcompeting native species. Invasive species negatively impact natural ecosystems by displacing native species, reducing biological diversity and interfering with natural succession.

Individual trees were rated in terms of general condition as either poor, fair, or good; none of the inventoried trees were noted as excellent or remarkable. Of the 548 non-exempt trees, 101 (18%) appeared in poor condition, 293 (54%) appeared in fair condition, and 154 (28%) appeared in good condition. A summary of the number of non-exempt inventoried trees by species and general condition rating is provided in table 1 below.

Table 1. Count of Non-Exempt Inventoried Trees by Species and Condition – Nyberg Rivers, Tualatin.

| Common Name | Species Name | Poor | Fair | Good | Total | % |
|------------------|---------------------------------|------|------|------|-------|-------|
| Apple | <i>Malus spp.</i> | 1 | | | 1 | 0.2% |
| Austrian pine | <i>Pinus nigra</i> | 2 | | 1 | 3 | 0.5% |
| bigleaf maple | <i>Acer macrophyllum</i> | 9 | 56 | 5 | 70 | 12.8% |
| black cottonwood | <i>Populus trichocarpa</i> | 1 | 1 | | 2 | 0.4% |
| black locust | <i>Robinia pseudoacacia</i> | 7 | | | 7 | 1.3% |
| copper beech | <i>Fagus sylvatica</i> | | | 3 | 3 | 0.5% |
| deodar cedar | <i>Cedrus deodara</i> | | | 1 | 1 | 0.2% |
| Dogwood | <i>Cornus spp.</i> | | 3 | | 3 | 0.5% |
| Douglas-fir | <i>Pseudotsuga menziesii</i> | | 75 | 98 | 173 | 31.6% |
| English hawthorn | <i>Crataegus monogyna</i> | 9 | 5 | | 14 | 2.6% |
| English holly | <i>Ilex aquifolium</i> | | 1 | | 1 | 0.2% |
| English walnut | <i>Juglans regia</i> | 1 | | | 1 | 0.2% |
| European white | <i>Betula pendula</i> | 6 | 1 | | 7 | 1.3% |
| flowering cherry | <i>Prunus spp.</i> | 18 | 6 | | 24 | 4.4% |
| flowering pear | <i>Pyrus spp.</i> | 3 | 4 | 2 | 9 | 1.6% |
| flowering plum | <i>Prunus spp.</i> | | 1 | | 1 | 0.2% |
| giant sequoia | <i>Sequoiadendron giganteum</i> | | 1 | 1 | 2 | 0.4% |
| grand fir | <i>Abies grandis</i> | 1 | 3 | 1 | 5 | 0.9% |
| hornbeam | <i>Ostrya virginiana</i> | | | 6 | 6 | 1.1% |
| Japanese maple | <i>Acer japonica</i> | | 1 | 1 | 2 | 0.4% |
| lodgepole pine | <i>Pinus contorta</i> | 1 | 9 | | 10 | 1.8% |
| magnolia | <i>Magnolia spp.</i> | | | 1 | 1 | 0.2% |
| Norway maple | <i>Acer platanoides</i> | 4 | 26 | 6 | 36 | 6.6% |

| Common Name | Species Name | Poor | Fair | Good | Total | % |
|-------------------------|--------------------------------|------------|------------|------------|-------------|-------------|
| Oregon ash | <i>Fraxinus latifolia</i> | | 31 | | 31 | 5.7% |
| Oregon white oak | <i>Quercus garryana</i> | | 4 | 3 | 7 | 1.3% |
| Pacific yew | <i>Taxus brevifolia</i> | | 1 | | 1 | 0.2% |
| pin oak | <i>Quercus palustris</i> | 6 | 2 | | 8 | 1.5% |
| ponderosa pine | <i>Pinus ponderosa</i> | | 1 | 1 | 2 | 0.4% |
| red alder | <i>Alnus rubra</i> | | 8 | | 8 | 1.5% |
| red maple | <i>Acer rubrum</i> | 3 | 12 | 2 | 17 | 3.1% |
| red oak | <i>Quercus rubra</i> | 2 | 9 | 4 | 15 | 2.7% |
| scarlet oak | <i>Quercus coccinea</i> | 2 | 4 | 4 | 10 | 1.8% |
| Scots pine | <i>Pinus sylvestris</i> | 2 | 2 | | 4 | 0.7% |
| Scouler's willow | <i>Salix scouleriana</i> | 1 | | | 1 | 0.2% |
| silk tree | <i>Albizia julibrissin</i> | | 1 | | 1 | 0.2% |
| spruce | <i>Abies spp.</i> | | 1 | | 1 | 0.2% |
| sugar maple | <i>Acer saccharum</i> | | 1 | 2 | 3 | 0.5% |
| sweet cherry | <i>Prunus avium</i> | 22 | 7 | 2 | 31 | 5.7% |
| sweetgum | <i>Liquidambar styraciflua</i> | | 1 | | 1 | 0.2% |
| tree-of-heaven | <i>Ailanthus altissima</i> | | 1 | | 1 | 0.2% |
| western redcedar | <i>Thuja plicata</i> | | 14 | 10 | 24 | 4.4% |
| Total | | 101 | 293 | 154 | 548 | 100% |
| Percent of Total | | 18% | 54% | 28% | 100% | |

Tree Plan Recommendations

Prior to preparation of this report we have reviewed and considered the approval criteria identified in the Tualatin Development Code Section 34.230. Section 34.230 requires a detailed justification for proposed tree removal. The enclosed tree inventory data and this written report, prepared on September 5, 2013, address all of the relevant criteria.

As provided in the enclosed tree inventory data, individual trees recommended for removal were assigned a reason for removal (shown for each tree to be removed under "criteria" in the tree inventory data table) based on the removal criteria as follows:

Criteria for Tree Removal per TDC 34.230:

- **D1** – Diseased and the disease threatens the structural integrity of the tree;
- **D2** – Diseased and the disease permanently and severely diminishes the aesthetic value of the tree; or
- **D3** – Diseased and the continued retention of the tree could result in other trees being infected with a disease that threatens either their structural integrity or aesthetic value.
- **H** – Hazardous.
- **C** – Construction necessitates tree removal.

None of the 548 non-exempt inventoried trees are remarkable and based on the general condition of existing trees and the proposed site plan which necessitates significant grading, 287 (52%) trees are recommended for removal and 261 (48%) trees are recommended for preservation. Of the 287 non-exempt inventoried trees planned for removal, four are recommended for removal solely because of

hazardous condition and 283 require removal for the purposes of construction; removal of these trees is necessary in order to construct the proposed improvements. In addition, 11 of the trees recommended for removal for construction are diseased and the disease threatens the structural integrity of the tree (D1), one tree is diseased and the disease permanently and severely diminishes the aesthetic value of the tree (D2), and 23 of these trees are hazardous and present a danger of failure (H). Thus, 35 of the trees to be removed are diseased and/or hazardous. Note that D3 was not utilized as a justification for tree removal. Table 2 provides a summary of the number of trees to be removed based on the criteria.

Table 2. Count of Non-Exempt Inventoried Trees by Removal Criteria – Nyberg Rivers, Tualatin.

| Criteria for Tree Removal* | Number of Trees | % |
|----------------------------|-----------------|-------------|
| C | 252 | 87.8% |
| C and D1 | 8 | 2.8% |
| C, D1, and H | 3 | 1.0% |
| C, D2, and H | 1 | 0.3% |
| C and H | 19 | 6.6% |
| H | 4 | 1.4% |
| Total | 287 | 100% |

*Refer to definitions provided on the previous page.

Trees recommended for preservation will be retained in their relatively natural condition along the northern boundary of the project site and in a relatively natural grove in the northeast portion of the site and along the I-5 frontage. Based on the overall condition of the grove and proximity to proposed construction impacts, these trees are the most suitable trees for preservation on the site and are recommended for retention intact as an undisturbed group. Specifications for tree protection are provided in the next section.

Tree Protection Standards

The trees recommended for preservation will need special consideration to assure their protection during construction. We highly recommend a preconstruction meeting with the owner, contractors, and project arborist to review tree protection measures and address questions or concerns on site. Tree protection measures include:


- **Fencing.** Trees to remain on site shall be protected by installation of tree protection fencing to prevent injury to tree trunks or roots, or soil compaction within the root protection area, which generally coincides with tree driplines. Fences shall be 6-foot high steel on concrete blocks or orange plastic construction fencing on metal stakes. The project arborist shall determine the exact location and type of tree protection fencing. Trees located more than 30-feet from construction activity shall not require fencing.
- **Tree Protection Zone.** Without authorization from the Project Arborist, none of the following shall occur beneath the dripline of any protected tree:
 1. Grade change or cut and fill;
 2. New impervious surfaces;
 3. Utility or drainage field placement;
 4. Staging or storage of materials and equipment; or
 5. Vehicle maneuvering.

Root protection zones may be entered for tasks like surveying, measuring, and, sampling. Fences must be closed upon completion of these tasks.

- **Removal and Pruning.** Trees to be removed shall be clearly identified in the field with tree marking paint or by other means, and inspected and verified by the project arborist prior to site clearing. The need for pruning is not anticipated, but the project arborist shall help identify whether pruning is necessary once trees recommended for removal have been removed and the site is staked and prepared for construction. Tree removal and pruning shall be performed by a Qualified Tree Service.
- **Quality Assurance.** The project arborist shall supervise proper execution of this plan during construction and will be available on-call. It is the developer's responsibility to coordinate with the project arborist as needed.
- **Final Report.** After the project has been completed, the project arborist shall provide a final report that describes the measures needed to maintain and protect the remaining trees.

Please contact us if you have questions or need any additional information. Thank you for choosing Morgan Holen & Associates, LLC, to provide consulting arborist services for the Nyberg Rivers project.

Thank you,
Morgan Holen & Associates, LLC



Morgan E. Holen, Owner
ISA Certified Arborist, PN-6145A
ISA Tree Risk Assessment Qualified
Forest Biologist

Enclosures: MHA1324 Nyberg Rivers – Tree Inventory Data 7-29-13
Nyberg Rivers Tree Preservation Site Plan



| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove Criteria ³ |
|-----|------------------|------------------------------|------------------|-----------|--|---------------------|------------------------------|
| 500 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 20 | good | | | no |
| 501 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 9 | fair | | | no |
| 502 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 32 | good | | | no |
| 503 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | fair | dead - snag | | no |
| 505 | grand fir | <i>Abies grandis</i> | 16 | fair | | | no |
| 506 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | good | | | no |
| 508 | bigleaf maple | <i>Acer macrophyllum</i> | 20 | good | | | no |
| 509 | bigleaf maple | <i>Acer macrophyllum</i> | 20 | good | | | no |
| 511 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 26 | good | | | no |
| 512 | bigleaf maple | <i>Acer macrophyllum</i> | 8 | fair | | | no |
| 513 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 25 | good | | | no |
| 514 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 20 | good | | | no |
| 515 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 3*17 | fair | | | no |
| 516 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 17 | good | | | no |
| 518 | western redcedar | <i>Thuja plicata</i> | 12 | good | | | no |
| 519 | western redcedar | <i>Thuja plicata</i> | 14 | good | | | no |
| 520 | bigleaf maple | <i>Acer macrophyllum</i> | 18 | fair | extensive basal decay - meander path away from tree for safety | | no |
| 521 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 8 | fair | | | no |
| 522 | western redcedar | <i>Thuja plicata</i> | 9 | good | | | no |
| 523 | bigleaf maple | <i>Acer macrophyllum</i> | 22 | good | | | no |
| 527 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | good | | | no |
| 528 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 17 | good | | | no |
| 529 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | good | | | no |
| 530 | Oregon ash | <i>Fraxinus latifolia</i> | 16 | fair | | | no |
| 531 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 26 | good | | | no |
| 532 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | good | | | no |
| 533 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | good | | | no |
| 534 | red alder | <i>Alnus rubra</i> | 12 | fair | | | no |
| 535 | western redcedar | <i>Thuja plicata</i> | 12 | good | | | no |



| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove | Criteria ³ |
|-----|------------------|------------------------------|------------------|-----------|----------|---------------------|--------|-----------------------|
| 536 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 12 | good | | | no | no |
| 537 | Oregon ash | <i>Fraxinus latifolia</i> | 12 | fair | | | no | no |
| 538 | bigleaf maple | <i>Acer macrophyllum</i> | 9 | fair | | | no | no |
| 539 | western redcedar | <i>Thuja plicata</i> | 8 | fair | | | no | no |
| 540 | western redcedar | <i>Thuja plicata</i> | 18 | fair | | | no | no |
| 541 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 20 | good | | | no | no |
| 542 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 20 | good | | | no | no |
| 543 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | good | | | no | no |
| 544 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 11 | fair | | | no | no |
| 545 | western redcedar | <i>Thuja plicata</i> | 15 | good | | | no | no |
| 546 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 17 | good | | | no | no |
| 547 | grand fir | <i>Abies grandis</i> | 8 | fair | | | no | no |
| 548 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | good | | | no | no |
| 549 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | good | | | no | no |
| 550 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 9 | fair | | | no | no |
| 551 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 8 | fair | | | no | no |
| 552 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 16 | good | | | no | no |
| 553 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 16 | good | | | no | no |
| 554 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 16 | good | | | no | no |
| 555 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 9 | fair | | | no | no |
| 556 | sweet cherry | <i>Prunus avium</i> | 10 | good | | | no | no |
| 557 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 16 | good | | | no | no |
| 558 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | good | | | no | no |
| 559 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 8 | fair | | | no | no |
| 561 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 11 | good | | | no | no |
| 562 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 19 | good | | | no | no |
| 563 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 24 | good | | | no | no |
| 564 | western redcedar | <i>Thuja plicata</i> | 18 | good | | | no | no |
| 565 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 14 | good | | | no | no |
| 566 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | good | | | no | no |



| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove | Criteria ³ |
|-----|------------------|------------------------------|------------------|-----------|----------|---------------------|--------|-----------------------|
| 567 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 8 | fair | | | no | |
| 568 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 9 | fair | | | no | |
| 569 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 34 | good | | | no | |
| 570 | western redcedar | <i>Thuja plicata</i> | 8 | fair | | | no | |
| 571 | western redcedar | <i>Thuja plicata</i> | 8 | fair | | | no | |
| 572 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 26 | good | | | no | |
| 573 | western redcedar | <i>Thuja plicata</i> | 8 | fair | | | no | |
| 574 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 12 | fair | | | no | |
| 575 | western redcedar | <i>Thuja plicata</i> | 18 | fair | | | no | |
| 576 | Oregon ash | <i>Fraxinus latifolia</i> | 10 | fair | | | no | |
| 577 | Oregon ash | <i>Fraxinus latifolia</i> | 10 | fair | | | no | |
| 578 | western redcedar | <i>Thuja plicata</i> | 12 | fair | | | no | |
| 579 | western redcedar | <i>Thuja plicata</i> | 9 | fair | | | no | |
| 580 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 8 | fair | | | no | |
| 581 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 28 | good | | | no | |
| 582 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | good | | | no | |
| 583 | western redcedar | <i>Thuja plicata</i> | 18 | fair | | | no | |
| 584 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 20 | good | | | no | |
| 585 | western redcedar | <i>Thuja plicata</i> | 10 | good | | | no | |
| 586 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 9 | fair | | | no | |
| 587 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 17 | good | | | no | |
| 588 | western redcedar | <i>Thuja plicata</i> | 10 | fair | | | no | |
| 589 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 10 | fair | | | no | |
| 590 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 16 | good | | | no | |
| 591 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 8 | fair | | | no | |
| 592 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 10 | fair | | | no | |
| 593 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 12 | fair | | | no | |
| 594 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 10 | fair | | | no | |
| 595 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 8 | fair | | | no | |
| 596 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 8 | fair | | | no | |



| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove Criteria ³ |
|------|------------------|------------------------------|------------------|-----------|----------------------------------|---------------------|------------------------------|
| 597 | western redcedar | <i>Thuja plicata</i> | 12 | good | | | no |
| 597b | western redcedar | <i>Thuja plicata</i> | 20 | good | located 28-ft. north of tree 597 | | no |
| 598 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | good | | | no |
| 599 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 28 | good | | | no |
| 600 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 8 | fair | | | no |
| 601 | dogwood | <i>Cornus spp.</i> | 8 | fair | | | no |
| 602 | red alder | <i>Alnus rubra</i> | 12 | fair | | | no |
| 603 | red alder | <i>Alnus rubra</i> | 10 | fair | | | no |
| 604 | Oregon ash | <i>Fraxinus latifolia</i> | 10 | fair | | | no |
| 605 | bigleaf maple | <i>Acer macrophyllum</i> | 3*8 | fair | | | no |
| 606 | bigleaf maple | <i>Acer macrophyllum</i> | 2*8 | fair | | | no |
| 607 | bigleaf maple | <i>Acer macrophyllum</i> | 8 | fair | | | no |
| 608 | bigleaf maple | <i>Acer macrophyllum</i> | 2*10 | fair | | | no |
| 609 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 26 | good | | | no |
| 610 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | good | | | no |
| 611 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 14 | fair | | | no |
| 612 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 16 | good | | | no |
| 613 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | good | | | no |
| 614 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 12 | fair | | | no |
| 615 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 13 | fair | | | no |
| 616 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 24 | good | | | no |
| 617 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 19 | good | | | no |
| 618 | western redcedar | <i>Thuja plicata</i> | 17 | good | | | no |
| 619 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 36 | good | | | no |
| 620 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 24 | good | | | no |
| 621 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 30 | good | | | no |
| 622 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 30 | good | | | no |
| 623 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 22 | good | | | no |
| 624 | Pacific yew | <i>Taxus brevifolia</i> | 8 | fair | | | no |
| 625 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 17 | good | | | no |



| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove | Criteria ³ |
|------|---------------|------------------------------|------------------|-----------|---------------------------------------|---------------------|--------|-----------------------|
| 626 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 10 | fair | | | no | |
| 626b | Douglas-fir | <i>Pseudotsuga menziesii</i> | 8 | fair | located 20-ft 230-degrees from 626 | | no | |
| 627 | bigleaf maple | <i>Acer macrophyllum</i> | 16 | good | | | no | |
| 628 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 34 | good | | | no | |
| 629 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 22 | good | | | no | |
| 639 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 15 | good | | | no | |
| 641 | sweet cherry | <i>Prunus avium</i> | 16 | good | | | no | |
| 642 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 16 | good | | | no | |
| 643 | grand fir | <i>Abies grandis</i> | 10 | good | | | no | |
| 644 | grand fir | <i>Abies grandis</i> | 8 | fair | | | no | |
| 645 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 25 | good | | | no | |
| 646 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 21 | good | | | no | |
| 647 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | good | | | no | |
| 648 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 22 | good | | | no | |
| 649 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 8 | fair | | | no | |
| 650 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | good | | | no | |
| 651 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 17 | good | | | no | |
| 652 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 26 | good | | | no | |
| 653 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 12 | fair | | | no | |
| 654 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 17 | fair | | | no | |
| 655 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 17 | fair | | | no | |
| 656 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 8 | fair | | | no | |
| 657 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 22 | good | | | no | |
| 658 | bigleaf maple | <i>Acer macrophyllum</i> | 10 | fair | | | no | |
| 659 | bigleaf maple | <i>Acer macrophyllum</i> | 8 | fair | | | no | |
| 660 | bigleaf maple | <i>Acer macrophyllum</i> | 2*12 | fair | | | no | |
| 661 | bigleaf maple | <i>Acer macrophyllum</i> | 10 | fair | | | no | |
| 663 | bigleaf maple | <i>Acer macrophyllum</i> | 21,2*16 | fair | trees 663-665 are 1 tree; tip dieback | | yes | C |
| 666 | bigleaf maple | <i>Acer macrophyllum</i> | 10 | fair | intermediate crown class | | yes | C |
| 667 | bigleaf maple | <i>Acer macrophyllum</i> | 13 | fair | broken branches, branch decay | | yes | C |



| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove | Criteria ³ |
|------|------------------|------------------------------|------------------|-----------|---|---------------------|--------|-----------------------|
| 673 | bigleaf maple | <i>Acer macrophyllum</i> | 32 | fair | | | no | |
| 674 | bigleaf maple | <i>Acer macrophyllum</i> | 2*10 | fair | | | no | |
| 675 | bigleaf maple | <i>Acer macrophyllum</i> | 8 | fair | | | no | |
| 676 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 26 | fair | | | no | |
| 678 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 21 | fair | | | no | |
| 679 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 13 | fair | | | no | |
| 680 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 15 | fair | | | no | |
| 681 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 20 | fair | | | no | |
| 682 | bigleaf maple | <i>Acer macrophyllum</i> | 10 | fair | | | no | |
| 683 | bigleaf maple | <i>Acer macrophyllum</i> | 2*8 | fair | | | no | |
| 684 | bigleaf maple | <i>Acer macrophyllum</i> | 2*10 | fair | | | no | |
| 687 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 17 | fair | dead - habitat value, no target potential | | no | |
| 688 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 10 | fair | thin crown | | no | |
| 689 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | fair | thin crown | | no | |
| 690 | bigleaf maple | <i>Acer macrophyllum</i> | 8 | fair | | | no | |
| 695 | sweet cherry | <i>Prunus avium</i> | 13 | poor | invasive species | | yes | C |
| 697 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 22 | good | | | yes | C |
| 697b | Oregon white oak | <i>Quercus garryana</i> | 12 | good | located 24' 220-degrees from 697 | | yes | C |
| 698 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 14 | fair | ivy infestation | | yes | C |
| 699 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 14 | fair | ivy infestation | | yes | C |
| 700 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 10 | fair | ivy infestation | | yes | C |
| 701 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 34 | good | ivy infestation | | yes | C |
| 702 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 16 | fair | ivy infestation | | yes | C |
| 703 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 9 | fair | ivy infestation | | yes | C |
| 705 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 20 | good | | | yes | C |
| 706 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 24 | good | | | no | |
| 707 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 17 | good | | | yes | C |
| 708 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 34 | good | | | yes | C |
| 709 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 17 | good | | | yes | C |
| 711 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 30 | good | | | no | |



| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove | Criteria ³ |
|------|------------------|------------------------------|------------------|-----------|-------------------------|---------------------|--------|-----------------------|
| 712 | dogwood | <i>Cornus spp.</i> | 8 | fair | ivy infestation | | yes | C |
| 713 | bigleaf maple | <i>Acer macrophyllum</i> | 13 | fair | ivy infestation | | yes | C |
| 715 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 28 | good | | | yes | C |
| 716 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 9 | fair | | | yes | C |
| 717 | bigleaf maple | <i>Acer macrophyllum</i> | 10 | fair | | | yes | C |
| 718 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 13 | fair | | | yes | C |
| 719 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 10 | fair | | | yes | C |
| 720 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 24 | good | | | yes | C |
| 721 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 26 | good | | | yes | C |
| 722 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 10 | fair | | | yes | C |
| 723 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 10 | fair | | | yes | C |
| 724 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 28 | good | | | yes | C |
| 725 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 30 | good | | | yes | C |
| 726 | bigleaf maple | <i>Acer macrophyllum</i> | 10 | fair | | | yes | C |
| 727 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 12 | fair | | | yes | C |
| 728 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 9 | fair | | | yes | C |
| 728b | bigleaf maple | <i>Acer macrophyllum</i> | 14 | fair | located 22' west of 728 | | yes | C |
| 729 | English hawthorn | <i>Crataegus monogyna</i> | 12 | fair | invasive species | | yes | C |
| 730 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 11 | fair | | | yes | C |
| 731 | bigleaf maple | <i>Acer macrophyllum</i> | 12 | fair | dead branches | | yes | C |
| 732 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 11 | fair | | | yes | C |
| 733 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 16 | fair | | | yes | C |
| 734 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 10 | fair | | | yes | C |
| 735 | bigleaf maple | <i>Acer macrophyllum</i> | 10 | fair | | | yes | C |
| 736 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 12 | fair | | | yes | C |
| 737 | bigleaf maple | <i>Acer macrophyllum</i> | 8 | fair | | | yes | C |
| 738 | bigleaf maple | <i>Acer macrophyllum</i> | 8 | fair | | | yes | C |
| 739 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 12 | fair | | | yes | C |
| 740 | bigleaf maple | <i>Acer macrophyllum</i> | 8 | fair | | | yes | C |
| 741 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 22 | good | | | yes | C |



| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove | Criteria ³ |
|-----|------------------|------------------------------|------------------|-----------|------------------|---------------------|--------|-----------------------|
| 742 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 20 | good | | | yes | C |
| 743 | grand fir | <i>Abies grandis</i> | 8 | poor | | | yes | C |
| 744 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 22 | good | | | yes | C |
| 745 | bigleaf maple | <i>Acer macrophyllum</i> | 12 | fair | | | yes | C |
| 746 | English holly | <i>Ilex aquifolium</i> | 8 | fair | invasive species | | yes | C |
| 747 | bigleaf maple | <i>Acer macrophyllum</i> | 20 | fair | | | no | |
| 748 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 38 | good | | | no | |
| 749 | bigleaf maple | <i>Acer macrophyllum</i> | 18 | fair | | | no | |
| 750 | bigleaf maple | <i>Acer macrophyllum</i> | 16 | fair | | | no | |
| 751 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 26 | good | | | no | |
| 752 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 10 | fair | | | no | |
| 753 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 26 | good | | | no | |
| 754 | bigleaf maple | <i>Acer macrophyllum</i> | 10 | fair | | | no | |
| 755 | bigleaf maple | <i>Acer macrophyllum</i> | 8 | fair | | | no | |
| 756 | bigleaf maple | <i>Acer macrophyllum</i> | 10 | fair | | | no | |
| 757 | bigleaf maple | <i>Acer macrophyllum</i> | 2*8 | fair | | | no | |
| 758 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 24 | good | | | no | |
| 759 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 10 | fair | | | no | |
| 760 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 26 | good | | | no | |
| 761 | bigleaf maple | <i>Acer macrophyllum</i> | 12 | fair | | | no | |
| 762 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 12 | fair | | | no | |
| 763 | bigleaf maple | <i>Acer macrophyllum</i> | 11 | fair | | | no | |
| 764 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 11 | fair | | | no | |
| 765 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 42 | good | | | no | |
| 785 | English hawthorn | <i>Crataegus monogyna</i> | 4*12 | fair | invasive species | | no | |
| 786 | English hawthorn | <i>Crataegus monogyna</i> | 2*8 | fair | invasive species | | no | |
| 787 | bigleaf maple | <i>Acer macrophyllum</i> | 9 | fair | | | no | |
| 788 | Oregon white oak | <i>Quercus garryana</i> | 14 | fair | | | no | |
| 789 | bigleaf maple | <i>Acer macrophyllum</i> | 2*10 | fair | | | no | |
| 790 | bigleaf maple | <i>Acer macrophyllum</i> | 2*8 | fair | | | no | |



| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove | Criteria ³ |
|-----|------------------|------------------------------|------------------|-----------|--------------------------------------|---------------------|--------|-----------------------|
| 791 | bigleaf maple | <i>Acer macrophyllum</i> | 8 | fair | | | no | |
| 792 | bigleaf maple | <i>Acer macrophyllum</i> | 8 | fair | | | no | |
| 793 | bigleaf maple | <i>Acer macrophyllum</i> | 8 | fair | | | no | |
| 794 | bigleaf maple | <i>Acer macrophyllum</i> | 11 | fair | | | no | |
| 795 | bigleaf maple | <i>Acer macrophyllum</i> | 12 | fair | | | no | |
| 796 | bigleaf maple | <i>Acer macrophyllum</i> | 12 | fair | | | no | |
| 844 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 17 | good | existing hardscape to south | | yes | C |
| 845 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 17 | good | existing hardscape to south | | yes | C |
| 847 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 24 | good | existing hardscape to south | | yes | C |
| 848 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 19 | good | existing hardscape to south | | yes | C |
| 849 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | fair | codominant stems with included bark | | yes | C, H |
| 850 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 22 | good | only suitable for retention in group | | yes | C |
| 851 | sweet cherry | <i>Prunus avium</i> | 2*10 | poor | invasive species | | yes | C |
| 852 | sweet cherry | <i>Prunus avium</i> | 9 | poor | invasive species | | yes | C |
| 853 | pin oak | <i>Quercus palustris</i> | 8 | poor | | | yes | C |
| 854 | pin oak | <i>Quercus palustris</i> | 8 | poor | | | yes | C |
| 855 | English hawthorn | <i>Crataegus monogyna</i> | 3*8 | poor | invasive species | | yes | C |
| 856 | red oak | <i>Quercus rubra</i> | 3*10 | fair | twig dieback, thin crown | | yes | C |
| 874 | English hawthorn | <i>Crataegus monogyna</i> | 8 | fair | | | yes | C |
| 875 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 12 | fair | | | yes | C |
| 876 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 12 | fair | | | yes | C |
| 877 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 28 | good | | | yes | C |
| 878 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 25 | good | | | yes | C |
| 879 | Oregon white oak | <i>Quercus garryana</i> | 8 | good | | | yes | C |
| 880 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | good | | | yes | C |
| 881 | Oregon white oak | <i>Quercus garryana</i> | 10 | fair | | | yes | C |
| 882 | Scouler's willow | <i>Salix scouleriana</i> | 2*8 | poor | | | yes | C |
| 884 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 30 | good | | | yes | C |
| 885 | English hawthorn | <i>Crataegus monogyna</i> | 8 | poor | invasive species | | yes | C |
| 886 | English hawthorn | <i>Crataegus monogyna</i> | 8 | poor | invasive species | | yes | C |



| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove | Criteria ³ |
|------|----------------------|------------------------------|------------------|-----------|---------------------------------------|---------------------|--------|-----------------------|
| 887 | sweet cherry | <i>Prunus avium</i> | 2*8 | poor | invasive species | | yes | C |
| 888 | sweet cherry | <i>Prunus avium</i> | 8 | poor | invasive species | | yes | C |
| 889 | Oregon white oak | <i>Quercus garryana</i> | 8 | good | | | yes | C |
| 890 | sweet cherry | <i>Prunus avium</i> | 2*10 | poor | invasive species | | yes | C |
| 891 | English hawthorn | <i>Crataegus monogyna</i> | 2*8 | poor | invasive species | | yes | C |
| 892 | sweet cherry | <i>Prunus avium</i> | 8 | poor | invasive species | | yes | C |
| 901 | hornbeam | <i>Ostrya virginiana</i> | 10 | good | | | yes | C |
| 902 | hornbeam | <i>Ostrya virginiana</i> | 5*8 | good | | | yes | C |
| 903 | hornbeam | <i>Ostrya virginiana</i> | 2*8 | good | | | yes | C |
| 904 | hornbeam | <i>Ostrya virginiana</i> | 3*8 | good | | | yes | C |
| 904b | hornbeam | <i>Ostrya virginiana</i> | 3*8 | good | located north of 904 | | yes | C |
| 904c | hornbeam | <i>Ostrya virginiana</i> | 3*8 | good | located north of 904b | | yes | C |
| 905 | red oak | <i>Quercus rubra</i> | 12 | poor | decline; dead branches, branch decay | | yes | C |
| 906 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 8 | fair | young, vigorous; one-sided | | yes | C |
| 907 | European white birch | <i>Betula pendula</i> | 3*10 | fair | invasive species, poor structure, ivy | | yes | C |
| 908 | Japanese maple | <i>Acer japonica</i> | 3*8 | good | some stem decay | | yes | C |
| 909 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 21 | fair | codom, included bark, sap flow | | yes | C, H |
| 910 | red oak | <i>Quercus rubra</i> | 13 | good | low branch structure | | yes | C |
| 911 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 18 | good | codom - appears stable | | yes | C |
| 912 | red oak | <i>Quercus rubra</i> | 19 | good | dead branches | | yes | C |
| 913 | red oak | <i>Quercus rubra</i> | 24 | good | dead branches | | yes | C |
| 914 | sweet cherry | <i>Prunus avium</i> | 14 | fair | invasive species | | yes | C |
| 915 | red oak | <i>Quercus rubra</i> | 28 | good | unable to evaluate base | | yes | C |
| 916 | scarlet oak | <i>Quercus coccinea</i> | 3*11 | good | | | yes | C |
| 917 | scarlet oak | <i>Quercus coccinea</i> | 22 | good | low branches | | yes | C |
| 918 | scarlet oak | <i>Quercus coccinea</i> | 17 | good | low branches | | yes | C |
| 919 | scarlet oak | <i>Quercus coccinea</i> | 18 | good | low branches | | yes | C |
| 920 | sweet cherry | <i>Prunus avium</i> | 3*10 | poor | ivy infestation; invasive species | | yes | C |
| 921 | sweet cherry | <i>Prunus avium</i> | 10 | poor | ivy infestation; invasive species | | yes | C |
| 922 | sweet cherry | <i>Prunus avium</i> | 12 | poor | ivy infestation; invasive species | | yes | C |



| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove | Criteria ³ |
|-----|------------------|------------------------------|------------------|-----------|-----------------------------------|---------------------|--------|-----------------------|
| 923 | sweet cherry | <i>Prunus avium</i> | 8 | poor | ivy infestation; invasive species | | yes | C |
| 924 | sweet cherry | <i>Prunus avium</i> | 8 | poor | ivy infestation; invasive species | | yes | C |
| 925 | sweet cherry | <i>Prunus avium</i> | 2*8 | poor | ivy infestation; invasive species | | yes | C |
| 926 | sweet cherry | <i>Prunus avium</i> | 2*10 | poor | ivy infestation; invasive species | | yes | C |
| 927 | sweet cherry | <i>Prunus avium</i> | 8 | poor | ivy infestation; invasive species | | yes | C |
| 928 | sweet cherry | <i>Prunus avium</i> | 8 | fair | ivy infestation; invasive species | | no | |
| 929 | sweet cherry | <i>Prunus avium</i> | 2*12 | fair | ivy infestation; invasive species | | no | |
| 930 | sweet cherry | <i>Prunus avium</i> | 9 | poor | ivy infestation; invasive species | | yes | C |
| 931 | sweet cherry | <i>Prunus avium</i> | 12 | poor | ivy infestation; invasive species | | yes | C |
| 932 | sweet cherry | <i>Prunus avium</i> | 10 | fair | invasive species | | no | |
| 933 | sweet cherry | <i>Prunus avium</i> | 12 | fair | invasive species | | no | |
| 936 | Oregon white oak | <i>Quercus garryana</i> | 12 | fair | | | no | |
| 937 | Oregon white oak | <i>Quercus garryana</i> | 12 | fair | | | no | |
| 938 | bigleaf maple | <i>Acer macrophyllum</i> | 12 | fair | | | no | |
| 939 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 26 | good | | | no | |
| 940 | bigleaf maple | <i>Acer macrophyllum</i> | 10 | fair | not accessible | | no | |
| 941 | bigleaf maple | <i>Acer macrophyllum</i> | 12 | fair | not accessible | | no | |
| 942 | bigleaf maple | <i>Acer macrophyllum</i> | 10 | fair | not accessible | | no | |
| 943 | red alder | <i>Alnus rubra</i> | 3*8 | fair | not accessible | | no | |
| 944 | red alder | <i>Alnus rubra</i> | 2*8 | fair | not accessible | | no | |
| 945 | red alder | <i>Alnus rubra</i> | 2*8 | fair | not accessible | | no | |
| 946 | Oregon ash | <i>Fraxinus latifolia</i> | 10 | fair | not accessible | | no | |
| 947 | Oregon ash | <i>Fraxinus latifolia</i> | 8 | fair | not accessible | | no | |
| 948 | Oregon ash | <i>Fraxinus latifolia</i> | 10 | fair | not accessible | | no | |
| 949 | Oregon ash | <i>Fraxinus latifolia</i> | 8 | fair | not accessible | | no | |
| 950 | Oregon ash | <i>Fraxinus latifolia</i> | 8 | fair | not accessible | | no | |
| 951 | Oregon ash | <i>Fraxinus latifolia</i> | 10 | fair | not accessible | | no | |
| 952 | Oregon ash | <i>Fraxinus latifolia</i> | 8 | fair | not accessible | | no | |
| 953 | Oregon ash | <i>Fraxinus latifolia</i> | 8 | fair | not accessible | | no | |
| 954 | Oregon ash | <i>Fraxinus latifolia</i> | 12 | fair | not accessible | | no | |



| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove Criteria ³ |
|------|------------------|---------------------------|------------------|-----------|---------------------------------------|---------------------|------------------------------|
| 955 | red alder | <i>Alnus rubra</i> | 10 | fair | not accessible | | no |
| 956 | red alder | <i>Alnus rubra</i> | 8 | fair | not accessible | | no |
| 957 | western redcedar | <i>Thuja plicata</i> | 16 | fair | not accessible | | no |
| 958 | Oregon ash | <i>Fraxinus latifolia</i> | 8 | fair | not accessible | | no |
| 959 | Oregon ash | <i>Fraxinus latifolia</i> | 14 | fair | not accessible | | no |
| 960 | Oregon ash | <i>Fraxinus latifolia</i> | 10 | fair | not accessible | | no |
| 961 | Oregon ash | <i>Fraxinus latifolia</i> | 12 | fair | not accessible | | no |
| 962 | Oregon ash | <i>Fraxinus latifolia</i> | 16 | fair | not accessible | | no |
| 963 | Oregon ash | <i>Fraxinus latifolia</i> | 20 | fair | not accessible | | no |
| 964 | Oregon ash | <i>Fraxinus latifolia</i> | 8 | fair | not accessible | | no |
| 965 | Oregon ash | <i>Fraxinus latifolia</i> | 12 | fair | not accessible | | no |
| 966 | sweet cherry | <i>Prunus avium</i> | 3*8 | fair | invasive species | | no |
| 967 | Oregon ash | <i>Fraxinus latifolia</i> | 2*9 | fair | poor structure | | no |
| 968 | Oregon ash | <i>Fraxinus latifolia</i> | 8 | fair | poor structure | | no |
| 969 | Oregon ash | <i>Fraxinus latifolia</i> | 12 | fair | poor structure | | no |
| 1008 | red oak | <i>Quercus rubra</i> | 2*14 | fair | codom at 1'; some branch decay | | yes C |
| 1011 | scarlet oak | <i>Quercus coccinea</i> | 12 | fair | twig dieback, some branch decay | | yes C |
| 1012 | pin oak | <i>Quercus palustris</i> | 12 | poor | dead top | | yes C, H |
| 1020 | pin oak | <i>Quercus palustris</i> | 12 | fair | hollows with decay; dieback | | yes C, H |
| 1029 | red oak | <i>Quercus rubra</i> | 12 | fair | twig dieback | | yes C |
| 1030 | pin oak | <i>Quercus palustris</i> | 12 | poor | dead branches, branch decay | | yes C |
| 1167 | pin oak | <i>Quercus palustris</i> | 15 | fair | twig dieback | | yes C |
| 1230 | scarlet oak | <i>Quercus coccinea</i> | 16 | poor | dieback, thin crown, chlorotic | | yes C |
| 1231 | scarlet oak | <i>Quercus coccinea</i> | 12 | poor | dead branches, decline | | yes C |
| 1292 | scarlet oak | <i>Quercus coccinea</i> | 14 | fair | recent branch failure; poor structure | | yes C, H |
| 1293 | pin oak | <i>Quercus palustris</i> | 14 | poor | dead top, branch dieback | | yes C |
| 1302 | pin oak | <i>Quercus palustris</i> | 14 | poor | dead top, branch dieback | | yes C |
| 1305 | red oak | <i>Quercus rubra</i> | 14 | poor | dead leader, branch dieback | | yes C |
| 1318 | scarlet oak | <i>Quercus coccinea</i> | 16 | fair | poor branch distribution; dieback | | yes C |
| 1319 | scarlet oak | <i>Quercus coccinea</i> | 16 | fair | some dieback | | yes C |



| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove | Criteria ³ |
|------|----------------------|----------------------------|------------------|-----------|---|---------------------|--------|-----------------------|
| 1352 | red maple | <i>Acer rubrum</i> | 6 | fair | | yes | yes | C |
| 1360 | red maple | <i>Acer rubrum</i> | 6 | fair | | yes | yes | C |
| 1365 | red maple | <i>Acer rubrum</i> | 6 | poor | sunscald, chlorotic, poor vigor | yes | yes | C |
| 1369 | red maple | <i>Acer rubrum</i> | 6 | fair | forked top with included bark | yes | yes | C |
| 1379 | lodgepole pine | <i>Pinus contorta</i> | 3*12 | fair | codom at base; sequoia pitch moth | | yes | C, D1 |
| 1400 | red maple | <i>Acer rubrum</i> | 10 | fair | moderate vigor; chlorotic | | yes | C |
| 2181 | black cottonwood | <i>Populus trichocarpa</i> | 42 | fair | multiple leaders; species limitations | | yes | C, H |
| 2192 | black cottonwood | <i>Populus trichocarpa</i> | 4*12 | poor | poor structure; species limitations | | yes | C |
| 2198 | European white birch | <i>Betula pendula</i> | 3*13 | poor | dead | | yes | C |
| 2203 | Norway maple | <i>Acer platanoides</i> | 10 | good | invasive species | | no | |
| 2215 | Norway maple | <i>Acer platanoides</i> | 10 | poor | sunscald, decay, ants; invasive species | | yes | C, D1 |
| 2275 | bigleaf maple | <i>Acer macrophyllum</i> | 18 | poor | | | yes | C |
| 2276 | sweet cherry | <i>Prunus avium</i> | 18 | poor | invasive species | | yes | C |
| 2277 | sweet cherry | <i>Prunus avium</i> | 12 | poor | invasive species | | yes | C |
| 2278 | Oregon ash | <i>Fraxinus latifolia</i> | 8 | fair | | | yes | C |
| 2279 | sweet cherry | <i>Prunus avium</i> | 5*8 | poor | invasive species | | yes | C |
| 2280 | sweet cherry | <i>Prunus avium</i> | 14 | poor | invasive species | | yes | C |
| 2282 | sweet cherry | <i>Prunus avium</i> | 10 | poor | invasive species | | yes | C |
| 2284 | Oregon ash | <i>Fraxinus latifolia</i> | 8 | fair | | | yes | C |
| 2285 | Oregon ash | <i>Fraxinus latifolia</i> | 18 | fair | | | yes | C |
| 2286 | Oregon ash | <i>Fraxinus latifolia</i> | 10 | fair | extensive ivy infestation | | yes | C |
| 2287 | sweet cherry | <i>Prunus avium</i> | 8 | fair | invasive species | | yes | C |
| 2288 | Oregon ash | <i>Fraxinus latifolia</i> | 8 | fair | | | yes | C |
| 2289 | bigleaf maple | <i>Acer macrophyllum</i> | 18 | good | | | yes | C |
| 2290 | bigleaf maple | <i>Acer macrophyllum</i> | 7*12 | fair | | | yes | C |
| 2292 | Oregon ash | <i>Fraxinus latifolia</i> | 12 | fair | | | yes | C |
| 2293 | tree-of-heaven | <i>Ailanthus altissima</i> | 15 | fair | invasive species; poor structure | | yes | C |
| 2294 | bigleaf maple | <i>Acer macrophyllum</i> | 3*14 | poor | poor structure; dead branches | | yes | C |
| 2295 | bigleaf maple | <i>Acer macrophyllum</i> | 3*14 | poor | poor structure, codom stems | | yes | C |
| 2296 | bigleaf maple | <i>Acer macrophyllum</i> | 2*12 | poor | extensive ivy infestation, thin crown | | yes | C |



| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove | Criteria ³ |
|------|------------------|---------------------------|------------------|-----------|--|---------------------|--------|-----------------------|
| 2297 | bigleaf maple | <i>Acer macrophyllum</i> | 18 | poor | extensive ivy infestation, thin crown | | yes | C |
| 2298 | bigleaf maple | <i>Acer macrophyllum</i> | 12 | poor | extensive ivy infestation, thin crown | | yes | C |
| 2299 | bigleaf maple | <i>Acer macrophyllum</i> | 8 | poor | extensive ivy infestation, thin crown | | yes | C |
| 2300 | bigleaf maple | <i>Acer macrophyllum</i> | 8 | poor | extensive ivy infestation, thin crown | | yes | C |
| 2301 | English hawthorn | <i>Crataegus monogyna</i> | 12 | poor | invasive species; ivy infestation | | yes | C |
| 2302 | bigleaf maple | <i>Acer macrophyllum</i> | 12 | poor | top dieback, decay | | yes | C |
| 2303 | English hawthorn | <i>Crataegus monogyna</i> | 8 | fair | invasive species | | yes | C |
| 2304 | lodgepole pine | <i>Pinus contorta</i> | 10 | fair | sequoia pitch moth | | yes | C |
| 2305 | English hawthorn | <i>Crataegus monogyna</i> | 12 | poor | invasive species; overtopped | | yes | C |
| 2379 | lodgepole pine | <i>Pinus contorta</i> | 4*8 | fair | codom at base; sequoia pitch moth | | yes | C |
| 2382 | red maple | <i>Acer rubrum</i> | 6 | poor | sunscald, decay, dead branches | yes | yes | C, D1 |
| 2407 | red maple | <i>Acer rubrum</i> | 3 | poor | severe sunscald, mostly dead | yes | yes | C, D1 |
| 2414 | red maple | <i>Acer rubrum</i> | 4 | poor | thin crown, chlorotic | yes | yes | C |
| 2420 | red maple | <i>Acer rubrum</i> | 5 | fair | sunscald | yes | yes | C |
| 2434 | red maple | <i>Acer rubrum</i> | 8 | poor | sunscald 0-5'; codom | | yes | C, D1 |
| 2462 | red maple | <i>Acer rubrum</i> | 8 | fair | moderate vigor | | yes | C |
| 2527 | red maple | <i>Acer rubrum</i> | 10 | poor | sunscald, stem decay, dieback | | yes | C, D1 |
| 2533 | red maple | <i>Acer rubrum</i> | 6 | poor | decay, included bark | yes | yes | C |
| 2544 | red maple | <i>Acer rubrum</i> | 6 | fair | multiple leaders | yes | yes | C |
| 2548 | red maple | <i>Acer rubrum</i> | 6 | poor | sunscald, decay, dead branches | yes | yes | C, D1 |
| 2553 | red maple | <i>Acer rubrum</i> | 6 | poor | sunscald, decay in codom juncture | yes | yes | C, D1 |
| 2677 | red maple | <i>Acer rubrum</i> | 4 | fair | stem decay | yes | yes | C |
| 2702 | red maple | <i>Acer rubrum</i> | 2*6 | fair | stem decay | | yes | C |
| 2731 | Norway maple | <i>Acer platanoides</i> | 8 | poor | invasive species; stem & branch decay | | yes | C, D1, H |
| 2743 | Norway maple | <i>Acer platanoides</i> | 8 | fair | invasive species; poor crown structure | | yes | C |
| 2747 | Norway maple | <i>Acer platanoides</i> | 6 | poor | invasive species; dead leader & branches | yes | yes | C |
| 2753 | Norway maple | <i>Acer platanoides</i> | 8 | fair | invasive species | | yes | C |
| 2766 | Norway maple | <i>Acer platanoides</i> | 8 | fair | invasive species | | yes | C |
| 2807 | flowering plum | <i>Prunus spp.</i> | 2 | good | | yes | yes | C |
| 2829 | flowering plum | <i>Prunus spp.</i> | 6 | good | | yes | yes | C |



| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove | Criteria ³ |
|------|------------------|-------------------------|------------------|-----------|---|---------------------|--------|-----------------------|
| 2950 | Norway maple | <i>Acer platanoides</i> | 2 | good | invasive species | yes | yes | C |
| 2954 | Norway maple | <i>Acer platanoides</i> | 12 | fair | invasive species; some branch decay | | yes | C |
| 2974 | flowering cherry | <i>Prunus spp.</i> | 3 | good | | yes | yes | C |
| 2979 | Norway maple | <i>Acer platanoides</i> | 12 | good | | | yes | C |
| 2993 | Norway maple | <i>Acer platanoides</i> | 8 | fair | broken branches | | yes | C |
| 3069 | red maple | <i>Acer rubrum</i> | 4*4 | fair | poor vigor | | yes | C |
| 3160 | red maple | <i>Acer rubrum</i> | 4 | good | | yes | yes | C |
| 3205 | red maple | <i>Acer rubrum</i> | 3 | good | | yes | yes | C |
| 3206 | red maple | <i>Acer rubrum</i> | 3 | good | | yes | yes | C |
| 3212 | red maple | <i>Acer rubrum</i> | 3 | good | | yes | yes | C |
| 3309 | red maple | <i>Acer rubrum</i> | 3 | good | | yes | yes | C |
| 3310 | red maple | <i>Acer rubrum</i> | 3 | good | | yes | yes | C |
| 3315 | red maple | <i>Acer rubrum</i> | 3 | good | sunscald | yes | yes | C |
| 3318 | red maple | <i>Acer rubrum</i> | 3 | fair | sunscald | yes | yes | C |
| 3322 | red maple | <i>Acer rubrum</i> | 3 | good | | yes | yes | C |
| 3413 | red maple | <i>Acer rubrum</i> | 10 | fair | decay in codom juncture | yes | yes | C, D1, H |
| 3417 | red maple | <i>Acer rubrum</i> | 10 | fair | sunscald, included bark | | yes | C |
| 3436 | red maple | <i>Acer rubrum</i> | 10 | fair | sunscald, included bark | | yes | C |
| 3443 | red maple | <i>Acer rubrum</i> | 10 | poor | hollow with decay; poor structure | | yes | C, D1 |
| 3445 | red maple | <i>Acer rubrum</i> | 10 | good | multiple attachments | | yes | C |
| 3610 | Norway maple | <i>Acer platanoides</i> | 12 | good | invasive species | | yes | C |
| 3634 | Norway maple | <i>Acer platanoides</i> | 10 | fair | invasive species; branch decay, dieback | | yes | C |
| 3643 | Norway maple | <i>Acer platanoides</i> | 3 | poor | invasive species; sunscald, decay | yes | yes | C |
| 3652 | Norway maple | <i>Acer platanoides</i> | 8 | fair | invasive species; dead branches | | yes | C |
| 3739 | spruce | <i>Abies spp.</i> | 6 | fair | against existing building | yes | no | |
| 3826 | Amur maple | <i>Acer ginnala</i> | 3 | poor | severe basal & stem decay | yes | yes | C, D1 |
| 3841 | Norway maple | <i>Acer platanoides</i> | 14 | fair | invasive species; branch dieback | | no | |
| 3990 | Norway maple | <i>Acer platanoides</i> | 14 | fair | | | no | |



| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove | Criteria ³ |
|-------|----------------|------------------------------|------------------|-----------|---|---------------------|--------|-----------------------|
| 4035 | Norway maple | <i>Acer platanoides</i> | 14 | fair | | | no | |
| 4052 | Norway maple | <i>Acer platanoides</i> | 12 | good | invasive species | | yes | C |
| 4054 | Norway maple | <i>Acer platanoides</i> | 10 | good | invasive species | | yes | C |
| 4072 | Norway maple | <i>Acer platanoides</i> | 12 | poor | invasive species; sunscald, lean | | yes | C, D1, H |
| 4083 | flowering pear | <i>Pyrus spp.</i> | 10 | fair | thin crown | | no | |
| 4084 | flowering pear | <i>Pyrus spp.</i> | 12 | fair | thin crown | | no | |
| 4085 | Norway maple | <i>Acer platanoides</i> | 12 | fair | invasive species; thin crown | | yes | C |
| 4203 | red maple | <i>Acer rubrum</i> | 10 | good | one-sided to building | | yes | C |
| 4222 | Norway maple | <i>Acer platanoides</i> | 3 | fair | invasive species; sunscald, basal decay | yes | yes | C, D1 |
| 4223 | red maple | <i>Acer rubrum</i> | 3 | poor | severe sunscald; dead branches | yes | yes | C, D1 |
| 4282 | red maple | <i>Acer rubrum</i> | 4 | fair | one-sided to building | yes | yes | C |
| 4286 | red maple | <i>Acer rubrum</i> | 2 | poor | severe sunscald; dead branches | yes | yes | C |
| 4411 | flowering pear | <i>Pyrus spp.</i> | 14 | poor | dieback; codom with included bark | | yes | C, H |
| 4456 | flowering pear | <i>Pyrus spp.</i> | 8 | poor | dieback; lean to parking lot | | yes | C, H |
| 4483 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 26 | good | few dead branches | | yes | C |
| 4484 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 12 | fair | one-sided crown; young tree | | yes | C |
| 4492 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 22 | fair | pruned high; only sustainable in group | | yes | C |
| 4493 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 24 | fair | pruned high; only sustainable in group | | yes | C |
| 4495 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 24 | fair | pruned high; only sustainable in group | | yes | C |
| 4496 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 16 | fair | small, high live crown; re-evaluate following adjacent tree removal | | no | |
| 4497 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 26 | fair | pruned high; only sustainable in group | | no | |
| 4510 | lodgepole pine | <i>Pinus contorta</i> | 24 | fair | asymmetrical crown; sequoia pitch moth | | no | |
| 4511 | flowering pear | <i>Pyrus spp.</i> | 14 | poor | mostly dead | | no | |
| 4516 | lodgepole pine | <i>Pinus contorta</i> | 15 | fair | poor structure; sequoia pitch moth | | no | |
| 4516b | lodgepole pine | <i>Pinus contorta</i> | 15 | fair | poor structure; sequoia pitch moth | | no | |
| 4531 | Norway maple | <i>Acer platanoides</i> | 8 | fair | invasive species; dieback | | yes | C |
| 4546 | Norway maple | <i>Acer platanoides</i> | 6 | poor | invasive species; dead leader | yes | yes | C |
| 4556 | Norway maple | <i>Acer platanoides</i> | 8 | poor | invasive species; extensive decay column | | yes | C, D1 |
| 4556b | Norway maple | <i>Acer platanoides</i> | 4 | poor | located 37' north of 4556 | yes | yes | C |



Morgan Holen
— & — ASSOCIATES, LLC

| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove | Criteria ³ |
|------|------------------|-----------------------------|------------------|-----------|---|---------------------|--------|-----------------------|
| 4583 | Norway maple | <i>Acer platanoides</i> | 8 | fair | invasive species; dead branches | | yes | C |
| 4618 | red maple | <i>Acer rubrum</i> | 3*6 | fair | poor vigor | | yes | C |
| 4682 | red maple | <i>Acer rubrum</i> | 3*6 | fair | stem & branch decay | | yes | C, D1 |
| 4730 | red maple | <i>Acer rubrum</i> | 6 | fair | sunscald | yes | yes | C |
| 4787 | red maple | <i>Acer rubrum</i> | 10 | fair | multiple leaders; moderate vigor | | yes | C |
| 4854 | red maple | <i>Acer rubrum</i> | 12 | fair | some branch decay | | yes | C |
| 4915 | Norway maple | <i>Acer platanoides</i> | 3 | poor | invasive species; sunscald, basal decay | yes | yes | C, D1 |
| 4924 | Norway maple | <i>Acer platanoides</i> | 3 | fair | invasive species; sunscald 0-4' | yes | yes | C, D1 |
| 5022 | Austrian pine | <i>Pinus nigra</i> | 14 | poor | poor structure, unnatural lean | | yes | C, H |
| 5023 | Austrian pine | <i>Pinus nigra</i> | 12 | poor | poor structure, unnatural lean | | yes | C, H |
| 5093 | red maple | <i>Acer rubrum</i> | 16 | fair | | | no | |
| 5186 | Norway maple | <i>Acer platanoides</i> | 12 | fair | | | yes | C |
| 5190 | Norway maple | <i>Acer platanoides</i> | 14 | fair | | | no | |
| 5211 | Norway maple | <i>Acer platanoides</i> | 14 | fair | | | no | |
| 5219 | Norway maple | <i>Acer platanoides</i> | 16 | fair | | | no | |
| 5228 | Norway maple | <i>Acer platanoides</i> | 16 | fair | | | no | |
| 5234 | Norway maple | <i>Acer platanoides</i> | 16 | fair | | | no | |
| 5321 | English hawthorn | <i>Crataegus monogyna</i> | 6*12 | poor | invasive species | | yes | C |
| 5324 | English hawthorn | <i>Crataegus monogyna</i> | 3*12 | poor | invasive species | | yes | C |
| 5326 | English hawthorn | <i>Crataegus monogyna</i> | 8 | poor | invasive species | | yes | C |
| 5438 | Norway maple | <i>Acer platanoides</i> | 12 | fair | prune to remove dead wood | | no | |
| 5598 | flowering cherry | <i>Prunus spp.</i> | 8 | fair | dead branches; moderate vigor | | yes | C |
| 5692 | black locust | <i>Robinia pseudoacacia</i> | 2*8 | poor | invasive species, decay, dead branches | | yes | H |
| 5693 | black locust | <i>Robinia pseudoacacia</i> | 2*18 | poor | invasive species, decay, dead branches | | yes | H |
| 5695 | black locust | <i>Robinia pseudoacacia</i> | 18 | poor | invasive species, decay, dead branches | | yes | H |
| 5696 | black locust | <i>Robinia pseudoacacia</i> | 18 | poor | invasive species, decay, dead branches | | yes | H |
| 5735 | bigleaf maple | <i>Acer macrophyllum</i> | 3*8 | fair | | | no | |
| 5823 | lodgepole pine | <i>Pinus contorta</i> | 12 | fair | | | no | |
| 5824 | lodgepole pine | <i>Pinus contorta</i> | 10 | poor | | | no | |
| 6000 | sugar maple | <i>Acer saccharum</i> | 16 | fair | top dieback | | yes | C |



Morgan Holen
 & ASSOCIATES, LLC

| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove | Criteria ³ |
|-------|----------------------|------------------------------|------------------|-----------|--|---------------------|--------|-----------------------|
| 6315 | red maple | <i>Acer rubrum</i> | 3 | good | | yes | yes | C |
| 6446 | zelkova | <i>Zelkova spp.</i> | 4 | fair | needs supplemental watering | yes | yes | C |
| 6458 | zelkova | <i>Zelkova spp.</i> | 4 | fair | needs supplemental watering | yes | yes | C |
| 6468 | zelkova | <i>Zelkova spp.</i> | 4 | fair | needs supplemental watering | yes | yes | C |
| 6479 | zelkova | <i>Zelkova spp.</i> | 4 | poor | severe sunscald, dead top | yes | yes | C, D1 |
| 6489 | zelkova | <i>Zelkova spp.</i> | 4 | fair | | yes | yes | C |
| 6503 | zelkova | <i>Zelkova spp.</i> | 4 | poor | sunscald, stem decay | yes | yes | C, D1 |
| 6522 | red oak | <i>Quercus rubra</i> | 26 | fair | one-sided crown; history of branch failure | | yes | C |
| 6523 | red oak | <i>Quercus rubra</i> | 19 | fair | hollow with slime flux; crown asymmetry | | yes | C, D1 |
| 6524 | red oak | <i>Quercus rubra</i> | 29 | fair | large leaders, crown asymmetry | | yes | C |
| 6524b | Douglas-fir | <i>Pseudotsuga menziesii</i> | 30 | good | located 30' north of 6524 | | yes | C |
| 6524c | deodar cedar | <i>Cedrus deodara</i> | 36 | good | located 20' east of 6524b | | yes | C |
| 6525 | ponderosa pine | <i>Pinus ponderosa</i> | 2*18 | fair | | | yes | C |
| 6526 | ponderosa pine | <i>Pinus ponderosa</i> | 2*26 | good | | | yes | C |
| 6527 | European white birch | <i>Betula pendula</i> | 16 | poor | dead; invasive species | | yes | C, H |
| 6528 | copper beech | <i>Fagus sylvatica</i> | 14 | good | overcrowded | | yes | C |
| 6529 | European white birch | <i>Betula pendula</i> | 18 | poor | dead top; invasive species | | yes | C, H |
| 6530 | copper beech | <i>Fagus sylvatica</i> | 28 | good | needs soil aeration & seasonal irrigation | | yes | C |
| 6531 | copper beech | <i>Fagus sylvatica</i> | 34 | good | needs soil aeration & seasonal irrigation | | yes | C |
| 6542 | flowering cherry | <i>Prunus spp.</i> | 6*6 | fair | | | yes | C |
| 6543 | flowering cherry | <i>Prunus spp.</i> | 6*6 | fair | | | yes | C |
| 6544 | flowering cherry | <i>Prunus spp.</i> | 2*8 | fair | | | yes | C |
| 6547 | flowering cherry | <i>Prunus spp.</i> | 5*6 | fair | | | yes | C |
| 6548 | flowering cherry | <i>Prunus spp.</i> | 3*6 | fair | | | yes | C |
| 6549 | flowering cherry | <i>Prunus spp.</i> | 3*6 | poor | dead branches, branch decay | | yes | C |
| 6550 | flowering cherry | <i>Prunus spp.</i> | 4*6 | poor | dead branches, branch decay | | yes | C |
| 6556 | flowering cherry | <i>Prunus spp.</i> | 3*6 | poor | mostly dead | | yes | C |
| 6557 | flowering cherry | <i>Prunus spp.</i> | 4*6 | poor | dead branches, branch decay | | yes | C |
| 6558 | flowering cherry | <i>Prunus spp.</i> | 6 | poor | dead | | yes | C |
| 6559 | flowering cherry | <i>Prunus spp.</i> | 3*6 | poor | dead & broken branches, branch decay | | yes | C |



| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove | Criteria ³ |
|------|------------------|---------------------------------|------------------|-----------|--|---------------------|--------|-----------------------|
| 6560 | flowering cherry | <i>Prunus spp.</i> | 2*6 | poor | dead & broken branches, branch decay | | yes | C |
| 6563 | flowering cherry | <i>Prunus spp.</i> | 3*6 | poor | dead & broken branches, branch decay | | yes | C |
| 6564 | flowering cherry | <i>Prunus spp.</i> | 3*6 | poor | dead & broken branches, branch decay | | yes | C |
| 6566 | red oak | <i>Quercus rubra</i> | 24 | fair | history of large branch failure; small hollow | | yes | C |
| 6567 | Austrian pine | <i>Pinus nigra</i> | 40 | good | | | yes | C |
| 6570 | magnolia | <i>Magnolia spp.</i> | 20 | good | ivy infestation | | yes | C |
| 6571 | sweetgum | <i>Liquidambar styraciflua</i> | 24 | fair | moderate vigor | | yes | C |
| 6579 | Norway maple | <i>Acer platanoides</i> | 2*19 | good | invasive species; codom at 1'; ivy infestation | | yes | C |
| 6582 | red oak | <i>Quercus rubra</i> | 22 | fair | twig dieback; one-sided crown | | yes | C |
| 6583 | giant sequoia | <i>Sequoiadendron giganteum</i> | 29 | fair | ivy infestation; crown asymmetry | | yes | C |
| 6584 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 22 | fair | | | yes | C |
| 6585 | western redcedar | <i>Thuja plicata</i> | 2*16 | fair | ivy | | yes | C |
| 6586 | silk tree | <i>Albizia julibrissin</i> | 2*15 | fair | extensive ivy infestation | | yes | C |
| 6587 | Douglas-fir | <i>Pseudotsuga menziesii</i> | 29 | fair | ivy infestation; heavy cone production | | yes | C |
| 6588 | western redcedar | <i>Thuja plicata</i> | 18 | fair | forked top; crown asymmetry | | yes | C |
| 6602 | apple | <i>Malus spp.</i> | 2*12 | poor | decay | | yes | C |
| 6603 | spruce | <i>Abies spp.</i> | 18 | fair | old broken top | | yes | C |
| 6605 | English walnut | <i>Juglans regia</i> | 40 | poor | decrepit | | yes | C, H |
| 6609 | dogwood | <i>Cornus spp.</i> | 12 | fair | | | yes | C |
| 6610 | lodgepole pine | <i>Pinus contorta</i> | 17 | fair | | | yes | C |
| 6629 | giant sequoia | <i>Sequoiadendron giganteum</i> | 38 | good | ivy at base; inadequate soil volume | | yes | C |
| 6631 | Scots pine | <i>Pinus sylvestris</i> | 14 | poor | dead | | yes | C, H |
| 6632 | flowering cherry | <i>Prunus spp.</i> | 12 | poor | not well maintained | | yes | C |
| 6633 | flowering cherry | <i>Prunus spp.</i> | 10 | poor | not well maintained | | yes | C |
| 6634 | flowering cherry | <i>Prunus spp.</i> | 10 | poor | not well maintained | | yes | C |
| 6635 | flowering cherry | <i>Prunus spp.</i> | 10 | poor | not well maintained | | yes | C |
| 6636 | flowering cherry | <i>Prunus spp.</i> | 10 | poor | not well maintained | | yes | C |
| 6637 | flowering cherry | <i>Prunus spp.</i> | 10 | poor | not well maintained | | yes | C |
| 6638 | flowering cherry | <i>Prunus spp.</i> | 10 | poor | not well maintained | | yes | C |
| 6639 | flowering cherry | <i>Prunus spp.</i> | 10 | poor | not well maintained | | yes | C |



| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove | Criteria ³ |
|------|----------------------|-----------------------------|------------------|-----------|---|---------------------|--------|-----------------------|
| 6640 | flowering cherry | <i>Prunus spp.</i> | 6 | poor | not well maintained | yes | yes | C |
| 6641 | flowering cherry | <i>Prunus spp.</i> | 8 | poor | not well maintained | | yes | C |
| 6642 | flowering cherry | <i>Prunus spp.</i> | 12 | poor | not well maintained | | yes | C |
| 6664 | Norway maple | <i>Acer platanoides</i> | 2*14 | fair | invasive; codom at 1'; less than 1' to building | | yes | C |
| 6693 | Scots pine | <i>Pinus sylvestris</i> | 12 | fair | | | yes | C |
| 6714 | Japanese maple | <i>Acer japonica</i> | 3*6 | fair | one-sided to building; some decay | | yes | C |
| 6813 | Norway maple | <i>Acer platanoides</i> | 14 | fair | invasive species; codom at 6', ivy infestation | | yes | C |
| 6818 | Norway maple | <i>Acer platanoides</i> | 16 | fair | invasive species; codom at 5', ivy infestation | | yes | C |
| 6824 | Norway maple | <i>Acer platanoides</i> | 18 | fair | invasive species; codom at 5', included bark | | yes | C |
| 6828 | Norway maple | <i>Acer platanoides</i> | 15 | fair | invasive species; codom at 5' | | yes | C |
| 6833 | Norway maple | <i>Acer platanoides</i> | 17 | fair | invasive species; multiple attachments at 5' | | yes | C |
| 6893 | Scots pine | <i>Pinus sylvestris</i> | 24 | poor | chlorotic, poor structure, ivy infestation | | yes | C, H |
| 6895 | Scots pine | <i>Pinus sylvestris</i> | 19 | fair | forked top | | yes | C |
| 6896 | European white birch | <i>Betula pendula</i> | 2*16 | poor | dead; invasive species | | yes | C, H |
| 6901 | European white birch | <i>Betula pendula</i> | 10 | poor | invasive species; ivy infestation | | yes | C |
| 7052 | bigleaf maple | <i>Acer macrophyllum</i> | 18 | fair | | | no | |
| 7242 | lodgepole pine | <i>Pinus contorta</i> | 10 | fair | sequoia pitch moth | | no | |
| 7524 | sugar maple | <i>Acer saccharum</i> | 18 | good | | | yes | C |
| 7597 | zilkova | <i>Zelkova spp.</i> | 3 | fair | branch decay, poor crown structure | yes | yes | C, D1 |
| 7670 | western redcedar | <i>Thuja plicata</i> | 6 | fair | coniferous | yes | no | |
| 7673 | western redcedar | <i>Thuja plicata</i> | 6 | fair | coniferous | yes | no | |
| 7675 | western redcedar | <i>Thuja plicata</i> | 6 | fair | coniferous | yes | no | |
| 7676 | western redcedar | <i>Thuja plicata</i> | 6 | fair | coniferous | yes | no | |
| 7677 | western redcedar | <i>Thuja plicata</i> | 5 | fair | coniferous | yes | no | |
| 7678 | western redcedar | <i>Thuja plicata</i> | 8 | fair | coniferous | | no | |
| 7679 | western redcedar | <i>Thuja plicata</i> | 4 | fair | coniferous | yes | no | |
| 7815 | sugar maple | <i>Acer saccharum</i> | 16 | good | | | no | |
| 7833 | flowering plum | <i>Prunus spp.</i> | 3*8 | fair | multiple attachments | | no | |
| 7923 | flowering pear | <i>Pyrus spp.</i> | 8 | fair | | | no | |
| 7954 | black locust | <i>Robinia pseudoacacia</i> | 30 | poor | invasive species; decay, dead branches | | yes | C, H |



| No. | Common Name | Species Name | DBH ¹ | Condition | Comments | Exempt ² | Remove | Criteria ³ |
|------|----------------------|-----------------------------|------------------|-----------|--|---------------------|--------|-----------------------|
| 7957 | black locust | <i>Robinia pseudoacacia</i> | 2*28 | poor | invasive species; decay, dead branches | | yes | C, H |
| 7963 | European white birch | <i>Betula pendula</i> | 18 | poor | invasive species; bronze birch borer | | yes | C, D2, H |
| 7966 | red oak | <i>Quercus rubra</i> | 10 | fair | aphids | | yes | C |
| 7983 | black locust | <i>Robinia pseudoacacia</i> | 10 | poor | invasive species; decay, dead branches | | yes | C, H |
| 8001 | flowering pear | <i>Pyrus spp.</i> | 3 | fair | moderate lean to street | yes | yes | C |
| 8002 | flowering pear | <i>Pyrus spp.</i> | 3 | good | | yes | no | |
| 8035 | flowering pear | <i>Pyrus spp.</i> | 4 | good | | yes | no | |
| 8080 | flowering pear | <i>Pyrus spp.</i> | 8 | good | | | yes | C |
| 8089 | flowering pear | <i>Pyrus spp.</i> | 3 | good | | yes | yes | C |
| 8093 | flowering pear | <i>Pyrus spp.</i> | 8 | fair | minor lean to street | | yes | C |
| 8099 | flowering pear | <i>Pyrus spp.</i> | 8 | good | | | no | |

¹DBH is tree diameter measured at 4.5-feet above the ground level, in inches.

²Exempt identifies trees measuring less than eight inches in diameter.

³Criteria provides justification for the proposed tree removal (per TDC 34.230):

D1: Diseased and the disease threatens the structural integrity of the tree;

D2: Diseased and the disease permanently and severely diminishes the aesthetic value of the tree; or

D3: Diseased and the continued retention of the tree could result in other trees being infected with a disease that threatens either their structural integrity or aesthetic value.



H: Hazardous.

C: Construction necessitates tree removal.


| | |
|-------------|----------|
| PROJECT NO. | 71818 |
| DATE | 08/11/11 |
| DESIGNED BY | MARKUS |
| DRAWN BY | SCS |
| CHECKED BY | SCS |

TREE PRESERVATION SITE PLAN
 08/11/11
 ARCHITECTURE

- LEGEND**
- EXISTING WATER LINE
 - PROPOSED WATER PRIVATE LINE
 - PROPOSED WATER PUBLIC LINE
 - PROPOSED FIRE WATER LINE
 - PROPOSED DRAINAGE WATER LINE
 - EXISTING FIRE HYDRANT
 - EXISTING WATER METER
 - EXISTING WATER VALVE
 - PROPOSED FIRE HYDRANT
 - PROPOSED WATER METER
 - PROPOSED DOUBLE CHECK VALVE
 - EXISTING TREE TO BE REMOVED
 - EXISTING TREE REMOVED FOR PUBLIC UTILITY INSTALLATION OR EXISTING PUBLIC UTILITY REMOVAL
 - EXISTING TREE TO BE REMOVED IN 14-200 TREE REMOVAL PERMIT PROPERTY (PER SINGLE PARCEL OF PROPERTY)
 - EXISTING TREE TO BE REMOVED FOR PUBLIC STREET IMPROVEMENTS
 - EXISTING TREE REMOVED WHEN APPROVED BY CDOT
 - EXISTING TREE TO BE PROTECTED IN PLACE WITH FENCING AROUND THE TRUNK ONLY
 - EXISTING TREE TO BE REMOVED AND REPLACED WITH APPROVED TREE
- EXISTING IMPACT CONTOUR
 - PROPOSED IMPACT CONTOUR
 - EXISTING MAJOR CONTOUR
 - PROPOSED MAJOR CONTOUR
 - EXISTING MINOR CONTOUR
 - PROPOSED MINOR CONTOUR
 - EXISTING LOT LINE
 - PROPOSED LOT LINE
 - EXISTING CLEARANCE LINE
 - PROPOSED CLEARANCE LINE
 - EXISTING STORM LINE
 - PROPOSED STORM PRIVATE LINE
 - PROPOSED STORM PUBLIC LINE
 - EXISTING STORM MANHOLE
 - PROPOSED STORM MANHOLE
 - EXISTING STORM CATCH BASIN
 - PROPOSED STORM CATCH BASIN
 - PROPOSED STORM CLEAN OUT
 - EXISTING DESIGN FEATURE / LOW IMPACT DESIGN FEATURE
 - PROPOSED EASEMENT
 - EXISTING BASEMENT
 - EXISTING SANITARY LINE
 - PROPOSED SANITARY PRIVATE LINE
 - PROPOSED SANITARY PUBLIC LINE
 - EXISTING SANITARY MANHOLE
 - PROPOSED SANITARY MANHOLE
 - EXISTING PRIVATE MANHOLE
 - PROPOSED PRIVATE MANHOLE
 - EXISTING SANITARY CLEAN OUT
 - PROPOSED SANITARY CLEAN OUT
 - PROPOSED GREASE INTERCEPTOR



MATCHLINE - SEE SHEET C2.1



S.W. NYBERG ROAD
 C.R. NO. 254C




S.W. MARTINAZZI AVENUE

ORCA OWNERS
 S.W. NYBERG RD


LEGEND

- 100- - - - - EXISTING MAJOR CONTOUR
- 130- - - - - EXISTING MAJOR CONTOUR
- 150- - - - - EXISTING MAJOR CONTOUR
- - - - - PROPERTY LINE
- - - - - LOT LINE
- - - - - VISION CLEARANCE LINE
- - - - - EXISTING STORM LINE
- - - - - PROPOSED STORM PRIVATE LINE
- - - - - PROPOSED STORM PUBLIC LINE
- - - - - EXISTING STORM MANHOLE
- - - - - EXISTING STORM CATCH BASIN
- - - - - PROPOSED STORM MANHOLE
- - - - - PROPOSED STORM CATCH BASIN
- - - - - PROPOSED STORM CLEAN OUT
- - - - - PROPOSED STORM LOW IMPACT DESIGN FEATURE
- - - - - EXISTING BASEMENT
- - - - - PROPOSED BASEMENT
- - - - - EXISTING SANITARY LINE
- - - - - PROPOSED SANITARY PRIVATE LINE
- - - - - PROPOSED SANITARY PUBLIC LINE
- - - - - EXISTING SANITARY MANHOLE
- - - - - PROPOSED PUBLIC MANHOLE
- - - - - PROPOSED PRIVATE MANHOLE
- - - - - PROPOSED SANITARY CATCH BASIN
- - - - - PROPOSED SANITARY CLEAN OUT
- - - - - PROPOSED GREASE INTERCEPTOR
- - - - - EXISTING WATER LINE
- - - - - PROPOSED WATER PRIVATE LINE
- - - - - PROPOSED WATER PUBLIC LINE
- - - - - EXISTING FIRE WATER LINE
- - - - - PROPOSED DOMESTIC WATER LINE
- - - - - EXISTING FIRE HYDRANT
- - - - - EXISTING WATER METER
- - - - - EXISTING WATER VAULT

- EXISTING WATER VAULT
- PROPOSED FIRE HYDRANT
- PROPOSED FIRE DEPT. CONNECTION
- PROPOSED WATER METER
- PROPOSED DOUBLE CHECK VALVE
- EXISTING TREE TO BE REMOVED
- EXISTING TREE REMOVED FOR ACCOMMODATION WITH SECTION 34.000 OF PROPERTY'S
- EXISTING TREE REMOVED FOR PUBLIC STREET IMPROVEMENTS, APPROVED BY CDDA
- EXISTING TREE TO BE PRESERVED IN PLACES WITH FENCING AROUND THE DRIP LINE



KEY MAP
SCALE: 1/8\"/>



TREE PRESERVATION SITE PLAN
 NYBERG RIVERS - ARCHITECTURAL REVIEW BOARD
 CENTRAL PROPERTIES, LLC.
 TUALATIN, OREGON

| | |
|-------------|---------|
| PROJECT NO. | 21003 |
| DATE | 2/20/20 |
| DESIGNED BY | DMH |
| CHECKED BY | BCF |
| CREATED BY | BCF |

6866
 ATTORNEYS AT LAW
TREE PRESERVATION SITE PLAN

MEMORANDUM



To: City of Tualatin

From: Atalia Raskin, PE
Water Resource Project Engineer

Date: September 6, 2013

Project: Nyberg Rivers
Cardno#: 21198310
Re: Nyberg Rivers Architectural Review Board – Stormwater Analysis

5415 SW Westgate Drive
Suite 100
Portland, Oregon 97221
USA

Phone (503) 419-2500
Fax (503) 419-2600

www.cardno.com

This memorandum will discuss the water quality systems being proposed as part of the Nyberg Rivers development. Treatment facilities were designed to City of Tualatin and Clean Water Services (CWS) standards. The stormwater management approach, as described below, is intended to meet these requirements and provide a high level of treatment for the proposed development.

Project Overview

The Nyberg Rivers project is located on the northwest corner of Interstate 5 (I-5) and SW Nyberg Street, in Tualatin, Oregon. The site currently contains a shopping center and a large parking lot. The proposed redevelopment will include the construction of several new retail buildings. Additionally, the project includes frontage improvements to SW Nyberg Street and the construction of Street "A" and SW Seneca Street east of SW Martinazzi Avenue.

Water Quality

Water quality will be accomplished through Contech StormFilters. Contech StormFilters are an approved method of treatment by CWS and are able to remove suspended sediment, metals, oils and total nutrients.

Pre-treatment

Additionally, the site plan was reviewed for opportunities to install green infrastructure as pre-treatment facilities. Green infrastructure features (green features) are landscaped reservoirs that collect stormwater runoff through vegetation and soil media. They may also provide pollutant reduction and flow attenuation to reduce hydraulic impacts from urban developments on downstream rivers. The proposed green features are not required to meet a pollutant reduction or flow attenuation standard.

The proposed green features, as described below, do not meet the sizing requirements of CWS's, but will provide a water quality and flow reduction benefit as the site plan allows. All generated runoff from impervious areas will flow through a Contech StormFilter facility for treatment.

Green Features

Two styles of green features are proposed; sloped planters and rain gardens. Sloped planters are linear landscaped reservoirs with slopes of 1 to 1.5%, widths of 3 to 5 feet, check dams, and vertical side walls. The proposed rain garden is a depressed basin with 4 to 1 side slopes. Overflows will be provided for water depths greater than 3 inches. A perforated pipe surrounded by gravel will collect the treated stormwater and convey it to a Contech StormFilter facility. The green feature section is listed below:

- > Freeboard Depth: 3 inches
- > Maximum Treatment Water Depth: 3 inches
- > Growing Media Depth: 18 inches
- > Gravel Depth: 6 inches

1.57 acres (68,200 sq.-ft) of impervious area will flow into a proposed green feature before being treated by a Contech StormFilter. These areas are hatched on the attached Water Quality Map.

Australia • Belgium • Indonesia • Kenya • New Zealand • Papua New Guinea
United Arab Emirates • United Kingdom • United States • Operations in 60 Countries

Exhibit 1
Attachment N



Treatment

Design Standards

The proposed water quality facilities were designed per City of Tualatin and Clean Water Services standards. The proposed facilities were designed using a rainfall depth of 0.36" over a 4-hour period with a return period of 96-hours as outlined in section 4.05.06 of the *Design and Construction Standards for Sanitary Sewer and Surface Water Management* issued in June of 2007 and updated in 2009.

Per Section 4.05.6 of the design manual, the water quality volume and flow rate are calculated according to the equations below:

$$\text{Water Quality Volume (cu.-ft)} = \frac{0.36 \text{ (in)} \times \text{Area (sq.-ft)}}{12 \text{ (in/ft)}} \quad \text{Water Quality Flow} = \frac{\text{WQV (cu.-ft)}}{14,400}$$

Mechanical Treatment

Clean Water Services requires pre-treatment prior to proposed water quality facilities. Trapped Catch Basins are an approved pretreatment facility and will provide pretreatment for the site, when not flowing to a green feature.

Contech StormFilter catch basins, manholes and vaults are the selected water quality facilities. These facilities were selected for their ability to integrate into the existing and proposed site plan. Each StormFilter system will have the standard cartridge size with an 18-inch drop and have a treatment capacity of 0.033 cfs (15 gpm). The maximum bypass flow is 1.80 cfs; an internal bypass structure will be provided as needed. Peak diversion (PD) vaults have an internal baffle to divert flows higher than the water quality storm.

Table 1-1 lists the number of cartridges within each system. Sixteen facilities will provide treatment to the required surface area. Facilities SDMH#P7-WQ and SDMH#P9-WQ will be public stormwater treatment facilities.

Table 1-1 Mechanical Water Quality Facilities

| Facility | Basin # | Impervious Area (sf) | Water Quality Flow Rate (cfs) | Quantity of Cartridges | Facility Type |
|------------|---------|----------------------|-------------------------------|------------------------|---------------|
| SDMH#A1-WQ | A | 63,426 | 0.13 | 4.0 | Manhole |
| SDVT#B1-WQ | B/C | 220,734 | 0.46 | 14.0 | 8x11 PD Vault |
| SDVT#D1-WQ | D | 215,227 | 0.45 | 14.0 | 8x11 PD Vault |
| SDMH#E1-WQ | E | 30,107 | 0.06 | 2.0 | Manhole |
| SDMH#F1-WQ | F | 28,871 | 0.06 | 2.0 | Manhole |
| SDCB#G1-WQ | G1 | 4,070 | 0.01 | 1.0 | Catch Basin |
| SDCB#G2-WQ | G2 | 10,516 | 0.02 | 1.0 | Catch Basin |
| SDVT#H1-WQ | H | 219,685 | 0.46 | 14.0 | 8x11 PD Vault |
| SDTD#A1-WQ | I | 28,798 | 0.06 | 2.0 | Catch Basin |
| SDMH#J1-WQ | J | 32,138 | 0.07 | 3.0 | Manhole |
| SDCB#K1-WQ | K | 21,026 | 0.04 | 2.0 | Catch Basin |
| SDCB#N1-WQ | N1 | 8,073 | 0.02 | 1.0 | Catch Basin |
| SDCB#N2-WQ | N2 | 12,991 | 0.03 | 1.0 | Catch Basin |
| SDMH#M1-WQ | M | 81,949 | 0.17 | 6.0 | Manhole |
| SDMH#P7-WQ | P1 | 15,095 | 0.03 | 1.0 | Manhole |
| SDMH#P9-WQ | P2 | 24,888 | 0.05 | 2.0 | Manhole |
| Total | - | 1,017,594 | 2.12 | - | - |



Conclusion


In conclusion, the proposed stormwater management system will meet the requirements of the City of Tualatin and Clean Water Services design standards. Contech StormFilters will provide water quality treatment and follow Clean Water Services' *Design and Construction Standards for Sanitary Sewer and Surface Water Management* issued in June of 2007 and updated in 2009.

Attachments: Exhibit 1 – Water Quality Map


PROJECT NO. 21198310
DATE: 09/06/2013
BY: ASR
EXHIBIT: 1

WATER QUALITY BASIN MAP
NYBERG RIVERS
CENTRAL PROPERTIES, LLC.
Tualatin, Oregon

PORTLAND
5415 SW REGAN DR. STE 100, PORTLAND, OR 97221
TEL: (503) 719-2000 FAX: (503) 419-2000
www.cardno.com
Shaping the Future
Cardno



GREEN FEATURE
TREATMENT AREA



Nyberg Rivers

Tualatin, Oregon

An Application For:
Architectural Review Board
 Deemed complete October 31, 2013

Developer
 Centercal Properties, LLC
 7455 SW Bridgeport Road, Suite 205
 Tigard, Oregon 97224
 Phone: 503 968-8940


Civil Engineering,
 Landscape Architecture, Survey,
 and Land Use Planning
 Cardno
 5415 SW Westgate Drive, Suite 100
 Portland, Oregon 97221

Architect
 Mulvanny G2
 18200 Von Karman Avenue, Suite 810
 Irvine, California 92612
 Phone: 949-705-0700

Transportation
 Kittelson and Associates
 610 SW Alder, Suite 700
 Portland, Oregon 97205
 Phone: 503-226-5230

Geotechnical
 GeoDesign
 15575 SW Sequoia Parking, Suite 100
 Portland, Oregon 97224
 Phone: 503-968-8787

Photometrics
 Musgrove Engineering PA
 234 S. Whitepawood Way
 Boise, Idaho 83709
 Phone: 208-384-0585



Vicinity Map
Not to Scale

Deemed complete October 31, 2013

Nyberg Rivers

Tualatin, Oregon

An Application For:
Architectural Review Board


Sheet Index

| | | | |
|------|--|--------|--|
| C0.0 | Overall Existing Conditions | L1.3 | Planting Plan - Southeast |
| C0.1 | Existing Conditions | L1.4 | Planting Plan - Northwest |
| C0.2 | Existing Conditions - West | L1.5 | Planting Plan - Northeast |
| C0.3 | Existing Conditions - East | L1.6 | Planting Plan - North |
| C0.4 | Existing Conditions - North | L1.7 | Enlargement Plan - Building D |
| C1.0 | Overall Site Plan | L1.8 | Enlargement Plan - Building 1040 |
| C1.1 | Site Plan - West | L1.9 | Enlargement Plan - Building H & J |
| C1.2 | Site Plan - East | L1.10 | Materials Photoboard |
| C1.3 | Site Plan - North | L1.11 | Sections & Details |
| C2.0 | Tree Preservation Site Plan - West | E-1 | Photometric Overall |
| C2.1 | Tree Preservation Site Plan - East | E-2 | Photometric Area A - SW |
| C2.2 | Tree Preservation Site Plan - North | E-3 | Photometric Area B - SE |
| C2.3 | Tree Preservation Site Plan - Table 1 | E-4 | Photometric Area C - NW |
| C2.4 | Tree Preservation Site Plan - Table 2 | E-5 | Photometric Area D - NE |
| C2.5 | Tree Preservation Site Plan - Table 3 | E-6 | Photometric Area E - N |
| C3.0 | Grading Plan - West | A1.10 | Building A & B Elevations |
| C3.1 | Grading Plan - East | A2.10a | Overall Building D Elevations |
| C3.2 | Grading Plan - North | A2.10b | Overall Building D Elevations |
| C4.0 | Storm Sewer (Public Facilities) - West | A2.10c | Overall Building D Street Perspectives |
| C4.1 | Storm Sewer (Public Facilities) - East | A2.11 | Enlarged Building D Elevations - West |
| C4.2 | Storm Sewer (Public Facilities) - North | A2.12 | Enlarged Building D Elevations - Central |
| C5.0 | Sanitary Sewer (Public Facilities) - West | A2.13 | Enlarged Building D Elevations - East |
| C5.1 | Sanitary Sewer (Public Facilities) - East | A2.14 | Loading Dock Sections |
| C5.2 | Sanitary Sewer (Public Facilities) - North | A3.10a | Cabela's Elevations |
| C6.0 | Water System (Public Facilities) - West | A3.10b | Cabela's Sightlines |
| C6.1 | Water System (Public Facilities) - East | A3.10c | Cabela's Sightlines |
| C6.2 | Water System (Public Facilities) - North | A4.10 | Building F (LA Fitness) Elevations |
| L1.0 | Planting Legend and Notes | A5.10 | Building J (BJ's) Elevations |
| L1.1 | Planting Plan - Overall | A6.10 | Building K Elevations |
| L1.2 | Planting Plan - Southwest | A7.10 | Trash Enclosures and Bike Parking |


ATTENTION: OREGON LAW REQUIRES YOU TO FOLLOW RULES
ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER.
IF YOU HAVE ANY QUESTIONS OR NEED ASSISTANCE,
PLEASE CALL THE CENTER AT 1-800-352-2344 OR VISIT
WWW.OREGONUTILITYNOTIFICATIONCENTERS.COM FOR
MORE INFORMATION. YOU MAY CALL ANYTIME OF THE DAY,
7 DAYS A WEEK. FOR THE OREGON UTILITY NOTIFICATION CENTER IS
(503) 285-1961.



OREGON UTILITY
NOTIFICATION CENTER
1-800-352-2344



- LEGEND:**
- EXISTING SANITARY LINE
 - EXISTING RIGHT-OF-WAY LINE
 - SECTIONAL LINE
 - EMBANKMENT LINE
 - SETBACK LINE
 - BUILDING OVERHANG LINE
 - UNDERGROUND WATER LINE
 - UNDERGROUND IRRIGATION LINE
 - UNDERGROUND TELEPHONE LINE
 - UNDERGROUND ELECTRICAL LINE
 - STORM DRAINAGE LINE
 - UNDERGROUND TELEPHONE LINE
 - UNDERGROUND ELECTRICAL LINE
 - UNDERGROUND GAS LINE
 - UNDERGROUND CABLE TV LINE
 - BUILDING FACE
 - EXISTING CONCRETE SURFACE
 - GAS VALVE
 - GAS METER
 - TELEPHONE RISER
 - TELEPHONE MANHOLE
 - COMPRIUSUS TREE
 - DECIDUOUS TREE
 - SANITARY SEWER CLEANOUT
 - SANITARY SEWER MANHOLE
 - PATCH BASIN
 - STORM DRAIN MANHOLE
 - ROOF DRAIN
 - FIRE SPRINKLER
 - FIRE DEPARTMENT CONNECTION
 - POST INDICATOR VALVE
 - UNDERGROUND WATER VALVE
 - WATER VALVE
 - WATER METER BOX
 - SPRINKLER VALVE
 - STREET LIGHT (CROWN ARM)
 - GROUND LIGHT
 - CHECKBOX LIGHT (BRICK)
 - ADDRESSABLE LIGHT
 - ELECTRIC METER
 - PARKING BUMPER
 - TRAFFIC SIGNAL BOX
 - SIGNAL JUNCTION BOX
 - UNKNOWN CLEANOUT
 - UNKNOWN MANHOLE
 - BOLLARD
 - GATE POST
 - MAILBOX
 - SIGN



DATUM:
WASHINGTON COUNTY, OREGON, NAD 83
A 2" BENCH MARK SET IN CONCRETE CURB AT THE SW CORNER OF PERRY ROAD AND S.W. TUALATIN ROAD.
ELEVATION = 123.70'

BASIS OF BEARINGS:
ESTABLISHED BY FOLDING INSTRUMENTS (TMS) AND (TOM).
PROPERTY LINES AND PARCELS ARE BASED ON THE REPORT DATED 11/10/09 BY THE SURVEYOR, WASHINGTON COUNTY, OREGON, 2101.


UTILITY NOTE:
SEE PUBLIC UTILITY PLANS FOR ALL PUBLIC UTILITY MAINTENANCE SERVICE TO ALL BUILDINGS DURING CONSTRUCTION.

PROPERTY DESCRIPTION:
LOCATED IN THE SE QUARTER AND SW QUARTER OF SECTION 24, TOWNSHIP 2 NORTH, RANGE 1 WEST, WASHINGTON COUNTY, OREGON.




SEE SHEET C0.4

SEE SHEET C0.3



SEE SHEET C0.2




- LEGEND:**
- EXISTING BOUNDARY LINE
 - EXISTING RIGHT-OF-WAY LINE
 - SECTIONAL LINE
 - FENCE LINE
 - FENCE LINE, TYPE AS NOTED
 - BUILDING OVERHANG LINE
 - UNDERGROUND WATER LINE
 - UNDERGROUND RECREATION LINE
 - SANITARY SEWER LINE
 - GAS SERVICE LINE
 - UNDERGROUND TELEPHONE LINE
 - OVERHEAD WIRE
 - UNDERGROUND GAS LINE
 - UNDERGROUND CABLE TV LINE
 - BUILDING FACE
 - TRANSDUCER LINE
 - EXISTING ASPHALT SURFACE
 - EXISTING CONCRETE SURFACE
 - GAS VALVE
 - GAS METER
 - TELEPHONE MANHOLE
 - CONIFEROUS TREE
 - DECIDUOUS TREE
- SANITARY SEWER CLEANOUT
 - SANITARY SEWER MANHOLE
 - CATCH BASIN
 - STEEL DRAIN MANHOLE
 - ROOF DRAIN
 - PRE-PACKAGE
 - FREE DEPARTMENT CONNECTION
 - POST INDICATOR VALVE
 - UNDERGROUND WATER VAULT
 - WATER VALVE
 - SPRINKLER VALVE
 - SPRINKLER BOX
 - GROUND LIGHT
 - STREET LIGHT (COURT YARD)
 - STREET LIGHT (BIKELER)
 - AEROCLOUSE LIGHT
 - TRANSFORMER
 - PARADE BUMPER
 - TRAFFIC SIGNAL POLE
 - SIGNAL JUNCTION BOX
 - UNKNOWN CLEANOUT
 - UNKNOWN MANHOLE
 - BOLLARD
 - GATE POST
 - MAILBOX
 - SIGN



- LEGEND:**
- EXISTING BOUNDARY LINE
 - EXISTING RIGHT-OF-WAY LINE
 - SECTIONAL LINE
 - PARKING LINE
 - BOUNDARY LINE
 - FENCE LINE TYPE AS NOTED
 - UNDERGROUND WATER LINE
 - UNDERGROUND IRRIGATION LINE
 - SANITARY SEWER LINE
 - STORM DRAINAGE LINE
 - UNDERGROUND ELECTRICAL LINE
 - UNDERGROUND TELEPHONE LINE
 - OVERHEAD WIRE
 - OVERHEAD WIRE
 - UNDERGROUND GAS LINE
 - UNDERGROUND CABLE TV LINE
 - BUILDING FACE
 - TRIVERTICATION LINE
 - EXISTING ASPHALT SURFACE
 - EXISTING CONCRETE SURFACE
 - GAS VALVE
 - GAS METER
 - TELEPHONE RISER
 - TELEPHONE MANHOLE
 - CONIFEROUS TREE
 - DECIDUOUS TREE
- SANITARY SEWER CLEANOUT
 - SANITARY SEWER MANHOLE
 - CATCH BASIN
 - STORM DRAIN MANHOLE
 - FOSTER-SHAIN
 - FOSTER-SHAIN CONNECTION
 - FOSTER-SHAIN VALVE
 - UNDERGROUND WATER VAULT
 - WATER METER BOX
 - WATER VALVE
 - SPRINKLER VALVE
 - SPRINKLER
 - STREET LIGHT (COURBA ARM)
 - STREET LIGHT (SHIMULE)
 - SHIMULE LIGHT
 - AERONAUTICAL LIGHT
 - ELECTRIC METER
 - TELEPHONE RISER
 - PARKING MARKER
 - TRAFFIC SIGNAL POLE
 - SIGNAL JUNCTION BOX
 - UNDERGROUND CLEANOUT
 - UNDERGROUND MANHOLE
 - ROLLARD
 - GATE POST
 - MAILBOX
 - SIGN




KEY MAP
 SCALE: 1" = 50'





LEGEND

| | |
|--|-----------------------------|
| | EXISTING BOUNDARY LINE |
| | EXISTING HIGH CAPACITY LINE |
| | EXISTING LINE |
| | EASEMENT LINE |
| | SETBACK LINE |
| | BUILDING OVERHANG LINE |
| | FENCE LINE, TYPE AS NOTED |
| | UNDERGROUND WATER LINE |
| | UNDERGROUND IRRIGATION LINE |
| | STORM SEWER LINE |
| | UNDERGROUND ELECTRICAL LINE |
| | OVERHEAD WIRE |
| | UNDERGROUND GAS LINE |
| | UNDERGROUND CABLE TV LINE |
| | TREE VEGETATION LINE |
| | EXISTING ASPHALT SURFACE |
| | EXISTING CONCRETE SURFACE |
| | GAS VALVE |
| | TELEPHONE RISER |
| | TELEPHONE MANHOLE |
| | CONIFEROUS TREE |
| | DECIDUOUS TREE |

| | |
|--|----------------------------|
| | SANITARY SEWER CLEANOUT |
| | SANITARY SEWER MANHOLE |
| | CATCH BASIN |
| | STORM DRAIN MANHOLE |
| | ROOF DRAIN |
| | FIRE HYDRANT |
| | FIRE DEPARTMENT CONNECTION |
| | POST INDICATOR VALVE |
| | UNDERGROUND WATER VAULT |
| | WATER VALVE |
| | WATER METER BOX |
| | SPRINKLER VALVE |
| | GROUND LIGHT |
| | STREET LIGHT (FORBIKAM) |
| | STREET LIGHT (GRINDER) |
| | TRANSFORMER |
| | ELECTRIC METER |
| | PARKING BUMPER |
| | TRAFFIC SIGNAL POLE |
| | SIGNAL JUNCTION BOX |
| | UNKNOWN CLEANOUT |
| | UNKNOWN MANHOLE |
| | BOLLARD |
| | GATE POST |
| | MAILBOX |
| | SIGN |







NOTE:
 SEE 50 SCALE PLAN SHEETS FOR DETAILS


PROJECT SUMMARY:

| | |
|--|---------------------|
| SITE AREA | 91.74 ACRES |
| CONSERVATION AREA | 5.23 ACRES |
| REQUIRED LANDSCAPE AREA | 26.42 ACRES |
| PAVED AREA | 4.71 ACRES |
| HARDSCAPE AREA | 10.89 ACRES |
| PROPOSED LANDSCAPE AREA | 45 ACRES |
| PROPOSED PAVED AREA | 4.14 ACRES |
| PROPOSED ASPHALT AREA | 14.40 ACRES |
| ROOF AREA RATIO: | 0.21 |
| TENANTS BUILDING AREA: | |
| 1005 RETAIL | 21,572 SF |
| 1006 RETAIL | 21,720 SF |
| 1007 RETAIL | 10,000 SF |
| BLDG A | 5,850 SF |
| BLDG C PAD | 3,950 SF |
| BLDG D | 22,495 SF |
| 1008 RETAIL | 10,000 SF |
| PAD E-100 | 3,175 SF |
| PAD F-100 | 3,374 SF |
| 1009 RESTAURANT | 4,000 SF |
| 1010 RESTAURANT | 5,777 SF |
| N-100 HEALTH CLUB | 45,000 SF |
| OVERALL TENANTS BUILDING SF: | 232,917 SF |
| TENANTS BUILDING PERIMETER (IF DIFFERENT FROM OVERALL PERIMETER): | |
| 1005 RETAIL PERIMETER | 158,800 SF |
| 1006 RETAIL PERIMETER | 167,250 SF |
| N-100 HEALTH CLUB PERIMETER | 367,250 SF |
| OVERALL TENANTS BUILDING PER. SF: | 281,445 SF |
| STANDARD PARKING STALLS (P+V) | 109 STALLS |
| COMPACT PARKING STALLS (7.75' x 6') | 228 STALLS |
| A.D.A. PARKING STALLS (P+V) | 50 STALLS |
| OVERALL PROVIDED STALLS: | 1,314 STALLS |
| OVERALL PARKING RATIO: | 4.46/1000 |




NOTES:
 (1) PROJECT AREA INCLUDES PARCELS AND ADJACENT RIGHT-OF-WAY AREA ALONG NYBERG ROAD. TOTAL PROJECT AREA ASSUMES ACQUISITION OF EXCESS, ADJACENT HIGHWAY.
 (2) PROJECT AREA INCLUDES THE EXISTING LAND AREA FROM THE NYBERG STREET EXTENSION AND RELOCATION OF THE CITY BUILDING.
 (3) BUILDING AREAS PROVIDED BY CENTRAL PROPERTIES, LLC ARE COMPOSED OF PLANTED AREA AND HARDSCAPE AREA.






MATCHLINE - SEE SHEET C1.2



- LEGEND**
- PROPERTY LINE
 - EXISTING CURB
 - PROPOSED BUILDING USE
 - PROPOSED WALL LINE
 - PROPOSED CURB LINE
 - PROPOSED COMPACT STALL
 - PROPOSED ADA STALL
 - PROPOSED CROSSWALK STRIPING
 - PROPOSED TRASH ENCLOSURE
 - EXISTING TREE
 - PROPOSED LIGHT POLES





- LEGEND**
- PROPERTY USE
 - EXISTING CURBLINE
 - PROPOSED CURBLINE
 - PROPOSED WALLLINE
 - PROPOSED CURBLINE
 - PROPOSED CONTACT STALL
 - PROPOSED ADA STALL
 - PROPOSED CROSSWALK LETTERING
 - PROPOSED TRASH ENCLOSURE
 - EXISTING TREE
 - PROPOSED LIGHT POLES





KEY MAP
 SCALE: 1" = 50'

- LEGEND**
- - - - - EXISTING WATER LINE
 - - - - - PROPOSED WATER PRIVATE LINE
 - - - - - PROPOSED WATER PUBLIC LINE
 - - - - - EXISTING FIRE WATER LINE
 - - - - - PROPOSED FIRE WATER LINE
 - - - - - PROPOSED DOMESTIC WATER LINE
 - - - - - EXISTING FIRE HYDRANT
 - - - - - EXISTING WATER METER
 - - - - - EXISTING WATER VALVE
 - - - - - EXISTING FIRE VALVE
 - - - - - PROPOSED FIRE DEPT. CONNECTION
 - - - - - PROPOSED WATER SUBJECT MATTER
 - - - - - PROPOSED DOUBLE CHECK VALVE
 - - - - - EXISTING TREE TO BE REMOVED
 - - - - - EXISTING TREE TO BE REMOVED FOR SANITARY PUBLIC UTILITY REMOVAL
 - - - - - EXISTING TREE TO BE REMOVED FOR ADDITIONAL W/RT SECTION 3A.220
 - - - - - EXISTING TREE TO BE REMOVED FOR TREE REMOVAL UNDESIRABLE TO SINGLE-PHASE OF PROPERTY
 - - - - - EXISTING TREE TO BE REMOVED FOR PUBLIC STREET IMPROVEMENTS
 - - - - - EXISTING TREE TO BE REMOVED WHEN APPROVED BY CDDT
 - - - - - EXISTING TREE TO BE PROTECTED AND REMOVED AFTER
 - - - - - EXISTING TREE TO BE PROTECTED AND REPLACED WITH APPROVED TREE
- - - - - EXISTING MAJOR CONTOUR
 - - - - - EXISTING MAJOR CONTOUR
 - - - - - EXISTING MAJOR CONTOUR
 - - - - - PROPERTY LINE
 - - - - - LOT LINE
 - - - - - VISION CLEARANCE LINE
 - - - - - EXISTING STORM LINE
 - - - - - PROPOSED STORM PRIVATE LINE
 - - - - - PROPOSED STORM PUBLIC LINE
 - - - - - EXISTING STORM MANHOLE
 - - - - - EXISTING STORM CATCH BASIN
 - - - - - PROPOSED STORM MANHOLE
 - - - - - PROPOSED STORM CATCH BASIN
 - - - - - PROPOSED STORM CLEAN OUT
 - - - - - PROPOSED STORM LOW IMPACT DESIGN FEATURE
 - - - - - EXISTING CASSEMENT
 - - - - - PROPOSED CASSEMENT
 - - - - - EXISTING SANITARY LINE
 - - - - - PROPOSED SANITARY PRIVATE LINE
 - - - - - PROPOSED SANITARY PUBLIC LINE
 - - - - - EXISTING SANITARY MANHOLE
 - - - - - PROPOSED SANITARY MANHOLE
 - - - - - PROPOSED PRIVATE MANHOLE
 - - - - - PROPOSED SANITARY CATCH BASIN
 - - - - - PROPOSED SANITARY CLEAN OUT
 - - - - - PROPOSED GRIFFAGE INTERCEPTOR



LEGEND




| | | | |
|--|--------------------------------|--|--|
| | EXISTING MINOR CONTOUR | | EXISTING WATER LINE |
| | PROPOSED MINOR CONTOUR | | PROPOSED WATER PRIVATE LINE |
| | EXISTING MAJOR CONTOUR | | PROPOSED WATER PUBLIC LINE |
| | PROPOSED MAJOR CONTOUR | | PROPOSED FIRE WATER LINE |
| | PROPERTY LINE | | PROPOSED FIRE HYDRANT |
| | LOT LINE | | EXISTING FIRE HYDRANT |
| | EXISTING CLEARANCE LINE | | EXISTING FIRE HYDRANT METER |
| | EXISTING STORM LINE | | EXISTING WATER METER |
| | PROPOSED STORM PRIVATE LINE | | EXISTING WATER VALVE |
| | PROPOSED STORM PUBLIC LINE | | PROPOSED FIRE DEPT. CONNECTION |
| | EXISTING STORM MANHOLE | | PROPOSED WATER/REDUCT METER |
| | EXISTING STORM CATCH BASIN | | PROPOSED DOUBLE CHECK VALVE |
| | PROPOSED STORM MANHOLE | | EXISTING TREE TO BE REMOVED |
| | PROPOSED STORM CATCH BASIN | | EXISTING TREE TO BE PROTECTED IN PLACE WITH FENCING AROUND THE DRIP LINE |
| | PROPOSED STORM CLEAN OUT | | EXISTING TREE REMOVED FOR PUBLIC STREET IMPROVEMENTS |
| | EXISTING EASEMENT | | EXISTING TREE TO BE PROTECTED WHEN APPROVED BY CDOT |
| | PROPOSED EASEMENT | | EXISTING TREE REMOVED FOR PUBLIC UTILITY INSTALLATION OR EXISTING PUBLIC UTILITY REMOVAL |
| | EXISTING SANITARY LINE | | EXISTING TREE REMOVED IN ACCORDANCE WITH SECTION 4A.000 OF PROPERTY |
| | PROPOSED SANITARY PRIVATE LINE | | EXISTING TREE REMOVED FOR PUBLIC STREET IMPROVEMENTS |
| | PROPOSED SANITARY PUBLIC LINE | | EXISTING TREE TO BE PROTECTED WHEN APPROVED BY CDOT |
| | EXISTING SANITARY MANHOLE | | EXISTING TREE REMOVED FOR PUBLIC UTILITY INSTALLATION OR EXISTING PUBLIC UTILITY REMOVAL |
| | PROPOSED SANITARY MANHOLE | | EXISTING TREE REMOVED IN ACCORDANCE WITH SECTION 4A.000 OF PROPERTY |
| | PROPOSED SANITARY CATCH BASIN | | EXISTING TREE TO BE PROTECTED WHEN APPROVED BY CDOT |
| | PROPOSED SANITARY CLEAN OUT | | EXISTING TREE REMOVED FOR PUBLIC STREET IMPROVEMENTS |
| | PROPOSED DOUBLE CHECK VALVE | | EXISTING TREE TO BE PROTECTED WHEN APPROVED BY CDOT |



KEY MAP
SCALE: 1/2"

MATCHLINE - SEE SHEET C2.2

MATCHLINE - SEE SHEET C2.0



- LEGEND**
- - - - - EXISTING WATER VALVE
 - - - - - PROPOSED FIRE HYDRANT
 - - - - - EXISTING TREE DEF. CONNECTION
 - - - - - PROPOSED WATER/SEWER METER
 - - - - - PROPOSED DOUBLE CHECK VALVE
 - - - - - EXISTING TREE TO BE REMOVED
 - - - - - EXISTING TREE MANHOLE FOR PUBLIC UTILITY INSTALLATION OR EXISTING PUBLIC UTILITY REMOVAL
 - - - - - EXISTING TREE REMAINED IN ACCESSIBLE WITH SECTION 54.200 ACCORDANCE WITH SECTION 54.200 OF PROPERTY (1 PER SHALE PARCEL)
 - - - - - EXISTING TREE REMAINED FOR PUBLIC STREET IMPROVEMENTS
 - - - - - EXISTING TREE REMAINED WITHIN APPROVED BY ODOT
 - - - - - EXISTING TREE TO BE PROTECTED IN PLACE WITH FENCING AROUND THE GAP LINE
- EXISTING WATER VALVE
 - PROPOSED FIRE HYDRANT
 - EXISTING TREE DEF. CONNECTION
 - PROPOSED WATER/SEWER METER
 - PROPOSED DOUBLE CHECK VALVE
 - EXISTING TREE TO BE REMOVED
 - EXISTING TREE MANHOLE FOR PUBLIC UTILITY INSTALLATION OR EXISTING PUBLIC UTILITY REMOVAL
 - EXISTING TREE REMAINED IN ACCESSIBLE WITH SECTION 54.200 ACCORDANCE WITH SECTION 54.200 OF PROPERTY (1 PER SHALE PARCEL)
 - EXISTING TREE REMAINED FOR PUBLIC STREET IMPROVEMENTS
 - EXISTING TREE REMAINED WITHIN APPROVED BY ODOT
 - EXISTING TREE TO BE PROTECTED IN PLACE WITH FENCING AROUND THE GAP LINE
- EXISTING MAJOR CONTOUR
 - - - - - PROPOSED MAJOR CONTOUR
 - - - - - EXISTING MINOR CONTOUR
 - - - - - PROPOSED MINOR CONTOUR
 - - - - - PROPERTY LINE
 - - - - - LOT LINE
 - - - - - VISION CLEARANCE LINE
 - - - - - EXISTING STORM LINE
 - - - - - PROPOSED STORM PRIVATE LINE
 - - - - - PROPOSED STORM PUBLIC LINE
 - - - - - EXISTING STORM MANHOLE
 - - - - - EXISTING STORM CATCH BASIN
 - - - - - PROPOSED STORM MANHOLE
 - - - - - PROPOSED STORM CATCH BASIN
 - - - - - PROPOSED STORM CLEAN OUT
 - - - - - PROPOSED STORM LOW IMPACT DESIGN FEATURE
 - - - - - EXISTING EASEMENT
 - - - - - PROPOSED EASEMENT
 - - - - - EXISTING SANITARY LINE
 - - - - - PROPOSED SANITARY PRIVATE LINE
 - - - - - PROPOSED SANITARY PUBLIC LINE
 - - - - - EXISTING SANITARY MANHOLE
 - - - - - PROPOSED SANITARY MANHOLE
 - - - - - PROPOSED PRIVATE CATCH BASIN
 - - - - - PROPOSED SANITARY CLEAN OUT
 - - - - - PROPOSED GREASE INTERCEPTOR
 - - - - - EXISTING WATER LINE
 - - - - - PROPOSED WATER PRIVATE LINE
 - - - - - PROPOSED WATER PUBLIC LINE
 - - - - - PROPOSED FIRE WATER LINE
 - - - - - PROPOSED DOMESTIC WATER LINE
 - - - - - EXISTING WATER METER
 - - - - - EXISTING WATER VALVE
 - - - - - EXISTING WATER VENT

MATCHLINE - SEE SHEET C2.1



| No. | Common Name | Species Name | DBH | Condition | Comments | Temp2 | Prune | Remove | Criteria3 |
|-----|---------------|-----------------------|-----|-----------|------------|-------|-------|--------|-----------|
| 500 | Douglas Fir | Pseudotsuga menziesii | 9 | Bar | | | | | 10 |
| 501 | Douglas Fir | Pseudotsuga menziesii | 2 | Bar | | | | | 10 |
| 502 | Douglas Fir | Pseudotsuga menziesii | 2 | Good | | | | | 10 |
| 503 | Douglas Fir | Pseudotsuga menziesii | 18 | Good | | | | | 10 |
| 504 | Grand Fir | Abies grandis | 18 | Bar | about 20ft | | | | 10 |
| 505 | Douglas Fir | Pseudotsuga menziesii | 18 | Good | | | | | 10 |
| 506 | Douglas Fir | Pseudotsuga menziesii | 20 | Good | | | | | 10 |
| 507 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 508 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 509 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 510 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 511 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 512 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 513 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 514 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 515 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 516 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 517 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 518 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 519 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 520 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 521 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 522 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 523 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 524 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 525 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 526 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 527 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 528 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 529 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 530 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 531 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 532 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 533 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 534 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 535 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 536 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 537 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 538 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 539 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 540 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 541 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 542 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 543 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 544 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 545 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 546 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 547 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 548 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 549 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 550 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 551 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 552 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 553 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 554 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 555 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 556 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 557 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 558 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 559 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 560 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 561 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 562 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 563 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 564 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 565 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 566 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 567 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 568 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 569 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 570 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 571 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 572 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 573 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 574 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 575 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 576 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 577 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 578 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 579 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 580 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 581 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 582 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 583 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 584 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 585 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 586 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 587 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 588 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 589 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 590 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 591 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 592 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 593 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 594 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 595 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 596 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 597 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 598 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 599 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |
| 600 | Bigleaf Maple | Acer macrophyllum | 20 | Good | | | | | 10 |



| No. | Common Name | Species Name | DBH1 | Condition | Comments | Empty? | Remove | Options |
|-----|-------------|-----------------------|------|-----------|----------|--------|--------|---------|
| 751 | Bald Maple | Acer macrocarpum | 26 | Good | | | Yes | Yes |
| 752 | Douglas Fir | Pseudotsuga menziesii | 10 | Good | | | Yes | Yes |
| 753 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 754 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 755 | Bald Maple | Acer macrocarpum | 6 | Fair | | | Yes | Yes |
| 756 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 757 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 758 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 759 | Douglas Fir | Pseudotsuga menziesii | 10 | Fair | | | Yes | Yes |
| 760 | Douglas Fir | Pseudotsuga menziesii | 10 | Good | | | Yes | Yes |
| 761 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 762 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 763 | Bald Maple | Acer macrocarpum | 11 | Fair | | | Yes | Yes |
| 764 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 765 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 766 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 767 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 768 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 769 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 770 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 771 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 772 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 773 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 774 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 775 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 776 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 777 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 778 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 779 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 780 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 781 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 782 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 783 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 784 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 785 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 786 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 787 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 788 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 789 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 790 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 791 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 792 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 793 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 794 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 795 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 796 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 797 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 798 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 799 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 800 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 801 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 802 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 803 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 804 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 805 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 806 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 807 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 808 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 809 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 810 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 811 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 812 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 813 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 814 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 815 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 816 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 817 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 818 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 819 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 820 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 821 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 822 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 823 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 824 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 825 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 826 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 827 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 828 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 829 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 830 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 831 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 832 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 833 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 834 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 835 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 836 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 837 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 838 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 839 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 840 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 841 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 842 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 843 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 844 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 845 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 846 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 847 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 848 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 849 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |
| 850 | Bald Maple | Acer macrocarpum | 10 | Good | | | Yes | Yes |

| No. | Common Name | Species Name | DBH | Condition | Comments | Example | Prune | Remove | Check |
|------|-------------|--------------|-----|-----------|----------|---------|-------|--------|-------|
| 4510 | Red Maple | Acer rubrum | 1 | poor | dead | Y1 | Y | Y | C |
| 4511 | Red Maple | Acer rubrum | 2 | poor | dead | Y1 | Y | Y | C |
| 4512 | Red Maple | Acer rubrum | 3 | poor | dead | Y1 | Y | Y | C |
| 4513 | Red Maple | Acer rubrum | 4 | poor | dead | Y1 | Y | Y | C |
| 4514 | Red Maple | Acer rubrum | 5 | poor | dead | Y1 | Y | Y | C |
| 4515 | Red Maple | Acer rubrum | 6 | poor | dead | Y1 | Y | Y | C |
| 4516 | Red Maple | Acer rubrum | 7 | poor | dead | Y1 | Y | Y | C |
| 4517 | Red Maple | Acer rubrum | 8 | poor | dead | Y1 | Y | Y | C |
| 4518 | Red Maple | Acer rubrum | 9 | poor | dead | Y1 | Y | Y | C |
| 4519 | Red Maple | Acer rubrum | 10 | poor | dead | Y1 | Y | Y | C |
| 4520 | Red Maple | Acer rubrum | 11 | poor | dead | Y1 | Y | Y | C |
| 4521 | Red Maple | Acer rubrum | 12 | poor | dead | Y1 | Y | Y | C |
| 4522 | Red Maple | Acer rubrum | 13 | poor | dead | Y1 | Y | Y | C |
| 4523 | Red Maple | Acer rubrum | 14 | poor | dead | Y1 | Y | Y | C |
| 4524 | Red Maple | Acer rubrum | 15 | poor | dead | Y1 | Y | Y | C |
| 4525 | Red Maple | Acer rubrum | 16 | poor | dead | Y1 | Y | Y | C |
| 4526 | Red Maple | Acer rubrum | 17 | poor | dead | Y1 | Y | Y | C |
| 4527 | Red Maple | Acer rubrum | 18 | poor | dead | Y1 | Y | Y | C |
| 4528 | Red Maple | Acer rubrum | 19 | poor | dead | Y1 | Y | Y | C |
| 4529 | Red Maple | Acer rubrum | 20 | poor | dead | Y1 | Y | Y | C |
| 4530 | Red Maple | Acer rubrum | 21 | poor | dead | Y1 | Y | Y | C |
| 4531 | Red Maple | Acer rubrum | 22 | poor | dead | Y1 | Y | Y | C |
| 4532 | Red Maple | Acer rubrum | 23 | poor | dead | Y1 | Y | Y | C |
| 4533 | Red Maple | Acer rubrum | 24 | poor | dead | Y1 | Y | Y | C |
| 4534 | Red Maple | Acer rubrum | 25 | poor | dead | Y1 | Y | Y | C |
| 4535 | Red Maple | Acer rubrum | 26 | poor | dead | Y1 | Y | Y | C |
| 4536 | Red Maple | Acer rubrum | 27 | poor | dead | Y1 | Y | Y | C |
| 4537 | Red Maple | Acer rubrum | 28 | poor | dead | Y1 | Y | Y | C |
| 4538 | Red Maple | Acer rubrum | 29 | poor | dead | Y1 | Y | Y | C |
| 4539 | Red Maple | Acer rubrum | 30 | poor | dead | Y1 | Y | Y | C |
| 4540 | Red Maple | Acer rubrum | 31 | poor | dead | Y1 | Y | Y | C |
| 4541 | Red Maple | Acer rubrum | 32 | poor | dead | Y1 | Y | Y | C |
| 4542 | Red Maple | Acer rubrum | 33 | poor | dead | Y1 | Y | Y | C |
| 4543 | Red Maple | Acer rubrum | 34 | poor | dead | Y1 | Y | Y | C |
| 4544 | Red Maple | Acer rubrum | 35 | poor | dead | Y1 | Y | Y | C |
| 4545 | Red Maple | Acer rubrum | 36 | poor | dead | Y1 | Y | Y | C |
| 4546 | Red Maple | Acer rubrum | 37 | poor | dead | Y1 | Y | Y | C |
| 4547 | Red Maple | Acer rubrum | 38 | poor | dead | Y1 | Y | Y | C |
| 4548 | Red Maple | Acer rubrum | 39 | poor | dead | Y1 | Y | Y | C |
| 4549 | Red Maple | Acer rubrum | 40 | poor | dead | Y1 | Y | Y | C |
| 4550 | Red Maple | Acer rubrum | 41 | poor | dead | Y1 | Y | Y | C |
| 4551 | Red Maple | Acer rubrum | 42 | poor | dead | Y1 | Y | Y | C |
| 4552 | Red Maple | Acer rubrum | 43 | poor | dead | Y1 | Y | Y | C |
| 4553 | Red Maple | Acer rubrum | 44 | poor | dead | Y1 | Y | Y | C |
| 4554 | Red Maple | Acer rubrum | 45 | poor | dead | Y1 | Y | Y | C |
| 4555 | Red Maple | Acer rubrum | 46 | poor | dead | Y1 | Y | Y | C |
| 4556 | Red Maple | Acer rubrum | 47 | poor | dead | Y1 | Y | Y | C |
| 4557 | Red Maple | Acer rubrum | 48 | poor | dead | Y1 | Y | Y | C |
| 4558 | Red Maple | Acer rubrum | 49 | poor | dead | Y1 | Y | Y | C |
| 4559 | Red Maple | Acer rubrum | 50 | poor | dead | Y1 | Y | Y | C |
| 4560 | Red Maple | Acer rubrum | 51 | poor | dead | Y1 | Y | Y | C |
| 4561 | Red Maple | Acer rubrum | 52 | poor | dead | Y1 | Y | Y | C |
| 4562 | Red Maple | Acer rubrum | 53 | poor | dead | Y1 | Y | Y | C |
| 4563 | Red Maple | Acer rubrum | 54 | poor | dead | Y1 | Y | Y | C |
| 4564 | Red Maple | Acer rubrum | 55 | poor | dead | Y1 | Y | Y | C |
| 4565 | Red Maple | Acer rubrum | 56 | poor | dead | Y1 | Y | Y | C |
| 4566 | Red Maple | Acer rubrum | 57 | poor | dead | Y1 | Y | Y | C |
| 4567 | Red Maple | Acer rubrum | 58 | poor | dead | Y1 | Y | Y | C |
| 4568 | Red Maple | Acer rubrum | 59 | poor | dead | Y1 | Y | Y | C |
| 4569 | Red Maple | Acer rubrum | 60 | poor | dead | Y1 | Y | Y | C |
| 4570 | Red Maple | Acer rubrum | 61 | poor | dead | Y1 | Y | Y | C |
| 4571 | Red Maple | Acer rubrum | 62 | poor | dead | Y1 | Y | Y | C |
| 4572 | Red Maple | Acer rubrum | 63 | poor | dead | Y1 | Y | Y | C |
| 4573 | Red Maple | Acer rubrum | 64 | poor | dead | Y1 | Y | Y | C |
| 4574 | Red Maple | Acer rubrum | 65 | poor | dead | Y1 | Y | Y | C |
| 4575 | Red Maple | Acer rubrum | 66 | poor | dead | Y1 | Y | Y | C |
| 4576 | Red Maple | Acer rubrum | 67 | poor | dead | Y1 | Y | Y | C |
| 4577 | Red Maple | Acer rubrum | 68 | poor | dead | Y1 | Y | Y | C |
| 4578 | Red Maple | Acer rubrum | 69 | poor | dead | Y1 | Y | Y | C |
| 4579 | Red Maple | Acer rubrum | 70 | poor | dead | Y1 | Y | Y | C |
| 4580 | Red Maple | Acer rubrum | 71 | poor | dead | Y1 | Y | Y | C |
| 4581 | Red Maple | Acer rubrum | 72 | poor | dead | Y1 | Y | Y | C |
| 4582 | Red Maple | Acer rubrum | 73 | poor | dead | Y1 | Y | Y | C |
| 4583 | Red Maple | Acer rubrum | 74 | poor | dead | Y1 | Y | Y | C |
| 4584 | Red Maple | Acer rubrum | 75 | poor | dead | Y1 | Y | Y | C |
| 4585 | Red Maple | Acer rubrum | 76 | poor | dead | Y1 | Y | Y | C |
| 4586 | Red Maple | Acer rubrum | 77 | poor | dead | Y1 | Y | Y | C |
| 4587 | Red Maple | Acer rubrum | 78 | poor | dead | Y1 | Y | Y | C |
| 4588 | Red Maple | Acer rubrum | 79 | poor | dead | Y1 | Y | Y | C |
| 4589 | Red Maple | Acer rubrum | 80 | poor | dead | Y1 | Y | Y | C |
| 4590 | Red Maple | Acer rubrum | 81 | poor | dead | Y1 | Y | Y | C |
| 4591 | Red Maple | Acer rubrum | 82 | poor | dead | Y1 | Y | Y | C |
| 4592 | Red Maple | Acer rubrum | 83 | poor | dead | Y1 | Y | Y | C |
| 4593 | Red Maple | Acer rubrum | 84 | poor | dead | Y1 | Y | Y | C |
| 4594 | Red Maple | Acer rubrum | 85 | poor | dead | Y1 | Y | Y | C |
| 4595 | Red Maple | Acer rubrum | 86 | poor | dead | Y1 | Y | Y | C |
| 4596 | Red Maple | Acer rubrum | 87 | poor | dead | Y1 | Y | Y | C |
| 4597 | Red Maple | Acer rubrum | 88 | poor | dead | Y1 | Y | Y | C |
| 4598 | Red Maple | Acer rubrum | 89 | poor | dead | Y1 | Y | Y | C |
| 4599 | Red Maple | Acer rubrum | 90 | poor | dead | Y1 | Y | Y | C |
| 4600 | Red Maple | Acer rubrum | 91 | poor | dead | Y1 | Y | Y | C |
| 4601 | Red Maple | Acer rubrum | 92 | poor | dead | Y1 | Y | Y | C |
| 4602 | Red Maple | Acer rubrum | 93 | poor | dead | Y1 | Y | Y | C |
| 4603 | Red Maple | Acer rubrum | 94 | poor | dead | Y1 | Y | Y | C |
| 4604 | Red Maple | Acer rubrum | 95 | poor | dead | Y1 | Y | Y | C |
| 4605 | Red Maple | Acer rubrum | 96 | poor | dead | Y1 | Y | Y | C |
| 4606 | Red Maple | Acer rubrum | 97 | poor | dead | Y1 | Y | Y | C |
| 4607 | Red Maple | Acer rubrum | 98 | poor | dead | Y1 | Y | Y | C |
| 4608 | Red Maple | Acer rubrum | 99 | poor | dead | Y1 | Y | Y | C |
| 4609 | Red Maple | Acer rubrum | 100 | poor | dead | Y1 | Y | Y | C |

1. This tree is to be preserved if it is in good health, in 2011.
 2. The tree is to be preserved if it is in good health, in 2012.
 3. The tree is to be preserved if it is in good health, in 2013.
 4. The tree is to be preserved if it is in good health, in 2014.
 5. The tree is to be preserved if it is in good health, in 2015.
 6. The tree is to be preserved if it is in good health, in 2016.
 7. The tree is to be preserved if it is in good health, in 2017.
 8. The tree is to be preserved if it is in good health, in 2018.
 9. The tree is to be preserved if it is in good health, in 2019.
 10. The tree is to be preserved if it is in good health, in 2020.

- LEGEND**
- PROPOSED BUILDING LINE
 - EXISTING BOUNDARY LINE
 - PROPOSED LOT LINES
 - EXISTING MINOR CONTOUR
 - EXISTING MAJOR CONTOUR
 - PROPOSED MINOR CONTOUR
 - PROPOSED MAJOR CONTOUR
 - PROPOSED WALL
 - PROPOSED RET WALL
 - PROPOSED RET WALL
 - PROPOSED RET WALL
 - PROPOSED RET WALL
 - PROPOSED RET WALL
 - PROPOSED STORM CATCHMENT

GRADING AND EROSION CONTROL NOTES

ALL VERTICALS AND SLOPES TO BE GRADDED AT 2% MAX IN ALL DIRECTIONS TO BE MAINTAINED AWAY FROM BUILDINGS AT ALL TIMES.

ALL PROPOSED GRADINGS TO MATCH INTO EXISTING GRADINGS ON SURROUNDING STREETS, DRIVEWAYS, AND EXISTING AREAS.




INSTALL SLOPE PROTECTION ON ALL EXISTING AND NEW EXPOSED SLOPES TO BE MAINTAINED THROUGHOUT THE DURATION OF ALL CONSTRUCTION ACTIVITIES.

SEEDING FENCE TO BE PLACED AND MAINTAINED DURING ALL CONSTRUCTION ACTIVITIES TO PREVENT SEDIMENT FROM LEAVING THE SITE.

ALL OPTIONAL EROSION AND SEDIMENT CONTROL BEST MANAGEMENT PRACTICES SHALL BE IMPLEMENTED FOR ANTICIPATED CONSTRUCTION ACTIVITIES TO PREVENT SEDIMENT FROM LEAVING THE SITE.

ALL EROSION AND SEDIMENT CONTROL FACILITIES WILL BE INSTALLED PRIOR TO ANY CLEARING AND GRADING ACTIVITIES.

EROSION AND SEDIMENT CONTROL FACILITIES SHALL BE FENCED AND MAINTAINED THROUGHOUT THE DURATION OF ALL CONSTRUCTION ACTIVITIES.






LEGEND


| | |
|---|--------------------------|
| — | PROPOSED BUILDING LINE |
| — | EXISTING BOUNDARY LINE |
| — | PROPOSED LOT LINES |
| — | EXISTING INNER CONTOUR |
| — | EXISTING MAJOR CONTOUR |
| — | PROPOSED INNER CONTOUR |
| — | PROPOSED MAJOR CONTOUR |
| — | PROPOSED WALL |
| — | PROPOSED TOP OF WALL |
| — | PROPOSED FOOTING |
| — | PROPOSED NEW FOOT |
| — | PROPOSED STORM CATCHMENT |

GRADING AND EROSION CONTROL NOTES

ALL GRASS STALLS AND AREAS TO BE GRADED AT 2% MAX IN ALL DIRECTIONS.
 ALL PROPOSED GRASSES TO BE MAINTAINED AWAY FROM SUBSIDED AT SURROUNDING STREETS, PROPERTIES, AND URBAN AREAS.
 INSTALL SILT SEDIMENT PROTECTION ON ALL SETTINGS AND BOW MAINTAINED FOR THE DURATION OF ALL CONSTRUCTION ACTIVITIES.
 SEDIMENT FENCE TO BE PLACED AND MAINTAINED DURING ALL PHASES OF CONSTRUCTION TO PREVENT SEDIMENT FROM LEAVING THE SITE.
 ALL ADDITIONAL EROSION AND SEDIMENT CONTROL, BEST MANAGEMENT PRACTICES SHALL BE IMPLEMENTED FOR UNANTICIPATED FACILITIES TO BE IMPROVED AS NEEDED FOR STORM EVENTS.
 ALL EROSION AND SEDIMENT CONTROL FACILITIES SHALL BE CONSTRUCTED PRIOR TO ANY CLEARING AND GRADING ACTIVITIES.
 STORMING NEEDS TO BE PROTECTED ON RETAINING WALLS BE FORCED WITH AN OVERLAP OF 10 FEET TO ADJACENT PERIODS DURING CONSTRUCTION.



MATCHLINE - SEE SHEET C3.1



LEGEND



- PROPERTY LINE
- ADT LINE
- EXISTING STORM LINE
- PROPOSED STORM PRIVATE LINE
- PROPOSED STORM PUBLIC LINE
- EXISTING STORM MANHOLE
- EXISTING STORM CATCH BASIN
- PROPOSED STORM MANHOLE
- PROPOSED STORM CATCH BASIN
- PROPOSED STORM CLEAN OUT
- EXISTING STORM EASEMENT
- PROPOSED STORM EASEMENT
- EXISTING VACATED EASEMENT

STORM STRUCTURE CATCHBASIN TABLE

| NO. | DESCRIPTION | DATE | BY |
|-----|-------------------|----------|-----|
| 1 | 20' DIA. CONCRETE | 10/03/10 | JES |
| 2 | 18' DIA. CONCRETE | 10/03/10 | JES |
| 3 | 15' DIA. CONCRETE | 10/03/10 | JES |
| 4 | 12' DIA. CONCRETE | 10/03/10 | JES |
| 5 | 10' DIA. CONCRETE | 10/03/10 | JES |
| 6 | 8' DIA. CONCRETE | 10/03/10 | JES |
| 7 | 6' DIA. CONCRETE | 10/03/10 | JES |
| 8 | 4' DIA. CONCRETE | 10/03/10 | JES |
| 9 | 3' DIA. CONCRETE | 10/03/10 | JES |
| 10 | 2' DIA. CONCRETE | 10/03/10 | JES |

STORM STRUCTURE MANHOLE/Vault TABLE

| NO. | DESCRIPTION | DATE | BY |
|-----|-------------------|----------|-----|
| 1 | 24" DIA. CONCRETE | 10/03/10 | JES |
| 2 | 20" DIA. CONCRETE | 10/03/10 | JES |
| 3 | 18" DIA. CONCRETE | 10/03/10 | JES |
| 4 | 15" DIA. CONCRETE | 10/03/10 | JES |
| 5 | 12" DIA. CONCRETE | 10/03/10 | JES |
| 6 | 10" DIA. CONCRETE | 10/03/10 | JES |
| 7 | 8" DIA. CONCRETE | 10/03/10 | JES |
| 8 | 6" DIA. CONCRETE | 10/03/10 | JES |
| 9 | 4" DIA. CONCRETE | 10/03/10 | JES |
| 10 | 3" DIA. CONCRETE | 10/03/10 | JES |



LEGEND





- PROPERTY LINE
- LOT LINE
- EXISTING STORM LINE
- PROPOSED STORM PRIVATE LINE
- PROPOSED STORM PUBLIC LINE
- EXISTING STORM MANHOLE
- PROPOSED STORM MANHOLE
- EXISTING STORM CLEAN-OUT
- PROPOSED STORM CLEAN-OUT
- EXISTING STORM BASEMENT
- PROPOSED STORM BASEMENT
- EXISTING WASTED BASEMENT
- PROPOSED WASTED BASEMENT
- EXISTING STORMWATER LID FACILITY
- PROPOSED STORMWATER LID FACILITY

STORM STRUCTURE CATCH-BASIN TABLE

| MANHOLE | STRUCTURE | COORDINATES |
|------------|-------------------------|---------------------|
| MANHOLE 1 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 2 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 3 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 4 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 5 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 6 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 7 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 8 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 9 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 10 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 11 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 12 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 13 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 14 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 15 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 16 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 17 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 18 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 19 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 20 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 21 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 22 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 23 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 24 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 25 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 26 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 27 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 28 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 29 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 30 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 31 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 32 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 33 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 34 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 35 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 36 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 37 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 38 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 39 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 40 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 41 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 42 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 43 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 44 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 45 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 46 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 47 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 48 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 49 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 50 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |


STORM STRUCTURE MANHOLE/Vault TABLE

| MANHOLE | STRUCTURE | COORDINATES |
|------------|-------------------------|---------------------|
| MANHOLE 1 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 2 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 3 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 4 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 5 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 6 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 7 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 8 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 9 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 10 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 11 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 12 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 13 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 14 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 15 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 16 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 17 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 18 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 19 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 20 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 21 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 22 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 23 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 24 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 25 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 26 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 27 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 28 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 29 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 30 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 31 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 32 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 33 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 34 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 35 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 36 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 37 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 38 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 39 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 40 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 41 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 42 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 43 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 44 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 45 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 46 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 47 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 48 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 49 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |
| MANHOLE 50 | STORMWATER LID FACILITY | E CUT (FC) = 102.41 |




LEGEND

| | |
|-----|----------------------------------|
| --- | PROPERTY LINE |
| --- | EXISTING STORMLINE |
| --- | PROPOSED STORM PRIVATE LINE |
| --- | PROPOSED STORM PUBLIC LINE |
| ○ | EXISTING STORM MANHOLE |
| ○ | PROPOSED STORM CATCH BASIN |
| ○ | PROPOSED STORM MANHOLE |
| ○ | PROPOSED STORM CATCH BASIN |
| ○ | PROPOSED STORM CLEAN OUT |
| --- | EXISTING STORM EASEMENT |
| --- | PROPOSED STORM EASEMENT |
| --- | EXISTING VACATED EASEMENT |
| --- | PROPOSED STORMWATER LID FACILITY |



MATCHLINE - SEE SHEET C4.1





STORMWATER LOW IMPACT DESIGN FEATURE DETAIL
 SEE C4.2

STORM STRUCTURE MANHOLE/VAULT TABLE

| ITEM NO. | DESCRIPTION | DATE | CONTRACT NO. | CONTRACT NO. |
|----------|-------------|----------|--------------|--------------|
| 1 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 2 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 3 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 4 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 5 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 6 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 7 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 8 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 9 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 10 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 11 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 12 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 13 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 14 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 15 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 16 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 17 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 18 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 19 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 20 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 21 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 22 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 23 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 24 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 25 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 26 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 27 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 28 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 29 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 30 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 31 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 32 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 33 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 34 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 35 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 36 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 37 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 38 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 39 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 40 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 41 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 42 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 43 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 44 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 45 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 46 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 47 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 48 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 49 | MANHOLE | 11/15/13 | 1144 | 1144 |
| 50 | MANHOLE | 11/15/13 | 1144 | 1144 |

STORM STRUCTURE CATCH-BASIN TABLE

| ITEM NO. | DESCRIPTION | DATE | CONTRACT NO. | CONTRACT NO. |
|----------|-------------|----------|--------------|--------------|
| 1 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 2 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 3 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 4 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 5 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 6 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 7 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 8 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 9 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 10 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 11 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 12 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 13 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 14 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 15 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 16 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 17 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 18 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 19 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 20 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 21 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 22 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 23 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 24 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 25 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 26 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 27 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 28 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 29 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 30 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 31 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 32 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 33 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 34 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 35 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 36 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 37 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 38 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 39 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 40 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 41 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 42 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 43 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 44 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 45 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 46 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 47 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 48 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 49 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |
| 50 | CATCH-BASIN | 11/15/13 | 1144 | 1144 |



KEY MAP
 SCALE: 1" = 100'

LEGEND



| | | | | | | | | | | | | | | | | | | | | | |
|---------------|------------------------|--------------------------------|-------------------------------|---------------------------|---------------------------|--------------------------|---------------------------|------------------------------|----------------|------------------------|---------------------|---------------------|------------------------|------------------------|----------------------------|--------------------------|---------------------|-----------------------|----------------------|----------------------|----------------------|
| PROPERTY LINE | EXISTING SANITARY LINE | PROPOSED SANITARY PRIVATE LINE | PROPOSED SANITARY PUBLIC LINE | EXISTING SANITARY MANHOLE | PROPOSED SANITARY MANHOLE | PROPOSED PRIVATE MANHOLE | PROPOSED GREASE CLEAN OUT | PROPOSED GREASE INTERCEPTION | EXISTING BASIN | EXISTING MANHOLE BASIN | EXISTING STORM LINE | PROPOSED STORM LINE | EXISTING STORM MANHOLE | PROPOSED STORM MANHOLE | PROPOSED STORM DITCH BASIN | PROPOSED STORM CLEAN OUT | EXISTING WATER LINE | EXISTING FIRE HYDRANT | EXISTING WATER METER | EXISTING WATER VAULT | EXISTING WATER VALVE |
| --- | --- | --- | --- | ○ | ○ | ○ | --- | --- | --- | --- | --- | --- | ○ | ○ | --- | --- | --- | --- | --- | --- | --- |

GREASE INTERCEPTOR DATA

| NO. | LOCATION | SIZE | DATE |
|-----|----------|------|----------|
| 1 | LOT 34 | 1000 | 10/21/13 |
| 2 | LOT 35 | 1000 | 10/21/13 |
| 3 | LOT 36 | 1000 | 10/21/13 |

MANHOLE DATA

| NO. | LOCATION | SIZE | DATE |
|-----|----------|------|----------|
| 1 | LOT 34 | 1000 | 10/21/13 |
| 2 | LOT 35 | 1000 | 10/21/13 |
| 3 | LOT 36 | 1000 | 10/21/13 |



- LEGEND**
- PROPERTY LINE
 - LOT LINE
 - EXISTING SANITARY LINE
 - PROPOSED SANITARY PRIVATE LINE
 - PROPOSED SANITARY PUBLIC LINE
 - EXISTING SANITARY MANHOLE
 - PROPOSED PUBLIC MANHOLE
 - PROPOSED SANITARY CATCH BASIN
 - PROPOSED SANITARY CLEAN OUT
 - PROPOSED CLEANSE INTERCEPTOR
 - EXISTING BASEMENT
 - PROPOSED BASEMENT
 - EXISTING VACATED BASEMENT
 - EXISTING STORM LINE
 - PROPOSED STORM PRIVATE LINE
 - PROPOSED STORM PUBLIC LINE
 - EXISTING STORM MANHOLE
 - PROPOSED STORM MANHOLE
 - PROPOSED STORM CATCH BASIN
 - PROPOSED STORM CLEAN OUT
 - EXISTING WATER LINE
 - EXISTING FIRE HYDRANT
 - EXISTING WATER METER
 - EXISTING WATER VALVE
 - EXISTING WATER VALVE

BASEMENT INTERCEPTOR DATA



| NO. | COORDINATES | DIAMETER | DEPTH |
|-----|-------------------------------------|----------|--------|
| 1 | E IN (P) = 1024 E OUT (P) = 1024 | 36" | 10'-0" |
| 2 | E IN (P) = 1024 E OUT (P) = 1024 | 36" | 10'-0" |
| 3 | E IN (P) = 1024 E OUT (P) = 1024 | 36" | 10'-0" |
| 4 | E IN (P) = 1024 E OUT (P) = 1024 | 36" | 10'-0" |
| 5 | E IN (P) = 1024 E OUT (P) = 1024 | 36" | 10'-0" |

MANHOLE DATA

| NO. | COORDINATES | DIAMETER | DEPTH |
|-----|-------------------------------------|----------|--------|
| 1 | E IN (P) = 1024 E OUT (P) = 1024 | 36" | 10'-0" |
| 2 | E IN (P) = 1024 E OUT (P) = 1024 | 36" | 10'-0" |
| 3 | E IN (P) = 1024 E OUT (P) = 1024 | 36" | 10'-0" |
| 4 | E IN (P) = 1024 E OUT (P) = 1024 | 36" | 10'-0" |
| 5 | E IN (P) = 1024 E OUT (P) = 1024 | 36" | 10'-0" |

CATCH BASIN DATA

| NO. | COORDINATES | DIAMETER | DEPTH |
|-----|-------------------------------------|----------|--------|
| 1 | E IN (P) = 1024 E OUT (P) = 1024 | 36" | 10'-0" |
| 2 | E IN (P) = 1024 E OUT (P) = 1024 | 36" | 10'-0" |
| 3 | E IN (P) = 1024 E OUT (P) = 1024 | 36" | 10'-0" |
| 4 | E IN (P) = 1024 E OUT (P) = 1024 | 36" | 10'-0" |
| 5 | E IN (P) = 1024 E OUT (P) = 1024 | 36" | 10'-0" |



MATCHLINE - SEE SHEET C5.2

MATCHLINE - SEE SHEET C5.0

WATER SYSTEM PLAN (PUBLIC FACILITIES PLAN)
NYBERG RIVERS - ARCHITECTURAL REVIEW BOARD
CENTRAL PROPERTIES, L.L.C.
 TUALATIN, OREGON

| | |
|--------------|----------|
| PROJECT NO.: | 111839 |
| DATE: | 11/04/10 |
| DESIGNED BY: | PH/MSD |
| DRAWN BY: | BJF |
| CHECKED BY: | JCS |

WATER SYSTEM
(PUBLIC FACILITIES)
C6.1
 Exhibit 1
 Attachment 0-5

- LEGEND**
- PROPERTY LINE
 - EXISTING WATER LINE
 - PROPOSED WATER PRIVATE LINE
 - PROPOSED WATER PUBLIC LINE
 - PROPOSED FIRE WATER LINE
 - EXISTING FIRE WATER LINE
 - EXISTING FIRE HYDRANT
 - EXISTING WATER WALL
 - EXISTING FIRE HYDRANT
 - PROPOSED FIRE HYDRANT
 - PROPOSED FIRE METER
 - PROPOSED FIRE METER/DETECT METER
 - PROPOSED DOUBLE CHECK VALVE
 - EXISTING WATER EXHAUST
 - PROPOSED WATER EXHAUST
 - EXISTING WATER EXHAUST
 - EXISTING FIRE HYDRANT

WATER GENERAL NOTES:

1. ALL EXISTING WATER METERS AND INDUCT VALVES SHALL BE MAINTAINED AND REPAIRS PROVIDED AS NECESSARY.
2. ALL EXISTING WATER LINES TO BE MAINTAINED SHALL BE MAINTAINED AS NECESSARY.
3. ALL FIRE DEPARTMENT CONNECTIONS SHALL BE WITHIN 100' OF A FIRE HYDRANT.
4. ALL FIRE LINES BACKFLOW TO BE PROVIDED INSIDE THE BUILDING.

EXISTING FIRE FLOW TEST DATA:

TEST DATE: 8/10/09

STATIC HYDRANT: NYBERG ROAD

FLOW HYDRANT: NYBERG ROAD

DEE PLAN LOCATION



STATIC PRESSURE: ~ 70 PSI

RESIDUAL PRESSURE: ~ 66 PSI

FLOW: 1400 GPM

PRESSURE: ~ 20 PSI

AVAILABLE FLOW: ~ 3750 GPM



KEY MAP
 SCALE: 1" = 50'

MATCHLINE - SEE SHEET C6.2


MATCHLINE - SEE SHEET C6.0

WATER SYSTEM PLAN (PUBLIC FACILITIES PLAN)
 NYBERG RIVERS - ARCHITECTURAL REVIEW BOARD
 CENTRAL PROPERTIES, LLC
 TUALATIN, OREGON

| | |
|-------------|----------|
| PROJECT NO. | 211624 |
| DATE | 11/04/13 |
| REVISION BY | RH/RSB |
| DRAWN BY | RSB |
| CHECKED BY | JS |

WATER SYSTEM
 (PUBLIC FACILITIES)

C6.2
 Exhibit 1
 Attachment 03



- LEGEND**
- PROPERTY LINE
 - EXISTING WATER LINE
 - PROPOSED WATER PRIVATE LINE
 - PROPOSED WATER PUBLIC LINE
 - PROPOSED FIRE WATER LINE
 - PROPOSED DOMESTIC WATER LINE
 - EXISTING FIRE HYDRANT
 - EXISTING WATER METER
 - EXISTING WATER VALVE
 - PROPOSED FIRE HYDRANT
 - PROPOSED WATER METER
 - PROPOSED FIRE DEPT. CONNECTION
 - PROPOSED WATER METER/DECK/VALVE
 - PROPOSED DOUBLE CHECK VALVE
 - EXISTING WATER BASIN/ST
 - PROPOSED WATER BASIN/ST
 - EXISTING WATER BASIN/ST
 - EXISTING FIRE PLUM/HYDRANT

WATER GENERAL NOTES:

- ALL DOMESTIC WATER METERS AND DECK/VALVE CONNECTIONS SHALL BE PROVIDED INSIDE THE BUILDING PROTECTED WATER VAPOR.
- ALL DOMESTIC WATER LINES TO BE INSTALLED AND CONNECTIONS TO BE PROVIDED INSIDE THE BUILDING.
- ALL FIRE DEPARTMENT CONNECTIONS SHALL BE WITHIN 100' OF A FIRE HYDRANT.
- ALL FIRE LINES BACKFLOW TO BE PROVIDED INSIDE THE BUILDING.

EXISTING FIRE FLOW TEST DATA:

TEST DATE: 09/02/09

STATIC HYDRANT: INTERSTATE ROAD (SEE PLAN LOCATION)

FLOW HYDRANT: NYBERG ROAD (SEE PLAN LOCATION)


STATIC PRESSURE = 70 PSI

RESIDUAL PRESSURE = 60 PSI


FLOW = 840 GPM


PRESSURE = 20 PSI


AVAILABLE FLOW = 371 GPM





MATCHLINE - SEE SHEET C6.1













































HARDSCAPE PAVING

| | | |
|--|---|--|
|  |  <p>TRIM PAVERS MANUFACTURER: METAL MATERIALS MODEL: ARCHITECTURAL SLAB SIZE: 12" x 12" SQUARE COLOR: VANOUVERBAY (GRAY)</p>  <p>1/2" Thick 12" x 12" Square</p>  <p>12" x 12" Square 1/2" Thick</p> | <p>TRIM PAVERS MANUFACTURER: HANOVER ARCHITECTURAL PRODUCTS MODEL: TRIM PAVERS SIZE: 12" x 12" SQUARE COLOR: CREAM FINISH: TUBER</p>  <p>12" x 12" Square 1/2" Thick</p>  <p>12" x 12" Square 1/2" Thick</p> <p>SAMPLE OF PATTERN</p> |
| <p>NOT TO SCALE</p> <p>1 STANDARD CONCRETE w/ POLISHED FINISH</p> <p>NOT TO SCALE</p> <p>2 18" ARCHITECTURAL SLAB - TRIM PAVER</p> <p>NOT TO SCALE</p> <p>3 24" x 36" & 12" x 24" ARCHITECTURAL SLAB PAVERS</p> <p>NOT TO SCALE</p> | | |

SITE FURNISHINGS

| | | |
|---|---|--|
|  <p>BENCH MANUFACTURER: INTERCRAFT MODEL: BMJ STRAIGHT w/ BACK SIZE: 8' LENGTH MOUNTING SURFACE</p> |  <p>BENCH MANUFACTURER: INTERCRAFT MODEL: BMJ STRAIGHT w/ BACK SIZE: 8' LENGTH MOUNTING SURFACE</p> |  <p>BENCH MANUFACTURER: INTERCRAFT MODEL: BMJ STRAIGHT w/ BACK SIZE: 8' LENGTH MOUNTING SURFACE</p> |
|  <p>TRASH RECEPTACLE</p> <p>MANUFACTURER: FARMWEATHER SF MODEL: SP412 PINE SQUARE SIZE: 24" x 48" w/ 12" TOP MOUNTING SURFACE</p> |  <p>BENCH MANUFACTURER: INTERCRAFT MODEL: BMJ STRAIGHT w/ BACK SIZE: 8' LENGTH MOUNTING SURFACE</p> |  <p>TRASH RECEPTACLE</p> <p>MANUFACTURER: FARMWEATHER SF MODEL: SP412 PINE SQUARE SIZE: 24" x 48" w/ 12" TOP MOUNTING SURFACE</p> |
| <p>NOT TO SCALE</p> <p>4 8' STANDARD WOODEN BENCH</p> <p>NOT TO SCALE</p> <p>5 8' STANDARD WOODEN BENCH w/o BACK</p> <p>NOT TO SCALE</p> <p>6 8' CURVED WOODEN BENCH</p> <p>NOT TO SCALE</p> <p>7 TRASH RECEPTACLE</p> <p>NOT TO SCALE</p> | | |
|  <p>ASH URN MANUFACTURER: FARMWEATHER SF MODEL: SP412 PINE SQUARE SIZE: 24" x 48" w/ 12" TOP MOUNTING SURFACE</p> |  <p>METAL TREE GRATES</p> <p>MANUFACTURER: FARMWEATHER SF MODEL: SP412 PINE SQUARE SIZE: 24" x 48" w/ 12" TOP MOUNTING SURFACE</p> |  <p>METAL TREE GRATES</p> <p>MANUFACTURER: FARMWEATHER SF MODEL: SP412 PINE SQUARE SIZE: 24" x 48" w/ 12" TOP MOUNTING SURFACE</p> |
| <p>NOT TO SCALE</p> <p>8 ASH URNS</p> <p>NOT TO SCALE</p> <p>9 BOLLARD</p> <p>NOT TO SCALE</p> <p>10 METAL TREE GRATES</p> <p>NOT TO SCALE</p> <p>11 ROOT BARRIER UNDER PLANTER ISLAND</p> <p>NOT TO SCALE</p> <p>12 5'x5' PLANTER DIAMOND w/ IRRIGATION</p> <p>NOT TO SCALE</p> | | |






ELECTRICAL SITE PLAN
 NYBERG RIVERS AR
 CENTRAL PROPERTIES, LLC
 TUALATIN, OREGON

PROJECT NO: 211000
 DATE: 10/10/11
 APPROVED BY: [Signature]
 DRAWN BY: [Signature]
 CHECKED BY: [Signature]


PHOTOMETRIC
 AREA A

E-2
 Exhibit 1
 Attachment 0-5

TASKER
 ELECTRICAL
 CONSTRUCTION
 1984 W. JARVIS CT.
 MERIDIAN, IDAHO 83642
 PHONE: (208) 318-5599



KEY PLAN



ELECTRICAL - AREA A




ELECTRICAL SITE PLAN
 NYBERG RIVERS AR
 CENTRAL PROPERTIES, LLC.
 TUALATIN, OREGON

PROJECT NO: 21889
 DATE: 08/20/08
 DESIGNED BY: RLF
 DRAWN BY: RLF
 CHECKED BY: JEL



PHOTOMETRIC
 AREA B

E-3
 Exhibit 1
 Attachment 05

TASKER
 ELECTRICAL
 CONSTRUCTION
 1085 W. LARVIST
 MERIDIAN, IDAHO 83642
 PHONE: (509) 518-6599



KEY PLAN



ELECTRICAL - AREA B

TASKER
ELECTRICAL
CONSTRUCTION

1998 W. LARVIS CT.
MERRIDEN, DARTMOUTH 8342
PHONE: (360) 516-5699






ELECTRICAL SITE PLAN
NYBERG RIVERS AR
CENTRAL PROPERTIES, LLC
TUALATIN, OREGON

PROJECT NO: 210010
DATE: 08/03/09
DESIGNED BY: NAL
DRAWN BY: RAN
CHECKED BY: REL

PHOTOMETRIC
AREA C

E-4
Exhibit 1
Attachment D05



ELECTRICAL - AREA C

TASKER
ELECTRICAL
CONSTRUCTION

1984 W. LARVIS CT.
MERIDIAN, IDAHO 83842
PHONE: (800) 338-6899





ELECTRICAL SITE PLAN
NYBERG RIVERS AR
CENTRAL PROPERTIES, L.L.C.
TUALATIN, OREGON

PROJECT NO.: 210000
DATE: 07/20/07
DESIGNED BY: JEL
DRAWN BY: BMS
CHECKED BY: JEL

PHOTOMETRIC
AREA D

E-6
Exhibit 1
Attachment 05



KEY PLAN



ELECTRICAL - AREA D

TASKER
ELECTRICAL
CONSTRUCTION

1986 W. JARVIS CT.
MERIDIAN, IDAHO 83642
PHONE: (208) 314-6999




ELECTRICAL SITE PLAN
NYBERG RIVERS AR
CENTRAL PROPERTIES, LLC
TUALATIN, OREGON

PROJECT NO. 1718210
DATE 08/11/10
DESIGNED BY JEL
DRAWN BY JMM
CHECKED BY JEL

PHOTOMETRIC
AREA E


E-6
Exhibit 1
Attachment 0-5



KEY PLAN




ELECTRICAL - AREA E







Building A - South Elevation (A1) - Proposed New Paint & Signage




Building A - East Elevation (A2) - Proposed New Paint & Signage




Building A - North Elevation (A3) - Proposed New Paint & Signage




Building B - South Elevation (B1) - Proposed New Paint & Signage




Building B - North Elevation (B2) - Proposed New Paint & Signage



| Legend | Color / Finishes |
|--------|------------------|
| 1 | PAVING |
| 2 | ASPHALT DRIVE |
| 3 | GRAVEL DRIVE |
| 4 | GRAVEL DRIVE |
| 5 | GRAVEL DRIVE |
| 6 | GRAVEL DRIVE |
| 7 | GRAVEL DRIVE |
| 8 | GRAVEL DRIVE |
| 9 | GRAVEL DRIVE |
| 10 | GRAVEL DRIVE |
| 11 | GRAVEL DRIVE |
| 12 | GRAVEL DRIVE |
| 13 | GRAVEL DRIVE |
| 14 | GRAVEL DRIVE |
| 15 | GRAVEL DRIVE |
| 16 | GRAVEL DRIVE |
| 17 | GRAVEL DRIVE |
| 18 | GRAVEL DRIVE |
| 19 | GRAVEL DRIVE |
| 20 | GRAVEL DRIVE |
| 21 | GRAVEL DRIVE |
| 22 | GRAVEL DRIVE |
| 23 | GRAVEL DRIVE |
| 24 | GRAVEL DRIVE |
| 25 | GRAVEL DRIVE |
| 26 | GRAVEL DRIVE |
| 27 | GRAVEL DRIVE |
| 28 | GRAVEL DRIVE |
| 29 | GRAVEL DRIVE |
| 30 | GRAVEL DRIVE |
| 31 | GRAVEL DRIVE |
| 32 | GRAVEL DRIVE |
| 33 | GRAVEL DRIVE |
| 34 | GRAVEL DRIVE |
| 35 | GRAVEL DRIVE |
| 36 | GRAVEL DRIVE |
| 37 | GRAVEL DRIVE |
| 38 | GRAVEL DRIVE |
| 39 | GRAVEL DRIVE |
| 40 | GRAVEL DRIVE |
| 41 | GRAVEL DRIVE |
| 42 | GRAVEL DRIVE |
| 43 | GRAVEL DRIVE |
| 44 | GRAVEL DRIVE |
| 45 | GRAVEL DRIVE |
| 46 | GRAVEL DRIVE |
| 47 | GRAVEL DRIVE |
| 48 | GRAVEL DRIVE |
| 49 | GRAVEL DRIVE |
| 50 | GRAVEL DRIVE |
| 51 | GRAVEL DRIVE |
| 52 | GRAVEL DRIVE |
| 53 | GRAVEL DRIVE |
| 54 | GRAVEL DRIVE |
| 55 | GRAVEL DRIVE |
| 56 | GRAVEL DRIVE |
| 57 | GRAVEL DRIVE |
| 58 | GRAVEL DRIVE |
| 59 | GRAVEL DRIVE |
| 60 | GRAVEL DRIVE |
| 61 | GRAVEL DRIVE |
| 62 | GRAVEL DRIVE |
| 63 | GRAVEL DRIVE |
| 64 | GRAVEL DRIVE |
| 65 | GRAVEL DRIVE |
| 66 | GRAVEL DRIVE |
| 67 | GRAVEL DRIVE |
| 68 | GRAVEL DRIVE |
| 69 | GRAVEL DRIVE |
| 70 | GRAVEL DRIVE |
| 71 | GRAVEL DRIVE |
| 72 | GRAVEL DRIVE |
| 73 | GRAVEL DRIVE |
| 74 | GRAVEL DRIVE |
| 75 | GRAVEL DRIVE |
| 76 | GRAVEL DRIVE |
| 77 | GRAVEL DRIVE |
| 78 | GRAVEL DRIVE |
| 79 | GRAVEL DRIVE |
| 80 | GRAVEL DRIVE |
| 81 | GRAVEL DRIVE |
| 82 | GRAVEL DRIVE |
| 83 | GRAVEL DRIVE |
| 84 | GRAVEL DRIVE |
| 85 | GRAVEL DRIVE |
| 86 | GRAVEL DRIVE |
| 87 | GRAVEL DRIVE |
| 88 | GRAVEL DRIVE |
| 89 | GRAVEL DRIVE |
| 90 | GRAVEL DRIVE |
| 91 | GRAVEL DRIVE |
| 92 | GRAVEL DRIVE |
| 93 | GRAVEL DRIVE |
| 94 | GRAVEL DRIVE |
| 95 | GRAVEL DRIVE |
| 96 | GRAVEL DRIVE |
| 97 | GRAVEL DRIVE |
| 98 | GRAVEL DRIVE |
| 99 | GRAVEL DRIVE |
| 100 | GRAVEL DRIVE |



① Overall East Elevation - Building 0
Scale of 1/8" = 1'-0"



② Overall West Elevation - Building 0
Scale of 1/8" = 1'-0"

③ Materials

| | | | | | | | |
|---|---|---|---|---|--------------------------------------|---|--|
|  | Paint / Plaster / CMU Color - Golden Professional #201V Golden Sand |  | Paint / Plaster / Precast Concrete Color - Golden Professional #201V Iron White |  | Block Veneer Finish - Stone Blend |  | Tongue & Groove Siding Finish - Vertical Slat |
|  | Paint / Plaster / CMU Color - Golden Professional #201V Dimension |  | Paint Color - New Supreme Prism |  | Stone Veneer Finish - Earth |  | Steel Tile Roof |

EXHIBIT 1
ATTACHMENT O-6

SHEET PLAN
NYBERG RIVERS ARB
 CENTERCAL PROPERTIES, LLC.
 TUALATIN, OREGON



Cardno
Shaping the Future

PORTLAND
 5415 SW WESTGATE DR, STE 110, PORTLAND, OR 97221
 TEL: (503) 419-2500 FAX: (503) 419-2020
 www.cardno.com

| | |
|-------------|----------|
| PROJECT NO. | 210404 |
| DATE | 03.20.20 |
| DRAWN BY | XXX |
| CHECKED BY | XXX |
| DATE | XXX |

OVERALL BUILDING 0
 CHANGE EVALUATION
 A2.10b



Here: Landscape at Summer and Spring for building mass-ships

Here: These perspective renderings are provided for building massing review only and do not reflect the completed landscape scope (see attached landscape plan for landscape information).

EXHIBIT 3
Attachment 04c

SHEET PLAN
NYBERG RIVERS ARB
 CENTERCAL PROPERTIES, LLC.
 TUALATIN, OREGON



| | |
|---|------------|
| PROJECT NO. | 2108006 |
| DATE | 03.23.2017 |
| DRAWING BY | XXX |
| CHECKED BY | XXX |
| INTEGRAL BUILDING & STREET PERSPECTIVES | |
| A210c | |



| Symbol | Materials |
|--------|-----------------------------|
| ⊖ | A. FLOOR |
| ⊖ | B. BRICK VENTIL |
| ⊖ | C. PRESS-TITE/CORTE |
| ⊖ | D. METAL PANELS |
| ⊖ | E. FIBER PANELS |
| ⊖ | F. ALUMINUM EXTRUSION |
| ⊖ | G. TRIMMER AND SHIMS - SHIM |
| ⊖ | H. SLAB TRIMMER |
| ⊖ | I. STAIN STEEL |
| ⊖ | J. WOOD GRAIN SIGNAGE |
| ⊖ | K. CONCRETE BRICK PATTERNS |
| ⊖ | L. DASHING |
| ⊖ | M. SPILT PALE SELECT |

| Symbol | Color / Finishes |
|--------|------------------|
| ⊖ | 1. SANDY LAMB |
| ⊖ | 2. KHAKI STONE |
| ⊖ | 3. LIGHT GREY |
| ⊖ | 4. WINDMILL TONE |
| ⊖ | 5. DUSKY BROWN |
| ⊖ | 6. DARK BROWN |
| ⊖ | 7. SLATE |
| ⊖ | 8. WOOD SIGNAGE |


EXHIBIT 1
Attachment 0-6

SHEET PLAN
NYBERG RIVERS ARB
 CENTRAL PROPERTIES, LLC.
 TUALATIN, OREGON



| | |
|-------------|----------|
| PROJECT NO. | 2118430 |
| DATE | 03/23/20 |
| DRAWN BY | XXX |
| CHECKED BY | XXX |
| DATE | XXX |

PREPARED BY: J. O'NEILL
 CALORIO ELEVATIONS
 AZ11



① South Elevation
Scale: 1/8" = 1'-0"

② North Elevation
Scale: 1/8" = 1'-0"

| ⊕ | MATERIALS |
|---|-------------------------|
| A | PAVING |
| B | BRICK VENEER |
| C | PRECAST CONCRETE |
| D | WOOD SHAKES |
| E | TRUSSES |
| F | TRUSS LINING |
| G | TRUSS BRACING |
| H | TRUSS AND BRACING STUDS |
| I | TRUSS AND BRACING STUDS |
| J | TRUSS BRACING |
| K | TRUSS AND BRACING STUDS |
| L | TRUSS AND BRACING STUDS |
| M | CANOPY |
| N | TRUSS AND BRACING STUDS |

| ⊕ | COLOR / FINISHES |
|---|------------------|
| 1 | EXTERIOR PAINT |
| 2 | EXTERIOR PAINT |
| 3 | EXTERIOR PAINT |
| 4 | EXTERIOR PAINT |
| 5 | EXTERIOR PAINT |
| 6 | EXTERIOR PAINT |
| 7 | EXTERIOR PAINT |
| 8 | EXTERIOR PAINT |


ARCHITECT
ALBERKANE O-6

SHEET PLAN
NYBERG RIVERS ARB
 CENTRAL PROPERTIES, LLC.
 TUALATIN, OREGON




Cardno
 Shaping the Future
 PORTLAND
 5415 SW HESTONATE DR. STE 100, PORTLAND, OR 97221
 TEL: (503) 419-2500 FAX: (503) 419-2000
 www.cardno.com

PROJECT NO: 2119610
 DATE: 02.20.20
 DRAWING BY: JCC
 CHECKED BY: JCC
 ENLARGED REVISIONS:
 CHANGED ELEVATIONS
 AZ12




1 South Elevation
Scale: 1/8" = 1'-0"

| MATERIALS | |
|-----------|----------------|
| A | PAVING |
| B | BRICK VENEER |
| C | WYCKS/DOCKRITZ |
| D | WYCKS/DOCKRITZ |
| E | WYCKS/DOCKRITZ |
| F | WYCKS/DOCKRITZ |
| G | WYCKS/DOCKRITZ |
| H | WYCKS/DOCKRITZ |
| I | WYCKS/DOCKRITZ |
| J | WYCKS/DOCKRITZ |
| K | WYCKS/DOCKRITZ |
| L | WYCKS/DOCKRITZ |
| M | WYCKS/DOCKRITZ |
| N | WYCKS/DOCKRITZ |
| O | WYCKS/DOCKRITZ |
| P | WYCKS/DOCKRITZ |
| Q | WYCKS/DOCKRITZ |
| R | WYCKS/DOCKRITZ |
| S | WYCKS/DOCKRITZ |
| T | WYCKS/DOCKRITZ |
| U | WYCKS/DOCKRITZ |
| V | WYCKS/DOCKRITZ |
| W | WYCKS/DOCKRITZ |
| X | WYCKS/DOCKRITZ |
| Y | WYCKS/DOCKRITZ |
| Z | WYCKS/DOCKRITZ |



2 East Elevation
Scale: 1/8" = 1'-0"



3 North Elevation
Scale: 1/8" = 1'-0"

EXHIBIT 1
Attachment 0-6

Cardno
Shaping the Future
PORTLAND
5415 SW VESTY GATE DR. SITE 103 PORTLAND, OR 97221
TEL: (503) 419-2500 FAX: (503) 419-2000
www.cardno.com

CENTRAL
PROPERTY, LLC
MULVANNY G2
ARCHITECTURE

SHEET PLAN
NYBERG RIVERS ARB
CENTRAL PROPERTIES, LLC.
TUALATIN, OREGON

PROJECT NO: 2186830
DATE: 08/20/2013
DRAWN BY: JAC
CHECKED BY: JAC
ENCL: 01/13
ENLARGED BUILDINGS &
COLORADO PLANNING
A213






EXHIBIT 1
Attachment 0-6

SHEET PLAN
 NYBERG RIVERS ARB
 CENTRAL PROPERTIES, L.L.C.
 TUALATIN, OREGON




LOADING DOCK SECTIONS
A2/H


| | |
|-------------|------------|
| PROJECT NO: | 2108040 |
| DATE: | 02/20/2012 |
| DRAWN BY: | XXX |
| CHECKED BY: | XXX |
| DATE: | 02/20/12 |




1 INTERSECTION OF NYBERG STREET & I-5 OFF-RAMP



2 MAIN DEVELOPMENT ENTRANCE




3 INTERSTATE-5 OFF-RAMP #1



4 INTERSTATE-5 OFF-RAMP #2

GENERAL NOTES:

PARAPET HAS BEEN RAISED 16" (2 CMU COURSES)
 ALL ROOF TOP UNITS SIT ON A 24" CURB



RTU STUDY | 16" RAISED PARAPET



HBA HOLENDAK & BARNETT ARCHITECTS
 10/17/13 P# 12511.1
CABELA'S ROOF TOP UNIT SIGHTLINE STUDY
 RETAIL | TUALATIN, OR

| | |
|--------------|----------|
| PROJECT NO: | 21040 |
| DATE: | 08/03 |
| DESIGNED BY: | 02/28/13 |
| DRAWN BY: | 02/28/13 |
| CHECKED BY: | 02/28/13 |


SHEET PLAN
NYBERG RIVERS ARB
CENTERCAL PROPERTIES, LLC.
TUALATIN, OREGON



Cardno Shaping the Future
 PORTLAND
 5415 SW VESTGATE DR. STE 100, PORTLAND, OR 97221
 TEL: (503) 419-2500 FAX: (503) 419-2500
 www.cardno.com



1 INTERSECTION OF NYBERG STREET & I-5 OFF-RAMP:
 TAKEN FROM A CAR'S VIEW AT A POINT 19'-0" A.F.F. OF CABELA'S RETAIL STORE



GENERAL NOTES:

PARAPET HAS BEEN RAISED 16" (2 CMU COURSES)
 ALL ROOF TOP UNITS SIT ON A 24" CURB



CABELA'S | PRELIMINARY DRAWINGS
RETAIL | TUALATIN, OR

HBA HOLDINGS ARCHITECTS
 09/23/13 P# 12511.1




| | |
|--------------|--------------|
| PROJECT NO: | 218010 |
| DATE: | 09/23/13 |
| DESIGNED BY: | 023.000 |
| DRAWN BY: | 023.000 |
| CHECKED BY: | 023.000 |
| SCALE: | 1/8" = 1'-0" |

SHEET PLAN
NYBERG RIVERS ARB
CENTERCAL PROPERTIES, LLC.
TUALATIN, OREGON



Cardno
 Shaping the Future

PORTLAND
 5445 SW WESTGATE DR, STE 100, PORTLAND, OR 97221
 TEL: (503) 416-2500 FAX: (503) 419-2500
 www.cardno.com



Color Legend

- 1 Concrete
Masonry Unit -
Natural
Color: Warm
Taupe
- 2 Concrete
Masonry Unit -
Natural
Color: Mountain
Brown
- 3 Brick - Adobe
Color: Warm
Taupe
Pattern: Random
Pattern
- 4 EIFS Cornice -
Color: Warm
Taupe
- 5 Standard 8 Edge Board - Anodized
Finish
- 6 Pre-Finished
EIFS Panels -
Color: Warm
Taupe
- 7 Brick - Field
Color: Mountain
Brown
Pattern: Random
Pattern
- 8 Brick - Field
Color: Mountain
Brown
Pattern: Random
Pattern
- 9 Metal Edge Cornice &
Panel -
Color: Warm
Taupe
- 10 Light Fabric - Dark
Color: Warm
Taupe
- 11 Concrete
Masonry Unit -
Natural
Color: Mountain
Brown

| | |
|--------------|--------------|
| PROJECT NO: | 2186310 |
| DATE: | 07/20/10 |
| DESIGNED BY: | IMULVANNY G2 |
| DRAWN BY: | XXX |
| CHECKED BY: | XXX |



SHEET PLAN
NYBERG RIVERS ARB
CENTERCAL PROPERTIES, LLC.
TUALATIN, OREGON



Cardno
 Shaping the Future
 PORTLAND
 5415 SW WESTGATE DR. STE 100, PORTLAND, OR 97221
 TEL: (503) 410-2500 FAX: (503) 410-2800
 www.cardno.com

SCALE:
 DIMENSIONS:
 A4.10

EXHIBIT 4
 AMENDED 04



AMERICAN SLATE
CHERRY BLOSSOM
18"x18" TILE VENEER
TOWER AND PLASTER

AMERICAN SLATE
GOLDEN MIGRATION
SPLIT FACE TYPE
COLOR: GREYS AND TANS
WAINSCOT

STUCCO
DUNNEDWARDS
COLOR: ARAJIAN RED
MAIN BUILDING FIELD

CORONADO STONE
CHRISTIED CREAM
WAINSCOT CAP

COLOR: BLACK
METAL CANOPIES

CORNICE
DUNNEDWARDS
COLOR: DARK CHOCOLATE



DATE: 04/10
DRAWN BY: [unintelligible]
CHECKED BY: [unintelligible]

Copyright © 2010 W.D. Partners, LLC


| | |
|--------------|------------------|
| PROJECT NO: | 218610 |
| DATE: | 08/10 |
| DESIGNED BY: | [unintelligible] |
| DRAWN BY: | [unintelligible] |
| CHECKED BY: | [unintelligible] |
| DATE: | 08/10 |

SHEET PLAN
NYBERG RIVERS ARB
 CENTERCAL PROPERTIES, LLC.
 TUALATIN, OREGON



Cardno
 Shaping the Future
 PORTLAND
 5415 SW WESTGATE DR, STE 100, PORTLAND, OR 97221
 TEL: (503) 419-2500 FAX: (503) 419-2600
 www.cardno.com


1 North Elevation
SCALE: 1/4" = 1'-0"



2 West Elevation
SCALE: 1/4" = 1'-0"



3 South Elevation
SCALE: 1/4" = 1'-0"



4 East Elevation
SCALE: 1/4" = 1'-0"




DANISH + ANTHONY LLP

SHEET PLAN
NYBERG RIVERS ARB
 CENTERCAL PROPERTIES, LLC.
 TUALATIN, OREGON

| | |
|--------------|----------|
| PROJECT NO: | 278018 |
| DATE: | 08/09/13 |
| DESIGNED BY: | 1023332 |
| DRAWN BY: | XXX |
| CHECKED BY: | XXX |

SEALING & CALIBER ELEVATIONS
 AB10











| LEGEND | TYPE OF BIKE EXIST |
|--------|---|
| | BIKE EXIST - 1103 SPACES BY NORTON |
| | BIKES TO BE INCLUDED WITH MACHINE RACKS - 1103 SPACES |
| | BIKE EXIST/NEW - 1103 SPACES |

| | REQUIRED | PROVIDED | MADE TYPE/AMT |
|------------------------|-------------------------|------------|------------------------------------|
| OVERALL BIKE RACKING | 147 SPACES | 515 SPACES | 604 TYPE A, 200 TYPE B, 200 TYPE C |
| COVERED BIKE RACKING | 74 SPACES (TYPE A ONLY) | 74 SPACES | 604 TYPE A, 200 TYPE B, 200 TYPE C |
| UNCOVERED BIKE RACKING | 73 SPACES | 77 SPACES | 604 TYPE A |

BIKE RACKING REQUIREMENTS: 1.25' space per bike rack, 6' of gross floor area, 50% coverage
 200% SEE: 1103 - 1103 - 1103 SEE 1103 - 1103 - 1103 (SEE 1103)



| VIEW | MATERIALS |
|------|------------|
| 1 | WOOD FRAME |
| 2 | ALUMINUM |
| 3 | STEEL |
| 4 | GLASS |
| 5 | ROOFING |
| 6 | PAINT |
| 7 | FINISHING |
| 8 | LANDSCAPE |
| 9 | LANDSCAPE |
| 10 | LANDSCAPE |
| 11 | LANDSCAPE |
| 12 | LANDSCAPE |
| 13 | LANDSCAPE |
| 14 | LANDSCAPE |
| 15 | LANDSCAPE |
| 16 | LANDSCAPE |
| 17 | LANDSCAPE |
| 18 | LANDSCAPE |
| 19 | LANDSCAPE |
| 20 | LANDSCAPE |
| 21 | LANDSCAPE |
| 22 | LANDSCAPE |
| 23 | LANDSCAPE |
| 24 | LANDSCAPE |
| 25 | LANDSCAPE |
| 26 | LANDSCAPE |
| 27 | LANDSCAPE |
| 28 | LANDSCAPE |
| 29 | LANDSCAPE |
| 30 | LANDSCAPE |
| 31 | LANDSCAPE |
| 32 | LANDSCAPE |
| 33 | LANDSCAPE |
| 34 | LANDSCAPE |
| 35 | LANDSCAPE |
| 36 | LANDSCAPE |
| 37 | LANDSCAPE |
| 38 | LANDSCAPE |
| 39 | LANDSCAPE |
| 40 | LANDSCAPE |
| 41 | LANDSCAPE |
| 42 | LANDSCAPE |
| 43 | LANDSCAPE |
| 44 | LANDSCAPE |
| 45 | LANDSCAPE |
| 46 | LANDSCAPE |
| 47 | LANDSCAPE |
| 48 | LANDSCAPE |
| 49 | LANDSCAPE |
| 50 | LANDSCAPE |

EXHIBIT A
 ALTERNATIVE 06



City of Tualatin

www.tualatinoregon.gov

January 27, 2014

RECOMMENDATION TO THE CITY COUNCIL

Amended Analysis and Findings for the January 27th Hearing

Case #: AR-13-07
Project: Nyberg Rivers Shopping Center
Location: 7455 - 7925 SW Nyberg Road (Tax Map 2S1 24 A, Tax Lots 1601, 1602, 1900, 2502, 2506, 2507, 2508, and 2700; Tax Map 2S1 24B, Tax Lots 2000, 2001, and 2100)
Applicant: Michael Kirk, CenterCal (503-968-8940)
Michael Cerbone, Cardno (503-419-2500)
Property Owners: Tuala Northwest, LLC, Dean McBale, George A. Gill, and ODOT

I. INTRODUCTION

Center Cal, LLC proposes developing an approximately 300,000 square foot shopping center on 31.91 acres of the old Kmart shopping center site. The shopping center includes a Cabela's, New Seasons, Michael's, Home Goods, LA Fitness, BJ's Restaurant, Barbara Johnson s, and a Wendy's. There are some additional tenant spots and pads that have yet to be determined. This includes the former Sylvan Learning Center, the former Curves, pad G-100, and pad H-100.

The redevelopment site is generally bounded by the Tualatin River to the north, SW Nyberg Street to the south, Interstate 5 to the east, and SW Martinazzi Avenue to the west.

The plan designations on the subject site are Office Commercial (CO), Center Commercial (CC), and High Density Residential (RH).

On August 26, 2013 the City Council voted unanimously to approve the Nyberg Rivers Master Plan and Conditional Use Permit with Resolution 5163-13 and 5164-13 respectively.

ARRANGEMENTS CAN BE MADE TO PROVIDE THESE MATERIALS IN ALTERNATIVE FORMATS, SUCH AS LARGE TYPE OR AUDIO RECORDING. PLEASE CONTACT THE COMMUNITY DEVELOPMENT DEPARTMENT AND ALLOW AS MUCH LEAD TIME AS POSSIBLE.

Exhibit 2

A public hearing before the Architectural Review Board was held on December 3, 2013 with a presentation by staff, a presentation by the applicant, an opportunity for proponents and opponents to make comment and for the public to ask questions. After the Architectural Review Board asked questions of the applicant and the staff the public hearing portion was closed. However, deliberations and a decision were delayed for two weeks after a request was made to leave the record open for seven days. The record closed at 5pm on December 10th. The hearing was continued on December 16th with the deliberations and a decision by the Architectural Review Board approving with conditions the application. A final order was issued on December 20th and a Request for Review was filed on January 3, 2014 by Steven L. Pfeiffer or Perkins Coie on behalf of the Zian limited partnership, in accordance with TDC 31.078.

Reason #1: Concerning the ability of the applicant to obtain ownership of the ODOT owned portion of the project.

Reason #2: Concerning the negative traffic impacts to appellant, Zian Properties.

The following analysis and findings have been amended to reflect amendments made in the final order and to address the issues raised in the Request for Review.

A neighborhood meeting was held by the applicant on August 8, 2013. One member of the public attended. Questions about timeline and procedure were answered. No concerns were raised. Staff mailed out notice of this ARB public hearing on November 5, 2013 and has received one letter of comment from surrounding property owners and the public. This comment is addressed in Section O of this staff report.

II. APPLICABLE STANDARDS

- A. City of Tualatin Resolution 5163-13, approving MP-13-01
- B. City of Tualatin Resolution 5164-13, approving CU-13-04
- C. City of Tualatin Development Code (TDC)
- D. City of Tualatin Community Plan
- E. City of Tualatin Municipal Code
- F. City of Tualatin Transportation System Plan (Public Facilities Report, Attachment **A**)
- G. City of Tualatin Public Works Construction Code (Public Facilities Report, Attachment **A**)
- H. Washington County Road Standards (Washington County Staff Report, Attachment **B**)
- I. Washington County Community Development Code (CDC) (Washington County Staff Report, Attachment **B**)
- J. Clean Water Services (CWS) Design and Construction Standards, Resolution and Order 07-20. (Clean Water Services Memorandum, Attachment **C**)
- K. Oregon Department of Transportation Highway Design Manual (ODOT Response to Local Land Use Notification, Attachment **D**)
- L. Oregon Department of Transportation Light Policy and Guidelines (ODOT Response to

- Local Land Use Notification, Attachment D)
- M. American Association of State Highway and Transportation Officials Illumination Standards (AASTHO) (ODOT Response to Local Land Use Notification, Attachment D)
- N. Oregon Revised Statutes (ORS) 276.071 (ODOT Response to Local Land Use Notification, Attachment D)
- O. Oregon Fire Code (OFC) (Tualatin Valley Fire & Rescue (TVF&R) Letter, Attachment E)
- P. Americans with Disabilities Act (ADA)

III. ARCHITECTURAL REVIEW RECOMMENDED FINDINGS

A. Previous Land Use Actions:

- Tax Lot: 2S1 124B 2100: Case files: AR-75-25; AR 76-01; AR-78-33; AR-85-09; AR-85-10; AR 91-33; AR-92-10; AR-96-21; AR-99-22; AR-00-11; AR-06-09 AR 09-10; CU-78-02; CU-80-04; CU-13-04; MP-13-01
- Tax Lot: 2S1 12A 2502: Case file: AR-83-15; CU-13-04; MP-13-01
- Tax Lot: 2S1 24A 2507: Case file: AR-73-10; CU-13-04
- Tax Lot: 2S1 24B 1602: Case files: AR-75-11; AR-78-28; AR-80-02; AR 84-03a; AR-85-10, AR-06-02; CU-13-04; MP-13-01
- Tax Lot: 2S1 24B 2000: Case file: AR-06-02

NOTE: *The above does not reflect the recent lot consolidations still under the recording and cartography process at Washington County.*

B. Other Permit Actions:

1. **Demolition permits for removal of the old site buildings including K-mart and Jiggles.**
2. **Resolution 5163-13**

A. Limit the number of drive-thru facilities in the Nyberg Rivers development to no more than four and design any new or re-located drive-thru facilities so the service windows and service aisles are screened from public streets. (Goal 1)

The site plan consists of four drive-thru businesses: Building C (US Bank), building B (multi-tenant), building E-100 (Banner Bank), and building F-100 (Wendy's). The site plan is consistent with this condition.

B. Master Plan area and Nyberg Rivers site shall design provide attractive and pedestrian-oriented features including accessways and pathways that will connect to existing and future residential development in the downtown area and specifically to the adjoining Heron's Landing

Apartments property. (Goal 2)

The site plan (C1.0) shows three connections to Heron's Landing, the apartment complex to the north. The site plan and architectural elevations also show accessways to downtown, outdoor café seating, pedestrian oriented landscaping, a water feature, and a sculpture. The water feature and sculpture are proposed south west of building 1040 (Cabela's). The site plan is consistent with this condition.

C. Recreational equipment, apparel and sports outfitting sales are prohibited in areas identified as public gathering, multi-function open plaza and plaza seating with fire pit on Attachment 1020 page 60 Building Frontage landscape plan. (Goal 4)

The "Conditional Use Exhibit" in Exhibit A of the application shows the allowed area for outdoor sales. Staff finds this allowed area is consistent with this condition.

D. A minimum of 12 feet of clear, unobstructed width for walkways or accessways through a plaza or along the building frontage between Building D1 and northeast corner of the public gathering, multi-function plaza seating with fire pit on Attachment 102D page 60 Building Frontage landscape plan. (Goal 4)

It appears that 12-feet of walkway including the gutters and shy area have been shown on the site and landscaping plans.

E. The Truck Route designations from Street "A" and Seneca Street are removed. (Goals 4 and 5)

The truck route designations for Street A and Seneca Street were removed.

F. The following transportation improvements are necessary for the Master Plan (Goal 5):

a. The Seneca Street extension to the Nyberg Rivers site with a signal at SW Martinazzi Avenue constructed to the standards of a Minor Collector Street. The time of construction will be determined through the public facilities decision process. The time of construction will be determined through the public facilities decision and is not anticipated or required to occur prior to removal of the Council Chambers building.

b. A westbound right turn lane on SW Nyberg Road.

c. Two southbound left turn lanes and a shared through/right turn lane from the site's access onto SW Nyberg Road.

d. Two inbound receiving lanes; and

e. The associated signal improvements at the main entrance.
Please refer to the Public Facilities Report (Attachment A).

G. The street cross-sections are necessary for the Master Plan and are approved with the following modifications (Goal 5):

a. Attachment 1020-Exhibit 8: Cross-section A-A:

1. *A 4 to 7-foot planter strip on the east side with curb, streetlights, and trees*
2. *A 4-foot planter on the west side with curb, streetlights adjacent to the travel lanes, and groundcover and shrubs with a 14-foot shared path with tree wells*
3. *Three 12-foot southbound travel lane*
4. *Two northbound 12-foot travel lanes*
5. *A center median consisting of an 18-inch concrete median, with striping on both sides for a total of 2.5-feet.*
6. *The road shall be a public road.*

Please refer to the Public Facilities Report (Attachment A).

b. Attachment 1020 - Exhibit C: Cross-section 8-8:

1. *A 12-foot pedestrian walkway on the north side with tree wells*
2. *Two 13-foot travel lanes. 12 foot travel lanes are acceptable.*
3. *A 6-foot planter on the south side*
4. *A 5-foot sidewalk on the south side*
5. *The road shall be a public road.*

Please refer to the Public Facilities Report (Attachment A).

c. Attachment 1020 - Exhibit O: Cross-section C-C:

1. *A 10-foot wide pedestrian walkway on the east side with tree wells*
2. *17.5-foot angled parking on both sides*
3. *Two 14-foot travel lanes*
4. *A 4-foot sloped landscape area on the west side*
5. *A 12-foot multi-use path on the west side*
6. *The road shall be a public road.*

Please refer to the Public Facilities Report (Attachment A).

d. Attachment 1020 - Exhibit E: Street "A": Cross section 0-0:

1. *A 12-foot multi-use path on the west side*
2. *A 4-foot planter strip with curb, streetlights, and trees*
3. *Two 12-foot travel lanes*
4. *A 6-foot bike lane on the east side*
5. *A 5-foot sidewalk on the east side*
6. *The pork chop at the intersection of Boones Ferry Road will be mountable for emergency vehicles*
7. *The road shall be a public road.*

Please refer to the Public Facilities Report (Attachment A).

e. City Parking Lot/Heron's Landing/Access to Street "A" and intersection with the greenway:

1. *The accessway shown is 40-feet wide*
2. *The multiuse path crossing is located south of the accessway*
3. *The crossing will include striping and bump-outs*
4. *The Heron's Landing Apartment access easement opposite the City staff parking lot access.*
5. *A crosswalk on Street "A" adjacent to SW Boones Ferry Road*
6. *The road shall be a public road.*

Please refer to the Public Facilities Report (Attachment A).

- f. Attachment 1020-Exhibit G: Nyberg Street between the entrance of the site and Martinazzi Avenue: Cross section F-F:**
- 1. A 4-6 foot planter strip with trees. This planter does not include curbs and streetlights, which are placed on the curb-tight sidewalk.**
 - 2. A 5-6-foot curb-tight sidewalk on the north side of Nyberg Road**
 - 3. A 6-foot bike lane**
 - 4. Two 11-foot westbound travel lanes**
 - 5. The north-south crosswalk across Nyberg Street will have a dedicated pedestrian/bicyclist-activated sequence**
 - 6. The road shall be a public road.**

Please refer to the Public Facilities Report (Attachment A).

- g. Attachment 1020 - Exhibit H: Nyberg Street between the entrance of the site and 1-5: Cross section G-G**
- 1. A minimum 12-feet for bike and pedestrian use on the north side of Nyberg Road**
 - 2. A 4-foot planter strip with curb, streetlights, and trees**
 - 3. A 15-foot westbound right-turn lane**
 - 4. No proposed changes to the existing west and east-bound turn lanes**
 - 5. A two foot landscape strip prior to a hand rail on top of a retaining wall, then a water quality pond**
 - 6. The road shall be a public road.**

Please refer to the Public Facilities Report (Attachment A).

- h. Seneca Street and the signal at SW Martinazzi Avenue**
- 1. Two 12-foot travel lanes**
 - 2. One 14-foot center turn lane**
 - 3. Two 6-foot bike lanes**
 - 4. Two 8-foot parking strips**
 - 5. Two 6-foot planter strips with curbs, streetlights, and street trees**
 - 6. Two 6-foot sidewalks**
 - 7. The road shall be a public road.**

Please refer to the Public Facilities Report (Attachment A).

- H. All shared pathways shall be open to the public. (Goal 5 and 6)**
Staff recommends a condition for an easement or 75-year land lease be executed over all pedestrian and bike accessways and pathways.

- I. New or relocated buildings on the Nyberg Rivers site shall have bicycle parking facilities. (Goal 5 and 6)**
Sheet A7.10 shows the bike parking plan for the subject site. Staff recommends a condition that bike parking facilities also be shown on the site plan and landscaping plans.

- J. The Master Plan area shall use vegetative treatment of stormwater where feasible. (Goal 8)**

Please refer to the Public Facilities Report (Attachment A).

K. No increase in the 100-Year Floodplain associated with improvements to public "Street A" and SW Seneca Street. (Goal 10)

Please refer to the Public Facilities Report (Attachment A).

L. There shall be additional window and architectural features that break up the building mass and add architectural interest on each of the four sides of Buildings 1040, G-100, H-100, J-100 and N-100. (Goal 11)

Staff recommends conditions that require the applicant to upgrade some elevations of some of the buildings. Building N-100 (LA Fitness) shows almost completely blank walls on the northeast and northwest elevations (sheet A4.10). Staff recommends that similar quantity and quality of architectural features be shown and constructed on the northeast and northwest elevations and that is shown on the southeast and southwest elevations. The northeast and northwest elevations of building N-100 will face the Tualatin River Greenway; therefore the architecture should be consistent with other architecture facing the public right-of-way.

Staff also recommends the west elevation of building 1040 (Cabela's) upgrade to the quality and quantity of architectural features shown on the other elevations of the same building. The west elevation will be the one that faces the main pedestrian path leading to the Tualatin River Greenway, proposed sculpture, and fountain. Therefore staff recommends that the architecture be of the same quantity and quality that will face I-5, the front parking lot, and the rear of the building.

M. Building 1040 shall have variations in building height, additional gabled roof feature, canopy feature, entry feature, dimensional wall feature such as columns or pilaster and projected entries, show larger window and entry areas and show diversity in the exterior wall design and material on all four sides of the building. (Goal 11)

As stated above, staff recommends the applicant upgrade the west elevation of the building to include the same quantity and quality of architectural features on the other elevations.

N. The loading and service facilities for the existing Michaels (Building 02) and new Buildings 1005, 1010 and 1040 shall provide adequate visual and noise buffering for the benefit of nearby public areas and residential areas. (Goal 11)

Staff recommends a condition that Michael's build a screen wall to cover and buffer the back loading dock area.

Condition AR-3.A.8 was inserted to respond to the ARB's December 3rd concerns that the architecture on the north side of Michaels, New Seasons, and Home Goods would not create a pedestrian friendly environment for the Tualatin River Greenway. Staff also added this condition to ensure that the north side architecture met N of Resolution 5163-13. Condition N requires the applicant to add adequate visual buffering to the north side of Michaels, New Seasons, and Home Goods. At the December 16th Hearing the ARB decided to revise this condition to make it more flexible for the developer.

- O. If oversized vehicle parking stalls occupy or replace standard parking stalls proposed in the Master Plan, the total number of parking stalls and the dimensions shall be adjusted accordingly to reflect the revision. (Goal 11)**

The applicant has not proposed any oversize parking stalls.

- P. Trees planted in "diamond planters" shall achieve a growth that is a minimum of 66 % (2/3) of the 30 ft. mature tree height standard in TDC 73.360(7)(a-e) within 5 years of planting. If the trees do not meet the performance requirement, then Applicant, its successors and assigns, must remedy the failure. Such remedy shall be up to and including rebuilding and expanding the planting area. (Goal 11)**

Staff recommends a condition that the applicant provide evidence and/or documentation that the trees proposed for the diamond planters will meet Condition P of Resolution 5163-13.

- Q. Trees planted in the "diamond planters" shall be monitored annually. The applicant, its successors or assigns, shall submit a report from a certified arborist that documents tree height, health of canopy, and size of trunk by November 1 of each year after planting. (Goal 11)**

Staff will look for compliance with this Condition of Approval in the future. Staff recommends that the applicant be conditioned to provide an arborist's report that the trees in the diamond planters have been planted properly and according to Condition Q of Resolution 5163-13.

- R. Prior to development, a tree maintenance plan shall be established for all trees in Master Plan area where development occurs. (Goal 11)**

Staff recommends a condition that this tree maintenance plan be submitted prior to certificate of occupancy for any buildings on the subject site.

- S. All trees on the former Nyberg House site (tax lot 2502), adjacent to Building C (Tax Lot 1602) and in the vicinity of the proposed Building N-100 shall be preserved and retained as reasonably feasible. Where tree preservation is not reasonably feasible, 3" caliper or 10-12 foot replacement tree plantings of a similar character shall be planted in the vicinity of where trees were removed on Tax Lot 2502. (Goal 11)**

Staff finds that the preservation of trees on tax lot 2502 is not feasible due to the necessary grading and construction activities associated with building buildings and a new parking lot. Therefore, the applicant must supply and demarcate the mitigation trees spelled out in this condition. All of the plantings on the landscape plan are shown at either 2-inch caliper or 8-feet high. Staff recommends a condition that the applicant revises the landscaping plan to show the replacement trees at the proper size prior to issuance of a building permit for construction of any building. Staff also recommends the applicant prepare an extra landscaping plan sheet showing tax lot 2502, what trees are proposed to be removed, and each associated replacement planting.

T. *Plant 15 additional Douglas Fir, Western Red Cedar, or other fall-maturing conifer tree plantings in the landscape plan for location on the site's eastern frontage along I-5. (Goal 1)*

Staff recommends a condition that the applicant show or demarcate where the additional 15 trees have been planted pursuant to Condition T of Resolution 5163-13. Staff recommends an additional landscaping sheet in the revised landscaping plans that show specific compliance with Condition S&T of Resolution 5163-13.

U. *The following items requested for approval are not within the purview of the Master Plan process and are not approved with the Master Plan decision:*

- 1. *Approve and permit retail uses within the Office Commercial (CO) designated portions of the property.***
- 2. *Approve and permit outdoor sales within the Central Commercial designated portion of the property.***
- 3. *Approve right-of-way vacation of the Oregon Department of Transportation property along Nyberg Road.***
- 4. *Approval of any modification of land uses.***
- 5. *Acceptance by the City of any easements or other land transactions for pedestrian or transportation facilities.***
- 6. *A decision on whether to adopt a separate review procedure for the Master Plan***
- 7. *Approve the Nyberg Rivers alternate sign program.***

Condition U.1., U.2., and U.4. were approved through case file CU-13-04. U3 is managed through ODOT. The rest of Condition U will be performed subsequent to this land use decision.

3. Resolution 5164-13:

Recreational equipment, apparel, and sports outfitting sales are prohibited in areas identified as public gathering, multi-function open plaza and plaza seating with fire pit in the approved Master Plan Exhibit Q1 Building Frontage landscape plan.

The applicant has shown compliance with this condition per Exhibit A "Conditional Use Exhibit" of this AR-13-07 application

C. Tualatin Community Plan:

The Community Plan is implemented by the Development Code. When built in conformance with the conditions of approval, the project will be in compliance with the Community Plan.

D. Planning Districts and Adjacent Land Uses:

The proposed Nyberg Rivers redevelopment project will be located on the existing Mercury Development/ (former) Kmart/Schatz Furniture shopping center with a portion of the undeveloped north tax lot 2700, two parcels (2508 & 2502) where the Jiggles restaurant is located and a segment of Oregon Department of Transportation Interstate I-5 Exit 289/Nyberg Street interchange property.

The properties are in the Central Commercial (CC) Planning District, the Commercial Office (CO) Planning District and a small portion of the High Density Residential (RH) Planning District.

The Nyberg Rivers site encompasses Central Urban Renewal District Blocks 1, 2, 3 and 4 (segment). SW Seneca Street improvement shown on Block 5.

The Nyberg Rivers site is at the northwest corner of the I-5 Freeway Exit 289/Nyberg interchange, has extensive frontage adjoining the I-5 Freeway property and includes Tualatin River Greenway frontage where public access and natural area enhancements are identified. The subject site is on the eastern edge of downtown Tualatin. To the west, the City Hall/Library campus directly abuts the site and the Lake of the Commons is nearby. The Fred Meyer Shopping Center and the recently installed Gateway Feature are located south of the site. SW Nyberg Street and SW Tualatin-Sherwood Road adjoin the site to the south and will provide the primary access to the development. SW Martinazzi Avenue is west of the site and SW Boones Ferry Road is at the northwest corner. Both of these streets are intended to provide secondary access to the development.

E. Setback Requirements:

Chapter 43: *High Density Residential Planning District (RH)*

43.070 Setback Requirements for Permitted Uses.

No building is proposed on tax lot 2S1 24B 1601. This tax lot is the only parcel is the RH plan designation for the subject site.

Chapter 50: *Office Commercial Planning District (CO)*

50.060 Setback Requirements.

There is one building proposed on tax lot 2700. Building N-100 (LA Fitness) is 80-feet from the east property line. This is the closest setback for building N-100 and exceeds the minimum required side yard setback of 0-15 feet.

Chapter 53: *Central Commercial Planning District (CC)*

53.080 Setback Requirements

(1) Front yard. Except as provided by TDC 53.090(2)(a), zero to 20 feet, as determined through the Architectural Review process.

(2) Side yard. Except as provided by TDC 53.090(2)(a), zero to 20 feet, as determined through the Architectural Review process.

(3) Rear yard. Zero to 15 feet, as determined through the Architectural Review process.

(4) Corner lot yards. Zero to 20 feet for a sufficient distance to provide adequate sight distance for vehicular and pedestrian traffic at an intersection, as determined through the Architectural Review process.

Building 1040 (Cabela's) closest rear yard setback is 23-feet. A minimum 0-15 setback is required. Therefore, a 23-foot setback meets the standards of this

Section. Building 1010 (Home Goods), 1030 (unnamed restaurant), 1005 (New Seasons), D-110 (Michaels), D-130 (the former Curves), D125 (the former Sylvan Learning Center), and D-120 (Barbara Johnsons) are all set further back from all property lines than 23-feet as shown on C1.0 of the plan set. Therefore, this conglomerate of attached tenants meets the minimum setback standards of this Section.

Building J-100 (BJ's Brewhouse) is set back 9.77-feet from the southeast property line and 34-feet from the southern property line. Buildings H-100 and G-100 are not a part of this Architectural Review process, but are shown to be 6.63-feet and 9.45-feet from the southeast property line as shown on plan set sheet C1.2. Building F-100 (Wendy's) is shown 20.93-feet from the southern property line. Building E-100 (Banner Bank) is shown 30-feet from the southern property line. All of these figures exceed the minimum front and side yard setbacks of 0-20-feet and 0-15-feet respectively.

F. Structure Height:

Chapter 43: *High Density Residential Planning District (RH)*

43.100 Structure Height.

No building is proposed on tax lot 2S1 24B 1601, this is the only parcel in the RH plan designation for the subject site.

Chapter 50: *Office Commercial Planning District (CO)*

50.070 Structure Height.

The maximum height in this district is 45-feet. Building N-100 (LA Fitness) has been labeled that the top of the building is 45-feet. However, the elevations appear to measure to 46.5-feet on sheet A4.10 of the plan set. Staff recommends a condition to amend this elevation to meet a 45-foot building height prior to issuance of a building permit.

The maximum height in this district is 45-feet. Building 1040 (Cabela's) highest ridge line is 48-feet. The eve is 29-feet high. The average height between the ridge line and the eve is 38.5-feet, which meets the standard for maximum height in this district.

Chapter 53: *Central Commercial Planning District (CC)*

53.090 Structure Height.

The maximum height in this district is 45-feet. Building 1040 (Cabela's) highest ridge line is 48-feet. The eve is 29-feet high. The average height between the ridge line and the eve is 38.5-feet, which meets the standard for maximum height in this district.

Plan sheet A2.10a shows the highest point of the conglomeration of buildings (D-120 (Barbara Johnsons), D-125 (former Sylvan's Learning Center), D-130 (former Curves), D-110 (Michael's), 1005 (New Seasons), 1010 (Home Goods), and 1030 (unnamed restaurant) at 52-feet inclusive of architectural features. Excluding the spire, the cupola tower is proposed to be 48-feet high.

The spire is not measureable on elevation sheets A2.11 and A2.13 as it runs off the edge. Staff recommends a condition to revise this feature to meet the standards of this Section. The rest of the buildings in the above mentioned attached tenancy fall far below the maximum allowed building height.

G. Site Planning:

Chapter 73: Community Design Standards

73.050 Criteria and Standards

Section 73.050(1)(a) The proposed site development, including the site plan, architecture, landscaping and graphic design, conforms to the standards of this and other applicable City ordinances, insofar as the location, height, appearance, etc. of the proposed development are involved.

This project has been reviewed based on TDC standards and other applicable general ordinances of the City of Tualatin. The proposed location, height, appearance, etc., of the development comply with the TDC and other applicable City ordinances as identified in this report and with applicable conditions of approval will be in compliance.

73.150 Standards

73.150(10) Create opportunities for, or areas of, visual and aesthetic interest for occupants and visitors to the site.

Condition AR-3.A.5 was inserted to add several improvements to the architecture of Cabela's. This proposed condition was amended by staff to respond to the ARB's concerns that the architecture on Cabela's was lacking interest, relief, massing breaks, and features previously shown on other elevation submittals for Cabela's. Staff also anticipated that the new December 9th submittal for Cabela's architecture would not be approved by the ARB and did not meet Condition M of Resolution 5163-13. Therefore, staff proposed a conglomeration of best architectural features from the architectural submittals over the last six months for Cabela's.

Condition AR-3.A.9 was added to anticipate the ARB's concerns over creating a viable pedestrian experience through the main pedestrian plaza pursuant to TDC 73.150(10). The purpose of AR-3.A.9 is to add additional architectural features to create a positive pedestrian experience for the main pedestrian plaza area.

Condition AR-3.A.10 was added to anticipate the ARB's December 3rd concerns over creating a visually interesting focal point for the development pursuant to TDC 73.150(10). Condition AR-3.A.10's purpose is to improve the aesthetics of Home Goods as focal point for the main entrance to the development.

Condition AR-3.A.12 was added to respond to and anticipate the ARB's concerns over the aesthetics of retaining walls pursuant to TDC 73.150(10). Condition AR-3.A.12 adds visual and aesthetic interest pursuant to TDC 73.150(10) and ensures retaining walls are permitted on ODOT land through ODOT. After the Oregon Department of Transportation (ODOT) reviewed the December 16th Recommendation and Staff Report, comments were submitted

that request an addition to the condition. ODOT wants make sure retaining walls on their property are reviewed and approved through ODOT in coordination with the City.

Condition AR-3.F.18 was added to buffer and screen the dog kennels from other animals and people on the adjacent Tualatin River Greenway. Any potential issues between the future Tualatin River Greenway and the proposed dog kennels behind Cabela's will be mitigated through the conditioned screening that matches the building.

73.160 Standards.

73.160(1)(a) For commercial, public and semi-public uses:

(i) a walkway shall be provided between the main entrance to the building and any abutting public right-of-way of an arterial or collector street where a transit stop is designated or provided. The walkway shall be a minimum of 6 feet wide and shall be constructed to meet the requirements for sidewalks in the Public Works Construction Code.

The only transit line that abuts the subject site is on SW Martinazzi Avenue, the west property line of tax lot 2S1 24B 2000. Building A is the only building on tax lot 2000. It is existing and currently has a sidewalk that connects out to the public sidewalk on SW Martinazzi Avenue, giving access to existing transit stops.

(ii) walkways shall be provided between the main building entrances and other on-site buildings and accessways. The walkways shall be a minimum of 6 feet wide and shall be paved with asphalt or concrete.

There is a 12-foot wide sidewalk with tree wells that runs between building D-130 (former Curves), south to D-120 (Barbara Johnsons), and then east to the east side of building 1040 (Cabela's). There is a proposed crosswalk and sidewalk south of building N-100 (LA Fitness) to building J-100 (BJ's Brewhouse), then south to building H-100 and north to building 1040 (Cabela's). There is 5-foot sidewalk/crosswalk shown between building H-100 and G-100, and F-100. From F-100 a third sidewalk/crosswalk goes north back up to building 1040 (Cabela's) and south again to building E-100 (Banner Bank). All of these sidewalks and crosswalks have a 5-foot width except for the aforementioned 12-foot wide sidewalk. This code section requires these accessways, crosswalks, and sidewalks to be at least a 6-foot width. Staff recommends the applicant be conditioned to revise plans to meet the standards of this section.

The parking lot for the west side of the subject site is being partially redesigned to accommodate more sidewalks/crosswalks. There are four new sidewalks/crosswalks coming south from buildings D-120 (Barbara Johnsons), D-110 (Michaels), and 1005 (New Seasons). One of these sidewalk/crosswalks connect to existing building B and A, one connects to C-100 (US Bank). The only places where crosswalks or sidewalks have been omitted are when placing a sidewalk/crosswalk would force pedestrians into a drive-thru aisle. Staff finds that this layout meets this subsection of the TDC.

Condition AR-3.F.11 was amended to make it clear that only existing sidewalks may be 5-feet wide. AR-3.F.11's purpose is to ensure that all new sidewalks are built 6-feet wide per TDC 73.160(1)(a)(ii).

(iii) walkways through parking areas, drive aisles, and loading areas shall be visibly raised and of a different appearance than the adjacent paved vehicular areas.

The applicant has proposed some crosswalks with different materials. For example the crosswalks in front of D-120 (Barbara Johnsons) all the way east to building 1040 (Cabela's) are shown on sheet C1.0 and L1.2 to be constructed of a paver and/or a brick pattern. Staff recommends that the applicant be conditioned to this proposal. For the rest of the crosswalks the applicant proposes painted crosswalks. Staff finds that paint alone does not meet the standards of this section for crosswalks to be raised and of different material than the rest of the pavement. Therefore, staff has included in the recommended Conditions of Approval for these crosswalk stripes to be created of raised, different material such as thermal plastic, raised and scored colored concrete, or raised brick or stone pavers. Staff notes that Nyberg Woods's crosswalks were created with scored concrete. Staff thinks that these crosswalks are not highly visible. Therefore, staff has recommended that Nyberg River's crosswalk be raised per TDC and colored a significantly different color than the asphalt to be readily apparent to motorists.

(iv) accessways shall be provided as a connection from the development's internal bikeways and walkways to all of the following locations that apply: abutting arterial or collector streets upon which transit stops or bike lanes are provided or designated; abutting undeveloped residential or commercial areas; adjacent undeveloped sites where an agreement to provide an accessway connection exists; and to abutting publicly-owned land intended for general public use, including schools.

There is currently a bike lane on SW Nyberg Street that will be extended as conditioned by Washington County and the Oregon Department of Transportation through this Decision. The applicant has provided a main pedestrian entrance off SW Nyberg Street that includes a shared sidewalk and bikeway. Staff finds that this connection coupled with the internal connectively already described in this staff report meets the standard for connectivity to arterials with bike lanes as in SW Nyberg Street.

The subject site also contains a proposed greenway along the Tualatin River. This greenway is considered a walkway and a bikeway. The applicant shows three connections to this greenway: one northwest of building D-130 (former Curves), a second north of building 1010 (Home Goods), and a third northeast of building 1040 (Cabela's) as shown on plan sheet C1.0.

Condition AR-3.A.11 was added to condition the applicant to their proposed light fixtures shown on page 5.4 of the December 9th submittal booklet.

(v) Fences or gates which prevent pedestrian and bike access shall not be allowed at the entrance to or exit from any accessway.

To ensure the requirement of 73.160(1)(a)(v) is met, fences or gates which prevent pedestrian and bike access shall not be allowed at the entrance to or exit from any accessway.

(vi) Bikeways shall be provided which link building entrances and bike facilities on the site with adjoining public right-of-way and accessways.

The applicant has provided a main pedestrian and bike entrance off SW Nyberg Street that includes a shared sidewalk and bikeway. Staff finds that this connection coupled with the internal connectively already described in this staff report and shown on sheet C1.0 of the plan set meets the standard for bikeways that are linked to building entrances, right-of-ways, and accessways.

(vii) Outdoor Recreation Access Routes shall be provided between the development's walkway and bikeway circulation system and parks, bikeways and greenways where a bike or pedestrian path is designated.

There are three pedestrian and bike proposed connections to the Tualatin River Greenway as discussed in Section 73.160(1)(a)(iv) of this staff report. Staff finds that the type and number of connection proposed as shown on plan set sheet C1.0 is adequate to meet this standard.

73.160(1)(d) Accessways shall be constructed of Portland Concrete Cement and be paved a minimum of 8 feet wide.

The applicant has proposed two 14-foot wide accessways and one 6-foot wide accessway from the subject site to the Tualatin River Greenway. The applicant has been conditioned to widen the 6-foot accessway to 8-feet and construct all three with Portland Concrete Cement.

Condition AR-3.F.3 was amended to make it clear that the accessway in question was not in the sensitive area, but abutting the sensitive area.

73.160(2)(a) Drive-up uses shall provide a minimum stacking area clear of the public right-of-way and parking lot aisles from the window serving the vehicles as follows:

(i) Banks--each lane shall provide a minimum capacity for five automobiles.

Only building E-100 (Banner Bank) proposes a lot reconfiguration. E-100 shows stacking in excess of five vehicles. The other banks on the subject site are existing and lot reconfiguration is not proposed.

(ii) Restaurants--each lane shall provide a minimum capacity for eight automobiles.

The only proposed drive-thru restaurant is building F-100 (Wendy's). Building F-100 is showing a stacking capacity of 14 vehicles.

(iii) Other Drive-Up Uses--each lane shall provide a minimum capacity for two to eight automobiles, as determined through the architectural review process.

The only other drive-thru is the existing building C (US Bank). Building C shows stacking capacity of at least two lanes of six vehicles.

(iv) For purposes of this Section, an automobile shall be considered no less than twenty feet in length. The width and turning radius of drive-up aisles shall be approved through the architectural review process.

The vehicles shown on the plan are 18-feet in length. However, all proposed drive-thru uses are showing an excess of vehicle stacking. Therefore, this criterion is met.

(b) Parking maneuvers shall not occur in the stacking area. The stacking area shall not interfere with safe and efficient access to other parking areas on the property.

(c) Locate drive-up aisles and windows a minimum of 50 feet from residential planning districts to avoid adverse impacts. A wall or other visual or acoustic may be required through the architectural review process.

The stacking areas proposed are defined away from parking areas for the stacking length required by the TDC. Drive-up aisles are located in excess of 50-feet from residentially zoned properties.

73.160(3)(a) Locate windows and provide lighting in a manner which enables tenants, employees and police to watch over pedestrian, parking and loading areas.

Buildings J-100, F-100, and E-100 are proposed with windows on all sides.

Therefore, there is viewing from within the building to the parking lots.

Buildings D-130, D-125, D-120, D-110-, 1005, 1010, 1040, and N-100 all show windows on the front façade. This will facilitate views out onto the parking lots adjacent to the front of this second group of buildings. Lighting is provided 360-degrees for all proposed buildings. This will aide in parking lot safety in the presence and absence of windows. Staff finds that the proposal meets the criteria of this subsection.

Condition AR-3.D.3 was added to condition the applicant to the LED lighting poles proposed at the December 3rd Hearing.

73.160(3)(b) In commercial, public and semi-public development and where possible in industrial development, locate windows and provide lighting in a manner which enables surveillance of interior activity from the public right-of-way.

SW Nyberg Street allows views into all proposed buildings along its right-of-way on the subject site. Building A is existing and its interior is viewable from SW Nyberg Street. SW Seneca Street is proposed adjacent to Building A and C which already exist. Staff finds that these criteria are met by the proposal.

73.160(3)(c) Locate, orient and select on-site lighting to facilitate surveillance of on-site activities from the public right-of-way.

As stated in Section 73.160(3)(a) of this staff report, lighting is proposed 360-degrees from all proposed buildings on the subject site. The light plan demonstrates in the photometric plans (E-series) that illumination is proposed over all parking, landscaping, and drive aisle areas on the subject site.

73.160(3)(d) Provide an identification system which clearly locates buildings and their entries for patrons and emergency services.

Staff recommends a condition to provide a sign plan that meets emergency service signage requirements prior to building permit. Staff recommends a condition to provide sign permit package separately from this Architectural Review process that properly identifies buildings and their entries for the public.

73.160(3)(e) Shrubs in parking areas must not exceed 30 inches in height. Tree canopies must not extend below 8 feet measured from grade.

The applicant has been conditioned to provide a note on the landscaping plans that all shrubs in parking areas must not exceed 30-inches in height and that all trees must not extend below 8-feet measured from grade.

73.160(4)(a) On and above grade electrical and mechanical equipment such as transformers, heat pumps and air conditioners shall be screened with sight obscuring fences, walls or landscaping.

The applicant has been conditioned to show all mechanical equipment and to provide screening for all such equipment.

At the December 16th Hearing staff brought up that the trash compacter was not shown to be screened on the elevations. The applicant however, did propose a screen wall on the November 12th site plan submittal. Therefore staff recommended that the applicant be conditioned to build a screen wall around the trash compacter that matches the conditioned loading dock screen wall to meet TDC 73.160(4)(a)

73.160(4)(b) Outdoor storage, excluding mixed solid waste and source separated recyclables storage areas listed under TDC 73.227, shall be screened with a sight obscuring fence, wall, berm or dense evergreen landscaping.

No outdoor storage is proposed. Outdoor sales are proposed and have been approved through Conditional Use Permit CU-13-04.

73.160(5) The Federal Americans with Disabilities Act (ADA) applies to development in the City of Tualatin. Although TDC, Chapter 73 does not include the Oregon Structural Specialty Code's (OSSC) accessibility standards as requirements to be reviewed during the Architectural Review process, compliance with the OSSC is a requirement at the Building Permit step. It is strongly recommended all materials submitted for Architectural Review show compliance with OSSC.

Accessibility standards shall be in compliance with the OSSC, which will be reviewed at the Building Permit step. Staff recommends that the applicant is conditioned to construct the subject site to ADA standards.

H. Structure Design:

Section 73.050(1)(b) The proposed design of the development is compatible with the design of other developments in the same general vicinity.

Section 73.050(1)(c) The location, design, size, color and material of the exterior of all structures are compatible with the proposed development and appropriate to the design character of other development in the same vicinity.

The proposal shows compatible architectures to the adjacent Nyberg Woods shopping center across I-5 and to the newly renovated Fred Meyer across SW Nyberg Street. The proposed architecture complements the City offices abutting the subject site to the west. The design of the site is similar to other shopping centers nearby.

73.100(2) All building exterior improvements approved through the Architectural Review Process shall be continually maintained including necessary painting and repair so as to remain substantially similar to original approval through the Architectural Review Process, unless subsequently altered with Community Development Director approval.

A condition stating this exact subsection is included in the recommended Conditions of Approval.

73.150 (18) Screen elements such as mechanical and electrical equipment, above ground sewer or water pump stations, pressure reading stations and water reservoirs from view.

Staff recommends a condition that the applicant submit revised architectural elevations showing a roof top equipment being screened.

73.210(7) Select building materials which contribute to the project's identity, form and function, as well as to the surrounding environment.

Condition AR-3.A.5 was inserted to add several improvements to the architecture of Cabela's. This proposed condition was amended by staff to respond to the ARB's concerns that the architecture on Cabela's was lacking interest, relief, massing breaks, and features previously shown on other elevation submittals for Cabela's. Staff also anticipated that the new December 9th submittal for Cabela's architecture would not be approved by the ARB and did not meet Condition M of Resolution 5163-13. Therefore, staff proposed a conglomeration of best architectural features from the architectural submittals over the last six months for Cabela's

I. Mixed Solid Waste and Source Separated Recyclables Storage Areas for New or Expanded Multi-Unit Residential, Commercial, Industrial, Public and Semi-Public Development:

73.227(2)(a) The size and location of the storage area(s) shall be indicated on the site plan. Compliance with the requirements set forth below are reviewed through the Architectural Review process.

The recycling and trash receptacle areas are shown for the new portions of the subject site, except for building E-100 (Banner Bank) and N-100 (LA Fitness). Staff has included in the recommended Conditions of Approval to show the refuse plan and any necessary revised site plan for these buildings. In addition building A's parking lot is proposed to be reconfigured. It appears existing landscaping is covering what used to be a trash dumpster enclosure. Staff recommends conditioning the applicant to prune this landscaped area so the trash enclosure can be used once again. Currently, the north lot of Building A is filled with several unscreened trash receptacles. Staff also recommends that the applicant is conditioned to show how the current amount of trash receptacles on-site can be screened in a revised site and landscaping plan.

73.227(2)(a)(v) Commercial, industrial, public and semi-public developments shall provide a minimum storage area of 10 square feet plus: office - 4 square feet/1000 square feet gross leasable area (GLA); Retail - 10 square feet/1000 square feet GLA; Wholesale/Warehouse/Manufacturing - 6 square feet/1000 square feet GLA; Educational and institutional - 4 square feet/1000 square feet GLA; and other - 4 square feet/1000 square feet GLA.

There are proposed trash storage areas on plan set sheet A7.10. The application does not show how this section is met. Staff recommends the applicant be conditioned to show how they meet the storage requirements of this section. There are also several buildings where no outdoor or indoor refuse and recycling storage areas are shown. Staff recommends that the applicant be conditioned to refine the site plan to show refuse and recycling storage areas for building A, B, C, E-100, D-130, D-125, D-120, and D-110. This includes the existing recycling and refuse storage areas that exist, but are not shown on the site plan. In addition building 1005 shows a trash compactor and bicycle parking in the same area. This conflict needs to be worked out through a revised site and refuse plan.

73.227(6)(a)(i) To encourage its use, the storage area for source separated recyclables

may be co-located with the storage area for mixed solid waste.

Staff recommends conditioning the applicant to show where recycling will be located on a revised trash enclosure and site plan to meet the standards of this section.

(ii) Indoor and outdoor storage areas shall comply with Building and Fire Code requirements.

The storage areas are required to meet this standard.

(iii) Storage area space requirements can be satisfied with a single location or multiple locations, and can combine both interior and exterior locations.

As stated previously, the revised recycling and refuse plan needs to show the minimum required storage areas for the buildings not yet included in the recycling and refuse storage plan.

(iv) Exterior storage areas shall not be located within a required front yard setback or in a yard adjacent to a public or private street.

Locations of proposed exterior storage areas are not in required setbacks.

(v) Exterior storage areas shall be located in central and visible locations on the site to enhance security for users.

All proposed storage areas are located in central areas or accessible internally from the building. This requirement is met for what has been currently proposed.

(v) Exterior storage areas can be located in a parking area, if the proposed use provides parking spaces required through the Architectural Review process. Storage areas shall be appropriately screened according to 73.227(6)(b)(iii).

The proposed exterior storage areas are shown to be screened with a decorative wall and bike racks. The trash compactors are shown to be screen with a wall on the north side of the subject site.

(vi) Storage areas shall be accessible for collection vehicles and located so that the storage area will not obstruct pedestrian or vehicle traffic movement on site or on public streets adjacent to the site.

The proposed exterior storage areas meet this requirement.

73.227(6)(b)(i) The dimensions of the storage area shall accommodate containers consistent with current methods of local collection at the time of Architectural Review approval.

The Hauler (Republic) indicates the proposed exterior storage areas can meet this requirement. The letter is provided in Exhibit I of the application.

(ii) Storage containers shall meet Fire Code standards and be made and covered with waterproof materials or situated in a covered area.

The proposed storage area facility will be required to meet this standard.

(iii) Exterior storage areas shall be enclosed by a sight obscuring fence or wall at least 6 feet in height. In multi-family, commercial, public and semi-public developments evergreen plants shall be placed around the enclosure walls, excluding the gate or

entrance openings. Gate openings for haulers shall be a minimum of 10 feet wide and shall be capable of being secured in a closed and open position. A separate pedestrian access shall also be provided in multi-family, commercial, public and semi-public developments.

The proposed exterior storage areas are proposed to be enclosed with CMU walls. The walls have an opening in excess of 10-feet wide, and have a separate pedestrian access. Staff recommends the applicant be conditioned to show that the plants around the trash enclosure walls will be evergreen exclusive of the bike racks.

Condition AR-3.F.19 was added to improve the aesthetics north of Building A to meet TDC 73.227(6)(b)(iii).

(iv) Exterior storage areas shall have either a concrete or asphalt floor surface.
The proposed exterior storage/compactor areas meet this requirement.

(v) Storage areas and containers shall be clearly labeled to indicate the type of material accepted.

The proposed storage areas will have containers for different types of materials. Metro provides that different materials are accepted in different colors of receptacles. Staff finds that this color coding method already provided by Metro trash haulers meets this requirement.

73.227(6)(c)(i) Access to storage areas can be limited for security reasons. However, the storage areas shall be accessible to users at convenient times of the day, and to hauler personnel on the day and approximate time they are scheduled to provide hauler service.

The hauler indicates that suitable access will be available and will meet this requirement.

(ii) Storage areas shall be designed to be easily accessible to hauler trucks and equipment, considering paving, grade, gate clearance and vehicle access. A minimum of 10 feet horizontal clearance and 8 feet vertical clearance is required if the storage area is covered.

The proposed (unroofed) exterior storage areas are designed for the hauler truck to approach the storage containers on a paved service aisle and directly toward opening. The hauler agrees to the storage area locations and facility dimensions. The proposed storage area design requirements are met.

(iii) Storage areas shall be accessible to collection vehicles without requiring backing out of a driveway onto a public street. If only a single access point is available to the storage area, adequate turning radius shall be provided to allow vehicles to safely exit the site in a forward motion.

The proposed exterior storage area meets this requirement.

J. Landscaping:

73.020 (1) The City Council finds that excessive uniformity, dissimilarity, inappropriateness, or poor quality of design in the exterior appearance of structures and the lack of proper attention to site development and landscaping, in the business,

commercial, industrial, and certain residential areas of the City hinders the harmonious development of the City; impairs the desirability of residence, investment or occupation in the City; limits the opportunity to attain the optimum use and value of land and improvements; adversely affects the stability and value of property; produces degeneration of property in such areas with attendant deterioration of conditions affecting the peace, health and welfare of the City; and destroys a proper relationship between the taxable value of property and the cost of municipal services therefore.

(2) The City Council declares that the purposes and objectives of community design standards are to:

(a) Encourage originality, flexibility and innovation in site planning and development, including the architecture, landscaping and graphic design of development.

(b) Discourage monotonous, drab, unsightly, dreary and inharmonious development.

(c) Promote the City's natural beauty and visual character and charm by ensuring that structures and other improvements are properly related to their sites, and to surrounding sites and structures, with due regard to the aesthetic qualities of the natural terrain, natural environment, and landscaping. Exterior appearances of structures and other improvements should enhance these qualities.

(d) Encourage site planning and development to incorporate bikeways, pedestrian facilities, greenways, wetlands, and other natural features of the environment and provide incentives for dedication of access easements and property to the public through shift of residential density, system development charge credits, landscaping credits and setback allowances.

(e) Protect and enhance the City's appeal to tourists and visitors and thus support and stimulate business and industry and promote the desirability of investment and occupancy in business, commercial and industrial properties.

(f) Stabilize and improve property values and prevent blighted areas and thus increase tax revenues.

(g) Achieve the beneficial influence of pleasant environments for living and working on behavioral patterns and thus decrease the cost of governmental services.

(h) Foster civic pride and community spirit so as to improve the quality and quantity of citizen participation in local government and in community growth, change and improvement.

(i) Sustain the comfort, health, safety, tranquility and contentment of residents and attract new residents by reason of the City's favorable environment and thus pro-mote and protect the peace, health and welfare of the City.

(j) Determine the appropriate yard setbacks, building heights, minimum lot sizes when authorized to do so by City ordinance. [Ord. 862-92, §51, 3/23/92; Ord. 864-92, §11, 4/13/92; Ord. 933-94, §45, 11/28/94]

Staff recommends the following conditions be placed on the applicant to meet the standards of this section: six more vine maples or other similar small tree shall be added to the northwest side of LA Fitness and two more vine maples or other similar small tree shall be added to the northeast side of LA Fitness to break up the massing and the monotony of those two building elevations.

Staff also recommends a condition that the applicant plant 2 canopy trees and 4 understory trees south of the Tualatin River Greenway and north of the parking and loading lot. This is to help screen the loading dock, semi-trailer trucks, trash area, and possible trash compactors from view. It will also help screen parking.

Condition AR-3.C.20 was added to address the ARB's concerns that the landscaping along I-5 help reduce air pollution according to ODOT's approved

landscaping list. AR-3.C.20's purpose is to ensure planted vegetation helps to reduce air pollution by conforming to the ODOT approved list.

73.100(1) All landscaping approved through the Architectural Review Process shall be continually maintained, including necessary watering, weeding, pruning and replacement, in a manner substantially similar to that originally approved through the Architectural Review Process, unless subsequently altered with Community Development Director approval.

A condition stating the exact subsection has been included in the recommended Conditions of Approval.

73.160(3)(e) Shrubs in parking areas must not exceed 30 inches in height. Tree canopies must not extend below 8 feet measured from grade.

Staff recommends a condition that the landscaping plan be amended to show that all vegetation will not be allowed to grow into paths and that trees shall be trimmed to maintain an 8-foot clearance.

73.240(2) The minimum area requirement for landscaping for conditional uses for RL, RML, RMH, RH and RH/HR Planning Districts, listed in 40.030, 41.030, 42.030, 43.030 and 44.030, excluding 40.030(3), 40.030(5)(j), 40.030(5)(m), 40.030(5)(n) and 41.030(2) shall be twenty-five (25) percent of the total area to be developed. When a dedication is granted on the subject property for a greenway and/or natural area, the minimum area requirement for landscaping shall be twenty (20) percent of the total area to be developed as determined through the AR process.

(3) The minimum area requirement for landscaping for uses in CO, CR, CC, CG, ML and MG Planning Districts shall be fifteen (15) percent of the total land area to be developed, except within the Core Area Parking District, where the minimum area requirement for landscaping shall be 10 percent. When a dedication is granted in accordance with the planning district provisions on the subject property for a fish and wildlife habitat area, the minimum area requirement for landscaping may be reduced by 2.5 percent from the minimum area requirement as determined through the AR process.

Approximately 27-percent of the subject site is proposed to be landscaping according to sheet L1.0 of the plan set. This amount of landscaping exceeds the requirement for all three plan designations on the subject site including RH, CO, and CC.

73.240(9) Yards adjacent to public streets, except as described in 73.240(7), shall be planted to lawn or live groundcover and trees and shrubs and shall be perpetually maintained in a manner providing a park-like character to the property as approved through the Architectural Review process.

The plans show the yards adjacent to SW Nyberg Street, I-5, and SW Martinazzi Avenue will be planted with shrubs, lawn, groundcover and trees. This creates a park-like setting, which meets the requirement.

73.240(11) Any required landscaped area shall be designed, constructed, installed, and maintained so that within three years the ground shall be covered by living grass or other plant materials. (The foliage crown of trees shall not be used to meet this requirement.) A maximum of 10% of the landscaped area may be covered with unvegetated areas of bark chips, rock or stone.

Staff recommends that the applicant show on a revised landscaping plan how the proposed ground cover will fully cover the ground.

73.260(1)(a) Deciduous shade and ornamental trees shall be a minimum one and one-half inch (1 1/2") caliper measured six inches (6") above ground, balled and burlapped.

Bare root trees will be acceptable to plant during their dormant season. Trees shall be characteristically shaped specimens.

All deciduous trees are shown on the plans at 2-inches in caliper at breast height. Staff recommends conditioning the applicant to the proposal.

73.260(1)(b) Coniferous trees shall be a minimum five feet (5') in height above ground, balled and burlapped. Bare root trees will be acceptable to plant during their dormant season. Trees shall be well branched and characteristically shaped specimens.

The coniferous trees are proposed at at-least 8-feet in height. Staff recommends conditioning the applicant to this proposal.

73.260(1)(c) Evergreen and deciduous shrubs shall be at least one (1) to five (5) gallon size. Shrubs shall be characteristically branched. Side of shrub with best foliage shall be oriented to public view.

All evergreen and deciduous shrubs proposed on the landscape plan are at least one (1) to five (5) gallon size, meeting the requirement.

73.260(1)(d) Groundcovers shall be fully rooted and shall be well branched or leafed. English ivy (Hedera helix) is considered a high maintenance material, which is detrimental to other landscape materials and buildings and is therefore prohibited.

The groundcover proposed is able to meet this requirement.

73.260 (1)(e) Lawns shall consist of grasses, including sod, or seeds of acceptable mix within the local landscape industry. Lawns shall be 100 percent coverage and weed free.

The proposed lawns will be planted with a rush/sedge mix consisting of plugs. This method should be able to produce a 100 percent coverage within a short period of time.

73.280 Landscaped areas shall be irrigated with an automatic underground or drip irrigation system.

Staff recommends that the applicant is conditioned to provide an irrigation plan prior to building permit, that the irrigation be installed with a doublecheck system and water meter, and finally supply irrigation to this ODOT frontage.

Condition AR-3.C.4 was added to ensure that irrigations systems brought into ODOT property will be permitted and approved by ODOT. ODOT requested a revision to this condition after reviewing the proposed conditions in the December 16th Recommendation and Staff Report.

73.290(1) Where natural vegetation has been removed or damaged through grading in areas not affected by the landscaping requirements and that are not to be occupied by structures or other improvements, such areas shall be replanted.

To meet the requirement of 73.290(1), staff recommends the applicant be conditioned to revised the site and grading plans to include a specification for replanting areas where existing vegetation or landscaping has been removed or damaged through grading and construction activities.

73.310(1) A minimum 5-foot-wide landscaped area must be located along all building perimeters, which are viewable by the general public from parking lots or the public right-of-way, excluding loading areas, bicycle parking areas and pedestrian egress/ingress locations. Pedestrian amenities such as landscaped plazas and arcades may be substituted for this requirement. This requirement shall not apply where the

distance along a wall between two vehicle or pedestrian access openings (such as entry doors, garage doors, carports and pedestrian corridors) is less than 8 feet.
The proposed landscaping plan has a 5-foot perimeter of landscaping, a fountain, sculpture, and café seating areas. This requirement is met.

73.310(3) *All areas not occupied by buildings, parking spaces, driveways, drive aisles, pedestrian areas or undisturbed natural areas shall be landscaped.*
The landscape plans indicate that all areas unoccupied by buildings, parking spaces, driveways, drive aisles, plazas and pedestrian areas are landscaped. The requirement is met.

73.340(1) *A clear zone shall be provided for the driver at ends of on-site drive aisles and at driveway entrances, vertically between a maximum of 30 inches and a minimum of 8 feet as measured from the ground level, except for parking structures and underground parking, where this provision shall not apply.*
Staff recommends the applicant is conditioned to maintain vegetation to these specifications.

73.340(2) *Perimeter site landscaping of at least 5 feet in width shall be provided in all off-street parking and vehicular circulation areas (including loading areas).*
73.340(2)(a) *The landscape area shall contain:*
(i) Deciduous trees an average of not more than 30 feet on center. The trees shall meet the requirements of 73.360(7).
(ii) Plantings which reach a mature height of 30 inches in 3 years which provide screening of vehicular headlights year round.
(iii) Shrubs or ground cover, planted so as to achieve 90 percent coverage within three years.

The site has been provided with the aforementioned 5-foot landscaping buffer. Staff has checked the tree plantings on the landscape plan. It appears trees have been proposed at not more than 30-feet on center. It appears the shrubs are capable of reaching 30-inches in 3 years and groundcovers are capable of reaching 90-percent ground coverage.

73.360(1) *A minimum of 25 square feet per parking stall shall be improved with landscape island areas, which are protected from vehicles by curbs. These landscape areas shall be dispersed throughout the parking area [see 73.380(3)].*

73.360(2) *All landscaped island areas with trees shall be a minimum of 5 feet in width (60 inches from inside of curb to curb) and protected with curbing from surface runoff and damage by vehicles. Landscaped areas shall contain groundcover or shrubs and deciduous shade trees.*

The landscape islands were previously approved during the master plan process MP-13-01.

73.360(3) *Provide a minimum of one deciduous shade tree for every four (4) parking spaces to lessen the adverse impacts of glare from paved surfaces and to emphasize circulation patterns. Required shade trees shall be uniformly distributed throughout the parking lot. The trees shall meet the requirements of 73.360(7).*

Shade trees are uniformly distributed throughout the parking lot. It appears that as many shade trees as possible have been incorporated into the landscape plan. Staff finds that these criteria are met.

73.360(4) *Landscaped islands shall be utilized at aisle ends to protect parked vehicles*

from moving vehicles and emphasize vehicular circulation patterns.

As previously stated, diamond landscape islands were approved through the master plan process in MP-13-01. Landscape islands are shown at the ends of all parking rows.

73.360(5) Required landscaped areas shall be planted so as to achieve 90 percent coverage within three years.

As discussed under 73.240(11) above, with the groundcover spacing condition, the landscaping will meet the 90% coverage within the three (3) year requirement.

73.360(6)(a) Site access from the public street shall be defined with a landscape area not less than 5 feet in width on each side and extend 25 feet back from the property line for commercial, public, and semi-public development with 12 or more parking spaces and extend 30 feet back from the property line for industrial development.

The main entrance contains landscaping on each side that is 5-feet deep and approximately 340-feet in length.

73.360(7) Deciduous shade trees shall meet the following criteria:

- (a) Reach a mature height of 30 feet or more**
- (b) Cast moderate to dense shade in summer**
- (c) Long lived, i.e., over 60 years**
- (d) Do well in an urban environment**
 - (i) Pollution tolerant**
 - (ii) Tolerant of direct and reflected heat**
- (e) Require little maintenance**
 - (i) Mechanically strong**
 - (ii) Insect and disease resistant**
 - (iii) Require little pruning**
- (f) Be resistant to drought conditions**
- (g) Be barren of fruit production.**

It appears that the applicant has provided trees that can withstand the rigors of being planted in a parking lot as required above. This is addressed through Condition P of Resolution 5163-13.

74.765 All trees, plants or shrubs planted in the right-of-way of the City shall conform in species and location and in accordance with the street tree plan in Schedule A.

Staff recommends the applicant is conditioned to revise their landscaping plan to meet the approved street tree list for the City on SW Nyberg Street and the main entrance. Staff also recommends the applicant be conditioned to revise their landscaping so that Street Trees are not more than 30-feet on center.

K. Tree Preservation:

73.050(4) As part of Architectural Review, the property owner may apply for approval to cut trees in addition to those allowed in TDC 34.200. The granting or denial of tree cutting permits shall be based on the criteria in TDC 34.230.

The proposal includes tree cutting. Therefore, TDC 34.230 applies.

34.230 The Community Development Director shall consider the following criteria when

approving, approving with conditions, or denying a request to cut trees.

(1) The Community Development Director may approve a request to cut a tree when the applicant can satisfactorily demonstrate that any of the following criteria are met:

(a) The tree is diseased, and

(i) The disease threatens the structural integrity of the tree; or

(ii) The disease permanently and severely diminishes the aesthetic value of the tree; or

(iii) The continued retention of the tree could result in other trees being infected with a disease that threatens either their structural integrity or aesthetic value.

(b) The tree represents a hazard which may include but not be limited to:

(i) The tree is in danger of falling;

a. Substantial portions of the tree are in danger of falling.

(c) It is necessary to remove the tree to construct proposed improvements based on Architectural Review approval, building permit, or approval of a Subdivision or Partition Review.

As demonstrated in the Tree Preservation Plans (plan set C2 series sheets) of the plan set, the vast majority of the proposed tree cuttings will allow for grading of buildings, a parking lot, drive aisles, and other improvements. Some trees were shown to be diseased and/or dying as well. This was also addressed in the Master Plan Conditions of Approval.

73.250(1) Trees and other plant materials to be retained shall be identified on the landscape plan and grading plan.

73.250(2)(a) During the construction process, the owner or the owner's agents shall provide above and below ground protection for existing trees and plant materials identified to remain.

73.250(2)(b) Trees and plant materials identified for preservation shall be protected by chain link or other sturdy fencing placed around the tree at the drip line.

The applicant has been conditioned in the recommended Conditions of Approval to show all preserved trees protected with sturdy fencing during the construction process on the final landscaping and grading plans.

73.250(2)(c) If it is necessary to fence within the drip line, such fencing shall be specified by a qualified arborist as defined in 31.060.

The tree preservation plan shows fencing around, not within, the drip line.

73.250(2)(d) Neither top soil storage nor construction material storage shall be located within the drip line of trees designated to be preserved.

Staff recommends adding a condition to place the above language on the grading, landscaping, and tree preservation plan.

73.250(2)(e) Where site conditions make necessary a grading, building, paving, trenching, boring, digging, or other similar encroachment upon a preserved tree's drip line area, such grading, paving, trenching, boring, digging, or similar encroachment shall only be permitted under the direction of a qualified arborist. Such direction must assure that the health needs of trees within the preserved area can be met.

The Landscape Plans and Grading Plans indicate the location of preserved trees. The notation on the plans does not specify that an arborist's direction is required where construction activities occur within the drip line of preserved trees. To meet the requirement of 73.250(2)(e), encroachment upon any identified preserved trees must occur under the direction of a qualified arborist to assure the health needs of trees within the preserved area can be met.

73.250(2)(f) Tree root ends shall not remain exposed.

The plans do not indicate that tree root ends shall not remain exposed. To meet the requirement of 73.250(2)(f), staff recommends a condition a note on the grading plan that grading activities in the vicinity of the trees to be preserved shall not allow tree root ends to remain exposed.

73.250(3) Landscaping under preserved trees shall be compatible with the retention and health of said tree.

Landscaping under preserved trees will be compatible with the health of the trees and meets the requirement.

L. Grading:

73.270(1) After completion of site grading, topsoil is to be restored to exposed cut and fill areas to provide a suitable base for seeding and planting.

The Grading and Landscape Plans specify topsoil placement in landscape planter areas and the requirement is met.

73.270(4) Impervious surface drainage shall be directed away from pedestrian walkways, dwelling units, buildings, outdoor private and shared areas and landscape areas except where the landscape area is a water quality facility.

The storm drainage system has been designed so water is directed away from walkways, buildings and landscape areas (not intended for storm water detention or water quality), which meets the requirement.

M. Bicycle Parking, Off-Street Parking and Loading:

73.370(1)(a) At the time of establishment of a new structure or use, or change in use, or change in use of an existing structure, within any planning district of the City, off-street parking spaces, off-street vanpool and carpool parking spaces for commercial, institutional and industrial uses, off-street bicycle parking, and off-street loading berths shall be as provided in this and following sections, unless greater requirements are otherwise established by the conditional use permit or the Architectural Review process, based upon clear findings that a greater number of spaces are necessary at that location for protection of public health, safety and welfare or that a lesser number of vehicle parking spaces will be sufficient to carry out the objectives of this section.

The appropriate amount of bicycle parking has been provided. Staff recommends conditioning the applicant to revise their site plan to show carpool and vanpool spaces and their civil plans to show how they will sign or strip to demarcate those spaces in the field.

73.370(1)(n) Bicycle parking facilities shall either be lockable enclosures in which the bicycle is stored, or secure stationary racks, which accommodate a bicyclist's lock securing the frame and both wheels.

The plans include 147 bike parking spaces. The spaces are being provided in both outdoor and enclosed facilities. Both types are capable of locking the frame and both wheels.

73.370(1)(o) Each bicycle parking space shall be at least 6 feet long and 2 feet wide, and

overhead clearance in covered areas shall be at least 7 feet, unless a lower height is approved through the Architectural Review process.

The three types of bike parking proposed count one space for every 2-foot by 6-foot dimension. Therefore, this requirement is met.

73.370(1)(r) Required bicycle parking shall be located in convenient, secure, and well lighted locations approved through the Architectural Review process.

The proposed bicycle parking is provided at many locations throughout the site. This includes spaces for employees behind the stores and spaces in front of the stores for patrons. Many spaces are also provided adjacent to the Tualatin River Greenway.

73.370(1)(u) Bicycle parking areas and facilities shall be identified with appropriate signing as specified in the Manual on Uniform Traffic Control Devices (MUTCD) (latest edition). At a minimum, bicycle parking signs shall be located at the main entrance and at the location of the bicycle parking facilities.

No bicycle parking signage has been identified on the plans. Because no signage has been identified, the requirement has not been met. To meet the requirement of 73.370(1)(u), staff recommends revised plans shall be submitted that show bicycle parking areas and facilities to be identified with appropriate signage as specified in the Manual on Uniform Traffic Control Devices (MUTCD) (latest edition). At a minimum, bicycle parking signs shall be located at the location of the bicycle parking facilities.

73.370(2)(a) The following are the minimum and maximum requirements for off-street motor vehicle parking in the City, except for minimum parking requirements for the uses in TDC 73.370(2)(a) (Residential Uses: iii, iv, v, vi, vii; Places of Public Assembly: i, ii, iv; Commercial Amusements: i, ii; and Commercial: i, ii, xi, xii, xiv) within the Core Area Parking District (CAPD). Minimum standards for off-street motor vehicle parking for the uses in 73.370(2) (a) Residential Uses: iii, iv, v, vi, vii; Places of Public Assembly: i, ii, iv; Commercial Amusements: i, ii; and Commercial: i, ii, xi, xii, xiv in the CAPD are in TDC 73.370(2)(b). The maximum requirements are divided into Zone A and Zone B, as shown on the Tualatin Parking Zone Map, Figure 73-3. The following are exempt from calculation of maximum parking requirements: parking structures; fleet parking; parking for vehicles for sale, lease or rent; car/vanpool parking; dedicated valet parking; and user-paid parking.

| USE | MINIMUM MOTOR VEHICLE PARKING REQUIREMENT | MAXIMUM MOTOR VEHICLE PARKING REQUIREMENT | BICYCLE PARKING REQUIREMENT | PERCENTAGE OF BICYCLE PARKING TO BE COVERED |
|---|---|--|--|---|
| <u>Commercial</u> | | | | |
| (i) Retail shops (under 100,000 sq. ft. gross floor area) | 4.00 spaces per 1,000 sq. ft. of gross floor area | Zone A: 5.1 spaces per 1,000 sq. ft. gross floor area Zone B: 6.2 | 0.50 space per 1,000 sq. ft. of gross floor area | 50 |

AR-13-07—Nyberg Rivers Shopping Center

| | | | | |
|--|--|--|--|----|
| | | spaces per 1,000 sq. ft. gross floor area | | |
| (iii) Shopping center (over 100,000 sq. ft. of gross floor area) | 4.1 spaces per 1,000 sq. ft. of gross floor area | Zone A: 5.1 spaces per 1,000 sq. ft. gross floor area Zone B: 6.2 spaces per 1,000 sq. ft. gross floor area | 0.50 space per 1,000 sq. ft. of gross floor area | 50 |
| (iv) Banks/Savings and loans | 4.30 spaces per 1,000 sq. ft. of gross floor area | Zone A: 5.4 spaces per 1,000 sq. ft. gross floor area Zone B: 6.5 spaces per 1,000 sq. ft. gross floor area | 2, or 0.33 spaces per 1,000 sq. ft. whichever is greater | 10 |
| viii) Restaurant | 10.00 spaces per 1,000 sq. ft. of gross floor area | Zone A: 19.1 spaces per 1,000 sq. ft. gross floor area Zone B: 23.0 spaces per 1,000 sq. ft. gross floor area | 2.00 spaces per 1,000 gross sq. ft. | 25 |
| (ix) Drive-up restaurant | 9.90 spaces per 1,000 sq. ft. of gross floor area | Zone A: 12.4 spaces per 1,000 sq. ft. gross floor area Zone B: 14.9 spaces per 1,000 sq. ft. gross floor area | 2.00 spaces per 1,000 gross sq. ft | 25 |

As shown in the calculation on page 56 and 57 of the applicant's narrative, the applicant proposes 1,316 parking stalls. The minimum required number of parking stalls is 1,203 and the maximum number required is 1,614. The applicant meets the requirement of this section. The applicant also proposes 147 bike parking stalls. The subject site can be determined to be a shopping center. Therefore, 147 bike parking stalls are adequate. Half of these are shown to be covered as required by this Section.

73.370(3) The minimum number of off-street Vanpool and Carpool parking for

commercial, institutional, and industrial uses is as follows:

| <u>Number of Required Parking Spaces</u> | <u>Number of Vanpool or Carpool Spaces</u> |
|--|--|
| 0 to 10 | 1 |
| 10 to 25 | 2 |
| 26 and greater | 1 for each 25 spaces |

This project contains 1,316 parking stalls. Therefore, the TDC requires that 53 vanpool and carpool parking spaces are designated. Staff recommends as state previously, that the applicant provide a revised site plan showing vanpool and carpool spaces.

73.370(1)(x) Required vanpool and carpool parking shall meet the 9-foot parking stall standards in Figure 73-1 and be identified with appropriate signage.

Staff recommends that the applicant be conditioned to designate carpool and vanpool spaces in the field with either signage or asphalt paint demarcation in the appropriate size

73.380(1) Off-street parking lot design shall comply with the dimensional standards set forth in Figure 73-1 of this section.

There are 1,316 parking spaces with both standard and subcompact dimensions proposed. Parking stall width and depth requirements are met for the proposed standard and subcompact size, for 90-degree and 45-degree angle parking. The aisle requirement of 24-feet for two-way circulation and 12-feet for one-way circulation is also met.

73.380(2) Parking stalls for sub-compact vehicles shall not exceed 35 percent of the total parking stalls required by Section 73.370(2).

Sub-compact stall account for 21-percent of the overall parking spaces.

73.380(3) Off-street parking stalls shall not exceed eight continuous spaces in a row without a landscape separation.

Staff has counted the spaces between landscape islands and diamonds and the number does not exceed eight. Landscape diamonds are allowed as a result of the Master Plan Decision.

73.380(4) Areas used for standing or maneuvering of vehicles shall have paved asphalt or concrete surfaces maintained adequately for all-weather use and so drained as to avoid the flow of water across sidewalks.

The drive aisles and parking areas are asphalt, which meets the requirement.

73.380(6) Artificial lighting, which may be provided, shall be so deflected as not to shine or create glare in any residential planning district or on any adjacent dwelling, or any street right-of-way in such a manner as to impair the use of such way.

Staff recommends a condition that requires the applicant to submit a revised lighting plan that shows all foot-candle measurement from on-site sources as measured over the property line. The current lighting plans measurements stop at the property line. Staff has also recommended a condition that the applicant provide specification sheets of all proposed lighting, so cutoff can be determined.

Condition AR-3.D.4 was added to respond to the ARB's concerns that the lights proposed without full cut-off would not be dark sky friendly pursuant to 73.380(6).

73.380(7) Groups of more than 4 parking spaces shall be so located and served by driveways that their use will require no backing movements or other maneuvering within a street right-of-way other than an alley. The proposed parking meets the requirement.

73.380(9) Parking bumpers or wheel stops or curbing shall be provided to prevent cars from encroaching on the street right-of-way, adjacent landscaped areas, or adjacent pedestrian walkways.

There will be curbing in the parking areas, which meets the requirement.

73.380(11) On-site drive aisles without parking spaces, which provide access to parking areas with regular spaces or with a mix of regular and sub-compact spaces, shall have a minimum width of 22 feet for two-way traffic and 12 feet for one-way traffic. On-site drive aisles without parking spaces, which provide access to parking areas with only sub-compact spaces, shall have a minimum width of 20 feet for two-way traffic and 12 feet for one-way traffic.

The proposed drive aisle and circulation system meets the requirement.

73.390(1) The minimum number of off-street loading berths for commercial, industrial, public and semi-public uses is as follows:

| <u>Square Feet of Floor Area</u> | <u>Number of Berths</u> |
|----------------------------------|-------------------------|
| Less than 5,000 | 0 |
| 5,000 - 25,000 | 1 |
| 25,000 - 60,000 | 2 |
| 60,000 and over | 3 |

Building D-100 (Michaels), 1005 (New Seasons), and 1010 (Home Goods are a combined total of 82,822 square feet. Per this Section 3 loading docks are required. A loading dock has been proposed for each of these stores. Building 1040 is proposed to be 110,093 square feet and three loading dock berths are proposed as required. These standards have been met.

73.390(2) Loading berths shall conform to the following minimum size specifications:

(a) Commercial, Public and Semi-Public uses > 25,000 GSF 12' x 35'

(c) Berths shall have an unobstructed height of 14'

(d) Loading berths shall not use the public right-of-way as part of the required off-street loading area.

All the loading berths have a height clearance over 20-feet and a minimum 16-foot width. The proposed lengths are 120-feet. None of the loading berths proposed use public right-of-way. These requirements are met.

N. Access:

73.400(11) Public Semi-Public and Commercial Uses with over 250 Required Parking Spaces, Accessways determined by City Engineer. Ingress and egress for commercial uses shall be determined by the City Engineer. Number of walkways determined by the City Engineer.

Accessways, walkways, and ingress and egress were approved through the master plan process MP-13-01 by the City Engineer.

Vision clearance requirements at the driveways and street intersection shall comply with the requirements of 73.400(13).

The locations of proposed landscaping and street trees meet vision clearance requirements of 73.400(16).

O. Signs:

All new signage proposed for the site shall be submitted separately for sign permits. Staff recommends this as a condition.

P. Public Comments Received:

Staff has received one public comment in support of the application.

"I do hope the persons approving the architectural review of Cabela's project agree to Cabela's traditional log front, lodge type entrance to their store. The lodge front is known throughout the US. Cabela's and Center Cal are working with us, the Chamber and City regarding the ice age history of the Willamette/Tualatin/Yamhill Valley and this type of historical architecture could mark the I-5/ I-205 scene as the gateway to ice age history in all of the valleys. It could become the center piece for efforts to further the economic Tualatin Ice Age Tourism Plan.

Please refer my support to proper staff in charge of architectural review of plans.

*Yvonne Addington, Board Member
Chair, Ice Age History
Tualatin Historical Society'*

Staff is supportive and recommends approval of the proposed log/lodge front theme for Cabela's.

The issues raised in the Request for Review with a staff response are:

Reason #1 APPELLANT'S COMMENTS

Appellant Steven L. Pfeiffer, states, "The Decision is not in conformance with applicable law because it does not establish, based upon substantial evidence, that compliance with TDC 73.050(1)(a) is possible, likely, and reasonably certain to succeed when Applicant does not own or control 'the property in the southeast portion of the site plan. Alternatively, Applicant has not demonstrated that it is feasible to develop the Property in compliance with applicable development standards as required by TDC 73.050(1.a) if this portion of the Property is removed. (Attachment A-Steven L. Pfeiffer Request for Review January 3, 2014, pg. 2)

Reason #1 STAFF RESPONSE

Appellant claims that the ARB findings are deficient under TDC 73.050(1) (a) based on a claim that allowed use of the ODOT right-of-way is not “possible, likely, and reasonably certain to succeed.” *Meyer v. City of Portland*, 67 Or App 274, 280, 678 P2d 741 (1984).

In *Meyer*, the City of Portland imposed detailed conditions of approval on a Planned Unit Development requiring the applicant to later submit technical studies to ensure that the project could be constructed in a landslide hazard area. The appellant argued that deferring a discretionary decision to a later stage of the development removed the opportunity for public comment and also left the record void of substantial evidence to demonstrate that the project was in fact feasible. Both LUBA and the Court of Appeals rejected this argument and instead found:

Petitioners appeared and were entitled to present evidence at the public hearings upon which the city’s findings in this matter were based. It is apparent therefore that the city made the findings required by Code section 33.106 6 and that petitioners had a full opportunity to be heard on the critical land use issues before the city’s decision became final. This is what *Fasano* requires. *Id.* at 282.

Unlike *Meyer*, the City of Tualatin has not deferred any discretionary decision in a condition of approval and has not deferred any technical study necessary to determine if the development is feasible. Instead, the City required detailed traffic studies and supplements to those studies to determine the traffic impacts and appropriate mitigation measures for the development. The applicant had ample opportunity on the record to present evidence, and did so, at the public hearing refuting the City’s evidence. The City then imposed a condition of approval requiring a widening of Nyberg Road. The appellant did not contest that improvement. Instead, the appellant now claims under *Meyer*, that the record does not show that the improvement is feasible or likely to occur. To support this claim, the appellant states that ODOT has not declared the property as surplus, that the applicant does not yet own or control the land, or that any of this will occur in a timely manner.

The appellant’s claims are refuted by the record. ODOT has already declared the property surplus. (See Exhibit A). ODOT has acknowledged that the property will be sold to the Nyberg Rivers development. (Exhibit B). Lastly, ODOT has directly corresponded with the City that it approves the widening (Exhibit C) and is in the process of conveying title to the applicant. (Exhibit B).

Certainly, in light of *Meyer*, this evidence constitutes substantial evidence a reasonable person would rely on to reach a decision that compliance with the condition of approval is feasible, “possible, likely, and reasonably certain to succeed.” *Meyer*, 67 Or App 274, 280.

No additional technical studies are required and none were imposed as a condition of approval. The appellant had the opportunity to contest the technical studies during the proceedings and the evidence clearly demonstrates that the acquisition or allowed use of the ODOT right of way is reasonably likely to succeed.

Reason #1 CONCLUSION

Staff recommends the City Council agree with the ARB's Decision and deny the Request for Review regarding the applicant's control of the ODOT property.

Reason #2 APPELLANT'S COMMENTS

Appellant Steven L. Pfeiffer states, "Zian is adversely affected by the Decision because Zian's property is located one-half mile west of the Project site and directly accesses two roads (SW Tualatin Sherwood Road and SW Boones Ferry Road) that will be heavily affected by traffic congestion associated with the Project." (Attachment A, Steven L. Pfeiffer, Request for Review pg. 3).

Reason #2 STAFF RESPONSE

Applicant states, "To establish standing, appellant must demonstrate under TDC 31.078 (1) that it submitted comments before the ARB and may be adversely affected by the decision. There is no question that the appellant submitted comments below. To establish adverse affect, the appellant argues that heavy congestion of SW Tualatin-Sherwood Road and SW Boones Ferry Road will impact its site located one-half mile west of the project.

The ARB review is an architectural review; not a transportation review. There are no ARB approval criteria that require any findings regarding transportation improvements on either of these facilities. Further, the appellant claims that adverse impact includes "increase in trips in the area." This is not the threshold for transportation impacts. Instead, Washington County and the City of Tualatin have long established thresholds for determining adverse impact on transportation facilities. These thresholds are measured by levels of service and vehicle to capacity ratios; not simply an increase in trips in the area. Thus, the appellant cannot claim adverse affect here based on traffic trips that are not relevant to the ARB approval criteria. Regardless of this analysis of the appellant's standing to proceed with the ARB appeal, the City will consider the appeal with the advisory that transportation facilities issues are not relevant to the ARB approval criteria." (Attachment B, Christie White, Response pg 1).

Reason #2 CONCLUSION

The appeal of the AR based on traffic impacts is not within the purview of the AR.

STAFF CONCLUSION

Based on the findings of this report and on the supporting materials and information cited in the findings, Staff concludes the Steven L. Pfeiffer Request for Review of the ARB Decision on Nyberg Rivers Shopping Center, AR-13-07, the ODOT property and traffic impact should be denied.

Q. Occupancy Requirements:

Except as allowed by Subsection (2), all landscaping and exterior improvements required as part of the Community Development Director's, Architectural Review Board's or City Council's approval shall be completed in addition to Fire and Life Safety, and Engineering/Building Department requirements prior to the issuance of any certificate of occupancy.

Staff recommends conditioning the applicant to the aforementioned code section.

R. Conformance With Community Plan and Development Code.

31.114 No building permit shall be issued by the Building Official for the City of Tualatin for the erection, construction, conversion or alteration of any building or structure or use of land unless the Community Development Director or designee has first determined that such land use, building or structure, as proposed, would comply with the Tualatin Community Plan and Development Code. All applications for building permits shall be accompanied by plans and specifications, drawn to scale, showing the exact sizes and locations on the lot of the building and other structures existing and proposed; the existing and intended use of each building, structure, structures, or part thereof; and such other information as is needed to determine conformance with the Tualatin Community Plan and Development Code. If, during the course of constructing any building or structure, the Building Official determines that such construction activity is in violation of any provision of the Tualatin Community Plan or Development Code, the Building Official is hereby authorized to issue a stop-work order under the applicable provisions of the Uniform Building Code. This remedy is in addition to and not in lieu of any other right or remedy available to the City to enforce the provisions of this ordinance. [Ord. 590-83 §1, 04/11/83; Ord. 699-86 §20, 06/23/86]

Staff recommends the applicant be conditioned to this code section.

S. Time Limit on Approval:

73.056 Architectural Review approvals shall be void after one year unless:
(1) A building, or grading permit submitted in conjunction with a building permit application, has been issued and substantial construction pursuant thereto has taken place and an inspection performed by a member of the Building Division; or
(2) An extension is requested by the applicant of the Architectural Review and approved by the Community Development Director and City Engineer. Before approving an extension the Community Development Director and City Engineer shall find that there have been no significant changes in any ordinances, standards, regulations or other conditions affecting the previously approved project so as to warrant its resubmittal. The following conditions shall also apply:
(a) An extension request shall be submitted prior to the initial one year expiration, and
(b) No more than one 6-month extension shall be granted for a project receiving Architectural Review approval.

AR-13-07—Nyberg Rivers Shopping Center

Staff has recommended a Condition of Approval consistent with Section 73.056.

IV. ARCHITECTURAL REVIEW RECOMMENDED CONDITIONS OF APPROVAL

Based on the Findings and Conclusions presented in the staff report, staff recommends that AR-13-07 be approved, subject to the following Architectural Review Conditions of Approval:

NOTE: *Conditions and findings in this staff report refer to pages of the plan set intake date stamped November 12, 2013 and December 9th, 2013.*

The Architectural Review Board Decision approves AR-13-07 subject to the following Architectural Review conditions:

AR-1 Prior to issuance of any grading permits or other on-site work on the entirety of the subject site per CWS, TVF&R and ODOT:

A. CWS: Submit to the City of Tualatin Planning Division a copy of the Clean Water Services Site Development Permit to show compliance with the following:

A Clean Water Services (the District) Storm Water Connection Permit Authorization must be obtained. Application for the District's Permit Authorization must be in accordance with the requirements of the Design and Construction Standards, Resolution and Order No. 07-20, (or current R&O in effect at time of Engineering plan submittal), and is to include:

1. Detailed plans prepared in accordance with Chapter 2, Section 2.04.2.b-l.
2. Detailed grading and erosion control plan. An Erosion Control Permit will be required.
3. Area of Disturbance must be clearly identified on submitted construction plans. If site area and any offsite improvements required for this development exceed one-acre of disturbance, project will require a 1200-CN Erosion Control Permit. If site area and any offsite improvements required for this development exceed five-acres of disturbance, project will require a 1200-C Erosion Control Permit.
4. Detailed plans showing the development having direct access by gravity to public storm and sanitary sewer.
5. Provisions for water quality in accordance with the requirements of the above named design standards. Water Quality is required for all new development and redevelopment areas per R&O 07-20, Section 4.05.5, Table 4-1. Access shall be provided for maintenance of facility per R&O 07-20, Section 4.02.4.
6. If use of an existing offsite or regional Water Quality Facility is proposed, it must be clearly identified on plans, showing its location, condition, capacity to treat this site and, any additional improvements and/or upgrades that may be needed to utilize that facility.
7. If private lot LIDA systems proposed, must comply with the current CWS

Design and Construction Standards. A private maintenance agreement, for the proposed private lot LIDA systems, needs to be provided to the City for review and acceptance.

8. Show all existing and proposed easements on plans. Any required storm sewer, sanitary sewer, and water quality related easements must be granted to the City.
9. Application may require additional permitting and plan review from the District's Source Control Program. For any questions or additional information, please contact Source Control at (503) 681-5175.
10. Site contains a "Sensitive Area." Applicant shall comply with the conditions as set forth in the Service Provider Letter No. 13-000801, dated April 4, 2013.
11. Clean Water Services shall require an easement over the Vegetated Corridor conveying storm and surface water management to Clean Water Services that would prevent the owner of the Vegetated Corridor from activities and uses inconsistent with the purpose of the corridor and any easements therein.
12. Detailed plans showing the sensitive area and corridor delineated, along with restoration and enhancement of the corridor.
13. Provide DSL and Corps of Engineers permits for any work in the wetlands or creek prior to any on site work, including grading and erosion control. Include permit number on cover sheet of plans or provide concurrence with the delineation.
14. Any proposed offsite construction activities will require an update or amendment to the current Service Provider Letter for this project.

This Land Use Review does not constitute the District's approval of storm or sanitary sewer compliance to the NPDES permit held by the District. The District, prior to issuance of any connection permits, must approve final construction plans and drainage calculations.

B. Fire: Provide the City of Tualatin Planning Division evidence/documentation that the following has been reviewed and approved. Submit plans to TVF&R for review and approval showing the following.

1. Parking lots and drive aisles able to sustain 60,000 pounds GVW and 12,500 pounds point load.
2. Please provide a full size scaled drawing at a scale of 1" = 40' or 1" = 50' for verification of turning radius.

C. ODOT: The applicant shall obtain an ODOT Permit for construction of the bike lane, right turn lane, planter strip, sidewalk, landscape buffer, retaining wall and drainage within the state highway right of way. Tree placement and design shall be consistent with the ODOT Highway Design Manual or a design exception shall be obtained. The types of trees to be approved by ODOT. Applicant shall enter into a Cooperative Improvement Agreement with ODOT to address ODOT permit requirements, providing graffiti removal and maintenance of the retaining wall including and the transfer of

ownership of the improvement to ODOT. The agreement shall address the work standards that must be followed, maintenance responsibilities, and compliance with ORS 276.071, which includes State of Oregon prevailing wage requirements.

To facilitate the closure of SW 75th Ave (private), the applicant shall:

1. Ensure that a permanent access easement is recorded to provide access to a public roadway (Nyberg Rd) for tax lots 2508, 2502, 2506, 2100, 2507, and 2700.
2. Record a 15ft maintenance easement adjacent to the retaining wall and a maintenance vehicle access easement through the development with ODOT.

Illumination within the ODOT right of way must be in accordance with AASHTO illumination standards and the ODOT Lighting Policy and Guidelines, January 2003, which states that local jurisdictions must enter into an intergovernmental agreement (IGA) with ODOT wherein the local jurisdiction is responsible for installation, maintenance, operation, and energy costs.

Noise Advisory:

The applicant is advised that outdoor activity areas on the proposed site may be exposed to traffic noise levels that exceed federal noise guidelines. Builders should take appropriate measures to mitigate this impact. It is generally not the State's responsibility to provide mitigation for receptors that are built after the noise source is in place.

AR-2 No building permit shall be issued by the Building Official for the City of Tualatin for the erection, construction, conversion or alteration of any building or structure or use of land unless the Community Development Director or designee has first determined that such land use, building or structure, as proposed, would comply with the Tualatin Community Plan and Development Code (TDC 31.114).

AR-3 Prior to Issuance of the Building Permit for construction of any of the buildings on the entirety of the subject site, the applicant shall submit a revised plan set inclusive of the following for review and approval. Provide evidence or documentation to the City of Tualatin Planning Division that all items have been completed prior to Planning signing off on any building construction permit:

A. Architecture

1. All roof top equipment on all buildings shall be entirely screened from view from all sides and from all public sidewalk vantage points 6-feet above grade (TDC 73.150 (18)).
2. On the west side of Cabela's, the entirety of the load dock screen wall as shown on plan sheet A3.10a shall be at least 15-foot high and opaque to fully screen a semi-trailer truck (TDC 73.390(3)).
3. On the north side of Michael's (building D-110) install a 15-foot high wall to screen, a semi-trail truck parked at the loading dock to meet Condition N of Resolution 5163-13.

4. Add manufactured stone veneer columns and the trellis architectural features to the west side of Cabela's to match the north and east elevations to meet Condition M of Resolution 5163-13.
5. The applicant shall construct the west elevation (along the pedestrian walkway) of Cabela's including the stone veneer and wood screen wall with the architecture proposed on page 5.3 and 5.4 of the December 9th submittal booklet. The applicant shall also add the architectural features shown in the picture below to all sides and all corners of the building as proposed during the master plan. The applicant shall also add all architectural features shown on page 30 of the December 3rd presentation to the Architectural Review Board. In addition the Cabela's building shall also add the trellises shown on the north side of Cabela's on page A3.10a of the complete plan set intake stamped date November 12, 2013 to the south side of the building. These trellises shall be 62-feet wide, 18-feet in height, and have three stone veneer columns exactly like the trellises shown on the north side of the building. The applicant shall also screen the trash compactor with the exact same treatment as the proposed Cabela's loading dock screen wall shown on page 5.3 and 5.4 of the December 9th submittal booklet.



6. The northwest and northeast elevation of building N-100 shall be upgraded with architectural features that match the quantity and quality of the features shown on the southwest and southeast elevation of the building to meet Condition L of Resolution 5163-13.
7. Elevations and building permit application shall be revised to show building N-100 (LA Fitness) to have a 45-foot building height inclusive of any architectural features (TDC 53.090).
8. The north side of New Seasons, Michaels, and Home Goods shall be upgraded with the same quantity and quality of architecture shown in the front of the buildings. This includes showing more reliefs, more changes in color, and more material changes and other elements to break up large massing to improve pedestrian scale over what was proposed with the December 9th submittal packet.
9. The entirety of the east side of Restaurant 1030 shall be upgraded to have the same quality and quantity of architectural features as shown on the front façade. This includes showing reliefs, changes in color, and material changes. The upgrade shall also show the windows and awnings proposed with the December 9th submittal.
10. The south side of the Home Goods architecture shall be enhanced to provide a change in roof line, more changes in color, more reliefs, and more material changes. The south elevation of Home Goods shall be further explored, developed, enhanced to create a stronger focal point and entry for the site.

11. The applicant shall install the lighting fixtures along the entirety of the plaza area shown on page 5.4 of the December 9th submittal booklet.
12. Any retaining walls shall be decorative like the right image on sheet 9.0 of the December 9th submittal booklet. Plain retaining walls as shown on the left image on sheet 9.0 are not acceptable, and shall be upgraded with a stone veneer. The architectural treatment on the retaining wall for the Nyberg Street right turn lane shall be approved by ODOT in coordination with the City of Tualatin.

B. Civil:

1. On the revised grading plan show all preserved trees protected with sturdy fencing (chain link fence) during the construction process.
2. A note shall be placed on the grading plans that states, "No grading activities will allow preserved tree roots to remain exposed per TDC 73.250(2)(f)."
3. Provide for required vanpool and carpool spaces on the striping and signage plan.
4. All site plan amendments shall reflect required revised and approved planning site plan.

C. Landscaping and Irrigation

1. Fill in the street tree gaps along all public and public-like streets to match the City standard of 30-feet on center (TDC 74.765 and Map 74-1) (landscape plan sheet L1.0-L1.2)
2. Choose from the City's street tree list for SW Nyberg Street frontage and the main entrance frontage (TDC 74.765 and Map 74-1). Unapproved trees such as Beach Plum, Quaking Aspen, and Serviceberry are shown (landscape plan sheet L1.0-L1.2). Street Tree List:
<http://www.tualatinoregon.gov/developmentcode/tdc-chapter-74-public-improvement-requirements#74.765>
3. Replace all "Central Oregon" species with either "Coast Range" or "Tualatin River" species (landscape plan sheets L1.0-L1.9) to meet Condition T of Resolution 5163-13.
4. An irrigation system is required pursuant to TDC 73.280. Supply an irrigation plan. The future irrigation plan shall relocate all City irrigation lines and install a water meter with doublecheck to assure continued service (TDC 73.280). The irrigation plan shall also supply lines to the ODOT frontage. The irrigation plan shall be approved by ODOT for the ODOT frontage. A permit from ODOT shall be obtained for installation of the irrigation system.
5. On the south side of the trail between the west end of building D-130 and the east end of building 1010, plant 2 canopy trees and 4 understory trees per 100 lineal feet. No Central Oregon plant species allowed per 73.020.
6. Add six more Vine Maples to the northwest side of LA Fitness (building N-100) or other similar tall growing shrub or small tree in the planter strip to break up the massing of the building per 73.020.

7. Add two more Vine Maples to the northeast side of LA Fitness (building N-100) or other similar tall growing shrub or small tree in the planter strip to break up the massing of the building per 73.020.
8. Move trees and shrubs to appropriate locations from the edge of the shared pathway shy area so routine pruning to prevent branches/plants from encroaching over shy or path when full grown is not required. This does not include tree that can have branches pruned to maintain an eight to ten foot clearance above shared paths (73.160(3)(e) and 73.260(5)).
9. Provide a note on the revised landscaping plans that shrubs in all parking areas will be maintained to not exceed 30-inches in height and that all trees will be maintained to not extend below 8-feet measured from grade pursuant to TDC 73.160(3)(e).
10. Show all trees preserved in the C2 series of preliminary plans protected with chain link fence or other sturdy fencing through the duration of the construction process per 73.250(2)(6).
11. The applicant shall plant all coniferous to at least 8-feet in height as proposed.
12. The applicant shall plant deciduous trees to at least 2-inches in caliper at breast height as proposed.
13. Pursuant to TDC 73.290(1) the revised site and grading plans shall include a specification for replanting areas where existing vegetation or landscaping has been removed or damaged through grading and construction activities.
14. Add or demarcate where 15 additional Douglas Fir, Western Red Cedar, or other tall-maturing conifer trees were placed on tax lot 2502 pursuant to Condition T of Resolution 5163-13. Add an additional landscaping sheet in the revised landscaping plans that show specific compliance with Condition T of Resolution 5163-13.
15. Add or demarcate where the replacement trees pursuant to Condition S of Resolution 5163-13 are shown. Deciduous replacement trees shall be at least 3-inches in caliper at breast height and coniferous trees shall be at least 10 feet in height at time of planting. Add an additional landscaping sheet that shows specific compliance with Condition S of Resolution 5163-13.
16. Add the bike parking plans to the site and landscaping plans. Show revised landscaping based on placement of bike racks and covered bike storage. Show a 5-foot clear concrete or asphalt walkway around all bike parking per 73.370(1)(p).
17. Show that planting around trash enclosure walls will be evergreen exclusive of the bike rack pursuant to TDC 73.227(6)(b)(iii).
18. Show how the proposed ground cover will fully cover the ground in 3 years pursuant to TDC 73.240(11).
19. Provide evidence and/or documentation that the trees proposed for the diamond planters will meet Condition P of Resolution 5163-13.
20. Landscaping abutting I-5 shall be consistent with the ODOT approved list.

D. Lighting

1. Provide elevations and/or spec sheets of all proposed lighting to determine if cut-offs meet TDC 73.160(3)(c) and 73.380(6).
2. Provide a lighting plan that shows all light measurements down to .1 foot candles as it passes over the property line per 73.380 (6).
3. Light poles shall be LED with pedestrian scale lighting at the entries to the subject site as proposed.
4. Show how lights without full cut-off will not cause light pollution.

E. Fire (See TVF&R full comment letter for explanation).

1. New buildings shall have full NFPA 13 fire sprinklers.
2. Identify aerial apparatus access lanes on each building in excess of 30 feet in height.
3. A parking restriction sign plan (OFC D103.6).
4. A fire lane curb marking plan (OFC 503.3).
5. Any proposed gates with approved Fire District lock mechanisms.
6. A current fire flow test of the nearest fire hydrant demonstrating available flow at 20 psi residual pressure as well as fire flow calculation worksheets. Please forward copies to both TVF&R as well as local building department. Fire flow calculation worksheets as well as instructions are available at www.tvfr.com. Please provide fire flow calculation worksheets for each new building on the campus.
7. A fire hydrant distribution plan based on fire flow calculations.
8. Bollards at each new fire hydrant and fire department connection.
9. Fire sprinkler Fire Department connections shall be plumbed to the fire sprinkler riser downstream of all control valves.
10. Each new building is to be afforded with a Knox box.
11. Pursuant to TDC 73.160(3)(d), provide an identification system which clearly locates buildings and their entries emergency services.

F. Planning

1. All crosswalks shown to be striped on sheet C1.0 of the plan set shall be made of different raised material such as solid colored thermal plastic. Crosswalks made with paint only are not allowed per 73.160(1)(a)(iii).
2. All crosswalks shown to be a brick or paver pattern shall be created of raised brick or pavers of a significantly different color than the underlying asphalt or cement per 73.160(1)(a)(iii). Raised and scored colored concrete is acceptable.
3. The accessway proposed on plan set sheet C1.3 from northeast side of building 1040 to the edge of the sensitive area containing the Tualatin River Greenway shall be at least 8-feet wide and constructed of Portland Concrete Cement pursuant to TDC 73.160(1)(d).

4. The 14-foot wide accessway from the rear of building 1010 on tax lot 1601 to the Tualatin River Greenway shall be constructed of Portland Concrete Cement pursuant to TDC 73.160(1)(d).
5. Show all mechanical and electrical equipment on site. Show that all electrical and mechanical equipment will be fully screen with landscaping, fencing, or a wall pursuant to TDC 73.160(4)(a).
6. Refine the site plan to show refuse and recycling storage areas for building A, B, C, E-100, D-130, D-125, D-120, and D-110 that meet Section 73.227. These include the existing recycling and refuse storage areas that exist and are not shown on the site plan. In addition building 1005 shows a trash compactor and bicycle parking in the same area. This conflict shall be rectified through a revised site and refuse plan.
7. Place a note on the grading, landscaping, and tree preservation plan that neither top soil storage nor construction material storage shall be located within the drip line of trees designated to be preserved pursuant to TDC 73.250(2)(d).
8. Pursuant to 73.370(1)(a), show designated carpool and vanpool spaces on the revised site plan.
9. Pursuant to 73.370(1)(u) a bike parking signage plans shall be submitted in the revised plan set and through the sign plan package for site signage. Bike parking directional signage shall be placed at the main pedestrian entrance for each building if bike parking is not within 50-feet and viewable from the pedestrian main entrance.
10. 53 carpool or vanpool spaces shall be indicated in a revised site plan and signed or otherwise designated in the parking lot per 73.370(1)(x).
11. All internal walk ways, access ways, crosswalks, and sidewalks shall be at least 6-feet in width pursuant to TDC 73.160(1)(a)(ii). A reduction may be requested if existing sidewalk.
12. Show where recycling will be located on a revised trash enclosure and site plan to meet TDC 73.226(5).
13. Show that trash enclosure doors can open wider than a 90-degree angle, that there will be no center pole between the trash enclosure doors, and that the doors can be lockable in this open position as requested by the trash hauler.
14. Show how trash and site plan meet TDC 73.227.
15. Provide for required vanpool and carpool spaces on the striping and signage plan.
16. The elevation for building J-100 (BJ's restaurant), do not match the footprint of the site plan, please revise.
17. Revise the west side of the main entrance to be a City standard 5-foot tree well and 9-foot wide pathway.
18. All dog kennels shall be fully screened with the same material used to build Cabela's, (no chain link fencing with slats).
19. All dumpsters and trash cans on the north side of Building A shall be fully screened in an enclosure that matches the building materials of Building A.



STAFF REPORT CITY OF TUALATIN

TO: Honorable Mayor and Members of the City Council

THROUGH: Sherilyn Lombos

FROM: Linda Odermott, Paralegal
Sean Brady, City Attorney

DATE: 02/10/2014

SUBJECT: Consideration of Resolution No. 5179-14 Approving with Conditions, a Public Utilities Decision for the Nyberg Rivers Shopping Center Development Located at 7455-7925 SW Nyberg Street (Tax Map 2S1 24A, Tax Lots 1601, 1602, 1900, 2502, 2506, 2507, 2508, and 1700; Tax Map 2S1 24B, Tax Lots 2000, 2001, and 2100)

ISSUE BEFORE THE COUNCIL:

Council will consider Resolution No. 5179-14 approving with conditions, a public utilities decision for the Nyberg Rivers Shopping Center Development.

RECOMMENDATION:

Staff recommends Council approve Resolution No. 5179-14 approving with conditions, a Public Facilities Decision for the Nyberg Rivers Shopping Center.

EXECUTIVE SUMMARY:

CenterCal Properties LLC (CenterCal) submitted an application for a Public Utilities decision for the Nyberg Rivers Shopping Center development. The City Engineer issued a Public Utilities decision on December 20, 2013. The Public Utilities decision was appealed to City Council by Zian Limited Partnership, a neighboring shopping center, for a *de novo* hearing. On January 27, 2014, City Council held a quasi-judicial hearing on the Public Utilities application. The City Council considered the information and testimony presented at the hearing and deliberated to a decision. The City Council voted 7-0 to approve with conditions the Public Utilities application for the Nyberg Rivers Shopping Center. Resolution No. 5179-14 will be the final written order of the City Council on the Public Utilities application.

Attachments: Resolution No. 5179-14 Utilities Decision
Reso No 5179-14 Exhibits