

ARCHITECTURAL REVIEW

New development, or substantial redevelopment, of multi-family (“common wall”) residential, commercial, and industrial use properties is generally subject to Architectural Review (AR). The Architectural Review decision by the Planning Department considers all site design elements, including: building height and appearance, lighting, landscaping, tree preservation, pedestrian circulation, parking, and loading facilities.

Architectural Review also encompasses a Public Facilities Review led by the Engineering Department, to evaluate transportation and access management; sewer, water, and stormwater; water quality and erosion control; and protection of environmentally sensitive areas.

Both departments coordinate with other City departments and outside agencies, such as Tualatin Valley Fire and Rescue and Clean Water Services, to ensure compliance with all applicable development standards.

MINOR ARCHITECTURAL REVIEW (TYPE I): Minor Architectural Review (MAR) is used for small exterior modifications to an existing site or building as described in TDC 33.020(7). See the separate MAR packet for details.

TYPE II: This land use procedure is used when the standards and criteria require limited discretion and interpretation. Type II decisions are decided by staff and require public notice with an opportunity for appeal to the Architectural Review Board, or to City Council for Public Facility review.

TYPE III: This land use procedure requires discretion made by the Architectural Review Board to implement established policy. Type III decisions require public notice and are decided at a public hearing, with an opportunity for appeal to the City Council.

General thresholds for Type III Review are as follows:

- Commercial Buildings: 50,000 square feet and larger
- Industrial Buildings: 150,000 square feet and larger
- Multifamily Housing: 100 units and above, or abutting a single family zone

PRIOR TO APPLICATION SUBMITTAL

- Attend a Pre-Application Meeting (TDC 32.110)
- Notice and host a Neighborhood/Developer Meeting (TDC 32.120)

Following submittal of an Architectural Review application, the applicant must post a sign on the subject property to provide notice of the pending land use application.

SUBMITTAL REQUIREMENTS

Please submit all materials in digital media format (USB preferred), plus two paper copies of your site plans. Details regarding submittal requirements are listed in TDC 32.140, 33.020(4), and 33.110(4).

GENERAL:

- Land Use Application form
- Narrative addressing all applicable approval criteria and standards
- Title Report
- Hydraulic Modeling Worksheet
- Service Provider Letter from Clean Water Services
- Service Provider Letter/Agreement from Republic Services

PLANS:

- Existing Conditions
- Site Plan
- Tree Preservation Plan
- Grading Plan
- Utility Plan
- Landscape Plan
- Lighting Plan
- Color Elevations
- Materials Board

PUBLIC NOTICE:

- Documentation for Neighborhood Developer Meeting
- Certification of Sign Posting

TYPICAL REPORTS:

- Tree Assessment Report
- Transportation Impact Study
- Stormwater Management Report

APPROVAL CRITERIA

The applicant's plans and narrative must work together to demonstrate that all applicable criteria are met. The following criteria apply to all AR's.

Other criteria, such as zoning and overlay standards, or standards applicable to a specific use, also apply.

Tualatin Development Code:

- Chapter 33.110 Tree Removal
- Chapter 73A: Site Design
- Chapter 73B: Landscaping
- Chapter 73C: Parking Standards
- Chapter 73D: Waste Management Standards
- Chapter 74: Public Improvement
- Chapter 75: Access Management

Tualatin Municipal Code:

- Chapter 03-02: Sewer Regulations
- Chapter 03-03: Water Service
- Chapter 03-05: Soil Erosion, Surface Water Management, Water Quality Facilities

Hedges D – Fleet Parking Lot

11507 SW 115th Avenue (private street), Tualatin, OR 97062

Table of Contents - For AR Submittal

1. General

- a. Land Use Application – Type II
- b. Narrative addressing all applicable approval criteria and standards
- c. Title Report
- d. Hydraulic Modeling Worksheet
- e. Service Provider letter from Clean Water Services.
- f. Service Provider letter/agreement from Republic Services

2. Plans

- a. Existing Conditions – See sheet C0.01
- b. Site Plan – See sheet A1.1
- c. Tree Preservation Plan – (none)
- d. Grading Plan – See sheet C1.20 – C1.30
- e. Utility Plan - See sheet C1.30
- f. Landscape Plan – See sheet L1.0
- g. Lighting Plan – See sheet 1 of 1
- h. Colored Elevations (None – there is no building proposed)
- j. Materials Board (None – there is no building proposed)

Index of AR Drawings:

Architectural	A1.1	site plan and details
	A1.2	site details
Civil	C0.00	cover sheet
	C 0.01	topographic survey
	C 0.02	construction notes & specifications
	C 1.10	site plan
	C 1.20	grading plan
	C1.21	grading plan enlargements
	C1.30	utility plan
	C1.40	erosion and sediment control plan cover sheet
	C1.41	clearing, demolition, mass grading erosion and sed control plan
	C1.42	utility & street construction grading & stabilization esc plan
	C1.43	erosion and sediment control details
	C5.10	civil details
	C5.11	civil details
R2.0	public water main extension - plan and profile	
R3.0	public water main extension - details	
Landscape	L1.0	landscape plan
	L2.0	landscape Details & Specifications
Site lighting	1 of 1	lighting level point by point calculation plan

3. Public Notice

- a. Documentation for Neighborhood Development Meeting
- b. Certification of Sign Posting (Installation after AR is accepted & I.D. provided)

4. Reports

- a. Transportation Impact Study
- b. Stormwater Management Report
- c. Existing Bridge – Field Evaluation Report


Hedges D – Fleet Parking Lot

11507 SW 115th Avenue (private street), Tualatin, OR 97062

1. General

- a. Land Use Application – Type II
- b. Narrative addressing all applicable approval criteria and standards
- c. Title Report
- d. Hydraulic Modeling Worksheet
- e. Service Provider letter from Clean Water Services.
- f. Service Provider letter/agreement from Republic Services

Land Use Application

Project Information		
Project Title: Hedges D - Fleet Parking Lot		
Brief Description: 349 stall fleet truck parking lot on an unimproved 9.447-acre property located at the west termination of SW 115th Avenue.		
Property Information		
Address: 11505 SW 115th Avenue		
Assessor's Map Number and Tax Lots: Map 190388317; Map Tax Lot 2S127BA00800; Prop ID R2198560		
Applicant/Primary Contact		
Name: Mac Martin	Company Name: Hedges D, an LLC	
Address: P. O. Box 15523		
City: Seattle	State: WA	ZIP: 98115
Phone: 206-399-6676	Email: MacMartinis@gmail.com	
Property Owner		
Name: Same		
Address:		
City:	State:	ZIP:
Phone:	Email:	
Property Owner's Signature: 	Date: 9/9/2020	
<i>(Note: Letter of authorization is required if not signed by owner)</i>		
AS THE PERSON RESPONSIBLE FOR THIS APPLICATION, I HEREBY ACKNOWLEDGE THAT I HAVE READ THIS APPLICATION AND STATE THAT THE INFORMATION IN AND INCLUDED WITH THIS APPLICATION IN ITS ENTIRETY IS CORRECT. I AGREE TO COMPLY WITH ALL APPLICABLE CITY AND COUNTY ORDINANCES AND STATE LAWS REGARDING BUILDING CONSTRUCTION AND LAND USE.		
Applicant's Signature:	Date:	

Land Use Application Type:

- | | | |
|--|---|---|
| <input type="checkbox"/> Annexation (ANN) | <input type="checkbox"/> Historic Landmark (HIST) | <input type="checkbox"/> Minor Architectural Review (MAR) |
| <input checked="" type="checkbox"/> Architectural Review (AR) | <input type="checkbox"/> Industrial Master Plan (IMP) | <input type="checkbox"/> Minor Variance (MVAR) |
| <input type="checkbox"/> Architectural Review—Single Family (ARSF) | <input type="checkbox"/> Plan Map Amendment (PMA) | <input type="checkbox"/> Sign Variance (SVAR) |
| <input type="checkbox"/> Architectural Review—ADU (ARADU) | <input type="checkbox"/> Plan Text Amendment (PTA) | <input type="checkbox"/> Variance (VAR) |
| <input type="checkbox"/> Conditional Use (CUP) | <input type="checkbox"/> Tree Removal/Review (TCP) | |

Office Use		
Case No:	Date Received:	Received by:
Fee:	Receipt No:	

Hedges D – Fleet Parking Lot

September 2020

11507 SW 115th Avenue, Tualatin, OR 97062

Architectural Review Narrative:

Project Description: The applicant, Hedges D, LLC, requests approval for an approximately 349 stall fleet truck parking lot on an unimproved 9.447-acre property located at the west termination of SW 115th Avenue. The parking lot fills the buildable portion of Lot 12; while the unbuildable Tract D, a sensitive area/vegetated corridor, remains. Access to the Hedges D fleet parking lot is from nearby SW Tualatin Sherwood Road, then east on SW 112th Street, west on SW Amu Street that turns into SW 115th street. You enter the property over an existing bridge over Hedges Creek that is partially on-site.

The Hedges D fleet parking lot is custom designed for the tenant’s trucks, which at approximately 27’ long are larger than typical passenger cars or vans. The parking lot is gated and fenced to prevent public access; and includes the usual parking amenities such as landscaping, pedestrian walks, and lighting. It also has a driver’s shelter, portable toilets, bike racks, and a dumpster enclosure. The parking lot is largely invisible from public view due to being surrounded by Hedges Creek and the large Hedges Creek Greenway setbacks that are largely wetlands or wetland buffers. To the east, the Machine Sciences building (aka Hedges C) screens Hedges D fleet parking from the only public street access on SW 115th Street.

The tenant predicts that the Hedges D parking lot could have a daily on-site presence from approximately 5:30AM – 10:30PM, with the first wave of drivers arriving about 6:30AM and the last driver wave departing to deliver packages about 1:00PM. Some drivers arrive onsite with their delivery trucks. Others access their onsite delivery vans using personal vehicles or via public transportation. Once at the fleet parking lot with their delivery trucks, drivers load and depart to deliver packages directly to customers. Due to the wide window of dispatch times from 6:30-12:30, the tenant expects no more than 40-50 vehicles to queue in place during a 30min interval, and the tenant will develop a mix of dispatch times to reduce offsite parking congestion and overall presence. To end the day, drivers park the delivery truck either on the Hedges D parking lot or at an offsite location, and those that leave trucks on-site depart using a personal vehicle or public transport.

Located on improved land in Franklin Industrial Park, Hedges D gets its name from the adjacent Hedges Creek. The “D” designates it as the fourth contiguous industrial project by this ownership team in Franklin Business Park. Hedges A & B are the adjacent phase 1 buildings in stained precast concrete walls and steel structure, and Perlo Construction occupies B. Hedges C is Phase 2, a large metal skinned structure occupied by Machine Sciences. and it largely screens the Hedges D parking lot from the nearest public street. The other contiguous building built by this ownership is Industry Restaurant, also part of phase 1 on Tualatin-Sherwood Road and SW 112th Avenue. This is a much smaller and more intimate building that is a popular restaurant also serving the area with a coffee shop and catering services.

This Architectural Review is in addition to the approved AR 19-0010 for an industrial building on this same lot. AR 19-0010 remains active in case the Fleet Parking project does not go forward.



Hedges A is a 2015 adjacent example of the development team's adjacent projects, showing the high quality of the work in concept and execution. This includes 12" stained precast concrete wall, substantial recessed windows for natural light and façade relief, quality lighting fixtures, substantial landscaping, and concrete drive entries and pedestrian paths. Lower soil bearing led the team to choose a lighter steel structure with metal skin for Hedges C, but the quality remains in a different material and aesthetic. Landscaping will be similar on Hedges D.



The Hedges D site on July 26, 2019 is top-of-image, that was taken when Hedges C (Machine Sciences) started site construction. The SW 115th Avenue access and bridge are to right, and Hedges Creek is left of Hedges C. The image is taken from the roof of Hedges B (Perlo Construction), and you can see a small portion of their parking on the bottom. The Machine Sciences building blocks public views of Hedges D fleet parking. Photo from Perlo Construction files.

Surrounding Uses: Surrounding uses are generally natural no-build areas, transitioning to include a variety of industrial uses

North: General Manufacturing (MG)

- One-story industrial buildings & storage yards

West: General Manufacturing (MG)

- Hedges Creek Greenway
- Undeveloped property

East: General Manufacturing (MG)

- SW 115th Street and water quality pond
- Two-story industrial building (Machine Sciences)

South: General Manufacturing (MG)

- Hedges Creek Greenway
- Undeveloped property

Previous Land Use Actions: The site has been subject to the following previous land use actions:

- SB-97-03 Franklin Business Park No. 4- Replat of a portion of Lot 4 recorded with Washington County as Document No. 2008010869
- PTA-99-06 Applied the Industrial Business Park Overlay (IBPO) District to the Franklin Business Park AR-99-23 Franklin Business Park Bldgs A, B & C (Withdrawn and not constructed)
- AR 19-0010 Architectural Review approval for an ±64,000sf industrial building on a 9.447 acre lot - the same lot 12 as this AR submittal. This permit remains active in case the Fleet Parking project does not go forward.

Project Schedule:

- A pre-application/scoping conference for this project was held November 2018 with Tualatin Planner Erin Engman attending.
- A neighborhood/developer meeting—as required by Tualatin Development Code (TDC) 31.063 was held on August 7th, 2020 via Zoom, and no one showed up for the meeting or participated. Meeting documentation is included in the submittal package.
- The proponent's plan is to obtain the relevant entitlement and building permits in 2020, and begin site work construction as soon as possible.

Applicable Criteria: The following Chapters of the Tualatin Development Code (TDC) are applicable to the subject proposal:

- B.** TDC Chapter 61: General Manufacturing Planning District
- C.** TDC Chapter 63: Industrial Uses & Utilities & Manufacturing Zones—Environmental Regulations
- D.** TDC Chapter 69: Industrial Business Park Overlay Planning District
- E.** TDC Chapter 72: Natural Resource Protection Overlay District
- F.** TDC Chapter 73: Community Design Standards
- G.** TDC Chapter 74: Public Improvement Requirements

TDC Chapter 61: General Manufacturing Planning District

CHAPTER 61 - GENERAL MANUFACTURING ZONE (MG)

TDC 61.100. - Purpose.

The purpose of this zone is to provide areas of the City that are suitable for a wide range of heavier manufacturing and processing activities, including those of a more intense nature and impact than the uses allowed in the Light Manufacturing (ML) Planning Zone. Industrial uses that are environmentally adverse or pose a hazard to life and safety are prohibited. A limited amount of commercial service and other support uses are permitted as regulated by the Commercial Services Overlay zone and the Limited Commercial Setback. **Acknowledge.**

TDC 61.200. - Use Categories.

(1) Use Categories. Table 61-1 lists use categories Permitted Outright (P) or Conditionally Permitted (C) in the MG zone.

Our anticipated use on the table (which is permitted outright):

- Vehicle Storage (note, we are out of Limited Commercial Setback).

TDC 61.210. - Additional Limitations on Uses.

(1) Sale of Goods Produced On-Site. The retail sale of goods produced on-site is permitted, provided that the retail sale area, including the showroom area, is no greater than five percent of the gross floor area of the building and does not exceed 1,500 square feet. **Acknowledge.**

TDC 61.300. - Development Standards.

Development standards in the MG zone are listed in Table 61-2. Additional standards may apply to some uses and situations, see TDC [61.310](#).

Lot Size & Dimensions: **Acknowledge** – we meet the standards.

Minimum Setbacks: **Acknowledge** – we easily meet the standards because of the sensitive area/vegetated corridors that surround our site.

Structure Height: **Acknowledge** – we easily meet the standards.

TDC 61.310. - Additional Development Standards.

(1) Outdoor Uses. All uses must be conducted wholly within a completely enclosed building, except off-street parking and loading, **Acknowledge.**

TDC Chapter 63: INDUSTRIAL USES AND UTILITIES AND MANUFACTURING ZONES— ENVIRONMENTAL REGULATIONS

TDC 63.010. - Purpose. The purpose of this section is to protect the public health, safety and general welfare by applying environmental regulations to all industrial uses and utilities, and manufacturing planning districts in the City. These environmental regulations are also intended to protect natural areas from the adverse effects of industrial development. It is intended that the following standards provide statutory authority for the enforcement of regulations relating to noise, vibration, air quality, odors, heat, glare and lighting, storage and stored materials, liquid and solid waste materials, and dangerous substances.

TDC 63.020. - Applicability. The regulations of this Chapter apply to:

(1) All industrial uses and utilities, regardless of the Planning District in which they are located, and

(2) All Manufacturing Planning Districts, regardless of the use category. **Acknowledge.**

TDC 63.051. - Noise. All uses and development must comply with the Oregon State Department of Environmental Quality standards relating to noise and the City of Tualatin noise ordinance in, TMC 6-14. **Acknowledge, the tenant is not known at this time so it is difficult to address specifically.**

TDC 63.052. - Vibration. Restrictions. All uses and development must not cause or permit ground vibration into the property of another person that exceeds the limits set forth below in this section (not included). **Acknowledge.**

TDC 63.053 - Air Quality.

(1) Restrictions. All uses and development must comply with the most recent air quality standards adopted by the Oregon Department of Environmental Quality. Plans of construction and operations must comply with the recommendations and regulations of the State Department of Environmental Quality. **Acknowledge.**

(2) Method of Measurement. All measurements of air pollution must be by the procedures and with equipment approved by the State Department of Environmental Quality or equivalent and acceptable methods or measurement approved by the City. Upon request of the City, persons responsible for a suspected source of air pollution must provide quantitative and qualitative information regarding the discharge that will adequately and accurately describe operation conditions.

Acknowledge.

TDC 63.054. - Odors. All uses and development must not emit odors in such quantities as to create a nuisance condition at any point beyond the subject property line of the emitting use. **Acknowledge.**

TDC 63.055. - Heat and Glare.

(1) All uses and development must conduct all operations producing heat or glare entirely within an enclosed building.

(2) All uses and development may utilize exterior lighting, but the exterior lighting must be screened, baffled or directed away from residential planning districts. **Acknowledge.** Our exterior lighting fixtures all include glare cut-off baffles. **TDC 63.056. - Storage and Stored Materials.**

(1) All uses and development must store all materials, including wastes, in a manner that will not attract or aid the propagation of insects or rodents, or in any other way create a health or safety hazard. **Acknowledge.**

(2) All uses and development that utilize open storage that would otherwise be visible at the property line must conceal it from view at the abutting property line by a sight obscuring fence not less than six feet high and not accessible to the general public to protect public safety. **Acknowledge.** No open storage is requested.

TDC 63.057. - Liquid or Solid Waste Materials.

All uses and development are prohibited from disposing waste onto the site or into adjacent drainage ditches, creeks or other natural waterways in violation of State of Oregon DEQ standards, Clean Water Services Standards, City Standards, or in a manner that causes harm to wildlife. **Acknowledge.**

TDC 63.058. - Dangerous Substances.

All uses and development are prohibited from the storage, transfer, or processing of hazardous, toxic, or radioactive waste. **Acknowledge.**

TDC Chapter 69: Industrial Business Park Overlay Planning District

TDC 69.010. - Purpose. The purpose of this district is to recognize and accommodate the changing Industrial Commercial marketplace by allowing mixed uses within the context of an enforceable Master Plan reviewed and approved during Architectural Review. Industrial uses are emphasized, but office and selected service and retail uses are allowed through the operation of the Industrial Business Park Overlay District. A second purpose of this district is to recognize that it is not necessarily appropriate to assume that all industrial, office, service and retail uses are incompatible and, therefore, must be separated based on planning districts. The Industrial Business Park Overlay District allows flexibility in the uses permitted for selected General Manufacturing (MG) District areas. Further, the purpose of this district is to allow selected retail and service uses that are supportive of and secondary to the industrial and office uses.

TDC 69.040. - Implementation of the Industrial Business Park Overlay District. At the time of application for Architectural Review, the applicant shall state in writing if the proposed project is to be developed under the provisions of the Industrial Business Park Overlay District. Selection of the overlay district is at the option of the developer and application of the overlay district shall be implemented upon the developer's statement as part of the Architectural Review application. No public hearing shall be held to decide to apply the overlay district. The overlay district shall only be used in conjunction with the selected MG District areas. The Architectural Review decision may include conditions of approval in accordance with TDC 73.055. The proponent acknowledges this section, and declines to have this project developed under the provisions of this overlay district.

TDC Chapter 72: Natural Resource Protection Overlay District (NPRO)

TDC 72.010. - Purpose.

(1) To identify and protect by preservation and conservation the designated significant natural resources and Other Natural Areas. The designated significant natural resources are greenways and natural areas, which include the riparian areas and scenic areas of the Tualatin River and certain creeks and drainage swales, wetlands, upland forests, meadows, fish and wildlife resources, and the geologic features of the Tonquin Scablands. Significant Natural Resources are identified on the Significant Natural Resource List and Map TDC 72.013 and Map 72-3, TDC). The significant natural resources designated for protection are shown on Map 72-1, TDC. Other Natural Areas are identified on Figure 3-4 of the Parks and Recreation Master Plan. Our 4.45-acre Tract D is recognized as a sensitive area/vegetated corridor, which must be preserved. The owners propose that Clean Water Services improve and maintain the vegetated corridor using their fee-in-lieu process. The owners also propose that they landscape and maintain the sensitive (or buffer) area portion (adjacent to lot 12) after receiving approval from Clean Water Services on the landscape plan. At AR submittal we are not proposing landscaping on Tract D, pending discussions with Clean Water Services on this proposal.

(2) To provide sufficient area for stormwater runoff to reduce flood hazards and enhance water quality. **Acknowledge.**

(3) To provide public access to scenic and riparian areas, where appropriate, by designating pedestrian and bicycle path locations. **Acknowledge.**

(4) To provide specific design standards for development adjacent to, and within, greenways and natural areas in order to preserve and conserve them, and provide mechanisms for the granting of easements or dedications for Greenways, and Natural Areas while allowing reasonable economic development of property adjacent to the greenways and natural areas.

Acknowledge.

TDC 72.056. - Vegetated Corridors of Sensitive Areas. Lands subject to these regulations are also subject to the regulations in the Unified Sewage Agency's Design and Construction Standards. **Acknowledge.**

TDC 72.060. - Development Restrictions in Greenways and Natural Areas.

(1) Except as provided in Subsection (2), no building, structure, grading, excavation, placement of fill, vegetation removal, impervious surface, use, activity or other development shall occur within Riverbank, Creek and Other Greenways, and Wetland and Open Space Natural Areas. **Acknowledge.**

(2) The following uses, activities and types of development are permitted within Riverbank, Creek and Other Greenways, and Wetland and Open Space Natural Areas provided they are designed to minimize intrusion into riparian areas:

(a) Public bicycle or pedestrian ways, subject to the provisions of TDC [72.070](#). **We will work with CWS on possible pedestrian recreation paths in the sensitive area as a possible amenity.**

(b) Public streets, including bridges, when part of a City approved transportation plan, and public utility facilities, (f) Landscaping, when part of a landscape plan approved through the Architectural Review process. City initiated landscape projects are exempt from the Architectural Review process. Landscaping in Greenways and Natural Areas shall comply with the approved Plant List in the Parks and Recreation Master Plan. When appropriate, technical advice shall be obtained from the Oregon Department of Fish and Wildlife, U.S. Soil Conservation Service, or similar agency, to ensure the proposed landscaping will enhance the preservation of any existing fish or wildlife habitats in the vicinity. **Acknowledge.**

(g) Wildlife protection and enhancement, including the removal of non-native vegetation and replacement with native plant species. **Acknowledge.**

(h) Except in Wetland Natural Areas, public boating facilities, irrigation pumps, water-related and water-dependent uses including the removal of vegetation necessary for the development of water-related and water-dependent uses, and replacement of existing structures with structures in the same location that do not disturb additional riparian surface. **Acknowledge.**

(i) In Wetland Natural Areas, perimeter mowing and other cutting necessary for hazard prevention.

(3) The City may, through the subdivision, conditional use, architectural review, or other development approval process, attach appropriate conditions to approval of a development permit. Such conditions may include, but are not limited to:

(a) Use of Greenways and Natural Areas for storm drainage purposes; **Acknowledge.**

(b) Location of approved landscaping, pedestrian and bike access areas, and other non-building uses and activities in Greenways and Natural Areas; **Acknowledge.**

(c) Setback of proposed buildings, parking lots, and loading areas away from the Greenway and Natural Area boundary. **Acknowledge.**

(4) Greenways and Natural Areas in which an access easement is owned by the City, but retained in private ownership, shall be maintained by the property owner in their natural state and may only be modified if a landscape and maintenance plan complies with the approved Plant List in the Parks and Recreation Master Plan, and has been approved through the Architectural Review process or by the Parks and Recreation Director when Architectural Review is not required.

Acknowledge.

(5) The Parks and Recreation Director shall be included as a commentor when a development application proposes dedication of Greenway or Natural Area property to the City or when development is pro-posed on Greenway or Natural Areas property maintained by the Parks and Recreation Department. **Acknowledge.**

TDC 72.070. - General Guidelines for Pedestrian and Bike Paths in Greenways. To construct bike and pedestrian paths in greenways, the developer of the path shall adhere to the following guidelines, wherever practicable: **Acknowledge. We no intentions to construct bike or pedestrian paths in Tract D.**

TDC 72.085. - Landscaping Credit within Commercial and Industrial Planning Districts Adjacent to Greenways and Natural Areas.

(1) When a property owner in a Commercial, Institutional, or Industrial Planning District dedicates to the City a portion of the NRPO District, an Other Natural Area or vegetated corridor located within or adjacent to the NRPO District in accordance with a City-approved landscape plan, a Greenway and Natural Area Landscaping Credit shall be applied toward a portion of the site's percentage landscaping requirement. **We are taking the landscape percentage credit – see our calculations.**

(2) The amount of the Greenway and Natural Area Landscaping Credit shall be as provided in TDC Chapter 73. The applicant must meet all landscaping requirements in this Code to the satisfaction of the Planning Director through the Architectural Review process. **Acknowledge.**

TDC 72.090. - Reduction in Setback Requirements. When a property owner in a IN, CO, CR, CO/MR, ML, or MG Planning District dedicates to the City land in the NRPO District or Other Natural Area, a bikeway or pedestrian path facility, or a vegetated corridor located within or adjacent to the NRPO District, the minimum front yard setback may be reduced through the AR process as provided in Chapters 50, 51, 52, 55, 60, and [61](#). **Acknowledge, and we are not requesting setback reduction.**

TDC 72.120. - Wetlands Protection District. In cases where land within the NRPO District is also within the Wetlands Protection District, [Chapter 71](#), any development permitted by TDC [72.060](#) shall be subject to the provisions of [Chapter 71](#). **Acknowledge. We are working with Clean Water Services on Tract D per our response on TDC 72.010 above.**

TDC 72.150. - Modifications for Storm Drainage Improvements. Nothing in this chapter shall prohibit the City or any property owner from altering, enlarging, straightening, piping, or otherwise modifying a creek channel in the NRPO District upon a finding by the City Engineer that such modification is necessary for maintaining the ability of the creek to transmit storm water run-off. **Acknowledge.**

General Purpose and Objectives of Site and Building Design Standards

TDC 73A.010. - Site and Building Design Standards Purpose and Objectives.

(1) Purpose. The purpose of the site and building design objectives and standards found in TDC [73A](#) through TDC [73G](#) is to promote functional, safe, innovative, and attractive sites and buildings that are compatible with the surrounding environment, including, but not limited to:

(a) The building form, articulation of walls, roof design, materials, and placement of elements such as windows, doors, and identification features; and Following high quality previous developments with buildings in Tualatin and Wilsonville by this owner, this proposal is for a fleet parking lot. **This section is not applicable.**

(b) The placement, design, and relationship of proposed site elements such as buildings, vehicular parking, circulation areas, bikeways and bike parking, accessways, walkways, buffer areas, and landscaping. This is a destination site not seen from a public street and surrounded by landscaping and will be around 50% in landscaping. This section is largely not applicable.

(2) Objectives. The objectives of site and building design standards in TDC [73A](#) through TDC [73G](#) are to:

(a) Enhance Tualatin through the creation of attractively designed development and streetscapes;

(b) Encourage originality, flexibility, and innovation in building design; **This proposal is for a fleet parking lot. This section is not applicable.**

(c) Create opportunities for, or areas of, visual and aesthetic interest for occupants and visitors to the site;

(d) Provide a composition of building elements which responds to function, land form, identity and image, accessibility, orientation and climatic factors;

(e) Conserve, protect, and restore fish and wildlife habitat areas, and maintain or create visual and physical corridors to adjacent fish and wildlife habitat areas; See TDC 72.010., 1.

(f) Enhance energy efficiency through the use of landscape and architectural elements; and

(g) Minimize disruption of natural site features such as topography, trees, and water features. There are no existing trees to preserve. See TDC 72.010., 1.

Industrial Design Standards

TDC 73A.400. - Industrial Design Standards.

The following standards are minimum requirements for commercial development in all zones:

(1) Walkways. Commercial development must provide walkways as follows:

(a) Walkways must be a minimum of five feet in width; We provide the minimum 5' of width plus the allowance for car overhangs.

(b) Walkways must be constructed of asphalt, concrete, or a pervious surface such as pavers or grasscrete (not gravel or woody material); Ours are proposed as asphalt with contrasting paint striping to distinguish from vehicle paving.

(c) Walkways must meet ADA standards applicable at time of construction or alteration; We comply.

(e) Walkways through parking areas, drive aisles, and loading areas must be visibly raised and of a different appearance than the adjacent paved vehicular areas; We comply and slopes are modest.

(f) Walkways through parking areas, drive aisles, and loading areas must be of a different appearance than the adjacent paved vehicular areas; and We comply. Walkways are proposed as stamped asphalt to distinguish from vehicle paving.

(g) Outdoor Recreation Access Routes must be provided between the development's walkway and bikeway circulation system and parks, bikeways and greenways where a bike or pedestrian path is designated. With no adjoining public ROW, bikes will use on-site private drives and serve only as access for fleet parking drivers.

(4) Safety and Security. Industrial development must provide safety and security features as follows:

(a) Locate windows and provide lighting in a manner that enables tenants, employees, and police to watch over pedestrian, parking, and loading areas; **Not applicable – no building proposed.**

(b) Locate windows and interior lighting to enable surveillance of interior activity from the public right-of-way; **Not applicable – no building proposed.**

(c) Locate, orient, and select exterior lighting to facilitate surveillance of on-site activities from the public right-of-way without shining into public rights-of-way or fish and wildlife habitat areas; **We comply – see our exterior lighting plan.**

(d) Provide an identification system which clearly locates buildings and their entries for patrons and emergency services; and **Not Applicable as there is no building, but the tenant will add directional signs for the fleet parking use, which is closed to the public.**

(e) Above ground sewer or water pumping stations, pressure reading stations, water reservoirs, electrical substations, and above ground natural gas pumping stations must provide a minimum six foot tall security fence or wall. **Acknowledge.**

(5) Service, Delivery, and Screening. Industrial development must provide service, delivery, and screening features as follows:

(a) Above grade and on-grade electrical and mechanical equipment such as transformers, heat pumps and air conditioners must be screened with sight obscuring fences, walls or landscaping; **Acknowledge.**

(b) Outdoor storage must be screened with a sight obscuring fence, wall, berm or dense evergreen landscaping; and **Acknowledge – no outdoor storage proposed.**

(c) Above ground pumping stations, pressure reading stations, water reservoirs; electrical substations, and above ground natural gas pumping stations must be screened with sight-obscuring fences or walls and landscaping. **Acknowledge.**

(6) Adjacent to Transit. Industrial development adjacent to transit must comply with the following; **No adjacent transit.**

CHAPTER 73B - LANDSCAPING STANDARDS

TDC 73B.010. - Landscape Standards Purpose and Objectives.

(1) Purpose. The purpose of this Chapter is to establish standards for landscaping within Tualatin in order to enhance the environmental and aesthetic quality of the City.

(2) Objectives. The objectives of this Chapter are to: **Acknowledge all.**

(a) Encourage the retention and protection of existing trees and requiring the planting of trees in new developments;

(b) Use trees and other landscaping materials to temper the effects of the sun, wind, noise, and air pollution.

(c) Use trees and other landscaping materials to define spaces and the uses of specific areas; and

(d) Use trees and other landscaping materials as a unifying element within the urban environment.

TDC 73B.020. - Landscape Area Standards Minimum Areas by Use and Zone. The following are the minimum areas required to be landscaped for each use and zone:

Zone	Minimum Area Requirement*	Minimum Area Requirement with dedication for a fish and wildlife habitat*
(3) CO, CR, CC, CG, ML and MG zones except within the Core Area Parking District—All uses	15 percent of the total area to be developed	12.5 percent of the total area to be developed

Zone	Minimum Area Requirement*	Minimum Area Requirement with dedication for a fish and wildlife habitat*
(6) Industrial Business Park Overlay District and MBP—must be approved through Industrial Master Plans	20 percent of the total area to be developed	Not applicable
* For properties within the Hedges Creek Wetland Protection District which have signed the "Wetlands Mitigation Agreement," the improved or unimproved wetland buffer area may reduce the required landscaping to 12.5 percent as long as all other landscape requirements are met. We will accept this reduction & meet the other landscape requirements.		

TDC 73B.050. - Additional Minimum Landscaping Requirements for Industrial Uses.

(1) General. In addition to requirements in TDC [73B.020](#), industrial uses must comply with the following:

(a) All areas not occupied by buildings, parking spaces, driveways, drive aisles, pedestrian areas, or undisturbed natural areas must be landscaped. We will comply on Lot 12.

(i) This standard does not apply to areas subject to the Hedges Creek Wetlands Mitigation Agreement.

Our 4.45-acre Tract D is recognized as a sensitive area/vegetated corridor, which must be preserved. The owners propose that Clean Water Services improve and maintain the vegetated corridor using their fee-in-lieu process. The owners also propose that they landscape and maintain the sensitive (or buffer) area portion (adjacent to lot 12) after receiving approval from Clean Water Services on the landscape plan. At AR submittal we are not proposing landscaping on Tract D, pending discussions with Clean Water Services on this proposal.

(b) Minimum 5-foot-wide landscaped area must be located along all building perimeters viewable by the general public from parking lots or the public right-of-way, but the following may be used instead of the 5-foot-wide landscaped area requirement: We comply.

(i) Pedestrian amenities such as landscaped plazas and arcades; and

(ii) Areas developed with pavers, bricks, or other surfaces, for exclusive pedestrian use and contain pedestrian amenities, such as benches, tables with umbrellas, children's play areas, shade trees, canopies.

(c) Five-foot-wide landscaped area requirement does not apply to:

(i) Loading areas,

(ii) Bicycle parking areas,

(iii) Pedestrian egress/ingress locations, and

(iv) Where the distance along a wall between two vehicle or pedestrian access openings (such as entry doors, garage doors, carports and pedestrian corridors) is less than eight feet.

TDC 73B.070. - Minimum Landscaping Standards for All Zones. The following are minimum standards for landscaping for all zones.

(1) Required Landscape Areas Acknowledge all.	<ul style="list-style-type: none"> • Must be designed, constructed, installed, and maintained so that within three years the ground must be covered by living grass or other plant materials. • The foliage crown of trees cannot be used to meet this requirement. • A maximum of ten percent of the landscaped area may be covered with un-vegetated areas of bark chips, rock or stone. • Must be installed in accordance with the provisions of the American National Standards Institute ANSI A300 (Part 1) (Latest Edition). • Must be controlled by pruning, trimming, or otherwise so that: It will not interfere with designated pedestrian or vehicular access; and It will not constitute a traffic hazard because of reduced visibility.
(2) Fences None proposed.	<ul style="list-style-type: none"> • Landscape plans that include fences must integrate any fencing into the plan to guide wild animals toward animal crossings under, over, or around transportation corridors.
(3) Tree Preservation Acknowledge all.	<ul style="list-style-type: none"> • Trees and other plant materials to be retained must be identified on the landscape plan and grading plan. • During construction: <ul style="list-style-type: none"> ○ Must provide above and below ground protection for existing trees and plant materials identified to remain; ○ Trees and plant materials identified for preservation must be protected by chain link or other sturdy fencing placed around the tree at the drip line;

	<ul style="list-style-type: none"> ○ If it is necessary to fence within the drip line, such fencing must be specified by a qualified arborist; ○ Top soil storage and construction material storage must not be located within the drip line of trees designated to be preserved; ○ Where site conditions make necessary a grading, building, paving, trenching, boring, digging, or other similar encroachment upon a preserved tree's drip-line area, such grading, paving, trenching, boring, digging, or similar encroachment must only be permitted under the direction of a qualified arborist. Such direction must assure that the health needs of trees within the preserved area can be met; and ○ Tree root ends must not remain exposed. <ul style="list-style-type: none"> ● Landscaping under preserved trees must be compatible with the retention and health of the preserved tree. ● When it is necessary for a preserved tree to be removed in accordance with TDC 33.110 (Tree Removal Permit) the landscaped area surrounding the tree or trees must be maintained and replanted with trees that relate to the present landscape plan, or if there is no landscape plan, then trees that are complementary with existing, landscape materials. Native trees are encouraged ● 100 percent of the area preserved under any tree or group of trees (Except for impervious surface areas) retained in the landscape plan must apply directly to the percentage of landscaping required for a development
(4) Grading Acknowledge all.	<ul style="list-style-type: none"> ● After completion of site grading, top-soil is to be restored to exposed cut and fill areas to provide a suitable base for seeding and planting. ● All planting areas must be graded to provide positive drainage. ● Soil, water, plant materials, mulch, or other materials must not be allowed to wash across roadways or walkways. ● Impervious surface drainage must be directed away from pedestrian walkways, dwelling units, buildings, outdoor private and shared areas and landscape areas except where the landscape area is a water quality facility.
(5) Irrigation Acknowledge all.	<ul style="list-style-type: none"> ● Landscaped areas must be irrigated with an automatic underground or drip irrigation system.
(6) Re-vegetation in Un-landscaped Areas Acknowledge all.	<ul style="list-style-type: none"> ● Vegetation must be replanted in all areas where vegetation has been removed or damaged in areas not affected by the landscaping requirements and that are not to be occupied by structures or other improvements. ● Plant materials must be watered at intervals sufficient to ensure survival and growth for a minimum of two growing seasons. ● The use of native plant materials is encouraged to reduce irrigation and maintenance demands. ● Disturbed soils should be amended to an original or higher level of porosity to regain infiltration and stormwater storage capacity.

TDC 73B.080. - Minimum Standards Trees and Plants.

The following minimum standards apply to the types of landscaping required to be installed for all zones.

(1) Deciduous Shade Trees Acknowledge all.	<ul style="list-style-type: none"> ● One and on-half inch caliper measured six inches above ground; ● Balled and burlapped; bare root trees will be acceptable to plant during their dormant season; Reach a mature height of 30 feet or more; ● Cast moderate to dense shade in summer; ● Live over 60 years; ● Do well in urban environments, tolerant of pollution and heat, and resistant to drought; ● Require little maintenance and mechanically strong; ● Insect- and disease-resistant; ● Require little pruning; and ● Barren of fruit production.
--	---

(2) Deciduous Ornamental Trees Acknowledge all.	<ul style="list-style-type: none"> One and on-half inch caliper measured six inches above ground; balled and burlapped; bare root trees will be acceptable to plant during their dormant season; and Healthy, disease-free, damage-free, well-branched stock, characteristic of the species
(3) Coniferous Tree Acknowledge all.	<ul style="list-style-type: none"> Five feet in height above ground; Balled and burlapped; bare root trees will be acceptable to plant during their dormant season; and Healthy, disease-free, damage-free, well-branched stock, characteristic of the species.
(4) Evergreen and Deciduous Shrubs Acknowledge all.	<ul style="list-style-type: none"> One to five gallon size; Healthy, disease-free, damage-free, well-branched stock, characteristic of the species; and Side of shrub with best foliage must be oriented to public view.
(5) Groundcovers Acknowledge all.	<ul style="list-style-type: none"> Fully rooted; Well branched or leafed; Healthy, disease-free, damage-free, well-branched stock, characteristic of the species; and English ivy (<i>Hedera helix</i>) is prohibited.
(6) Lawns Acknowledge all.	<ul style="list-style-type: none"> Consist of grasses, including sod, or seeds of acceptable mix within the local landscape industry; 100 percent coverage and weed free; and Healthy, disease-free, damage-free, characteristic of the species.

CHAPTER 73C - PARKING STANDARD

In General

Parking Lot Landscaping

TDC 73C.010. - Off-Street Parking and Loading Applicability and General Requirements.

(1) *Applicability.* Off-street parking and loading is required to be provided by the owner and/or developer, in all zones, whenever the following occurs:

(a) *Establishment of a new structure or use; Acknowledge. Our use is fleet parking.*

(2) *General Requirements.* Off-street parking spaces, off-street vanpool and carpool parking spaces, off-street bicycle parking, and off-street loading berths must be as provided as set forth in TDC [73C.100](#), unless greater requirements are otherwise established by the conditional use permit or the Architectural Review process. **Acknowledge all below in this section – except as noted:**

(a) *The following apply to property and/or use with respect to the provisions of TDC [73C.100](#):*

(i) *The requirements apply to both the existing structure and use, and enlarging a structure or use; Our use is fleet parking.*

(ii) *The floor area is measured by gross floor area of the building primary to the function of the particular use of the property other than space devoted to off-street parking or loading;*

(iii) *Where employees are specified, the term applies to all persons, including proprietors, working on the premises during the peak shift;*

(iv) *Calculations to determine the number of required parking spaces and loading berths must be rounded to the nearest whole number;*

(v) *If the use of a property changes, thereby increasing off-street parking or loading requirements, the increased parking/loading area must be provided prior to commencement of the new use;*

(vi) *Parking and loading requirements for structures not specifically listed herein must be determined by the City Manager, based upon requirements of comparable uses listed;*

(vii) *When several uses occupy a single structure, the total requirements for off-street parking may be the sum of the requirements of the several uses computed separately or be computed in accordance with TDC 73.370(1)(m), Joint Use Parking;*

(ix) *Required parking spaces must be available for the parking of operable passenger automobiles of residents, customers, patrons and employees and must not be used for storage of vehicles or materials or for the parking of trucks used in conducting the business;*

(xi) *Required vanpool and carpool parking must meet the 9-foot parking stall standards in Figure 73-1 and be identified with appropriate signage.*

TDC 73C.020. - Parking Lot Design Standards. A parking lot, whether an accessory or principal use, intended for the parking of automobiles or trucks, must comply with the following: **Acknowledge all below in this section – we have added a few clarifications:**

(1) *Off-street parking lot design must comply with the dimensional standards set forth in Figure 73-1; Our fleet trucks are larger than passenger vehicles, so our stalls and drive aisles are larger to comply with tenant requirements.*

(2) *Parking lot drive aisles must be constructed of asphalt, concrete, or pervious concrete;*

(3) *Parking stalls must be constructed of asphalt, concrete, pervious concrete, or a pervious surface such as pavers or grasscrete, but not gravel or woody material. Pervious surfaces, are encouraged for parking stalls in or abutting the Natural Resource Protection Overlay District, Other Natural Areas, or in a Clean Water Services Vegetated Corridor;*

(4) *Parking lots must be maintained adequately for all-weather use and drained to avoid water flow across sidewalks;*

(5) *Parking bumpers or wheel stops or curbing must be provided to prevent cars from encroaching on adjacent landscaped areas, or adjacent pedestrian walkways.*

(6) *Disability parking spaces and accessibility must meet ADA standards applicable at time of construction or alteration;*

(7) *Parking stalls for sub-compact vehicles must not exceed 35 percent of the total parking stalls required by TDC [73C.100](#). Stalls in excess of the number required by TDC [73C.100](#) can be sub-compact stalls;*

(8) *Groups of more than four parking spaces must be so located and served by driveways that their use will require no backing movements or other maneuvering within a street right-of-way other than an alley;*

(9) *Drives to off-street parking areas must be designed and constructed to facilitate the flow of traffic, provide maximum safety of traffic access and egress, and maximum safety of pedestrians and vehicular traffic on the site;*

(10) *On-site drive aisles without parking spaces, which provide access to parking areas with regular spaces or with a mix of regular and sub-compact spaces, must have a minimum width of 22 feet for two-way traffic and 12 feet for one-way traffic; When 90 degree stalls are located on both sides of a drive aisle, a minimum of 24 feet of aisle is required. On-site drive aisles without parking spaces, which provide access to parking areas with only sub-compact spaces, must have a minimum width of 20 feet for two-way traffic and 12 feet for one-way traffic;*

(11) *Artificial lighting, must be deflected to not shine or create glare in a residential zones, street right-of-way, a Natural Resource Protection Overlay District, Other Natural Areas, or a Clean Water Services Vegetated Corridor; Our site lighting has glare control devices so our lighting does not intrude into our Clean Water Services Vegetated Corridor – see our lighting plan.*

(12) *Parking lot landscaping must be provided pursuant to the requirements of TDC [73C.200](#); and*

(13) *Except for parking to serve residential uses, parking areas adjacent to or within residential zones or adjacent to residential uses must be designed to minimize disturbance of residents. We are not adjacent to residential zones. TDC [73C.050](#). - **Bicycle Parking Requirements and Standards.***

(1) *Requirements. Bicycle parking facilities must include:*

(a) *Long-term parking that consists of covered, secure stationary racks, lockable enclosures, or rooms in which the bicycle is stored;*

(i) *Long-term bicycle parking facilities may be provided inside a building in suitable secure and accessible locations. **We propose bike racks for truck drivers only, as public access is prohibited.***

(b) *Short-term parking provided by secure stationary racks (covered or not covered), which accommodate a bicyclist's lock securing the frame and both wheels. **Same.***

(2) *Standards. Bicycle parking must comply with the following: **Acknowledge all in this section on standards.***

(a) *Each bicycle parking space must be at least six feet long and two feet wide, with overhead clearance in covered areas must be at least seven feet;*

(b) *A five-foot-wide bicycle maneuvering area must be provided beside or between each row of bicycle parking. It must be constructed of concrete, asphalt, or a pervious hard surface such as pavers or grasscrete, and be maintained;*

(c) *Access to bicycle parking must be provided by an area at least three feet in width. It must be constructed of concrete, asphalt, or a pervious hard surface such as pavers or grasscrete, and be maintained;*

(d) *Bicycle parking areas and facilities must be identified with appropriate signing as specified in the Manual on Uniform Traffic Control Devices (MUTCD) (latest edition). At a minimum, bicycle parking signs must be located at the main entrance and at the location of the bicycle parking facilities;*

(e) *Bicycle parking must be located in convenient, secure, and well-lighted locations approved through the Architectural Review process. Lighting, which may be provided, must be deflected to not shine or create glare into street rights-of-way or fish and wildlife habitat areas;*

(f) *Required bicycle parking spaces must be provided at no cost to the bicyclist, or with only a nominal charge for key deposits, etc. This does not preclude the operation of private for-profit bicycle parking businesses;*

(h) The City Manager or the Architectural Review Board may approve a form of bicycle parking not specified in these provisions but that meets the needs of long-term and/or short-term parking pursuant to Architectural Review.

TDC 73C.100. - Off-Street Parking Minimum/Maximum Requirements.

(1) The following are the minimum and maximum requirements for off-street motor vehicle parking in the City, except these standards do not apply in the Core Area Parking District. The Core Area Parking District standards are in TDC 73C.110.

USE	MINIMUM MOTOR VEHICLE PARKING	MAXIMUM MOTOR VEHICLE PARKING	BICYCLE PARKING	PERCENTAGE OF BICYCLE PARKING
e) Commercial				
(vi) General office	2.70 spaces per 1,000 square feet of gross floor area	Zone A: 3.4 spaces per 1,000 square feet of gross floor area Zone B: 4.1 spaces per 1,000 square feet of gross floor area	2, or 0.50 spaces per 1,000 gross square feet, whichever is greater	First ten spaces or 40 percent, whichever is greater
f) Industrial				
(i) Manufacturing	1.60 spaces per 1,000 sf of gross floor area	None	2, or 0.10 spaces per 1,000 gross sf, whichever is greater	First five spaces or 30 percent, whichever is greater
(ii) Warehousing	0.30 spaces per 1,000 sf of gross floor area	Zone A: 0.4 spaces per 1,000 square feet of gross floor area Zone B: 0.5 spaces per 1,000 square feet of gross floor area	2, or 0.10 spaces per 1,000 gross square feet, whichever is greater	First five spaces or 30 percent, whichever is greater

None of this table is applicable to fleet parking.

(2) In addition to the general parking requirements in subsection (1), the following are the minimum number of off-street vanpool and carpool parking for commercial, institutional, and industrial uses. **Not applicable to fleet parking.**

TDC 73C.130. - Parking Lot Driveway and Walkway Minimum Requirements. Parking lot driveways and walkways must comply with the following requirements:

(3) Industrial Use. Ingress and egress for industrial uses must not be less than the following:

Required Parking Spaces	Minimum Number Required	Minimum Pavement Width	Minimum Pavement Walkways, etc.
1-250	1	36 feet for first 50' from ROW, 24 feet thereafter	No curbs or walkway required

This section does not apply because our site is accessed from a private drive and our lot is 400' west of the nearest ROW. That said, our access is excellent because you drive straight into the site with excellent visibility of other vehicles.

TDC 73C.200. - Parking Lot Landscaping Standards Purpose and Applicability.

(1) Purpose. The goals of the off-street parking lot standards are to create shaded areas in parking lots, to reduce glare and heat buildup, provide visual relief within paved parking areas, emphasize circulation patterns, reduce the total number of spaces, reduce the impervious surface area and stormwater runoff, and enhance the visual environment. The design of the off-street parking area must be the responsibility of the developer and should consider visibility of signage, traffic circulation, comfortable pedestrian access, and aesthetics. **Acknowledge.**

(2) Applicability. Off-street parking lot landscaping standards apply to any surface vehicle parking or circulation area. **Acknowledge.**

TDC 73C.230. - Industrial Parking Lot Landscaping Requirements. Industrial uses must comply with the following landscaping requirements for parking lots in all zones.

(1) General. Locate landscaping or approved substitute materials in all areas not necessary for vehicular parking and maneuvering. **Acknowledge.**

- (2) *Clear Zone.* Clear zone required for the driver at ends of on-site drive aisles and at driveway entrances, vertically between a maximum of 30 inches and a minimum of eight feet as measured from the ground level. **Acknowledge.**
- (3) *Perimeter.* Minimum five feet in width in all off-street parking and vehicular circulation areas, including loading areas and must comply with the following: **Acknowledge all in this section.**
- (a) Deciduous trees located not more than 30 feet apart on average as measured on center;
 - (b) Shrubs or ground cover, planted so as to achieve 90 percent coverage within three years;
 - (c) Plantings which reach a mature height of 30 inches in three years which provide screening of vehicular headlights year round;
 - (d) Native trees and shrubs are encouraged; and
 - (e) Exception: Not required where off-street parking areas on separate lots are adjacent to one another and connected by vehicular access.
- (4) *Landscape Island.* Minimum 25 square feet per parking stall must be improved with landscape island areas and must comply with the following. **Acknowledge all in this section.**
- (a) May be lower than the surrounding parking surface to allow them to receive stormwater run-off and function as water quality facilities as well as parking lot landscaping;
 - (b) Must be protected from vehicles by curbs, but the curbs may have spaces to allow drainage into the islands;
 - (c) Islands must be utilized at aisle ends to protect parked vehicles from moving vehicles and emphasize vehicular circulation patterns;
 - (d) Landscape separation required for every eight continuous spaces in a row;
 - (e) Must be planted with one deciduous shade trees for every four parking spaces; Required trees must be evenly dispersed throughout the parking lot;
 - (f) Must be planted with groundcover or shrubs;
 - (g) Native plant materials are encouraged;
 - (h) Landscape island areas with trees must be a minimum of five feet in width (from inside of curb to curb);
 - (i) Required plant material in landscape islands must achieve 90 percent coverage within three years; and
 - (j) Exception: Landscape square footage requirements do not apply to parking structures and underground parking.
- (5) *Landscaping Along Driveway Access.* For lots with 12 or more parking spaces: **Acknowledge all in this section.**
- (a) Landscape area at least five (5) feet in width on each side of an accessway;
 - (b) Landscape area must extend 30 feet back from the property line; and

CHAPTER 73D - WASTE AND RECYCLABLES MANAGEMENT STANDARDS

TDC 73D.020. - Design Methods. An applicant required to provide mixed solid waste and source separated recyclables storage areas must comply with one of following methods:

(1) The minimum standards method in TDSC [73D.030](#);

TDC 73D.030. - Minimum Standards Method.

(1) The size and location of the storage area(s) must be indicated on the site plan. Requirements are based on an assumed storage area height of four feet for mixed solid waste and source separated recyclables. Vertical storage higher than four feet, but no higher than seven feet may be used to accommodate the same volume of storage in a reduced floor space (potential reduction of 43 percent of specific requirements). Where vertical or stacked storage is proposed, submitted plans must include drawings to illustrate the layout of the storage area and dimensions for containers.

(2) The storage area requirement is based on uses. If a building has more than one use and that use occupies 20 percent or less of the gross leasable area (GLA) of the building, the GLA occupied by that use must be counted toward the floor area of the predominant use(s). If a building has more than one use and that use occupies more than 20 percent of the GLA of the building, then the storage area requirement for the whole building must be the sum of the area of each use. Minimum storage area requirements by use is as follows:

(c) Commercial, industrial, and institutional developments must provide a minimum storage area of ten square feet plus: **We propose a 12' x 14' mixed solid waste and source separated recyclables enclosure. There does not appear to be City requirements for a fleet parking lot, so we based the size on tenant requirements, and upsized slightly to Republic Services' minimum commercial enclosure size..**

(i) Office—Four square feet/1,000 square feet gross leasable area (GLA);

(ii) Retail—Ten square feet/1,000 square feet GLA;

(iii) Wholesale/Warehouse/Manufacturing—Six square feet/1,000 square feet GLA;

(iv) Educational and Institutional—Four square feet/1,000 square feet GLA; and

(v) All other uses—Four square feet/1,000 square feet GLA.

(3) Mixed solid waste and source separated recyclables storage areas for multiple tenants on a single site may be combined and shared. **Acknowledge, and our intent is to include both in the enclosure.**

TDC 73D.070. - Location, Design and Access Standards. The following location, design, and access standards are applicable to all storage areas:

(2) Design Standards. **Acknowledge all in this section.**

(a) The dimensions of the storage area must accommodate containers consistent with current methods of local collection at time of construction or alteration. **Our design has been reviewed and approved by Republic Services, and the approval letter is attached.**

(b) Indoor and outdoor storage areas must comply with Oregon Building and Fire Code requirements.

(c) Exterior storage areas must be enclosed by a sight obscuring fence or wall at least six feet in height.

(d) Evergreen plants must be placed around the enclosure walls, excluding the gate or entrance openings for common wall, commercial, and institutional developments.

(e) Gate openings for haulers must be a minimum of ten feet wide and must be capable of being secured in a closed and open position.

(f) Horizontal clearance must be a minimum of ten feet and a vertical clearance of eight feet is required if the storage area is covered.

(g) A separate pedestrian access must also be provided in common wall, commercial, and institutional developments.

(h) Exterior storage areas must have either a concrete or asphalt floor surface. **Ours is concrete.**

(i) Storage areas and containers must be clearly labeled to indicate the type of material accepted.

(3) Access Standards.

(a) Storage areas must be accessible to users at convenient times of the day, and to hauler personnel on the day and approximate time they are scheduled to provide hauler service. **Our design has been reviewed and approved by Republic Services, and the approval letter is attached.**

(b) Storage areas must be designed to be easily accessible to hauler trucks and equipment, considering paving, grade, gate clearance and vehicle access.

(c) Storage areas must be accessible to hauler trucks without requiring backing out of a driveway onto a public street. If only a single access point is available to the storage area, adequate turning radius must be provided to allow hauler trucks to safely exit the site in a forward motion.

(d) Storage areas must be located so that pedestrian and vehicular traffic movement are not obstructed on site or on public streets adjacent to the site.

CHAPTER 74 - PUBLIC IMPROVEMENT REQUIREMENTS

In General

Improvements

Right-of-Way

Easements and Tracts

Utilities

IN GENERAL

TDC 74.010. - Purpose. The City's Community Plan sets forth the requirements for providing adequate transportation and utility systems to serve the community's present and future needs. Land development without adequate transportation and utility systems will adversely affect the overall economic growth of the City and cause undue damage to the public health and welfare of its citizens. Consequently, the City finds that it is in the public interest to require land development to meet the following improvement requirements. **We access our site from the previously established private road on adjacent Lot 8 with an existing private bridge over Hedges Creek. The utilities we need are existing in the same private road.**

TDC 74.020. - Authority.

(3) *Supervision of Planting.* The City Manager has jurisdiction over all trees, plants and shrubs planted or growing in or upon the public rights-of-way of the City and their planting, removal, care, maintenance and protection. The City Manager is to enforce these provisions. **Not applicable as we are not adjacent to a ROW.**

IMPROVEMENTS

TDC 74.110. - Phasing of Improvements. The applicant may build the development in phases. If the development is to be phased the applicant must submit a phasing plan to the City Manager for approval with the development application. The timing and extent or scope of public improvements and the conditions of development must be determined by the City Council on subdivision applications and by the City Manager on other development applications. **No phasing proposed for our fleet parking lot.**

TDC 74.120. - Public Improvements.

(1) *Except as specially provided, all public improvements must be installed at the expense of the applicant. All public improvements installed by the applicant must be constructed and guaranteed as to workmanship and material as required by the Public Works Construction Code prior to acceptance by the City. Work must not be undertaken on any public improvement until after the construction plans have been approved by the City Manager and a Public Works Permit issued and the required fees paid.* **Acknowledge.**

TDC 74.130. - Private Improvements. All private improvements must be installed at the expense of the applicant. The property owner must retain maintenance responsibilities over all private improvements. **Acknowledge.**

EASEMENTS AND TRACTS

TDC 74.310. - Greenway, Natural Area, Bike, and Pedestrian Path Dedications and Easements.

(1) *Areas dedicated to the City for Greenway or Natural Area purposes or easements or dedications for bike and pedestrian facilities during the development application process must be surveyed, staked and marked with a City approved boundary marker prior to acceptance by the City.* **None proposed.**

(2) *For subdivision and partition applications, the Greenway, Natural Area, bike, and pedestrian path dedication and easement areas must be shown to be dedicated to the City on the final subdivision or partition plat prior to approval of the plat by the City; or*

(3) *For all other development applications, Greenway, Natural Area, bike, and pedestrian path dedications and easements must be submitted to the City Manager ; building permits must not be issued for the development prior to acceptance of the dedication or easement by the City.* **None proposed.**

TDC 74.320. - Slope Easements.

(1) *The applicant must obtain and convey to the City any slope easements determined by the City Manager to be necessary adjacent to the proposed development site to support the street improvements in the public right-of-way or accessway or utility improvements required to be constructed by the applicant.* **None proposed.**

(2) *For subdivision and partition applications, the slope easement dedication area must be shown to be dedicated to the City on the final subdivision or partition plat prior to approval of the plat by the City; or*

(3) *For all other development applications, a slope easement dedication must be submitted to the City Manager; building permits must not be issued for the development prior to acceptance of the easement by the City.*

TDC 74.330. - Utility Easements.

(1) *Utility easements for water, sanitary sewer and storm drainage facilities, telephone, television cable, gas, electric lines and other public utilities must be granted to the City.* **Acknowledge.**

(4) *For development applications other than subdivisions and partitions, and for both on-site and off-site easement areas, a utility easement must be granted to the City; building permits must not be issued for the development prior to acceptance of the easement by the City. The City may elect to exercise eminent domain and condemn necessary off-site public utility easements at the applicant's request and expense. The City Council must determine when condemnation proceedings are to be used.* **Acknowledge.**

(5) *The width of the public utility easement must meet the requirements of the Public Works Construction Code. All subdivisions and partitions must have a 6-foot public utility easement adjacent to the street and a 5-foot public utility easement adjacent to all side and rear lot lines. Other easements may be required as determined by the City Manager.* **Acknowledge.**

TDC 74.340. - Watercourse Easements.

(1) *Where a proposed development site is traversed by or adjacent to a watercourse, drainage way, channel or stream, the applicant must provide a storm water easement, drainage right-of-way, or other means of preservation approved by the City Manager, conforming substantially with the lines of the watercourse. The City Manager must determine the width of the easement, or other means of preservation, required to accommodate all the requirements of the Surface Water Management Ordinance, existing and future storm drainage needs and access for operation and maintenance.* **We have**

an existing bridge over Hedges Creek for our private access road and Hedges Creek is already in a sensitive area/vegetated corridor.

(4) *The storm water easement must be sized to accommodate the existing water course and all future improvements in the drainage basin. There may be additional requirements as set forth in TDC [Chapter 72](#), Greenway and Riverbank Protection District, and the Surface Water Management Ordinance. Water quality facilities may require additional easements as described in the Surface Water Management Ordinance. Easements for this purpose already exist and are assumed to be adequate unless notified otherwise.*

TDC 74.350. - Maintenance Easement or Lots. *A dedicated lot or easement will be required when access to public improvements for operation and maintenance is required, as determined by the City Manager. Access for maintenance vehicles must be constructed of an all-weather driving surface capable of carrying a 50,000-pound vehicle. The width of the lot or easement must be at least 15-feet in order to accommodate City maintenance vehicles. In subdivisions and partitions, the easement or lot must be dedicated to the City on the final plat. In any other development, the easement or lot must be granted to the City and recorded prior to issuance of a building permit. **Acknowledge.***

TDC 74.485. - Street Trees. *Prior to approval of a residential subdivision or partition final plat, the applicant must pay the City a non-refundable fee equal to the cost of the purchase and installation of street trees. The location, placement, and cost of the trees must be determined by the City. This sum must be calculated on the interior and exterior streets as indicated on the final subdivision or partition plat. **Not applicable** because our lot is accessed via an existing private street.*

UTILITIES

TDC 74.610. - Water Service.

(1) *Water lines must be installed to serve each property in accordance with the Public Works Construction Code. Water line construction plans must be submitted to the City Manager for review and approval prior to construction. **Acknowledged.***

(2) *If there are undeveloped properties adjacent to the subject site, public water lines must be extended by the applicant to the common boundary line of these properties. The lines must be sized to provide service to future development, in accordance with the City's Water System Master Plan, TDC Chapter 12. **Acknowledged.***

(3) *As set forth in TDC Chapter 12, Water Service, the City has three water service levels. All development applicants must be required to connect the proposed development site to the service level in which the development site is located. If the development site is located on a boundary line between two service levels the applicant must be required to connect to the service level with the higher reservoir elevation. The applicant may also be required to install or provide pressure reducing valves to supply appropriate water pressure to the properties in the proposed development site. Only one water supply source exists and will be connected for service.*

TDC 74.620. - Sanitary Sewer Service.

(1) *Sanitary sewer lines must be installed to serve each property in accordance with the Public Works Construction Code. Sanitary sewer construction plans and calculations must be submitted to the City Manager for review and approval prior to construction. **Acknowledged.***

(2) *If there are undeveloped properties adjacent to the proposed development site which can be served by the gravity sewer system on the proposed development site, the applicant must extend public sanitary sewer lines to the common boundary line with these properties. The lines must be sized to convey flows to include all future development from all up stream areas that can be expected to drain through the lines on the site, in accordance with the City's Sanitary Sewer System Master Plan, TDC Chapter 13. **Not applicable.***

TDC 74.630. - Storm Drainage System.

(1) *Storm drainage lines must be installed to serve each property in accordance with City standards. Storm drainage construction plans and calculations must be submitted to the City Manager for review and approval prior to construction. **Acknowledged.***

(2) *The storm drainage calculations must confirm that adequate capacity exists to serve the site. The discharge from the development must be analyzed in accordance with the City's Storm and Surface Water Regulations. **Acknowledged.***

(3) *If there are undeveloped properties adjacent to the proposed development site which can be served by the storm drainage system on the proposed development site, the applicant must extend storm drainage lines to the common boundary line with these properties. The lines must be sized to convey expected flows to include all future development from all up stream areas that will drain through the lines on the site, in accordance with the Tualatin Drainage Plan in TDC Chapter 14. **Not applicable.***

TDC 74.640. - Grading.

(1) *Development sites must be graded to minimize the impact of storm water runoff onto adjacent properties and to allow adjacent properties to drain as they did before the new development. **Acknowledged.***

(2) A development applicant must submit a grading plan showing that all lots in all portions of the development will be served by gravity drainage from the building crawl spaces; and that this development will not affect the drainage on adjacent properties. The City Manager may require the applicant to remove all excess material from the development site.

Acknowledged.

TDC 74.650. - Water Quality, Storm Water Detention and Erosion Control. *The applicant must comply with the water quality, storm water detention and erosion control requirements in the Surface Water Management Ordinance. If required:*

*(1) On subdivision and partition development applications, prior to approval of the final plat, the applicant must arrange to construct a permanent on-site water quality facility and storm water detention facility and submit a design and calculations indicating that the requirements of the Surface Water Management Ordinance will be satisfied and obtain a Stormwater Connection Permit from Clean Water Services; or **Not applicable.***

*(2) On all other development applications, prior to issuance of any building permit, the applicant must arrange to construct a permanent on-site water quality facility and storm water detention facility and submit a design and calculations indicating that the requirements of the Surface Water Management Ordinance will be met and obtain a Stormwater Connection Permit from Clean Water Services. **Acknowledged.***

*(3) For on-site private and regional non-residential public facilities, the applicant must submit a stormwater facility agreement, which will include an operation and maintenance plan provided by the City, for the water quality facility for the City's review and approval. The applicant must submit an erosion control plan prior to issuance of a Public Works Permit. No construction or disturbing of the site must occur until the erosion control plan is approved by the City and the required measures are in place and approved by the City. **Acknowledged.***

TDC 74.660. - Underground.

*(1) All utility lines including, but not limited to, those required for gas, electric, communication, lighting and cable television services and related facilities must be placed underground. Surface-mounted transformers, surface-mounted connection boxes and meter cabinets may be placed above ground. Temporary utility service facilities, high capacity electric and communication feeder lines, and utility transmission lines operating at 50,000 volts or above may be placed above ground. The applicant must make all necessary arrangements with all utility companies to provide the underground services. The City reserves the right to approve the location of all surface-mounted transformers. **Acknowledged.***

*(2) Any existing overhead utilities may not be upgraded to serve any proposed development. If existing overhead utilities are not adequate to serve the proposed development, the applicant must, at their own expense, provide an underground system. The applicant must be responsible for obtaining any off-site deeds and/or easements necessary to provide utility service to this site; the deeds and/or easements must be submitted to the City Manager for acceptance by the City prior to issuance of the Public Works Permit. **Acknowledged.***

TDC 74.670. - Existing Structures. **Not applicable – none.**

TDC 74.700. - Removal, Destruction or Injury of Trees. *It is unlawful for a person, without a written permit from the City Manager, to remove, destroy, break or injure a tree, plant or shrub, that is planted or growing in or upon a public right-of-way within the City, or cause, authorize, or procure a person to do so, authorize or procure a person to injure, misuse or remove a device set for the protection of any tree, in or upon a public right-of-way. **Acknowledged.***

TDC 74.705. - Street Tree Removal Permit. **Not applicable – no street trees because no ROW.**

k

End of Narrative



PROPERTY INFORMATION REPORT

Date: September 15, 2020

File No.: 20-299861
Property: 11507 SW Amu Street, Tualatin, OR 97062

Martin Development NW
P O Box 15523
Seattle, WA 98115

Your Reference: Hedges D, An LLC

The information contained in this report is furnished by WFG National Title Insurance Company (the "Company") as an information service based on the records and the indices maintained by the Company for the county identified below. This report does not constitute title insurance and is not to be construed or used as a commitment for title insurance. The Company assumes and shall have no liability whatsoever for any errors or inaccuracies in this report. In the event any such liability is ever asserted or enforced, such liability shall in no event exceed the paid herein. No examination has been made of the Company's records, other than as specifically set forth in this report.

The effective date of this report is September 4, 2020

REPORT FINDINGS

A. The land referred to in this report is located in the county of Washington State of Oregon, and is described as follows:

See Attached Exhibit "A"

B. As of the Effective Date and according to the last deed of record, we find the title to the land to be vested as follows:

Hedges D, An LLC, an Oregon limited liability company

C. As of the Effective Date and according to the Public Records, the Land is subject to the following liens and encumbrances, which are not necessarily shown in the order of priority:

1. Any adverse claim or defect in the title based upon the assertion that some portion of said land has been removed from or brought within the boundaries of the premises by a avulsive movement of Hedges Creek or has been formed by a process of accretion or reliction or has been created by artificial means or has accreted to such portion so created.
2. Government rights to connect with floor control and propagation of anadromous fish and public rights of fishing and recreational navigation in and to the water, bed and shoreline of the Hedges Creek.
3. Easement, including the terms and provisions thereof:

For	:	Storm Drain Channel
Granted to	:	the City of Tualatin, its successors in interest and assigns
Recorded	:	February 9, 2000
Recording No(s)	:	2000-010208
Affects	:	Said Storm Drain channel is delineated on the plat of Franklin Business Park No. 6. - affects the most Easterly portion of Lot, which abuts the private roadway
4. Covenants, Conditions and Restrictions, including the terms and provisions thereof, as shown on the recorded plat of [Franklin Business Park](#).

5. Easement as shown on the plat of [Franklin Business Park](#)
 For : Conservation purposes
 Affects : 25 foot strips shown on the plat - affects the most
 Easterly portion of Lot, which abuts the private roadway

Also delineated on the Plat of Franklin Business Park No. 6.

6. Covenants, Conditions, Restrictions and Easements, including the terms and provisions thereof, in Declaration of Franklin Business Park:
 Recorded : November 10, 2004
 Recording No(s) : [2004-129475](#)

Easements rights over the common areas for the benefit of the Association and the Owners of Franklin Business Park, for access, ingress and egress over all the common areas disclosed in above Declaration, subject to terms therein.

As amended by First Amendment:
 Recorded : August 5, 2005
 Recording No(s) : [2005-093498](#)

As amended by Second Amendment:
 Recorded : July 8, 2011
 Recording No(s) : [2011-047427](#)

Said Second Amendment was
 Re-Recorded : July 15, 2011
 Recording No(s) : [2011-049589](#)

Assignment of Declarant Rights
 From : Franklin Business Park LLC, an Oregon limited liability company
 To : Franklin Business Park Owners Association, an Oregon
 nonprofit corporation
 Recorded : April 17, 2018
 Recording No(s) : [2018-026472](#)

7. Said Covenants, Conditions and Restrictions set forth above contain, amount other things, levies and assessments of Franklin Business Park Owners Association.

8. Easement, including the terms and provisions thereof:
 For : Public Utility Access
 Granted to : the City of Tualatin, its successors in interest and
 assigns
 Recorded : December 16, 2005
 Recording No(s) : [2005-158560](#)
 Affects : Portion within private roadway easement

9. Covenants, Conditions and Restrictions, including the terms and provisions thereof, as shown on the recorded Plat of [Franklin Business Park No. 4](#).

10. Terms and Provisions of Easement and Maintenance Agreement, in Declaration of Access Easement
 For : Ingress and egress for vehicular and pedestrian traffic on Hedges
 Creek Drive
 And : Lot 7, Franklin Business Park No. 3, Lot 8, Franklin Business
 Park No. 4, and the portion of Lot 4, Franklin Business Park
 (now known as Franklin Business Park No. 6)
 Recorded : July 6, 2011
 Recording No(s) : [2011-047430](#)
 Affects : the private roadway - appurtenant rights.

11. Covenants, Conditions and Restrictions, including the terms and provisions thereof, as shown on the recorded Plat of [Franklin Business Park No. 6](#).

12. Easement as shown on the plat of [Franklin Busienss Park No. 6](#):
 For : Storm Sewer, surface water, drainage and detention easement
 Affects : Tract "D" (Sensitive Area and Vegetated Corridor) over its entirety, being Parcel II herein
13. Access and Water Management Easement, including the terms and provisions thereof:
 For : Pedestrian and vehicle ingress and egress and turnaround for access to water channel easement area referred to as Hedges Creek
 Granted to : Franklin Business Park Owners Association, an Oregon nonprofit corporation
 Recorded : April 17, 2018
 Recording No(s) : [2018-026470](#)
 Affects : see document for location - Appurtenant to Tract "D", Franklin Business Park No. 6
14. 2020-2021 taxes, a lien not yet due and payable.
15. Taxes, including the current fiscal year, not assessed due to Homeowners Association/Common Area (ORS 94.728). If the exempt status is terminated, an additional tax may be levied.
 Property ID No. : [R2198561](#)
 Levy Code : 088.15
 Map Tax Lot No. : 2S127BA 00900
 (Affects Parcel II)
16. City liens, if any, of the City of Tualatin.
17. Any unrecorded leases or rights of tenants in possession.
18. No search has been made for Financing Statements filed in the office of the Secretary of State. Exception may be taken to such matters as may be shown thereby. No liability is assumed if a Financing Statement is filed in the office of the County Recorder covering timber, crops, fixtures or contracts on the premises wherein the lands are described other than by metes and bounds or under the rectangular survey system or by recorded lot and block.

LINKS FOR ADDITIONAL SUPPORTING DOCUMENTS:

[Assessor's Map](#)
[Taxes R2198560](#)
[Taxes R2198561](#)
[Plat Map Franklin Business Park](#)
[Plat Map Franklin Business Park No. 4](#)
[Plat Map Franklin Business Park No. 6](#)
[Vested Deed](#)
 Access amd Water Management Ease ref in legal [2018-026470](#)
 Declaration of Access ref in legal [2011-047430](#)
 Full Assessors Map [2S1W27BA](#)
 Adjoiner Deed [TL 400 2S127BA](#)
 Adjoiner Deed [TL 500 2S127BA](#)
 Adjoiner Deed [TL 600 2S127BA](#)
 Adjoiner Deed [TL 100 2S127BB](#)
 Adjoiner Deed [TL 200 2S127BB](#)
 Adjoiner Deed [TL 1500 2S122C](#)
 Adjoiner Deed [TL 1502 2S122C](#)

END OF EXCEPTIONS

NOTE: We find NO judgments or Federal Tax Liens against the name(s) of Hedges D, An LLC, an Oregon Limited Liability Company.

NOTE: Taxes paid in full for 2019 -2020:

Levied Amount : \$7,210.15
Property ID No. : [R2198560](#)
Levy Code : 088.15
Map Tax Lot No. : 2S127BA00800
(Affects Parcel I)

NOTE: The Oregon Corporation Commission disclosed that [Hedges D, An LLC](#), is an active Oregon limited liability company:

Filed : April 16, 2018
Member : Mac Martin
Member : John Martin
Registered Agent : Mac Martin

END OF REPORT

Diane Brokke
WFG National Title Insurance Company
12909 SW 68th Pkwy., Suite 350
Portland, OR 97223
Phone: **(503) 431-8504**
Fax: **(503) 684-2978**
Email: **dbrokke@wfgnationaltitle.com**

**EXHIBIT A
LEGAL DESCRIPTION**

PARCEL I:

Lot 12, FRANKLIN BUSINESS PARK NO. 6, in the City of Tualatin, County of Washington and State of Oregon, a subdivision recorded August 24, 2016, Recording No. 2016-067801.


TOGETHER WITH access rights over and across private road (known as Hedges Creek Drive) as described in Declaration of Access Easement recorded July 6, 2011, Recording No. 2011-047430.

PARCEL II:

Tract "D", FRANKLIN BUSINESS PARK NO. 6, in the City of Tualatin, County of Washington and State of Oregon, a subdivision recorded August 24, 2016, Recording No. 2016-067801.

TOGETHER WITH access rights over and across private road (known as Hedges Creek Drive) as described in Declaration of Access Easement recorded July 6, 2011, Recording No. 2011-047430.

ALSO TOGETHER WITH Access rights granted in Access and Water Management Easement recorded April 17, 2018, Recording No. 2018-026470.



ParcelID: R2198560 2S127BA 00800
11507 SW Amu Street
Tualatin, OR 97062 R2108561 2S127BA 00900



This map/plat is being furnished as an aid in locating the herein described land in relation to adjoining streets, natural boundaries and other land, and is not a survey of the land depicted. Except to the extent a policy of title insurance is expressly modified by endorsement, if any, the company does not insure dimensions, distances, location of easements, acreage or other matters shown thereon.

18-145135 COMM
WFG Title

File No.: 18-145135

Grantor
Franklin Business Park LLC
Grantee
HEDGES D, AN LLC
After recording return to
HEDGES D, AN LLC P.O. Box 15523 Seattle, WA 98115
Until requested, all tax statements shall be sent to
HEDGES D, AN LLC P.O. Box 15523 Seattle, WA 98115
Tax Acct No(s): R2198560 and R2198561

Washington County, Oregon **2018-026473**
D-DW
Stn=19 C DEMMER **04/17/2018 08:48:12 AM**
\$25.00 \$11.00 \$5.00 \$20.00 \$350.00 **\$411.00**

I, Richard Hobernicht, Director of Assessment and Taxation and Ex-Officio County Clerk for Washington County, Oregon, do hereby certify that the within instrument of writing was received and recorded in the book of records of said county.

Richard Hobernicht, Director of Assessment and Taxation, Ex-Officio

Reserved for Recorder's Use

STATUTORY WARRANTY DEED

Franklin Business Park LLC, an Oregon limited liability company, Grantor(s) convey and warrant to HEDGES D, AN LLC, an Oregon limited liability company, Grantee(s), the real property described in the attached Exhibit A, subject only to those liens and encumbrances set forth on the attached Exhibit B.

The true consideration for this conveyance is **\$350,000.00**. (Here comply with requirements of ORS 93.030)

BEFORE SIGNING OR ACCEPTING THIS INSTRUMENT, THE PERSON TRANSFERRING FEE TITLE SHOULD INQUIRE ABOUT THE PERSON'S RIGHTS, IF ANY, UNDER ORS 195.300, 195.301 AND 195.305 TO 195.336 AND SECTIONS 5 TO 11, CHAPTER 424, OREGON LAWS 2007, SECTIONS 2 TO 9 AND 17, CHAPTER 855, OREGON LAWS 2009, AND SECTIONS 2 TO 7, CHAPTER 8, OREGON LAWS 2010. THIS INSTRUMENT DOES NOT ALLOW USE OF THE PROPERTY DESCRIBED IN THIS INSTRUMENT IN VIOLATION OF APPLICABLE LAND USE LAWS AND REGULATIONS. BEFORE SIGNING OR ACCEPTING THIS INSTRUMENT, THE PERSON ACQUIRING FEE TITLE TO THE PROPERTY SHOULD CHECK WITH THE APPROPRIATE CITY OR COUNTY PLANNING DEPARTMENT TO VERIFY THAT THE UNIT OF LAND BEING TRANSFERRED IS A LAWFULLY ESTABLISHED LOT OR PARCEL, AS DEFINED IN ORS 92.010 OR 215.010, TO VERIFY THE APPROVED USES OF THE LOT OR PARCEL, TO DETERMINE ANY LIMITS ON LAWSUITS AGAINST FARMING OR FOREST PRACTICES, AS DEFINED IN ORS 30.930, AND TO INQUIRE ABOUT THE RIGHTS OF NEIGHBORING PROPERTY OWNERS, IF ANY, UNDER ORS 195.300, 195.301 AND 195.305 TO 195.336 AND SECTIONS 5 TO 11, CHAPTER 424, OREGON LAWS 2007, SECTIONS 2 TO 9 AND 17, CHAPTER 855, OREGON LAWS 2009 AND SECTIONS 2 TO 7, CHAPTER 8, OREGON LAWS 2010.

Executed this 16 day of April, 2018

Franklin Business Park LLC, an Oregon limited liability company

By: Marlborough Enterprises, Inc., an Oregon Corporation
Its: Manager

By: Amy Drake Reeves
By: Amy Drake Reeves
Its: President

By: Matthew B. Drake
By: Matthew B. Drake
Its: Vice President and Secretary

STATE OF OREGON
COUNTY OF MULTNOMAH

This instrument was acknowledged before me this 16 day of April, 2018 by Amy Drake Reeves and Matthew B. Drake, as President and Vice President and Secretary, of Marlborough Enterprises, Inc., an Oregon Corporation, as Manager of Franklin Business Park LLC, an Oregon limited liability company, on behalf of the limited liability company.

Trevor Garrett Cheyne
Print Name: Trevor Garrett Cheyne
Notary Public for Oregon
My Commission Expires: 10/15/21




EXHIBIT "A"
LEGAL DESCRIPTION

PARCEL I:

Lot 12, FRANKLIN BUSINESS PARK NO. 6, in the City of Tualatin, County of Washington and State of Oregon, a subdivision recorded August 24, 2016, Recording No. 2016-067801.

TOGETHER WITH access rights over and across private road (known as Hedges Creek Drive) as described in Declaration of Access Easement recorded July 6, 2011, Recording No. 2011-047430.

PARCEL II:

Tract "D", FRANKLIN BUSINESS PARK NO. 6, in the City of Tualatin, County of Washington and State of Oregon, a subdivision recorded August 24, 2016, Recording No. 2016-067801.

EXHIBIT "B"
Exceptions

1. Any adverse claim or defect in the title based upon the assertion that some portion of said land has been removed from or brought within the boundaries of the premises by a avulsive movement of Hedges Creek or has been formed by a process of accretion or reliction or has been created by artificial means or has accreted to such portion so created.
2. Government rights to connect with floor control and propagation of anadromous fish and public rights of fishing and recreational navigation in and to the water, bed and shoreline of the Hedges Creek.
3. Easement, including the terms and provisions thereof:

For	:	Storm Drain Channel
Granted to	:	the City of Tualatin, its successors in interest and assigns
Recorded	:	February 9, 2000
Recording No(s)	:	<u>2000-010208</u>
Affects	:	Said Storm Drain channel is delineated on the plat of Franklin Business Park No. 6.
4. Covenants, Conditions and Restrictions, including the terms and provisions thereof, as shown on the recorded plat of Franklin Business Park.
5. Easement as shown on the plat of Franklin Business Park

For	:	Conservation purposes
Affects	:	25 foot strips shown on the plat

Also delineated on the Plat of Franklin Business Park No. 6.
6. Covenants, Conditions, Restrictions and Easements, including the terms and provisions thereof, in Declaration of Franklin Business Park:

Recorded	:	November 10, 2004
Recording No(s)	:	<u>2004-129475</u>

Easements rights over the common areas for the benefit of the Association and the Owners of Franklin Business Park, for access, ingress and egress over all the common areas disclosed in above Declaration, subject to terms therein.

As amended by First Amendment:

Recorded	:	August 5, 2005
Recording No(s)	:	<u>2005-093498</u>

As amended by Second Amendment:

Recorded	:	July 8, 2011
Recording No(s)	:	<u>2011-047427</u>

Said Second Amendment was

Re-Recorded	:	July 15, 2011
Recording No(s)	:	<u>2011-049589</u>
7. Said Covenants, Conditions and Restrictions set forth above contain, amount other things, levies and assessments of Franklin Business Park Owners Association.

8. Easement, including the terms and provisions thereof:

For	:	Public Utility Access
Granted to	:	the City of Tualatin, its successors in interest and assigns
Recorded	:	December 16, 2005
Recording No(s)	:	<u>2005-158560</u>
Affects	:	Portion within private street known as Hedges Creek Drive -

easement insured herein on Parcel I.

9. Covenants, Conditions and Restrictions, including the terms and provisions thereof, as shown on the recorded Plat of Franklin Business Park No. 4.

10. Terms and Provisions of Easement and Maintenance Agreement, in Declaration of Access

Easement	:	Ingress and egress for vehicular and pedestrian traffic
For	:	Creek Drive
on Hedges	:	Lot 7, Franklin Business Park No. 3, Lot 8, Franklin
And	:	Park No. 4, and the portion of Lot 4, Franklin Business
Business	:	(now known as Franklin Business Park No. 6)
Park	:	July 6, 2011
Recorded	:	<u>2011-047430</u>
Recording No(s)	:	the Easement insured in Parcel I - appurtenant rights.
Affects	:	

11. Covenants, Conditions and Restrictions, including the terms and provisions thereof, as shown on the recorded Plat of Franklin Business Park No. 6.

12. Easement as shown on the Plat of Franklin Business Park No. 6:

For	:	Storm Sewer, surface water, drainage and detention
easement	:	
Affects	:	Tract "D" (Sensitive Area and Vegetated Corridor), over
its	:	entirety, being Parcel II herein.

Property Owner Property Address 2020 In Process Real Market Value
 R2198560 HEDGES D, AN LLC 11507 SW AMU ST, TUALATIN, OR 97062 \$442,580

2020 GENERAL INFORMATION

Property Status A Active
 Property Type Industrial
 Legal Description FRANKLIN BUSINESS PARK NO.6, LOT 12, ACRES 5.00
 Alternate Account Number -
 Neighborhood YTSH TUALATIN & SHERWOOD
 Map Number 25127BA00800
 Property Use 2300: COUNTY APPRAISED VACANT INDUSTRIAL LAND
 Levy Code Area 088.15

RELATED PROPERTIES

Linked Properties -
 Property Group ID -
 Grouped Properties -
 Split / Merge Date -
 Split / Merge Accounts -
 Split / Merge Message -

2020 OWNER INFORMATION

Owner Name HEDGES D, AN LLC
 Mailing Address PO BOX 15523 SEATTLE, WA 98115

2020 LAND SEGMENTS

STATE CODE	SEGMENT TYPE	LAND SIZE
L1	30: INDUSTRIAL PARKS	5.00 acres
TOTALS		5.00 acres

CERTIFIED / IN PROCESS VALUES

YEAR	IMPROVEMENTS	LAND	RMV	SPECIAL USE	ASSESSED VALUE
2020 (In Process)	\$0	\$442,580	\$442,580	\$0	\$430,120
2019	\$0	\$398,260	\$398,260	\$0	\$398,260

SALES HISTORY

SALE DATE	SELLER	BUYER	INST #	SALE PRICE	INST TYPE
4/16/2018	FRANKLIN BUSINESS PARK LLC	HEDGES D, AN LLC	2018026473	\$350,000	DW

• If applicable, the described property is receiving special valuation based upon its use. Additional rollback taxes which may become due based on the provisions of the special valuation are not indicated in this listing.

TOTAL TAXES DUE	
Current Year Due	\$0.00
Past Years Due	\$0.00
Total Due	\$0.00

TAX SUMMARY

Effective Date: 9/14/2020 [Details](#)

TAXYEAR	TOTAL BILLED	AD VALOREM	SPECIAL ASMT	PRINCIPAL	INTEREST	DATE PAID	TOTAL OWED
2019	\$7,210.15	\$7,210.15	\$0	\$7,210.15	\$0.00	-	\$0.00
2018	\$6,935.56	\$6,935.56	\$0	\$6,935.56	\$0.00	-	\$0.00
2017	\$7,512.91	\$7,512.91	\$0	\$7,512.91	\$0.00	-	\$0.00

TAXYEAR	RECEIPT NUMBER	TRANSACTION DATE	PAYMENT AMOUNT
2019	WASH-2020-6770	5-19-2020	\$2,403.38
2019	6163664	2-12-2020	\$2,403.38
2019	6149497	11-21-2019	\$2,403.39
2018	5957352	5-10-2019	\$2,311.85
2018	5946961	2-14-2019	\$2,311.85
2018	5905035	11-15-2018	\$2,311.86

2017	5707215	11-17-2017	\$7,287.52
------	---------	------------	------------

Property Owner Property Address 2020 In Process Real Market Value
 R2198561 HEDGES D, AN LLC - \$0

2020 GENERAL INFORMATION

Property Status A Active
 Property Type Commercial
 Legal Description FRANKLIN BUSINESS PARK NO.6, LOT D, ACRES 4.45
 Alternate Account Number -
 Neighborhood YTSH TUALATIN & SHERWOOD
 Map Number 25127BA00900
 Property Use 0000: EXEMPT COMMON PROPERTY IN PLANNED COMMUNITIES
 Levy Code Area 088.15

RELATED PROPERTIES

Linked Properties -
 Property Group ID -
 Grouped Properties -
 Split / Merge Date -
 Split / Merge Accounts -
 Split / Merge Message -

2020 OWNER INFORMATION

Owner Name HEDGES D, AN LLC
 Mailing Address PO BOX 15523 SEATTLE, WA 98115

EXEMPTIONS/DEFERRALS

EXEMPTION CODE	EXEMPTION DESCRIPTION	EXPIRATION YEAR
HOA	HOA: Homeowners Association/Common Area (ORS 94.728)	-

PROPERTY FLAGS

PROPERTY FLAG CODE	PROPERTY FLAG DESCRIPTION
NA	NON-ASSESSABLE

CERTIFIED / IN PROCESS VALUES

YEAR	IMPROVEMENTS	LAND	RMV	SPECIAL USE	ASSESSED VALUE
2020 (In Process)		\$0	\$0	\$0	\$0
2019		\$0	\$0	\$0	\$0

SALES HISTORY

SALE DATE	SELLER	BUYER	INST #	SALE PRICE	INST TYPE
4/16/2018	FRANKLIN BUSINESS PARK LLC	HEDGES D, AN LLC	2018026473	\$350,000	DW
	FRANKLIN BUSINESS PARK OWNERS ASSOC	FRANKLIN BUSINESS PARK LLC	2018026469	-	DQ

• If applicable, the described property is receiving special valuation based upon its use. Additional rollback taxes which may become due based on the provisions of the special valuation are not indicated in this listing.

TAX SUMMARY

Effective Date: 9/14/2020 [Details](#)

TAXYEAR	TOTAL BILLED	AD VALOREM	SPECIAL ASMT	PRINCIPAL	INTEREST	DATE PAID	TOTAL OWED
2019	\$0.00	\$0.00	\$0	\$0.00	\$0.00	-	\$0.00
2018	\$0.00	\$0.00	\$0	\$0.00	\$0.00	-	\$0.00
2017	\$0.00	\$0.00	\$0	\$0.00	\$0.00	-	\$0.00

TOTAL TAXES DUE	
Current Year Due	\$0.00
Past Years Due	\$0.00
Total Due	\$0.00

Payment History for R2198561 not found.
 Please contact the district if you have further questions.

FRANKLIN BUSINESS PARK NO. 6
A REPLAT OF A PORTION OF LOT 4,
"FRANKLIN BUSINESS PARK"
IN THE NW 1/4 OF SECTION 27
T.2S., R.1W., WILLAMETTE MERIDIAN
CITY OF TUALATIN, WASHINGTON COUNTY, OREGON
APRIL 6, 2016

RECORDED AS DOCUMENT NO. 2016067801




DOC. NO. 79010860
(MARINE LUMBER CO.)

DOC. NO. 2006-083653
(TUALATIN YARDS, LLC)

REFERENCE MATERIAL

SN 5534	DOC. NO. 79010860	DOC. NO. 98096419
SN 12254	DOC. NO. 80018262	DOC. NO. 2000010206
SN 18954	DOC. NO. 87024139	DOC. NO. 2000010208
SN 18777	DOC. NO. 87024688	DOC. NO. 2000029818
SN 17143	DOC. NO. 86000527	DOC. NO. 2001087204
SN 21940	DOC. NO. 90-48078	DOC. NO. 2002-061523
SN 25092	DOC. NO. 90-69330	DOC. NO. 2003-044039
SN 27366	DOC. NO. 98098416	DOC. NO. 2005-158560
SN 28004	DOC. NO. 98098417	DOC. NO. 2011-038786
SN 29072	DOC. NO. 98096418	DOC. NO. 2013-039098
SN 31067	FRANKLIN BUSINESS PARK	
SN 31473	FRANKLIN BUSINESS PARK NO. 3	
SN 31523	FRANKLIN BUSINESS PARK NO. 4	



CURVE TABLE

CURVE	RADIUS	LENGTH	DELTA	CHORD	CHORD BEAR.
C1	230.00'	126.49'	31°30'33"	124.90'	S 80°37'37" E
C2	100.00'	109.99'	31°30'33"	108.61'	S 89°17'51" E
C3	170.00'	93.49'	31°30'33"	92.52'	S 80°37'37" E
C4	250.00'	60.14'	13°30'48"	60.00'	N 44°35'41" E
C5	255.00'	30.09'	6°45'37"	30.07'	N 41°13'08" E
C6	255.00'	30.05'	6°45'11"	30.04'	N 47°58'32" E

- LEGEND**
- 5/8" x 30" IRON ROD WITH RED PLASTIC CAP STAMPED "RYAN LS 58833", SET APRIL 5, 2016
 - FOUND 1" COPPER DISK STAMPED "LS 58833", PER FBP 3, UNLESS OTHERWISE NOTED
 - ▲ FOUND 1-5/8" DIAMETER ALUMINUM CAP STAMPED "RYAN LS 58833", PER FBP 3
 - FOUND 5/8" IRON ROD WITH RED PLASTIC CAP STAMPED "GARY W. CHEEL PL5 42849", PER FBP & DOC. NO. 2002-090055
 - () RECORD BEARING AND/OR DISTANCE
 - [] PROBABLE ORIGIN OR FIRST RECORD OF MONUMENT
- DOC. NO. DOCUMENT NUMBER, WASHINGTON COUNTY DEED RECORDS
- FBP PLAT OF "FRANKLIN BUSINESS PARK"
 FBP 3 PLAT OF "FRANKLIN BUSINESS PARK NO. 3"
 FBP 4 PLAT OF "FRANKLIN BUSINESS PARK NO. 4"
- R/W RIGHT-OF-WAY
- SN SURVEY NUMBER, WASHINGTON COUNTY SURVEY RECORDS

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Anthony B. Ryan
 OREGON
 JULY 13, 2004
 ANTHONY B. RYAN
 58833

RENEWAL: DECEMBER 31, 2016

WEDDLE SURVEYING INC.
 Excellence is our benchmark.

6950 SW HAMPTON ST., STE. 170, TIGARD, OR 97223
 PH: (503) 941-9685 FAX: (503) 941-9640
 www.weddlesurveying.net

FRANKLIN BUSINESS PARK NO. 6
A REPLAT OF A PORTION OF LOT 4,
"FRANKLIN BUSINESS PARK"
IN THE NW 1/4 OF SECTION 27
T.2S., R.1W., WILLAMETTE MERIDIAN
CITY OF TUALATIN, WASHINGTON COUNTY, OREGON
APRIL 6, 2016

APPROVALS
APPROVED THIS 24 DAY OF August 2016
WASHINGTON COUNTY BOARD OF COMMISSIONERS

BY [Signature]

APPROVED THIS 11th DAY OF August 2016
MAYOR OF THE CITY OF TUALATIN

BY [Signature]

ATTEST THIS 11th DAY OF August 2016
CITY OF TUALATIN RECORDER

BY [Signature]

APPROVED THIS 24th DAY OF AUGUST 2016
WASHINGTON COUNTY SURVEYOR

BY [Signature] D.C.S.

ALL TAXES, FEES, ASSESSMENTS OR OTHER CHARGES AS PROVIDED BY ORS
92.095 HAVE BEEN PAID AS OF THIS 24th DAY OF August, 2016
DIRECTOR OF ASSESSMENT AND TAXATION
(WASHINGTON COUNTY ASSESSOR)

BY [Signature]
DEPUTY

ATTEST THIS 24th DAY OF August 2016
DIRECTOR OF ASSESSMENT AND TAXATION,
EX-OFFICIO COUNTY CLERK

BY [Signature]
DEPUTY



STATE OF OREGON }
COUNTY OF WASHINGTON } SS

I DO HEREBY CERTIFY THAT THIS SUBDIVISION PLAT WAS RECEIVED FOR RECORD ON
THIS 24th DAY OF August 2016 AT 2:30 O'CLOCK P.M.
AND RECORDED IN THE COUNTY CLERK RECORDS.

BY [Signature]
DEPUTY COUNTY CLERK

DECLARATION

KNOW ALL MEN BY THESE PRESENTS THAT FRANKLIN BUSINESS PARK, LLC, AN OREGON
LIMITED LIABILITY COMPANY, DOES HEREBY MAKE, ESTABLISH AND DECLARE THE ANNEXED
MAP OF "FRANKLIN BUSINESS PARK NO. 6" AS DESCRIBED IN THE ACCOMPANYING
SURVEYOR'S CERTIFICATE TO BE A TRUE MAP AND PLAT THEREOF, AND HAS CAUSED THE
SUBDIVISION TO BE PREPARED AND THE PROPERTY SUBDIVIDED IN ACCORDANCE WITH THE
PROVISIONS OF O.R.S. CHAPTER 92, AND DOES HEREBY GRANT ALL EASEMENTS AS SHOWN
OR NOTED HEREON. TRACT "D" IS HEREBY CONVEYED TO THE FRANKLIN BUSINESS PARK
OWNERS ASSOCIATION.

[Signature] FRANKLIN G. DRAKE
PRESIDENT
MARLBOROUGH ENTERPRISES, INC.
MANAGING MEMBER OF
FRANKLIN BUSINESS PARK, LLC

[Signature] MATTHEW B. DRAKE
SECRETARY
MARLBOROUGH ENTERPRISES, INC.
MANAGING MEMBER OF
FRANKLIN BUSINESS PARK, LLC

ACKNOWLEDGEMENT

STATE OF OREGON }
COUNTY OF MULTNOMAH } SS

THIS INSTRUMENT WAS ACKNOWLEDGED BEFORE ME ON
August 8, 2016

BY FRANKLIN G. DRAKE, AS PRESIDENT OF MARLBOROUGH ENTERPRISES, INC.,
MANAGING MEMBER OF FRANKLIN BUSINESS PARK, LLC.

BY MATTHEW B. DRAKE, AS SECRETARY OF MARLBOROUGH ENTERPRISES, INC.,
MANAGING MEMBER OF FRANKLIN BUSINESS PARK, LLC.

[Signature]
(NOTARY SIGNATURE)

[Signature]
NOTARY PUBLIC - OREGON (PRINTED NAME)

COMMISSION NO. 947805

MY COMMISSION EXPIRES: MARCH 01, 2020

NOTES

1. THIS PLAT IS SUBJECT TO THE CONDITIONS OF APPROVAL CONTAINED IN THE
CITY OF TUALATIN CASE FILE SB 97-03.
2. TRACT "D" IS FOR A SENSITIVE AREA AND VEGETATED CORRIDOR. TRACT "D" IS
SUBJECT TO A STORM SEWER, SURFACE WATER, DRAINAGE AND DETENTION
EASEMENT OVER ITS ENTIRETY FOR THE BENEFIT OF CLEAN WATER SERVICES.
3. TRACT "D" SHALL BE OWNED AND MAINTAINED BY THE FRANKLIN BUSINESS
PARK OWNERS ASSOCIATION.

SURVEYOR'S CERTIFICATE

I, ANTHONY B. RYAN, A REGISTERED PROFESSIONAL LAND SURVEYOR IN THE STATE OF
OREGON, DO HEREBY CERTIFY THAT I HAVE CORRECTLY SURVEYED AND MARKED WITH
PROPER MONUMENTS THE LAND REPRESENTED ON THE ANNEXED MAP OF "FRANKLIN
BUSINESS PARK NO. 6", BEING A REPLAT OF A PORTION OF LOT 4, "FRANKLIN
BUSINESS PARK, A DULY RECORDED SUBDIVISION IN WASHINGTON COUNTY, SITUATE IN
THE NORTHWEST QUARTER OF SECTION 27, TOWNSHIP 2 SOUTH, RANGE 1 WEST OF
THE WILLAMETTE MERIDIAN, CITY OF TUALATIN, COUNTY OF WASHINGTON AND STATE OF
OREGON AND THAT FOR THE INITIAL POINT OF SAID PLAT I HELD THE POSITION OF A
FOUND 1" DIAMETER COPPER DISK STAMPED "LS 58833" MARKING THE SOUTHWEST
CORNER OF LOT 7, "FRANKLIN BUSINESS PARK NO. 3, ALSO A DULY RECORDED PLAT
IN SAID COUNTY. THE BOUNDARY OF "FRANKLIN BUSINESS PARK NO. 6" IS MORE
PARTICULARLY DESCRIBED AS FOLLOWS:

BEGINNING AT THE ABOVE DESCRIBED INITIAL POINT, ALSO BEING THE NORTHWEST
CORNER OF LOT 5, "FRANKLIN BUSINESS PARK NO. 4", ALSO A DULY RECORDED PLAT
IN SAID COUNTY; THENCE ALONG THE WESTERLY LINES OF SAID LOT 8 THE FOLLOWING
COURSES: SOUTH 41°39'17" WEST, 87.36 FEET; THENCE SOUTH 38°27'08" WEST, 99.83
FEET; THENCE SOUTH 21°16'45" WEST, 75.84 FEET; THENCE SOUTH 05°20'18" WEST,
207.57 FEET TO A POINT ON THE SOUTHERLY LINE OF SAID LOT 4, "FRANKLIN
BUSINESS PARK"; THENCE ALONG SAID SOUTHERLY LINE NORTH 89°20'21" WEST, 561.11
FEET TO THE SOUTHWEST CORNER OF SAID LOT 4; THENCE ALONG THE WESTERLY LINE
THEREOF NORTH 00°02'48" WEST, 608.68 FEET TO THE NORTHWESTERLY CORNER OF
SAID LOT 4; THENCE ALONG THE NORTHERLY LINE THEREOF NORTH 89°37'58" EAST,
888.88 FEET TO THE NORTHWEST CORNER OF SAID LOT 7, "FRANKLIN BUSINESS PARK
NO. 3"; THENCE ALONG THE WESTERLY LINE THEREOF SOUTH 38°48'29" WEST, 235.96
FEET TO AN ANGLE CORNER THEREIN; THENCE SOUTH 41°39'17" WEST, 19.05 FEET TO
THE INITIAL POINT.

CONTAINING THEREIN 8.447 ACRES, MORE OR LESS.

NARRATIVE

THE PURPOSE OF THIS SURVEY IS TO PLAT INTO A SINGLE LOT AND A TRACT
THE REMAINING PORTION OF LOT 4, "FRANKLIN BUSINESS PARK" A DULY
RECORDED SUBDIVISION IN WASHINGTON COUNTY, OREGON, SITUATE IN THE
NORTHWEST QUARTER OF SECTION 27, TOWNSHIP 2 SOUTH, RANGE 1 WEST,
OF THE WILLAMETTE MERIDIAN, IN THE CITY OF TUALATIN, WASHINGTON
COUNTY, OREGON.

THE BOUNDARY RESOLUTION IS PER SAID PLAT OF "FRANKLIN BUSINESS
PARK". THE BASIS OF BEARINGS IS PER THE PLAT OF "FRANKLIN BUSINESS
PARK NO. 3", WASHINGTON COUNTY PLAT RECORDS. ALL FOUND MONUMENTS
WERE HELD FOR POSITION UNLESS OTHERWISE NOTED. FALLINGS TO FOUND
MONUMENT POSITIONS ARE SHOWN AS BEARING AND DISTANCE FROM
CALCULATED POSITION TO FOUND POSITION. THE EASTERLY PROPERTY LINES
WERE LOCATED BY HOLDING RECORD DATA PER SAID PLAT OF "FRANKLIN
BUSINESS PARK NO. 3" AND THE PLAT OF "FRANKLIN BUSINESS PARK NO. 4".



6950 SW HAMPTON ST., STE. 170, TIGARD, OR 97223
PH: (503) 941-9585 FAX: (503) 941-9640
www.weddlesurveying.net

REGISTERED
PROFESSIONAL
LAND SURVEYOR

[Signature]
OREGON
JULY 13, 2004
ANTHONY B. RYAN
58833

RENEWAL: DECEMBER 31, 2016



Water supply modeling is necessary for larger projects to determine the impact of the project’s water demand on the water supply system. Water supply modeling will be performed by a consulting engineer based on the most recent version of the Tualatin Water System Master Plan.

Due to possible impacts to the water supply system, the following projects in Tualatin require hydraulic modeling based on the size and type of the project and projected water use for the finished project. The outcome of modeling could require offsite improvements to the water supply system in order to ensure that adequate water supply is available to serve the project and reduce impacts to the overall system.

Hydraulic modeling of the water supply system is required for the following project type/sizes/demand:

Project Type	Criteria	Permit Fee
Commercial or Industrial Building	Building floor area greater than 48,300 square feet or Anticipated daily water demand greater than 870 gallons per acre per day	\$ 300 per building
Residential development	More than 49 dwelling units	\$ 1,000
Multi-family development	More than 49 dwelling units or a combined building floor area greater than 48,300 square feet	\$ 300 per building

Please complete this form and submit the form and required fee (if applicable) with your land-use application (architectural review, subdivision, etc.).

Commercial or Industrial Development

- Building floor area _____ square feet
- Anticipated water demand (if known) _____ gallons per day
- Described planned building use _____

Residential Development

- Number of dwelling units or single family home lots _____

Multi-Family Residential Development

- Number of dwelling units _____
- Building floor area (sum of all building) _____
- Number of multi-family buildings _____

Permit fee required based on the information provided above \$ _____

- If no fee is required, enter \$0.

NOTE: Water Supply Modeling does not replace the requirement for fire hydrant flow testing. Flow testing of fire hydrants will still be required to verify adequate fire flow of finished system

SENSITIVE AREA PRE-SCREENING SITE ASSESSMENT

Clean Water Services File Number 20-001845

1. **Jurisdiction:** Tualatin, OR

2. **Property Information** (example: 1S234AB01400)
 Tax lot ID(s): 2S127BA00800, 2S127BA00900,

OR Site Address: 11507 SW Amu Street
 City, State, Zip: Tualatin, OR 97062
 Nearest cross street: SW 112th Ave.

3. **Owner Information**
 Name: Mac Martin
 Company: Hedges C & D LLC
 Address: 841 SW 37th Avenue
 City, State, Zip: Portland, OR 97219
 Phone/fax: 206-399-6676
 Email: MacMartinis@gmail.com

4. **Applicant Information**
 Name: Bob Wells
 Company: Lance Mueller & Associates
 Address: 130 Lakeside Avenue S., Suite 250
 City, State, Zip: Seattle, WA 98122
 Phone/fax: 206-325-2552; 206-328-0554
 Email: bwells@lmueller.com

4. **Development Activity** (check all that apply)
 Addition to single family residence (rooms, deck, garage)
 Lot line adjustment Minor land partition
 Residential condominium Commercial condominium
 Residential subdivision Commercial subdivision
 Single lot commercial Multi lot commercial
 Other _____

6. **Will the project involve any off-site work?** Yes No Unknown
 Location and description of off-site work: _____

7. **Additional comments or information that may be needed to understand your project:** _____
 Proposed construction of a 71,758sf industrial building and site work. No demolition required.

This application does NOT replace Grading and Erosion Control Permits, Connection Permits, Building Permits, Site Development Permits, DEQ 1200-C Permit or other permits as issued by the Department of Environmental Quality, Department of State Lands and/or Department of the Army COE. All required permits and approvals must be obtained and completed under applicable local, state, and federal law.

By signing this form, the Owner or Owner's authorized agent or representative, acknowledges and agrees that employees of Clean Water Services have authority to enter the project site at all reasonable times for the purpose of inspecting project site conditions and gathering information related to the project site. I certify that I am familiar with the information contained in this document, and to the best of my knowledge and belief, this information is true, complete, and accurate.

Print/type name Bob Wells Print/type title Project Manager
 Signature Bob Wells Date 5/21/20

Digitally signed by Bob Wells
 DN: cn=Bob Wells, o=Clean Water Services, ou=Administration, email=bwells@mueller.com, c=US
 Date: 2020.05.21 11:30:12 -0700

FOR DISTRICT USE ONLY

Sensitive areas potentially exist on site or within 200' of the site. **THE APPLICANT MUST PERFORM A SITE ASSESSMENT PRIOR TO ISSUANCE OF A SERVICE PROVIDER LETTER.** If Sensitive Areas exist on the site or within 200 feet on adjacent properties, a Natural Resources Assessment Report may also be required.

Based on review of the submitted materials and best available information sensitive areas do not appear to exist on site or within 200' of the site. This Sensitive Area Pre-Screening Site Assessment does NOT eliminate the need to evaluate and protect water quality sensitive areas if they are subsequently discovered. This document will serve as your Service Provider Letter as required by Resolution and Order 19-5, Section 3.02.1, as amended by Resolution and Order 19-22. All required permits and approvals must be obtained and completed under applicable local, State and federal law.

Based on review of the submitted materials and best available information the above referenced project will not significantly impact the existing or potentially sensitive area(s) found near the site. This Sensitive Area Pre-Screening Site Assessment does NOT eliminate the need to evaluate and protect additional water quality sensitive areas if they are subsequently discovered. This document will serve as your Service Provider Letter as required by Resolution and Order 19-5, Section 3.02.1, as amended by Resolution and Order 19-22. All required permits and approvals must be obtained and completed under applicable local, state and federal law.

THIS SERVICE PROVIDER LETTER IS NOT VALID UNLESS _____ CWS APPROVED SITE PLAN(S) ARE ATTACHED.

The proposed activity does not meet the definition of development or the lot was platted after 9/9/95 ORS 92.040(2). **NO SITE ASSESSMENT OR SERVICE PROVIDER LETTER IS REQUIRED.**

Reviewed by *Chuck Bushnell* Date 7/16/2020

Once complete, email to: SPLReview@cleanwaterservices.org • Fax: (503) 681-4439
 OR mail to: SPL Review, Clean Water Services, 2550 SW Hillsboro Highway, Hillsboro, Oregon 97123



10295 Southwest Ridder Road Wilsonville, OR 97070
o 503.570.0626 f 503.582.9307 republicservices.com

September 4, 2020

Bob Wells
Lance Mueller & Associates

Re: Hedges D
TBD 115th Street
Tualatin, OR 97026

Dear Bob,

Thank you, for sending us the site plans for this proposed development in Tualatin Oregon.

My Company: Republic Services of Clackamas and Washington Counties has the franchise agreement to service this area with the City of Tualatin. We will provide complete commercial waste removal and recycling services as needed on a weekly basis for this location

The design locations of the enclosures sent 9/3/2020 and site traffic pattern will allow access for our trucks to service the trash and recycling.

The enclosure design plans and dimensions sent 9/3/2020 which includes 12' wide post to post ID and 14' depth, and gate swing radius of minimum 120 degrees with gate cane poles, is adequate to house two 3-yard trash/recycle containers and 1-65 gallon glass cart.

Thanks Bob, for your help and concerns for our services prior to this project being developed.

Sincerely,

A handwritten signature in black ink, appearing to read "Kelly Herrod".

Kelly Herrod
Operations Supervisor
Republic Services Inc.

Hedges D – Fleet Parking Lot

11507 SW 115th Avenue (private street), Tualatin, OR 97062

2. Plans







- a. Existing Conditions – See sheet C0.01
- b. Site Plan – See sheet A1.1
- c. Tree Preservation Plan – (none)
- d. Grading Plan – See sheet C1.20 – C1.30
- e. Utility Plan - See sheet C1.30
- f. Landscape Plan – See sheet L1.0
- g. Lighting Plan – See sheet 1 of 1
- h. Colored Elevations (None – there is no building proposed)
- j. Materials Board (None – there is no building proposed)

Index of AR Drawings:

Architectural	A1.1	site plan and details
	A1.2	site details
Civil	C0.00	cover sheet
	C 0.01	topographic survey
	C 0.02	construction notes & specifications
	C 1.10	site plan
	C 1.20	grading plan
	C1.21	grading plan enlargements
	C1.30	utility plan
	C1.40	erosion and sediment control plan cover sheet
	C1.41	clearing, demolition, mass grading erosion and sed control plan
	C1.42	utility & street construction grading & stabilization esc plan
	C1.43	erosion and sediment control details
	C5.10	civil details
	C5.11	civil details
	R2.0	public water main extension - plan and profile
	R3.0	public water main extension - details
Landscape	L1.0	landscape plan
	L2.0	landscape Details & Specifications
Site lighting	1 of 1	lighting level point by point calculation plan

(MARINE LUMBER CO.)


DOC. NO. 2006-083653
(TUALATIN YARDS, LLC)



SITE PLAN


SCALE: 1" = 40'

11' x 27' STALLS - 342
10' MIN. X 24' MIN. STALL - 7
TOTAL 349



SHEET INDEX


- ARCHITECTURAL**
- A1.1 SITE PLAN AND DETAILS
- A1.2 SITE DETAILS
- CIVIL**
- C0.00 COVER SHEET
- C0.01 TOPOGRAPHIC SURVEY
- C0.02 CONSTRUCTION NOTES & SPECIFICATIONS ABBREVIATIONS AND LEGEND
- C1.10 SITE PLAN
- C1.20 GRADING PLAN
- C1.21 GRADING PLAN ENLARGEMENTS
- C1.30 UTILITY PLAN
- C1.40 EROSION AND SEDIMENT CONTROL PLAN COVER SHEET
- C1.41 CLEARING, DEMOLITION, MASS GRADING EROSION AND SED CONTROL PLAN
- C1.42 UTILITY & STREET CONSTRUCTION GRADING & STABILIZATION ESC PLAN
- C1.43 EROSION AND SEDIMENT CONTROL DETAILS
- C5.10 CIVIL DETAILS
- C5.11 CIVIL DETAILS
- R2.0 PUBLIC WATER MAIN EXTENSION - PLAN AND PROFILE
- R3.0 PUBLIC WATER MAIN EXTENSION - DETAILS
- LANDSCAPE**
- L1.0 LANDSCAPE PLAN
- SITE LIGHTING**
- 1 OF 2 LIGHTING CALCULATION




SITE PLAN AND DETAILS
LANDE MUELLER & ASSOCIATES
 ARCHITECTS
 130 LAKESIDE • SUITE 250 • SEATTLE, WA 98122 • (206) 325-2553
 sheet **A1.1**
 SCHEME H

DATE	9-1-20	BY	LM	CHECKED	LM	NO.	1
DATE	9-1-20	BY	LM	CHECKED	LM	NO.	1
DATE	9-1-20	BY	LM	CHECKED	LM	NO.	1
DATE	9-1-20	BY	LM	CHECKED	LM	NO.	1
DATE	9-1-20	BY	LM	CHECKED	LM	NO.	1
DATE	9-1-20	BY	LM	CHECKED	LM	NO.	1
DATE	9-1-20	BY	LM	CHECKED	LM	NO.	1
DATE	9-1-20	BY	LM	CHECKED	LM	NO.	1
DATE	9-1-20	BY	LM	CHECKED	LM	NO.	1
DATE	9-1-20	BY	LM	CHECKED	LM	NO.	1


C:\wsg\18002 martin - hedges d\18002-parking scheme h.dwg
 15/2/20




1 DUMPSTER ELEVATION
SCALE: 1/4" = 1'-0"




7 DETAIL
SCALE: 3" = 1'-0"



8 DETAIL
SCALE: 3" = 1'-0"



A ENLARGED DUMPSTER PLAN
SCALE: 1/8" = 1'-0"



18-002	job no.	EM	BW	9-1-20	date
		drawn	checked		revision
				AF SUBMITTAL	no.

REGISTERED ARCHITECT
LANDE MUELLER
SEATTLE, WA 1491
STATE OF OREGON

HEDGES D
SW 115TH STREET
TUALATIN, OREGON




SITE DETAILS
LANDE MUELLER & ASSOCIATES
ARCHITECTS
130 LAKESIDE • SUITE 250 • SEATTLE, WA 98122 • (206) 325-2553

sheet
A1.2

CIVIL SITE IMPROVEMENTS

HEDGES D PARKING LOT

TUALATIN, OREGON



NOTICE TO EXCAVATORS:
ATTENTION: OREGON LAW REQUIRES YOU TO FOLLOW RULES ADOPTED BY THE OREGON UTILITY NOTIFICATION CENTER. THESE RULES ARE SET FORTH IN OAR 952-001-0010 THROUGH OAR 952-001-0090. YOU MAY OBTAIN COPIES OF THE RULES BY CALLING THE CENTER.
 (NOTE: THE TELEPHONE NUMBER FOR THE OREGON UTILITY NOTIFICATION CENTER IS (503)-232-1987).

POTENTIAL UNDERGROUND FACILITY OWNERS

Dig Safely.
 Call the Oregon One-Call Center
DIAL 811 or 1-800-332-2344

EMERGENCY TELEPHONE NUMBERS

NW NATURAL GAS
 M-F 7am-6pm 503-226-4211 Ext.4313
 AFTER HOURS 503-226-4211

PGE
 503-464-7777

QWEST
 1-800-573-1311

CITY BUREAU OF MAINTENANCE 503-823-1700

CITY WATER 503-823-4874

VERIZON 1-800-483-1000

PROJECT LOCATION

11507 SW AMU STREET
 TUALATIN, OREGON
 LATITUDE = 45°22'28"
 LONGITUDE = -122°47'57"

PROPERTY DESCRIPTION

LOT 12, "FRANKLIN BUSINESS PARK" NO. 6
 NW 1/4 OF SECTION 27 T. 2 S., R. 1 W., W.M.
 CITY OF TUALATIN
 WASHINGTON COUNTY, OREGON

EXISTING LAND USE

THE SITE IS CURRENTLY UNDEVELOPED

VERTICAL DATUM

NGVD '29. SEE "BASIS OF ELEVATIONS"
 DESCRIPTION ON TOPOGRAPHIC SURVEY
 SHEET C0.01

AREA SUMMARY

TOTAL SITE AREA = 217,682 SF (5.00 AC)

- NEW IMPERVIOUS AREA
- WITHIN PUBLIC RIGHT-OF-WAY: ± 0 SF
 - WITHIN PRIVATE PROPERTY: ±191,301 SF

APPLICANT

MARTIN DEVELOPMENT
 PO BOX 15523
 SEATTLE, WA 98115
 CONTACT: MAC MARTIN
 PHONE: (206) 399-6676
 macmartin@gmail.com

CIVIL ENGINEER

MACKENZIE
 CONTACT: GREG MINO
 1515 SE WATER AVE
 PORTLAND, OR 97214
 PHONE: 503-224-6569
 gmino@mcknze.com

ARCHITECT

LANCE MUELLER & ASSOCIATES
 CONTACT: BOB WELLS
 130 LAKESIDE AVENUE, SUITE 250
 SEATTLE, WA 98122
 PHONE: 206-325-2553
 bwells@mueller.com

GEOTECHNICAL ENGINEER

GEOTECHNICAL ENGINEERS, INC.
 CONTACT: GREG LANDAU
 4000 KRUSE WAY PLACE, BLDG 3, STE 200
 LAKE OSWEGO, OR 97035
 PHONE: 503-603-9652
 glandau@geoengineers.com

CITY OF TUALATIN

PUBLIC WORKS DEPARTMENT
 CONTACT: MARK SCHLAGEL
 10699 HERMAN ROAD
 TUALATIN, OR 97062
 PHONE: 503-691-3059
 mschlage@tualatin.gov

UTILITY PROVIDERS

PORTLAND GENERAL ELECTRIC
 9480 SW BOECKMAN ROAD
 WILSONVILLE, OR 97070
 PHONE: 503-672-5428
 CONTACT: TRAVIS SMALLWOOD

NW NATURAL GAS
 220 NW 2ND AVENUE
 PORTLAND, OR 97209
 PHONE: 503-226-4211

TVF&R
 11945 SW 70TH AVE
 TIGARD, OR 97223
 PHONE: 503-699-8577
 CONTACT: TOM MOONEY

COMCAST
 14200 SW BRIGADONO PLACE
 BEAVERTON, OR 97005
 PHONE: 503-605-4834

FRONTIER
 4155 SW CEDAR HILLS BOULEVARD
 BEAVERTON, OR 97005
 PHONE: 503-641-2004

SHEET INDEX

C0.00	COVER SHEET
C0.01	TOPOGRAPHIC SURVEY
C0.02	CONSTRUCTION NOTES & SPECIFICATIONS ABBREVIATIONS AND LEGEND
C1.10	SITE PLAN
C1.20	GRADING PLAN
C1.21	GRADING PLAN ENLARGEMENTS
C1.30	UTILITY PLAN
C1.40	EROSION AND SEDIMENT CONTROL PLAN COVER SHEET
C1.41	CLEARING, DEMOLITION, MASS GRADING EROSION AND SED CONTROL PLAN
C1.42	UTILITY & STREET CONSTRUCTION GRADING & STABILIZATION ESC PLAN
C1.43	EROSION AND SEDIMENT CONTROL DETAILS
C5.10	CIVIL DETAILS
C5.11	CIVIL DETAILS
R2.0	PUBLIC WATER MAIN EXTENSION - PLAN AND PROFILE
R3.0	PUBLIC WATER MAIN EXTENSION - DETAILS

M.
 Architecture • Interiors
 Planning • Engineering

Portland, OR
 503.224.9560
 Vancouver, WA
 360.695.7879
 Seattle, WA
 206.749.9993
 www.mcknze.com

MACKENZIE
 DESIGN DRIVEN • CLIENT FOCUSED

MARTIN DEVELOPMENT NW
 PO BOX 15523
 SEATTLE, WA 98115

HEDGES D PARKING LOT
 11507 SW AMU STREET
 TUALATIN, OREGON



© MACKENZIE 2020
 ALL RIGHTS RESERVED
 THESE DRAWINGS ARE THE PROPERTY OF
 MACKENZIE AND ARE NOT TO BE USED
 OR REPRODUCED IN ANY MANNER
 WITHOUT PRIOR WRITTEN PERMISSION

REVISION SCHEDULE

Delta	Issued As	Issue Date

SHEET TITLE:
COVER SHEET

DRAWN BY: BTS

CHECKED BY: GIM

SHEET

C0.00

JOB NO. **2200339.00**

THE SURVEY INFORMATION SHOWN AS A BACKGROUND SCREEN ON THIS SHEET IS SHOWN FOR REFERENCE ONLY AND IS BASED ON A SURVEY BY: WEGGLE SURVEYING DATE: 10/27/2019

TOPOGRAPHIC SURVEY HEDGES C AND D

LOT 8, "FRANKLIN BUSINESS PARK" NO. 4 &
LOT 12, "FRANKLIN BUSINESS PARK" NO. 6
NW 1/4 OF SECTION 27
T. 2 S., R. 1 W., W.M.
CITY OF TUALATIN
WASHINGTON COUNTY, OREGON


OWNER: HEDGES C, LLC
HEDGES D, LLC
REQUESTED BY: MAC MARTIN
MARTIN DEVELOPMENT NW

LEGEND

	CLEANOUT
	CURB INLET
	COMMUNICATIONS MANHOLE
	COMMUNICATIONS RISER
	FIRE HYDRANT
	GAS RISER
	GAS VALVE
	LIGHT POLE
	5/8" IRON ROD WITH RED PLASTIC CAP "RYAN LS 58833"
	POWER BOX
	POWER VAULT
	SANITARY SEWER MANHOLE, SSMH
	SIGN
	SPOT GRADE
	TOP BACK OF CURB
	GUT
	GUTTER
	EP EDGE OF PAVEMENT
	NATURAL GROUND
	STORM MANHOLE, SDMH
	WATER METER
	WATER VALVE
	GAS LINE
	SANITARY SEWERLINE
	STORM SEWERLINE
	UNDERGROUND POWER
	WATERLINE
	ASPHALT
	CONCRETE
	GRAVEL



SCALE: 1" = 30'
CONTOUR INTERVAL = 1'
SEPTEMBER 17, 2018



BASIS OF ELEVATIONS
WEDDLE CONTROL POINTS WITH ELEVATIONS DERIVED FROM WASHINGTON COUNTY BENCHMARK NO. 89, A BRASS CAP IN MONUMENT BOX MARKING THE QUARTER CORNER BETWEEN SECTIONS 26 & 35, T.2S., R.1E., AT THE INTERSECTION OF IBACH ROAD AND BOONES FERRY ROAD.
ELEVATION = 276.48' (NGVD '29) (MONUMENT HAS BEEN DESTROYED. RELATIVE ELEVATIONS HAVE BEEN PERPETUATED.)

- SURVEYOR'S NOTES**
- UTILITIES SHOWN HEREON ARE PER ABOVE GROUND EVIDENCE, AS BUILT MAPPING FROM THE CITY OF TUALATIN AND NORTHWEST NATURAL GAS AND UTILITY LOCATE SERVICE PAINT. THE SURVEYOR MAKES NO GUARANTEE AS TO THE EXACT LOCATION, OR EXTENT OF UNDERGROUND UTILITIES. CALL 811 BEFORE DIGGING!
 - THE BASIS OF BEARINGS FOR THIS SURVEY IS THE PLAT OF "FRANKLIN BUSINESS PARK", WASHINGTON COUNTY PLAT RECORDS.
 - EASEMENTS ARE SHOWN PER THE PLAT OF FRANKLIN BUSINESS PARK NO. 4 AND 6.
 - NOT ALL SURVEY MONUMENTS ARE NOT SHOWN. REFER TO THE PLAT OF FRANKLIN BUSINESS PARK NO. 4 AND 6 FOR MONUMENT LOCATIONS.
 - UTILITIES AT BRIDGE NOT TIED DUE TO EXTREME HORNET INFESTATION

REVISIONS/UPDATES

09/17/18
EXPANDED TOPOGRAPHY TO SOUTH AND WEST (TOWARD CREEK) OVER HEDGES 'C' SITE, DUE TO RECENT CLEARING, GRADING AND BRUSH REMOVAL.

REGISTERED PROFESSIONAL LAND SURVEYOR
ANTHONY B. RYAN
58833
RENEWAL: DECEMBER 31, 2018



C0.01

6950 SW HAMPTON ST., STE. 170, TIGARD, OR 97223
PH: (503) 941-9585 FAX: (503) 941-9540
www.weddlesurveying.net



© MACKENZIE 2020
ALL RIGHTS RESERVED
THESE DRAWINGS ARE THE PROPERTY OF
MACKENZIE AND ARE NOT TO BE USED
OR REPRODUCED IN ANY MANNER
WITHOUT PRIOR WRITTEN PERMISSION


REVISION SCHEDULE		
Delta	Issued As	Issue Date

SHEET TITLE:
SITE PLAN

DRAWN BY: BTC
CHECKED BY: GIM
SHEET

C1.10

JOB NO. **2200339.00**





PAVEMENT LEGEND

*PAVEMENT SECTIONS SHOWN BELOW REFER TO THE GEOTECHNICAL REPORT BY GEOENGINEERS, INC. DATED JULY 10, 2019. ALL RECOMMENDATIONS THEREIN SHALL BE FOLLOWED.

- ASPHALT PAVEMENT SECTION**
ASPHALTIC CONCRETE (AC) OVER CRUSHED ROCK BASE (CRB) OVER COMPACTED SUBGRADE PER GEOTECHNICAL REQUIREMENTS
- DRIVE AISLES: 4.0" AC OVER 11.0" CRB
- PARKING STALLS: 3.0" AC OVER 8.0" CRB
- CONCRETE PAVEMENT SECTION**
PORTLAND CEMENT CONCRETE (PCC) OVER CRUSHED ROCK BASE (CRB) OVER COMPACTED SUBGRADE PER GEOTECHNICAL REQUIREMENTS
- SITE SLABS-ON-GRADE: 6.0" PCC OVER 6.0" CRB, REINFORCED W/ #4 REBAR @ 12" OC, EW
- SIDEWALKS: 4.0" PCC OVER 2.0" CRB, REINFORCED W/ #4 REBAR @ 24" OC, EW


PARKING LEGEND



KEYNOTES

- 6" CONCRETE VERTICAL CURB PER 1/C5.10
- 6" DEEPENED CONCRETE VERTICAL CURB PER 2/C5.10. CONTRACTOR TO DETERMINE APPLICABLE LOCATIONS BASED ON FIELD CONDITIONS
- CONCRETE SIDEWALK PER 3/C5.10
- CONCRETE CURB CHANNEL FOR DRAINAGE PER 4/C5.10
- STAMPED ASPHALT WALKWAY PER 5/C5.10
- ACCESSIBLE CURB RAMP PER 6/C5.10
- 4" WHITE PARKING STRIPE PER 7/C5.10
- WHEEL STOP PER 8/C5.10
- SPEED BUMP PER 9/C5.10
- SAWCUT 12" ONTO BRIDGE SECTION AND REPLACE PAVEMENT FULL DEPTH PER 10/C5.10
- PROVIDE VEHICLE LOAD LIMIT SIGN (AASHTO HS20) AT BRIDGE CROSSING PER 11/C5.10. COORDINATE REQUIREMENTS WITH FIRE MARSHAL
- BIKE RACK PER ARCHITECTURAL PLANS
- PERIMETER SECURITY FENCE PER ARCHITECTURAL PLANS
- TRASH ENCLOSURE PER ARCHITECTURAL PLANS
- ELECTRICAL TRANSFORMER ON CONCRETE PAD PER ELECTRIC SERVICE PROVIDER
- SITE LIGHT (DESIGN-BUILD BY CONTRACTOR)
- AUTOMATIC ENTRY GATE (DESIGN-BUILD BY CONTRACTOR). ADJUST CURB ALIGNMENTS TO ACCOMMODATE WITHOUT DECREASING DRIVE LANE WIDTH
- 20'x20' STAND UP SHELTER BY TENANT
- PORTABLE TOILET BY TENANT
- ADJUST CURB ALIGNMENT TO ACCOMMODATE EXISTING GAS VALVE

PARKING TABULATIONS	
11' x 27' DELIVERY VAN STALLS	342
11' x 24' DELIVERY VAN STALLS	7
TOTAL DELIVERY VAN STALLS	349



Project



© MACKENZIE 2020
 ALL RIGHTS RESERVED
 THESE DRAWINGS ARE THE PROPERTY OF
 MACKENZIE AND ARE NOT TO BE USED
 OR REPRODUCED IN ANY MANNER
 WITHOUT PRIOR WRITTEN PERMISSION

REVISION SCHEDULE		
Delta	Issued As	Issue Date

SHEET TITLE:
GRADING PLAN


DRAWN BY: GIM

CHECKED BY: MWB

SHEET

C1.20

JOB NO. **2200339.00**



Architecture • Interiors
Planning • Engineering

Portland, OR
503.224.9560
Vancouver, WA
360.695.7879
Seattle, WA
206.749.9993
www.mcknze.com





MACKENZIE
DESIGN DIVISION • CLIENT PROVIDED

Client

**MARTIN
DEVELOPMENT NW**
PO BOX 15523
SEATTLE, WA 98115

Project

**HEDGES D
PARKING LOT**
11507 SW AMU STREET
TUALATIN, OREGON



© MACKENZIE 2020
ALL RIGHTS RESERVED
THESE DRAWINGS ARE THE PROPERTY OF
MACKENZIE AND ARE NOT TO BE USED
OR REPRODUCED IN ANY MANNER
WITHOUT PRIOR WRITTEN PERMISSION

REVISION SCHEDULE		
Delta	Issued As	Issue Date

SHEET TITLE:
**GRADING PLAN
ENLARGEMENTS**

DRAWN BY: GIM



CHECKED BY: MWB

SHEET

C1.21

JOB NO. **2200339.00**

ARCHITECTURAL REVIEW SUBMITTAL 09/01/20



- KEYNOTES**
1. INSTALL STORM PIPE, SIZE PER PLAN, TRENCHING PER 12/C5.10 AND PROJECT SPECIFICATIONS
 2. INSTALL CATCH BASIN PER 13/C5.10
 3. INSTALL FLOW CONTROL MANHOLE PER 1-1B/C5.11
 4. INSTALL PIPE OUTFALL, PROVIDE CLASS 50 RIP RAP PAD PER 2/C5.11
 5. INSTALL WATER QUALITY CATCH BASIN (# CARTRIDGES AS NOTED) PER SAMPLE CUT SHEET ON C5.11
 6. INSTALL UNDERGROUND DETENTION SYSTEM (372 CHAMBERS TOTAL, 6" STONE ENCASUREMENT) WITH 12" HEADER SYSTEM AND CONNECTOR MANHOLES PER SAMPLE CUT SHEET ON C5.11
 7. REFER TO SHEETS R2.0 AND R3.0 FOR PUBLIC WATER FACILITY CONSTRUCTION
 8. ADJUST EXISTING GAS VALVE TO GRADE



© MACKENZIE 2020
 ALL RIGHTS RESERVED
 THESE DRAWINGS ARE THE PROPERTY OF
 MACKENZIE AND ARE NOT TO BE USED
 OR REPRODUCED IN ANY MANNER
 WITHOUT PRIOR WRITTEN PERMISSION

REVISION SCHEDULE		
Delta	Issued As	Issue Date

SHEET TITLE:
UTILITY PLAN

DRAWN BY: BTC
 CHECKED BY: GIM
 SHEET

C1.30

JOB NO. **2200339.00**



Architecture • Interiors
Planning • Engineering

Portland, OR
503.224.9560
Vancouver, WA
360.695.7879
Seattle, WA
206.749.9993
www.mcknzie.com

MACKENZIE
DESIGN DRIVEN • CLIENT FOCUSED

Client

**MARTIN
DEVELOPMENT NW**
PO BOX 15523
SEATTLE, WA 98115

Project

**HEDGES D
PARKING LOT**
11507 SW AMU STREET
TUALATIN, OREGON



© MACKENZIE 2020
ALL RIGHTS RESERVED
THESE DRAWINGS ARE THE PROPERTY OF
MACKENZIE AND ARE NOT TO BE USED
OR REPRODUCED IN ANY MANNER
WITHOUT PRIOR WRITTEN PERMISSION

REVISION SCHEDULE		
Delta	Issued As	Issue Date

SHEET TITLE:

**CLEARING,
DEMOLITION,
MASS GRADING
EROSION AND
SED CONTROL
PLAN**


DRAWN BY: GIM

CHECKED BY: MWB


SHEET

C1.41

JOB NO. **2200339.00**



**CLEARING, DEMOLITION, MASS GRADING
EROSION AND SED CONTROL PLAN**



LEGEND

- EXISTING DRAINAGE FLOW DIRECTION
- COMPOST FILTER BERM
- SEDIMENT FENCE/STRAW WATTLE
- INLET PROTECTION
- GRAVEL CONSTRUCTION ENTRANCE
- CONCRETE WASHOUT

STAGING AND STOCKPILE AREAS ARE TO BE DETERMINED BY THE CONTRACTOR AND ADJUSTED TO ACCOMMODATE THE PROGRESS OF CONSTRUCTION. THE OWNER'S EROSION CONTROL INSPECTOR SHALL BE MADE AWARE OF ALL CHANGES AND CONSULTED FOR BMP IMPLEMENTATIONS THAT MAY BE NECESSARY TO ACCOMMODATE THE SELECTED LOCATIONS.

THIS PLAN IS INTENDED TO BE ONLY A BASELINE APPROACH TO EROSION AND SEDIMENT CONTROL FOR THE PROJECT SITE. THE OWNER'S EROSION AND SEDIMENT CONTROL INSPECTOR SHALL BE RESPONSIBLE FOR INSTRUCTING THE CONTRACTOR TO ADJUST BMP'S AS NECESSARY TO PROPERLY MANAGE THE VARIOUS PHASES OF CONSTRUCTION AND ANY UNFORESEEN CONDITIONS REQUIRING DIFFERENT OR ADDITIONAL BMP'S TO MANAGE.

SEE SHEETS C1.43 FOR EROSION AND SEDIMENT CONTROL DETAILS



© MACKENZIE 2020
 ALL RIGHTS RESERVED
 THESE DRAWINGS ARE THE PROPERTY OF
 MACKENZIE AND ARE NOT TO BE USED
 OR REPRODUCED IN ANY MANNER
 WITHOUT PRIOR WRITTEN PERMISSION



REVISION SCHEDULE		
Delta	Issued As	Issue Date

SHEET TITLE:
UTILITY & STREET CONSTRUCTION GRADING & STABILIZATION ESC PLAN

DRAWN BY: GIM
 CHECKED BY: MWB
 SHEET

C1.42

JOB NO. **2200339.00**









LEGEND

EXISTING	PROPOSED	
---	---	DRAINAGE FLOW DIRECTION
—○—	—○—	COMPOST FILTER BERM
—□—	—□—	SEDIMENT FENCE
—⊕—	—⊕—	INLET PROTECTION
—⊕—	—⊕—	GRAVEL CONSTRUCTION ENTRANCE
—□—	—□—	DRIVE THROUGH TIRE WASH

STAGING AND STOCKPILE AREAS ARE TO BE DETERMINED BY THE CONTRACTOR AND ADJUSTED TO ACCOMMODATE THE PROGRESS OF CONSTRUCTION. THE OWNER'S EROSION CONTROL INSPECTOR SHALL BE MADE AWARE OF ALL CHANGES AND CONSULTED FOR BMP IMPLEMENTATIONS THAT MAY BE NECESSARY TO ACCOMMODATE THE SELECTED LOCATIONS.

THIS PLAN IS INTENDED TO BE ONLY A BASELINE APPROACH TO EROSION AND SEDIMENT CONTROL FOR THE PROJECT SITE. THE OWNER'S EROSION AND SEDIMENT CONTROL INSPECTOR SHALL BE RESPONSIBLE FOR INSTRUCTING THE CONTRACTOR TO ADJUST BMP'S AS NECESSARY TO PROPERLY MANAGE THE VARIOUS PHASES OF CONSTRUCTION AND ANY UNFORESEEN CONDITIONS REQUIRING DIFFERENT OR ADDITIONAL BMP'S TO MANAGE.

SEE SHEETS C1.43 FOR EROSION AND SEDIMENT CONTROL DETAILS



© MACKENZIE 2020
 ALL RIGHTS RESERVED
 THESE DRAWINGS ARE THE PROPERTY OF MACKENZIE AND ARE NOT TO BE USED OR REPRODUCED IN ANY MANNER WITHOUT PRIOR WRITTEN PERMISSION


REVISION SCHEDULE		
Delta	Issued As	Issue Date

SHEET TITLE:
EROSION AND SEDIMENT CONTROL DETAILS

DRAWN BY: GIM
 CHECKED BY: MWB
 SHEET

C1.43


JOB NO. 2200339.00




1 VERTICAL CURB
C5.10 NTS




KEYNOTES:
1. CONCRETE FOR CURBING PER PROJECT SPECIFICATIONS
2. PAVEMENT SECTION PER CIVIL PLANS
3. SEE CIVIL PLANS FOR IMPROVEMENTS AT BACK OF CURB. WHERE SIDEWALK OCCURS, THE SIDEWALK AND TOP OF CURB SHALL BE FLUSH. WHERE ABUTTING A PLANTER AREA, THE FINAL GRADE SHALL BE 1\"/>




2 DEEPENED VERTICAL CURB
C5.10 NTS




3 CONCRETE SIDEWALK AND JOINTS
C5.10 NTS




4 CONCRETE CURB CHANNEL
C5.10 NTS




5 STAMPED ASPHALT
C5.10 NTS




6 PARALLEL CURB RAMPS
C5.10 NTS




7 PARKING STALL STRIPING
C5.10 NTS




8 PRECAST WHEEL STOP
C5.10 NTS




9 SPEED BUMP
C5.10 NTS




10 ASPHALT PAVEMENT SAWCUT
C5.10 NTS




11 SIGN POST
C5.10 NTS




12 UTILITY TRENCH BEDDING AND BACKFILL
C5.10 NTS




13 STEEL CATCH BASIN
C5.10 NTS




14 COMPACT CARPOOL
C5.10 NTS



15 CONCRETE CURB CHANNEL
C5.10 NTS



16 CONCRETE CURB CHANNEL
C5.10 NTS



© MACKENZIE 2020
ALL RIGHTS RESERVED
THESE DRAWINGS ARE THE PROPERTY OF
MACKENZIE AND ARE NOT TO BE USED
OR REPRODUCED IN ANY MANNER
WITHOUT PRIOR WRITTEN PERMISSION







REVISION SCHEDULE		
Delta	Issued As	Issue Date

SHEET TITLE:
CIVIL DETAILS

DRAWN BY: GIM
CHECKED BY: MWB
SHEET

C5.10

JOB NO. **2200339.00**



StormTech **4DS**

STORMTECH SC-740 CHAMBER

Designed to meet the most stringent industry performance standards for superior structural integrity while providing designers with a cost-effective method to save valuable land and protect water resources, the StormTech system is designed primarily to be used under parking lots, thus maximizing land usage for private (commercial) and public applications. StormTech chambers can also be used in conjunction with Green Infrastructure, thus enhancing the performance and extending the service life of these practices.

STORMTECH SC-740 CHAMBER
(not to scale)

Nominal Chamber Specifications
Size (L x W x H)
85.4" x 51" x 30"
2,170 mm x 1,295 mm x 762 mm


Chamber Storage
45.9 ft³ (1.30 m³)

Min. Installed Storage*
74.9 ft³ (2.12 m³)

Weight
74.0 lbs (33.6 kg)

Shipping
30 chambers/pallet
80 end caps/pallet
12 pallets/truck

*Minimum 1" (25 mm) stone above, below and between chambers and 40% stone porosity.



STORMFILTER STEEL CATCHBASIN DESIGN NOTES

STORMFILTER TREATMENT CAPACITY IS A FUNCTION OF THE CARTRIDGE SELECTION AND THE NUMBER OF CARTRIDGES. A CARTRIDGE CATCHBASIN HAS A MAXIMUM OF FOUR CARTRIDGES. SYSTEM IS SHOWN WITH AN 18" CARTRIDGE. STORMFILTER CATCHBASIN CONFIGURATIONS ARE AVAILABLE WITH A DRY INLET BAY FOR VECTOR CONTROL.

RECOMMENDED HYDRAULIC DROP (ft)

CATCHBASIN HEIGHT	27"	19"	18" DEEP
CATCHBASIN HEIGHT (ft)	2.25	1.58	1.50
SPECIFIC FLOW RATE (gpm/ft ²)	2 gpm/ft ²	1.67 gpm/ft ²	1.67 gpm/ft ²
CATCHBASIN FLOW RATE (gpm)	22.5	18.75	11.25
PEAK HYDRAULIC CAPACITY	1.0	1.0	1.8
INLET PERMANENT POOL LEVEL (ft)	1'-0"	1'-0"	2'-0"
OVERALL STRUCTURE HEIGHT (ft)	4'-0"	3'-0"	4'-0"

* 1.67 gpm/ft² SPECIFIC FLOW RATE IS APPROVED WITH PHOSPHORUS® (PSORB) MEDIA ONLY.

GENERAL NOTES

- CONTRACTOR TO PROVIDE ALL MATERIALS UNLESS NOTED OTHERWISE.
- FOR SITE SPECIFIC DRAWINGS WITH DETAILED STORMFILTER CATCHBASIN STRUCTURE DIMENSIONS AND WEIGHTS, PLEASE CONTACT YOUR CONTECH ENGINEERED SOLUTIONS LLC REPRESENTATIVE. www.contechES.com
- STORMFILTER CATCHBASIN WATER QUALITY STRUCTURE SHALL BE IN ACCORDANCE WITH ALL DESIGN DATA AND INFORMATION CONTAINED IN THIS DRAWING.
- INLET SHOULD NOT BE LOWER THAN OUTLET. INLET (IF APPLICABLE) AND OUTLET PIPING TO BE SPECIFIED BY ENGINEER AND PROVIDED BY CONTRACTOR.
- MANUFACTURER TO APPLY A SURFACE BEAD WELD IN THE SHAPE OF THE LETTER 'O' ABOVE THE OUTLET PIPE STUB ON THE EXTERIOR SURFACE OF THE STEEL SPID.
- STORMFILTER CATCHBASIN EQUIPPED WITH 4 INCH (APPROXIMATE) LONG STUBS FOR INLET (IF APPLICABLE) AND OUTLET PIPING. STANDARD OUTLET STUB IS 8 INCHES IN DIAMETER. MAXIMUM OUTLET STUB IS 15 INCHES IN DIAMETER. CONNECTION TO COLLECTION PIPING CAN BE MADE USING FIBER OPTIC BY CONTRACTOR.
- STEEL STRUCTURE TO BE MANUFACTURED OF 1/4 INCH STEEL PLATE. CASTINGS SHALL MEET AASHTO HRRG LOAD RATING TO MEET H200 LOAD RATING ON STRUCTURE. A CONCRETE COLLAR IS REQUIRED. WHEN REQUIRED, CONCRETE COLLAR WITH REINFORCING BARS TO BE PROVIDED BY CONTRACTOR.
- FILTER CARTRIDGES SHALL BE MEDIA FILLED, PASSIVE, SIPHON ACTIVATED, RADIAL FLOW, AND SELF-CLEANING. RADIAL MEDIA DEPTH SHALL BE 7 INCHES. FILTER MEDIA CONTACT TIME SHALL BE AT LEAST 38 SECONDS.
- SPECIFIC FLOW RATE IS EQUAL TO THE FILTER TREATMENT CAPACITY (gpm) DIVIDED BY THE FILTER CONTACT SURFACE AREA (ft²).

INSTALLATION NOTES

- ANY SUB-BASE, BACKFILL, DEPTH, AND/OR ANTI-FLOTTATION PROVISIONS ARE SITE-SPECIFIC DESIGN CONSIDERATIONS AND SHALL BE SPECIFIED BY ENGINEER OF RECORD.
- CONTRACTOR TO PROVIDE EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE CATCHBASIN (LIFTING CLUTCHES PROVIDED).
- CONTRACTOR TO TAKE APPROPRIATE MEASURES TO PROTECT CARTRIDGES FROM CONSTRUCTION-RELATED EROSION RUNOFF.

4-CARTRIDGE CATCHBASIN STORMFILTER DATA

STRUCTURE ID	XXXX
WATER QUALITY FLOW RATE (g/s)	XXX
PEAK FLOW RATE (<1 cfs)	XXX
RETURN PERIOD OF PEAK FLOW (yrs)	XXX
CATCHBASIN FLOW RATE (gpm)	XXX
MEDIA TYPE (PERLITE, ZPG, PSORB)	XXXXXX
PIPE DATA	XXXXXX
INLET STUB	XXXXXX
OUTLET STUB	XXXXXX

CONFIGURATION

SLOPED LID YES/NO
SOLID COVER YES/NO
NOTES/SPECIAL REQUIREMENTS:
PER ENGINEER OF RECORD

CONTECH
ENGINEERED SOLUTIONS LLC
www.contechES.com
9025 Center Pointe Dr., Suite 405, West Chester, OH 45380
900-226-3999 919-646-7000 919-646-7089 FAX

WATER QUALITY CATCH BASIN AND UNDERGROUND DETENTION SYSTEM CUT SHEETS ARE SAMPLES FOR REFERENCE ONLY. CONTRACTOR RESPONSIBLE FOR OBTAINING SITE SPECIFIC SHOP DRAWINGS FROM PRODUCT MANUFACTURERS AND SUBMITTING TO ENGINEER FOR REVIEW AND APPROVAL PRIOR TO ORDERING. PRODUCT INSTALLATION SHALL BE PER MANUFACTURER RECOMMENDATIONS.



EXPIRES: 12/31/20

REVISION SCHEDULE		
Delta	Issued As	Issue Date

SHEET TITLE:
CIVIL DETAILS

DRAWN BY: GIM
CHECKED BY: MWB
SHEET

C5.11

JOB NO. 2200339.00

REVISION SCHEDULE		
Delta	Issued As	Issue Date


SHEET TITLE:
**PUBLIC WATER MAIN
EXTENSION -
PLAN AND
PROFILE**

DRAWN BY: BTC


CHECKED BY: GIM

SHEET:



R2.0


NOTES

- PRIOR TO MOBILIZATION OF CONSTRUCTION EQUIPMENT AND MATERIALS, CONTRACTOR SHALL POTHOLE EXISTING UTILITIES IN THE AREA OF WORK AND NOTIFY ENGINEER IMMEDIATELY OF ANY DISCREPANCIES FROM THE INFORMATION SHOWN ON THE PLANS.
- PRIOR TO WATERLINE WORK, EXISTING MAINLINE SHALL BE SHUT OFF AT THE NEAREST DOWNSTREAM POINT. CONTRACTOR TO COORDINATE WITH THE APPROPRIATE CITY OF TUALATIN STAFF ACCORDINGLY.
- ALL WORK AND MATERIALS SHALL CONFORM TO THE CITY OF TUALATIN TECHNICAL SPECIFICATIONS. SEE CHAPTER 300, SECTIONS 326 THROUGH 329 (AND ASSOCIATED REFERENCES) FOR WATERLINE CONSTRUCTION AND SECTION 320 FOR TRENCH EXCAVATION AND BACKFILL REQUIREMENTS. SEE CITY OF TUALATIN DWG NO. 241 ON R3.0 FOR TRENCH & SURFACE RESTORATION DETAIL.
- ALL DUCTILE IRON AND PVC C900 PIPE AND FITTING WORK SHOWN HEREON SHALL BE FULLY RESTRAINED.
- CONTRACTOR TO COORDINATE DEPTHS OF NEW WATERLINES WITH PROPOSED/FUTURE FRANCHISE UTILITY SERVICE CONDUITS AND INFRASTRUCTURE. MAINTAIN A MINIMUM 1 FOOT CLEARANCE FROM WATER LINE.
- DO NOT BACKFILL EXCAVATIONS FOR CONNECTIONS UNTIL INSPECTED AND ACCEPTED BY THE CITY OF TUALATIN.
- CONTRACTOR TO COORDINATE FINISHED GRADES AND LANDSCAPING AROUND BACKFLOW DEVICES TO ENSURE ADEQUATE VISUAL SCREENING.


KEYNOTES

- CUT AND REMOVE PORTION OF EXISTING 12" DI WATER MAIN AS REQUIRED TO INSTALL NEW TEE. INSTALL 12" x 6" DI MJ x FLG TEE WITH 12" MJ CUT-IN SLEEVE
- 6" FLG x MJ GATE VALVE PER CITY OF TUALATIN DWG NO. 600
- 6" DI CL52 PIPE
- FIRE HYDRANT PER CITY OF TUALATIN DWG NO. 610
- REMOVE EXISTING FIRE HYDRANT AND GATE VALVE ASSEMBLY AND INSTALL DI BLIND FLANGE ON LATERAL
- REMOVE EXISTING 90 DEGREE PIPE BEND, PIPE, GATE VALVE, AND BLOW OFF ASSEMBLY.
- NOT USED
- 2" STAINLESS STEEL SADDLE TAP WITH CORPORATION STOP PER CITY OF TUALATIN DWG NO. 633
- 12" x 10" DI MJ REDUCER
- 10" x 10" DI MJ 90 DEGREE BEND
- 12" MJ x MJ GATE VALVE PER CITY OF TUALATIN DWG NO. 600
- 10" DI CL52 PIPE
- 10" DI MJ 45 DEGREE BEND
- 10" DOUBLE CHECK DETECTOR WITHOUT FDC PER CITY OF TUALATIN DWG NO. 614. COORDINATE POWER SUPPLY FOR SUMP PUMP AND FIRE ALARM SERVICE FOR TAMPER SWITCHES FROM HEDGES D BUILDING
- NOT USED
- NOT USED
- NOT USED
- MECHANICALLY JOIN EXISTING 10" WATER PIPE. USE PIPE ADAPTERS AS REQUIRED TO ACCOMMODATE DIFFERENCES IN MATERIAL.
- 2" "TYPE K" RIGID COPPER TUBE PER CITY OF TUALATIN DWG NO. 633
- 2" 90 DEGREE BRASS COMPRESSION FITTING PER CITY OF TUALATIN DWG NO. 633
- 2" METER BOX AND METER SETTER ASSEMBLY PER CITY OF TUALATIN DWG NO. 633
- 2" REDUCED PRESSURE BACKFLOW ASSEMBLY IN HEATED ENCLOSURE PER CITY OF TUALATIN DWG NO. 807. COORDINATE POWER SUPPLY FOR HEATED ENCLOSURE FROM HEDGES D BUILDING
- 2" SCH 40 PIPE
- 2" SCH 40 45 DEGREE BEND
- 2" SCH 40 90 DEGREE BEND
- 2" x 4" SCH 40 PIPE INCREASER
- JOIN EXISTING 4" WATER PIPE. USE PIPE ADAPTERS AS REQUIRED TO ACCOMMODATE DIFFERENCES IN MATERIAL
- PROPOSED LIGHT POLE LOCATION PER HEDGES C CIVIL PLANS
- POTENTIAL FRANCHISE UTILITY CONDUIT ROUTE
- EXISTING UTILITY BANK CROSSING BRIDGE TO HEDGES D SIDE OF CREEK
- INSTALL CATCH BASIN SEDIMENT FILTER PER 1/R3.0
- INSTALL SEDIMENT FENCE PER 2/R3.0

WATERLINE LEGEND

2 PUBLIC WATER MAIN EXTENSION - PROFILE
 R2.0 HORIZONTAL: 1" = 5'
 VERTICAL: 1" = 3'

REVISION SCHEDULE		
Delta	Issued As	Issue Date

SHEET TITLE:
**PUBLIC WATER
MAIN
EXTENSION -
DETAILS**

DRAWN BY: BTC
CHECKED BY: GIM
SHEET:

R3.0

PIPE SIZE	OLDCASTLE	COVER OFFSET
4"	687-WA	2-332P
6"	687-WA	2-332P
8"	5106-LA	3-332P
10"	5106-LA	3-332P

NOTES:

- USE DUCTILE IRON PIPE THROUGH AND 5' BEYOND VAULT ON PRIVATE SIDE DUE TO VAULT SETTLEMENT; NO PIPE BELL ENDS INSIDE VAULT.
- INSTALL PLUGS IN TEST COCKS.
- ASSEMBLY MAY ALSO BE MOUNTED ABOVE GROUND IN AN INSULATED PROTECTIVE ENCLOSURE AT THE RIGHT-OF-WAY.
- CHECK VAULT FLOTATION AND CORRECT IF NECESSARY.
- BACKFLOW ASSEMBLY AND INSTALLATION TO COMPLY WITH AWWA C510 AND OAR 333-61-070.
- PROVIDE SUMP PUMP WITH DIAPHRAGM OR VERTICAL FLOAT SWITCH AND 2" PVC CHECK VALVE AND PIPE DISCHARGE TO DAYLIGHT. SUPPLY POWER THRU GFCI INTERNAL WALL MOUNT 12" BELOW CEILING.
- PROVIDE INSPECTOR WITH CERTIFIED TEST REPORT UPON COMPLETION.

NOTES:

- APPLY WATER MAIN'S TEST PRESSURE AGAINST CLOSED MAIN VALVE IN THE HYDRANT AND NOT THROUGH THE HYDRANT.
- FIRE HYDRANT REQUIREMENTS: WATERLOUS PACER WB-67 (WITH 1 1/2" UPPER STANDPIPE), CLOW MEDALLION OR F-2500; MUELLER SUPER CONTORION 250, M & H VALVE 929 RELIANT, EAST JORDAN 500 250, OR KENNEDY-K-81; WITH ONE 4-7/2" PUMPER W/ 1 1/2" TAP. ALL HYDRANT PARTS TO BE YELLOW. REMOVE NOZZLE CHIP CHAIN. RED PRIVATE HYDRANTS ARE TO BE YELLOW. REMOVE NOZZLE CHIP CHAIN.
- INSTALL HYDRANT IN ACCORDANCE WITH AWWA MANUAL M17 AND CONFORM TO AWWA C502.
- PROVIDE HORIZONTAL CLEAR ZONE OF 36" MINIMUM AROUND FIRE HYDRANT.

NOTES:

- COMPLY WITH OAR 333-61-070 AND AWWA C511, WHICH REQUIRES BACKFLOW ASSEMBLY TO BE APPROVED BY THE OREGON STATE HEALTH DIVISION; FLUSH SUPPLY LINE BEFORE INSTALLATION.
- MOUNT ASSEMBLY ABOVE GROUND IN A HEATED, INSULATED, AND PROTECTIVE ENCLOSURE (HOT BOX OR SIMILAR) AT THE RIGHT-OF-WAY IN A LOCATION APPROVED BY CITY OF TUALATIN.
- PLACE FLOOR LEVEL ABOVE THE 100-YEAR FLOOD ELEVATION WITH ADEQUATE DRAINAGE FOR DISCHARGE TO DAYLIGHT CAPABLE OF DRAINING A FULL RELIEF VALVE DISCHARGE SIZED PER AWWA STANDARDS.
- DESIGNED HEATING TO MAINTAIN A MINIMUM AMBIENT TEMPERATURE OF 40°F WITH AN OUTSIDE TEMPERATURE OF -10°F AND WIND SPEED OF 20 MPH. CLEARANCES SHOWN ARE MINIMUM.
- WALL MOUNT ALL ELECTRICAL EQUIPMENT TO MEET ALL RELEVANT CODES FOR ELECTRICAL EQUIPMENT AND INSTALLATION.
- PROVIDE INSPECTOR WITH CERTIFIED TEST REPORT UPON COMPLETION.

NOTES:

- EAST JORDAN IRON WORKS, OLYMPIC FOUNDRY, INC. OR EQUAL MUST BE HEAVY DUTY CAST IRON VALVE BOX TOP SECTION 18" LENGTH ALIGN OVER WRENCH NUT. VALVE BOX LID EMBOSSED WITH WORD, "WATER".
- 4" MIN., 14" MAX. WHEN TOP SECTION IN FINAL POSITION.
- BOTTOM SECTION (WHEN REQUIRED) ONE PIECE 6" SEWER PIPE ASTM D3034 OR 35 CUT TO FIT VALVE BONNET.
- 2" SQUARE WRENCH NUT OPEN LEFT HAND PROVIDE EXTENSION STEM TO POSITION NUT MAXIMUM 4" BELOW FINISHED GRADE.
- AWWA C509 RESILIENT-SEAT GATE VALVE NRS SIZES 16" AND SMALLER.
- HAND TAMP BACKFILL AROUND VALVE BOX TOP AND BOTTOM SECTIONS, AND GATE VALVE.
- NRS GATE VALVE WITH MECHANICAL JOINT OR FLANGED ENDS. USE MECHANICAL JOINT WHEN CONNECTING TO PIPE AND FLANGE WHEN ADJACENT TO FITTING. SET VALVE STEM VERTICAL TRANSVERSE TO LINE. DO NOT INSTALL VALVE ON ITS SIDE EVEN WHEN NON-FUNCTIONAL.

NOTES:

- BURY BOTTOM OF FILTER FABRIC 6" MIN VERTICALLY BELOW FINISHED GRADE
- UTILIZE 2" x 2" FIR, PINE, OR STEEL FENCE POSTS TO ANCHOR FENCING
- ATTACH FENCING TO POSTS USING STITCHED LOOPS INSTALLED ON UPHILL SIDE OF SLOPE
- COMPACT THE NATIVE FILL IN ALL AREAS OF FILTER FABRIC TRENCH
- ACCUMULATED SEDIMENT CAN BE ALLOWED TO REACH NO MORE THAN ONE-THIRD OF THE SEDIMENT FENCE HEIGHT

NOTES:

- THE CONTRACTOR IS RESPONSIBLE FOR PROVIDING THE CORRECT SIZE DEVICE FOR EACH INLET
- THE INLET SEDIMENT CONTROL DEVICE SHALL BE OF NORMAL FLOW DESIGN, 40 GAL/MIN/SF WITH NO OVERFLOWS
- THE SEDIMENT CONTROL DEVICE SHALL BE INSPECTED DAILY BY THE CONTRACTOR AND MAINTAINED A MINIMUM OF ONCE PER MONTH AND WITHIN THE 24 HOURS FOLLOWING A STORM EVENT
- SUBSTITUTION OF A SHEET OF FILTER FABRIC PLACED OVER THE OPENING OF THE INLET IS NOT APPROVED

NOTES:

- FLUSH LINE AFTER CONNECTION TO CORPORATION STOP AND BEFORE CONNECTING TO METER
- NOT EXCEED 80 GPM
- APPROVED EQUAL VALVES & FITTINGS FROM FORD OR MUELLER SHALL MEET THE REQUIREMENTS OF AWWA C-500

NOTES:

- SEE STANDARD DRAWING NO. 480 FOR ROADS PAVED WITHIN THE LAST 5 YEARS.
- SEE STANDARD DRAWING NO. 481 FOR CONCRETE ROADWAY RESTORATION.
- WHEN TRENCH WIDTH IS LESS THAN 2' WIDE, BACKFILL WITH CLASS E, CONTROLLED LOW STRENGTH MATERIAL (CLSM) WITH A 28-DAY DESIGN STRENGTH OF 100-200 PSI.
- SAWCUT A MINIMUM OF 12" OF PAVEMENT FROM EDGE OF TRENCH.
- COMPACT CRUSHED AGGREGATE BACKFILL TO 92% AASHTO T 180, AND COMPACT NATIVE MATERIAL TO 90% AASHTO T 99, OR TO SATISFACTION OF CITY ENGINEER.
- PROVIDE A MINIMUM ASPHALT THICKNESS OF 6" OR MATCH EXISTING THICKNESS, WHICHEVER IS GREATER.
- IF LESS THAN 3" OF UNDISTURBED ASPHALT REMAINS BETWEEN THE EXCAVATION AND EDGE OF THE ROADWAY, REMOVE AND REPAIR THE REMAINING AREA.

S 89°37'58" W 888.88'

TOP OF BANK

FLAGGED WETLAND LINE

TOP OF BANK

N 00°02'48" W 606.66'

25'-0"

32


TOP OF BANK

FLAGGED WETLAND LINE

S 89°20'21" E 561.11'

LANDSCAPE PLAN

SCALE 1" = 30'-0"




PLANT LEGEND: GENERAL LANDSCAPING

SYMBOL	QTY.	LATIN NAME / Common Name	SIZE	SPACING
TREES				
	15	ACER MACROPHYLLUM Big Leaf Maple	1.5" cal.	As Shown
	51	ACER TRUNC. x PLAT. 'KEITHSFORM' Norwegian Sunset Maple	1.5" cal.	As Shown
	7	CARPINUS BETULUS 'FRANZ FONTAINE' Franz Fontaine European Hornbeam	1.5" cal.	As Shown
	15	THUJA PLICATA 'HOGAN' Hogan Western Red Cedar	1.5" cal.	As Shown
SHRUBS				
	292	ABELIA GRAND. 'PROSTRATA' Prostrata White Abelia	1 gal.	3' o.c.
	20	LIGUSTRUM JAPONICUM 'TEXANUM' Waxleaf Privet	5 gal.	4' o.c.
	40	NANDINA 'LEMON LIME' Lemon Lime Nandina	2 gal.	3' o.c.
	79	PIERIS JAPONICA 'FOREST FLAME' Forest Flame Pieris	5 gal.	4' o.c.
	51	RHODODENDRON 'DORA AMATEIS' Dora Amateis Rhododendron	5 gal.	4' o.c.
	216	VIBURNUM DAVIDII David Viburnum	2 gal.	3' o.c.
GROUNDCOVER & PERENNIALS				
	452	ARCTOSTAPHYLOS U.L. 'MASSACHUSETTS' Massachusetts Kinikinnick	1 gal.	3' o.c.
	427	COTONEASTER DAM. 'CORAL BEAUTY' Bearberry Cotoneaster	1 gal.	4' o.c.
	23	Sword Fern	1 gal.	3' o.c.

GENERAL NOTES:

1. Sensitive Area/vegetated corridor landscaping to be coordinated by owners with Clean Water Services.
2. Contractor is to verify all plant quantities.
3. Adjust plantings in the field as necessary.
4. Project is to be irrigated by an automatic, underground system, which will provide full coverage for all plant material. System is to be design/ build by Landscape Contractor. Guarantee system for a minimum one year. Show drip systems as alternate bid only.
5. All plants are to be fully foliated, well branched and true to form.
6. Contractor is to notify Landscape Architect or Owner's Representative of any site changes or unforeseen conditions that may be detrimental to plant health, or cause future problems to any structural elements of the project.
7. Contractor shall notify the Landscape Architect if specified materials or methods are not consistent with local climate and/or practices.

NO.	DATE	REVISIONS



OTTEN + ASSOCIATES
LANDSCAPE ARCHITECTURE
3933 South Kelly Avenue, Suite B • Portland, OR 97239
Phone: (503) 972-0311 • www.ottenla.com

HEDGES D
SW 115TH STREET
TUALATIN, OREGON
LANDSCAPE PLAN

DATE	9-2-2020
SCALE	NOTED
DRAWN	CHECKED
DM	EH

SHEET NO
L1.0
1 OF 1

OUTLINE SPECIFICATIONS PLANTING AND SEEDING:

GENERAL: All plants shall conform to all applicable standards of the latest edition of the "American Association of Nurserymen Standards", A.N.S.I. Z60.1 – 1973. Meet or exceed the regulations and laws of Federal, State, and County regulations, regarding the inspection of plant materials, certified as free from hazardous insects, disease, and noxious weeds, and certified fit for sale in Oregon.

The apparent silence of the Specifications and Plans as to any detail, or the apparent omission from them of a detailed description concerning any point, shall be regarded as meaning that only the best general practice is to prevail and that only material and workmanship of first quality are to be used. All interpretations of these Specifications shall be made upon the basis above stated.

Landscape contractor shall perform a site visit prior to bidding to view existing conditions.

PERFORMANCE QUALITY ASSURANCE: Use adequate numbers of skilled workmen who are thoroughly trained and experienced in the necessary horticultural practices and who are completely familiar with the specified requirements and methods needed for the proper performance of the work of this section.

NOTIFICATION: Give Landscape Architect minimum of 2 days advance notice of times for inspections. Inspections at growing site does not preclude Landscape Architect's right of rejection of deficient materials at project site. Each plant failing to meet the above mentioned "Standards" or otherwise failing to meet the specified requirements as set forth shall be rejected and removed immediately from the premises by the Contractor and at his expense, and replaced with satisfactory plants or trees conforming to the specified requirements.

SUBSTITUTIONS: Only as approved by the Landscape Architect or the Owner's Representative.

GUARANTEE AND REPLACEMENT: All plant material shall be guaranteed from final acceptance for one full growing season or one year, whichever is longer. During this period the Contractor shall replace any plant material that is not in good condition and producing new growth (except that material damaged by severe weather conditions, due to Owner's negligence, normally unforeseen peculiarities of the planting site, or lost due to vandalism). Guarantee to replace, at no cost to Owner, unacceptable plant materials with plants of same variety, age, size and quality as plant originally specified. Conditions of guarantee on replacement plant shall be same as for original plant.

Landscape Contractor shall keep on site for Owner's Representative's inspection, all receipts for soil amendment and topsoil deliveries.

PROTECTION: Protect existing roads, sidewalks, and curbs, landscaping, and other features remaining as final work. Verify location of underground utilities prior to doing work. Repair and make good any damage to service lines, existing features, etc. caused by landscaping installation.

PLANT QUALITY ASSURANCE: Deliver direct from nursery. Maintain and protect roots of plant material from drying or other possible injury. Store plants in shade and protect them from weather immediately upon delivery, if not to be planted within four hours.

Nursery stock shall be healthy, well branched and rooted, formed true to variety and species, full foliated, free of disease, injury, defects, insects, weeds, and weed roots. Trees shall have straight trunks, symmetrical tips, and have an intact single leader. Any trees with double leaders will be rejected upon inspection. All Plants: True to name, with one of each bundle or lot tagged with the common and botanical name and size of the plants in accordance with standards of practice of the American Association of Nurserymen, and shall conform to the Standardized Plant Names, 1942 Edition.

Container grown stock: Small container-grown plants, furnished in removable containers, shall be well rooted to ensure healthy growth. **Grow container plants in containers a minimum of one year** prior to delivery, with roots filling container but not root bound. Bare root stock: Roots well-branched and fibrous. Balled and burlapped (B&B): Ball shall be of natural size to ensure healthy growth. Ball shall be firm and the burlap sound. No loose or made ball will be acceptable.

TOPSOIL AND FINAL GRADES: Landscape Contractor is to supply and place 12" of topsoil in planting beds and 6" in lawn areas. Landscape Contractor is to verify with the General Contractor if the on-site topsoil is or is not conducive to proper plant growth. The topsoil shall be a sandy loam, free of all weeds and debris inimical to lawn or plant growth. Furnish soil analysis by a qualified soil testing laboratory stating percentages of organic matter; gradation of sand, silt and clay content; cation exchange capacity; deleterious material; pH; and plant nutrient content of the topsoil. Report suitability of topsoil for plant growth and recommended quantities of nitrogen, phosphorus and potash nutrients and soil amendments (including compost) to be added to produce satisfactory topsoil. If stockpiled topsoil on site is not conducive to proper plant growth, the Landscape Contractor shall import the required amount.

Landscaping shall include finished grades and even distribution of topsoil to meet planting requirements. Grades and slopes shall be as indicated. Planting bed grades shall be approximately 3" below adjacent walks, paving, finished grade lines, etc., to allow for bark application. Finish grading shall remove all depressions or low areas to provide positive drainage throughout the area.

PLANTING SPECIFICATIONS:

HERBICIDES: Prior to soil preparation, all areas showing any undesirable weed or grass growth shall be treated with Round-up in strict accordance with the manufacturer's instructions.

SOIL PREPARATION: Work all areas by rototilling to a minimum depth of 8". Remove all stones (over 1 1/2" size), sticks, mortar, large clumps of vegetation, roots, debris, or extraneous matter turned up in working. Soil shall be of a homogeneous fine texture. Level, smooth and lightly compact area to plus or minus .10 of required grades.

In groundcover areas add 2" of compost (or as approved) and till in to the top 6" of soil.

PLANTING HOLE: Lay out all plant locations and excavate all soils from planting holes to 2 1/2 times the root ball or root system width. Loosen soil inside bottom of plant hole. Dispose of any "subsoil" or debris from excavation. Check drainage of planting hole with water, and adjust any area showing drainage problems.

SOIL MIX: Prepare soil mix in each planting hole by mixing:

- 2 part native topsoil (no subsoil)
- 1 part compost (as approved)

Thoroughly mix in planting hole and add fertilizers at the following rates:

- Small shrubs - 1/8 lb./ plant
- Shrubs - 1/3 to 1/2 lb./ plant
- Trees - 1/3 to 1 lb./ plant

FERTILIZER: For trees and shrubs use Commercial Fertilizer "A" Inorganic (5-4-3) with micro-nutrients and 50% slow releasing nitrogen. For initial application in fine seed lawn areas use Commercial Fertilizer "B" (8-16-8) with micro-nutrients and 50% slow-releasing nitrogen. For lawn maintenance use Commercial Fertilizer "C" (22-16-8) with micro-nutrients and 50% slow-releasing nitrogen. DO NOT apply fertilizer to Water Quality Swale.

PLANTING TREES AND SHRUBS: Plant upright and face to give best appearance or relationship to adjacent plants and structures. Place 6" minimum, lightly compacted layer of prepared planting soil under root system. Loosen and remove twine binding and burlap from top 1/2 of root balls. Cut off cleanly all broken or frayed roots, and spread roots out. Stagger Plants in rows. Backfill planting hole with soil mix while working each layer to eliminate voids.

When approximately 2/3 full, water thoroughly, then allow water to soak away. Place remaining backfill and dish surface around plant to hold water. Final grade should keep root ball slightly above surrounding grade, not to exceed 1". Water again until no more water is absorbed. Initial watering by irrigation system is not allowed.

STAKING OF TREES: Stake or guy all trees. Stakes shall be 2" X 2" (nom.) quality tree stakes with point. They shall be of Douglas Fir, clear and sturdy. Stake to be minimum 2/3 the height of the tree, not to exceed 8'-0". Drive stake firmly 1'-6" below the planting hole. Tree ties for deciduous trees shall be "Chainlock" (or better). For Evergreen trees use "Gro-Strait" Tree Ties (or a reinforced rubber hose and guy wires) with guy wires of a minimum 2 strand twisted 12 ga. wire. Staking and guying shall be loose enough to allow movement of tree while holding tree upright.

MULCHING OF PLANTINGS: Mulch planting areas with dark, aged, medium grind fir or hemlock bark (aged at least 6 months) to a depth of 2" in ground cover areas and 2 1/2" in shrub beds. Apply evenly, not higher than grade of plant as it came from the nursery, and rake to a smooth finish. Water thoroughly, then hose down planting area with fine spray to wash leaves of plants.

FINE LAWN AREAS: In fine lawn area apply Commercial Fertilizer Mix "B" at 4.5 lbs. per 1,000 sq.ft. and rake into soil surface. Establish an even, fine textured seedbed meeting grades, surfaces and texture. Sow seed with a mechanical spreader at the uniform rates as noted below. Rake seed lightly to provide cover.

ROUGH SEED AREA: In rough seeded area, establish an evenly graded seedbed. Sow seed with a mechanical spreader at the uniform rates as noted below. Rake seed lightly to provide cover.

SEED: Blue tag grass seed conforming to applicable State laws. No noxious weed seeds. Submit Guaranteed analysis.

Fine Lawn Seed Mix: To contain 50% Top Hat Perennial Ryegrass, 30% Derby Supreme Ryegrass, 20% Longfellow Chewings Fescue (Hobbs and Hopkins Pro-Time 303 Lawn Mix or as approved) Sow Seed at 5 lbs. / 1000 sq. ft.


Rough Seed Mix: To Contain: 60% Perennial Ryegrass, 15% Eureka Hard Fescue, and 20% Herbaceous Plants and Clover (Hobbs and Hopkins Pro-Time 705 PDX, or approved equal). Sow at 2 lbs. Per 1,000 sq.ft.

MAINTENANCE OF SEEDED AREAS:


Fine Lawn Areas: The lawn areas shall be maintained by watering, mowing, reseeding, and weeding for a minimum of 60 days after seeding. After 30 days, or after the second mowing, apply Commercial Fertilizer Mix "C" at 5 lbs. per 1,000 sq. ft. Mow and keep at 1 1/2" to 2" in height. Remove clippings and dispose of off site.

GENERAL MAINTENANCE: Protect and maintain work described in these specifications against all defects of materials and workmanship, through final acceptance. Replace plants not in normal healthy condition at the end of this period. Water, weed, cultivate, mulch, reset plants to proper grade or upright position, remove dead wood and do necessary standard maintenance operations. Irrigate when necessary to avoid drying out of plant materials, and to promote healthy growth.


CLEAN-UP: At completion of each division of work all extra material, supplies, equipment, etc., shall be removed from the site. All walks, paving, or other surfaces shall be swept clean, mulch areas shall have debris removed and any soil cleared from surface. All areas of the project shall be kept clean, orderly and complete.



SHRUB PLANTING DETAIL
NOT TO SCALE



EVERGREEN TREE STAKING DETAIL
NOT TO SCALE



NOTE: ANY PROPOSED CHANGES TO OUR SPECIFICATION OR DETAIL SHOULD BE APPROVED BY THE LANDSCAPE ARCHITECT. LIKEWISE, IN ACCORDANCE WITH BEST PRACTICES OF LOCAL LANDSCAPE INSTALLATION, SHOULD THE LANDSCAPE CONTRACTOR FIND A PREFERRED ALTERNATE METHOD, THE LANDSCAPE ARCHITECT MAY BE SO ADVISED.

GENERAL DECIDUOUS TREE PLANTING DETAIL
NOT TO SCALE


NO.	DATE	REVISIONS



OTTEN + ASSOCIATES
LANDSCAPE ARCHITECTURE
3933 South Kelly Avenue, Suite B • Portland, OR 97239
Phone: (503) 972-0311 • www.ottenla.com

HEDGES D
SW 115TH STREET
TUALATIN, OREGON
LANDSCAPE PLAN

DATE	9-2-2020
SCALE	AS SHOWN
DRAWN	CHECKED
DM	EH
SHEET NO	L2.0
	2 OF 2



Scale: 1 inch= 30 Ft.

Label	Description	CalcType	Units	Avg	Max	Min	Avg/Min	Max/Min
PERIMETER PARKING	calculation at perimeter of Sensitive Area Vegetated No Build area	Illuminance	Fc	1.51	4.0	0.2	7.55	20.00
perimeter 10'	calculation 10' inside the Sensitive Area Vegetated No Build area	Illuminance	Fc	0.31	1.6	0.0	N.A.	N.A.
perimeter 5'	calculation 5' inside the Sensitive Area Vegetated No Build area	Illuminance	Fc	0.15	0.4	0.0	N.A.	N.A.

Symbol	Qty	Label	Manufacturer	Part # Description	LLF	Arm	Arrangement	Arr. Lum. Lumens	Arr. Watts	Filename	BUG Rating
1	1	TMU-E05-SL	COOPER LIGHTING SOLUTIONS - STREETWORKS (FORMERLY EATON)	TMU-E05-LED-E-U-SLL	0.900	0.66725	SINGLE	13912	127.3	TMU-E05-LED-E-U-SLL.ies	B2-UD-G3
1	1	TMU-E05-SLR	COOPER LIGHTING SOLUTIONS - STREETWORKS (FORMERLY EATON)	TMU-E05-LED-E-U-SLR	0.900	0.66725	SINGLE	13912	127.3	TMU-E05-LED-E-U-SLR.ies	B2-UD-G3
4	4	TMU-E05-SL4-HSS	COOPER LIGHTING SOLUTIONS - STREETWORKS (FORMERLY EATON)	TMU-E05-LED-E-U-SL4-HSS	0.900	0.66725	SINGLE	10174	127.3	TMU-E05-LED-E-U-SL4-HSS.ies	B1-UD-G3
12	12	TMU-E05-SL3-HSS	COOPER LIGHTING SOLUTIONS - STREETWORKS (FORMERLY EATON)	TMU-E05-LED-E-U-SL3-HSS	0.900	0.66725	SINGLE	8669	127.3	TMU-E05-LED-E-U-SL3-HSS.ies	B0-UD-G2
16	16	TMU-E05-T4_D	COOPER LIGHTING SOLUTIONS - STREETWORKS (FORMERLY EATON)	TMU-E05-LED-E-U-T4	0.900	0.66725	2 @ 180 DEGREES	30220	254.6	TMU-E05-LED-E-U-T4.ies	B2-UD-G3

NOTES:
 1. LIGHT LOSS FACTOR APPLIED, INITIAL VALUES WILL BE HIGHER
 2. FIXTURE HEIGHT: NOTED
 3. POLE HEIGHT: FIXTURE HEIGHT LESS BASE
 4. STANDARD REFLECTANCE USED: 20% GROUND EQUAL TO ASPHALT
 5. CALCULATION POINTS LOCATED ON GROUND

Hedges D – Fleet Parking Lot



11507 SW 115th Avenue (private street), Tualatin, OR 97062

3. Public Notice

- a. Documentation for Neighborhood Development Meeting
- b. Certification of Sign Posting (Installation after AR is accepted & I.D. provided)

Meeting Minutes

The meeting was held on 8/7/2020 @ 6:00 PM via Zoom. There were no people who showed up for the meeting or participated. I have screenshot below from the meeting to show that the meeting was held for 30 minutes without any other participants.



**NOTICE OF NEIGHBORHOOD
DEVELOPER MEETING**

July 22nd, 2020

Hedges D, an LLC
PO Box 15523
Seattle WA 98115

RE: Hedges D, located at the end of SW 115th St.

Dear Property Owner:

You are cordially invited to attend a neighborhood meeting on **8/7/2020 @ 6:00 PM via Zoom, log in for free with Meeting ID: 759 2066 8950, Passcode: 9Hcen6**. This meeting shall be held to discuss a proposed project located at the end of SW 115th St. The proposal is to build a vehicle storage parking lot. This parking lot will conform to all Tualatin city standards and will have 4.5 acres of buffer and plantings around it for screening and environmental benefits. This site is zoned General Manufacturing ("MG") and is controlled by Chapter 61 of the Tualatin Development Code. Per Table 61-1, Vehicle Storage is a permitted use in the MG zone. We have already received land use approval for this site in the past, but we have changed the site plan enough to require another land use approval.

This is an informational meeting to share the development proposal with interested neighbors. You will have the opportunity to review preliminary plans and identify topics of interest for consideration. If you have any questions or comments ahead of time, please email them to me at the email provided below.

Regards,



Mac Martin
Martin Development
MartinDevelopment@outlook.com

cc: lsanford@tualatin.gov ; Tualatin Community Development Department

CERTIFICATION OF SIGN POSTING

<p>NOTICE</p> <p>NEIGHBORHOOD / DEVELOPER MEETING</p> <p>___/___/2010 __:__.m.</p> <p>SW _____</p> <p>503-___-___</p>

In addition to the requirements of [TDC 31.064\(2\)](#), the 18" x 24" sign must display the meeting date, time, and address as well as a contact phone number. The block around the word "NOTICE" must remain orange composed of the RGB color values Red 254, Green 127, and Blue 0. Staff has a Microsoft PowerPoint 2007 template of this sign design available through the Planning Division homepage at:

<https://www.tualatinoregon.gov/planning/land-use-application-sign-templates>

As the applicant for the Hedges D, Parking Lot project, I hereby certify that on this day, July 24th, 2020 sign(s) was/were posted on the subject property in accordance with the requirements of the Tualatin Development Code and the Community Development Division.

Applicant's Name: Mac Martin, Managing Member

(Please Print)

Applicant's Signature: 

Date: September 2nd, 2020

Hedges D: Neighborhood Meeting Packet: Parking Lot



Neighborhood Developer Meetings
Community Development Department - Planning Division

AFFIDAVIT OF MAILING NOTICE

STATE OF OREGON)
) SS
COUNTY OF WASHINGTON)

I, Mackenzie Martin being first duly sworn, depose and say:

That on the 2nd day of September, 2020, I served upon the persons shown on Exhibit "A" (Mailing Area List), attached hereto and by this reference incorporated herein, a copy of the Notice of Neighborhood/Developer Meeting marked Exhibit "B," attached hereto and by this reference incorporated herein, by mailing to them a true and correct copy of the original hereof. I further certify that the addresses shown on said Exhibit "A" are their regular addresses as determined from the books and records of the Washington County and/or Clackamas County Departments of Assessment and Taxation Tax Rolls, and that said envelopes were placed in the United States Mail with postage fully prepared thereon.



Signature

SUBSCRIBED AND SWORN to before me this _____ day of _____, 20_____.

Due to COVID concerns,
I didn't want to go into an office
and get this notarized, but this
makes my statement no less true
or valuable. Thanks

Notary Public for Oregon
My commission expires:

RE: _____

CERTIFICATION OF SIGN POSTING



The applicant must provide and post a sign pursuant to Tualatin Development Code (TDC 32.150). The block around the word "NOTICE" must remain yellow composed of the RGB color values Red 255, Green 255, and Blue 0. A template is available at:

<https://www.tualatinoregon.gov/planning/land-use-application-sign-templates>

NOTE: For larger projects, the Community Development Department may require the posting of additional signs in conspicuous locations.

As the applicant for the _____ project,
I hereby certify that on this day, _____ sign(s) was/were posted on the subject property in
accordance with the requirements of the Tualatin Development Code and the Community Development Division.

Applicant's Name: _____
(Please Print)

Applicant's Signature: _____

Date: _____

Hedges D – Fleet Parking Lot

11507 SW 115th Avenue (private street), Tualatin, OR 97062

4. Reports

- a. Transportation Impact Study
- b. Stormwater Management Report
- c. Existing Bridge – Field Evaluation Report

September 11, 2020

Project #: 23574

Mac Martin
Martin Development
P.O. Box 15523
Seattle, WA 98115

RE: Hedges D Development Trip Debiting Letter – September 2020 Update

Dear Mac:

This letter documents the anticipated site trip generation for Hedges D development within the Franklin Business Park in Tualatin. Kittelson & Associates, Inc. previously prepared a debiting letter for this site dated January 16, 2020 reflecting the anticipated construction of a 76,872 square foot manufacturing building. Based on evolving market conditions and tenant needs, a 349-space secure fleet surface parking facility is now proposed in lieu of the planned manufacturing building.

This letter provides trip generation estimates for the fleet parking use, documents trips associated with previously approved site development, and compares the total trip generation of the proposed and constructed uses with the vested overall site trip generation. As documented herein, the trip generation associated with the proposed Hedges D development is consistent with the previously analyzed full build-out of Franklin Business Park. Further, upon completion of Hedges D, additional vested trips will remain for other future site development. As such, no further traffic impact analysis is needed.

BACKGROUND

As documented in the 1999 traffic study for the Franklin Business Park, a total of 1,328 trips were vested for overall site development. To date, approved and constructed site development includes:

- 101,400 square foot warehousing building;
- 64,808 square foot building with 30,000 square feet of office space and 34,808 square feet of warehousing space; and,
- 72,255 square foot Hedges C manufacturing building (as constructed).

The proposed new secure surface parking lot will be used for overnight storage of a fleet of Sprinter delivery vans (the delivery vans will all be dispatched off-site during the daytime supporting a nearby distribution center). Typical use of the surface parking lot is anticipated as follows:

- The parking area will house Sprinter vans overnight and employee's personal vehicles during the daytime hours.

- The drivers (employees) will arrive at the site in the morning, pick-up their assigned Sprinter van and travel off-site for package loading at the distribution center and subsequent customer delivery.
 - Sprinter drivers will arrive at the parking lot and then depart in their assigned delivery van over the course of staggered start times to allow for appropriate pick-up staging at the delivery center.
 - Sprinter drivers are expected to arrive for their workday in nine groups of people spaced between 9:15 AM and 1:00 PM. The drivers will participate in a daily safety meeting lasting about 15 minutes and then depart for loading off-site. The designated start time for individual drivers reflects both operator efforts to avoid their fleet mixing with peak traffic loading on the transportation network and the delivery needs (timing) of customers.
- Drivers will return their assigned Sprinter van to the parking area in the evening after completing their 10-hour delivery shift.
 - Sprinter drivers are expected to return to the overnight parking lot between approximately 7:10 PM and 10:30 PM (many customer deliveries occur in the late afternoon/early evening hours). The return times reflect operator efforts to spread out the arrivals of inbound drivers with the departures of outbound personal vehicles and outside the evening commuter peak.
- Most of the drivers are expected to commute to and from the fleet parking facility in one of three ways:
 - By personal vehicle, in which case they will park their vehicle on-site upon arrival in the morning and depart with their personal vehicle in the evening;
 - By a company shuttle that provides transportation for drivers to an off-site parking location whether their personal vehicles are housed; or
 - By bicycle, in which case they will park their bicycle in the designated bike rack on-site.

A small number of drivers may be dropped off at the parking area by others, given the somewhat uncertain return end-of-day pickup time associated with variable delivery needs/scheduling for any given driver.

TRIP GENERATION ESTIMATE

To date, weekday daily, AM peak hour and PM peak hour vehicle trip generation estimates for Franklin Business Park site development have been prepared using trip rates from the *Trip Generation Manual, 9th Edition*, as published by the Institute of Transportation Engineers. Our review of both the 9th and

10th Edition of the *Trip Generation Manual* revealed that there is no land use data available directly reflective of the proposed fleet parking use or the unique staffing hours proposed for the fleet drivers.¹ Lacking data from the *Trip Generation Manual*, a quantitative estimate of the site trip generation was developed predicated on the following assumptions:

- The adjacent street system morning commute peak is generally considered to occur between 7:00 and 9:00 AM whereas the fleet parking shift arrival is expected to occur between 9:15 AM and 1:00 PM, suggesting the vast majority (and possibly all) of the inbound driver movements in the morning should occur outside the traditional commuter peak hour.
- The adjacent street system evening commute peak is generally considered to occur between 4:00 and 6:00 PM whereas the fleet parking shift is expected to conclude between 7:10 and 10:30 PM, suggesting all of the evening site trips could occur well outside the traditional commuter peak hour.
- The owner anticipates the parking lot will be fully utilized overnight during the peak November-early January delivery period and about 50% utilized the remainder of the year².
- Trips can be tracked to individual Sprinter vehicles and employee vehicles as presented below by season.

Sprinter Vehicle Trips

- Each Sprinter vehicle will depart the site in the morning at the start of the delivery driver shift (one trip out) and will enter the site in the evening at the end of the shift (one trip in), resulting in two trips at the site per day per Sprinter van.

December-Early January Peak Season

- Daily Sprinter van trips = (1 trip out + 1 trip in) × 349 Sprinter vans = 698 trips

¹ The Park-and-Ride Lot with Bus or Light Rail Service (Land Use Code 90) was noted as a potential proxy use in the *Trip Generation Manual, 10th Edition* and has an average trip rate of 0.43 trips per parking space. While available, the Park-and-Ride Lot trip data is not reflective of the bi-directional nature of site trips with employees arriving in one vehicle and departing in another within the same hour.

² Additional “surge fleet” vehicle use is anticipated on-site during the Christmas holiday shopping season when supplemental delivery vehicles are used to support peak holiday delivery volume. The operator expects the entire surface parking lot to be occupied overnight by delivery vehicles during peak delivery season (typically November through late December/early January) with the lot approximately 50 percent utilized the remainder of the year.

- 9:15-1:00 PM trips = 1 trip out × 349 Sprinter vans = 349 trips out
 - Recognizing that all outbound trips are anticipated to occur starting after the safety briefing that begins at 9:15 AM, one could reasonably conclude no outbound trips occur between 7:00 and 9:00 AM.
- 7:10-10:30 PM trips = 1 trip in × 349 Sprinter vans = 349 trips in
 - Recognizing that all of inbound trips are anticipated to occur starting at 7:10 PM, one could reasonably conclude no site trips occur between 4:00 and 6:00 PM.

Late January-October Season

- Daily Sprinter van trips = (1 trip out + 1 trip in) × 175 Sprinter vans = 350 trips
- 9:15 AM-1:00 PM trips = 1 trip out × 175 Sprinter vans = 175 trips out
 - Recognizing that all outbound trips are anticipated to occur starting after the safety briefing that begins at 9:15 AM, one could reasonably conclude no outbound trips occur between 7:00 and 9:00 AM.
- 7:10-10:30 PM trips = 1 trip in × 175 Sprinter vans = 175 trips in
 - Recognizing that all of inbound trips are anticipated to occur starting at 7:10 PM, one could reasonably conclude no site trips occur between 4:00 and 6:00 PM.

Sprinter Employee Trips

- Each Sprinter vehicle is operated by a single employee during the course of a typical workday.
- Each employee that commutes to the fleet parking facility in a single occupant personal vehicle will generate one trip in at the start of their shift and one trip out at the end of their shift, resulting in two trips per day per employee single occupant vehicle.

December-Early January Peak Season

- Daily employee trips = (1 trip out + 1 trip in) × 349 employees = 698 trips
 - 9:15 AM-1:00 PM trips = 1 trip in × 349 employees = 349 trips in
- Assume up to 10% of 349 trips occur between 8:00 and 9:00 AM associated with employees who arrive early = 35 trips in

- Therefore AM commuter peak hour trips = 35 in
- 7:10-10:30 PM trips = 1 trip in × 349 employees = 349 trips out
 - As noted above, no trips occur between 4:00 and 6:00 PM

Late January-October Season

- Daily employee trips = (1 trip out + 1 trip in) × 175 employees = 350 trips
 - 9:15 AM -1:00 PM trips = 1 trip in × 175 employees = 175 trips in
- Assume 10% of 175 trips occur between 8:00 and 9:00 AM = 18 trips in
 - Therefore AM commuter peak hour trips = 18 in
- 7:10-10:30 PM trips = 1 trip in × 175 employees = 175 trips out
 - As noted above, no trips occur between 4:00 and 6:00 PM
- Each employee commuting by bicycle to and from the site will result in one fewer entry and one fewer exit trip per day compared to commuting along in a private vehicle. For the purposes of the trip generation estimate, no reductions in vehicular trips were applied associated with employees arriving by bicycle.
- Each employee commuting by shuttle van has the potential to result in one fewer entry and one fewer exit trip per day compared to commuting along in a private vehicle, though any shuttle trips made for the exclusive transport of one employee will result in no net change to vehicle trips to and from the site. For the purposes of the trip generation estimate, no reductions in vehicular trips were applied associated with employees arriving via shuttle van.

Tables 1 and 2 summarize seasonal trip estimates for the site based on the assumptions above and conservatively assuming all employees commute by themselves in private vehicles.

Table 1. November-Early January Fleet Parking Site Trip Generation Estimate (349 delivery vehicles)

Trip Source	Daily Trips	7-9 AM Commuter Peak Hour			4-6 PM Commuter Peak Hour		
		Total	In	Out	Total	In	Out
Sprinter Vehicle	698	0	0	0	0	0	0
Employee Vehicle	698	35	35	0	0	0	0
Total	1,396	35	35	0	0	0	0

Table 2. Late January-October Fleet Parking Site Trip Generation Estimate (175 delivery vehicles)

Trip Source	Daily Trips	AM Commuter Peak Hour			PM Commuter Peak Hour		
		Total	In	Out	Total	In	Out
Sprinter Vehicle	350	0	0	0	0	0	0
Employee Vehicle	350	18	18	0	0	0	0
Total	700	18	18	0	0	0	0

The trip estimates shown in Tables 1 and 2 are considered conservatively high (over-estimating) because:

- The estimates assume 10% of site trips occur during the 7:00-9:00 AM commuter peak period even though the first group of the Sprinter van drivers are expected to arrive on site for a 9:15 AM delivery shift start.
- The trip estimates assume every employee commutes to and from the fleet parking site in their own personal vehicle.
 - No reduction was made for employee trips made by bicycle.
 - No reduction was made for employee trips made by carpool.
 - No reduction was made for employee trips made via the employer shuttle.

OVERALL SITE TRIP DEBITING SUMMARY

Incorporating the trip data in Table 1 (peak season), trip generation estimates for the existing and proposed uses are summarized in Table 2.

Table 2 Trip Generation Estimates

Land Use	ITE Code	Size (square feet)	Daily Trips	AM Peak Hour Trips			PM Peak Hour Trips		
				Total	In	Out	Total	In	Out
Existing (Constructed) Uses									
Light Industrial	110	101,300	710	93	82	11	98	12	86
Warehousing	150	136,208	485	41	32	9	44	11	33
Office	710	30,000	331	47	41	6	45	8	37
Manufacturing (Hedges C) ¹	140	72,255	276	53	41	12	53	19	34
Subtotal Trips			1,802	234	196	38	240	50	190
Proposed Use									
Fleet Parking (Peak Season)		-	1,396	35	35	0	0	0	0
Existing + Proposed Uses									
Total Trips			3,198	269	231	38	240	50	190

¹ The December 6, 2019 Hedges C Trip Debiting Letter assumed a 72,970 square foot building whereas the actual constructed is slightly smaller.

Trip Accounting

Table 3 provides a trip summary of the existing and proposed uses at Franklin Business Park along with the corresponding trip debiting.

Table 3 Trip Debiting Summary

Use	Number of PM Peak Hour Trips	PM Peak Hour Vested Trips Remaining
1999 Traffic Study Vesting	1,328	1,328
Uses constructed to date	(240)	1,088
Proposed Hedges D	(0)	1,088

After accounting for the existing uses and the proposed Hedges D development, 1,088 weekday PM peak hour trips remain vested for future development of the site.

Please call us at (503) 535-7433 if additional information is needed regarding this evaluation or if you have questions.

Sincerely,
KITTELSON & ASSOCIATES, INC.

Chris Brehmer, PE
Senior Principal Engineer



MACKENZIE.

DESIGN DRIVEN | CLIENT FOCUSED

DRAINAGE REPORT

To
City of Tualatin

For
Hedges D Parking Lot

Submitted
September 1, 2020

Project Number
2200339.00



MACKENZIE
Since 1960

RiverEast Center | 1515 SE Water Avenue, Suite 100, Portland, OR 97214
T 503.224.9560 | F 503.228.1285 | www.mcknze.com

TABLE OF CONTENTS

1. INTRODUCTION..... 1

2. BASIS OF DESIGN AND ASSUMPTIONS..... 2

 BASIS OF DESIGN 2

 ASSUMPTIONS 2

3. WATER QUALITY 3

4. HYDROMODIFICATION 4

5. CONVEYANCE DESIGN 6

6. CONCLUSION 7

FIGURES

Figure 1: Vicinity Map 1

TABLES

Table 1: Storm Events to be Used in CWS Design (CWS Table 4-4) 2

Table 2: Water Quality Summary..... 3

Table 3: Hydromodification Approach Project Category Table (CWS Table 4-2) 4

Table 4: Pre-Development Peak Runoff Rate Targets (CWS Table 4-7)..... 4

Table 5: Hydromodification Summary 5

Table 6: General Pipe Sizing for Conveyance..... 6

APPENDICES

- Appendix A: NRCS Web Soil Survey Summary
- Appendix B: Water Quantity Sizing Calculations
- Appendix C: O&M Manual
- Appendix D: Geotechnical Report
- Appendix E: Basin Map

1. INTRODUCTION

The following storm drainage calculations are intended to support the water quality and hydromodification systems for the Hedges D Parking Lot Development. This report demonstrates the proposed stormwater system’s compliance with Clean Water Services Design and Construction Standards (April 2019).

The 5-acre development includes surface parking for delivery vans and van driver personal vehicles, a concrete paved gathering area with a tent and portable restrooms, at-grade walking paths, proprietary treatment devices, and underground storage on currently undeveloped fallow land in the City of Tualatin. The project is tributary to Hedges Creek of the Tualatin River Watershed. The property is surrounded by a vegetated corridor and storm surface drainage easements. The project is subject to the 2019 Clean Water Services Design and Construction Standards, including water quality and hydromodification requirements.




Figure 1: Vicinity Map

2. BASIS OF DESIGN AND ASSUMPTIONS

BASIS OF DESIGN

This project is subject to the design requirements of the 2019 Clean Water Services Design and Construction Standards.

- Hydrologic calculations are computed using TR-55, the Santa Barbara Urban Hydrograph (SBUH), and Autodesk Hydraflow Hydrographs Extension, Version 2020.
- Impervious area used in design of water quality, conveyance capacity, and hydromodification
 - Quality: Area = New Impervious + 3(Modified Impervious)
 - Quantity: All new and modified impervious area created by the development
- The project creates more than 1,000 square feet of impervious surfaces and so is subject to implement water quality components mitigate impacts of hydromodification
 - Conveyance facilities will be sized from the 25-year storm
 - Water Quality: A dry weather storm event totaling 0.36 inches of precipitation falling in 4 hours with an average storm return period of 96 hours.
 - To address Hydromodification requirements, the project follows Category 2, option 2 Peak-Flow Matching design to address Hydromodification requirements: attenuate the 2-year post-development peak flow to ½ the 2-year pre-developed peak flow, the 5-year-post-developed peak to the 5-year pre-developed peak, and the 10-year post-developed peak to the 10-year pre-developed peak.

Table 1: Storm Events to be Used in CWS Design (CWS Table 4-4)

Recurrence Interval	Total 24-Hour Precipitation Depth (water equivalent inches)
2-year	2.5
5-year	3.10
10-year	3.45
25-year	3.90

ASSUMPTIONS

- Groundwater does not interact with the system for the scope of this analysis
- Infiltration rates are negligible
- Hedges Creek has sufficient capacity for project flows and downstream analysis is not required
- Backwater from Hedges creek will be negligible at worst within the scope of this analysis

3. WATER QUALITY

This project creates more than 1,000 square feet of impervious surface and is thus required to implement techniques to reduce impacts to the downstream receiving water body. Water quality will be provided using Contech StormFilter Catch Basins. Per section 4.07.8 of the CWS manual, proprietary devices meeting the removal efficiency requirements (designed to remove 65 percent of the total phosphorus from the runoff from the impervious area that is tributary to the facility) in section 4.04.3(a) are allowed for single commercial, industrial, multi-family, or condominium parcels. Per Contech’s Phosphorb Media Brochure, the Stormfilter Cartridges containing Phosphorb Media have a TSS removal efficiency of 89% and phosphorous removal efficiency of 82%, and thus meet the requirements of CWS. Each filter is capable of providing this level of treatment for up to 15 gpm (18” tall cartridge) to 22 gpm (27” tall).

The impervious area and resultant number of required filters for each of the four drainage basins (shown in the Basin Map in Appendix E) are summarized in Table 2. See Appendix D for operations and maintenance procedures for the Contech StormFilters.

Table 2: Water Quality Summary			
Drainage Basin	Impervious Area (ft ²)	Water Quality Flow (gpm)	Required # of Filters
NW	20,000	18.85	2 (27” Tall)
NE	63,800	59.70	4 (18” Tall)
SW	39,500	36.80	2 (27” Tall)
SE	80,900	75.85	4 (27” Tall)

CWS standards for water quality is to design for a storm event totaling 0.36 inches or precipitation over 4 hours, and is calculated as follows:

$$\text{Water Quality Volume (ft}^3\text{)} = \frac{0.36 \text{ (in.)} \times \text{Area (sq. ft.)}}{12 \text{ (in/ft)}}$$

$$\text{Water Quality Flow (ft}^3\text{/s)} = \frac{\text{Water Quality Volume (ft}^3\text{)}}{14,400 \text{ seconds}}$$

Pollutants of concern in parking lot include zinc from brake pads and copper from wheels, which are addressed with the proprietary media.

4. HYDROMODIFICATION

This project creates more than 1,000 square feet of impervious surface and is thus required to implement techniques to reduce impacts to the downstream receiving water body. Impacts for this project will be mitigated by implementing an ADS StormTech underground detention system with a flow control manhole. The facility will outfall directly to Hedges Creek with a rip rap pad for energy dissipation.

CWS requires a Hydromodification Assessment (per section 4.03.3 of the CWS Design and Construction Standards) to determine the method that must be used to meet flow control standards. Using the CWS Hydromodification Map Web Tool, the project is determined to be low risk and exists in a developed area. Because the project is over 80,000 ft², the project falls under Approach Category 2 per Table 3.

Table 3: Hydromodification Approach Project Category Table (CWS Table 4-2)

Development Class/ Risk Level	Small Project 1,000 – 12,000 SF	Medium Project >12,000 – 80,000 SF	Large Project > 80,000 SF
Expansion/ High	Category 1	Category 3	Category 3
Expansion/ Moderate		Category 2	
Expansion/ Low		Category 3	
Developed/ High		Category 2	Category 2
Developed/ Moderate			
Developed/ Low			

Under Category 2, the following options may be used to address hydromodification:

1. Infiltration Low Impact Development Approach (LIDA), using the Standard LIDA Sizing, described in Section 4.08.5; or
2. Peak-Flow Matching Detention, using design criteria described in Section 4.08.6; or
3. Combination of Infiltration LIDA and Peak-Flow Matching Detention, using criteria described in Section 4.08.5 and 4.08.6; or
4. Any option listed in Category 3

The Peak-Flow Matching Detention design criteria was chosen to be pursued for this project. Per section 4.08.6 of the 2019 CWS Design and Construction Standards, approaches shall be designed such that the post-development runoff rates from the site do not exceed the pre-development runoff rates shown in Table 4.

Table 4: Pre-Development Peak Runoff Rate Targets (CWS Table 4-7)

Post-Development Peak Runoff Rate	Pre-Development Peak Runoff Rate Target
2-year, 24-hour	50% of 2-year, 24-hour
5-year, 24-hour	5-year, 24 hour
10-year, 24-hour	10-year, 24-hour

Peak flow matching flows for each of the detention systems are summarized in Table 5. See Appendix B for supporting calculations and Appendix D for operations and maintenance procedures for the underground detention system.

Table 5: Hydromodification Summary			
Storm Event	Pre-Development Flow (ft³/s)	Post-Development Flow (ft³/s)	Required Storage Volume (ft³)
(½) 2-year	0.133	0.132	43,550
5-year	0.562	0.184	
10-year	0.766	0.211	

5. CONVEYANCE DESIGN

The conveyance design was determined using TR-55 and the Santa Barbara Urban Hydrograph. The 25-year design storm was applied over the entire site to determine a peak flow value. This peak flow value was prorated over each area tributary to catch basins, area drains, and roof drains (see attached Basin Map). Critical points along the system were identified and these prorated flow values were balanced against the capacity at each critical point. The Table 6 was used for design of the conveyance system.

The peak 25-yr developed flow was prorated into each of the 4 major subareas to determine the design flow for conveyance. Per Hydraflow calculations in Appendix B, the peak 25-yr developed flow across the site is 4.31 cfs over 4.73 acres, thus the ratio is 0.91 cfs/ac. Prorations into each of the major subareas is shown in Table 7. Comparing the maximum capacities outlined in Table 6 with the sizes indicated on the project plans, it can be seen that the pipe sizes selected for the conveyance system will be adequate.

Table 6: General Pipe Sizing for Conveyance	
Pipe Size/Slope	Capacity (ft ³ /s)
8" @ 0.50%	0.85
12" @ 0.30%	1.94
12" @ 0.50%	2.50


Table 7: Subarea Peak Flows for Conveyance	
Subarea	Peak Flow
NW	0.42
NE	1.33
SW	0.83
SE	1.69

6. CONCLUSION


The on-site private stormwater management approach for the Hedges D project includes the implementation of an underground detention system and proprietary treatment devices, which meets the water quality and hydromodification criteria of the 2019 CWS Design and Construction Standards.

APPENDIX A
**NRCS WEB SOIL
SURVEY SUMMARY**
































Hydrologic Soil Group—Washington County, Oregon



Map Scale: 1:2,050 if printed on A landscape (11" x 8.5") sheet.



MAP LEGEND

Area of Interest (AOI)		 C
Area of Interest (AOI)		 C/D
		 D
		 Not rated or not available
Soils		
Soil Rating Polygons		
 A		
 A/D		
 B		
 B/D		
 C		
 C/D		
 D		
 Not rated or not available		
Soil Rating Lines		
 A		
 A/D		
 B		
 B/D		
 C		
 C/D		
 D		
 Not rated or not available		
Soil Rating Points		
 A		
 A/D		
 B		
 B/D		
Water Features		
 Streams and Canals		
Transportation		
 Rails		
 Interstate Highways		
 US Routes		
 Major Roads		
 Local Roads		
Background		
 Aerial Photography		

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:20,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
 Web Soil Survey URL:
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Washington County, Oregon
 Survey Area Data: Version 17, Sep 10, 2019

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Aug 3, 2014—Aug 23, 2014

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
21B	Hillsboro loam, 3 to 7 percent slopes	B	0.0	0.2%
27	Labish mucky clay	C/D	7.9	44.5%
43	Wapato silty clay loam	C/D	4.7	26.3%
2027A	Verboort silty clay loam, 0 to 3 percent slopes	D	5.1	29.1%
Totals for Area of Interest			17.7	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher

APPENDIX B
**WATER QUANTITY
SIZING
CALCULATIONS**

Hydrograph Return Period Recap.....	1
2 - Year	
Summary Report.....	2
Hydrograph Reports.....	3
Hydrograph No. 1, SBUH Runoff, Pre-Developed.....	3
TR-55 Tc Worksheet.....	4
Hydrograph No. 2, SBUH Runoff, Developed.....	5
Hydrograph No. 3, Reservoir, Route Through Pond.....	6
Pond Report - Pond.....	7
5 - Year	
Summary Report.....	8
Hydrograph Reports.....	9
Hydrograph No. 1, SBUH Runoff, Pre-Developed.....	9
Hydrograph No. 2, SBUH Runoff, Developed.....	10
Hydrograph No. 3, Reservoir, Route Through Pond.....	11
10 - Year	
Summary Report.....	12
Hydrograph Reports.....	13
Hydrograph No. 1, SBUH Runoff, Pre-Developed.....	13
Hydrograph No. 2, SBUH Runoff, Developed.....	14
Hydrograph No. 3, Reservoir, Route Through Pond.....	15
25 - Year	
Summary Report.....	16
Hydrograph Reports.....	17
Hydrograph No. 1, SBUH Runoff, Pre-Developed.....	17
Hydrograph No. 2, SBUH Runoff, Developed.....	18
Hydrograph No. 3, Reservoir, Route Through Pond.....	19
IDF Report.....	20

Hydrograph Return Period Recap

Hydroflow Hydrographs Extension for Autodesk® Civil 3D® 2019 by Autodesk, Inc. v2020

Hyd. No.	Hydrograph type (origin)	Inflow hyd(s)	Peak Outflow (cfs)								Hydrograph Description
			1-yr	2-yr	3-yr	5-yr	10-yr	25-yr	50-yr	100-yr	
1	SBUH Runoff	-----	-----	0.265	-----	0.562	0.766	1.054	-----	-----	Pre-Developed
2	SBUH Runoff	-----	-----	2.607	-----	3.340	3.764	4.308	-----	-----	Developed
3	Reservoir	2	-----	0.104	-----	0.243	0.390	0.541	-----	-----	Route Through Pond

Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® 2019 by Autodesk, Inc. v2020


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description	
1	SBUH Runoff	0.265	2	498	10,797	-----	-----	-----	Pre-Developed	
2	SBUH Runoff	2.607	2	474	36,589	-----	-----	-----	Developed	
3	Reservoir	0.104	2	1444	12,395	2	138.71	33,401	Route Through Pond	
339-Pond.gpw					Return Period: 2 Year			Thursday, 08 / 27 / 2020		

Hydrograph Report

Hyd. No. 1

Pre-Developed

Hydrograph type	= SBUH Runoff	Peak discharge	= 0.265 cfs
Storm frequency	= 2 yrs	Time to peak	= 8.30 hrs
Time interval	= 2 min	Hyd. volume	= 10,797 cuft
Drainage area	= 4.890 ac	Curve number	= 74
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 27.80 min
Total precip.	= 2.50 in	Distribution	= Type IA
Storm duration	= 24 hrs	Shape factor	= n/a



TR55 Tc Worksheet

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® 2019 by Autodesk, Inc. v2020

Hyd. No. 1

Pre-Developed

<u>Description</u>	<u>A</u>	<u>B</u>	<u>C</u>	<u>Totals</u>
Sheet Flow				
Manning's n-value	= 0.150	0.011	0.011	
Flow length (ft)	= 300.0	0.0	0.0	
Two-year 24-hr precip. (in)	= 2.50	0.00	0.00	
Land slope (%)	= 2.00	0.00	0.00	
Travel Time (min)	= 26.70	+ 0.00	+ 0.00	= 26.70
Shallow Concentrated Flow				
Flow length (ft)	= 150.00	0.00	0.00	
Watercourse slope (%)	= 2.00	0.00	0.00	
Surface description	= Unpaved	Paved	Paved	
Average velocity (ft/s)	=2.28	0.00	0.00	
Travel Time (min)	= 1.10	+ 0.00	+ 0.00	= 1.10
Channel Flow				
X sectional flow area (sqft)	= 0.00	0.00	0.00	
Wetted perimeter (ft)	= 0.00	0.00	0.00	
Channel slope (%)	= 0.00	0.00	0.00	
Manning's n-value	= 0.015	0.015	0.015	
Velocity (ft/s)	=0.00	0.00	0.00	
Flow length (ft)	{{0}}0.0	0.0	0.0	
Travel Time (min)	= 0.00	+ 0.00	+ 0.00	= 0.00
Total Travel Time, Tc				27.80 min

Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® 2019 by Autodesk, Inc. v2020


Thursday, 08 / 27 / 2020

Hyd. No. 2

Developed

Hydrograph type	= SBUH Runoff	Peak discharge	= 2.607 cfs
Storm frequency	= 2 yrs	Time to peak	= 7.90 hrs
Time interval	= 2 min	Hyd. volume	= 36,589 cuft
Drainage area	= 4.890 ac	Curve number	= 96*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 5.00 min
Total precip.	= 2.50 in	Distribution	= Type IA
Storm duration	= 24 hrs	Shape factor	= n/a

* Composite (Area/CN) = $[(0.440 \times 74) + (4.450 \times 98)] / 4.890$



Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® 2019 by Autodesk, Inc. v2020


Thursday, 08 / 27 / 2020

Hyd. No. 3

Route Through Pond

Hydrograph type	= Reservoir	Peak discharge	= 0.104 cfs
Storm frequency	= 2 yrs	Time to peak	= 24.07 hrs
Time interval	= 2 min	Hyd. volume	= 12,395 cuft
Inflow hyd. No.	= 2 - Developed	Max. Elevation	= 138.71 ft
Reservoir name	= Pond	Max. Storage	= 33,401 cuft

Storage Indication method used. Exfiltration extracted from Outflow.



Pond No. 1 - Pond

Pond Data

UG Chambers -Invert elev. = 137.92 ft, Rise x Span = 2.50 x 4.25 ft, Barrel Len = 7.12 ft, No. Barrels = 370, Slope = 0.00%, Headers = Yes
Encasement -Invert elev. = 137.42 ft, Width = 4.75 ft, Height = 3.50 ft, Voids = 40.00%

Stage / Storage Table

Stage (ft)	Elevation (ft)	Contour area (sqft)	Incr. Storage (cuft)	Total storage (cuft)
0.00	137.42	n/a	0	0
0.35	137.77	n/a	4,090	4,090
0.70	138.12	n/a	7,223	11,312
1.05	138.47	n/a	9,512	20,824
1.40	138.82	n/a	9,337	30,162
1.75	139.17	n/a	9,039	39,201
2.10	139.52	n/a	8,592	47,792
2.45	139.87	n/a	7,942	55,734
2.80	140.22	n/a	6,949	62,683
3.15	140.57	n/a	4,916	67,599
3.50	140.92	n/a	4,090	71,689


Culvert / Orifice Structures

	[A]	[B]	[C]	[PrfRsr]
Rise (in)	= 0.50	3.00	Inactive	Inactive
Span (in)	= 0.50	3.00	8.00	0.00
No. Barrels	= 1	1	1	0
Invert El. (ft)	= 136.80	138.50	139.70	0.00
Length (ft)	= 0.00	0.00	0.00	0.00
Slope (%)	= 0.00	0.00	0.00	n/a
N-Value	= .013	.013	.013	n/a
Orifice Coeff.	= 0.60	0.60	0.60	0.60
Multi-Stage	= n/a	No	No	No

Weir Structures

	[A]	[B]	[C]	[D]
Crest Len (ft)	= 2.09	0.00	0.00	0.00
Crest El. (ft)	= 139.50	0.00	0.00	0.00
Weir Coeff.	= 3.33	3.33	3.33	3.33
Weir Type	= 1	---	---	---
Multi-Stage	= No	No	No	No
Exfil.(in/hr)	= 0.010 (by Wet area)			
TW Elev. (ft)	= 0.00			

Note: Culvert/Orifice outflows are analyzed under inlet (ic) and outlet (oc) control. Weir risers checked for orifice conditions (ic) and submergence (s).



Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® 2019 by Autodesk, Inc. v2020


Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description	
1	SBUH Runoff	0.562	2	490	17,259	-----	-----	-----	Pre-Developed	
2	SBUH Runoff	3.340	2	474	47,049	-----	-----	-----	Developed	
3	Reservoir	0.243	2	1442	21,316	2	139.04	39,796	Route Through Pond	
339-Pond.gpw					Return Period: 5 Year			Thursday, 08 / 27 / 2020		

Hydrograph Report

Hyd. No. 1

Pre-Developed

Hydrograph type	= SBUH Runoff	Peak discharge	= 0.562 cfs
Storm frequency	= 5 yrs	Time to peak	= 8.17 hrs
Time interval	= 2 min	Hyd. volume	= 17,259 cuft
Drainage area	= 4.890 ac	Curve number	= 74
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 27.80 min
Total precip.	= 3.10 in	Distribution	= Type IA
Storm duration	= 24 hrs	Shape factor	= n/a



Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® 2019 by Autodesk, Inc. v2020


Thursday, 08 / 27 / 2020

Hyd. No. 2

Developed

Hydrograph type	= SBUH Runoff	Peak discharge	= 3.340 cfs
Storm frequency	= 5 yrs	Time to peak	= 7.90 hrs
Time interval	= 2 min	Hyd. volume	= 47,049 cuft
Drainage area	= 4.890 ac	Curve number	= 96*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 5.00 min
Total precip.	= 3.10 in	Distribution	= Type IA
Storm duration	= 24 hrs	Shape factor	= n/a

* Composite (Area/CN) = [(0.440 x 74) + (4.450 x 98)] / 4.890



Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® 2019 by Autodesk, Inc. v2020


Thursday, 08 / 27 / 2020

Hyd. No. 3

Route Through Pond

Hydrograph type	= Reservoir	Peak discharge	= 0.243 cfs
Storm frequency	= 5 yrs	Time to peak	= 24.03 hrs
Time interval	= 2 min	Hyd. volume	= 21,316 cuft
Inflow hyd. No.	= 2 - Developed	Max. Elevation	= 139.04 ft
Reservoir name	= Pond	Max. Storage	= 39,796 cuft

Storage Indication method used. Exfiltration extracted from Outflow.



Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® 2019 by Autodesk, Inc. v2020

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description	
1	SBUH Runoff	0.766	2	488	21,399	-----	-----	-----	Pre-Developed	
2	SBUH Runoff	3.764	2	474	53,179	-----	-----	-----	Developed	
3	Reservoir	0.390	2	1252	27,337	2	139.09	40,782	Route Through Pond	
339-Pond.gpw					Return Period: 10 Year			Thursday, 08 / 27 / 2020		

Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® 2019 by Autodesk, Inc. v2020

Thursday, 08 / 27 / 2020

Hyd. No. 1

Pre-Developed

Hydrograph type	= SBUH Runoff	Peak discharge	= 0.766 cfs
Storm frequency	= 10 yrs	Time to peak	= 8.13 hrs
Time interval	= 2 min	Hyd. volume	= 21,399 cuft
Drainage area	= 4.890 ac	Curve number	= 74
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 27.80 min
Total precip.	= 3.45 in	Distribution	= Type IA
Storm duration	= 24 hrs	Shape factor	= n/a



Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® 2019 by Autodesk, Inc. v2020


Thursday, 08 / 27 / 2020

Hyd. No. 2

Developed

Hydrograph type	= SBUH Runoff	Peak discharge	= 3.764 cfs
Storm frequency	= 10 yrs	Time to peak	= 7.90 hrs
Time interval	= 2 min	Hyd. volume	= 53,179 cuft
Drainage area	= 4.890 ac	Curve number	= 96*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 5.00 min
Total precip.	= 3.45 in	Distribution	= Type IA
Storm duration	= 24 hrs	Shape factor	= n/a

* Composite (Area/CN) = [(0.440 x 74) + (4.450 x 98)] / 4.890



Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® 2019 by Autodesk, Inc. v2020


Thursday, 08 / 27 / 2020

Hyd. No. 3

Route Through Pond

Hydrograph type	= Reservoir	Peak discharge	= 0.390 cfs
Storm frequency	= 10 yrs	Time to peak	= 20.87 hrs
Time interval	= 2 min	Hyd. volume	= 27,337 cuft
Inflow hyd. No.	= 2 - Developed	Max. Elevation	= 139.09 ft
Reservoir name	= Pond	Max. Storage	= 40,782 cuft

Storage Indication method used. Exfiltration extracted from Outflow.



Hydrograph Summary Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® 2019 by Autodesk, Inc. v2020

Hyd. No.	Hydrograph type (origin)	Peak flow (cfs)	Time interval (min)	Time to Peak (min)	Hyd. volume (cuft)	Inflow hyd(s)	Maximum elevation (ft)	Total strge used (cuft)	Hydrograph Description	
1	SBUH Runoff	1.054	2	486	27,040	-----	-----	-----	Pre-Developed	
2	SBUH Runoff	4.308	2	474	61,080	-----	-----	-----	Developed	
3	Reservoir	0.541	2	1046	35,193	2	139.13	41,537	Route Through Pond	
339-Pond.gpw					Return Period: 25 Year			Thursday, 08 / 27 / 2020		

Hydrograph Report


Hydraflow Hydrographs Extension for Autodesk® Civil 3D® 2019 by Autodesk, Inc. v2020

Thursday, 08 / 27 / 2020

Hyd. No. 1

Pre-Developed

Hydrograph type	= SBUH Runoff	Peak discharge	= 1.054 cfs
Storm frequency	= 25 yrs	Time to peak	= 8.10 hrs
Time interval	= 2 min	Hyd. volume	= 27,040 cuft
Drainage area	= 4.890 ac	Curve number	= 74
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= TR55	Time of conc. (Tc)	= 27.80 min
Total precip.	= 3.90 in	Distribution	= Type IA
Storm duration	= 24 hrs	Shape factor	= n/a



Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® 2019 by Autodesk, Inc. v2020


Thursday, 08 / 27 / 2020

Hyd. No. 2

Developed

Hydrograph type	= SBUH Runoff	Peak discharge	= 4.308 cfs
Storm frequency	= 25 yrs	Time to peak	= 7.90 hrs
Time interval	= 2 min	Hyd. volume	= 61,080 cuft
Drainage area	= 4.890 ac	Curve number	= 96*
Basin Slope	= 0.0 %	Hydraulic length	= 0 ft
Tc method	= User	Time of conc. (Tc)	= 5.00 min
Total precip.	= 3.90 in	Distribution	= Type IA
Storm duration	= 24 hrs	Shape factor	= n/a

* Composite (Area/CN) = [(0.440 x 74) + (4.450 x 98)] / 4.890



Hydrograph Report

Hydraflow Hydrographs Extension for Autodesk® Civil 3D® 2019 by Autodesk, Inc. v2020


Thursday, 08 / 27 / 2020

Hyd. No. 3

Route Through Pond

Hydrograph type	= Reservoir	Peak discharge	= 0.541 cfs
Storm frequency	= 25 yrs	Time to peak	= 17.43 hrs
Time interval	= 2 min	Hyd. volume	= 35,193 cuft
Inflow hyd. No.	= 2 - Developed	Max. Elevation	= 139.13 ft
Reservoir name	= Pond	Max. Storage	= 41,537 cuft

Storage Indication method used. Exfiltration extracted from Outflow.



Stormwater Operations & Maintenance Manual

For:

Hedges D Parking Lot
Tualatin, Oregon

September 2020

Prepared by:

Mackenzie
1515 SE Water Avenue
Suite 100
Portland, OR 97214
2200339.00



TABLE OF CONTENTS

I.	GENERAL- SITE DESCRIPTION, ASSUMPTIONS AND GENEREAL SYSTEM DESCRIPTION	1
II.	GENERAL MAINTENANCE AND FACILITY-SPECIFIC MAINTENANCE REQUIREMENTS	1
	Operations and Maintenance Contact	2
III.	GENERAL MAINTENANCE ACTIVITIES.....	2
IV.	SITE PLAN SHOWING LOCATION OF FACILITY COMPONENTS.....	2
V.	INSPECTION PROGRAM – PERFORMANCE MEASURES FOR MAINTENANCE ACTIVITIES.....	3
	Objective	3
	Requirements	3
	Collection System	4
	<i>Filter System</i>	4
	<i>Detention System</i>	4
VI.	O&M INSPECTION SCHEDULE	6
	Employee and Public Education	6
VII.	MAINTENANCE EQUIPMENT	6
	Suggested Maintenance Equipment and Materials	6
VIII.	SEDIMENT STORAGE, TESTING, AND DISPOSAL.....	7
IX.	EMERGENCY CONTACTS	7
	Emergency Contacts	7
	Maintenance Responsibilities	7
X.	SPILL PREVENTION AND CONTROL PLAN.....	7
XI.	ADDITIONAL MAINTENANCE REQUIREMENTS FOR INITIAL ESTABLISHMENT PERIOD	9

ATTACHMENTS

1. O&M Facility Map
2. Sample Maintenance Log
3. Contech StormFilter Inspection and Maintenance Guide
4. ADS StormTech Inspection and Maintenance Guide

I. GENERAL- SITE DESCRIPTION, ASSUMPTIONS AND GENERAL SYSTEM DESCRIPTION

This plan was developed to provide a basis for maintenance of stormwater facilities for the Hedges D parking lot project located in Tualatin, Oregon. Construction of the Hedges D project includes a delivery van parking lot, landscape, supporting utilities, water quality filter catch basins, and underground detention chambers.

Runoff from the site sheets flows to various filter or standard catch basins and is detained in underground chamber systems prior to outfall to the creek.

This Operations and Maintenance Plan generally provides maintenance requirements of the stormwater collection and treatment system. Best Management Practices (BMPs) related to maintenance of the facilities shall include regular maintenance and upkeep of the parking and landscape areas.

II. GENERAL MAINTENANCE AND FACILITY-SPECIFIC MAINTENANCE REQUIREMENTS

The Hedges D Facilities Manager shall be responsible for regular inspections and maintenance of the storm drainage system and related facilities. Inspections shall include observations of the landscaping, parking areas, catch basin grates and basins for debris, loose soil or sediment that may enter the system. Inspection of the collection system includes observation of the catch basins, and conveyance lines. General maintenance requirements of those facilities include removal of sediment and debris, repair of damaged components and general maintenance of mechanical systems.

Facility-specific maintenance requirements shall also be the responsibility of the Hedges D Facilities Manager. Inspections shall include documentation of observations and maintenance or repairs of each of the drainage system facilities. This would include:

- Landscape areas
- Parking areas
- Catch basins
- Cleanouts
- Conveyance pipes
- Treatment devices
- Detention elements



Operations and Maintenance Contact

Hedges D – Facilities Manager

#####

III. GENERAL MAINTENANCE ACTIVITIES

Maintenance of stormwater system components is the key to a successful stormwater plan. Most stormwater systems can fail in the first few years due to lack of adequate maintenance. The following guidelines will be used for general maintenance of the stormwater system.

1. Dry sweeping of the parking area to reduce accumulation of sediments and debris in the catch basins will be conducted regularly. Clogging the catch basin with sediments will result in its failure.
2. Quarterly visual inspection of the catch basins for debris and obstructions. All catch basins or other structures shall be kept clear of sediment, debris or other obstructions that may affect the flow or treatment of stormwater.
3. Visually inspect the stormwater system after all major storm events for evidence of system problems. Look for ponded water, debris, erosion, or any other signs of system problems.
4. Annually inspect the spill kit to ensure all supplies are available and have not deteriorated or expired (Note: each tenant shall have a separate spill kit or access to a shared spill kit). Check with city staff to stay aware of newly available products or spill containment procedures. Become familiar with the spill control plan (included with this O&M Plan) and ensure that at least one employee during each work shift is familiar with the plan (always have someone on-site who is aware of the spill containment kit and procedures).
5. Biannually or quarterly inspect the catch basin sumps. Sediments need to be removed along with any oils before the deposits reach one foot in depth and before the outlet is obstructed. Materials removed from the catch basin inlet shall be disposed of in accordance with applicable state law. Records of debris disposal shall be kept on file at the main office in accordance with the state law and shall be available for review by regulating agencies.

IV. SITE PLAN SHOWING LOCATION OF FACILITY COMPONENTS

The attached O&M Facility Map shows the general location of the facility components. The site utility “As-built” drawings should be consulted for further information regarding facility locations, sizes or details.

V. INSPECTION PROGRAM – PERFORMANCE MEASURES FOR MAINTENANCE ACTIVITIES

Objective

The objective of this manual is to help the property owner to maintain the storm sewer system for Hedges D so it can continue to operate as designed.

Requirements

Conduct inspections with the as-built plans in hand. Inspect the facility on a quarterly basis for the first 3 years from construction, and a minimum or semi-annually thereafter. Additional inspections will be necessary after long dry periods, large storms or spills. Immediately remove spilled material, taking the appropriate safety and disposal precautions.

Keep inspection records to track the progressive development of the system over time. The inspection records shall include:

1. Sediment condition and depth in sumps
2. Water elevation/observations (sheen, smell, etc.)
3. Conditions of the inlet and outlet pipes, and remaining storage capacity
4. Unscheduled maintenance needs
5. Components that do not meet performance criteria and require immediate maintenance
6. Common problem areas, solutions, and general observations
7. Aesthetic conditions

Collection System

The collection system consists of underground pipes and catch basins.

Catch Basins

The catch basins are metal basins with steel grates. The catch basins have a trapped outlet and sump and need to be inspected and maintained (if necessary) on a quarterly basis and following major storm events. Maintenance includes inspection of the structure itself and removal of any oils, debris or sediment as described in the maintenance table. Check to see if sediment has built up on the bottom of the catch basin by measuring down from the outlet pipe. If it is less than 12-inches then the catch basin needs to be cleaned out.

Storm Sewer Pipes

The storm sewer pipes are plastic with associated fittings. The pipes need to be inspected and cleaned quarterly (in necessary) following major storm events. Cleanouts and manholes are provided for access to the pipe system. The pipes need to be inspected for sediment buildup and cleaned out, if necessary, using a vactor truck so that sediment is removed.

Filter System

Refer to attached manufacturer recommendations.

Detention System

Refer to attached manufacturer recommendations.

Maintenance Schedule

Summer: Make structural repairs; clean gutters and downspouts; remove any build-up of weeds or organic debris.

Fall: Replant exposed soil and replace dead plants. Remove sediment and plant debris.

Winter: Clear gutters and downspouts.

Spring: Remove sediment and plant debris. Replant exposed soil and replace dead plants.

All season: Weed as necessary.

Maintenance Record

All facility operators are required to keep an inspection and maintenance log. Record date, description, and contractor (if applicable) for all repairs, landscape maintenance, and facility cleanout activities. Keep work orders and invoices on file and make available upon request of the City inspector.

Access

Maintain ingress/egress per design standards.

Vector (Mosquitoes and Rats)

Facilities must not harbor mosquito larvae or rodents. Record the time/date, weather, and site conditions when vector activity is observed. Record when vector abatement started and ended.

VI. O&M INSPECTION SCHEDULE

- Quarterly inspection of the catch basins and drainage system for accumulation of sediments or oils
- Annual inspection of the emergency spill kit to ensure that all supplies are available and have not deteriorated or expired
- Quarterly inspection of the swale for proper landscape maintenance, removal of trash or sediment and repair of erosion
- Materials removed from the catch basin or pipes shall be disposed of in accordance with state law

Employee and Public Education

Employees will be trained upon hiring and thereafter annually, when new requirements are published or when there are any changes to the system equipment. Employee training will include:

- Reading this Stormwater Management Plan
- Familiarity of all components and locations for materials indicated in the SWMP
- Spill response and Personal Protective Equipment (PPE)
- Documentation requirements

VII. MAINTENANCE EQUIPMENT

Hand tools or other specialized equipment may be necessary to maintain the facilities. Suggested maintenance equipment is listed in the Inspection Checklist. The Facility Manager shall be responsible to maintain on-site, or be able to make available, all required equipment.

Suggested Maintenance Equipment and Materials

- Push broom
- Rake
- Shovel
- Spill kit
- Manhole lid puller
- General landscape tools (weed cutters, pruning clippers, leaf rake, etc.)
- Vactor Truck

VIII. SEDIMENT STORAGE, TESTING, AND DISPOSAL

Maintenance of the storm drainage facilities (manholes and catch basins) may include removal of oils, sediments or debris that requires specialized testing or disposal. All removed oils, sediments or other debris shall be disposed of in accordance with applicable regulations. The Facility Manager shall be responsible to retain a qualified company to dispose of this material or otherwise comply with the applicable regulations. The Facility Manager should contact the City of Tualatin Public Works to verify current regulations or requirements. Local companies providing testing, storage and disposal services:

Evergreen Pacific: (503) 835-5028

Loy Clark: (503) 849-4560

All Vac: (503) 289-4063

IX. EMERGENCY CONTACTS

Emergency Contacts

#####

Maintenance Responsibilities

The Facility Manager shall be responsible to inspect, maintain or otherwise repair the stormwater facilities. Regular inspections shall occur, and documentation of the inspections, maintenance or repairs kept on-site for a minimum of three years from the date of the activity.

X. SPILL PREVENTION AND CONTROL PLAN

Spill prevention is an important factor in the successful operation of a stormwater management system. All employees will be trained to this plan so that they are certain of the location of materials, who to notify in case of a spill, and how to initially contain the spill of hazardous materials. Employees shall never dump water materials into the stormwater collection/treatment system. Employees shall be observant of other potential contamination occurrences. All employees will review the following page regarding detailed spill response steps.

This data will be posted in an accessible area.

WHAT TO DO IN CASE OF A SPILL

1. The spill kit is located #####
2. Get the spill kit (and spill kit instructions when provided)
 - a. If possible, determine visually what type of fluids have been spilled
 - b. Put on gloves and glasses or any other necessary Personal Protective Equipment (PPE)
 - c. Get the absorbent material provided in the kit and drain block cover (pig)
 - d. Place the absorbent material in the path of the spill
 - e. Remove any debris from the vicinity of the catch basin inlets in the parking lot
 - f. Unroll the drain blocker, and place is snugly over the catch basin inlet
 - g. Verify the cover has full contact with the rim of the catch basin inlet
 - h. Use snakes, pillow or pigs to completely contain the areas
 - i. If the spill cannot be contained locally, shut off the storm drain pumps so any spilled material does not leave the site

3. Notify the following personnel immediately:

City of Tualatin Public Works:	(503) 629-3091
After Hours:	(503) 629-0111



Department of Environmental Quality:	(800) 452-0311
	(800) 452-4011
	(503) 229-5263

Note: Only dry cleanup methods may be employed to clean up spills (i.e. no use of water to wash spilled materials from pavement will be conducted).

XI. ADDITIONAL MAINTENANCE REQUIREMENTS FOR INITIAL ESTABLISHMENT PERIOD

Initial maintenance of landscape vegetation may require additional attention to ensure that landscaping, groundcover and erosion control measures are established or maintained as intended. Proper landscaping and groundcover are an important feature of a successful storm drainage system.

1. During the initial 3-year establishment period, remove undesired vegetation using minimal (or preferably no) use of toxic herbicides and pesticides at least 3 times a year. Replace plants that die during this period.
2. Irrigate as necessary to establish site landscaping
3. Replenish mulch at least annually. Make sure that all exposed soil is covered with mulch or other groundcover
4. Do not use excessive fertilizers, herbicides or pesticides for vegetation maintenance
5. Use replacement plants that conform to the initial planting list



1
-

O&M SITE MAP



(IN FEET)
1 inch = 50 ft.

Date: _____ Initials: _____
Work performed by: _____
Work performed: _____

Work area or specific stormwater facility area: _____
Details: _____

Date: _____ Initials: _____
Work performed by: _____
Work performed: _____

Work area or specific stormwater facility area: _____
Details: _____

Date: _____ Initials: _____
Work performed by: _____
Work performed: _____

Work area or specific stormwater facility area: _____
Details: _____

Date: _____ Initials: _____
Work performed by: _____
Work performed: _____

Work area or specific stormwater facility area: _____
Details: _____

Date: _____ Initials: _____
Work performed by: _____
Work performed: _____

Work area or specific stormwater facility area: _____
Details: _____

Date: _____ Initials: _____
Work performed by: _____
Work performed: _____

Work area or specific stormwater facility area: _____
Details: _____

Maintenance Guidelines

The primary purpose of the Stormwater Management StormFilter® is to filter and prevent pollutants from entering our waterways. Like any effective filtration system, periodically these pollutants must be removed to restore the StormFilter to its full efficiency and effectiveness.

Maintenance requirements and frequency are dependent on the pollutant load characteristics of each site. Maintenance activities may be required in the event of a chemical spill or due to excessive sediment loading from site erosion or extreme storms. It is a good practice to inspect the system after major storm events.

Maintenance Procedures

Although there are many effective maintenance options, we believe the following procedure to be efficient, using common equipment and existing maintenance protocols. The following two-step procedure is recommended::

1. Inspection

- Inspection of the vault interior to determine the need for maintenance.

2. Maintenance

- Cartridge replacement
- Sediment removal

Inspection and Maintenance Timing

At least one scheduled inspection should take place per year with maintenance following as warranted.

First, an inspection should be done before the winter season. During the inspection the need for maintenance should be determined and, if disposal during maintenance will be required, samples of the accumulated sediments and media should be obtained.

Second, if warranted, a maintenance (replacement of the filter cartridges and removal of accumulated sediments) should be performed during periods of dry weather.

In addition to these two activities, it is important to check the condition of the StormFilter unit after major storms for potential damage caused by high flows and for high sediment accumulation that may be caused by localized erosion in the drainage area. It may be necessary to adjust the inspection/maintenance schedule depending on the actual operating conditions encountered by the system. In general, inspection activities can be conducted at any time, and maintenance should occur, if warranted, during dryer months in late summer to early fall.

Maintenance Frequency

The primary factor for determining frequency of maintenance for the StormFilter is sediment loading.

A properly functioning system will remove solids from water by trapping particulates in the porous structure of the filter media inside the cartridges. The flow through the system will naturally decrease as more and more particulates are trapped. Eventually the flow through the cartridges will be low enough to require replacement. It may be possible to extend the usable span of the cartridges by removing sediment from upstream trapping devices on a routine as-needed basis, in order to prevent material from being re-suspended and discharged to the StormFilter treatment system.

The average maintenance lifecycle is approximately 1-5 years. Site conditions greatly influence maintenance requirements. StormFilter units located in areas with erosion or active construction may need to be inspected and maintained more often than those with fully stabilized surface conditions.

Regulatory requirements or a chemical spill can shift maintenance timing as well. The maintenance frequency may be adjusted as additional monitoring information becomes available during the inspection program. Areas that develop known problems should be inspected more frequently than areas that demonstrate no problems, particularly after major storms. Ultimately, inspection and maintenance activities should be scheduled based on the historic records and characteristics of an individual StormFilter system or site. It is recommended that the site owner develop a database to properly manage StormFilter inspection and maintenance programs..





Inspection Procedures

The primary goal of an inspection is to assess the condition of the cartridges relative to the level of visual sediment loading as it relates to decreased treatment capacity. It may be desirable to conduct this inspection during a storm to observe the relative flow through the filter cartridges. If the submerged cartridges are severely plugged, then typically large amounts of sediments will be present and very little flow will be discharged from the drainage pipes. If this is the case, then maintenance is warranted and the cartridges need to be replaced.

Warning: In the case of a spill, the worker should abort inspection activities until the proper guidance is obtained. Notify the local hazard control agency and Contech Engineered Solutions immediately.

To conduct an inspection:

Important: Inspection should be performed by a person who is familiar with the operation and configuration of the StormFilter treatment unit and the unit's role, relative to detention or retention facilities onsite.

1. If applicable, set up safety equipment to protect and notify surrounding vehicle and pedestrian traffic.
2. Visually inspect the external condition of the unit and take notes concerning defects/problems.
3. Open the access portals to the vault and allow the system vent.
4. Without entering the vault, visually inspect the inside of the unit, and note accumulations of liquids and solids.
5. Be sure to record the level of sediment build-up on the floor of the vault, in the forebay, and on top of the cartridges. If flow is occurring, note the flow of water per drainage pipe. Record all observations. Digital pictures are valuable for historical documentation.
6. Close and fasten the access portals.
7. Remove safety equipment.
8. If appropriate, make notes about the local drainage area relative to ongoing construction, erosion problems, or high loading of other materials to the system.
9. Discuss conditions that suggest maintenance and make decision as to whether or not maintenance is needed.

Maintenance Decision Tree

The need for maintenance is typically based on results of the inspection. The following Maintenance Decision Tree should be used as a general guide. (Other factors, such as Regulatory Requirements, may need to be considered).

Please note Stormwater Management StormFilter devices installed downstream of, or integrated within, a stormwater storage facility typically have different operational parameters (i.e. draindown time). In these cases, the inspector must understand the relationship between the retention/detention facility and the treatment system by evaluating site specific civil engineering plans, or contacting the engineer of record, and make adjustments to the below guidance as necessary. Sediment deposition depths and patterns within the StormFilter are likely to be quite different compared to systems without upstream storage and therefore shouldn't be used exclusively to evaluate a need for maintenance.

1. Sediment loading on the vault floor.
 - a. If >4" of accumulated sediment, maintenance is required.
2. Sediment loading on top of the cartridge.
 - a. If >1/4" of accumulation, maintenance is required.
3. Submerged cartridges.
 - a. If >4" of static water above cartridge bottom for more than 24 hours after end of rain event, maintenance is required. (Catch basins have standing water in the cartridge bay.)
4. Plugged media.
 - a. While not required in all cases, inspection of the media within the cartridge may provide valuable additional information.
 - b. If pore space between media granules is absent, maintenance is required.
5. Bypass condition.
 - a. If inspection is conducted during an average rain fall event and StormFilter remains in bypass condition (water over the internal outlet baffle wall or submerged cartridges), maintenance is required.
6. Hazardous material release.
 - a. If hazardous material release (automotive fluids or other) is reported, maintenance is required.
7. Pronounced scum line.
 - a. If pronounced scum line (say $\geq 1/4$ " thick) is present above top cap, maintenance is required.

Maintenance

Depending on the configuration of the particular system, maintenance personnel will be required to enter the vault to perform the maintenance.

Important: If vault entry is required, OSHA rules for confined space entry must be followed.

Filter cartridge replacement should occur during dry weather. It may be necessary to plug the filter inlet pipe if base flows is occurring.

Replacement cartridges can be delivered to the site or customers facility. Information concerning how to obtain the replacement cartridges is available from Contech Engineered Solutions.

Warning: In the case of a spill, the maintenance personnel should abort maintenance activities until the proper guidance is obtained. Notify the local hazard control agency and Contech Engineered Solutions immediately.

To conduct cartridge replacement and sediment removal maintenance:

1. If applicable, set up safety equipment to protect maintenance personnel and pedestrians from site hazards.
2. Visually inspect the external condition of the unit and take notes concerning defects/problems.
3. Open the doors (access portals) to the vault and allow the system to vent.
4. Without entering the vault, give the inside of the unit, including components, a general condition inspection.
5. Make notes about the external and internal condition of the vault. Give particular attention to recording the level of sediment build-up on the floor of the vault, in the forebay, and on top of the internal components.
6. Using appropriate equipment offload the replacement cartridges (up to 150 lbs. each) and set aside.
7. Remove used cartridges from the vault using one of the following methods:

Method 1:

- A. This activity will require that maintenance personnel enter the vault to remove the cartridges from the under drain manifold and place them under the vault opening for lifting (removal). Disconnect each filter cartridge from the underdrain connector by rotating counterclockwise 1/4 of a turn. Roll the loose cartridge, on edge, to a convenient spot beneath the vault access.

Using appropriate hoisting equipment, attach a cable from the boom, crane, or tripod to the loose cartridge. Contact Contech Engineered Solutions for suggested attachment devices.

- B. Remove the used cartridges (up to 250 lbs. each) from the vault.



Important: Care must be used to avoid damaging the cartridges during removal and installation. The cost of repairing components damaged during maintenance will be the responsibility of the owner.

- C. Set the used cartridge aside or load onto the hauling truck.
- D. Continue steps a through c until all cartridges have been removed.

Method 2:

- A. This activity will require that maintenance personnel enter the vault to remove the cartridges from the under drain manifold and place them under the vault opening for lifting (removal). Disconnect each filter cartridge from the underdrain connector by rotating counterclockwise 1/4 of a turn. Roll the loose cartridge, on edge, to a convenient spot beneath the vault access.
- B. Unscrew the cartridge cap.
- C. Remove the cartridge hood and float.
- D. At location under structure access, tip the cartridge on its side.
- E. Empty the cartridge onto the vault floor. Reassemble the empty cartridge.
- F. Set the empty, used cartridge aside or load onto the hauling truck.
- G. Continue steps a through e until all cartridges have been removed.

8. Remove accumulated sediment from the floor of the vault and from the forebay. This can most effectively be accomplished by use of a vacuum truck.
9. Once the sediments are removed, assess the condition of the vault and the condition of the connectors.
10. Using the vacuum truck boom, crane, or tripod, lower and install the new cartridges. Once again, take care not to damage connections.
11. Close and fasten the door.
12. Remove safety equipment.
13. Finally, dispose of the accumulated materials in accordance with applicable regulations. Make arrangements to return the used **empty** cartridges to Contech Engineered Solutions.

Related Maintenance Activities - Performed on an as-needed basis

StormFilter units are often just one of many structures in a more comprehensive stormwater drainage and treatment system.

In order for maintenance of the StormFilter to be successful, it is imperative that all other components be properly maintained. The maintenance/repair of upstream facilities should be carried out prior to StormFilter maintenance activities.

In addition to considering upstream facilities, it is also important to correct any problems identified in the drainage area. Drainage area concerns may include: erosion problems, heavy oil loading, and discharges of inappropriate materials.

Material Disposal

The accumulated sediment found in stormwater treatment and conveyance systems must be handled and disposed of in accordance with regulatory protocols. It is possible for sediments to contain measurable concentrations of heavy metals and organic chemicals (such as pesticides and petroleum products). Areas with the greatest potential for high pollutant loading include industrial areas and heavily traveled roads.

Sediments and water must be disposed of in accordance with all applicable waste disposal regulations. When scheduling maintenance, consideration must be made for the disposal of solid and liquid wastes. This typically requires coordination with a local landfill for solid waste disposal. For liquid waste disposal a number of options are available including a municipal vacuum truck decant facility, local waste water treatment plant or on-site treatment and discharge.



Inspection Report

Date: _____ Personnel: _____

Location: _____ System Size: _____ Months in Service: _____

System Type: Vault Cast-In-Place Linear Catch Basin Manhole Other: _____

Sediment Thickness in Forebay: _____ Date: _____

Sediment Depth on Vault Floor: _____

Sediment Depth on Cartridge Top(s): _____

Structural Damage: _____

Estimated Flow from Drainage Pipes (if available): _____

Cartridges Submerged: Yes No Depth of Standing Water: _____

StormFilter Maintenance Activities (check off if done and give description)

Trash and Debris Removal: _____

Minor Structural Repairs: _____

Drainage Area Report _____

Excessive Oil Loading: Yes No Source: _____

Sediment Accumulation on Pavement: Yes No Source: _____

Erosion of Landscaped Areas: Yes No Source: _____

Items Needing Further Work: _____

Owners should contact the local public works department and inquire about how the department disposes of their street waste residuals.

Other Comments:

Review the condition reports from the previous inspection visits.

StormFilter Maintenance Report

Date: _____ Personnel: _____

Location: _____ System Size: _____

System Type: Vault Cast-In-Place Linear Catch Basin Manhole Other: _____

List Safety Procedures and Equipment Used: _____

System Observations

Months in Service: _____

Oil in Forebay (if present): Yes No

Sediment Depth in Forebay (if present): _____

Sediment Depth on Vault Floor: _____

Sediment Depth on Cartridge Top(s): _____

Structural Damage: _____

Drainage Area Report

Excessive Oil Loading: Yes No Source: _____

Sediment Accumulation on Pavement: Yes No Source: _____

Erosion of Landscaped Areas: Yes No Source: _____

StormFilter Cartridge Replacement Maintenance Activities

Remove Trash and Debris: Yes No Details: _____

Replace Cartridges: Yes No Details: _____

Sediment Removed: Yes No Details: _____

Quantity of Sediment Removed (estimate?): _____

Minor Structural Repairs: Yes No Details: _____

Residuals (debris, sediment) Disposal Methods: _____

Notes:

12.1 ISOLATOR ROW INSPECTION


Regular inspection and maintenance are essential to assure a properly functioning stormwater system. Inspection is easily accomplished through the manhole or optional inspection ports of an Isolator Row. Please follow local and OSHA rules for a confined space entry.

Inspection ports can allow inspection to be accomplished completely from the surface without the need for a confined space entry. Inspection ports provide visual access to the system with the use of a flashlight. A stadia rod may be inserted to determine the depth of sediment. If upon visual inspection it is found that sediment has accumulated to an average depth exceeding 3" (76 mm), cleanout is required.

A StormTech Isolator Row should initially be inspected immediately after completion of the site's construction. While every effort should be made to prevent sediment from entering the system during construction, it is during this time that excess amounts of sediments are most likely to enter any stormwater system. Inspection and maintenance, if necessary, should be performed prior to passing responsibility over to the site's owner. Once in normal service, a StormTech Isolator Row should be inspected bi-annually until an understanding of the sites characteristics is developed. The site's maintenance manager can then revise the inspection schedule based on experience or local requirements.

12.2 ISOLATOR ROW MAINTENANCE



JetVac maintenance is recommended if sediment has been collected to an average depth of 3" (76 mm) inside the Isolator Row. More frequent maintenance may be required to maintain minimum flow rates through the Isolator Row. The JetVac process utilizes a high pressure water nozzle to propel itself down the Isolator Row while scouring and suspending sediments. As the nozzle is retrieved, a wave of suspended sediments is flushed back into the manhole for vacuuming. Most sewer and pipe maintenance companies have vacuum/ JetVac combination vehicles. Fixed nozzles designed for culverts or large diameter pipe cleaning are preferable. Rear facing jets with an effective spread of at least 45" (1143 mm) are best. The JetVac process shall only be performed on StormTech Rows that have AASHTO class 1 woven geotextile over the foundation stone (ADS 315ST or equal).



Looking down the Isolator Row



A typical JetVac truck (This is not a StormTech product.)



Examples of culvert cleaning nozzles appropriate for Isolator Row maintenance. (These are not StormTech products).

12.0 Inspection & Maintenance

STORMTECH ISOLATOR™ ROW - STEP-BY-STEP MAINTENANCE PROCEDURES

Step 1) Inspect Isolator Row for sediment

- A) Inspection ports (if present)
 - i. Remove lid from floor box frame
 - ii. Remove cap from inspection riser
 - iii. Using a flashlight and stadia rod, measure depth of sediment
 - iv. If sediment is at, or above, 3" (76 mm) depth proceed to Step 2. If not proceed to Step 3.
- B) All Isolator Rows
 - i. Remove cover from manhole at upstream end of Isolator Row
 - ii. Using a flashlight, inspect down Isolator Row through outlet pipe
 - 1. Follow OSHA regulations for confined space entry if entering manhole
 - 2. Mirrors on poles or cameras may be used to avoid a confined space entry
 - iii. If sediment is at or above the lower row of sidewall holes [approximately 3" (76 mm)] proceed to Step 2. If not proceed to Step 3.


Step 2) Clean out Isolator Row using the JetVac process

- A) A fixed floor cleaning nozzle with rear facing nozzle spread of 45" (1143 mm) or more is preferable
- B) Apply multiple passes of JetVac until backflush water is clean
- C) Vacuum manhole sump as required during jetting

Step 3) Replace all caps, lids and covers

Step 4) Inspect and clean catch basins and manholes upstream of the StormTech system following local guidelines.

Figure 20 – StormTech Isolator Row (not to scale)



12.3 ECCENTRIC PIPE HEADER INSPECTION

These guidelines do not supercede a pipe manufacturer's recommended I&M procedures. Consult with the manufacturer of the pipe header system for specific I&M procedures. Inspection of the header system should be carried out quarterly. On sites which generate higher levels of sediment more frequent inspections may be necessary. Headers may be accessed through risers, access ports or manholes. Measurement of sediment may be taken with a stadia rod or similar device. Cleanout of sediment should occur when the sediment volume has reduced the storage area by 25% or the depth of sediment has reached approximately 25% of the diameter of the structure.


12.4 ECCENTRIC PIPE MANIFOLD MAINTENANCE

Cleanout of accumulated material should be accomplished by vacuum pumping the material from the header. Cleanout should be accomplished during dry weather. Care should be taken to avoid flushing sediments out through the outlet pipes and into the chamber rows.

Eccentric Header Step-by-Step Maintenance Procedures

1. Locate manholes connected to the manifold system
2. Remove grates or covers
3. Using a stadia rod, measure the depth of sediment
4. If sediment is at a depth of about 25% pipe volume or 25% pipe diameter proceed to step 5. If not proceed to step 6.
5. Vacuum pump the sediment. Do not flush sediment out inlet pipes.
6. Replace grates and covers
7. Record depth and date and schedule next inspection

Figure 21 – Eccentric Manifold Maintenance



Please contact StormTech's Technical Services Department at 888-892-2894 for a spreadsheet to estimate cleaning intervals.

APPENDIX D

**GEOTECHNICAL
REPORT**

**Report of Additional Geotechnical
Engineering Services**

The Hedges Development—Building D
Tualatin, Oregon

for
Martin Development

July 10, 2019



**Report of Additional Geotechnical
Engineering Services**

The Hedges Development—Building D
Tualatin, Oregon

for

Martin Development

July 10, 2019



4000 Kruse Way Place
Building 3, Suite 200
Lake Oswego, Oregon 97035
503.624.9274

**Report of Additional Geotechnical
Engineering Services**

**The Hedges Development—Building D
Tualatin, Oregon**

File No. 0821-014-06

July 10, 2019


Prepared for:

Martin Development
PO Box 15523
Seattle, Washington 98115

Attention: Mac Martin

Prepared by:


GeoEngineers, Inc.
4000 Kruse Way Place
Building 3, Suite 200
Lake Oswego, Oregon, 97035
503.624.9274



Tyler A. Pierce, PE
Project Engineer

Greg A. Landau,
PE, GE

Digitally signed
by Greg A.
Landau, PE, GE
Date: 2019.07.10
15:31:42 -07'00'



Greg A. Landau, PE, GE
Associate Geotechnical Engineer

EXPIRES: 12/31/20

TAP:GAL:cje

Disclaimer: Any electronic form, facsimile or hard copy of the original document (email, text, table, and/or figure), if provided, and any attachments are only a copy of the original document. The original document is stored by GeoEngineers, Inc. and will serve as the official document of record.

Table of Contents

1.0 INTRODUCTION	1
2.0 SCOPE OF SERVICES	1
3.0 FIELD EXPLORATIONS AND LABORATORY TESTING	1
3.1. Field Explorations.....	1
3.2. Laboratory Testing	2
4.0 SITE CONDITIONS	2
4.1. Surface Conditions.....	2
4.2. Subsurface Conditions	2
4.2.1. Northern Building (Building A)	2
4.2.2. Southern Building (Building B).....	3
4.2.3. Groundwater	3
5.0 CONCLUSIONS AND RECOMMENDATIONS	3
5.1. Summary	3
6.0 EARTHWORK RECOMMENDATIONS	3
6.1. Site Preparation	3
6.2. Subgrade Preparation and Evaluation.....	4
6.3. Wet Weather Construction	4
6.4. Excavation	5
6.5. Dewatering	5
6.6. Shoring	5
6.7. Structural Fill and Backfill	6
6.7.1. General.....	6
6.7.2. Use of On-site Soil	6
6.7.3. Imported Select Structural Fill.....	6
6.7.4. Aggregate Base.....	6
6.7.5. Trench Backfill	6
6.7.6. Fill Placement and Compaction.....	7
6.8. Temporary Cut Slopes	7
7.0 STRUCTURAL DESIGN RECOMMENDATIONS	7
7.1. Foundation Support Recommendations	7
7.1.1. Aggregate Piers.....	7
7.1.2. Bearing Capacity.....	8
7.1.3. Foundation Settlement	8
7.1.4. Lateral Resistance.....	8
7.2. Drainage Considerations	8
7.3. Slab-on-Grade Floors	9
8.0 RECOMMENDED ADDITIONAL GEOTECHNICAL SERVICES	9
9.0 LIMITATIONS	9
10.0 REFERENCES	10

LIST OF FIGURES

Figure 1. Vicinity Map

Figure 2. Site Plan

Figure 3. Geologic Cross Section A-A'

Figure 4. Geologic Cross Section B-B'

Figure 5. Geologic Cross Section C-C'

APPENDICES

Appendix A. Field Exploration and Laboratory Testing

Figure A-1. Key to Exploration Logs

Figures A-2 through A-4. Logs of Borings

Figures A-5 through A-8. Logs of CPT Probes

Appendix B. Report Limitations and Guidelines for Use

1.0 INTRODUCTION

This report presents the results of GeoEngineers' additional geotechnical engineering services for the proposed Hedges D site at the Hedges Development in Tualatin, Oregon. The site is located at the west end of SW 115th Street and is bounded by private properties, or undeveloped riparian wetlands, to the north, west and south, and by the Hedges Creek channel on the east. The location of the site is shown in the Vicinity Map, Figure 1.

GeoEngineers completed a Due Diligence and Preliminary Geotechnical Engineering Services Report for Hedges C & D, dated September 6, 2018 (Preliminary Report). Since the Preliminary Report was finalized, the proposed Hedges D development has been modified from a single 64,500-square-foot (sf) building to two buildings—a northern 34,600-sf building and a southern 25,000-sf building. Building loads have not been developed at the time this report was prepared, but we understand the proposed buildings will be a single-story, concrete tilt panel construction with the possibility of 50 percent mezzanine.

Subsurface conditions encountered during the due diligence phase encountered a variable thickness of human placed fill material over alluvium, including a variable layer of very soft elastic silt, very loose silty sand and peat.

2.0 SCOPE OF SERVICES

The purpose of this report is to better define the subsurface conditions beneath the proposed buildings and update our recommendations from the Preliminary Report, as appropriate. Our proposed scope of services included the following:

1. Reviewed previous explorations completed at the site.
2. Coordinated utility locating prior to our explorations by contacting the public "One Call" locating service.
3. Explored subsurface soil and groundwater conditions at the site by completing up to four cone penetrometer tests (CPT), to depths between 47 and 81 feet below ground surface (bgs). The CPTs were located within the proposed building footprints and completed in a single day.
4. Prepared this report that summarizes our findings and provides our recommendations for aggregate piers, including layout, estimated depths, and whether grouted aggregate piers are appropriate. Our report includes a description of surface and subsurface conditions and a Site Plan showing explorations locations and other pertinent features. Results of the CPTs, as well as updated subsurface cross sections are included.

3.0 FIELD EXPLORATIONS AND LABORATORY TESTING

3.1. Field Explorations

The subsurface conditions at the proposed building locations were evaluated by performing four CPTs to depths between 47 and 81 feet below ground surface (bgs), in addition to the three geotechnical borings to depths ranging from 41½ to 81½ feet bgs, performed for the Preliminary Report. We also reviewed logs of borings performed during earlier explorations of the site by others (GeoDesign, Inc. 1997).

The approximate locations of the explorations, including those performed by others, are shown in Figure 2. The results of our explorations are presented in Appendix A.

3.2. Laboratory Testing

Soil samples are not collected when performing CPT's, so laboratory testing was not completed for this phase of the project. Laboratory tests completed for Hedges D during the due diligence phase are presented in Appendix A.

4.0 SITE CONDITIONS

4.1. Surface Conditions

The site is an approximately 5-acre parcel located west of the Hedges Creek canal. Similar drainage canals have been excavated along the north and much of the west side of the parcel. The site is currently vacant and is covered with rough field grass and small trees. The site surface is flat to very gently undulating, with elevations across the site ranging from approximately 150 feet above mean sea level (MSL) to 153 feet MSL.

4.2. Subsurface Conditions

The project site is located within the Tualatin River valley, once dominated by the active floodplains and alluvial terraces of the Tualatin River and its tributaries such as Hedges Creek.

During agricultural development and later urbanization of Tualatin-Sherwood metropolitan area, these lowlands were altered, largely by channelization of the tributary streams as well as raising the grade of the original riparian lowlands by placing a variety of fill materials ranging from ditch channel spoil, silt, sand, gravel, and construction and demolition debris. The original topography of Hedges Creek as well as the surrounding agricultural areas were never documented or, if so, was not preserved, so the thickness, extent, and location of these fills are not well defined. The project site is mantled with these man-made fills.

Two types of soil were encountered underlying the site within the depth of exploration—fill and alluvial sediments. The latter are further divided into Holocene-age alluvial silt, fine sand, and clay overlying Pleistocene-age silts and sand to gravel alluvium deposited by the catastrophic Missoula Floods. Records of site grading indicate that silty and sandy man-made fill was placed across the bulk of the site in the late 1990s, raising the site grades between 8 and 19 feet.

Subsurface conditions beneath each building are described below.

4.2.1. Northern Building (Building A)

The fill extends between 10 and 18 feet bgs across the northern building footprint. The composition of the fill is likely variable across the building footprint, varying between stiff to very stiff silt and dense silty sand to soft silt or loose silty fine sand. The CPTs were predrilled through the fill, so information pertaining to the consistency of the fill is limited to the borings conducted for the Preliminary Report.

Very soft to medium stiff silt, sandy silt or elastic silt and loose silty sand or silty gravel was encountered below the fill to depths ranging between 70 and 89 feet. A layer of highly organic peat ranging between 8 and 22 feet thick was encountered underlying the building footprint, at depths between 20 and 24 feet bgs. Beneath the very soft/loose alluvial deposits, very stiff silt with sand and dense to very dense silty

gravels and sands were encountered. Dense gravels were encountered in B-02D at 40 feet bgs and in GeoDesign, Inc. (GDI) B-3 at a depth of 89 feet bgs.

4.2.2. Southern Building (Building B)

Beneath the southern building footprint, the fill extends between 9 and 10 feet bgs. No borings or CPTs were conducted within the fill beneath the southern building, but based on our explorations and surface observations, we anticipate the fill conditions are like those encountered below the northern building.

Very soft to medium stiff silt, sandy silt, elastic silt or organic silt, and very loose to loose silty gravel and sand was encountered to depths between 65 and 70 feet bgs. Similar to the northern building, a layer of highly organic peat or organic silt ranging between 19 and 28 feet thick was encountered at depths between 15 and 18 feet bgs. Beneath the very soft/very loose alluvial deposits, very stiff to hard silt or dense to very dense silty gravels and sands were encountered. The dense gravels were observed at a depth of 66 feet bgs in GDI B-7 and at 80 feet bgs in CPT-2.

4.2.3. Groundwater

During our drilling program completed in February 2018, groundwater was encountered within ½ foot to 4 feet bgs in B-01D and B-02D, respectively. Pore water dissipation tests performed during the CPT soundings estimate static groundwater between 7 and 15 feet bgs.

Groundwater conditions are expected to vary seasonally due to rainfall events and other factors.

5.0 CONCLUSIONS AND RECOMMENDATIONS

5.1. Summary

A summary of geotechnical considerations is provided below. The summary is presented for introductory purposes only and should be used in conjunction with the complete recommendations presented in this report.

- An 8 to 28-foot-thick layer of organic silt and peat was encountered under the proposed building footprints. This organic material is highly compressible and will likely continue to settle with additional loading, although the majority of settlement under the weight of the existing fill has likely occurred.
- Based on pore pressure readings, groundwater was estimated between approximately 7 to 15 feet bgs during CPT soundings completed in June 2019. Based on drilled borings completed in February 2018, groundwater was encountered at or near the surface.
- The buildings can be supported on aggregate piers under the building footings or the entire building footprint. Grouted aggregate piers will likely be required to mitigate for the organic soils encountered.

Our specific geotechnical recommendations are presented in the following sections of this report.

6.0 EARTHWORK RECOMMENDATIONS

6.1. Site Preparation

Initial site preparation and earthwork operations will include stripping and grading the site, and excavating for utilities and foundations.

Depending on the final layout of the buildings, stripping of grass rootzone and removal and grubbing of shrubs/trees surrounding the structures may be required. Existing shrubs/trees should be removed from the site in all proposed building pad and pavement areas and for a 5-foot margin around such areas. Typically, the depth of stripping is approximately 6 to 8 inches, although thicker stripping depths may be required. The actual stripping depth should be based on field observations at the time of construction. Stripped material should be transported off site for disposal or used in landscaped areas.

Trees and their root balls should be grubbed to the depth of the roots, which could exceed 3 feet bgs. Depending on the methods used to remove the preceding material, considerable disturbance and loosening of the subgrade could occur. We recommend that disturbed soil be removed to expose medium stiff or stiffer native soil. The resulting excavations should be backfilled with structural fill.

6.2. Subgrade Preparation and Evaluation

Upon completion of site preparation activities, the exposed subgrade should be proof-rolled with a fully-loaded dump truck or similar heavy rubber-tired construction equipment to identify soft, loose or unsuitable areas. Proof-rolling should be conducted prior to placing fill, and should be observed by a representative of GeoEngineers who will evaluate the suitability of the subgrade and identify areas of yielding that are indicative of soft or loose soil. If soft or loose zones are identified during proof-rolling, these areas should be excavated to the extent indicated by our representative and replaced with Imported Select Structural Fill as defined in this report.

During wet weather, or when the exposed subgrade is wet or unsuitable for proof-rolling, the prepared subgrade should be evaluated by observing excavation activity and probing with a steel foundation probe. Observations, probing and compaction testing should be performed by a member of our staff. Wet soil that has been disturbed due to site preparation activities or soft or loose zones identified during probing, should be removed and replaced with Imported Select Structural Fill as defined in this report.

6.3. Wet Weather Construction

The fine-grained soils at the site are highly susceptible to moisture. Wet weather construction practices will be necessary if work is performed during periods of wet weather. If site grading will occur during wet weather conditions, it will be necessary to use track-mounted equipment, use gravel working pads and employ other methods to reduce ground disturbance. The contractor should be responsible to protect the subgrade during construction.

During wet weather we recommend that:

- The ground surface in and around the work area should be sloped so that surface water is directed to a sump or discharge location. The ground surface should be graded such that areas of ponded water do not develop.
- The site soils should not be left uncompacted and exposed to moisture. Sealing the surficial soils by rolling with a smooth-drum roller prior to periods of precipitation will reduce the extent to which these soils become wet or unstable.
- Construction activities should be scheduled so that the length of time that soils are left exposed to moisture is reduced to the extent practicable.

- During periods of wet weather, concrete should be placed as soon as practical after preparing foundation excavations. Foundation bearing surfaces should not be exposed to standing water. Should water infiltrate and pool in the excavation, the water should be removed, and the foundation subgrade should be re-evaluated before placing reinforcing steel or concrete. Foundation subgrade protection, such as a 3- to 4-inch-thickness of crushed rock, may be necessary if footing excavations are exposed to extended wet weather conditions.

6.4. Excavation

It is our opinion that conventional earthmoving equipment in proper working condition should be capable of making necessary general excavations. The earthwork contractor should be responsible for reviewing this report, including the exploration logs, providing their own assessments, and providing equipment and methods needed to excavate the site soils while protecting subgrades.

6.5. Dewatering

As discussed in Section 4.2.3 of this report, depending on the time of year construction is completed, groundwater may be encountered at or near the ground surface. If groundwater is encountered, saturated/wet soils should be dewatered. Sump pumps are expected to adequately address groundwater encountered in shallow excavations.

6.6. Shoring

All trench excavations should be made in accordance with applicable Occupational Safety and Health Administration (OSHA) and state regulations. Site soils within expected excavation depths consist of a variable human placed fill, classified as OSHA Soil Type C, provided there is no seepage and excavations occur during periods of dry weather. Excavations deeper than 4 feet should be shored or laid back at an inclination of 1.5H:1V (horizontal to vertical) for Type C soils. Flatter slopes may be necessary if workers are required to enter. Excavations made to construct footings or other structural elements should be laid back or shored at the surface as necessary to prevent soil from falling into excavations.

Shoring for trenches less than 6 feet deep that are above the effects of groundwater should be possible with a conventional box system. Moderate sloughing should be expected outside the box. Shoring deeper than 6 feet or below the groundwater table should be designed by a registered engineer before installation. Further, the shoring design engineer should be provided with a copy of this report.

In our opinion, the contractor will be in the best position to observe subsurface conditions continuously throughout the construction process and to respond to the soil and groundwater conditions. Construction site safety is generally the sole responsibility of the contractor, who also is solely responsible for the means, methods and sequencing of the construction operations and choices regarding excavations and shoring. Under no circumstances should the information provided by GeoEngineers be interpreted to mean that GeoEngineers is assuming responsibility for construction site safety or the contractor's activities; such responsibility is not being implied and should not be inferred.

6.7. Structural Fill and Backfill

6.7.1. General

Materials used to support building foundations, floor slabs, hardscape, pavements and any other areas intended to support structures or within the influence zone of structures are classified as structural fill for the purposes of this report.

All structural fill should be free of debris, clay balls, roots, organic matter, frozen soil, man-made contaminants, particles with greatest dimension exceeding 4 inches and other deleterious materials. The suitability of soil for use as structural fill will depend on the gradation and moisture content of the soil. As the amount of fines in the soil matrix increases, the soil becomes increasingly more sensitive to small changes in moisture content and achieving the required degree of compaction becomes more difficult or impossible. Recommendations for suitable fill material are provided in the following sections.

6.7.2. Use of On-site Soil

As described in Section 4.2, the on-site near surface soil consists of variable silty fill. On-site soils can be used as structural fill, provided the material meets the above requirements, although due to moisture sensitivity, this material will likely be unsuitable as structural fill during most of the year. If the soil is too wet to achieve satisfactory compaction, moisture conditioning by drying back the material will be required. If the material cannot be properly moisture conditioned, we recommend using imported material for structural fill.

An experienced geotechnical engineer from GeoEngineers should determine the suitability of on-site soil encountered during earthwork activities for reuse as structural fill.

6.7.3. Imported Select Structural Fill

Imported select granular material may be used as structural fill. Imported Select Structural Fill should consist of pit or quarry run rock, crushed rock, or crushed gravel and sand that is fairly well-graded between coarse and fine sizes, with approximately 25 to 65 percent passing the U.S. No. 4 sieve. It should have less than 5 percent passing the U.S. No. 200 sieve and have a minimum of two mechanically fractured faces. During dry weather, the fines content can be increased to a maximum of 12 percent.

6.7.4. Aggregate Base

Aggregate base material located under floor slabs and pavements, and crushed rock used in footing overexcavations, should consist of imported clean, durable, crushed angular rock. Aggregate base material should be well-graded, have a maximum particle size of 1 inch and have less than 5 percent passing the U.S. No. 200 sieve. In addition, aggregate base shall have a minimum of 75 percent fractured particles according to American Association of State Highway and Transportation Officials (AASHTO) TP-61 and a sand equivalent of not less than 30 percent based on AASHTO T-176.

6.7.5. Trench Backfill

Backfill for pipe bedding and in the pipe zone should consist of well-graded granular material with a maximum particle size of $\frac{3}{4}$ inch and less than 5 percent passing the U.S. No. 200 sieve. Trench backfill material should be free of organic matter and other deleterious materials. Further, the backfill should meet

the pipe manufacturer's recommendations. Above the pipe zone, Imported Select Structural Fill may be used as described above.

6.7.6. Fill Placement and Compaction

Structural fill should be compacted to a minimum of 95 percent of the maximum dry density (MDD) at moisture contents that are within 3 percent of the optimum moisture content as determined by ASTM International (ASTM) Standard Practices Test Method D 1557 (Modified Proctor). The optimum moisture content varies with gradation and should be evaluated during construction. Fill material that is not near the optimum moisture content should be moisture conditioned prior to compaction.

Fill and backfill material should be placed in uniform, horizontal lifts and compacted with appropriate equipment. The appropriate lift thickness will vary depending on the material and compaction equipment used. It is the contractor's responsibility to select appropriate compaction equipment and place the material in lifts that are thin enough to meet these criteria. However, in no case should the loose lift thickness exceed 18 inches.

A representative from GeoEngineers should evaluate compaction of each lift of fill. Compaction should be evaluated by compaction testing, unless other methods are proposed for oversized materials and are approved by GeoEngineers prior to fill placement. These other methods typically involve procedural placement and compaction specifications together with verifying requirements such as proof-rolling.

6.8. Temporary Cut Slopes

Earthwork activities are expected to occur at grade, we do not expect significant cut slopes at the site.

7.0 STRUCTURAL DESIGN RECOMMENDATIONS

The foundation support recommendations provided below are based on our analysis and collaborative discussion considering required performance and cost for the project. We have carefully evaluated foundation support and subgrade preparation to provide efficient foundation design and adequate performance for the proposed building, while still considering the project schedule, soil conditions and cost of earthwork.

7.1. Foundation Support Recommendations

7.1.1. Aggregate Piers

Shallow spread footings supported on aggregate piers would provide relatively high bearing capacity and reduced settlement by creating a stiff soil subgrade. Ground improvement methods can consist of the Rammed Aggregate Pier® (RAP) System constructed by GeoPier Foundation Company, Vibro Piers™ constructed by Hayward Baker, or alternate systems if approved in advance by GeoEngineers. Aggregate pier systems are typically designed and constructed by the specialty contractor to a performance specification. They should submit a ground improvement design that has been completed and stamped by a registered professional engineer with experience in such projects. We recommend that GeoEngineers review the design on behalf of the Owner, although the specialty contractor will retain responsibility for the design and construction of the ground improvements to the specified performance criteria.

The inclusion of grout to the aggregate pier system provides additional structural rigidity within the pier element that extends through the soft compressible peat material. We anticipate that the aggregate piers would extend from footing subgrade to approximately 45 feet bgs, although the grout-improved zone would likely not extend the full depth.

We anticipate aggregate piers will extend one row outside the building footprint. They should be designed to meet the final bearing capacity and settlement tolerances provided by the structural engineer. The specialty contractor would provide final design and in-house quality control for the piers. We recommend that GeoEngineers provide construction quality assurance for the Owner during the construction process.

7.1.2. Bearing Capacity

The bearing capacity of the aggregate pier-improved subgrade would be determined by the specialty contractor and will be dependent on actual building loads and acceptable settlement magnitudes. Based on conversations with GeoPier, their aggregate piers typically can achieve bearing capacity of approximately 4,000 to 6,000 pounds per square foot (psf) in soils similar to those at the site that have been improved with aggregate piers. This value may be increased by one third when considering earthquake or wind loads.

We recommend footings have a minimum width of 24 inches and the bottom of the exterior footings be founded at least 18 inches below the lowest adjacent grade, or as needed to meet the design loads. The recommended minimum footing depth is greater than the anticipated frost depth.

7.1.3. Foundation Settlement

Settlement for shallow foundations supported on an aggregate pier improved subgrade, as described above, would depend on the specialty contractor's design. Typically, the systems are designed to a performance specification that is normally on the order of approximately 1 inch.

7.1.4. Lateral Resistance

Lateral foundation loads may be resisted by passive resistance on the sides of footings and by friction on the base of the shallow foundations. For shallow foundations supported on subgrade soils prepared as described above, the allowable frictional resistance may be computed using a coefficient of friction of 0.4 applied to vertical dead-load forces.

The allowable passive resistance may be computed using an equivalent fluid density of 280 pounds per cubic foot (pcf) (triangular distribution). These values are appropriate for foundation elements that are poured directly against undisturbed soils or surrounded by structural fill.

The above coefficient of friction and passive equivalent fluid density values incorporate a factor of safety of about 1.5.

7.2. Drainage Considerations

We recommend the ground surface be sloped away from the buildings at least 2 percent. All downspouts should be tightlined away from the building foundation areas and should also be discharged into a stormwater disposal system. Downspouts should not be connected to footing drains.

We recommend that perimeter footing drains be installed around the proposed buildings at the base of the exterior footings. The perimeter footing drains should be provided with cleanouts and should consist of at least 4-inch-diameter perforated pipe placed on a 3-inch bed of, and surrounded by, 6 inches of drainage material enclosed in a non-woven geotextile such as Mirafi 140N (or approved alternate) to prevent fine soil from migrating into the drain material. We recommend against using flexible tubing for footing drainpipes. The perimeter drains should be sloped to drain by gravity to a suitable discharge point, preferably a storm drain. We recommend that the cleanouts be covered and placed in flush-mounted utility boxes. Water collected in roof downspout lines must not be routed to the footing drain lines.

7.3. Slab-on-Grade Floors

The exposed subgrade should be evaluated after site grading is complete. Proof-rolling with heavy, rubber-tired construction equipment should be used for this purpose during dry weather. Probing should be used to evaluate the subgrade during periods of wet weather. The exposed soil should be firm and unyielding, and without significant groundwater. Loose and disturbed areas should be removed and replaced with compacted structural fill.

We recommend that GeoEngineers observe the condition of all subgrade areas to evaluate whether the work is completed in accordance with our recommendations.

Conventional slabs may be supported on-grade, provided the subgrade soils are prepared as recommended above. For slabs designed as a beam on an elastic foundation, a modulus of subgrade reaction of 150 pounds per cubic inch (pci) may be used for subgrade soils prepared as recommended over the capillary break. It should be noted that this minimum thickness of capillary break will not provide adequate support of construction traffic.

We recommend that the slab-on-grade floors be underlain by a 6-inch-thick capillary break consisting of clean (less than 5 percent passing the No. 200 sieve) $\frac{3}{4}$ -inch crushed gravel. We recommend that the capillary break be compacted to at least 95 percent of the MDD in accordance with ASTM Test Method D 1557. We also recommend that an appropriate vapor retarder be installed below the floor slab to further reduce the risk of moisture migration through the on-grade floor slabs if they are inhabited spaces.

Slab-on-grade settlements will be estimated by the ground improvement subcontractor.

8.0 RECOMMENDED ADDITIONAL GEOTECHNICAL SERVICES

During construction, GeoEngineers should observe the installation of the ground improvements, evaluate the suitability of the foundation subgrades, evaluate structural backfill, and provide a summary letter of our construction observation services. The purposes of GeoEngineers construction phase services are to confirm that the subsurface conditions are consistent with those observed in the explorations and other reasons described in Appendix B, Report Limitations and Guidelines for Use.

9.0 LIMITATIONS


We have prepared this report for the exclusive use of Martin Development and their authorized agents for The Hedges Development—Building D Project in Tualatin, Oregon.

Within the limitations of scope, schedule and budget, our services have been executed in accordance with generally accepted practices in the field of geotechnical engineering in this area at the time this report was prepared. No warranty or other conditions, express or implied, should be understood.



Please refer to Appendix B titled “Report Limitations and Guidelines for Use” for additional information pertaining to use of this report.

10.0 REFERENCES

GeoDesign, Inc. 1997. Report of Geotechnical Engineering Services, Lots 11 and 12, Franklin Business Park, Southwest Avery Street and Tualatin-Sherwood Road, Tualatin, Oregon, GDI Project: Drake-3, prepared for Drake Management Company, dated June 6, 1997.



P:\0\0821014\GIS\MXD\082101406_F01_VM_HedgesD.mxd Date Exported: 06/26/19 by ccabrera



Vicinity Map

**Hedges D
Tualatin, Oregon**



Figure 1


Notes:

1. The locations of all features shown are approximate.
2. This drawing is for information purposes. It is intended to assist in showing features discussed in an attached document. GeoEngineers, Inc. cannot guarantee the accuracy and content of electronic files. The master file is stored by GeoEngineers, Inc. and will serve as the official record of this communication.

Data Source: Mapbox Open Street Map, 2016

Projection: NAD 1983 UTM Zone 10N

P:\0_0821014\CAD\06\GeoTech\082101406_F02-F05_Site Plan and Sections.dwg TAB:F02 Date Exported: 06/25/19 - 19:19 by hmarra




Legend

- B-1D GeoEngineers Exploration Number and Approximate Location
- GDI B-1 Exploration Number and Approximate Location (by Others)
- A Cross Section Location
- A' Cross Section Location

Notes:



1. The locations of all features shown are approximate.
2. This drawing is for information purposes. It is intended to assist in showing features discussed in an attached document. GeoEngineers, Inc. cannot guarantee the accuracy and content of electronic files. The master file is stored by GeoEngineers, Inc. and will serve as the official record of this communication.

Data Source: Background PDF from Lance Muller Associates dated 4/19/19.
 Projection: OR State Plane, North Zone, NAD83, US Foot



Site Plan	
Hedges D Tualatin, Oregon	
	Figure 2


P:\0_0821014\CAD\06\GeoTech\082101406_F02-F05_Site Plan and Sections.dwg TAB:F03 Date Exported: 06/26/19 - 2:1:39 by hmara



Notes:

- The subsurface conditions shown are based on interpolation between widely spaced explorations and should be considered approximate; actual subsurface conditions may vary from those shown.
- This figure is for informational purposes only. It is intended to assist in the identification of features discussed in a related document. Data were compiled from sources as listed in this figure. The data sources do not guarantee these data are accurate or complete. There may have been updates to the data since the publication of this figure. This figure is a copy of a master document. The hard copy is stored by GeoEngineers, Inc. and will serve as the official document of record.

Datum: NAVD 88, unless otherwise noted.




Cross Section A-A'

Hedges D
Tualatin, Oregon



GEOENGINEERS

Figure 3




P:\0821014\CAD\06\GeoTech\082101406_F02-F05_Site Plan and Sections.dwg TAB:F04 Date Exported: 06/26/19 - 21:40 by hmara

P:\0_0821014\CAD\06\GeoTech\082101406_F02-F05_Site Plan and Sections.dwg TAB:F05 Date Exported: 06/26/19 - 21:40 by hmara



- Notes:**
1. The subsurface conditions shown are based on interpolation between widely spaced explorations and should be considered approximate; actual subsurface conditions may vary from those shown.
 2. This figure is for informational purposes only. It is intended to assist in the identification of features discussed in a related document. Data were compiled from sources as listed in this figure. The data sources do not guarantee these data are accurate or complete. There may have been updates to the data since the publication of this figure. This figure is a copy of a master document. The hard copy is stored by GeoEngineers, Inc. and will serve as the official document of record.

Datum: NAVD 88, unless otherwise noted.



Cross Section C-C'

Hedges D
Tualatin, Oregon

Figure 5

APPENDIX A
Field Exploration and Laboratory Testing

APPENDIX A

FIELD EXPLORATIONS AND LABORATORY TESTING

Subsurface conditions were explored by drilling two borings with a trailer-mounted drill rig employing sold-stem auger techniques provided by Dan Fisher Drilling on February 15, 2018, one boring with a tracked rig and mud-rotary techniques provided by Western States Drilling on February 21, 2018, and four cone CPT soundings on June 10, 2019, with a truck rig owned and operated by Oregon Geotechnical Explorations. The locations of the explorations were estimated by taping/pacing from existing site features. The approximate exploration locations are shown in the Site Plan, Figure 2.

Borings (Completed during Due Diligence Phase)

The drilling was continuously monitored by an engineering geologist from our office who maintained a detailed log of subsurface explorations, visually classified the soil encountered and obtained representative soil samples from the borings.

Representative soil samples were obtained from each boring at approximate 2½- to 10-foot-depth intervals using either: (1) a 1-inch, inside-diameter, standard split spoon sampler; or (2) a 2.4-inch, inside-diameter, split-barrel ring sampler (Dames & Moore [D&M]). The samplers were driven into the soil using a 140-pound hammer free-falling 30 inches on each blow; the trailer-mounted (Fisher) rig using rope-and-cathead methods, the track (Western States) using an autohammer.

The number of blows required to drive the sampler each of three, 6-inch increments of penetration were recorded in the field. The sum of the blow counts for the last two, 6-inch increments of penetration is reported on the boring logs as the ASTM International (ASTM) Standard Practices Test Method D 1556 standard penetration test (SPT) N-value. The N-value for D&M samples have been reduced by approximately 50 percent from the field readings to roughly correlate with the SPT N-values.

Recovered soil samples were visually classified in the field in general accordance with ASTM D 2488 and the classification chart listed in Key to Exploration Logs, Figure A-1. Logs of the borings are presented in Figures A-2 through A-4. The logs are based on interpretation of the field and laboratory data and indicate the depth at which subsurface materials or their characteristics change, although these changes might actually be gradual.

Cone Penetration Tests (CPT)

The CPT is a subsurface exploration technique in which a small-diameter steel tip with adjacent sleeve is continuously advanced with hydraulically operated equipment. Measurements of tip and sleeve resistance allow interpretation of the soil profile and the consistency of the strata penetrated. The tip, sleeve resistance and pore water pressure are recorded on the CPT logs. The logs of the CPT probes are presented in Figures A-5 through A-8.

Laboratory Testing (completed during Due Diligence Phase)

Soil samples obtained from the explorations were transported to GeoEngineers' laboratory and evaluated to confirm or modify field classifications, as well as to evaluate engineering properties of the soil samples. Representative samples were selected for laboratory testing to determine the moisture content, moisture-density, percent fines (material passing the U.S. No. 200 sieve), and organic content. The tests were performed in general accordance with ASTM standard practices or other applicable procedures.

The results of the moisture content and percent fines determinations are presented at the respective sample depths in the exploration logs in Appendix A.

Moisture Content

Moisture content tests were completed in general accordance with ASTM D 2216 for representative samples obtained from the explorations. The results of these tests are presented in the exploration logs in Appendix A at the depths at which the samples were obtained.

Moisture-Density

We completed moisture density (dry density) testing on selected D&M samples in general accordance with the ASTM D 2937 test method. The results are presented on the boring logs.

Percent Passing U.S. No. 200 Sieve (%F)

Selected samples were “washed” through the U.S. No. 200 mesh sieve to estimate the relative percentages of coarse- and fine-grained particles in the soil. The percent passing value represents the percentage by weight of the sample finer than the U.S. No. 200 sieve. These tests were conducted to verify field descriptions and to estimate the fines content for analysis purposes. The tests were conducted in accordance with ASTM D 1140, and the results are shown in the exploration logs in Appendix A at the respective sample depths.

Organic Content

Organic content tests were performed to determine the amount of organic material present in selected samples in general accordance with ASTM D 2974, Method C. The results of the organic content tests are presented in the exploration logs in Appendix A.

SOIL CLASSIFICATION CHART

MAJOR DIVISIONS			SYMBOLS		TYPICAL DESCRIPTIONS
			GRAPH	LETTER	
COARSE GRAINED SOILS	GRAVEL AND GRAVELLY SOILS	CLEAN GRAVELS <small>(LITTLE OR NO FINES)</small>		GW	WELL-GRADED GRAVELS, GRAVEL - SAND MIXTURES
		GRAVELS WITH FINES <small>(APPRECIABLE AMOUNT OF FINES)</small>		GP	POORLY-GRADED GRAVELS, GRAVEL - SAND MIXTURES
		GRAVELS WITH FINES <small>(APPRECIABLE AMOUNT OF FINES)</small>		GM	SILTY GRAVELS, GRAVEL - SAND - SILT MIXTURES
	SAND AND SANDY SOILS	CLEAN SANDS <small>(LITTLE OR NO FINES)</small>		SW	WELL-GRADED SANDS, GRAVELLY SANDS
		SANDS WITH FINES <small>(APPRECIABLE AMOUNT OF FINES)</small>		SP	POORLY-GRADED SANDS, GRAVELLY SAND
		SANDS WITH FINES <small>(APPRECIABLE AMOUNT OF FINES)</small>		SM	SILTY SANDS, SAND - SILT MIXTURES
FINE GRAINED SOILS	SILTS AND CLAYS	LIQUID LIMIT LESS THAN 50		ML	INORGANIC SILTS, ROCK FLOUR, CLAYEY SILTS WITH SLIGHT PLASTICITY
		LIQUID LIMIT LESS THAN 50		CL	INORGANIC CLAYS OF LOW TO MEDIUM PLASTICITY, GRAVELLY CLAYS, SANDY CLAYS, SILTY CLAYS, LEAN CLAYS
		LIQUID LIMIT LESS THAN 50		OL	ORGANIC SILTS AND ORGANIC SILTY CLAYS OF LOW PLASTICITY
	SILTS AND CLAYS	LIQUID LIMIT GREATER THAN 50		MH	INORGANIC SILTS, MICACEOUS OR DIATOMACEOUS SILTY SOILS
		LIQUID LIMIT GREATER THAN 50		CH	INORGANIC CLAYS OF HIGH PLASTICITY
		LIQUID LIMIT GREATER THAN 50		OH	ORGANIC CLAYS AND SILTS OF MEDIUM TO HIGH PLASTICITY
HIGHLY ORGANIC SOILS				PT	PEAT, HUMUS, SWAMP SOILS WITH HIGH ORGANIC CONTENTS

NOTE: Multiple symbols are used to indicate borderline or dual soil classifications

Sampler Symbol Descriptions

	2.4-inch I.D. split barrel
	Standard Penetration Test (SPT)
	Shelby tube
	Piston
	Direct-Push
	Bulk or grab
	Continuous Coring

Blowcount is recorded for driven samplers as the number of blows required to advance sampler 12 inches (or distance noted). See exploration log for hammer weight and drop.

"P" indicates sampler pushed using the weight of the drill rig.

"WOH" indicates sampler pushed using the weight of the hammer.

NOTE: The reader must refer to the discussion in the report text and the logs of explorations for a proper understanding of subsurface conditions. Descriptions on the logs apply only at the specific exploration locations and at the time the explorations were made; they are not warranted to be representative of subsurface conditions at other locations or times.

ADDITIONAL MATERIAL SYMBOLS

SYMBOLS		TYPICAL DESCRIPTIONS
GRAPH	LETTER	
	AC	Asphalt Concrete
	CC	Cement Concrete
	CR	Crushed Rock/Quarry Spalls
	SOD	Sod/Forest Duff
	TS	Topsoil

Groundwater Contact



Measured groundwater level in exploration, well, or piezometer



Measured free product in well or piezometer

Graphic Log Contact



Distinct contact between soil strata



Approximate contact between soil strata

Material Description Contact



Contact between geologic units



Contact between soil of the same geologic unit

Laboratory / Field Tests

%F	Percent fines
%G	Percent gravel
AL	Atterberg limits
CA	Chemical analysis
CP	Laboratory compaction test
CS	Consolidation test
DD	Dry density
DS	Direct shear
HA	Hydrometer analysis
MC	Moisture content
MD	Moisture density
Mohs	Mohs hardness scale
OC	Organic content
PM	Permeability or hydraulic conductivity
PI	Plasticity index
PP	Pocket penetrometer
SA	Sieve analysis
TX	Triaxial compression
UC	Unconfined compression
VS	Vane shear

Sheen Classification

NS	No Visible Sheen
SS	Slight Sheen
MS	Moderate Sheen
HS	Heavy Sheen

Key to Exploration Logs



Figure A-1

Start Drilled	2/15/2018	End	2/15/2018	Total Depth (ft)	41.5	Logged By	JLL	Checked By	GL	Driller	Dan Fischer Drilling	Drilling Method	Solid-stem Auger
Surface Elevation (ft)	149			Hammer Data	Rope & Cathead			140 (lbs) / 30 (in) Drop		Drilling Equipment		Paul Bunyan Trailer	
Vertical Datum	NAVD88			System Datum	OR State Plane North			NAD83 (feet)		See "Remarks" section for groundwater observed			
Easting (X)	7611554			Notes: D&M N-value reduced by 50 percent to approximate SPT N-value									
Northing (Y)	631175												

Elevation (feet)	Depth (feet)	FIELD DATA				Graphic Log	Group Classification	MATERIAL DESCRIPTION	Moisture Content (%)	Fines Content (%)	REMARKS
		Interval Recovered (in)	Blows/foot	Collected Sample	Sample Name Testing						
0						ML	Brown silt, low to medium plasticity, grass roots to 6 to 8 inches, trace to occasional sand (very stiff, moist) (fill)			Groundwater observed at approximately 6 inches below ground surface during drilling	
1.45	10	22	1								
5	14	9	2			SM	Brown silty fine to medium sand, fine gravel (loose, moist to wet)				
1.40	0	8	3								
10	12	8	4			ML	Light gray-brown fine sandy silt, low plasticity, trace brick fragments and gravel (medium stiff, moist to wet) Drill action indicates cobble or debris 12½ to 14½ feet				
1.35	0	12	5								
15	0	12	5				Dark gray fine to medium sandy silt with gravel, angular basalt gravel to 4 inches (stiff, wet)				
1.30	10	6	6	MD		ML	Dark gray silt, moderate plasticity, trace to occasional roots and organic fibers, trace fine sand (medium stiff, wet) (alluvium)	31		DD = 86 pcf	
1.25	12	3	7	OC		OL/PT	Dark gray to black organic silt with fine sand, occasional interbeds of brown peat, much fibrous organic matter (soft, wet)	276		OC = 40 percent	
1.20	1	4	8	OC			Gray sandy silt with organic silt (soft to medium stiff, wet)	95		OC = 10 percent	
1.15						ML/MH	Dark gray silt, moderate plasticity, trace fine sand (medium stiff, wet)				
35											

Note: See Figure A-1 for explanation of symbols.
Coordinates Data Source: Horizontal approximated based on USGS Topo. Vertical approximated based on USGS Topo.

Log of Boring B-01D



Project: The Hedges - Building C and D
Project Location: Tualatin, Oregon
Project Number: 0821-014-02

Date: 3/6/18 Path: P:\0821014\GINT\082101402.GPJ DBLibrary\Library\GEOENGINEERS_DF_STD_US_JUNE_2017\GLB\GEIB_GEOTECH_STANDARD_SF_NO_GW

Date: 3/6/18 Path: P:\0821-014\GINT\0821-014-02.GPJ DBLibrary\Library\GEOENGINEERS_DF_STD_US_JUNE_2017\GLB\GEIB_GEO TECH_STANDARD_SF_NO_GW

Elevation (feet)	FIELD DATA					Graphic Log	Group Classification	MATERIAL DESCRIPTION	Moisture Content (%)	Fines Content (%)	REMARKS
	Depth (feet)	Interval Recovered (in)	Blows/foot	Collected Sample	Sample Name Testing						
48	1	5		9							
40	12	38		10		SM	Dark gray silty medium to coarse sand, occasional gravel (dense, wet)				
						GM	Dark gray silty gravel with coarse sand, angular basalt gravel to 1-inch (dense, wet)				

Log of Boring B-01D (continued)



Project: The Hedges - Building C and D
 Project Location: Tualatin, Oregon
 Project Number: 0821-014-02

Start Drilled	2/15/2018	End	2/15/2018	Total Depth (ft)	41.5	Logged By	JLL	Checked By	GL	Driller	Dan Fischer Drilling	Drilling Method	Solid-stem Auger
Surface Elevation (ft)	150			Hammer Data	Rope & Cathead			140 (lbs) / 30 (in) Drop		Drilling Equipment		Paul Bunyan Trailer	
Vertical Datum	NAVD88			System Datum	OR State Plane North			NAD83 (feet)		See "Remarks" section for groundwater observed			
Easting (X)	7611117			Notes: D&M N-value reduced by 50 percent to approximate SPT N-value									
Northing (Y)	631187												

Elevation (feet)	FIELD DATA					Graphic Log	Group Classification	MATERIAL DESCRIPTION	Moisture Content (%)	Fines Content (%)	REMARKS
	Depth (feet)	Interval Recovered (in)	Blows/foot	Collected Sample	Sample Name Testing						
0							ML	Dark brown silt, trace sand and debris (roots to 6 to 8 inches) (stiff, moist) (fill)			
1.45		12	20		1			Mixed gray and brown silt with fine to medium sand, occasional gravel, low plasticity (very stiff, moist)			
5		14	2		2 %F		SM	Brown silty fine sand with occasional interbeds of sandy silt, occasional gravel to 3/4-inch, low plasticity to non-plastic (loose and soft, wet)	26	37	Groundwater observed at approximately 4 feet below ground surface during drilling
1.40		14	3		3 MD		ML	Dark gray to occasional brown mottling silt, trace fine sand, low to moderate plasticity (soft, wet)	30		DD = 95 pcf
10		12	1		4		ML/MH	Gray-brown silt to elastic silt, trace fine sand, occasional gravel, moderate plasticity (very soft, wet) (alluvium)			
1.35		16	4		5 MD		ML	Dark gray silt, low to moderate plasticity, occasional organic fragments including fibers, roots and stems, occasional 3- to 4-inch-thick organic silt layers with much organic matter (soft, wet)	31		DD = 88 pcf
1.30		0	2		6 MD		OL	Brown organic silt, trace peat, fibrous organic matter, trace fine sand (soft, wet)	212		DD = 33 pcf
1.25		4	2		7		SM	Becomes yellow-brown with red-brown mottling, moderate plasticity, stems and grass blades			
1.20		8	2		8		ML/MH	Dark gray silty fine sand, massive (very loose, wet)			
1.15								Mixed light gray and brown elastic silt with gray-brown silt, trace organic matter, low to medium plasticity (soft, wet)			

Note: See Figure A-1 for explanation of symbols.
Coordinates Data Source: Horizontal approximated based on USGS Topo. Vertical approximated based on USGS Topo.

Log of Boring B-02D



Project: The Hedges - Building C and D
Project Location: Tualatin, Oregon
Project Number: 0821-014-02

Date: 3/6/18 Path: P:\0821014\GINT\082101402.GPJ DBLibrary\Library\GEOENGINEERS_DF_STD_US_JUNE_2017\GLB\GEB\GEOTECH_STANDARD_%F_INO_GW

Date: 3/6/18 Path: P:\0821-014\GINT\0821-014-02.GPJ DBLibrary\Library\GEOENGINEERS_DF_STD_US_JUNE_2017\GLB\GEIB_GEO TECH_STANDARD_SF_NO_GW

Elevation (feet)	FIELD DATA					Group Classification	MATERIAL DESCRIPTION	Moisture Content (%)	Fines Content (%)	REMARKS
	Depth (feet)	Interval Recovered (in)	Blows/foot	Collected Sample	Sample Name Testing					
38	12	10		9		SP	Dark gray poorly-graded coarse sand, massive (loose, wet)			
40	6	21		10						

Log of Boring B-02D (continued)



Project: The Hedges - Building C and D
 Project Location: Tualatin, Oregon
 Project Number: 0821-014-02

Start Drilled	2/21/2018	End	2/21/2018	Total Depth (ft)	81.5	Logged By	JLL	Checked By	GL	Driller	Western States Soil Conservation, Inc.	Drilling Method	Mud Rotary
Surface Elevation (ft)	149			Hammer Data	Roper & Cathhead			140 (lbs) / 30 (in) Drop		Drilling Equipment	CME-850 Truck		
Vertical Datum	NAVD88			System Datum	OR State Plane North			NAD83 (feet)		Groundwater not observed at time of exploration			
Easting (X)	7611497												
Northing (Y)	630994												
Notes: D&M N-value reduced by 50 percent to approximate SPT N-value													

Elevation (feet)	FIELD DATA					Graphic Log	Group Classification	MATERIAL DESCRIPTION	Moisture Content (%)	Fines Content (%)	REMARKS
	Depth (feet)	Interval Recovered (in)	Blows/foot	Collected Sample	Sample Name Testing						
0							ML	Dark brown silt, roots and organic matter to 6 to 8 inches, low to moderate plasticity (soft, wet) (fill)			
1.45								Drill action and cuttings indicate occasional cobbles, cobble-sized brick, concrete debris 2 to 4 feet			
5	12	20		1				Becomes dark gray, trace fine sand, occasional fine sandy silt, low plasticity to non-plastic (very stiff, moist)			
1.40								Large debris/cobble fragments 7½ to 9 feet			
10	14	36		2	%F		ML/SM	Dark gray, occasional brown silt with fine to medium sand and gravel to silty medium to coarse sand with gravel, round to angular basalt gravels (dense and hard, moist)	18	36	
1.35											
15	14	10		3			ML	Dark gray, green, occasional medium silt, low plasticity, trace fine sand, occasional sand, trace angular gravel, brick fragments (stiff, moist)			
1.30											
20	18	4		4	OC		PT	Black, occasional brown peat, low plasticity, fibrous organic matter (soft, moist) (alluvium)	404		OC = 56 percent
1.25								Occasional wood fragments, wet			
25	18	2		5	MD				304		DD = 17 pcf
1.20											
30	18	4		6	OC		OL	Brown organic silt, much organic fibers, low plasticity, fine horizontal layers (soft, moist)	329		OC = 42 percent
1.15											
35							MH	Gray elastic silt, trace organic matter, moderate			

Note: See Figure A-1 for explanation of symbols.
Coordinates Data Source: Horizontal approximated based on USGS Topo. Vertical approximated based on USGS Topo.

Log of Boring B-03D



Project: The Hedges - Building C and D
Project Location: Tualatin, Oregon
Project Number: 0821-014-02

Date: 3/6/18 Path: P:\0821014\GINT\082101402.GPJ DBLibrary\Library\GEOENGINEERS_DF_STD_US_JUNE_2017\GLB\GEB_GEO TECH_STANDARD_SF_NO_GW

Date: 3/6/18 Path: P:\0821014\GINT\082101402.GPJ DBLibrary\Library\GEOENGINEERS_DF_STD_US_JUNE_2017\GLB\GEIB_GEOTECH_STANDARD_SF_NO_GW

Elevation (feet)	FIELD DATA				Graphic Log	Group Classification	MATERIAL DESCRIPTION	Moisture Content (%)	Fines Content (%)	REMARKS
	Depth (feet)	Interval Recovered (in)	Blows/foot	Collected Sample						
35		16	P		7		plasticity (very soft, moist)			
40	110	18	4		8 MD	ML/SM	Interbedded gray silt, low plasticity, trace fine sand and silty fine sand, occasional 1-inch layers of coarse sand (soft and loose, wet)	57		DD = 67 pcf
45	105	12	2		9	GM ML	Drill action indicates gravel 44 to 45 feet Gray silt, low to moderate plasticity, trace fine sand (soft, wet)			Lost circulation at 45 feet
50	100	0	22		10	GM/SM SM	Dark gray silty coarse sand with gravel to silty gravel with coarse sand (medium dense, wet)			Drill action indicates gravel, occasional cobble 47½ to 50 feet, coarse sand and gravel in cuttings Lost circulation at 48 feet
55	95	16	3		11	MH	Gray elastic silt, massive (soft, wet)			
60	90	6	18		12	GM SM	Dark gray silty coarse sand with gravel, angular basalt gravel to 1½ inches (medium dense, wet)			Drill action indicates gravel at 57½ Lost circulation at 58 feet
65	85	10	16		13	GM SP	Dark gray poorly-graded coarse sand with gravel (medium dense, wet)			Driller reports very loose to loose gravel
70	80	16	12		14	ML SM	Light gray silt, moderate to high plasticity (very soft, wet) Gray-green silty fine sand, massive to horizontal layers (medium dense, wet)	61		AL (LL = 40, PL = 29, PI = 17)
75	75	18	14		15	ML	Gray-green silt, low plasticity, trace fine sand, massive (stiff, moist)			

Log of Boring B-03D (continued)



Project: The Hedges - Building C and D
 Project Location: Tualatin, Oregon
 Project Number: 0821-014-02

Date: 3/6/18 Path: P:\0821-014\GINT\0821-014-02.GPJ DBLibrary/Library\GEOENGINEERS_DF_STD_US_JUNE_2017\GLB\GEIB_GEO TECH_STANDARD_SF_NO_GW

Elevation (feet)	FIELD DATA					MATERIAL DESCRIPTION	Moisture Content (%)	Fines Content (%)	REMARKS
	Depth (feet)	Interval Recovered (in)	Blows/foot	Collected Sample	Sample Name Testing				
80		0	28		16				Becomes gray-green with brown mottling, very stiff


Log of Boring B-03D (continued)



Project: The Hedges - Building C and D
 Project Location: Tualatin, Oregon
 Project Number: 0821-014-02

GeoEngineers / CPT-1 / Hedges SW 115th Street Tualatin

OPERATOR: OGE TAJ
 CONE ID: DPGL386
 HOLE NUMBER: CPT-1
 TEST DATE: 6/10/2019 1:10:12 PM
 TOTAL DEPTH: 65.617 ft




- | | | | |
|--|--|--|--|
| <ul style="list-style-type: none"> 1 sensitive fine grained 2 organic material 3 clay | <ul style="list-style-type: none"> 4 silty clay to clay 5 clayey silt to silty clay 6 sandy silt to clayey silt | <ul style="list-style-type: none"> 7 silty sand to sandy silt 8 sand to silty sand 9 sand | <ul style="list-style-type: none"> 10 gravelly sand to sand 11 very stiff fine grained (*) 12 sand to clayey sand (*) |
|--|--|--|--|
- *SBT/SPT CORRELATION: UBC-1983

Figure A-5

GeoEngineers / CPT-2 / Hedges SW 115th Street Tualatin

OPERATOR: OGE TAJ
 CONE ID: DPGL386
 HOLE NUMBER: CPT-2
 TEST DATE: 6/10/2019 11:38:23 AM
 TOTAL DEPTH: 81.037 ft




- | | | | | | | | |
|---------------------------------------|------------------------|--|---------------------------|---|--------------------------------|--|-----------------------------|
| ■ 1 | sensitive fine grained | ■ 4 | silty clay to clay | ■ 7 | silty sand to sandy silty sand | ■ 10 | gravelly sand to sand |
| ■ 2 | organic material | ■ 5 | clayey silt to silty clay | ■ 8 | sand to silty sand | ■ 11 | very stiff fine grained (*) |
| ■ 3 | clay | ■ 6 | sandy silt to clayey silt | ■ 9 | sand | ■ 12 | sand to clayey sand (*) |
- *SBT/SPT CORRELATION: UBC-1983

Figure A-6

GeoEngineers / CPT-3 / Hedges SW 115th Street Tualatin

OPERATOR: OGE TAJ
 CONE ID: DPGL386
 HOLE NUMBER: CPT-3
 TEST DATE: 6/10/2019 9:48:19 AM
 TOTAL DEPTH: 47.244 ft




- | | | | |
|--|---|--|---|
| <ul style="list-style-type: none"> 1 sensitive fine grained 2 organic material 3 clay | <ul style="list-style-type: none"> 4 silty clay to clay 5 clayey silt to silty clay 6 sandy silt to clayey silt | <ul style="list-style-type: none"> 7 silty sand to sandy silt 8 sand to silty sand 9 sand | <ul style="list-style-type: none"> 10 gravelly sand to sand 11 very stiff fine grained (*) 12 sand to clayey sand (*) |
|--|---|--|---|
- *SBT/SPT CORRELATION: UBC-1983

Figure A-7

GeoEngineers / CPT-4 / Hedges SW 115th Street Tualatin

OPERATOR: OGE TAJ
 CONE ID: DPG1386
 HOLE NUMBER: CPT-4
 TEST DATE: 6/10/2019 2:19:25 PM
 TOTAL DEPTH: 65.617 ft



- | | | | |
|--|--|--|--|
| <ul style="list-style-type: none"> 1 sensitive fine grained 2 organic material 3 clay | <ul style="list-style-type: none"> 4 silty clay to clay 5 clayey silt to silty clay 6 sandy silt to clayey silt | <ul style="list-style-type: none"> 7 silty sand to sandy silt 8 sand to silty sand 9 sand | <ul style="list-style-type: none"> 10 gravelly sand to sand 11 very stiff fine grained (*) 12 sand to clayey sand (*) |
|--|--|--|--|

*SBT/SPT CORRELATION: UBC-1983

Figure A-8

APPENDIX B
Report Limitations and Guidelines for Use

APPENDIX B REPORT LIMITATIONS AND GUIDELINES FOR USE¹

This appendix provides information to help you manage your risks with respect to the use of this report.

Geotechnical Services Are Performed for Specific Purposes, Persons and Projects

This report has been prepared for the exclusive use of the Martin Development and for the Project specifically identified in the report. The information contained herein is not applicable to other sites or projects.

GeoEngineers structures our services to meet the specific needs of our clients. For example, a geotechnical or geologic study conducted for a civil engineer or architect may not fulfill the needs of a construction contractor or even another civil engineer or architect that are involved in the same project. Because each geotechnical or geologic study is unique, each geotechnical engineering or geologic report is unique, prepared solely for the specific client and project site. Our report is prepared for the exclusive use of our Client. No other party may rely on the product of our services unless we agree in advance to such reliance in writing. This is to provide our firm with reasonable protection against open-ended liability claims by third parties with whom there would otherwise be no contractual limits to their actions. Within the limitations of scope, schedule and budget, our services have been executed in accordance with our Agreement with the Client and generally accepted geotechnical practices in this area at the time this report was prepared. This report should not be applied for any purpose or project except the one originally contemplated.

A Geotechnical Engineering or Geologic Report Is Based on a Unique Set of Project-specific Factors

This report has been prepared for The Hedges Development—Building D Project in Tualatin, Oregon. GeoEngineers considered a number of unique, project-specific factors when establishing the scope of services for this project and report. Unless GeoEngineers specifically indicates otherwise, do not rely on this report if it was:

- not prepared for you,
- not prepared for your project,
- not prepared for the specific site explored, or
- completed before important project changes were made.

For example, changes that can affect the applicability of this report include those that affect:

- the function of the proposed structure;
- elevation, configuration, location, orientation or weight of the proposed structure;
- composition of the design team; or
- project ownership.

¹ Developed based on material provided by ASFE, Professional Firms Practicing in the Geosciences; www.asfe.org.

If important changes are made after the date of this report, GeoEngineers should be given the opportunity to review our interpretations and recommendations and provide written modifications or confirmation, as appropriate.

Subsurface Conditions Can Change

This geotechnical or geologic report is based on conditions that existed at the time the study was performed. The findings and conclusions of this report may be affected by the passage of time, by manmade events such as construction on or adjacent to the site, or by natural events such as floods, earthquakes, slope instability or groundwater fluctuations. Always contact GeoEngineers before applying a report to determine if it remains applicable.

Most Geotechnical and Geologic Findings Are Professional Opinions

Our interpretations of subsurface conditions are based on field observations from widely spaced sampling locations at the site. Site exploration identifies subsurface conditions only at those points where subsurface tests are conducted or samples are taken. GeoEngineers reviewed field and laboratory data and then applied our professional judgment to render an opinion about subsurface conditions throughout the site. Actual subsurface conditions may differ, sometimes significantly, from those indicated in this report. Our report, conclusions and interpretations should not be construed as a warranty of the subsurface conditions.

Geotechnical Engineering Report Recommendations Are Not Final

Do not over-rely on the preliminary construction recommendations included in this report. These recommendations are not final, because they were developed principally from GeoEngineers' professional judgment and opinion. GeoEngineers' recommendations can be finalized only by observing actual subsurface conditions revealed during construction. GeoEngineers cannot assume responsibility or liability for this report's recommendations if we do not perform construction observation.

Sufficient monitoring, testing and consultation by GeoEngineers should be provided during construction to confirm that the conditions encountered are consistent with those indicated by the explorations, to provide recommendations for design changes should the conditions revealed during the work differ from those anticipated, and to evaluate whether or not earthwork activities are completed in accordance with our recommendations. Retaining GeoEngineers for construction observation for this project is the most effective method of managing the risks associated with unanticipated conditions.

A Geotechnical Engineering or Geologic Report Could Be Subject to Misinterpretation

Misinterpretation of this report by other design team members can result in costly problems. You could lower that risk by having GeoEngineers confer with appropriate members of the design team after submitting the report. Also retain GeoEngineers to review pertinent elements of the design team's plans and specifications. Contractors can also misinterpret a geotechnical engineering or geologic report. Reduce that risk by having GeoEngineers participate in pre-bid and preconstruction conferences, and by providing construction observation.

Do Not Redraw the Exploration Logs

Geotechnical engineers and geologists prepare final boring and testing logs based upon their interpretation of field logs and laboratory data. To prevent errors or omissions, the logs included in a geotechnical engineering or geologic report should never be redrawn for inclusion in architectural or other design drawings. Only photographic or electronic reproduction is acceptable but recognize that separating logs from the report can elevate risk.

Give Contractors a Complete Report and Guidance

Some owners and design professionals believe they can make contractors liable for unanticipated subsurface conditions by limiting what they provide for bid preparation. To help prevent costly problems, give contractors the complete geotechnical engineering or geologic report, but preface it with a clearly written letter of transmittal. In that letter, advise contractors that the report was not prepared for purposes of bid development and that the report's accuracy is limited; encourage them to confer with GeoEngineers and/or to conduct additional study to obtain the specific types of information they need or prefer. A pre-bid conference can also be valuable. Be sure contractors have sufficient time to perform additional study. Only then might an owner be in a position to give contractors the best information available, while requiring them to at least share the financial responsibilities stemming from unanticipated conditions. Further, a contingency for unanticipated conditions should be included in your project budget and schedule.

Contractors Are Responsible for Site Safety on Their Own Construction Projects

Our geotechnical recommendations are not intended to direct the contractor's procedures, methods, schedule or management of the work site. The contractor is solely responsible for job site safety and for managing construction operations to minimize risks to on-site personnel and to adjacent properties.

Read These Provisions Closely

Some clients, design professionals and contractors may not recognize that the geoscience practices (geotechnical engineering or geology) are far less exact than other engineering and natural science disciplines. This lack of understanding can create unrealistic expectations that could lead to disappointments, claims and disputes. GeoEngineers includes these explanatory "limitations" provisions in our reports to help reduce such risks. Please confer with GeoEngineers if you are unclear how these "Report Limitations and Guidelines for Use" apply to your project or site.

Geotechnical, Geologic and Environmental Reports Should Not Be Interchanged



The equipment, techniques and personnel used to perform an environmental study differ significantly from those used to perform a geotechnical or geologic study and vice versa. For that reason, a geotechnical engineering or geologic report does not usually relate any environmental findings, conclusions or recommendations; e.g., about the likelihood of encountering underground storage tanks or regulated contaminants. Similarly, environmental reports are not used to address geotechnical or geologic concerns regarding a specific project.

Biological Pollutants

GeoEngineers' Scope of Work specifically excludes the investigation, detection, prevention or assessment of the presence of Biological Pollutants. Accordingly, this report does not include any interpretations, recommendations, findings, or conclusions regarding the detecting, assessing, preventing or abating of Biological Pollutants and no conclusions or inferences should be drawn regarding Biological Pollutants, as they may relate to this project. The term "Biological Pollutants" includes, but is not limited to, molds, fungi, spores, bacteria, and viruses, and/or any of their byproducts.

If Client desires these specialized services, they should be obtained from a consultant who offers services in this specialized field.

APPENDIX E
BASIN MAP



© MACKENZIE 2020
ALL RIGHTS RESERVED
THESE DRAWINGS ARE THE PROPERTY OF
MACKENZIE AND ARE NOT TO BE USED
OR REPRODUCED IN ANY MANNER
WITHOUT PRIOR WRITTEN PERMISSION

REVISION SCHEDULE		
Delta	Issued As	Issue Date

SHEET TITLE:
BASIN MAP

DRAWN BY: BTC
CHECKED BY: GIM
SHEET

JOB NO. **2200339.00**



FIELD INVESTIGATION

To:	Martin Real Estate	Report Date:	September 9, 2020
Project:	Hedges Lot D	Site Visit:	September 3, 2020
Location:	SW 115th Street Tualatin, Oregon	VLMK Project Number:	20180292
Weather:	Sunny	Temperature:	Approx. 90 deg. F
File Path:	G:\ACAD2018\20180292\Correspondence\Hedges D Bridge _Field Evaluation Report.docx		

PRESENT AT SITE

Trent Nagele, P.E., S.E., VLMK Engineering + Design

PURPOSE

As requested, a site visit was made to review the general condition of the bridge that crosses Hedges Creek at the end of SW 115th Street and provides access to Lot D in the Franklin Industrial Park.

Specifically, this report addresses item #13 in Tualatin Valley Fire & Rescue's review notes dated January 17, 2020 for proposed development of Tax Lot I.D.: 2S127BA0800.

"Please provide an engineers report regarding the private bridge that indicates the weight limit and the soundness of the bridge. Please indicate who is responsible for the maintenance of the bridge. Vehicle load limits signs shall be posted at both entrances to the bridge."

OBSERVATIONS

Original design drawings for the bridge were obtained from Conlee Engineers, Inc. of Portland, Oregon. These drawings have two structural sheets – S1 and S2 – and are dated 10-15-01, with revision dates on sheet S2 of 4-15-02 and 4-27-04.

Structural Notes on sheet S1 indicate the bridge is designed to, "Highway Loads – AASHTO HS20". A copy of these drawings is attached, and the notes indicate additional criteria for sidewalks, railings and piping support.

The bridge is a single span concrete structure supported by abutments and piles on either side of the creek. The main deck utilizes precast concrete planks, 4-feet wide and 18-inches thick with a span of 39-feet measured from centerline of the abutments. Railings on either side of the bridge are

galvanized steel tubes. Utility piping is supported underneath the bridge and along the south side. A 6-foot sidewalk is present along the north side.

Based on visual observations of the structure at the site, the bridge is in good and sound condition. There were no observed signs of deterioration or other conditions that would reduce the capacity of the structure to support the design load.


RECOMMENDATIONS

1. Future maintenance and/or evaluations of the structure are the responsibility of the owner, Martin Real Estate, and will be coordinated by them.
2. The bridge was designed for the AASHTO HS20 design criteria which is consistent with typical highway bridge standards for over-the-road vehicles. Commonly, unless a bridge has a reduced load capacity that is less than the HS20 standard, it should not be necessary to post a load rating. Please confirm if posting is required for this bridge? Note that the HS20 criteria does not correspond to a single weight limit, but rather considers a number of factors, including quantity, spacing and weight distribution to the vehicle axles, which makes posting any specific weights difficult and not wholly accurate.

Should you have questions or need additional information, please contact us.

Submitted by,
VLMK Engineering + Design

TRENT NAGELE, P.E., S.E.
Principal



EXPIRES: 12/31/2020

Attachments: Figures (1)
Photographs (6)
Original Drawings (2 pp.)

Distribution: Mac Martin, Martin Real Estate
Bob Wells, LMA Architects

macmartinis@gmail.com
bwells@lmueller.com



Figure 1 – Aerial of Bridge Location



Photo 1

Bridge, looking generally west.



Photo 2
Bridge, looking west.



Photo 3
South side of bridge.



Photo 4
North side of bridge.



Photo 5
Bridge railing.



Photo 6
Underside of bridge
(looking toward east
abutment).




Photo 7
Underside of bridge
(looking toward west
abutment).

Handwritten signature

REVISIONS


NO.	DESCRIPTION	DATE

CONLEE ENGINEERS, INC.
1308 S.W. Bertha Blvd.
Portland, Oregon 97219 (503) 244-0579



BRIDGE DECK PLAN

SCALE: 1/8" = 1'-0"



FOUNDATION PLAN

SCALE: 1/8" = 1'-0"

STRUCTURAL NOTES

- CODE: STANDARD SPECIFICATIONS FOR BRIDGES (AASHTO LATEST EDITION)
- DESIGN: DEAD LOADS - AS REQUIRED
HIGHWAY LOADS - AASHTO HS20
SIDEWALKS - 85 PSF OR HS20
RAILING - PER ASHTO ART. 1.1.8
PIPING - 60# / PER B/S2
PILING - 60 TON PER GEOTECHNICAL REPORT (9-13-00) PREPARED BY GEODESIGN.
- CONCRETE: PLANT MIXED PER ASTM C 94. REFERENCE SPECIFICATIONS ACI 301.
1. STRENGTH - F'C = 3,000 PSI AT 28 DAYS. MINIMUM CEMENT CONTENT 5 1/2 SACKS/CU. YD. 5% + 1% ENTRAINED AIR.
2. REINFORCING - ASTM A615, GRADE 60. LAP BARS AS SHOWN ON PLANS WITH MINIMUM LAP OF 36 BAR DIAMETERS.
3. COVER - AS FOLLOWS UNLESS SHOWN OTHERWISE ON PLANS.
A. CONCRETE PLACES AGAINST EARTH - 3"
B. FORMED CONCRETE AGAINST EARTH - 2"
C. SLABS-ON-GRADE - 2" TOP
4. FINISH -
A. PILE CAPS - SMOOTH FORM FINISH. FILL TIE HOLES WITH NON-SHRINK GROUT AND GRIND SMOOTH. TOP OF CAP TO HAVE HARD TROWELED FINISH.
5. SUBMITTALS
A. MIX DESIGN - 4 COPIES.
B. REINFORCING SHOP DRAWINGS - 4 COPIES
6. INSPECTION - ENGINEER SHALL INSPECT REINFORCING IN PLACE PRIOR TO PLACING CONCRETE
1. SAMPLING AND TESTING - TESTING LABORATORY TO SAMPLE AND TEST CONCRETE PER AASHTO, ART. A2.4.1.
- PRECAST, PRESTRESSED VOIDED SLAB SYSTEM
1. REFERENCE STANDARDS - AASHTO SECTION 16 AND OSHD STANDARD PLANS (DWG. 40563 & 40510) FOR 18" STD. F/C, P/S SLAB.
2. DESIGN - FABRICATOR SHALL DESIGN AND DETAIL PRECAST PRESTRESSED MEMBERS. CALCULATIONS AND SHOP DRAWINGS SHALL BE STAMPED BY AN ENGINEER REGISTERED IN OREGON.
3. BEARING PADS - ELASTOMERIC CONFORMING TO DIVISION 2, SECTION 25 OF AASHTO SPECIFICATIONS FOR HIGHWAY BRIDGES.
4. SUBMITTALS
A. MIX DESIGN - 4 COPIES.
B. CALCULATIONS - 2 COPIES.
C. SHOP DRAWINGS - 4 COPIES.
D. TEST REPORTS - 4 COPIES.
- STRUCTURAL AND MISCELLANEOUS STEEL
1. MATERIALS -
A. SHAPES AND PLATES - ASTM A36
B. STRUCTURAL TUBING - ASTM A500, GRADE B
C. PIPE - ASTM A53
2. WELDING - BY CERTIFIED WELDERS PER AHS RECOMMENDATIONS.
E 10 XX ELECTRODES.
3. BOLTS - ASTM A307
4. FABRICATION AND ERECTION - PER AASHTO SECTION 2.10
5. FINISH - HOT DIP GALVANIZE AFTER FABRICATION PER AASHTO MIII (ASTM A123)
6. SUBMITTALS
A. SHOP DRAWINGS - 4 COPIES.

PRIVATE HAUL ROAD / HEDGES CREEK BRIDGE

FRANKLIN INDUSTRIAL PARK
TUALATIN, OREGON

BRIDGE PLANS & STRUCTURAL NOTES


DATE: 10-15-01

PROJECT NO: DMCO1


SHEET NO

S1


OF




1 SECTION AT SIDEWALK AND GUARDRAIL
S2 SCALE: 3/4" = 1'-0"




2 BRIDGE DECK / ABUTMENT
S2 SCALE: 3/4" = 1'-0"




3 SECTION @ CURB AND GUARDRAIL
S2 SCALE: 3/4" = 1'-0"




4 UTILITY SUPPORT
S2 SCALE: 3/4" = 1'-0"




A HEDGES CREEK BRIDGE - LONGITUDINAL SECTION
S2 SCALE: 1/4" = 1'-0"



B HEDGES CREEK BRIDGE - TRANSVERSE SECTION
S2 SCALE: 1/4" = 1'-0"



C PRECAST PRESTRESSED SLAB PLAN
S2 SCALE: N.T.S.



D TIE ROD DETAIL
S2 SCALE: 1/2" = 1'-0"

REVISIONS	
4-15-02	
4-27-04	

CONLEE ENGINEERS, INC.
1308 S.W. Bertha Blvd.
Portland, Oregon 97219 (503) 244-0579

PRIVATE HAUL ROAD / HEDGES CREEK BRIDGE
FRANKLIN INDUSTRIAL PARK
TUALATIN, OREGON
BRIDGE SECTIONS & DETAILS

DATE: 10-15-01
PROJECT NO: DMCC01
SHEET NO
S2
OF

Hedges D – Fleet Parking Lot

11507 SW 115th Avenue (private street), Tualatin, OR 97062

End