



October 29, 2020

Erin Engman
Associate Planner
City of Tualatin
18880 SW Martinazzi Avenue
Tualatin, Oregon 97062

**Re: Herman Road Industrial
Tax Lot I.D: 2S123BA2900, 3100, 2S123B0900**

Dear Erin,

Thank you for the opportunity to review the proposed site plan surrounding the above-named development project. These notes are provided regarding the plans received October 28, 2020 and are based on the current New Construction Guide. There may be more or less requirements needed based upon the final project design, however, Tualatin Valley Fire & Rescue will endorse this proposal predicated on the following criteria and conditions of approval.

FIRE APPARATUS ACCESS:

1. **FIRE APPARATUS ACCESS ROADS:** Access roads shall be provided for every facility, building, or portion of a building hereafter constructed or moved into or within the jurisdiction. **Exception:** Approved agricultural and equine structures complying with ORS 455.315 are not required to have fire apparatus access roads (see New Construction Guide Appendix C). Access roads are not required to be modified for commercial buildings that undergo a change in occupancy, change in use, or conversion from agricultural or equine exempt to non-exempt unless there is a change to the structure's square footage or building footprint. (OFC 503.1.1)
2. **FIRE ACCESS ROAD DISTANCE FROM BUILDINGS:** The access shall extend to within 150 feet of all portions of the exterior wall of the first story of the building as measured by an approved route around the exterior of the building or facility. (OFC 503.1.1)
3. **FIRE ACCESS ROAD EXCEPTIONS:** The requirements for fire apparatus access may be modified as approved by the Fire Marshal where any of the following apply: (OFC 503.1.1 Exceptions)
 - a. Buildings are equipped throughout with an approved automatic fire sprinkler system in accordance with sections 903.3.1.1, 903.3.1.2 or 903.3.1.3.
 - b. Fire apparatus access roads cannot be installed because of location on property, topography, waterways, non-negotiable grades, or other similar conditions, and an approved alternative means of fire protection is provided.
 - c. There are not more than (2) two group U occupancies.

Access road exception will apply.

4. **ADDITIONAL ACCESS ROADS – COMMERCIAL/INDUSTRIAL HEIGHT:** Buildings exceeding 30 feet in height or three stories in height shall have at least two separate means of fire apparatus access. (D104.1)

Access road exception will apply.

5. **ADDITIONAL ACCESS ROADS – COMMERCIAL/INDUSTRIAL SQUARE FOOTAGE:** Buildings or facilities having a gross building area of more than 62,000 square feet shall have at least two approved separate means of fire apparatus access. Exception: Projects having a gross building area of up to 124,000 square feet that have a single approved fire apparatus access road when all buildings are equipped throughout with approved automatic sprinkler systems. (OFC D104.2)

Access road exception will apply.

6. **AERIAL FIRE APPARATUS ROADS:** Buildings with a vertical distance between the grade plane and the highest roof surface that exceeds 30 feet in height shall be provided with a fire apparatus access road constructed for use by aerial apparatus with an unobstructed driving surface width of not less than 26 feet. For the purposes of this section, the highest roof surface shall be determined by measurement to the eave of a pitched roof, the intersection of the roof to the exterior wall, or the top of the parapet walls, whichever is greater. Any portion of the building may be used for this measurement, provided that it is accessible to firefighters and is capable of supporting ground ladder placement. (OFC D105.1, D105.2)

Plans indicate a drive aisle width of 26ft.

7. **AERIAL APPARATUS OPERATIONS:** At least one of the required aerial access routes shall be located within a minimum of 15 feet and a maximum of 30 feet from the building and shall be positioned parallel to one entire side of the building. The side of the building on which the aerial access road is positioned shall be approved by the Fire Marshal. Overhead utility and power lines shall not be located over the aerial access road or between the aerial access road and the building. (D105.3, D105.4)
8. **MULTIPLE ACCESS ROADS SEPARATION:** Where two access roads are required, they shall be placed a distance apart equal to not less than one half of the length of the maximum overall diagonal dimension of the area to be served (as identified by the Fire Marshal), measured in a straight line between accesses. (OFC D104.3)

Access road exception will apply.

9. **FIRE APPARATUS ACCESS ROAD WIDTH AND VERTICAL CLEARANCE:** Fire apparatus access roads shall have an unobstructed driving surface width of not less than 20 feet (26 feet adjacent to fire hydrants (OFC D103.1)) and an unobstructed vertical clearance of not less than 13 feet 6 inches. (OFC 503.2.1 & D103.1)

Plans do not indicate width of driveway apron from SW Herman Rd.

10. **NO PARKING SIGNS:** Where fire apparatus roadways are not of sufficient width to accommodate parked vehicles and 20 feet of unobstructed driving surface, "No Parking" signs shall be installed on one or both sides of the roadway and in turnarounds as needed. Signs shall read "NO PARKING - FIRE LANE" and shall be installed with a clear space above grade level of 7 feet. Signs shall be 12 inches wide by 18 inches high and shall have red letters on a white reflective background. (OFC D103.6)

See attached sheet for locations of fire lanes.

11. **NO PARKING:** Parking on emergency access roads shall be as follows (OFC D103.6.1-2):
1. 20-26 feet road width – no parking on either side of roadway
 2. 26-32 feet road width – parking is allowed on one side
 3. Greater than 32 feet road width – parking is not restricted

Note: For specific widths and parking allowances, contact the local municipality.

12. **PAINTED CURBS:** Where required, fire apparatus access roadway curbs shall be painted red (or as approved) and marked "NO PARKING FIRE LANE" at 25 foot intervals. Lettering shall have a stroke of not less than one inch wide by six inches high. Lettering shall be white on red background (or as approved). (OFC 503.3)

See attached sheet for locations of fire lanes.

13. **FIRE APPARATUS ACCESS ROADS WITH FIRE HYDRANTS:** Where a fire hydrant is located on a fire apparatus access road, the minimum road width shall be 26 feet and shall extend 20 feet before and after the point of the hydrant. (OFC D103.1)

14. **SURFACE AND LOAD CAPACITIES:** Fire apparatus access roads shall be of an all-weather surface that is easily distinguishable from the surrounding area and is capable of supporting not less than 12,500 pounds point load (wheel load) and 75,000 pounds live load (gross vehicle weight). Documentation from a registered engineer that the final construction is in accordance with approved plans or the requirements of the Fire Code may be requested. (OFC 503.2.3)

15. **TURNING RADIUS:** The inside turning radius and outside turning radius shall not be less than 28 feet and 48 feet respectively, measured from the same center point. (OFC 503.2.4 & D103.3)

Plans do not indicate turning radius. Indicate turning radius using Auto-turn.

16. **ACCESS ROAD GRADE:** Fire apparatus access roadway grades shall not exceed 15%. Alternate methods and materials may be available at the discretion of the Fire Marshal (for grade exceeding 15%).

17. **ANGLE OF APPROACH/GRADE FOR INTERSECTIONS:** Intersections shall be level (maximum 5%) with the exception of crowning for water run-off. (OFC 503.2.7 & D103.2)

18. **AERIAL APPARATUS OPERATING GRADES:** Portions of aerial apparatus roads that will be used for aerial operations shall be as flat as possible. Front to rear and side to side maximum slope shall not exceed 10%.

19. **GATES:** Gates securing fire apparatus roads shall comply with all of the following (OFC D103.5, and 503.6):

1. Minimum unobstructed width shall be not less than 20 feet (or the required roadway surface width).
2. Gates shall be set back at minimum of 30 feet from the intersecting roadway or as approved.
3. Electric gates shall be equipped with a means for operation by fire department personnel
4. Electric automatic gates shall comply with ASTM F 2200 and UL 325.

20. **ACCESS DURING CONSTRUCTION:** Approved fire apparatus access roadways shall be installed and operational prior to any combustible construction or storage of combustible materials on the site. Temporary address signage shall also be provided during construction. (OFC 3310.1)

21. **TRAFFIC CALMING DEVICES:** Shall be prohibited on fire access routes unless approved by the Fire Marshal. (OFC 503.4.1). Traffic calming measures linked here: <http://www.tvfr.com/DocumentCenter/View/1578>

FIREFIGHTING WATER SUPPLIES:

22. **COMMERCIAL BUILDINGS – REQUIRED FIRE FLOW:** The minimum fire flow and flow duration shall be determined in accordance with OFC Table B105.2. The required fire flow for a building shall not exceed the available GPM in the water delivery system at 20 psi residual. (OFC B105.3)

Note: OFC B106, Limiting Fire-Flow is also enforced, except for the following:

- The maximum needed fire flow shall be 3,000 GPM, measured at 20 psi residual pressure.
- Tualatin Valley Fire & Rescue does not adopt Occupancy Hazards Modifiers in section B105.4-B105.4.1 See attached

See attached sheet for required fire flow. Fire sprinkler demand must be added to this requirement.

23. **FIRE FLOW WATER AVAILABILITY:** Applicants shall provide documentation of a fire hydrant flow test or flow test modeling of water availability from the local water purveyor if the project includes a new structure or increase in the floor area of an existing structure. Tests shall be conducted from a fire hydrant within 400 feet for commercial projects, or 600 feet for residential development. Flow tests will be accepted if they were performed within 5 years as long as no adverse modifications have been made to the supply system. Water availability information may not be required to be submitted for every project. (OFC Appendix B)

Provide documentation of fire flow test or modeling.

24. **WATER SUPPLY DURING CONSTRUCTION:** Approved firefighting water supplies shall be installed and operational prior to any combustible construction or storage of combustible materials on the site. (OFC 3312.1)

FIRE HYDRANTS:

25. **FIRE HYDRANTS – COMMERCIAL BUILDINGS:** Where a portion of the building is more than 400 feet from a hydrant on a fire apparatus access road, as measured in an approved route around the exterior of the building, on-site fire hydrants and mains shall be provided. (OFC 507.5.1)

- This distance may be increased to 600 feet for buildings equipped throughout with an approved automatic sprinkler system.
- The number and distribution of fire hydrants required for commercial structure(s) is based on Table C105.1, following any fire-flow reductions allowed by section B105.3.1. Additional fire hydrants may be required due to spacing and/or section 507.5 of the Oregon Fire Code.

26. **FIRE HYDRANT(S) PLACEMENT:** (OFC C104)

- Existing hydrants in the area may be used to meet the required number of hydrants as approved. Hydrants that are up to 600 feet away from the nearest point of a subject building that is protected with fire sprinklers may contribute to the required number of hydrants. (OFC 507.5.1)
- Hydrants that are separated from the subject building by railroad tracks shall not contribute to the required number of hydrants unless approved by the Fire Marshal.
- Hydrants that are separated from the subject building by divided highways or freeways shall not contribute to the required number of hydrants. Heavily traveled collector streets may be considered when approved by the Fire Marshal.
- Hydrants that are accessible only by a bridge shall be acceptable to contribute to the required number of hydrants only if approved by the Fire Marshal.

See attached sheet for locations of fire hydrants. Note two additional hydrants.

27. **PRIVATE FIRE HYDRANT IDENTIFICATION:** Private fire hydrants shall be painted red in color. Exception: Private fire hydrants within the City of Tualatin shall be yellow in color. (OFC 507)

If the fire hydrants will be private, then TVFR will review the underground for the private system.

28. **FIRE HYDRANT DISTANCE FROM AN ACCESS ROAD:** Fire hydrants shall be located not more than 15 feet from an approved fire apparatus access roadway unless approved by the Fire Marshal. (OFC C102.1)

29. **REFLECTIVE HYDRANT MARKERS:** Fire hydrant locations shall be identified by the installation of blue reflective markers. They shall be located adjacent and to the side of the center line of the access roadway that the fire hydrant is located on. In the case that there is no center line, then assume a center line and place the reflectors accordingly. (OFC 507)

30. **PHYSICAL PROTECTION:** Where fire hydrants are subject to impact by a motor vehicle, guard posts, bollards or other approved means of protection shall be provided. (OFC 507.5.6 & OFC 312)

31. **CLEAR SPACE AROUND FIRE HYDRANTS:** A 3 foot clear space shall be provided around the circumference of fire hydrants. (OFC 507.5.5)

32. **FIRE DEPARTMENT CONNECTION (FDC) LOCATIONS:** FDCs shall be located within 100 feet of a fire hydrant (or as approved). Hydrants and FDC's shall be located on the same side of the fire apparatus access roadway or drive aisle, fully visible, and recognizable from the street or nearest point of the fire department vehicle access or as otherwise approved. (OFC 912.2.1 & NFPA 13)

- Fire department connections (FDCs) shall normally be located remotely and outside of the fall-line of the building when required. FDCs may be mounted on the building they serve, when approved.
- FDCs shall be plumbed on the system side of the check valve when sprinklers are served by underground lines also serving private fire hydrants.

FDC location is adequate. FDC's will be required to have signs attached to them indicating which building they serve.

BUILDING ACCESS AND FIRE SERVICE FEATURES

33. **EMERGENCY RESPONDER RADIO COVERAGE:** In new buildings where the design reduces the level of radio coverage for public safety communications systems below minimum performance levels, a distributed antenna system, signal booster, or other method approved by TVF&R and Washington County Consolidated Communications Agency shall be provided. (OFC 510)

- **Emergency responder radio system testing and/or system installation is required for this building. Please contact me (using my contact info below) for further information including an alternate means of compliance that is available. If the alternate method is preferred, it must be requested from TVF&R prior to issuance of building permit.**
- **Testing shall take place after the installation of all roofing systems; exterior walls, glazing and siding/cladding; and all permanent interior walls, partitions, ceilings, and glazing.**

This requirement is mandatory for Building 1. See attached application for fee in lieu.

34. **KNOX BOX:** A Knox Box for building access may be required for structures and gates. See Appendix B for further information and detail on required installations. Order via www.tvfr.com or contact TVF&R for assistance and instructions regarding installation and placement. (OFC 506.1)

A Knox box will be required for each building. Please contact me regarding location and mounting height.

35. **FIRE PROTECTION EQUIPMENT IDENTIFICATION:** Rooms containing controls to fire suppression and detection equipment shall be identified as “**Fire Control Room.**” Signage shall have letters with a minimum of 4 inches high with a minimum stroke width of 1/2 inch, and be plainly legible, and contrast with its background. (OFC 509.1)

Label doors for fire protection equipment as indicated above.

36. **PREMISES IDENTIFICATION:** New and existing buildings shall have approved address numbers; building numbers or approved building identification placed in a position that is plainly legible and visible from the street or road fronting the property, including monument signs. These numbers shall contrast with their background. Numbers shall be a minimum of 4 inches high with a minimum stroke width of 1/2 inch. (OFC 505.1)

While the minimum height for address numbers is 4 inches. On larger buildings it is recommended to double this size.

If you have questions or need further clarification, please feel free to contact me at **503-849-6020**.
Sincerely,


Tom Mooney

Tom Mooney
Deputy Fire Marshal II

Thomas.mooney@tvfr.com

Cc: File
City of Tualatin

A full copy of the New Construction Fire Code Applications Guide for Commercial and Multi-Family Development is available at <https://www.tvfr.com/DocumentCenter/View/1296/NC-Fire-Code-Application-Guide-for-Commercial-Development?bidId=>



Site Plan
Scale: 1" = 40'-0"

FIRE FLOW:

BUDE 1:
104,254 ft² = 6,750 GPM
75% Reduction = 1,688 GPM

BUDE 2:
27,325 ft² = 3,500 GPM
75% Reduction = 1,500 GPM

- Keynotes**
1. CONCRETE RAISED/RECYCLING ENCLOSURE, PAINTED - SEE DETAIL 1/AS.1
 2. PEDESTAL ACCESS AT CONCRETE WALL FLUSH WITH ACCESSIBLE PARKING SPACE, RAMP, STORAGE AND ACCESSIBLE RAMP - SEE DETAIL 1/AS.1
 3. ACCESSIBLE RAMP - SEE DETAIL 1/AS.1
 4. CONCRETE RETAINING WALL
 5. ELECTRICAL ROOM
 6. ELECTRICAL ROOM
 7. CONCRETE CORE/SMOKE PROTECTION DETAIL - SEE DETAIL 1/AS.1
 8. ACCESSIBLE RAMP
 9. CONCRETE CORE/SMOKE PROTECTION DETAIL - SEE DETAIL 1/AS.1
 10. CONCRETE CORE/SMOKE PROTECTION DETAIL - SEE DETAIL 1/AS.1
 11. 50' FRONT YARD SETBACK AND CIRCULATION
 12. 50' FRONT YARD SETBACK AND CIRCULATION
 13. 50' FRONT YARD SETBACK AND CIRCULATION
 14. BUREAU OF FIRE 2 BIKES COVERED UNDER ENTRY CANOPY
 15. WALL HANGING FIRE FIGHTER
 16. WALL HANGING FIRE FIGHTER
 17. WALL HANGING FIRE FIGHTER

Fire Hydrants

- Legend**
- △ DRIVE-IN DOOR
 - ▲ DOOR-HIGH DOOR

MILDREN DESIGN GROUP

1700 W. Independence Ave. 20
Tulsa, Oklahoma 74104
918.438.1111

REGISTERED ARCHITECT
STATE OF OKLAHOMA
No. 10078
1988

Client:
Lu Pacific Development

Project:
1185 SW Tenthon St
Tulsa, OK 74102


Site Plan
Development Building

Site Title:
1185 SW Tenthon St
Tulsa, OK 74102

Sheet Title:
Site Plan

Revision:

DATE: 04/11/2020
TIME: 10:00 AM
PROJECT: 1185 SW Tenthon St
SHEET: 1185-01



FIRE LANES

- Keynotes**
1. CONCRETE TRASH/RECYCLING ENCLOSURE, PAINTED - SEE DETAIL 1/4.5.1
 2. ACCESSIBLE ASHES AT CONCRETE WALK SPACES AND
 3. ASPHALTIC PAVING
 4. ACCESSIBLE ASHES - SEE DETAIL 1/4.5.1
 5. CONCRETE REPAIR APPROX. 1" THICK
 6. ELECTRICAL ROOM
 7. ACCESSIBLE RAMP
 8. 6" X CONCRETE GROUP FILLED PROTECTION BOLLARD - SEE DETAIL 1/4.5.1
 9. CONCRETE CURB
 10. KNOX BOX, COORDINATE LOCATION WITH OWNER
 11. 30' FRONT YARD SETBACK
 12. 30' FRONT YARD SETBACK
 13. 30' FRONT YARD SETBACK
 14. 10' SETBACK FOR PARKING AND CIRCULATION
 15. 10' SETBACK FOR PARKING AND CIRCULATION
 16. WALL WIND BREAK PACE
 17. VANPOOL/POOL STORAGE

- Legend**
- △ PRING-IN DOOR
 - ▲ DOCK-HIGH DOOR

Site Plan
Scale: 1" = 40'-0"

MILDREN DESIGN GROUP



Client:
Lu Pacific Development

11295 SW Thialla Street, Portland, OR 97106

Project:
Lu Pacific Development Building

1003 SW Hernan Blvd, Tualatin, OR 97146

Sheet Title:
Site Plan

Revisions:

DATE: 04/11/2020
 DRAWN BY: [Name]
 CHECKED BY: [Name]
 TITLE: [Title]
 SHEET: [Number]

**TUALATIN VALLEY FIRE & RESCUE
MOBILE EMERGENCY RESPONDER RADIO COVERAGE (MERRC) APPLICATION**

This application is to be used when requesting approval for participation in the TVF&R MERRC program in lieu of providing an in-building OFC 510 emergency responder radio coverage system

North Division

11945 SW 70th Avenue
Tigard, OR 97223
Phone: 503-649-8577

South Division

8445 SW Elligsen Road
Wilsonville, OR 97070
Phone: 503-259-1500

Building Information

(Separate Application Required for Each Building)

Business/ Building Name: _____

Proposed Use of Building: _____

Address: _____

City/County: _____

Building Permit # _____

Applicant Contact Information

Contact Person: _____

Phone: _____

Email: _____

MERRC FEE:

Approved Fee Schedule (as of 11/2015)

First 0 - 50,000 sq.ft. = \$0.50 per sq.ft.

Additional sq.ft. from 50,001 - 100,001 = \$0.30 per sq.ft.

For each sq.ft. over 100,000 = \$0.10 per sq.ft.

Example fee for 300,000 sf building:

First 50,000 sq.ft. x \$0.50 = \$25,000 +

50,001 to 100,001 sq.ft. x \$0.30 = \$15,000 +

100,002 to 300,000 sq.ft. x \$ 0.10 = \$19,999

TOTAL = \$59,999

Total Square Footage: _____

_____ SF x \$0.50 =

_____ SF x \$0.30 =

_____ SF x \$0.10 =

TOTAL MERRC FEE: \$ _____

As an authorized representative for the above referenced building, I hereby request the building be permanently approved under the TVF&R Mobile Emergency Responder Radio Coverage program as having an approved method of compliance with Oregon Fire Code Section 510 and TVF&R Resolution 2015-09. If the application is accepted, I understand that full payment of the calculated MERRC fee is required prior to completing the approval process. For construction projects under a building permit, payment must be received prior to plan review completion, unless otherwise approved by the Fire Marshal.

Name & Title of Authorized Representative

Signature

Date

For Fire Marshal's Office Use Only

This section is for APPLICATION APPROVAL ONLY.

Application Approved by Fire Marshal: YES or NO

Reviewer Name: _____

Reviewer Signature _____

Date: _____

Comments:

This section is for FINAL APPROVAL ONLY.

Payment Total: _____

Received By: _____

Date: _____

Comments:

Provide a signed, approved final copy to applicant.